

GOVERNMENT OF INDIA
DEPARTMENT OF ARCHAEOLOGY
CENTRAL ARCHÆOLOGICAL
LIBRARY

CALL No. 891.05 / J.A.O.S


ACC. No. 24509

D.G.A. 79.

GIPN—S1—2D. G. Arch.N. D./57—27-9-58—1,00,000

24509

~~A330~~
vol. 9



(JOURNAL

(119)

OF THE

AMERICAN ORIENTAL SOCIETY.)

24509

VOL. 9

NINTH VOLUME.

891.05

1871

J. A. O. S.

A330
vol. 9



NEW HAVEN:

FOR THE AMERICAN ORIENTAL SOCIETY,

PRINTED BY TUTTLE, MORSEHOUSE AND TAYLOR, PRINTERS TO YALE COLLEGE.

MDCCCLXXI

SOLD BY THE SOCIETY'S AGENTS:

NEW YORK: B. WESTERMANN & CO., 471 BROADWAY;

LONDON: TRÜBNER & CO., AND WILLIAMS & NORGATE;

LEIPZIG: F. A. BROCKHAUS.

CENTRAL ARCHAEOLOGICAL
LIBRARY, N. H.

Acc. No. 24509.

Date 15-10-56.

Call No. 891.05 / J.A.O.S

COMMITTEE OF PUBLICATION
OF THE
AMERICAN ORIENTAL SOCIETY,
FOR THE YEARS 1868-71.

EDWARD E. SALISBURY,	New Haven.
WILLIAM D. WHITNEY,	"
JAMES HADLEY,	"
EZRA ABBOT,	Cambridge.
ARNOLD GUYOT,	Princeton.

Entered according to Act of Congress, in the year 1871, by the
AMERICAN ORIENTAL SOCIETY,
in the office of the Librarian of Congress, at Washington.

CONTENTS

OF

NINTH VOLUME.

Page

ART. I.—THE TĀITTIKĪYA-PRĀTĪCĀKHYA, WITH ITS COMMENTARY, THE TRI- BHĀSHYARATNA: TEXT, TRANSLATION, AND NOTES. By WILLIAM D. WHITNEY, Professor of Sanskrit in Yale College,	1
---	---

APPENDIX:

AMERICAN ORIENTAL SOCIETY:

<i>Proceedings at Boston and Cambridge, May 16th, 1866,</i>	i
<i>Proceedings at New Haven, Oct. 24th and 25th, 1866,</i>	vii
<i>Proceedings at Boston and Cambridge, May 22d, 1867,</i>	xiii
<i>Additions to the Library and Cabinet, May, 1865—May, 1867,</i>	xix
<i>Proceedings at New Haven, Oct. 16th and 17th, 1867,</i>	xxvii
<i>Proceedings at Boston, May 20th, 1868,</i>	xxxviii
<i>Proceedings at New Haven, Oct. 14th and 15th, 1868,</i>	xli
<i>Proceedings at Boston, May 19th, 1869,</i>	li
<i>Proceedings at New Haven, Oct. 21st and 22d, 1869,</i>	lvi
<i>List of Members, October, 1869,</i>	lxvi
<i>Proceedings at Boston, May 18th, 1870,</i>	lxxiii
<i>Proceedings at New Haven, Oct. 20th and 21st, 1870,</i>	lxxxv

ARTICLE I.

THE TÂITTIRÎYA-PRÂTIÇÂKHYA,

WITH ITS COMMENTARY,

THE TRIBHÂSHYARATNA:

TEXT, TRANSLATION, AND NOTES.

BY WILLIAM D. WHITNEY,
PROFESSOR OF SANSKRIT IN YALE COLLEGE.

Presented to the Society October 14th, 1868.

INTRODUCTORY NOTE.

THE manuscript material on which is founded this edition of the Tâittirîya-Prâtiçâkhyâ and Tribhâshyaratna is as follows:

1. T. A copy of the text of the treatise alone, in a modern hand, on light-colored paper. It was sent me by Prof. Fitz-Edward Hall, from Benares, in 1857, and appears to be a copy made for him from some older manuscript: but it contains no intimation of its own date or of that of its original; presenting at the end, in place of the usual colophon, the beginning of a list of words which in *pada*-text show a final *n*. It is distinctly and correctly written. On the back is inscribed "Krishna-yajuh-prâtisâkhyâ, by Kârtikeya." On what ground this ascription of authorship is made, I do not know; it does not, so far as I am aware, find support from any other quarter.

2. W. A copy of the text and commentary together, each separate rule being followed by its own comment. This manuscript, like the preceding, I owe to the kindness of Prof. Hall. It is handsomely written, in a large clear hand, and fills 146 leaves (numbered 1-89, 100, 1-56), measuring about four and a half by nine and a half inches. To the end of 25a, seven lines are written on a page; thenceforward, nine lines. It has no statement of scribe, place, or date; but I imagine that a final leaf, with the end of the colophon, had been lost or destroyed some time before it was sent to me. The part remaining reads as follows: *grîkîshnâr-pabhastu grîkâlabbhâiravaprasann om yâyakâmdavidhâyardhvam rshayo rshayo rshih: ity âçîsraçîmakâpûrcam rsham ce ti svatantratâ: 1 kramyâdhvano bhavaty agre pâvako rpayatîti ca*. This just fills up the leaf; but another hand has written below, at its edge, what purports to be the ending of the second verse: *visha-*

*yeṅgira ity evāpy agra ity ādi lopyate.*2., and has added, as final benediction, *ṛṣiṣṣeṣvaraprasann.*

This is a virgin manuscript, containing neither erasures, insertions, nor alterations. Considering that it thus presents every first fault of its scribe unamended, it is very good and correct. Through the first twelve chapters, the rules of the *Prātiśākhya* are distinguished from the commentary by being rubbed over with a red powder.

3. **B.** This authority comes from the west of India, where (see Dr. Bühler, in *Zeitsch. Dent. Morg. Ges.*, xxii.319) the *Tribhāsh-yaratna* is said to be not very rare. From a manuscript there collected, a copy was made under direction of Dr. Bühler for the Berlin library, and forwarded to Prof. Weber, at whose friendly suggestion and instance it was transcribed for me, in roman letters, by Dr. Siegfried Goldschmidt, to whom I desire here to express my gratitude for a service so valuable and so kindly rendered. The manuscript contains more inaccuracies of reading than any of the others which I have used, yet they are in the main superficial, and the text given is a pretty complete and correct one.

4. **O.** Through the kind offices of Prof. Max Müller, I have been enabled to procure a collation (made with a copy of my own manuscript, "W.") of the incomplete Oxford manuscript (MS. Bodl. W. 478), first described by Roth (*Zur Lit. und Gesch. des Weda*, pp. 54, 62 seq.), and used also by Weber (*Ind. Stud.* iv.77 seq.). It begins in the middle of the comment upon iii.12, thus lacking somewhat less than a quarter of the entire work.

5. **G.** This is a romanized copy of a manuscript which belongs to the Royal Asiatic Society of Great Britain and Ireland, and is written on strips of palm leaf, in the Grantham character. The copy was made for me by Dr. Julius Eggeling, who has thus laid me under deep obligation, and contributed most essentially to the success of my work. Hardly less than to him is my indebtedness to Dr. Reinhold Rost, Secretary of the Royal Asiatic Society, who notified me of the existence of the manuscripts in the Society's library soon after their discovery, and who suggested and aided their transcription. There are doubtless few other Sanskritists in Europe, besides these gentlemen, to whom works written in the southern Indian characters are not sealed books, and there can be none, I am sure, who evince a more liberal readiness to make their peculiar knowledge of service to the rest. The catalogue which Dr. Rost is preparing to publish of the Royal Asiatic Society's collection of manuscripts will give such other particulars respecting age, condition, etc., as I am compelled here to omit.

6. **M.** The library of the same Society also contains a second copy of the *Prātiśākhya* and its commentary, written on paper, in the Malayālam character. Of this, Dr. Eggeling has taken the pains to note the various readings as compared with the Grantham manuscript, in his transcript of the latter.

Both these manuscripts from southern India are so arranged

that the rules of the *Prāṭiśākhya* are given first, in a body, and are followed by the commentary, also in bulk.

As regards the text of the *Prāṭiśākhya* itself, all these authorities agree very closely: there are but two or three cases of well-established variations of reading among them. In respect to the text of the commentary, their accordance, as was to be expected, is much less: they fall, in fact, into three well-marked classes; or, as one might say, present three different recensions of the work. The two codices belonging to the Royal Asiatic Society, the *Grantham* ("G.") and the *Malayālam* ("M."), stand in the nearest possible relation to one another, having almost all their errors, omissions, and orthographical peculiarities in common, and only by comparatively rare and inconspicuous differences proved not to be copied the one from the other. My own manuscript ("W.") and that sent by Dr. Bühler from Bombay ("B.") also offer substantially the same text, although their differences are much more frequent, and of a more important character, than those of G. and M. As for the Oxford manuscript ("O."), it is, in its earlier portions, pretty closely accordant with W. and B., having an especially near relationship to B., with whose slight variations of the text given by W. it almost uniformly agrees; later, however, it strikes off upon a track of its own, and comes to differ from both the other recensions in a much greater degree than they differ between themselves.

Such being the case, I have thought it best to adopt for publication the version offered by W., partly because this is the only one for which I possess an original manuscript (and a tolerably old and correct one), partly because it is, upon the whole, better supported than that of G. and M.—which, as I have shown above, can hardly be reckoned, both together, as constituting more than a single manuscript. I have accordingly, avoiding the making up of an eclectic text from the various recensions, followed W. as closely as I could; and especially, when it was supported by the joint authority of B. and O., or of B. alone—thus sometimes, undoubtedly, rejecting an intrinsically preferable and perhaps more original reading given by one or another of the remaining authorities, if that offered by W. was of a character to be endured. At the end of the comment to each rule are given the various readings of all the manuscripts, with sufficient fullness, I hope, to answer the desirable ends of critical comparison. Obvious and trifling errors of transcription, of course, I have not noted, but only those which made a false reading or tended to become such: I have been most liberal in overlooking the blunders of B., as being, on the whole, of least consequence.

In regard, however, to the two matters of punctuation and euphonic combination, I have taken liberties with the text of which I have given no account. The various manuscripts are in no slight degree discordant with one another, inconsistent with themselves, and careless of the requirements of the sense, in the use they make of the signs of interpunction: they offer absolutely

no standard to follow. For the occurrence of the signs as printed, therefore, I am alone responsible; and no one who can anywhere make a better division of clauses than I have made need be restrained from so doing by the belief that he is running counter to manuscript authority. Again, I have (except in certain cases at the end of a cited rule or passage, where a reference follows) put all the words of the commentary in euphonic combination according to the usual rules; while in the manuscripts (as is common in exegetical writings) they are very frequently, for the sake of greater clearness, separated from one another.* Here, too, the usage of the various authorities is too discordant and irregular to be followed. And to report their readings in these two particulars would burden the critical notes with a mass of useless and wearisome details.

In the same manner are treated such orthographical peculiarities of the several manuscripts as that G. and M. regularly write a final sibilant instead of *visarjanīya* before an initial sibilant, and often, where a *m* is assimilated to a following mute, write the nasal mute corresponding to the latter, instead of *anusvāra*. Moreover, in the representation of the nasal sounds, by the nasal consonants, *anusvāra* (*ñ*), or *m*, I have followed a consistent method, with disregard of the manuscript usage.

The text given at the foot of the page contains the whole comment, with two exceptions: citations from the Tāittirīya-Saṁhitā, being written out in full, with references, in the notes to the rules, are indicated below only by first words or letters, with signs of omission added; and again, where lists of affected words are given in a rule, in euphonic combination, and repeated, separate, at the beginning of the comment, they are replaced by signs of omission, as having been sufficiently presented uncombined in the translation of the rule. Errors of reading in the cited passages themselves are passed without notice, unless of such importance as to cast doubt upon the identity of the passage; but, on the other hand, the frequent differences of the versions as regards the extent of the illustrative passage cited are fully noted in the sequel of the reference.

I have preferred, instead of giving an express and direct translation of the commentary, to work its substance fully into my own notes upon the rules, somewhat as in my edition of the Atharva Prātiśākhya (Journ. Am. Or. Soc'y, Vol. vii., 1862). The different conditions of the case, however, impress quite a different character upon the present work. The completeness and elaborateness of the Tribhāshyaratna make its working-up by far the larger and more important part of what is to be done in illustration of the Prātiśākhya. Possessing no *index verborum* to the Tāittirīya-Saṁhitā, nor even a manuscript of its *pada*-text, I have not been able to try the Prātiśākhya by it with anything like the same

* Thus, to instance an extreme case, at the end of the comment on iv.10, the manuscripts read (for once, with almost perfect unanimity): *īṅgyasya antaḥ īṅgyāntaḥ na īṅgyāntaḥ aniṅgyāntaḥ*.

thoroughness as in the case of the similar treatise to the Atharvan. What could be done in the way of testing and supplementing the rules given, by a careful reading and excerption of the Sanhitā in a single good *sanhitā*-manuscript (also procured for me in India by Dr. Hall, and with one or two slight deficiencies in it made up from Berlin, by Prof. Weber), I have endeavored to do. I have been able to refer points of interest connected with the text, in its *sanhitā* or *pada* readings, to friends in Europe owning or having access to fuller manuscript material, namely to Professors Weber of Berlin and Haug of München, and have received from them important aid, which I desire here gratefully to acknowledge. Of references to the teachings of the other Prātiśākhya I have been much more sparing in this than in the former work, in order to avoid repetition: and, for the same reason, some matters of theory which were pretty fully discussed there receive here a more compendious treatment. The present work, in short, to a certain extent presupposes the other—not, however, in such a manner or degree as should interfere with its independence and separate intelligibility.

In making reference to the Tāittiriya-Sanhitā, I have used only three principal numbers, to designate book, chapter, and section, or *kāṇḍa*, *pragṇa*, and *anuvāka*. The further division of the sections or *anuvākas*, where they are of more considerable length, into parcels of fifty words each, is so artificial, destructive of the natural connection of passages, detrimental to the proper phonetic form of the text, and wholly ignored by the Prātiśākhya (see notes to the rules of chapter iii.), that I have preferred to express it by the use of "superior" figures attached to that which indicates the *anuvāka*. Of course, where such attached figure is wanting, the *anuvāka* is to be understood as composed of a single division.

In the notes of various readings, each figure refers only to the single word to which it is attached, unless a passage of more than one word is included between two repetitions of the same figure; in which case the reference figure, in the notes, is put within parentheses. The abbreviation "om." means 'omit,' and "ins." means 'insert.'

In all transliterated passages of Sanskrit, a colon stands in place of a single stroke of interpunction, and a full stop in place of a double stroke. The general method of transliteration is the same with that which I have hitherto used in the Journal of the American Oriental Society; it will be sufficiently understood from the alphabet given in the note to i.1 (p. 10).

CHAPTER I.

CONTENTS: 1-11, enumeration and classification of sounds composing the alphabet; 12-14, surd and sonant consonants; 15, list of prepositions; 16-21, 27, names of letters and classes of letters; 22-24, 28, terminology of cited words, etc.; 25, 26, 29, 30, respecting the interpretation of rules; 31-37, quantity of simple sounds; 38-40, the three accents; 41-47, details respecting the circumflex accent; 48, 49, compound words; 50-53, respecting cited words; 54-55, words consisting of a single vowel; 56-61, further specifications respecting the interpretation of rules.

THE commentator begins his work with a couple of rather awkwardly-constructed verses, as follows: "I, bowing low with devoted affection to the two feet of Gaṇeṣa, as also to the *gurus* and to divine Voice, shall proceed to utter this comment; which, made upon examination of the exposition of the *Prātiçākhyā* given by Vararuci etc., shines, a Treasure of Threefold Comment (*tribhāshyaratna*), approved of Brahmans." He adds an exposition of their meaning, explaining *giram devīm*, 'divine Voice,' by *vāgdevīm*, 'Goddess of Voice,' and *bhāsura*, 'Brahman' (literally 'earth-god'), by *vidvat*, 'learned man, sage.' On *lakṣhaṇa*, which, as name of a comment, is least in accordance

'bhaktiyuktāḥ praṇamyā 'haṁ gaṇeṣacaranadevayam:
gurāṁ api girām¹ devīm idam vakshyāmi lakṣhaṇam.1.
vyākhyānam prātiçākhyasya vikshya vārarucādikam²:
kṛtām tribhāshyaratnam yad bhāsate bhāsurapriyam.2.

glokeyor anayor ayam³ arthaḥ. bhaktiyukto 'haṁ gaṇeṣacaranadevayam gurāṁ girām⁴ api devīm: 'vāgdevīm ity arthaḥ: tāṁ ca⁵ praṇamyā lakṣhaṇam idam vakshyāmi ya⁶ lakṣhaṇam tribhāshyaratnanāmakam bhāsurapriyam vidvatpriyam bhāsate: kīdrçam lakṣhaṇam: prātiçākhyasya vyākhyānarūpakam⁷ vārarucādikam⁸ bhāshyajātam vikshya¹⁰ nyūnātirekaparihāreṇa kṛtām viracitam: ādicabdenā⁹ 'treyamāhisheyāu gṛhyete: ata eva tribhāshyaratnam iti nāmna upapattiḥ: trayāṇām bhāshyāṇām samāhāras tribhāshyam: tasya¹¹ ratnam bhāshaṇam.

¹ W. prefaces with *ṛigāṣeṣya namaḥ. ṛigāṣeṣa prasanno 'stu, oṁ*. B. prefaces with *ṛigāṣeṣya namaḥ. ṛisarasvatyaī namaḥ. ṛidatīnnayāya namaḥ*: and the additional verse

*śuklāmbāradharam devam śaṣivargam caturbhujam:
prasannavadanām dhyāyet sarvaviṣṇopacāntaye.1.*

² The white-ruiment-bearing god, moon-hued, four-armed, propitious-faced, must one meditate on, in order to the surcease of all disturbance.' It then numbers the other verses "2" and "3;" but proceeds to confess the unguineness of the inserted verse by reading, like the other MSS., *anayor glokeyor*.

³ G. M. *giram*. ⁴ B. *var*. ⁵ G. M. *om*. ⁶ G. M. *giram*. ⁷ G. M. *om*. ⁸ G. M. *tal*. ⁹ G. M. *-rūpam*; B. *-pūrvakam*. ¹⁰ B. *var*; W. *-ka*. ¹¹ G. M. *samikshya*.
¹² W. *om*.

with common usage, he makes no remark. To *vikshya*, 'having examined,' he adds *nyānātirekaparihārena*, 'with avoidance of deficiency and redundancy.' The "etc." after "Vararuci" is declared to refer to Ātreya and Māhisheya, these three being the authorities upon which the present work is founded, and from which it derives its name. Vararuci and Māhisheya are, indeed, often (about ten times each: see Index) referred to in the sequel, and their discordant views sometimes set forth and discussed: Ātreya has only once (under v.1) the honor of being mentioned. Who is the digester of their three works, and author of the present commentary, which has taken their place and crowded them out of existence, we are not informed; nor, so far as I am aware, has any evidence bearing upon the point been anywhere brought to knowledge. Notice of the different authorities cited by our commentator will be put together in an additional note at the end of this work, for the sake of the light cast by them upon his age.

अथ वणिसमान्नायः ॥ १ ॥

1. Now the list of sounds.

The commentator first gives himself a great deal of trouble to explain the meaning of *atha*, 'now,' in the rule. He quotes Amara's definition of *atho* and *atha* (Amarakosha iii.4.32.8; p. 349 of Deslongchamps's edition), and points out that, as a variety of meanings is there attributed to *atha*, it is necessary to fix upon a single meaning for it here. In the first place, then, a propitiatory significance is claimed for it, by reason of its equivalence with *om*; "since the Āikshā-makers declare, '*om* and *atha* are deemed propitiatory.'" Or, again, it indicates something coming next after another; "the implication being that, next after the reading of the Veda, one should gain a knowledge of the *lakṣhaṇa*: there hav-

1. *maṅgalānantarārambhapraçnakārtsnyeshv atho athe 'ti maṅgalādyanekāarthatvād athaçabdasya 'rthanirṇayārtham eko 'rtho' niçcetavyaḥ: tatra prathamam tāvan maṅgalārthatvam ucyate: tasya pravaçasādharmyāt: tathā hi samācakshate çik-
shākārāḥ:*

*omkāraç cā 'thaçabdaç ca maṅgalāv iti kīrtitāv
iti: āho' svid ānantaryārthatā: vedādhyayanānantaram lakṣha-
ṇajñānam kuryād iti sāpekṣatvāl lakṣhaṇasya pūrvam vedādhi-
game saty atha lakṣhaṇaparikṣhāvasaraḥ: atha vā 'dhikārārtho
'thaçabdaḥ: tv athai 've 'ti vinivartakādhikāraakāva-
dhārakāḥ (xxii.8) iti vidyamānateāt: atha varṇasamāmnāyah
pāthakramo' dhikriyata iti sūtrāncayāḥ: sam ity ekibhāve: ān
iti maryādāyām: mnāya ity ānupūryeṇo 'padeçāḥ: ekibhātā
akārādayo varṇāḥ svarabhaktiparyavasānān ānupūryeṇa pūrvaiḥ
çishtāir' upadiṣtāḥ.*

ing been study of the Veda before the *lakshana*, now comes the occasion for the investigation of the *lakshana*." Here, *lakshana* appears to be used to designate the *Prāṭiśākhya* itself, as above it denoted the commentary to the latter. Once more, *atha* is declared to have the force of an introduction or heading, according to rule xxii.6, below: "*tu, atha, and eva* are respectively exceptive, introductory, and limitative;" and the connection of the rule is that *now* the list of sounds, the order of reading (*pāṭhakrama*), is made the subject of treatment.

The composition of *saṁāmnāya*, 'list, rehearsal,' is next pointed out, and the word is stated to mean "the collective sounds, beginning with *a* and ending with the *svarabhakti*, in their order, as taught by former learned men."

The catalogue itself follows, as understood by the commentator to be taught or implied in the rules of the treatise. First come the vowels, of which only sixteen are reckoned (see rule 5, below): *a, i, and u* have each a short, a long, and a protracted value, *r* only a short and a long, *l* only a short (W. and B. take the pains to write a figure 2 after the long *r*, and a 1 after the *l*, to point out clearly the number of *moras* they respectively contain; and B. adds after the *āi* and *āu* a 2, for the same purpose); second, the twenty-five mutes (see rule 7); third, the four semivowels (rule 8); and fourth, the six spirants (rule 9). This makes fifty-one sounds, clearly specified and counted in their order in the next succeeding rules. Of the rest, there is no so direct enumeration; the commentator has to infer them from their recognition by rules found in later portions of the treatise. Thus, he finds *anusvāra* acknowledged as an alphabetic element in rule 34 of this chapter, which teaches that it has the quantity of a short vowel; for, he says, "since it is made the substrate of a specific quantity, it is itself a concrete thing, and not, like nasalization, a quality." A passage from the *Çikshā*, it is true, appears inconsistent with this, but finds its sufficient explanation in the circumstance that that work includes in one expression the concrete thing and its quality. The cited passage is not to be found in the known text of the

tathā hi: a ā ās i ī īs u ū ūs r ṛ ṛ e āi o āu iti svarāḥ shodaça: ka kha ga gha ṇa ca cha ja jha ṇa ṭa ṭha ḍa ḍha ṇa ta tha da dha ṇa pa pha ba bha ma iti sparśāḥ pañcaviṅcatih: ya ra la va iti catasro 'ntasthāḥ: ṣa sha sa ha ḥka' hpa' iti śaḍ ūshmāṇaḥ: anusvāraḥ ca (i.34) iti sūtreṇā 'nusrāra uktāḥ: kālaviçeṣhā-grayadvād-asū 'dharmā na tv' anuśāsikavad' dharmāḥ: vidher 'madhyasthanāsikya' iti çikshāvācane' satī' dharmadharminor abhedavivakshayo 'papadyate: atha visarjanīyah (viii.5) ity anena' visarjanīya uktāḥ: nāsikāvivaraṇād ānu-nāsikyam (ii.52) ity anena' raṅga uktāḥ: prkṭasvarāt paro lo ḍam (xiii.16) ity anena' lakāra uktāḥ: sparśād anuttamād (xxi.12) iti catvāro yamā uktāḥ: rephoshmasaṁyoge repha-svarabhaktir (xxi.15) iti svarabhaktir uktā: anena kramena

Çikshā (and the same is the case with several of the passages quoted later: see the additional notes): it is given again, with more fullness, under viii.15. Next, for the *visarjanīya*, which our *Prātiçākhyā* does not count among the spirants, is given as authority rule 5 of the eighth chapter, a rule introductory to the euphonic changes of a final *h*. The commentator brings in as next constituent of the alphabet an element which he calls *raṅga*, and for which he cites the rule (ii.52) that "nasal quality is given by the unclosing of the nasal passage." The word *raṅga*, "coloring," though a common name for the nasal tinge of utterance, is not found in our *Prātiçākhyā*, nor even used in the commentary excepting here and under ii.52. What is described in the latter rule is in fact a "quality" (*dharma*), and not a "qualified" or concrete thing (*dharmin*); and its inclusion in the alphabet would stultify the argument with which the inclusion of *anusvāra* was but just now supported. It would seem that the commentator ought to be aiming here at the *nāsikya*, or euphonic insertion between *h* and a following nasal mute, and should quote for it rule xxi.14; he does not otherwise take account of it in his list, while yet it is precisely as well entitled to a place there as are the *yamas*. The nasalized semivowels, it is true, into which *n* and *m* are directed to be converted before *y*, *l*, *v* (v.26-8), are also left out of the enumeration, unless we suppose the *raṅga* to be meant to apply to their nasality; and I think it altogether likely that the commentator had them in view in its definition: but this is only avoiding one difficulty by running into two worse ones—namely, by omitting the *nāsikya*, and by reckoning as a member of the alphabet what is really only one of the constituent elements of certain sounds. Further, rule xiii.18 is made the warrant for the lingual *l*, rule xxi.12 for the four *yamas*, and rule xxi.15, finally, for the *svarabhakti*: and the conclusion is reached that "by this process, the number of sixty is clearly derivable from the rules themselves as that of the letters in the *Yajur-Veda*."

*yājurvedikavarṇānām*¹⁷ *shashtisamkhyā sūtrata eva vispashtā drashtavyā. nanu*

*trishashtīḥ catuḥshashtīr vā varṇāḥ çambhumate*¹⁸ *matāḥ: iti çikshāvacane sati katham shashtisamkhyā niyamyate: etā*¹⁹ *laukikavāidikasarcavarṇavishayam*²⁰ *iti*²¹ *çikshāvacane na virodhaḥ: atra tu*²² *sūtrāir etāvatām varṇānām*²³ *evo 'palambhād esha eva*²⁴ *nirṇayo varṇitah*²⁵.

varṇānām samāmnāyo varṇasamāmnāyah.

⁽¹⁾ G. M. *maṅgalidyanekārtha*. ⁽²⁾ W. G. M. *çiksh-*. G. and M. always write *çikshā*, B. and O. always *çikshā*; W. has *çi-* only in one other place (under xiv.28). ⁽³⁾ W. B. *aho*. ⁽⁴⁾ G. M. *-ryatā*; W. adds *vā*. ⁽⁵⁾ G. M. *pathe kramo*. ⁽⁶⁾ W. B. *om*. ⁽⁷⁾ W. *çishyāir*. ⁽⁸⁾ B. *shka*. ⁽⁹⁾ B. *shpa*. ⁽¹⁰⁾ G. M. *om*. ⁽¹¹⁾ B. *dharmāgatvād anusvāsikah*. ⁽¹²⁾ G. *ins. dharma*. ⁽¹³⁾ G. M. *-kād*. ⁽¹⁴⁾ G. M. *-nām*. ⁽¹⁵⁾ B. *om*; G. M. *tu*. ⁽¹⁶⁾ B. G. M. *om*. ⁽¹⁷⁾ W. *-vaid-*. ⁽¹⁸⁾ B. *amsumate*. ⁽¹⁹⁾ G. M. *tal*. ⁽²⁰⁾ G. M. *-savarṇavarṇa-*. ⁽²¹⁾ G. M. *ins. na*. ⁽²²⁾ G. M. *om*. ⁽²³⁾ G. M. *om*. ⁽²⁴⁾ G. M. *om*. ⁽²⁵⁾ B. *nir-* *ṇitah*.

An objection is now raised and removed. "Considering that the *Çikshâ* says 'the letters are regarded as sixty-three or sixty-four, in the opinion of *Çambhu*' (*Çikshâ*, verse 3; see Weber's edition of the treatise, in his *Indische Studien*, iv.348-9), how is the number sixty established? Answer: there is no inconsistency with the *dictum* of the *Çikshâ*, seeing that the latter has in view the whole body of sounds, as used both in the Veda and in common life; while here the determination (of sixty) is derived from the assumption of just so many letters by the rules of the treatise."

The alphabetic scheme is, then, as follows:

Vowels	{ simple,	<i>a ā ā3 i ī ī3 u ū ū3</i>	9	
	{ impure and diphthongs,	<i>ṛ ṝ ṝ̄ e ai o au</i>	7	16
Mutes	{ guttural,	<i>k kh g gh ṇ</i>	5	
	{ palatal,	<i>c ch j jh ñ</i>	5	
	{ lingual,	<i>ṭ ṭh ḍ ḍh ṇ</i>	5	
	{ dental,	<i>t th d dh n</i>	5	
	{ labial,	<i>p ph b bh m</i>	5	25
Semivowels,		<i>y r l v</i>		4
Spirants,		<i>ś ṣ sh s ṣ h</i>		6
Anusvāra,		<i>ṁ</i>		1
Visarjanīya,		<i>h</i>		1
Lingual <i>l</i> ,		<i>l</i>		1
Nāsikya,		(not written)		1
Yamas,		do.		4
Svarabhakti,		do.		1
whole number of letters,				60

With the exception of the nasal *y, l, v*, already referred to, this list includes all the alphabetic sounds treated of by the *Prātiçākhyā*. For what concerns the peculiarities of their character or classification, see the special rules of which they are the subject; as also, for the differences between the teachings of this and of the other kindred treatises with reference to them. Only the *Vāja-saneyi-Prātiçākhyā* includes in its text a complete list and enumeration of letters, and that by an afterthought, in a later and less genuine chapter (viii.1-31).

अथ नवादितः समानाक्षराणि ॥ २ ॥

2. Now the nine at the beginning are simple vowels.

2. *athe 'ti sañjñādhikārārthaḥ: asmin' varṇasamāmnāya ādita ārabhya nava varṇāḥ samānāksharasañjñā bhavanti: 'yathā: a ā ā3 i ī ī3 u ū ū3. sañjñāyāḥ' prayojanam: dīrghaṇ samānākshare savarṇapare (x.2) ity ādi. nanv idṛçī mahatī sañjñā kimarthā: çikshādiçāstraprasiddhyanurodhāye 'ti brāmaḥ.*

¹ B. *tasmin*. ⁽²⁾ W. B. *a ā ā3 ity ādi*. ³ G. M. *-jñā*. ⁴ G. M. *-tham*. ⁵ G. M. *om. -di*.

Literally, 'are homogeneous syllables;' *samānākshara* and its correlative *samānākskhara*, 'syllable of combination,' being the current names for simple vowel and for diphthong; the latter, however, is not used in this treatise. The nine intended are, as shown in the preceding list, *a ā āḥ i ī īḥ u ū ūḥ*. The *ṛ* and *ḷ* vowels are denied the quality of simplicity or homogeneity, although their structure as composed of heterogeneous elements is not further described; the Rik Pr. (xiii.14), the Vāj. Pr. (iv.145), and the Ath. Pr. (i.37-9) give the details of their formation, while nevertheless the two first expressly include *ṛ* and *ḷ* among the *samānāksharas* (omitting *ḷ*, apparently, because no case anywhere occurs that should test its quality), and the same classification is inferribly recognized by the last.

The commentator explains the *atha* of this rule as signifying the introduction of the subject of names or technical appellations (*saṁjñā*), and cites, as example of the use of the term, rule x.2, respecting the coalescence of two similar simple vowels into a long vowel. Finally, the unwieldiness of the long word *samānākshara* striking his mind, he asks "why such a big name?" and relieves himself by the answer "we say, in order to correspond with the established usage of the *Ṣikshā* and other text-books." The *Ṣikshā* as we know it, it may be remarked, does not employ the term.

द्वे सवर्णे ह्रस्वदीर्घे ॥ ३ ॥

3. Two and two, short and long, are similar.

That is to say, as the commentary explains, of these simple vowels, two and two short, two and two long, or a long and a short, are called "similar." The meaning seems rather to be that, of the three triplets which make up the category of simple vowels, the first two in each triplet, the short and the long, will be designated as "similar"—to the exclusion, namely, of the *pluta* or protracted vowels. The term is used but once in the treatise (namely in x.2, the rule last above quoted), as applied to vowels, and nothing is practically gained by denying its inclusion of the protracted vowels, since these are specially protected from coalescence by the rule x.24. The *ṛ*-vowels are here again shut out, as in the preceding rule; and, in fact, no case occurs in the Vedic text in which two of them are fused into one.

3. *teshu¹ samānākshareshu dvedve hrasve dvedve dīrgha² hrasva-dīrgha³ dīrghahrasve vā 'kshare parasparam savarṇasaṁjñā bhavataḥ. iyaṁ anvarthasaṁjñā: savarṇatvaṁ nāma sādṛśyam ucyate: tasmād akārādīnām ikārādībhir na savarṇasaṁjñācāṅkā bhinnasthānaprayatnatvād⁴ anayoh. saṁjñāyāḥ prayojanam: dīrghaṁ samānākshare savarṇapare (x.2) iti.*

hrasvaṁ ca dīrghaṁ ca hrasvadīrgha.

¹ G. M. *teshu*. ² G. M. ins. *vā*. ³ B. om.; G. M. ins. *vā*. ⁴ B. *-tvād*.

The word translated 'similar' means literally 'of identical color' (i. e. sound), and is several times applied later to identity of consonantal sound. It is, as the commentator points out, a self-explaining term, or one whose application is directly in accordance with its natural meaning (*anvartā*); and hence no suspicion is to be entertained of the inclusion of *a* and *i*, for instance, as "similar," because of their different mode of organic production. As example of the use of the term is again cited x.2.

न पुतपूर्वम् ॥३॥

4. Not so, when a protracted vowel precedes.

This is an arbitrary exclusion, made to fit a particular case, which might with more evident propriety have been provided for later, where such cases are under treatment, rather than here in the preliminary definition of terms (compare a somewhat similar case in the Rik Pr., i.1, r. 4). The commentator paraphrases the rule "a simple vowel having a protracted one before it is not termed 'similar,'" and goes on to cite and explain in full the case to which it applies. In the phrase *agne: iti: āha* (vi.5.8⁴), the word *agne* has its final diphthong protracted, and becomes *agnā* ³*i*. By the rule (x.2) for the coalescence of two similar simple vowels into the corresponding long vowel, this would then unite with the following word to form *agnā* ³*i* ¹*ti*. The quality of similarity, however, being denied by the present rule to the final *i*, it is treated as a dissimilar vowel, being first converted into *y* by rule x.15, the *y* dropped by x.19, and the coalescence of the remaining *ās* with the following *i* (as prescribed by x.4) prevented by x.24: thus is assured the reading *agnā* ³*i* ¹*ty āha*.

षोडशादितः स्वराः ॥५॥

5. The sixteen at the beginning are vowels.

Namely, says the commentator, the sixteen beginning with *a* and ending with *au*. As example of the use of the technical term

4. *phutapūrvam samānāksharam savarnasamjñam na bhavati. phutam asmāt pūrvam iti phutapūrvam. yathā: agnā* ³*i* ¹*ty āha* ¹*ty ātra dīrghaṁ samānākshare savarnapare* (x.2) *ity ekādeṣaḥ prasaktaḥ: tac cā* ¹*'nishtam: pratishiddhāyām tv evaṁ savarnasamjñāyām pāriṣeṣhyād ivarṇokārāu yavakārāv* (x.15) *ity pūrvasye* ¹*'kārasya yatvam syāt': sa ca yakāro lupyete tv avarnapūrvāu yavakārāv* (x.19) *ity lupyate: yakāre lupte sati ivarnapara ekāram* (x.4) *ity ekārah* ²*prasaktaḥ: so* ¹*'pi* ¹*nishidhyate na plutapragrahāv* (x.24) *ity anena: tasmād agnā* ³*i* ¹*ty āhe* ¹*'ti prasidhyati*."

¹ W. om. ² G. M. *ekādeṣaḥ*. ³ G. M. *vi*. ⁴ G. M. *sidhyati*.

svara, 'vowel,' he quotes the rule (ix.10) prescribing the conversion of *visarjaniya* into *y* before a vowel.

Our *Prāṭiśākhya* is to be commended for not including in its list of vowels the long *ī*, and for postulating no useless protracted forms of *r* and *l*.

शेषो व्यञ्जनानि ॥ ६ ॥

6. The rest are consonants.

As example of the term *vyañjana*, 'consonant,' rule xxi.1, which pronounces the consonant a member of the adjacent vowel, is cited in the commentary, according to the two manuscripts from northern India; those from the south substitute for it the opening rule of the third chapter, and also omit the explanatory statement "beginning with *k* and ending with *svarabhakti*," which is given by the others.

आद्याः पञ्चविंशति स्पर्शाः ॥ ७ ॥

7. The first twenty-five are mutes.

The commentator explains: "among the consonants, the first twenty-five letters are called mutes" (*sparṣa*, literally 'contact'). The northern manuscripts add, as under the last rule, "beginning with *k*, and ending with *m*." It is next pointed out that rules 2 and 5 contain the specification *āditaḥ*, 'at the beginning,' and that the different phraseology of this rule, namely *ādyāḥ*, 'first,' indicates a difference of meaning: it signifies that the sounds referred to

5. *varnasamāmnāyasyā* "dita ārabhya shoḍaṣa varṇāḥ svarasamjñā bhavanti: akārādaya makārāparyantā ity arthah. samjñādyāḥ prayojanam: atha svaraparo yakāram (ix.10) ity ādi.

¹ G. M. *varṇānām sam-*.

6. *svarebhyaḥ śesho varṇarāḍṣir vyañjanasamjñā bhavati: 'kakārādisvarabhaktiparyantā ity arthah'. samjñādyāḥ prayojanam: 'vyañjanañ svarāṅgam' (xxi.1) iti.*

⁽¹⁾ G. M. om. ⁽²⁾ G. M. *atha* "dau uttare vibhāge hrasvañ vyañjanopara (iii.1).

7. *vyañjaneshv ādyāḥ pañcaviṃśativarṇā sparṣasamjñā bhavanti: 'kakārādayo makārāntāḥ'. 'samjñādyāḥ prayojanam: sparṣa sparṣaparaḥ (xiv.27)'. atha navā "ditaḥ samānākṣharāṇi (i.2): shoḍaṣā "ditaḥ svarāḥ (i.5) itivād ādita iti vaktavya ādyā iti śabdāntaraprayogo 'rthāntarasūcakāḥ: vyañjaneshv ādyā na tu svareṣv ādyā iti vijñeyam'.*

⁽¹⁾ G. M. om. ⁽²⁾ G. M. remove to end of exposition, and for *sparṣaparaḥ* read *sparṣa* ity ādi. ³ G. M. *jñeyam*.

are first among the consonants, not first among the vowels (better, we should say, not first in the whole list). Of this style of interpretation, which forces a special significance into very innocent variations of phraseology, we shall meet with other and more striking examples farther on.

Rule xiv.27 is given as instance of the employment of the technical term here defined.

पराश्रतस्रो ऽन्तस्याः ॥ ८ ॥

8. The next four are semivowels.

The four semivowels are *y*, *r*, *l*, *v*. The rule cited by the commentary in illustration of the use of the term "semivowel" (*antaśthā*, i. e. *antah-sthā*, 'standing between, intermediate [between consonant and vowel]': see note to Ath. Pr. i.30) is one (v.28) prescribing the treatment of final *m* before an initial semivowel.

परे षडूष्माणः ॥ ९ ॥

9. The next six are spirants.

Namely, the three sibilants, *ṣ*, *ś*, and *s*, the *jihvāmūliya*, *z*, the *upadhmanīya*, *q*, and the aspiration, *h*. As regards the sounds to which the name *āshman*, 'flatus,' shall be given, the phonetic treatises are greatly at variance. The Vāj. Pr. (viii.22) limits the class to the sibilants and *h*; the Ath. Pr. (see note to i.31) apparently adds the guttural and labial spirants and the more indistinct *visarjanīya*; the Rik Pr. (i.2), these and the *anusvāra*. We have an equal right to be surprised at the inclusion of this last in the class, and at the exclusion from it, by our treatise, of the *visarjanīya*.

To instance the employment of "spirant," the comment cites the rule (xiv.16) forbidding the duplication of a spirant before a vowel.

स्पर्शानामानुपूर्व्येण पञ्चपञ्च वर्गाः ॥ १० ॥

10. Of the mutes, the successive fives are the series.

The commentary paraphrases: "among the mutes, five and five sounds, in their order, have the designation 'series'; they begin respectively with *k*, *c*, *ṭ*, *t*, *p*, and end with *ś*, *ṣ*, *ṇ*, *n*, *m*." This

8. *sparṣebhyaḥ pare catvāro varṇā antasthāsamjñā bhavanti. samjñādyāḥ prayojanam*: 'antasthāparag ca savarṇam anusāsikam (v.28) ity ādi.

¹ A lacuna in W., extending to the word *prayojanam* in the commentary to the next rule.

9. *antasthābhyaḥ pare śhaḍ varṇā āśhmasamjñā bhavanti. samjñādyāḥ prayojanam*: *āśhmā svaraparah* (xiv.16) ity ādi.

exposition is in accordance with the requirements of the context, the treatise being here engaged in defining its technical terms. Otherwise, we might divide --- *pañca pañcavargāḥ*, and translate, like the corresponding rule in the Rik Pr. (i.2), 'there are five series, of five each.'

The illustrative rule (xiv.20) cited in the comment teaches the non-duplication of a mute of the lingual series before one of the dental series.

प्रथमद्वितीयतृतीयचतुर्थोत्तमाः ॥ ११ ॥

11. And are called first, second, third, fourth, and last.

Each series of five mutes, that is to say, is composed of a surd, a surd aspirate, a sonant, a sonant aspirate, and a nasal, as *t, th, ḍ, dh, n*; and these classes are named according to their order in the several series. The commentator makes no note here of the physical difference of the classes, but says "In each series, the sounds, in their order, are styled first, second, third, fourth, and last. Even though a name founded on enumeration obviously belongs to them [is assured them, without a special rule to that effect], yet, for the purpose of denying appellation on the ground of any other enumeration, the technical terms 'first' and so on are prescribed, to enjoin a certain enumeration.(?) How so? Why, to establish the designation 'first' and so on for *k* and its successors alone, and to deny to the vowels, semivowels, spirants, etc., designations founded on their enumeration." And he proceeds to cite four rules (ii.9; xiv.12, 24; viii.3: but the southern MSS. cite v.38 instead of ii.9) as examples of the use of the five terms defined.

10. *sparśānām madhya ānupāreyaṇa pañcopaṇca varṇā var-gasañjñā bhavanti: ka-cu-ṭa-ta-pādāyo² śa-ña-ṇa-na-māntā-ity arthaḥ. sañjñāyāḥ prayojanam: ṭavargaḥ ca tavargaparaḥ (xiv.20) iti.³*

¹ B. om. ² G. M. -pādāyāḥ. ³ W. om. the cited rule; G. M. *ity ādi.*

11. *ekāikāsmiṇ varge yathākramena¹ varṇāḥ prathamadvitī-yatrītiyacaturthottamasañjñā bhavanti: siddhe² pi saṁkhyāni-mitte nāman³ saṁkhyāntarānabhidhānārthaṁ⁴ saṁkhyāntaraṁ⁵ kathayitum prathamādisañjñāvidhānam: tat katham: kakārā-dīnām eva⁶ prathamādisañjñāpratītyartham: svarāntasthoshma-prabḥtiṣhu tatsaṁkhyāsañjñāpratishedhārthaṁ⁷. sañjñāyāḥ prayojanam: prathama ūshmaparo dvitīyam (xiv.12): trītiyaṁ svaraghoshavatparaḥ (viii.3): kakāro hacatur-theshu (ii.9): nā⁸ nuttama uttamaparaḥ (xiv.24): ity ādi.*

¹ G. M. -kramam. ² G. M. nāmni. ³ B. saṁkhyāntarābh.; G. M. saṁkhyābh. ⁴ M. sañjñāntaram: as to the true reading and interpretation of this clause I am by no means confident. ⁵ G. M. om. ⁶ G. M. *tu saṁkh.* ⁷ G. M. substitute for this rule part of v.38, viz. *prathamapūro kakāro caturtham tasya saṁhānam.*

The other Prâtiçâkhyas employ the same designations for the mutes (save that the Vâj. Pr. also calls the nasals *pañcama*, 'fifth'), but without taking the trouble to define them or prescribe their use by a rule.

उष्मविसर्जनीयप्रथमद्वितीया अघोषाः ॥ १२ ॥

12. The spirants, *visarjanīya*, and the first and second mutes, are surd.

The Rik Pr. gives (i.2,3) a similar statement; the Ath. Pr. uses the terms "surd" and "sonant" without defining which consonants form each class; the Vâj. Pr. (i.50-53) substitutes for the terms arbitrary formulas.

The physical peculiarity of the surd utterance is defined in the next chapter (rules 5,10).

The commentator illustrates the use of the term by the rule (ix.2) concerning the treatment of *visarjanīya* before a surd.

न रुकारः ॥ १३ ॥

13. But not *h*.

"*H* is not styled a surd; this is an exception rendered necessary by the circumstance that *h*, being [by i.9] a spirant, would otherwise be included [by the last rule] in the class of surds," says the comment.

All the phonetic treatises treat *h* as a sonant. For further definition of its character, see rules ii.6,9,46,47, below.

व्यञ्जनशेषो घोषवान् ॥ १४ ॥

14. The rest of the consonants are sonant.

The commentary enters into a rather lengthy defense of the propriety of this rule, which reads literally as follows: "The remainder of the consonants other than the surds is styled sonant. Even though, when the surds have already been stated in rule 12, the sonant quality of the rest, on the principle of 'remainder,' is assured—just as, when it is said, 'of Devadatta and Yajñadatta,

12. *āshmāṇaḥ ca visarjanīyaḥ ca prathamadvitīyāḥ¹ cā 'ghoṣhasamjñā bhavanti. samjñāyāḥ prayojanam: aghoṣhaparas tasya sasthānam āshmāṇam² (ix.2) ity ādī³.*

¹ B. *prathamāḥ ca dv-*. ² W. B. omit the last two words of the rule. ³ G. M. om.

13. *na bhavaty aghoṣhasamjñā¹ hakāraḥ: āshmatvād aghoṣhatve prāpte tadāpavādo 'yam.*

¹ W. *-jñāko*.

Devadatta owns no kine,' the conclusion is assured that Yajña-datta is a kine-owner—nevertheless, the indication of the technical term is made in the text-book, for the sake of practical convenience (?). Also, because of the superiority of express mention over inclusion in a remainder. Otherwise—the name of surd is denied to *h* by rule 13, nor is *h* sonant, there being no rule to that effect; and so with the rest of the consonants; the vowels are also in like manner not sonant and not surd—this being the case, when the rule shall be given (ix.8) 'also when followed by a sonant,' the doubt would arise, 'followed by a sonant' means followed by what? Let not this be so: in this view the present rule is undertaken." It is added "In this rule, the distinctive meaning, in the form of objection and replication, is set forth by Māhisheya." And the rule ix.8, already referred to, is quoted again by way of illustration of the use of the term "sonant."

The Rik Pr. (i.3), after specifying the surd letters, leaves the sonants to be inferred *pāriçeshyāt*, 'by the remainder-principle,' as is expressly pointed out in the commentary on the passage (see Regnier's edition, note to rule i.12).

The vowels are not included under the designation *ghoshavant*, 'sonant,' although (as is explained in rule ii.8) formed of the same material with the sonant consonants.

Our treatise does not, like the other Prātiçākhyas (R. Pr. i.3; V. Pr. i.54; A. Pr. i.10), define the "first" and "third" mutes as *soshman*, 'aspirated.'

14. *aghoshebhyo¹ vyañjanaçesho ghoshavatsamjño bhavati: yady apy ūshmaṇīsarjanīyapraṭhamesho² aghosheshū³ kteshu vyañjanaçeshasya pāriçeshyād ghoshavattvaṁ siddham: yathā devadattayajñadattayor⁴ apaçur devadatta ity ukte⁵ paraḥ paçumān iti siddham: tathā⁶ 'pi çāstre saṁvyavahārārtham⁷ samjñānirdeçah kriyate: pāriçeshyād api kañthokter viçeshāt⁸: anyathā na hakārah⁹ (i.13) iti hakārasyā¹⁰ ghoshasamjñā nishidhyate: nā¹¹ 'pi hakāro ghoshavān: vidhyabhāvāt: tathā¹² 'va vyañjanaçeshah: svarā api tathā¹³ na ghoshavanto nā¹⁴ 'py aghoshāḥ: tathā sati ghoshavatparaç ca (ix.8) iti yatra¹⁵ vakshyati tatra¹⁶ saṁdeçah syāt: ghoshavatparo nāma kimpāra iti: tan mā bhūd iti¹⁷ dān sūtram¹⁸ ārabhyate¹⁹.*

vyañjanarūpaḥ çesho vyañjanaçeshah²⁰.

atra sūtre codyaparīhārārūpa²¹ eṣa viçesho māhisheyabhāshitah.

samjñāyāḥ prayojanam: ghoshavatparaç ca (ix.8) ity ādi.

¹ G. M. ins. 'nyo. ² G. M. ūshmaṇīsarjanīy. 'ty. ³ B. ins. ca. ⁴ W. -dattaitiyor. ⁵ W. saṁhār. ⁶ G. M. viçeshatvāt. ⁷ G. M. om. ⁸ G. M. yatrayatra. ⁹ G. M. tatratatra. ¹⁰ B. çāstram. ¹¹ G. M. repeat the rule itself here. ¹² W. om.; B. adds yah çeshah. ¹³ G. M. om. rūpa.

आप्रावोपाभ्यधिप्रतिपरिविनीत्युपसर्गाः ॥ १५ ॥

15. *Ā, pra, ava, upa, abhi, adhi, prati, pari, vi, ni*—these are prepositions.

These ten words are but half the number which are reckoned as prepositions by the Rik and Vāj. Prātiçākhyas (R. Pr. xii.6; V. Pr. vi.24) and by Pāṇini (see the *gana prādayah*). The commentator notes the discordance with Pāṇini, and inquires why the maker of this rule presumingly cuts short the list of prepositions with the word *iti* in it. His reply is, that only so many are recognized by the Yajur-Veda. Another objection which he raises and removes, arriving at the comfortable conclusion "therefore there is no discordance whatever," I do not see the point of. The discordance is a real one, and difficult to explain. The term preposition (*upasarga*) is used in three of the rules of the treatise, viz. vi.4 (which is the cited instance in the commentary), x.9, and xiv.8: for the bearing of the restriction in number, see the notes on those rules.

वर्णः कारोत्तरो वर्णाख्या ॥ १६ ॥

16. A sound followed by *kāra* is the name of that sound.

That is, for example, *akāra* is the name of *a*, *ekāra* of *e*, and so on. The Vāj. Pr. (1.37) is the only other treatise which takes the trouble to prescribe this usage, common to them all. Our own refers to it also in a later rule (xxii.4). The word *kāra* means 'making, producing.' It is in the rules of the Prātiçākhyas added not only to simple alphabetic sounds (*varṇa*) as their names, but also to syllables like *aḥ* and *an* (see below, rules 23, 53), and the

15. *ity ete çabdā upasargasamjñā bhavanti. nanu praparāpasamanvavanirdureyān ityādi pāṇinīyā viçeshena bhaṇanti*: *katham atra sūtrakṛtā nirargalam upasargā iticabdena saṁkucitā ucyante. yajurvedavishaya etācanta eve 'ti mantavyam. tarhi praparāpasam¹ iti samuccaye viçeshapāṭhaḥ² katham upalabhyate³. itiparatcavidhāne tasya tātparyam na tā 'pasargasamjñāvidhāne viçeshapāṭhaḥ*: *tasmān na kenacid virodhaḥ. samjñāyāḥ prayojanam: upasarganishpūrvo 'nudatte pade* (vi.4). *iticabdaḥ prakāravācī*.

¹ W. B. and G. p. m. *bhavanti*. ² B. *prāpaparāpasam*; G. M. *prāpasam*. ³ G. M. *viçeshah*; W. *viçeshanip*. ⁴ B. *-lakshyate*. ⁵ W. B. *viçeshah p*.

16. *kārottaro varṇo varṇasyā 'khyā bhavati. yathā: athāi 'kārekārāv* (iv.8) *iti*.¹ *kāraçabda uttaro yasmād asāu kārotarah*.

¹ G. M. *ity ādi*.

commentator very frequently uses it to make names for brief words, like *ca*.

Rule iv.8, respecting *e* and *i*, is the chosen illustration of the combination here taught.

अकारव्यवेतो व्यञ्जनानाम् ॥ १७ ॥

17. But with an *a* interposed, in the case of the consonants.

That is, the name of *k*, for instance, is (*k-a-kāra*) *kakāra*. Compare the equivalent rule, Vāj. Pr. i.38.

The commentator cites rule v.22, respecting the conversion of *t* to *c*.

न विसर्जनीयजिह्वामूलीयोपध्मानीयानुस्वारनासि-
व्यानाम् ॥ १८ ॥

18. Not of *visarjaniya*, *jihvāmūliya*, *upadhmaniya*, *anuvāra*, and the *nāsikyas*.

The term *nāsikya* designates here, of course, the nasal figments taught in rules xxi. 12-14. All these indistinct, hardly articulate, sounds must be spoken of by their descriptive titles, not by any name founded upon their form. The commentator explains that the appending of *kāra* to the sounds here specified—which would otherwise be regular, since they come under the category of *varṇa*, 'alphabetic elements'—is annulled by the rule: adding as a reason, that they are nowhere met with thus treated. He then

17. *akāravavyavahito*¹ *varṇaḥ kāracaḥdottaro vyañjanānām ākhyā bhavati. yathā*²: *takāraḥ cakāram* (v.22) *ity ādi. akāreṇa vyavahito*³ *kāravavyavetaḥ.*

¹ W. -*vyaveto*. ² W. B. put this word after the cited rule. ³ G. M. *vyaveto*.

18. *visarjanīyādīnām varṇatvāviṣeṣhāt kārottaratvam prāptam anena nicartyate: na khalu visarjanīyādīnām kārottaratā bhavati: kutaḥ: sarvatra*¹ *prayogānupalambhāt. nanu yathā varṇaḥ kārottaro varṇākhyā* (i.16) *iti varṇacaḥdāvācyasyāi 'ca kārottaratvam nakāro nakāram* (vii.1 or xiii.6) *ity ādi: na tu vācakasyāi 'ca*²: *anyathā varṇakāra iti syāt: tadvad*³ *visarjanīyādīnām*⁴ *atrā 'pi vācyagrahaṇam eva yuktam: nā 'nyathā: tathā sati vācakaparatayā vararucyādiviracitam*⁵ *udāharaṇam avasāne ravisarjaniya* (xiv.15) *ity ādy aruciram: iti cet: māi 'cam maṁsthāḥ: vācyānām*⁶ *kevalānām aprayogād atra vācyavācakayor abhedavivakṣhayā sūtrasaraṇir*⁷ *ity udāharaṇaga-manikā.*⁸

¹ G. M. ins. *tathā*. ² G. M. om. *eva*. ³ W. *tad*. ⁴ G. M. ins. *ity*. ⁵ W. B. *vararucād*; G. M. *vārarucād*. ⁶ W. B. *vācyādīnām*. ⁷ W. -*nam gam*.

goes on to raise and refute a very subtle and hair-splitting objection. In rule 16, he says, *kāra* is prescribed to be added not to the vocable (*vācaka*) *varna*, 'sound,' itself, but only to the thing designated (*vācya*) by that vocable; so likewise in this rule it is proper to understand by *visarjanīya* etc. the things designated by those words, and nothing else (and hence, the rule must not be interpreted as implying that *visarjanīya* and the other names given are, in default of those formed with *kāra*, the accepted designations for the sounds in question). This being the case, the illustration given under the rule by Vararuci and others—namely, rule xiv.15, speaking of *r* and "*visarjanīya*" as not liable to duplication—is an unsuitable one. Such is the objection. The reply is: you must not think so; since the sounds designated by the terms in the rule are actually nowhere employed by themselves (as designations), the rule simply intends to include designation and thing designated in one expression; and the quoted example is proper enough.

एफस्तु रस्य ॥ ११ ॥

19. Of *r*, however, *epha* forms the name.

That is to say, the technical designation of *r* is *repha*; *ra* being also admitted, by rule 21, below: *rakāra* is not found anywhere in the Hindu grammatical literature. This peculiarity of treatment of *r*, as compared with the other consonants, is to be paralleled with the way in which it is written in consonant groups, almost as if a vowel.

The Vāj. Pr. has an equivalent rule (i.40).

The word *tu*, 'however,' in this rule, according to the commentator, is meant to deny the application to *r* of both the rules 16 and 17. Some, he says, hold that it denies only rule 17, or the insertion of *a* between *r* and the appended *kāra*; but this is wrong; for it would imply that the name of *r* was made sometimes by appending *kāra* and sometimes by appending *epha*, just as an alternation is in fact allowed by rule 21 below between *ra* and *repha*, and exemplified by rules vii.11 and xxi.15; while no

19. *rasya tv ephaçabda¹ ākhyā bhavati. yathā: rephoshma-
paraḥ² (xiii.2) iti. repḥasya vyañjanatvāviçeshāt prāptam kārōt-
taratvam akāravayetatvam ca: tad ubhayaṁ tuçabdo nivāra-
yati. anye tv anyathā manyante: akāravayetatvam eve³ 'ti: tad
asādhū: tathā sati kadācid ephottaratā⁴ kadācit kārōttaratā ce⁵ 'ti
vikalpaḥ syāt: yathā 'kāro vyañjanānām (i.21) iti vidhānād
vikalpaḥ: tathā hi⁶ rephoshmasamyoḡe repḥasvaraabhak-
tiḥ⁷ (xxi.15): rashahpūrvo havanī (vii.11) ity ādi: na tv evam
kārōttaratvam api vikalpena⁸ scikṛtam⁹ kutrācit: tasmād asmad-
ukta eva yuktas tuçabdārthaḥ.*

¹ G. M. *reph-*; and M. reads *repḥas* in the rule itself. ² W. -*shmaçabda*. ³ B. *rephaksharald*; W. *reph-*. ⁴ W. B. *pi*. ⁵ W. B. om. ⁶ G. M. *naka*. ⁷ G. M. *taḥ*.

instance of a name formed with *kāra* is anywhere to be met with. This is a very easy demolition of a very insignificant man of straw.

इस्वो वणोत्तरस्त्रयाणाम् ॥२०॥

20. The short vowel, with *varṇa* after it, is the name of the three vowels.

The "three vowels" referred to are the three quantities—short, long, and protracted—of the vowels *a*, *i*, *u*, respectively; *varṇa*, in this case, indicating only the 'color,' or phonetic complexion, of the vowel, without regard to its length. The Ath. Pr. has the same usage of this term, but without defining it by rule. As our treatise acknowledged no protracted *ṛ*, and neither a long nor a protracted *ḷ*, it does not admit the compounds *rvarṇa* and *lvarṇa*: of the other three it frequently avails itself. The instance selected by the commentator is rule x.4, which directs the combination of *a* with a following *i*, *ī*, *is* into *e*.

अकारो व्यञ्जनानाम् ॥२१॥

21. An *a* forms the names of consonants.

This rule allows us to call a consonant not only, as prescribed in rules 16 and 17 above, by a name formed by adding *kāra* with *a* interposed, but also by one formed with *a* alone. The commentator's example is rule v.22, where *t* and *c* are referred to as *ta-kāra*, *ca-kāra*, and *ṣ*, *c* again, and *ch*, as *ṣa*, *ca*, and *cha*. If something merely additional to the *kāra*, instead of alternative with it, were intended in the rule, we are told, rule 17 would be made meaningless. But, says an objector, why use *kāra* at all for the purpose, when even along with it the *a* has to be brought into requisition? let this alone furnish the name. The reasonableness of the objection is conceded, but the commentator alleges as sufficient justification of the practice followed, that it is in accordance with that of the *Çikshā* and other text-books.

He continues: others assert that the *a* added to a consonant indicates (not that consonant pure and simple, but) a syllable composed of the consonant and any following vowel; as for instance in rule ix.3, "*visarjanīya* followed by *kṣa* is not assimilated;" where the examples are *manah kṣheme* (v.2.17), *ghanāghanah kṣhobhanah* (iv.6.4¹: so all the MSS., both here and under ix.3; my MS. of the Sanhitā reads *kṣhobhanih*), and *ukthaḥāsaḥ kṣhāma* (ii.6.12⁴). This is unsound; for then we should have to read *ishe tvā* (for *ishe tvā*, i.1.1 et al.), by the rule vii.13, "after *vāghā* and *sha*, *t* becomes *ṭ*;" which is wrong. Moreover, in the rule (xii.

20. *varṇottaro hrasvo* ¹ *hrasvadirghaphlutāndm ākhyā bhavati. yathā: icarṇapara ekāram* (x.4) *ity ādi. varṇaḥabda uttaro yasmād asāu varṇottarah.*

¹ G. M. ins. *trayadān.*

4) "*ya, va, na, ha*, when followed by vowels," the final specification would be useless, because already implied in the names given to the letters. Hence the opinion referred to is wrong, and the name taught by the rule indicates the consonant alone.

As for the actual usage of the treatise, it is somewhat equally divided between the two modes of designation of the consonants: names formed with *a* alone occur nearly sixty times; with *akāra*, nearly eighty times. This is exclusive of *r*, which is called *ra* four times, *repha* fifteen times.

Compare rule i.39 of the Vāj. Pr.

ग्रहणस्य च ॥ २२ ॥

22. As also, of a cited word.

The term *grahana* is used in only two other rules of the Prātiśākhya (i.24,50), but occurs in the commentary times innumerable, in the sense of 'citation, word taken or extracted from the Saṃhitā to be made the subject of some prescription' (root *grah*, 'seize, take'). The commentator, however, gives it an artificial and false etymology: it denotes, he says, either a word respecting which something is to be enjoined (*lakshya*), or one which is the cause (*nimitta*) of an effect produced in some other word. The former is called *grahana* because it is "seized" (i. e. "affected"); the latter, because something is "seized" or "affected" by it. It is, he continues, a part of a word, a theme or base. The *ca*, 'also,' of the rule brings forward, or indicates the continued implication of, the *a* of the preceding rule. The meaning is, then, that *a* forms the name of a citation, a theme, in whatever situation it may occur.

21. *vyañjanānām akāra ākhyā bhavati. yathā: takāraḥ cakāraṇ¹ śacachaparāḥ* (v.22) *ity ādi. kārapabdottaratcam idam ca vikalpyate: samuccaye tv akārayaveto vyañjanānām* (i. 17) *iti vyartham syāt. namu tarhi kārottaratā² kimarthā: tadānām api svarāpenā³ 'kāralābhāt: sa evā⁴ 'khyā bhavatu. satyam: śikshādīgāstraprasiddhasamketānusāreṇa⁵ 'ti parihārah. apare tu saṅgirante: akārah sarvasvarāntasya vyañjanasya grāhaka iti: yathā: man-----: ghan-----: ukth-----: ity ādi na kshaparāḥ* (ix.3) *iti nishedhasyo 'dāharaṇam syād iti. tad asāram: kutah: vāghāshapārvas tash ṭam* (vii.13) *iti shapārvatvāt takārasya ṭatve kṛte ish----- ity syāt: tac cā⁶ 'nishtam: kim ca: yavanahasvarapareshe⁷ (xii.4) iti atra svaraparaśabdō vyarthah syāt: bhavanmate sarvasvarāntasya⁸ svikāranīyamāt: tasmād anupapannam eva⁹ tan matam manmahe: kim tu varṇamātrasyā¹⁰ 'khyā.*

¹ W. B. omit these first two words of the rule. ² G. M. -*tvam*. ³ G. M. -*tham*.
⁴ G. M. -*avyavaharā*. ⁵ G. M. -*sārāya*. ⁶ W. om. ⁷ G. M. om. ⁸ G. M. -*shatvapā*.
⁹ W. -*yavanahaparasvar*. ¹⁰ G. M. -*ntamātrasya*. ¹¹ G. M. -*evā*.

That is to say, if a word be cited in the text of a rule by its theme-ending *a*, all its cases or other derivative forms are to be regarded as equally had in view by the rule. Reference is twice made to this principle hereafter by the commentator (under rules vi.13 and x.14), to justify such inclusions. The latter of the cases he here brings up, as example of a *nimitta*, or citation of an affecting cause; the cited word is *oshtha*, which is declared to occasion the loss of a preceding *a* or *ā*: the only two instances of this combination which the Sanhitā contains are quoted in illustration, viz. *svāh* *oshthābhyām* (vii.3.16¹), and *upayāmam adharen' oshthena* (v.7.12). As example of a *lakshya*, or citation of a word to be determined by rule, he quotes the end of rule xvi.26, with its illustrative citations, *kiñčilap caturthah* (v.5.9²), and *kiñčilāya cakshayanāya ca* (iv.5.9¹). This latter example is not very well chosen, as the case is a somewhat difficult and anomalous one (see the note on xvi.26).

This rule, like some of those that follow, is of very small value, since final *a* is not the necessary sign of a cited theme in which other cases are included; and, on the other hand, parts of words not ending in *a* are often cited "for the sake of the inclusion of many words" (*bahūpādānārtham*).

अःकार आगमविकारिलोपिनाम् ॥ २३ ॥

23. *Ah* makes the name of an increment, or of an element suffering alteration or elision.

Here, again, is a precept hardly called for, as the construction and connection of each rule shows in what way any nominative it contains is to be understood, without such an explanation as this, which applies only to a part of the cases, and is unable to teach us which of the three possibilities it contemplates is the actuality in any given case. Moreover, it is faultily expressed, and the commentator is obliged to explain that *ah* here stands for the ending of the nominative case, in the dual and plural as well as the singular. He quotes in illustration five rules: xiv.5 exemplifies a singular increment; vii.1, a singular altered element; v.19, a singular elision; v.25, two-fold altered elements; xxi.12, plural increments.

22. 'lakshyam nimittam ca grahanam ity ucyate: grhyata' iti grahanam: grhyata anene 'ti nimittam api grahanam: paddi-kadeṣaḥ prātipadikam iti yāvat: cakārah pārvastrotkram akāram ākarshati: grahanasya prātipadikasya sarvāvasthasyā 'kāra' ākhyā bhavati. yathā: kiñčilakiñčilā (xvi.26) iti parakiñčilāśabdo lakshyam udāharanam: yathā: kiñṣ- cat-....²: kiñṣ- caksh-....: oshthevaḥparō lupyate (x.14) iti tu' nimittam: yathā: svā-....: upay-....

(1) W. inserts this passage out of place, between rule 19 and its commentary
² G. *grahanyata*. ³ G. M. omit this example. ⁴ G. M. om.

Rule 28, below, is very intimately connected with this, and the insertion of rules 25-27 between is quite unaccountable.

Rik. Pr. i.14 includes the second of the three specifications here made, along with rule 28.

ग्रहणं वा ॥ २४ ॥

24. Or the simple citation.

The commentator says: "Of these—namely the increment etc.—there is in some cases, alternatively, citation; the meaning is, without any *ah*." And he goes on to quote three rules, in which increment (xvi.29), alteration (vii.3), and elision (v.15) are taught otherwise than as prescribed in the preceding rule—which is not, however, thus amended into acceptableness.

ग्रामन् संदेहे ॥ २५ ॥

25. In case of doubt, citation is made of the next.

This rule, occurring where it does, appears to have been interpolated by an afterthought, attaching itself to the word *grahanam*, 'citation,' of the preceding rule, without regard to the connection in which that word is used. The meaning is, that when the mere citation of a word from the *Sanhitā* would leave a doubt as to which occurrence of the word is intended, some part of the context, a word or part of a word, is cited along with it. But the commentator's first example and its exposition are quite peculiar. He quotes *svayamātrānām ca vikārīm co 'ttame* (v.3.7³), and remarks: "There being a doubt, owing to the occurrence of two *ca*'s in this passage, which of them is to be taken to give the *pragraha*-character [to *uttame*], the one next to the proper subject of the rule [*kāryabhāḥ*], 'the word undergoing the prescribed

23. *āgamādinām aḥkāra ākhyā bhavati: aḥkāra iti prathamā-vibhakter upalakṣaṇam. āgamasya yathā: 'dvitīyacaturthayoḥ tu vyañjanottarayoh pārvah* (xiv.5): *vikārīṇo yathā: atha nakāro nakāram* (vii.1): *lopiṇo yathā: tishṭhantyskayā sapārvah* (v.19): *ity ekavacanāni: laparāu lakāram* (v.25): *iti dvivacanam: ānupūrvyān nāsikyāḥ* (xxi.12): *iti bahuvacanam. āgamaḥ ca vikārī ca lopī ca "gama-vikārīlopiṇoh: teshām.*

(³) B. om.

24. *teshām āgamādinām kvacid grahaṇam vā bhavati: aḥkārena vinā 'pi 'ti tātpariyam. āgamasya yathā: ādirañhatir* (xvi.29) *ity ādi: vikārīṇo yathā: hanyādūpyamānam ca* (vii.3) *ity ādi: lopiṇo yathā: eśhasasya* (v.15) *ity ādi.*

¹ G. M. om. *iti*.

effect'] is to be assumed, in the rule reading *co 'ttame* [iv.11]." He seems to suppose that the "doubt" referred to in the rule concerns the point, which of the two preceding *ca*'s is joined with *uttame* in the precept that establishes the latter's character as a *pragraha* word, and that we need authority for understanding that the latter of the two is taken. This is little less than silly. His other example is taken from rule iv.15, where *ā prshati* is made *pragraha*, the *ā* being the final letter of the preceding word *yuñjā* (*yuñjā prshati*, iv.6.9⁴).

Under a later rule (iv.23) this principle is twice referred to, and very curiously and artificially applied. See the note to that rule.

अनेकस्यापि ॥ २६ ॥

26. Even of more than one.

The genitive in this rule is grammatically inconsistent with the accusative of the one preceding, which I had to translate inaccurately in order to make the connection evident. The commentator declares the "even" (*api*) here to continue in force the word *sañdehe*, 'in case of doubt,' which is hardly to be approved. He interprets: "When there is ambiguity, citation is made of more than one word or sound," and quotes *tishthanty ekayā* (v.19) and *evo 'ttare* (iv.11) as examples. But in these we have only one additional word cited, though more than one additional letter; so that both are properly examples under the preceding rule. There is no case, I believe, where more than one word requires to be cited along with that at which the rule aims; of a part of a word containing more than one letter we have instances in vi.2,5 etc. I see no good reason, however, why these should not be regarded as authorized by the preceding rule, and this one, accordingly, omitted as superfluous.

प्रथमो वर्गीत्तरो वर्गाख्या ॥ २७ ॥

27. A first mute, followed by the word "series," is the name of the series.

25. *sañdehe saty' āsannam¹ 'varṇam padam² vā gṛhṇiyāt: svay-... ity atra cakāradvayasambhavāt pragrahanimittatena katarasyo 'pādānam kartavyam iti sañdehe yad' āsannam kāryabhājas tad eva svikartavyam co 'ttame (iv.11) iti sāt্রে³. varṇasya yathā: ā prshati (iv.15) ity ādi.*

¹ W. om. ² G. M. *padam varṇam*. ³ G. M. *yadā*. ⁴ W. B. *sarvatra*.

26. *sañdeha anekasya padasya varṇasya vā grahanam bhavati: apiçabdah sañdeha ity anvādiçati¹. yathā: tishthanty ekayā sapārvaḥ (v.19): evo 'ttare (iv.11) ity ādi.*

¹ G. M. *ādiçati*. ² W. B. om.

The commentator's example is rule xiv.20, "the *t*-series, followed by the *t*-series;" that is to say, a lingual mute followed by a dental. Compare Vāj. Pr. i.64.

अं विकारस्य ॥ २८ ॥

28. *Am* makes the name of a product of alteration.

This is the correlative rule to 23, above, from which it has become strangely separated. The commentator explains, as before, that *am* stands here as representative of the accusative case in any number; but the two examples he gives (v.38 and vii.1) are both of them such as the rule might strictly apply to without any such extension of its meaning.

पूर्व इति पूर्वः ॥ २९ ॥

29. By preceding is meant preceding.

A rule expressed in the form of an identical proposition cannot be claimed to cast much light of itself, but demands a comment as its essential part. Our commentator explains: "Whatever word is pointed out by the qualification 'preceding,' that word is to be understood as designated by its own form in that situation alone; but not, on account of identity of form, another word standing in a different situation. Thus, by the rules (iv.12,13) '*dyāvāprthivī* is *pragraha*;' also the preceding word,' the word *yāvatī* is made a *pragraha* in the passage *yāvatī dyāvāprthivī mahitvā* (iii.2.6¹); but it is not therefore *pragraha* in the passage *yāvatī vāi prthivī* (v.2.3¹)."

पर इत्युत्तरः ॥ ३० ॥

30. By following is meant succeeding.

27. *vargaçabdottaraḥ prathamah svavargasyā* "khyā bhavati: *ṭavargaç ca tavargaparaḥ* (xiv.20) *iti. vargaçabda uttaro yasmād asāu varçottaraḥ.*

¹ W. om. *sva*.

28. *am iti çabdo vikārasya* "khyā bhavati: *am iti dvītyādvē bhakter upalakṣaṇam. yathā: prathamapūrvō hakāraç caturtham* (v.38): *atha nakāro nakāram* (vii.1).

29. *yah pūrvāçabdena nirdiṣṭaḥ* 'sa tatrāi 'ca svena rūpeṇo 'palakṣhito jñātavyaḥ: *na tu rūpasāmānyād anyo bhinnadeça-sthaḥ. yathā: dyāvāprthivī: pūrvāç ca* (iv.12,13) *iti* 'pragraho bhavati' 'ti vakshyati: *pūrvato'ād yāv-... iti yāvatiçabdaḥ pragrahaḥ: yāv-... iti tu* 'na syāt pragrahaḥ.

¹ G. M. *viçishyate*. ² W. om. ³ G. M. om. ⁴ G. M. *-viçhyati*. ⁵ G. M. *atra*.

This is the counterpart of the preceding rule, and is explained by the commentator in corresponding terms. His illustration is taken from rules iv.49,50, where *dve* and the word following it are declared *pragraha*. In the passage, then, *dve jāye vindate* (vi.6.4³), *jāye* is *pragraha*, but not in the passage *yonir asi jāya e 'hi* (i.7.9¹: G. M. omit *e 'hi*).

The rule is only once referred to hereafter, namely under iv.52; and there for a purpose which it was not intended to answer.

ऋकारल्कारौ ह्रस्वौ ॥ ३१ ॥

31. *R* and *l* are short.

As examples of short *r* and *l*, the commentator cites *ṛtavo vāi* (vii.2.6¹), and *aklptasya klptyāi* (v.4.8⁵).

अकारश्च ॥ ३२ ॥

32. Also *a*.

"Also" (*ca*), says the commentator, brings forward the implication of "short" from the preceding rule. His example of short *a* is *ayam purah* (iv.3.2¹ or 4.3¹).

तेन च समानकालस्वरः ॥ ३३ ॥

33. Also any vowel having the same quantity with the latter.

Here again, the "also" continues the implication of the predicate of rule 31, we are told. The only vowels contemplated by the rule, further, are *i* and *u*, since there is an absence of the attribute of like quantity with *a* in the diphthongs. As examples from the *Sanhitā* are quoted *ishe tvā* (i.1.1 et al.), *upaprayantō adhvaram* (i.5.5¹ or 7¹: W. B. omit *adhvaram*), and *atrā 'ha tad urugā-yasya* (i.3.6²: but see the various readings below). The commentator then raises the objection (without introducing it, as usual,

30. *yah para ity anena viçishyate so 'pi tatrāi 'va svena rūpeṇa pratyetavyah. yathā: dve: paraç ca* (iv.49,50) *iti' pragraho bhavati 'ti vakshyati: parateād dve jā----- ity atra jāye iti ' pragrahaḥ: 'yo----- ity atra ' na pragrahaḥ'.*

¹ G. M. om. ² G. M. ins. *çabdaḥ*. ⁽³⁾ B. om. ⁴ G. M. ins. *ta*.

31. *ṛkāraç ca lkāraç ca hrasvasamjñāu bhavataḥ. yathā: ṛt-----: ak-----.*

¹ W. B. om.

32. *ākāraç ca hrasvasamjñāo bhavati: cakāro hrasvatvam¹ anv-ādiçati. yathā: ay----- iti.*

¹ G. M. -*svam*.

with *nanu*), that the matter of the three rules should have been put into this form: "A is short: also any vowel having like quantity with it;" because, as actually stated, they are liable to the reproach of saying the same thing over twice (since *r* and *l* are of the same quantity as *a*, and are therefore included in the prescription of the present rule). But he replies that the statement is right in its present shape; for *r* and *l* inhere in *r* and *l*; and one might therefore suppose that, being letters of more than one articulating position, they suffered an extension of quantity, and were not short: hence the special rule concerning them. The treatise, as was noticed above (under i.2), nowhere describes the formation of *r* and *l*, though it excludes them from the category of simple vowels.

The rule of the Vāj. Pr. (i.55) is nearly the same with this.

अनुस्वारश्च ॥ ३३ ॥

34. Also *anuvāra*.

The implication being the same as in the preceding rules, *anuvāra* is here defined as having the quantity of a short vowel. The commentator explains the occasion for the rule as follows: rule xxi.6, which teaches that *anuvāra* and *svārabhakti* are to be attached to the preceding vowel in syllabication, implies the consonantal character of the former; whence, by rule 37, below, it would have the quantity of a half-mora, and its true quantity of a mora requires special definition.

The Vāj. Pr. (iv.147,148) allows *anuvāra* to make with a preceding vowel, either long or short, two moras, oddly enough distributing the time between the two elements, vowel and nasal, in such a way that the latter has a mora and a half after a short vowel, the vowel being itself shortened to a half-mora, while after a long vowel the nasal is itself cut down to a half-mora, and a mora and a half are assigned to the vowel—a highly artificial ar-

33. *tenā 'kāreṇa yas tulyakālaḥ svarah sa ca hrasvo bhavati: atrā' pi cakāro hrasvādeṣakah': ikāra ukāraḥ cē' ty arthaḥ: saṁdhyaksharāṇām samānakālatvābhāvāt. yathā: ish-----: up-----: atr-----: akāro hrasvas tena ca samānakālasvara ity ārabdhavyam: ṛkāraḥ kārāu hrasvāc iti tu' nā "rabdhavyam: evam ārabhyamāṇe punaruktatayā gauravam bhaved iti. ucyate: ārabdhavyam evāi' tat: kuṭaḥ: ṛkāraḥ kārāyor antara' rephalakārāu staḥ: tattatsthānatvād' anayoḥ kālavyabhicārah syāt: hrasvatvam na¹⁰ gamyeta¹¹: tan mā bhūd ity evam ārabhyate: ṛkāraḥ kārāc¹² iti.*

¹ G. M. *tatrā*. ² G. M. *hrasvatvādeṣakah samānakāla svāra ity*. ³ G. M. *om*. ⁴ G. M. *-kālāsvaratvāc*. ⁵ W. *om*. ⁶ B. *atrā' ha only*; G. M. *atra hy*; both as if the introduction to what follows. ⁷ G. M. *om*. ⁸ G. M. *anantare*. ⁹ G. M. *tateth*. ¹⁰ B. *om*. ¹¹ G. M. *avagamyate*. ¹² G. M. *ina, hrasvāc*.

rangement. The Rik Pr. gives no special statement respecting the quantity of the nasal element, but leaves it to be included among the other consonants, which have half a mora of time each.

All the "short" elements being now enumerated, the commentator quotes, as example of the employment of the term "short," rule iii.1. As example of *anuvāra*, he quotes *tāñ haste* (vi.1.37).

दिस्तावान्दीर्घः ॥ ३५ ॥

35. An element of twice that quantity is long.

The literal meaning of this rule is, says the commentator, that one of the before-mentioned short vowels, when doubled, is long; but its virtual intent is that a vowel having twice the quantity of a short is long. I have translated in accordance with the latter interpretation. As example of the use of the term "long" is quoted rule x.2, respecting the coalescence of two similar simple vowels into the corresponding long vowel.

त्रिः प्लुतः ॥ ३६ ॥

36. An element of three times that quantity is protracted.

The commentator explains the virtual meaning of this rule in the same manner as that of the preceding, and quotes in illustra-

34. *bhavaty anuvāraḥ ca¹ hrasvasamjñāḥ. yathā: tāñ..... cakāro hrasvānvākārshakah²: anuvāraḥ svarabhaktiḥ ca (xxi.6) iti svarapratyañgatvaividhānād³ anuvārasya vyañjanatvam: tathā sati hrasvārdhakālaṁ vyañjanam (i.37) ity atrā⁴ 'rdhamātratvam⁵ prāptam⁶: tan mā bhūḍ iti hrasvateam vidhīyate. hrasvasamjñāyāḥ prayojanam: vibhāge hrasvam vyañjanaparaḥ (iii.1) iti.*

¹ G. M. apl. ² G. M. hrasvāk-. ³ MSS. svaram pr.; W. -āgavidh-. ⁴ G. M. om. ⁵ G. M. -tve. ⁶ G. M. -te.

35. *tācān iti prakṛto hrasva ucyaḥ: dvir iti dvirūpaḥ¹: tācān hrasvo dīrghasamjño bhavati² 'ti sūtrayojanā: tātparyam tu hrasvadvigunakālah³ svaro dīrghasamjño bhavati⁴ 'ti. samjñāyāḥ prayojanam: dīrghaṁ samānākshare savarnapare (x.2) ity ādi.*

¹ G. M. -pam. ² W. inserts here, out of place, samjñāyāḥ prayojanam. ³ B. -la; W. om. kah. ⁴ W. om. iti.

36. *atrā 'pi¹ hrasvo 'nuvartate sāmīdhyāt: trir iti trirūpaḥ²: trirūpo hrasvaḥ plutasamjño bhavati³ 'ti: tātparyam tv atrā 'pi brāmah: hrasvatrigunakālah⁴ svaraḥ plutasamjño bhavati⁵. samjñāyāḥ prayojanam: na plutapragrahāv (x.24) iti.*

¹ G. M. ins. sa. ² G. M. om. ³ G. M. om.

tion of the term "protracted" rule x.24, which directs that a protracted and a *pragraha* vowel are not liable to combination.

All the treatises agree closely in their definitions of vowel quantity; see Ath. Pr. i.59-62, and the notes upon those rules.

ह्रस्वार्धकालं व्यञ्जनम् ॥३७॥

37. A consonant has half the quantity of a short vowel.

This, the comment reminds us, is a rule defining the length of a consonant, not one giving the meaning of the term consonant. For, if it were the latter, the word "time" in rule xvii.5, which speaks of "the time of a consonant," would be open to the charge of redundancy. We hardly need so trifling and technical a proof of a thing so obvious. As example of a consonant, the word *vāk* (e. g. i.3.9¹: but G. M. read instead *vā*) is given us.

Of the other treatises, the Ath. Pr. (i.60) alone differs from this by giving to a consonant a whole mora as its quantity.

उच्चैरुदात्तः ॥३८॥

38. A syllable uttered in a high tone is acute.

The commentator enters into no explanation of the meaning of the definition of the acute tone or accent here given, but simply refers us to a later rule (xxii.9), where the action of the organs in producing the higher tone is more particularly described. He adds as example of an acute vowel *sā idhānāḥ* (iv.4.4²: but all the MSS. save W. read *sā itī*), and quotes rule xiv.29 as exemplifying the use of the term *udātta*, 'acute' (literally 'elevated'). I have explained in the note to Ath. Pr. i.14-16 why I prefer, instead of transferring the terms *udātta*, *anudātta*, and *svarita*, to translate them by 'acute,' 'grave,' and 'circumflex,' respectively.

नीचैरनुदात्तः ॥३९॥

39. In a low tone, grave.

37. *vyañjanam hrasvārdhakālam bhavati: na tu vyañjanam iti sañjñā: anyathā vyañjanakālaḥ ca svarasyā 'trā 'dhikāḥ' (xvii.5) iti 'kālaḥ pañcāśvāsyā pānuṣṭubhāyā yathā: vāk. hrasvāsyā 'rdho' hrasvārdhakāḥ: 'hrasvārdhakālaḥ' parimānam yasya tat tathā 'ktam.*

¹ G. M. om. ² G. M. omit the last two words of the rule. ³ G. M. ins. *atra*. ⁴ G. M. -*dham*. ⁵ G. M. *hrasvārdham kālaḥ parimānakālo yasya*—a good and consistent reading; B. is corrupt. ⁶ W. -*lam*.

38. *āyāmo dāruṇyam (xxii.9) iti lakṣaṇalakṣitaḥ' svara udātta ucyate. yathā: sā..... sañjñāyāḥ prayojanam: udāt-tāt paro 'nudāttaḥ svaritam (xiv.29) iti.*⁷

⁷ G. M. -*ta*. ⁸ G. M. *ity ādi*.

We are again referred to the rule in one of the last chapters (xxii.10) which defines the action of the organs in producing the lower tone. The example for the accent is *avadātām* (i.7.2²: but G. M. read *avadātām*), of which, in *pada*-text, all the syllables are grave; that for the term *anudātta*, 'grave' (literally, 'not elevated'), is, in W. B., rule iv.43; but in G. M., rule xiv.29.

समाहारः स्वरितः ॥४०॥

40. Their combination is circumflex.

The commentator explains *samāhāra*, 'combination,' as from *samāhriyate*, 'it is taken together, collected, combined;' and adds, "the accent arising from the mixing of those two is the circumflex (*svarita*). This is a precept concerning the peculiar nature of the accent; its occurrence is taught further on, in one and another place;" and he quotes not less than three of the rules (xiv.29, x.16, and xii.9) which teach under what circumstances the circumflex arises. His example of a circumflexed syllable is *tē 'bruvan* (iii.2.2³ et al.).

This rule is so far ambiguous that it does not tell us in what order the acute and grave tones are to be combined to produce the circumflex accent—whether acute and grave, or grave and acute; but we may perhaps assume that the treatise consciously intends them to be taken in the order in which they are defined by the two preceding rules.

All the authorities practically agree in their general definition of the three kinds of accent (see note to Ath. Pr. i.14-16); and Pāṇini's rules (i.2.29-31) are precisely the same with those here given. As regards the details which form the subject of the following rules of our treatise, the accordance is not so perfect (see note to Ath. Pr. i.17).

तस्यादिरुच्चैस्तरामुदात्तादनन्तरे वावर्द्धः द्रुस्वस्य ॥४१॥

41. Of this circumflex, in case it immediately follows an

39. *anvavasargaḥ* (xxii.10) *iti' sātralakṣitaḥ² svarō 'nudātta ucyate³. yathā: av- samjñāyāḥ prayojanam: anudāttona nityam* (iv.43) *iti.⁴*

¹ W. B. om. ² G. M. -ta. ³ B. lakṣhyate. ⁴ G. M. give xiv.29, and *ity ādi*.

40. *tayor udāttān nudāttayor yaḥ samāhāraḥ sa' svarita ucyate. yathā: tē..... samāhriyata iti samāhārah: tayor melanajanyasvarah² svarita³ ity arthah. svaritasvarāpasidhir ayam: uparishitāt tu 'tatratatra svarito lakṣhyate': yathā: udāttāt paro 'nudāttah svaritam* (xiv.29): *udāttayog ca paro 'nudāttah svaritam* (x.16): *tasminn' anudātte⁴ pārva udāttah svaritam* (xii.9) *ity ādi.*

¹ M. om. ² W. -ra: B. -nyaḥ svara. ³ G. M. om. ⁴ G. M. vak-. ⁵ W. om. ⁶ W. *tannudāte*.

acute, the first part, to the extent of half a short vowel, is uttered in a yet higher tone.

That is, higher than the tone of acute, which properly forms its first element; one is tempted to give the word *udāttāt* a double construction, as belonging in idea to *uccāstarām* as well as to *anantare*.

The subject of the more particular definition of the circumflex accent occupies the six following rules, and any comments upon the doctrines laid down will be better reserved until the last rule.

As example of the circumflex, the commentator cites the words *sā idhānāḥ* (iv.4.4⁶), already once given (under rule 38); the first syllable of the second word has the enclitic circumflex, by rule xiv.29, under which the same quotation is repeated.

उदात्तसमः शेषः ॥ ४२ ॥

42. The remainder has the same tone with acute.

The plain meaning of this rule is distorted by the commentator, in an attempt to avoid a seeming inconsistency. He claims, namely, that the word "same with" here signifies "a trifle lower than," "because otherwise there would be no circumflex"—the circumflex having been defined in rule 40 as including both the higher and lower tone. But the inconsistency is not evaded by claiming for the last portion of the circumflex any thing short of the actual "grave" tone which rule 40 prescribes: if, indeed, giving to its first portion a higher tone than "acute" be not an equal offense against the same rule.

सव्यञ्जनो ऽपि ॥ ४३ ॥

43. Along with the consonant, too.

Says the commentator—"the rule as formerly given applied to a pure vowel; now the same thing is taught of the circumflexed vowel even in case of its combination with a consonant. The circumflexed vowel along with its consonant, either the one which directly follows an acute or another, is as defined. The 'too' (*api*) continues the implication of the circumflexed vowel." To this explanation of *api*, as simply equivalent with *ca*, we must demur. As any one may see by referring to the various rules in

41. *udāttād anantare yaḥ svarah svaryate tasyā 'dis tāvad uccāstarām udāttataro bhavati yāvad dhrasvayā 'rdham. ya-thā: sā.....*

42. *hrasvārdhakālāc chesha udāttasamo bhavati: 'na tū 'dattu eva: samaḥśabdaprayogāt kimcin nyūnatvam pratiyate: anyathā svaritābhāvāt. pūrvoktam eva 'dāharāṇam.*

(1) W. repeats these clauses in the comment of the preceding rule, after *bhavati*.

which it occurs, it is always best translated by 'even,' as pointing out something which is to a certain degree anomalous, or not to have been naturally expected.

As examples of circumflexed syllables containing consonants, the commentary offers *sākhā sākhībhyo vāriṇaḥ kṛnotu* (iii.3.11¹: all the MSS. except W. give only the second and third words, which are the ones to which the rule applies; the second syllable of each has the enclitic *svārīta*, and they are to be read and divided *sā-khīb-bhyo vā-ri-ṇaḥ*), and *tishyadh* (ii.2.10² et al.: but G. M. omit this example).

I have not observed that any other of the treatises deems it necessary to lay down in terms the principle that the consonant shares in the accentuation of the vowel to which it is attached. Though the rule may be regarded as in a manner superfluous, it is less to be objected to in itself than on account of the place where it is thrust in, so wholly out of connection. It ought to be somewhere where it can be made to apply to all the three accents, and not to the circumflex alone.

अनन्तरो वा नीचैस्तराम् ॥३३॥

44. Or the part following is uttered in a lower tone.

The comment explains *anantara* in this rule as equivalent to *ṣeṣha* (in rule 42), and paraphrases by saying that "the remainder of this circumflexed syllable, after the half-mora [of which the character was defined in rule 41] is in a lower tone; that is, is *anudāttatara* ('lower than grave')." Whether this is the true meaning, and not rather that the last part of the syllable, instead of being "of the same tone with acute" (rule 42), is "of lower tone (than acute)," may well be made a question. It would be, I should think, an exaggeration of the circumflex of which hardly any theorist would be guilty, to begin it higher than acute, and end it lower than grave. The latter of the two interpretations suggested is also (though not unequivocally) supported by the next rule, which may most naturally be regarded as letting down the concluding tone of the syllable one degree farther than the present rule, as this than the preceding.

43. *kevalasyā 'yam vidhiḥ purastād uktaḥ: idānīm vyañjanasahitate 'pi 'svaritasya tathātecam ucyate: 'savyañjano 'pi 'svārīta 'udāttād anantaro' nyo 'eo 'ktavidhir' bhavati: api-ṣabdaḥ 'svaritam ākarṣhati'. yathā: sakhā....: tī.*

(¹) W. om. (²) W. -tānant-. (³) W. vā mukhya vi-. (⁴) B. om. (⁵) G. M. -ākar-
shakah.

44. *tasya svaritasya hrasvārdhakālāc chesho nīcāistarām anudāttataro' bhavati: anantaraḥ ṣeṣha ity arthaḥ: tad evo 'dāharaṇam.*

¹ W. -dāttaro.

अनुदात्तसमी वा ॥३५॥

45. Or in the same tone with grave.

The commentator does not attempt this time, as under rule 42, to show that "same" means in reality "a little different," but simply paraphrases (taking no account of the *vā*, 'or'): "That same remainder of this circumflexed syllable is the same with *anudātta*."

आदिरस्योदात्तसमः शेषो ऽनुदात्तसम इत्याचार्याः ॥३६॥

46. Its beginning is the same with acute; its remainder is the same with grave: so say the teachers.

Or, it may be, 'so says the teacher,' the plural being used in token of respect: the word *ācārya* is not elsewhere found in the treatise (save at xxiv.6) except in the expression *ekeshām ācāryānām*, 'of certain teachers,' which occurs several times. The commentator does not give us his opinion upon the point, but he declares this to be the only rule that is approved or of force (*iṣṭa*, literally 'desired') in the net-work (*jāla*) of alternative views here adduced, commencing with rule 41. It may, in fact, be looked upon as identical in meaning with the fundamental rule 40, and as presenting the only reasonable and sensible view of the true character belonging to the circumflex accent. The elaboration of the theory of the circumflex, the classification of its varieties, and the determination of their relations to one another, appear to have been quite a favorite weakness with the Hindu phonetists. The subject occupies the whole of one of the later chapters of this treatise (xx.), together with sundry rules in other chapters; and a more detailed examination of it, and criticism of the views taken respecting it, will be necessary in connection with some of those rules.

While approving this rule, for the reason that it is in accordance with the last two rules of chapter xx., which define the relation of

45. *tasya' svaritasya sa eva ṣeṣa anudāttasamo bhavati.*

¹ G. M. om.

46. *tasyāi 'va svaritasyā "dihrasvārdhakāla udāttasamo bhavati: 'ṣeṣas tv anudāttasamo bhavati: ṣeṣas tv anudāttasamā ity ācāryā bruvate. yathā: sakḥ----- tasyā "dir (i.41) ity ādyabhyāhite' 'smin vikalpajāle' sūtram etad eva 'iṣṭam: prāḷishta-prātihatayor mṛdutarah (xx.11): tāiroḅyañjana-pādavṛttayor (xx.12) iti lakṣaṇānukūlyāt: na tā 'paritanam apī sūtram iṣṭam: etallakṣaṇa-prātikūlyād eva.*

⁽¹⁾ G. M. omit, which is better. ² G. M. *ārabhya' bhāhite*; B. *ābhyahita* (?—corrupt). ³ W. B. *-lpya- (lpya?)*; W. *-jāle*.

four of the kinds of circumflex to one another in respect to hardness of utterance, the commentator rejects in advance the next following rule, as being discordant with them. The ground of the asserted accordance and discordance I am not able to discover.

सर्वः प्रवण इत्येके ॥ ४७ ॥

47. It is all a slide, say some.

The commentator says: "The word 'slide' (*pravāṇa*) is a synonym of 'circumflex': the circumflexed vowel, along with its consonants, starting from its beginning, is all of it a slide: so some teachers have said." And he adds the same example already more than once given, *sākhībhyo vārieaḥ* (iii.3.11¹). We have seen that, in his exposition of the preceding precept, he has rejected this one, upon grounds of inappreciable value. The view here taken is one that might well enough be held by any one, as virtually equivalent with the one before presented: the voice somehow makes its descent from the higher to the lower pitch within the compass of the accented syllable; whether by a leap or a slide, is a proper theme for hair-splitting argumentation, but of the smallest practical consequence.

नानापद्वदिग्यमसंख्यानं ॥ ४८ ॥

48. A separable word is treated like separate words, except in an enumeration.

The meaning and application of this precept may be best exhibited by means of the examples which the commentator quotes. We have a rule (iv.40) that *te* and *the* at the end of a word of more than two syllables are *pragraha* if preceded by *ā* or *e*. In the passages *ośatāt tigmahete* (i.2.14²) and *tat pravāte* (vi.4.7²), then, the final syllables would be *pragraha*, but that the words in which they occur are separable compounds, written in the *pada*-text *tig-ma-hete* and *pra-vāte*, and so are exempted by this rule from the

47. *pravāṇaśabdah¹ svaritaparyāyah: savyāñjana eva svarita ādita ārabhya sarvaḥ pravāṇo bhavati² 'ty eka³ ācāryā ācire. yathā: sakḥ⁴-----*

¹ B. has *prajasa* for *pravāṇa* everywhere. ² G. M. om. ³ M. *sarvebhyo*.

48. *iṅgyopadaṁ nānāpadavad bhavati: asankhyānavarishaye: nānāpadavad iti kim: ośh-----: tat----- ity ādāv ākāraikā-rapūrvas tu bahusvarasya te the (iv.40) ity atra¹ pragrahatvam mā bhūd iti: asankhyāna iti kim: dve: paraḥ ca: ekavyaveto² pi (iv.49-51):³ dve sav----- ity atra pragrahatvam bhavate⁴ iti vadāmaḥ. nānāpadam iva nānāpadavat.*

¹ G. M. -ne viśh-. ² G. M. om. ³ G. M. ins. *iti*. ⁴ G. M. *prabhavati*.

operation of iv.40: the *te* is in each case the ending of a dissyllabic word. What is meant by "enumeration" is not, in itself, very clear, as the case already cited is, in a certain sense, one of enumeration—namely, of the syllables of a word. The commentator shows its intent by pointing out that, by rules iv.49–51, the word *dve*, the next word to it, and the next but one, are made *pragraha*: hence, in the passage *dve savane gukravati* (vi.1.6⁴), *gukravati* (*pada*-text *gukra-rati*) must be counted as a single word only, or the *t* of *vati* would not be *pragraha*.

In this, as in the Rik and Atharva Prâtīcākyas, the word *īngya* T. W. B. and O. more usually write *īngya*, or *īnya*) means a compound word, treated as separable into its constituents in the *pada*-text. The St. Petersburg lexicon erroneously explains it as signifying a single member of such a compound.

Compare Rik Pr. i.25, and Vāj. Pr. i.153.

तस्य पूर्वपदमवग्रहः ॥ ४९ ॥

49. Of such a word, the former member is called *avagraha*.

The example quoted is *devāyata iti deva-yate* (iii.5.5²)—an instance of *carcā*, or repetition with *iti* interposed, such as is usual in the *krama*-texts, and, to a certain extent, in the *pada*-texts also. The existing *pada*-texts of the Rik and Atharvan would write this word simply *deva-yate*, reserving the repetition with *iti* for words which are *pragraha* and separable at the same time: but that of the Tāittirīya-Saṁhitā treats all separable compounds in the latter method (see, for the varying usages of different texts, the note to Ath. Pr. iv.74). In *deva-yate*, the part *deva* is denominated *avagraha*. As instance of the use of this technical term is given the rule (iv.2) which exempts all first members of compounds from the action of the rules prescribing *pragraha*.

The commentator, finally, calls attention to the mutual relation, or apposition, of the words *pada* and *avagraha* in the rule, each in its own gender (the former being neuter, the latter masculine): compare under ii.7 and v.2.

The other Prâtīcākyas use the term *avagraha* in this sense, but without taking the trouble to define it.

पदग्रहणेषु पदं गम्येत ॥ ५० ॥

50. In citations of a word, that word is to be understood.

That is to say, the cited word itself, and not a part of a word

49. ¹tasya ²īngyapadasya ³pūrvapadam *avagraha* ity ucyate. *yathā*: *dev*----- *avagrahasamīñāyāḥ* ⁴prayojanam: *nā* ⁵avagrahaḥ (iv.2) ity ādi. *padāvagrahasabdayor nīyataliṅgatō-nyonyāncayah* ⁶sambhavati.

(1) G. M. om. (2) G. M. om. *avagraha*. (3) W. *nīyama*.

identical in form with it. Thus (to take the commentator's example), *tve* is later (iv.10) declared *pragraha* except at the end of a separable word, as in the passage *tve kratum* (iii.5.10¹); the exception specified is necessary, because the *tve* of a word like *aditīve* (p. *aditi-tve*) is also a *pada* or vocable;—but it is not therefore to be inferred that the *tve* of *kratve*, in the passage *kratve dakshāya* (iii.2.5²; 3.11³), is also *pragraha*.

As the commentator had formerly derived *grahanam* (i.22) from *grhyate*, so now he derives *grahanāni* from *grhṇanti*, 'they seize, take.'

The principle here taught is appealed to several times (under iv. 11.38; vii.2) hereafter, in order to the settlement of doubtful points.

It would seem possible to be still made a question whether the citation in any particular rule were a *pada*, 'a full word,' or a *padāikadeśa*, 'part of a word,' since citations of the latter kind are also frequently made. Perhaps the commentator would settle the difficulty by asserting that no combination of articulate sounds which actually occurs in the *Samhitā* as a *pada* is ever cited in any other character.

अपि विकृतम् ॥ ५१ ॥

51. But that word, even when phonetically altered.

The commentator gives two examples. The word *vāhana*, he says, is cited later (vii.6) as one whose *n* is liable to conversion into *ṇ*: this conversion, then, still holds good, though the final syllable of the word have become *o*: thus, *pravāhano vahnih* (i.3.3). Again, *syah*, by v.15, loses its final *visarga*; and it does so, even when its *s* is changed to *śh*, as in *ayam u śhya pra decayuh* (iii.5.11¹). As regards the former of these examples, it might seem to be provided for by rule i.22, above: but the commentator would doubtless plead that the rule would apply to *vāhanah*, but not to *vāhano*.

50. *padagrahaneshu sūtreṣhu grhītam padam eva gamyeta*:¹ *jñātavyam*: *na padāikadeśaḥ*². *yathā*: *tve ity anīngyāntaḥ*³ (iv.10) *iti vakshyati*: *tathā sati tve.... iti pragraho bhavati*: *krā.... iti padāikadeśān*⁴ *na bhavati*. *grhṇanti* 'ti *grahanāni*: *padānām grahanāni padagrahanāni*; *teshu*.

¹ M. ins. *tad*. ² G. M. *-gam*. ³ W. *anīngy-*; B. *anīngy-*. ⁴ G. M. *-catvān*.

51. *apiṣadāḥ padam anvādiṣati*: *padagrahaneshu vikṛtam api padam avagantavyam*. *yathā*: *natcāpattāu vāhana* (vii.6) *iti grahishyate*: *padam iti kṛtā visarjanīya oṣam āpanne* 'pi *ṇatvam nāi* 'ca *nicartate*: *pra....*: *eshasasyah* (v.15) *iti visarjanīyalopagrahanam pathishyate*: *ay.... ity atra sakāre shatvam āpanne* ' *visargalopo bhavaty eva*.

¹ G. M. ins. 'pi.

अग्रकारादि ॥ ५२ ॥

52. And even when preceded by *a*.

The evident occasion of this rule is the frequent occurrence of words with the negative prefix *a* attached to them. But, it being once established, its sphere is not restricted to that class of compounds, as is shown in the very example chosen by the commentator to illustrate its working. By iii.2, *çvā* is included among the words whose final *ā* is liable to be shortened; then, by this rule, *açvā* is also included: e. g. *açvāntaṇ* (p. *açvāntam*) *sa-*
hasrinam (iii.3.11¹).

Application of this principle is quite frequently made below (under iii.2,8; v.13,16; vi.5,14; viii.8,13; xi.16; xvi.6,19).

अन्कारादि च ॥ ५३ ॥

53. And when preceded by *an*.

The origin and aim of this rule are obviously the same with those of the preceding, but the instances of its application are less frequent: it is appealed to but three times in the sequel (under rules iii.7, viii.8, and xvi.29). The last case is the one selected by the commentator as his example. The word *aṇṇu*, by xvi.29, contains *anusvāra*; hence the same word preceded by *an* is to be regarded as included with it, as in the passage *anaṇṇu kuraṇṭaḥ* (iii.2.2¹).

The commentator now raises the question: how comes *kāra* to

52. *atrā 'py apicabdah padānvādeçakah: padagrahaneshv akārādy' api padam vijñeyam: 'çvartāçayunā (iii.2) iti hravādeçe vakshyati: akārāder api tasya grahaṇāsya hravateam bhavati. yathā: açv-..... akāra ādir yasya tat tathoktam.*

¹ G. M. -diç. ² G. M. ca. ³ G. M. prefixes the preceding three words of the cited rule.

53. *akārah padam iti bodhayati: padagrahaneshv ankārādy api padam vijñeyam: aṇṇu (xvi.29) ity anusvārāgame vakshyati: ankārāder api tasyā 'nusvārāgamah syāt. yathā: an-..... ankāra ādir yasya tat tathoktam.*

nam atra sūtre 'n ity asya kārottaratvam katham kriyate: varṇaḥ kārottaraḥ (i.16) iti 'sūtre varṇasya' kārottaratvavi-dhānabhaṅgaprasaṅgat. ucyate: satyam¹ etacchāstrabalān 'na kriyate: kim tu çāstrāntarabalāt kriyate: yathā: pāṇinīyā² eva-kāra apikāra³ ityādinām sādhitvam kathayanti: eram atrā 'pi evam aḥkāra āgama (i.23) ity atra⁴ codyaparihārāu vijñeyāu.

⁽¹⁾ G. M. varṇaçabdasya. ⁽²⁾ G. M. tasya. ⁽³⁾ B. om. ⁽⁴⁾ G. M. evakāre 'pi.
⁵ G. M. atrā 'pi.

be added here to the syllable *an*? since offense is thus committed against the precept in rule 16, above, that *kāra* is added to an alphabetic sound to form its name. His answer is: true enough that it is not done by authority of this text-book; but it is done by the authority of other text-books; for example, Pāṇini's followers establish the propriety of such expressions as *evakāra*, *apikāra* (for the words *eva* and *api*). So likewise in this very treatise (in rule 23, above) we have *ahkāra* for *ah*; and the same objection and answer are to be understood as applying there. See the note under rule 16.

एकवर्णः पदमपृक्तः ॥ ५३ ॥

54. A single sound composing a word is called *apṛkta*.

The commentator explains *ekavarnah* after the fashion usual with him in treating a *karmadhāraya* or determinative compound: "that is both single (*eka*) and a sound (*varna*); hence, a single sound." The term *apṛkta* means, he says, "uncombined with a consonant." As example of an *apṛkta* word, he quotes *sa uv ekaviṇṣavartaniḥ* (iv.3.3²), where *uv* is, by rule ix.16, representative of the particle *u*; and, as counter-example, to illustrate the force of the specification "composing a word," *yajñapatāze iti* (vi.6.2³), where *e*, though in a manner isolated, is not *apṛkta*, being only a fragment of a word. * Rule ix.16 exemplifies the use of the term.

आद्यन्तवच्च ॥ ५५ ॥

55. And is treated both as initial and as final.

As an instance of the treatment of an *apṛkta* word as initial, the commentary again cites the passage *sa uv ekaviṇṣavartaniḥ* (iv.3.3²), and declares that in it is to be seen the effect of rule 41, above (G. M. have here a *lacuna*, and omit the reference to the rule, along with the other instance). This is quite unintelligible to me, since

54. *ekas cā'sau varnac cāi'kavarnah: sa cet padam bhavati so 'prktaḥ' syāt. yathā: sa..... padam iti kim: yaj-..... sañjñāyāḥ prayojanam: ukāro 'prktaḥ prakṛtyā' (ix.16) iti. apṛkta iti vyanjanenā'samnyuta' ity arthah.*

* B. ins. *sa*. * G. M. *-kṛtasamjñā*. * G. M. add the remaining two words of the cited rule. * G. M. *-yukta*.

55. *cakārāncādishtam tad apṛktasamjñam padam ādyantavac' ca kāryabhāg bhavati. ādivad yathā: sa.... ity atra 'tasyā' 'dir uccāistarām (i.41) iti kāryam bhavati: antavad yathā: o te.... ity atrā'ntah (iv.3) iti pragrahakāryam' bhavati. ādic cā'ntaḥ cā'dyantāu: tāv evā'dyantavat.*

* G. M. *ādivad ant-*. (†) G. M. *om.* * G. M. *-ho.*

the rule referred to teaches nothing whatever that is characteristic of an initial sound,—indeed, teaches no *kāryam*, ‘effect,’ at all. For the treatment of such a word as a final, we have as an example the passage *o te yanti* (i.4.33), in which *o* is *pragraha*; with reference to rule iv.3, which teaches that only a final vowel is *pragraha*.

With this rule and the preceding compare Vāj. Pr. i.151-2, which are nearly identical with them in form and meaning. The Rik Pr. does not define the term *apṛkta*, but gives respecting it a rule corresponding with the present one. Both give in illustration the same passage, *indre* “*hi* (*indra*: *ā*: *ihi*), analogous with the one (*bhakshe* “*hi*, iii.2.5¹) quoted below, under v.3.

वर्णस्य विकारलोपो ॥ ५६ ॥

56. Alteration and omission are of a single sound.

That is to say, not of a whole word. Where, as by v.19, more than one letter is omitted, each is specified. The cited examples are, of alteration, *dhārshāhau* (i.2.8²: by rule v.10); of omission, *sa te jānāti* (i.2.14²⁻³: by rule v.15).

I find this rule expressly appealed to but once in the sequel (under ix.7).

विनाशो लोपः ॥ ५७ ॥

57. Omission is complete loss.

As example of *lopa*, ‘omission,’ the commentator quotes the passage *sa im’andrā suprayasah* (iv.1.8¹⁻²), where the initial *m* of *māndrā* is lost after *im* (by rule v.12: see the note there given). As example of the use of the term, he gives rule v.11, which is introductory to the subject of omissions. He then proceeds to state a very curious reason why such a precept as this should seem called for: “some have maintained the eternity of sound: in order to the confutation of that doctrine, this rule hath been uttered, in conformity with general grammar.” Pāṇini’s corresponding precept (i.1.60) is *adarganam lopah*, ‘omission is disappearance from view.’

56. *varṇamātrasya vikāralopāu syātām na tu sarvasya padasya. vikāras tāvat: dhā-iti: ‘lopas tu’: sa.....*

¹ W. om. B. omits this whole comment, along with the following rule.

57. *varṇavināṣo lopasamjño bhavati. yathā: sa..... sam-jñāyāḥ prayojanam: atha lopah (v.11) ity ādi. varṇasya nityatām kecid āhuḥ: tannirākaranāya vyākaranāmudāreṇa sūtram etad abhāni.*

² G. M. *varṇasya v.*

अन्वादेशो ज्ञेयस्य ॥ ५८ ॥

58. Continued implication is of that which was last.

The term *anvādeça*, 'after-indication,' with its corresponding verbal forms, and other equivalent expressions (especially *anvākarshaka*, *ākārshaka*, etc.), is constantly employed in the commentary to signify the continued force in a given rule of some specification made in a preceding rule. And the simple meaning of the present precept appears to be, that such a bringing forward is of the predicate last used, the word last cited, or the like. The commentator's first example is entirely accordant with this understanding: in rule vii.3, namely, to the effect that the *n* of *hanyāt* and *upyamānam* is changed to *ñ*, the implication is "after *ñiḥ*," *ñiḥ* being the last mentioned in a list of altering words given in the preceding rule. But he goes on to make another application of the precept: rule xv.8 says "*a*, however, even in *saṃhitā* [is protracted and nasalized];" and it is to be understood that only a "last" or "final" *a* is intended—as in *suçlokāñ* (i.8.16²), protracted from *suçloka*; while in *brahmāñ n teaṇ rājan* (i.8.16^{1,2}), *agnāñ ity āha* (vi.5.8⁴), *vicityaḥ somāñ na vicitryāñ iti* (vi.1.9¹), where the words protracted are *brahman*, *agne*, *somah*, and *vicitryaḥ*, and the *a* is not a final, there is no nasalization. Evidently, this is a wholly forced and false interpretation: no rule can mean two things so utterly different. Compare the notes to iv.3 and xv.8, where the principle is appealed to.

The comment seeks a kind of support for its double interpretation by calling attention to the distinction between an "affecting cause" (*nimitta*), like the *ñiḥ* brought forward from vii.3 to vii.3 in the first example, and an "affected" word or element (*nimittin*, 'having a cause'), such as is concerned in the second example. The latter (nearly synonymous with *lakshya*, used in the comment to i.22) he defines as "something original (? *pradhāna* seems to be taken here in the sense of *prakṛti*) suffering a prescribed effect."

No one of the other *Prātiçākhyas* attempts to lay down any rules as to the *anvādeça* (or *anuvṛtti*); and its usages are, in fact, wholly irreducible to rule—a circumstance which involves the condemnation of the *sūtra* style of composition, because the *sūtras* are not and cannot be self-explanatory, or intelligible without an authoritative comment.

58. *nimittasya nimittino vā 'ntyasyā 'nvādeço bhavati: nimitti 'ti pradhānam' kāryabhāg iti yāvat. nimittasya yathā: hanyād upyamānam ca (vii.3) ity asyā 'tra' niḥçabdasya. nimittino yathā: akāras tu saṃhitāyām api (xv.8) ity atra suçlokāñ² ity antyasyā 'kārasya: antyasye 'ti kim: brah-----: ag-----: vic-----.*

¹ W. -nām; G. M. -na. ² G. M. om. ³ B. om, all the signs of protraction.

उपबन्धस्तु देशाय नित्यम् ॥ ५१ ॥

59. An *upabandha*, however, is for that particular passage, and of constant effect.

The commentator etymologizes *upabandha*, 'connection, tie,' as representing the meaning *upabadhyate*, 'it is tied up, bound to;' and he farther defines it as signifying a passage pointed out by the indication "in that," and one which is designated by an enumeration—referring to rules iv.22,23,48,52 as examples. An *upabandha*, then, is a connected part of the *Sanhitā*, pointed out and defined by the rules of the *Prātiśākhya* in various ways: by citing the first words of a single verse (iv.20) or of an *anuvāka* (iv.25,48; xi.3); by the accepted title of a number of *anuvākas*, either succeeding one another or otherwise (ii.9,11; iv.52; ix.20; xi.3); by giving the first and last words of a passage (iv.22,23); or by fixing a limit within a certain number of words from a specified word (iv.52). Respecting such a passage, we are told, this rule is intended to teach two things: first, that what is prescribed for it does not hold good in other passages—this is signified by the word *tu*, 'however,' in the rule;—second, that an exception which applies in other passages does not apply in it—this is signified by the word *nityam*, 'constantly, in all cases.'

Both prescriptions, as thus stated, the commentator undertakes to illustrate by quoted cases of their application. But his first illustration is imperfectly and obscurely set forth, and is, besides, of a very questionable character. He tells us that the passage *ity āha devī hy eṣhā devaḥ somah* (vi.1.7⁷) is brought, by the principle laid down in the next rule but one (i.61), under the action of rule iv.25—and this is all that he deigns to say about it. The meaning is this: the passage quoted contains a series of four words, *ity āha devī hi*, which are also found at ii.6.7⁵ (*devī devaputre ity āha devī hy ete devaputre*); and, as the *i* of *devī* in the latter passage is *pragraha* by iv.25, so, under the operation of i.61, it should be *pragraha* also in the other. Such, however, is not the case; for *devī* in *devī hy eṣhā* is singular, while in *devī hy ete* it is dual. It would seem, then, as if we ought to understand the commenta-

59. *upabandhas tu svadeśyāyāi 'va nityam nirdeśako bhavati: upabadhyata' ity upabandhaḥ: etasmīn ity' adhikaraṇarāpaḥ saṅkhyānaviśayaḥ ca pradeśa upabandha ity ucyate. yathā: irāvati (iv.22) ity ādi sūtradvayam: somāya svai' tasmīn (iv.48): gamayato bhavataḥ (iv.52) iti ca. upabandhe yad uktam tad anyatra na bhavati 'ti tuṣadārthaḥ. yathā: ity āha: atra tripadoprabhṛtīnyāyena (i.61) pūrvajeprobhṛty a'gam (iv.25) iti prāptiḥ. anyatra yo nishedhaḥ sa upabandhe na bhavati 'ti nityaṣadārthaḥ. yathā: sādohavirdhāne (iv.11) iti pragraho grāhishyate: kevalahavirdhāna' iti sarvathā'*

tor to maintain that the present rule annuls the application of i.61, and, through it, of iv.25, to the case in question. But this is wholly inadmissible: for rule 61, below, is directly intended as a limitation to the present one, and has no force or value except as it applies to just such passages as the one here instanced; and with the latter are closely analogous a part of the examples adduced for its illustration, and leading to an opposite conclusion to the one here apparently arrived at. I cannot account for the way in which the commentator treats the matter. So far as I can see, *devī* at vi.1.7¹ is *pragraha* according to the rules of the *Prātiṣākhya*, and has only by some oversight escaped being specially excepted: and the first restriction is of a general character, meaning that directions given for an *upabandha* passage are intended for that passage alone, and have no wider bearing—except as they receive it from i.61. The same, as will be seen below, limits also the other restriction, that expressed by *nityam*.

Further, the citation in rule iv.11 of the compound *sadoha-virdhāne* as *pragraha* implies that the simple word *havirdhāne* would always be of a contrary character, as it in fact is in the passage *havirdhāne khyāyante* (vi.2.11¹); but this implication does not hold in the passage *havirdhāne prācī pravartayeyuḥ* (iii.1.3¹), because of the inclusion of the latter among the *upabandhas* of rule iv.52. Here, however, is brought up an objection: the explanation given is not satisfactory, because an exception made elsewhere is sometimes of force also in an *upabandha* passage. For instance, in the passage *atha mithunī bhavataḥ* (vi.5.8⁶), the word *mithunī*, which would else be *pragraha* by iv.52, is made otherwise by iv.53. Again, an example of a similar class is afforded by *vāyava ārohanavāhau* (v.6.21), where *vāyave* ought to be *pragraha*, because occurring in the *anuvāka* to which iv.48 refers, while it is deprived of that character by iv.54. The answer is made, that, in the case of *grāmī*, *vāyave*, *manave*, and the like, the exception must be allowed to have force because those words are excepted by specific mention; while the exception of *havirdhāne* is inferential only, and therefore does not hold good: specific mention being of more force than mere inference.

na pragraho grhyate: yathā: hav-.... ity ayam atra² nishedhah: hav-.... ity atra na prasarati: gamayato bhavataḥ (iv.52) *ity ādinā prāptiḥ. nanv etad anupapannam: anyatra nishedhasya kvacid upabandhe 'pi darśanāt: yathā: atha.... ity atra gamayato bhavataḥ* (iv.52) *ity upabandhaprāptir na grāmī* (iv.53) *ity ādinā 'nyatra² nishedhena nishidhyate: tāthā¹⁸: vāy-.... ity atra somāya¹⁹ sva* (iv.48) *iti prāptir ate samānapada* (iv.54) *ity anenā 'nyatra nishedhena nishidhyate. atro 'pyate: grāmī vāyave manava ity ādinām kanthoktate²⁰ ad esha nishedhah prasaratu²¹ kevalahavirdhāne²² pragraho²³ ne²⁴ 'ty ārthiko nishedho na prasaraty eva: ārthikakanthoktayoh kan-*

But this suggests a further objection: why then is not the specific mention of *ate* and *ave* in rule iv.54 enough, and what is the use of adding the word *nityam*, 'in all cases,' in that rule? This, replies the commentator, is for the purpose of making the exception yet more strongly binding: the specific mention merely annuls the application of the *upabandha* rule; the addition of *nityam* avoids the application of any other rule. For example, in *dve jāye vindate* (vi.8.4¹), *vindate* should be *pragraha* (by rule iv.51), because separated by only one word from *dve*; and in *vanaspate vidvāṅ-gah* (iv.6.6²), the same character would belong to *vanaspate* (by iv.38) because followed by *vid*—and we are left to infer that the *nityam* renders rule iv.54 capable of reaching these passages, and taking away the *pragraha* character of the two words in question. This, adds the commentator, may be still further pursued; it has been thus drawn out in accordance with the view of Māhisheya.

In all this exposition is to be seen something of the artificial and hair-splitting character which is apt to belong to a Hindu comment, while upon the whole it is sound and to the point. The term *upabandha* is doubtless better understood actively, as representing *teno 'pabadyate*, 'that whereby there is binding up:' the presence of *deçāya* in the rule is hardly reconcilable with the other interpretation. The intent of the specification *nityam* is to exclude general exceptions, made in view of other passages, or of the text at large, but not at all to deny the possibility of exceptions made expressly for the *upabandha* passages: and such are iv.53 and others, referred to by the objector, and refuted by an inapplicable special pleading. The force which the commentator ascribes to the *tu* of the rule belongs rather to *deçāya*, and the *tu* has the value of a general disjunctive, bringing in a precept not connected with what has gone before.

Any additional instances of the application of the principles here laid down I have not searched for or chanced upon. The rule is appealed to but once in the sequel (under iv.54).

नानापदीयं च निमित्तं प्रग्रहस्रादिषु ॥ ६० ॥

60. Also a cause belonging to another word, in the case of a *pragraha* or of a word containing *anusvāra*.

thoktasya prābalyāt. nanv ate ave (iv.54) *ity anayoḥ kaṇthok-tyāi 'vā 'lam: tatra nityagrahaṇena kim. ucyate: nitarām pari-hārah: kaṇthoktir upabandhaprāptim eva nivartayati nitya-gra-bdas tu prāptyantaram api pariharati: yathā: dve.... ity atra ekavyaveto 'pi* (iv.51) *iti prāptih: van.... iti " vid* (iv.38) *ādiprāptih: evam ādy āhanīyam¹. māhisheyamatānusāreṇai 'vam prapañcitam.*

¹ B. *upanibadhyata*. ² W. *itya*. ³ G. M. om. *tu*. ⁴ W. B. om. ⁵ G. M. *kevalam* hav-. ⁶ G. M. *sarvadhā*. ⁷ W. om. ⁸ G. M. *anyatra*. ⁹ G. M. om. ¹⁰ G. M. *ya-thā*. ¹¹ G. M. *-ratī*. ¹² B. *kevalam* h-. ¹³ W. *-he*. ¹⁴ G. M. ins. *atra*. ¹⁵ G. M. *-nīyamam*.

The intent of this rule is made sufficiently clear by the commentator, but he is unable to show satisfactorily its connection, or the implication in virtue of which it comes to mean what it does. He puts, however, a bold face upon it, and declares that the *ca*, 'also,' implies the negative (*nañ*: compare Pāṇini ii.2.6 etc.) meaning signified by *tu* (that is to say, the *tu* of the preceding rule). This is quite unintelligible. More defensible would be the continuance of *nityam*, 'constantly': this, indeed, I conceive to be the real interpretation of the *ca*; although the rule is even thus left insufficiently explained by its context. The term *srādishu* points us to the sixteenth chapter, where is to be found an enumeration of all the cases in the *Saṁhitā* exhibiting an *anusvāra* which is not a consequence of the phonetic rules of the treatise—of all the words which in their *pada* form contain an *anusvāra*—and this enumeration is led off (xvi.2) with the syllable *sra*. Many of this class of words are pointed out, as elsewhere in the *Prāṭiśākhya*, by mentioning the words which they precede or follow; which latter, then, become in the view of the treatise their *nimitta*, or 'cause' (taking the *post hoc* or *ante hoc* for a *propter hoc*). Inasmuch, now, as the *pragraha* quality and the occurrence of this *anusvāra* belong to the word itself, independently of its surroundings, it becomes necessary to teach that, when a word has been defined by means of its surroundings as thus characterized, it retains its character even when separated from them, as it is in the *pada*-text. Or, in the language of the rule, the defined occasion of a *pragraha* or of a constituent *anusvāra* is of force, even when it is, or is in, another *pada*.

The commentator, in illustration of the action of the rule, refers us first to iv.28, where *ghñi* and *cakre* are declared *pragraha* when immediately followed by *p*; these words are *pragraha* also in the *pada*-text of the same passages, when there is a pause between them and the *p*. Again, he quotes rule xvi.11, where *mā* is declared to have no *anusvāra* after it when preceded by an *avagraha*; that is, when it begins the second member of a compound, as in *ardhamāse devāḥ* (ii.5.6⁶): here, too, the precept holds when

60. *caḥāras tuṣabdanigaditam¹ nañartham anvādiṣati: pragraheshu srādishu ca nānāpadasambandhi² nimittam asaṁhitāyām api svakāryam³ upadiṣati 'ti pragrahānusvāra-kāryam⁴ na nivartate. yathā: vakshyati: ghñi cakre papare (iv.28) pragrahāu bhavata ity: atra pragrahatve papareṇa⁵ padishṭe pada-kāle⁶ tathāi⁷ 'va. srādishu ca yathā: nā 'vagrahapārvah (xvi.11) ity avagraheṇa⁸ musvārāgame nishiddhe pada-kāle⁹ pi tathāi¹⁰ 'va: yathā: ardha----- shatvanatvādāu¹¹ tu nānāpadiyam¹² nimittam saṁhitāyām eva kāryam karoti¹³ 'ty ayam ārambhah: yathā¹⁴: śuc----- prav-----*

¹ G. M. -bdena nī. ² G. M. -dha. ³ G. M. svik. ⁴ W. -sarak-. B. -hanusvak-.
⁵ G. M. pakāreṇa. ⁶ G. M. ins. 'pi. ⁷ G. M. om. ⁸ W. om. ⁹ G. M. ins. ca.
¹⁰ G. M. -ya. ¹¹ W. om.

the *anagraha* pause intervenes between the two parts of the compound: as, *ardha-māse*. On the other hand, the cause (*nimitta*) of nasalization of a sibilant or nasal, if in a different *pada* from the letter it affects, is efficient only in *saṁhitā*: for example, *gucishad iti guci-sat* (iv.2.1²), and *pravāhana iti pra-vāhanah* (i.3.3): and this is the occasion of the rule.

I see no reason why this rule does not need to apply also to the cases of an original lingual nasal (*n*) enumerated in the thirteenth chapter.

यथोक्तं पुनरुक्तं त्रिपदप्रभृति त्रिपदप्रभृति ॥ ६१ ॥

61. A repeated passage, of three or more words, is as already established.

That is to say, the reading of any connected passage is as established by the rules for the first place where it occurs: if repeated in a later part of the *Sanhitā*, where other rules, there applicable, would change its reading, it is exempted from their influence.

Several examples are given in illustration by the commentator. In the third chapter (*pragña*) of the first book (*kānda*) of the *Sanhitā* occurs the phrase *devasya tvā sarituh prasave 'grinoh* (i.3.1¹); but the same phrase is found also twice before, at i.1.4^{2, 3}, and the initial *a* of its last word is cut off by the general rule xi.1; hence, when it occurs again in a *vājapeya* passage (namely at i.7.10³), where, by xi.3, the elision of the *a* is forbidden, the effect of the latter rule is suspended, and the passage reads as before. Again, the words *supathā rāye asmān* are first found at i.1.14², where, as the *anuvāka* is a *yājyā*, the *a* of *asmān* remains unelided by xi.3; and when they occur again at i.4.43¹, that letter still maintains its place. Once more, the phrase *sa jāto garbho asi rodasyoh* is read at iv.1.4², and again at v.1.5³⁻⁴; the former time in an *ukhya* passage, where the *a* of *asi* is retained by xi.3; and it is therefore retained in the other passage also.

The commentator applies to the rule the restriction that in the repeated passage the word respecting whose form there is question must hold the third place (that is to say, doubtless, that it must have not less than two other words before it). In support of this limitation, he cites a case: at iv.ii.8³, in an *ukhya* passage, occur

61. *trayānām padānām samāhāras tripadam: kāryabhāṣaḥ padasya tṛtīyatvam vijñeyam: idṛṣam tripadam: tat' prabhṛty ādir yasya tat tripadaprabhṛti yathoktam pūrvoctam vidhim karoti svavaiśeṣhanam' yatra' tripadaprabhṛti punaruktaṁ cet. tathā: ' lupyate tv akāra ekāraukārapārvaḥ (xi.1) ity anena prathamakāṇḍatṛtīyopragne dev-... ity atrā'kāre lupte tad eva vākyaṁ vājapeye 'py alopam bādhitvā tathāi'va bhavati: tripadaprabhṛtītvāt. ubhā vām (i.1.14¹) ity atra sup-... ity etad ud u tyaṁ jātavedasam (i.4.43¹) ity atrā'pi tathāi*

the words *prthivīm anu ye antarikshe ye divi tebhyah* (W. B. omit the first two words of the citation), and the *a* of *antarikshe* is left unelided by xi.3; but at iv.5.11² (in the last *anuvāka* of the chapter called *rudra*: see rule xi.3) we read *ye prthivīyām ye ntarikshe ye divi* (W. B., again, omit the first two words quoted, and also give *ye ant*)—which, but for his restriction, would be a violation of the rule. I cannot but question, however, the right of the commentator thus to limit the rule, for I have noted at least three cases where, if it be admitted, the retention of an initial *a* in a repeated passage would be left without authority: they are *pāvako asmabhyam* (v.4.4³ and iv.6.1^{2,3}), *pradtho agne* (v.4.7² and iv.6.5⁴), and *dadhikrāvo akārisham* (vii.4.19⁴ and i.v.11⁴). Whether there are other cases like that to which the commentator appeals, I am unable to say: but I cannot help suspecting that he devised this modification of the rule to suit that particular passage, without sufficient regard to what might be required by other parts of the text.

But he is guilty of another piece of arbitrary interpretation which is still more unjustifiable, and which he makes yet lamer work of defending. The term *tripadaprabhṛti* means, according to him, a series of words beginning with three words of which the third is the one whose form is in question—that is to say, a series of at least four words, of which one follows the word of doubtful reading. The case to which he appeals to establish this is as follows: the words *divas pari prathamam jajñe agnir asmat* (W. B. omit *asmat*) occur at i.3.14⁴, in a *yājyā* passage, where *agnih* keeps its initial vowel by xi.3; again, the words *itah prathamam jajñe agnih* are found at ii.2.4²: there seems to be a repetition, and a reading of *agnih* founded upon it; but it is not proper to claim that the retention of *a* here has this ground; it is due to the inclusion (in rule xi.16) of *jajñe* among the words which do not cause the elision: for such inclusion would otherwise be to no purpose (since there is in the *Saṁhitā* no other passage to which the prescription should apply). Any other case seeming to require the interpretation here in question I have not noticed; and we have the right to presume that, if the commentator had knowledge of one which supported his view more unequivocally, he would not have failed to refer to it. So far as appears, then, the sole object of this forced

'*va*. * *saṁ te vāyur* (iv.1.4¹) *ity atra sa*.... *ity etat krāram*
iva (v.1.5¹) *ity atrā 'pi tathāi 'va*. *brāhmaṇavākyeshu tu* *tripadamatrād vā kāryam bhavati*: *brāhmaṇavākyeshu pārvastha-*
lasyāi 'vo 'kteh: *yathā*: *imām agrbhānan raçanām*
(iv.1.2¹) *ity atra mar*.... *ity etad vākyam*" *ut krāma* (v.1.3¹)
ity atrā 'pi tathāi 'va bhavati. *kāryabhājah padasya trtiyatvam*
iti kim: *prth*.... *ity "* *ukhye*: *ye*.... *iti rudrottamanuvāke*.
prabhṛti 'ti kim: *tvam agne rudrah* (i.3.14¹) *iti yājyāyām*
divas.... *iti vākyam agnaye 'nnavate* (ii.2.4¹) *ity atra*

interpretation of the word *tripadaprabhṛti* (one which the word may be said decidedly not to admit of) is to save rule xi.16 from the charge of repetition in a single point: we shall presume with much greater plausibility that, when the rule was made, the fact that this particular case was already covered by i.61 was overlooked.

But the commentator virtually admits the unsoundness of his own work by acknowledging that in the *brāhmaṇa*-passages (*brāhmaṇavākya*) of the *Sanhitā* a simple phrase of three words is enough to justify the application of the rule, "because," he says, "of the quotation in the *brāhmaṇa*-passages of a previously-occurring phrase:" that is to say, because the prose part of the *Sanhitā* is to so great an extent occupied with citing and commenting on the phrases and words of other parts—a fact which has, doubtless, been the special occasion and suggestion of the present rule. Thus, the words *māryacī sphayad varṇo agniḥ* are quoted at v.i.3² (with the customary addition, *ity āha*), from the previous passage iv.1.2⁵; and although the *nābhim* which follows *agniḥ* at its first occurrence is not also quoted, and the quotation is not therefore a *tripadaprabhṛti* according to the commentator's construction of this term, the rule holds good, and the *a* of *agniḥ* has a right to stand.

The general value of this rule is that of a limitation to the last but one; it points out a class of cases in which a rule given for a particular passage is not limited to that passage, but also acts elsewhere; in which, moreover, such a rule does not govern *niṭyam*, 'against all opposition,' the reading of the passage to which it relates.

The commentator notices the fact that the repetition of the final word of the rule indicates the conclusion of the chapter. Such repetition is made at the end of each chapter, and by all the manuscripts; and, as it is thus farther ratified by the comment, I have not hesitated to admit it as an authentic part of the text of the *Prāticākhya*. G. M. repeat the whole rule in this case.

ītaḥ.... iti punaruktam: tat¹³ tathāi¹⁴ 'vā 'bhavad¹⁵ iti cet: māi¹⁶ 'cam: tripadamātrād¹⁷ eva tathābhāva¹⁸ iti¹⁹ vaktum na yuktam: kim tu jajñe sañsphānaḥ (xi.16) iti jajñegrahaṇasāmāthyāt: ¹⁷anyathā tasya¹⁷ cāiyarthyāt¹⁷.

padavīpsā¹⁸ 'dhyāyaparisaṁāptim dyotayati.

*iti tribhāshyaratne prāticākhyavivarane
prathamō 'dhyāyāḥ.*

¹ G. M. om. ² W. -*nāya*; G. M. -*shena*. ³ G. M. *idam*. ⁴ G. M. ins. *hi*. ⁵ G. M. ins. *tathā*. ⁶ G. M. om. ⁷ G. M. *pūrvasyāi*. ⁸ G. M. *'ktaḥ*. ⁹ G. M. om. ¹⁰ G. M. om. ¹¹ G. M. ins. *cāhya*. ¹² G. M. om. ¹³ G. M. *syād*. ¹⁴ G. M. *tripadād*. ¹⁵ G. M. *tathā bhavatu*. ¹⁶ G. M. ins. *atra*. ¹⁷ W. om. ¹⁸ G. M. *tasyāi 'va*. ¹⁹ G. M. *padavītyā*.

CHAPTER II.

CONTENTS: 1-11, general mode of production of articulate sounds, distinction of surd and sonant sounds, etc.; 12-29, special rules for the production of vowels and diphthongs; 30, nasals; 31-34, difference of vowels and consonants; 35-39, mode of production of mutes; 40-43, of semivowels; 44-45, of spirants; 46-48, of *h* and *ā*; 49-52, of nasal sounds.

अथ शब्दोत्पत्तिः ॥ १ ॥

1. Now for the origin of sound.

For the word *atha* in this rule the commentator allows us our choice between two interpretations: it either indicates immediate succession—thus, the list of articulate sounds having been given, there next arises the desire to know what is the cause of these sounds, or how they become apprehensible by the sense, and then follows the explanation here to be given—or it is introductory, signifying that from this point onward the subject of the origin of sound is the one had in hand. Compare the similar and yet more lengthy discussion under rule i.1. He then goes on to draw out the significance of the rule itself. *Ābda* he explains by *dhvani*: both, when used thus distinctively, mean audible sound in general, rather than articulate sound or voice (compare xxii.1,2; xxiii.3). He paraphrases: “of the articulate sounds, *a* etc., the cause of perception, or their origin, their birth, their apprehension by the sense—just as, even before water is seen, there is moisture in the ground, and that becomes visible in consequence of digging—this is the subject of description.” We seem to catch here a glimpse of that same doctrine of the eternity of sound to which reference was made above, under i.57: our organs do not properly produce it, but their action brings it to the cognizance of the senses, as the action of digging brings water to light.

1. *ukto varṇasamāmnāyah: teshām varṇānām kīdrk' kārānam' katham vā tadupalabdhir ity ākāṅkshānantaram' nirāpyata ity ānantaryārtho 'thaābdaḥ. atha vā: ita uttarām yad vakshyate tac chabdotpattir ity etad' adhikṛtaṁ veditavyam ity adhikārārthaḥ. ābdo nāma dhvaniḥ: varṇānām akārādīnām upādānakāraṇam' tadutpattir' janma upalabdhir vā: yatho 'dakasya 'darṇanāt pūrvaṁ eva bhūmāu jalam asty eva tat khaṇanāā' dr̥ṣyate tadvaḥ: se 'yam ucyate' iti sātrārthaḥ.*

¹ G. M. *kīdr̥gam*. ² W. *karāṇam*. ³ G. M. *ins. tan*. ⁴ G. M. *om*. ⁵ B. *-karāṇam*. ⁶ G. M. *taṣya ut*. ⁽⁷⁾ W. B. *om*. ⁸ MSS. *khaṇanā*. ⁹ G. M. *ārabhyata*.

वायुशरीरसमीरणात्कण्ठोरसोः संधाने ॥ २ ॥

2. By the setting in motion of air by the body, at the junction of throat and breast.

The first part of this rule (literally, 'from air-body-impulsion') is obscurely expressed, and of ambiguous meaning. The commentator gives three explanations of it, the first of which is also itself obscure. Agni ('fire, warmth'—'heat of the body?'), he says, impels Vāyu ('air, wind'); that is what "air-body" means (but how?). From such an impulsion—that is to say, expulsion, effort at utterance—at the junction of, or between, throat and breast, comes the origination of sound. And he quotes a verse from the Çikshā (verses 8-9 of the Yajus version, verses 6-7 of the Rik version: see Weber's Ind. Stud., iv.350-1): "the mind impels the body-fire; that sets in motion air; and air, moving in the breast, generates a gentle tone." Again (or rather, apparently, as a part of the same explanation: but its inconsistency with the rest is palpable), he makes a copulative compound of *vāyu-çarira*, namely 'air-and-body': "from the impulsion of those two." Once more, he quotes as the opinion of other authorities that *vāyu-çarira* means 'the air in the body,' the compound being of such a sort that that which should be its first member is put last, after the analogy of *rājadanta*, 'upper incisor' (literally, 'king-tooth'—that is, as the Hindu etymologists explain it, 'tooth-king, chief among the teeth'), and the other words composing that *gana* (to Pān. ii.2.31). And he adds the remark that, in this interpretation, the air is understood as the cause of the impulsion, not its product.

In the translation of the rule given above, the primary division of the compound is regarded as to be made after *vāyu*; *çarira-samīraṇa* meaning an 'impulsion by the body,' and *vāyu* being prefixed in a genitive relation, 'of the air.' This is harsh, but appears to me more acceptable and less violent than the other constructions proposed. Practically, the point is of small consequence.

2. *vāyūṃ agnīḥ samīrayati* 'ti *vāyūçarīram* : *tathābhūtāt samīraṇāt* : *preraṇād abhigātāt* 'ity arthaḥ : *kanthorasoh samdhāne madhyadeçe çabdotpattir bhavati* 'ti : *çikshā cāi* 'vam asti 'ti :

manah kāyāgnim 'āhanti' sa^{*} *prerayati mārutam* :

mārutas tū 'rasi caran mandraṃ janayati 'svaram

iti . *vāyūç ca çarīram ca vāyūçarīre* : *tayoḥ samīraṇam* : *tasmāt* .
anye tv āhuḥ : *vāyoh çarīre sataḥ samīraṇam* : ¹²*tasmāç çabdo-*
tpattir iti : *tatre* ¹¹*'ttham samāsoḥ* : *rājadantādītivāc charīrasya* ¹³
paranipātaḥ : *çarīre vāyur* ¹³ *vāyūçarīram* : *tasya samīraṇam* ¹⁴ :
tasmāt . *asmin mate vāyoh samīraṇakartṛtvam eva na tu karmā-*
tvam .

¹ G. M. abhīpā-. ² G. M. om. ³ G. M. om. ⁴ G. M. -gni. ⁵ G. M. kanti.
⁶ G. M. sam. ⁷ G. M. om. ⁸ G. M. om. ⁹ G. M. ins. *vāyūçarīrasamīraṇāt*.
¹⁰ B. om. ¹¹ G. M. atre. ¹² G. M. -raçabdasya. ¹³ G. M. om.

Compare with what is taught by our treatise here and later (xxii.1,2; xxiii.1-3) Vāj. Pr. i.6-9; Rik Pr. xiii.1.

तस्य प्रातिश्रुत्कानि भवत्युरः कण्ठः शिरो मुखं
नासिके इति ॥३॥

3. The parts which give it audible quality are breast, throat, head, mouth, and nostrils.

The commentator explains *prāticrutkāni* as signifying 'the places of production' (*sthānāni*), having to do with the resonance (*prāticrut=pratidhvani*, 'resonance'), of the aforesaid sound (*śabda*).¹ He offers no remark upon the organs enumerated, but leaves their various offices to be derived from the rules which follow. But, in anticipation of the next three rules, he observes that they teach the three-fold quality of sound, as sonant, surd, and *h*-sound, rule 4 giving the definition of the first kind.

The *Çikshā* (v.13: Weber's Ind. Stud. iv.351) makes an enumeration of eight *sthānas*, or places of production of articulate sounds, dividing the "mouth" of our list into root of the tongue, teeth, lips, and palate.

संवृते कण्ठे नादः क्रियते ॥४॥

4. When the throat is closed, tone is produced.

The commentator treats this rule as a definition of the technical term *nāda*, 'tone,' and cites rule 8, below, as an example of the use of the term.

The Rik Pr. (xiii.1) gives a corresponding definition of sonant utterance, but specifies the aperture (*kha*) of the throat as the part whose contraction or closure produces the tone. Compare also Vāj. Pr. i.11. It is greatly to the credit of the ancient Hindu phonetists that they had gained by acute observation so clear an idea of the manner in which the intonation of the breath is effected in the throat; but precisely how accurate a knowledge

3. *tasya prakṛtasya¹ śabdasyo² rahprabhṛtīni sthānāni³ bhavanti: prāticrut⁴ pratidhvaniḥ: 'tatsambandhīni prāticrutkāni'. 'samvṛte kaṇṭhe nādaḥ kriyate (ii.4) etadādina sūtratrayena śabdatrāividhyam⁵ ucyaṭe: nādaḥ⁶ gōṣo hakāraḥ ce⁷ 'ti: tāvaṇ nādalakṣaṇam āha⁸ '.*

¹ G. M. *prakṛti*. ² G. M. *ina*. *prāticrutkāni*. ³ G. M. *-rutkā*. ⁴ W. *om*. ⁵ G. M. insert this (excepting the rule) at the beginning of the commentary to the next rule. ⁶ G. M. *śabdasya tr*. ⁷ MSS. *nāda*. ⁸ G. M. *ucyaṭe*.

4. *saṁvṛte kaṇṭhe yaḥ śabdaḥ kriyate sa nādasamjño bhavati, samjñāyāḥ¹ prayojanam: nādo² nupradānam (ii.8) itī³.*

¹ G. M. *nādasamjñ*. ² G. M. *ity adī*.

they had of the nature and action of the vocal chords, whose tension produces the closure, we, of course, cannot say.

विवृते श्वासः ॥ ५ ॥

5. When it is opened, breath is produced.

The explanation given of this rule corresponds with that of the preceding, and the rule cited for the use of the term *çvāsa*, 'breath,' is ii.10.

मध्ये रुकारः ॥ ६ ॥

6. When in an intermediate condition, the *h*-sound is produced.

Madhye is explained as meaning 'in a method intermediate between closed and opened:' the rest of the comment agrees with the two preceding, and the cited rule is ii.9.

Of the other *Prātiçākhyas*, only that of the *Rig-Veda* sets up a third kind of articulated material, besides tone and breath; and that (xiii.2) derives the material from a combination of the two others, rather than their mean. I have already (note to *Ath. Pr.* i.13) expressed my opinion that the attempt to establish this distinction is forced and futile, and I see at present no reason for changing it. That intonated and unintonated breath should be emitted from the same throat at once is physically impossible. In loud stridulous whispering, there is a tension of the vocal chords only short of that which gives rise to sonant vibration; and if any one chooses to claim that the aspirations used in loud speaking partake of such a character, sometimes or always, we need not be at the pains to contradict him.

ता वर्णप्रकृतयः ॥ ७ ॥

7. Those are the materials of alphabetic sounds.

That is to say, the three kinds of material just described—tone, breath, and *h*-sound, some letters having one of these as the material out of which they are made, and others another. Just so, it is added, jars and dishes have clay for their material, and thread is the material of cloth.

The commentator then goes on to raise and answer a grammatical objection to the form of the rule. Since it is the office of a

5. *vivṛte kaṇṭhe yaḥ çabdaḥ kriyate sa çvāsasaṁjño bhavati. saṁjñāyāḥ prayojanam: aghosheshu çvāsaḥ (ii.10) iti.*

6. *saṁvṛtavivṛtayor madhye madhyaprakāre yaḥ çabdaḥ kriyate sa hākārasaṁjño bhavati. saṁjñāyāḥ prayojanam: hākāro hacaturtheshv (ii.9) iti.*

pronoun to call to mind things already mentioned, and the words *nāda*, *śvāsa*, and *hakāra*, which are referred to by the pronoun in this rule, are masculine, why is the pronoun feminine (*tāh*, instead of *te*)? The reply is: "by the *dictum* of the Mahābhāṣhya, 'pronouns effecting the equivalence of the thing pointed at and of that which is pointed out respecting it assume at pleasure the gender of either of the two,' is established the propriety of the form used in the rule; therefore there takes place a mutual accordance, or apposition." The passage referred to is apparently that found, not in the Mahābhāṣhya itself, but in Kaiyyāṭa's Mahābhāṣhya-pradīpa, nearly at the beginning of the work (I owe this reference to the kindness of Prof. Goldstücker): in Ballantyne's edition (p. 7) it reads, with several variations from the text given by our commentator, *uddiçyamānapratinirdiçyamānayoṛ ekatvam āpādayanti sarvaṇāmāni paryāyena talliṅgam upādadata iti*. Reference is again made to this passage for a similar purpose under v.2.

The Rik Pr. (xiii.2) has this rule also, in nearly identical form.

नादोऽनुप्रदानः स्वरघोषवत्सु ॥८॥

8. In vowels and sonant consonants, the emission is sound.

The term *anupradāna* is etymologized as representing *anupradīyate* 'nena varṇaḥ', 'therewith is given forth an articulate sound'; and *anupradīyate* is farther explained by *upādīyate*, 'is obtained,' and *janyate*, 'is generated.' As synonym for the same term is given *mūlakāraṇa*, 'radical cause.'

I have already (note to Ath. Pr. i.13) called attention to the praiseworthy unanimity with which the Hindu phonetists define

7. *varṇānām prakṛtayo varṇaprakṛtayah: tā varṇaprakṛtayo bhavanti ye nādaśvāśahakārā uktāḥ: nāduprakṛtayah kecid varṇāḥ: śvāsuprakṛtayo 'nye: hakāraprakṛtayo 'nye: yathā mṛtprakṛtayo ghaṭaśarāvādayah: yathā vā tantuprakṛtayah patāḥ. nanu sarvaṇāmnaḥ prakṛtaparāmarçitvān¹ nādaśvāśahakāreṣhu punliṅgeṣhu² satsu tā iti striliṅgaprayogaḥ katham sādhuḥ. ucyate: nirdiçyamānapratinirdiçyamānayoṛ³ ekatām āpādayanti sarvaṇāmāni kāmācāreṇa talliṅgam⁴ upādadata iti mahābhāṣhya-vacanāt prayogasādhutvam adhyavaśīyate: tasmād anyonyānvayaḥ⁵ sambhavati⁶.*

¹ G. M. om. ² G. M. -rçakato-. ³ G. M. ins. parāmarçārheṣhu. ⁴ W. -prakṛti-nird-. ⁵ W. -āgatām; G. M. tattall-. ⁶ G. M. -yasambhavaḥ. ⁷ G. M. om.

8. *svareshu ghoshavatsv ca¹ varṇeṣhu nādo 'nupradānam bhavati: anupradīyate 'nena varṇa² ity anupradānam mūlakāraṇam: anupradīyata upādīyate janyata ity arthaḥ.*

¹ W. om. ² W. B. -ṇa.

the true ground of the distinction between surd and sonant letters. European phonetists, after long perplexing the subject with such false distinctions as are expressed by the terms "soft" and "hard," "weak" and "strong," and the like, seem now at last to be coming to a universal accordance in the correct view.

हकारो हचतुर्थेषु ॥ १ ॥

9. In *h* and in sonant aspirate mutes, it is *h*-sound.

For the quality of this *h*-sound, see rule 6, above. The Rik Pr. (xiii.2,5: rules 6,17) connects in the same manner *h* and the "fourth" mutes. Our treatise evidently regards the peculiar *h*-sound belonging to the sonant aspirates not as something that follows the breach of contact, but as inhering in the letter, in the same manner as tone in the simple sonants. Whether the Rik Pr. hints at a difference of opinion on this point may be made a matter of question. But the failure on the part of the Prâtichkhyas to recognize the essentially compound character of the aspirate mutes, the fact that these differ from the unaspirated mutes by interposing something between the mute and the following vowel, is one of their marked weaknesses.

The commentator enters into no labored exposition of the rule, but spends his strength, rather, in defending its situation. He first suggests the objection that it is not in proper place, as offending against the order observed in the definition of the three kinds of material (the *h*-sound is defined last, and we should therefore expect the letters containing it to be specified last); but claims in reply that it is, after all, in place, being intended to obviate an undue extension of the preceding rule, which would otherwise be liable to be made, since *h* and the "fourth" mutes are included (by i.13,14) among the sonant consonants, to which that rule applies.

अधोषिषु श्वासः ॥ १० ॥

10. In surd consonants, it is breath.

Which are the surd consonants, was taught us in rule i.12.

9. *hakāraḥ*¹ ca caturthāḥ ca hacaturthāḥ: teshu varṇeshu² *hakāro* nupradānam bhavati. *nanu saṃjñāvidhānakramabhaṅga-prasaṅgān*³ nā tre⁴ dān sūtram avatarati. *ghoshavatse* iti sāmānyān nādo hacaturtheshu ca⁵ *prasajyuta*⁶ ity atiprasaṅgaparihārārthatvād avataraty eve⁷ ti vadāmaḥ⁸.

¹ W. haç. ² W. om. ³ G. M. B. -baṅgān. ⁴ G. M. om. ⁵ G. M. jyeta. ⁶ G. M. vādaḥ.

10. *aghosheshu varṇeshu* śvāso nupradānam bhavati¹.

¹ B. omits rule and comment.

भूयान्प्रथमेभ्यो अन्येषु ॥ ११ ॥

11. And more of it in the other surd letters than in the simple surd mutes.

Here *çvāsa*, 'breath,' is continued by implication from the preceding rule "in virtue of vicinage" (*sāmnidhyāt*), as the commentator says (there being no *ca*, 'and,' in the rule, to indicate it directly). The other surd letters are the surd aspirate mutes and the spirants (excepting *h*). There is no separation made of these two classes upon the important ground that in the spirants the greater expenditure of breath inheres in the whole character of the sound, as being fricative, while in the aspirate mutes it consists in a brief emission between the explosion of the contact and the following vowel.

The Rik Pr. (xiii.6: rule 19) says "some regard the breath in the aspirates as quicker"—an ambiguously indefinite expression.

अवर्णे नात्युपसंस्कृतमोष्ठदन्तु नातिव्यस्तम् ॥ १२ ॥

12. In forming the *a*-vowels, the lips and jaws must not be too nearly approximated, nor too widely separated.

The plain intent of this rule appears to be to guard against an excess either of openness or of closeness in the utterance of *a* and *ā*, while at the same time these two sounds are considered as alike in quality. Such is not, however, the understanding of the commentator; he declares it impossible to follow both directions in forming one sound, and directs that a division be made: excessive approximation is to be avoided in the case of *a*, and excessive separation in those of the long *ā* and protracted *ās*. If his intention had been to recognize the same difference in quality between *a* and *ā* which is taught by the Ath. Pr. and Vāj. Pr. and by Pāṇini (see note to Ath. Pr. I.36), he would have been likely to apply the two directions of the rule in a contrary manner, warning against over-openness in *a* and over-closeness in *ā*.

11. *sāmnidhyāt çvāsa iti labhyate: prathamēbhyo 'nyeshv aghosheshu çvāso' bhūyān adhiko bhavati.*

¹ G. M. om.

12. *avarṇa uccāryamāna oṣṭhahana atyupasaṁhṛtam atisaṁ-
gṛhītām na bhavati: ativyastam ativīrtam 'ca na' bhavati.
oṣṭhāu ca hanā c' oṣṭhahanu; dvandvaç ca prānitāryasendā-
gānām (Pān. ii.4.2) ity ekavadbhāvah: tad etad² ekasminn ubha-
yathā na çakyate kartum iti yogavibhāgaḥ kāryah³: akāre nā
'tyupasaṁhṛtam ākāre ca' plute ca nā⁴ tivyastam iti.*

⁽¹⁾ W. na ca. ² W. eva tad; G. M. om. ³ G. M. B. om. ⁴ W. G. ṇd. ⁵ W. B. om.

The term *oṣṭhahanu*, though singular, is declared to signify the two lips and the two jaws, and a rule of Pāṇini (ii.4.2) is quoted in justification of such treatment of a copulative compound.

ओकारे च ॥ १३ ॥

13. Also in uttering *o*.

The "also" (*ca*) of this rule, we are told, brings forward only the action of the jaws prescribed in the preceding rule: this appears from the fact that the one following gives a special direction with regard to the action of the lips. In forming an *o*, then, the jaws are not to be too widely separated.

ओष्ठौ तूपसंस्कृतौ ॥ १४ ॥

14. But the lips are more nearly approximated.

"Vicinage" is here again made the sufficiently obvious ground of assuming that the direction applies to the utterance of *o*. The "but" (*tu*) of the rule, according to Vararuci, one of the three authorities from whom our comment is principally derived (see the introduction), annuls the direction formerly (in rule 12) given as to the position of the lips: but Māhisheya, another of the same authorities, has explained it as exempting from the widely separated condition the *o* of such words as *bandhoḥ* (ii.5.87). This latter interpretation is quite absurd, or else I am very obtuse with regard to it.

As regards the precise tone of the *o*, such directions as these can teach us nothing satisfactory. The only valuable conclusion which we derive from them is that the authors of the *Prāticākhyā* looked upon the sound as a simple homogeneous tone—not phonetically diphthongal, although in classification excluded (by rule i.2) from the category of simple vowels. The same, we shall see, is the case with *e* also.

इषत्प्रकृष्टावेकारे ॥ १५ ॥

15. In uttering *e*, they are slightly protracted.

13. *cakāro hamumātrakāryānvādeṣakah: oṣṭhakāryasya parāsātrena viśeṣavidhānāt. okāra uccāryamāṇe hanu ativyaste na bhavatah.*

14. *sāmnidhyād okāra iti labhyate: okāre kārya oṣṭhāv' upasānhṛtatarāu syātām: tuṣabda oṣṭhayoḥ pārvoktavidhīm nivārayati 'ti vararucir uvāca. māhisheyas tu babhāshe: bandhor ity ādikam okāraṁ savyañjanam' vyastato' nivārayati 'ti.*

¹ W. B. om. ² G. M. vdr. ³ G. M. vyañj. ⁴ W. vyes.

That "they" means the lips is, we are told, sufficiently indicated by the dual number of the adjective. *Prakṛṣṭa*, 'protracted,' is glossed by *saṁnikṛṣṭa*, 'drawn down together, brought near.'

उपसङ्कृतरे हनू ॥ १६ ॥

16. The jaws are more nearly approached.

The force of the comparative is explained by the usual term *atiṣayena*, 'with excess.'

In the utterance of *e*, the position of the tongue is also a matter of importance, and is explained in the next rule.

त्रिह्रामध्यान्ताभ्यां चोत्तराङ्गम्यात्स्पर्शयति ॥ १७ ॥

17. And one touches the borders of the upper back jaws with the edges of the middle of the tongue.

The "and" (*ca*) in this rule we are directed to regard as bringing forward the *ekāra* of rule 15, "on the frog-leap principle"—that is to say, by overleaping the intervening rule. The terms descriptive of the organs concerned I have translated in accordance with the directions of the commentator, although much tempted to render *jambhyan* by 'jaw-teeth, grinders.' I cannot doubt that *jambhyan* is the true reading here, although the MSS. give a curious and perplexing variety of forms to the word, and *uttarāṇ jambhyānt* is not once read: T. comes nearest to it, giving *uttarāṇ jambhyām*; W. has *uttarā jambhyānt* in the rule, and *uttarā jambhyan* and *jambhyan* in the comment; B., *uttarāṇ jambhyāt* in the rule, *uttarā jambhyan* and *jambhyan* in the comment; G. and M., *uttarāṇ jambhyām* in the rule; G., *uttarāṇ jambhyām* and *jambhyām*; and M., *uttarāṇ jambhyām* and *jambhyām*, in the comment. The verb *sparṣayati* is equivalent to *spr̥ṣet*, the causative ending *nic* being added without altering the meaning of the simple verb (compare Pāṇ. iii.1.25), as in *pālay* for *pā*, and other like cases.

15. *prakṛṣṭāv ity atra deivacanena prakṛtāv oṣṭhāu gṛhyete: ekāre kārya oṣṭhāv iṣatprakṛṣṭāu syātām. prakṛṣṭatā saṁnikṛṣṭatā.*

16. *sāmnidhyād ekāra iti labhyate: ekāre kārye hanā upasamhṛtatare bhavataḥ. atiṣayeno 'pasamhṛte upasamhṛtatare.*

17. *ekāre kārye jihvāmadhyāntābhyām uttarāṇ jambhyānt sparṣayati spr̥ṣet ity arthaḥ: pālayati 'ty ādivat svārthe nic: jambhyan iti hanūmūlaprāntadeśān' ity arthaḥ: maṇḍūkaphluti-nyāyena' cokāra ekāram ākarṣhati. jihvāyā 'madhyām jihvāmadhyam: tasyā 'ntāu': tābhyām jihvāmadhyāntābhyām.*

¹ G. M. *pālay*. ² G. M. *-ṣam*; W. *-ntaprade*. ³ G. M. *-kagatiny*. ⁽⁴⁾ W. *madhyā antāu*; B. *madhyāya antāu*.

In order to complete the definition of the mode of production of *e*, rules 20 and 23, below, have yet to be applied; but they add nothing essential to the description of the present rule, which assures to the vowel, as clearly as any such description could do, the "continental" sound of *e*, or that which it has in *they*, short in *met*. There is no hint of a composite or diphthongal utterance, any more than in the case of *o*. A diphthongal utterance, however, as *ai*, *au* (in *aisle*, *house*), we must assume them to have had originally (compare note to Ath. Pr. i.40).

उपसंस्कृतरे च त्रिद्वयमृकार्कारल्कारेषु वर्त्ते-
पूपसंस्करति ॥ १८ ॥

18. The jaws, also, are more closely approximated, and the tip of the tongue is brought into close proximity to the upper back gums, in *r*, *ṛ*, and *l*.

The construction of this rule is very harsh; the subject *hanā*, 'jaws,' comes into its first member again with a flying leap from rule 16, drawn by the *ca*, 'also;' while the second member starts off independently, "one approximates," with no connective to bind it to the other. These roughnesses are unremarked by the commentator, and I have smoothed them over in the translation. The word *upasamharati*, 'approximates,' is glossed in the comment by *nikshipet*, 'let one throw down (or apply),' and *barsvāś* is explained as 'the high places behind the row of teeth'—that is, the swelling of the inner gums.

The commentator starts a question as to the propriety of the conversion of *ṛ* and *l* in this rule into *r* and *l* after *a* (*ṛkāraṛkā-ralkāra*, from *ṛkāra-ṛkāra-lkāra*), the cases not being covered by the prescription given below (at x.8: no case of the combination of *ṛ* and *l* occurring in the *Sanhitā*, the *Prāticākhya* makes no provision for it): he is compelled to acknowledge that this treatise does not teach the conversion, but claims that it is justified by the authority of other text-books; and that the same explanation applies to an earlier case (rule i.31) of a like combination.

This wholly insufficient direction is all that our treatise gives

18. *caṣabdo hanvor¹ anvādeṣakah: ṛkāra ṛkāra lkāre ca kārye hanā² upasamhṛtatāre bhavataḥ: jihvāgrāṇi ca barsveshā³ pasamharati nikshipet: barsveshe iti dantapaṇkter upariśtād uccapradeṣeṣu ity arthah. nānā arāṇi ṛkārapare (x.8) iti lakṣaṇā-sambhavad⁴ ṛkāraṛkāralkāreṣu iti kathāṁ saṁdhiḥ sādhuḥ. satyāṁ nāi⁵ tallakṣaṇāt: kim tu cāstrāntarabalāt⁶: evaṁ ṛkāra-lkāraṇi hrāsvāv (i.31) iti vijñeyam.*

¹ W. *hanvōr*; B. *h*; G. M. *hanor*. ² W. *om*. ³ G. M. *-ṇas-*; B. *-ṇasamjñavāddā*.
⁴ G. M. *ins. sādhuḥ*. ⁵ G. M. *jñeyam*.

us for the utterance of the difficult *r* and *l* vowels. By i.2, they are excluded from the category of simple homogeneous vowels. For the teachings of the other Prāṭicākhyas respecting them, see note to Ath. Pr. i.37. However they may have been pronounced at the period of grammatical treatment of the Vedic texts, we have no good reason to doubt that, at the time when those texts were composed, they were phonetically the same with the semi-vowels *r* and *l*, differing from them only as, for example, the *l* of *able* differs from that of *ably*, the *r* of (French) *aigre* from that of *aigri*. For a theoretical discussion of this double value of the articulated sounds which lie nearly upon the boundary line between vowels and consonants, see Journ. Am. Or. Soc. viii.362 seq.

एकेषामनुस्वारस्वरभक्तयोश्च ॥ ११ ॥

19. As also, according to some, in *anusvāra* and *svara-bhakti*.

In this case, we are told, the "also" (*ca*) brings down the whole of the preceding rule, and the meaning is, that there is approximation of the jaws in uttering *anusvāra*, and approach of the tip of the tongue to the gums in uttering the *svarabhakti*, according to the opinion of some; while others hold that *anusvāra* is simply nasal, and the *svarabhakti* (see xxi.15) equivalent to *r*. This, the commentator adds, is Vararuci's explanation, and its truth is questionable. We, in our turn, may regard it as matter for question whether this attribution and expression of doubt apply to the whole interpretation of the rule, or only to its concluding part, the statement of the opinion of "others." The latter is perhaps most probable.

So far as regards *anusvāra*, we can hardly ascribe any value or propriety to this rule; the definition of *svarabhakti* in connection with that of the *r*-vowels is natural enough.

अनादिशे प्राण्यस्ता त्रिह्वा ॥ २० ॥

20. In the absence of special direction, the tongue is thrust down forward.

When no such direction as "with the point of the tongue," "with

19. *cakārah pūrvoktavidhim anvādigati: yathāsaṅkhyeṇā' nusvārasvarabhaktyoḥ pūrvoktavidhir bhavati: anusvāre hanvor upasamhārah: svarabhaktāu jihvāgrasya barsvashā' pasamhārah: etad ekesham matam. anyeshām tu matam anusvārasya' nuna-sikamātratvam: svarabhakter ṛkāratulyatvam. iti vararucimatam: tac cintyam.*

¹ G. M. -khyo. ² G. M. -ciracitam. ³ W. cintyam; B. cāntyam.

the middle of the tongue" is given, then its position is to be understood as here directed. To explain *pranyastā*, the commentator gives, besides an ordinary analysis, the expression "in a quiescent state;" as example, he cites *upa mā* (iii.2.4¹: G. and M. spoil the citation by adding the following word, *dyāvāprthivī*), in the utterance of which words the tongue is not called perceptibly into action. But this interpretation evokes a difficulty: "since the position of quiescence is assured to all the articulating organs in the absence of any direction respecting them, of what use is this precept?" The reply is: *e* (as taught by rule 17, above) is to be produced with the edges of the middle of the tongue, and the *a* contained in that letter is of the same character; hence it might be inferred, from the identity of the *a*-quality, that *a* was to be so uttered in other situations, as in words like *atha* (i.1.13¹ et al., if the word is to be regarded here as a citation)—a misapprehension which the rule removes. To this reply the objection may be raised that our treatise acknowledges the presence of no such element as *a* in *e*, and that an *a* uttered with the middle of the tongue is a phonetic impossibility. The direction respecting the tongue may well enough be regarded as a not entirely negative one; or it may have been deemed desirable to fix so very mobile and unruly a member by a special law.

अकारवदोष्ठौ ॥ २१ ॥

21. The lips are as in the utterance of *a*.

We are directed to include in this rule, by vicinage, "in the absence of special direction." The proper position of the lips for uttering *a* was given in rule 12, above. As illustration is added, quite needlessly, the word *indrah* (*passim*); the southern manuscripts read instead *indriyāvaḥ* (vi.5.8²).

20. *yatra jihvāgreṇa jihvāmādhyeṇe 'ty ādir' anādeḥas² tatra vishaye jihvā pranyastā tāshnīmabhātā³ bhavati: prakarshena nyastā pranyastā⁴. yathā: upa..... nānā anādeḥe sarvakara-nānān tāshnīmabhāvasiddheḥ kimartha⁵ 'yam ārambhah. ucyate: ekārasya jihvāmādhyāntanishpādyatvam⁶ asti⁷: tadavayavasāyā⁸ 'kārasya tathātvam asti: akāratevasāmyād anyatrā⁹ 'py athe 'ty ādāu tathātvam prasajyeta: tac cā 'nishtam: tan mā bhād iti parihārah. 'nā¹⁰ 'deḥo 'nādeḥaḥ¹¹: tasmin: upadeḥābhāva ity arthah.*

¹ G. M. *ādind*. ² G. M. *ins.* *anupadeḥaḥ*. ³ W. B. *-nibh*. ⁴ W. B. *om*. ⁵ G. M. *dyamānateam*. ⁶ G. M. *asti 'ti*. ⁷ G. M. *ins.* *'pi*. ⁸ W. *anvadeḥaḥ*; B. *anādeḥaḥ*.

21. *sāmnidhyād anādeḥa ity labhyate: oshthayor yatrā 'nādeḥas tatrā 'kāravad akāre yathā tathā¹ oshthāu bhavataḥ: nā 'tyupa-samhṛtatarāv² ity arthah. yathā: indra³ iti.*

¹ MSS. *tathā*. ² G. M. *-hṛtāv*. ³ G. M. *indriyāva*.

तालो जिह्वामध्यमिवर्णे ॥ २२ ॥

22. In the *i*-vowels, the middle of the tongue is to be approximated to the palate.

The comment supplies, without remark, the predicate "to be approximated," and gives as example *iṣhe tvā* (i.1.1 et al.).

एकारे च ॥ २३ ॥

23. Also in *e*.

Here the "also" (*ca*) brings down the whole of the preceding precept, both the specification of the active organ (*karana*) and that of the passive organ or place (*sthāna*). The exposition of the meaning of the rule is very simple and easy; but the commentator does not fail to notice that its necessity is open to objection upon two grounds, and enters into its defense at considerable length. The first objection is, why make two separate rules (22 and 23) for a single direction?—that is to say, if the *i*-vowels and *e* are all produced by the approximation of the middle of the tongue to the palate, why not include them in one rule together? The answer given is that the degree of approximation is not the same in the two cases, but is less in the *e* than in the *i*-vowels. If it be asked, why is this so? the reply is made, because the *e* is mixed with *a*, and production of this *a* with the middle of the tongue is on account of its constituting a part of *e*, and not by reason of its own natural character (compare the comment to rule 20, above)—which special qualification is sufficient ground for the less degree of approximation. The second difficulty is stated thus: both place and organ of *e* have been already defined in rules 15–17, above; but here is laid down for the same letter something different: and it is not possible that both directions should be followed

22. *ivarṇe kārye jihvāmādhyam tālāḥ upasāṁhartavyam. yathā: iṣhe..... 'jihvāyā madhyam' jihvāmādhyam.*

¹ W. om. ² B. om.

23. *cakārah pūrvavidhim anvādicati: ekāre kārye 'jihvāmādhyam tālāḥ' upasāṁhartavyam. nanu vidhau samāne prthak-sūtrārambhaḥ kimarthaḥ. ucyate: ivarṇe yathā jihvāmādhyo-pasāṁhāro na khalv evam ekāre kim tu tato nyāna ity arthaḥ: kutaḥ: akāramiṣṛitātād ekārasya: akārasya ca tadekadeṣatvāj jihvāmādhyāntanishpādyatvaṁ na tu svataḥ: ata eva sopādhi-katcān nyānatvopapattiḥ. iṣhatprakṛṣhṭāv (ii.15) ity atra sūtrātrayeṇāi 'kārasya sthānakarane nirdiṣṭe: iha tu tato 'nyat tasyāi' 'va nirdiṣyate: tad ekasminn ubhayathā kartum na śak-yate: virodhāt tasmād atra yogavibhāgaḥ kartavyaḥ: avyān-*

in the production of one sound. To get rid of this difficulty, a division must be made; the former description must be understood as applying to *e* by itself, and the present one to *e* combined with a consonant. How is this determination made? Why, when we say in a general way "the letter *e*," it lies nearest, or is most natural, to understand that letter itself, without a consonant; hence, because of its prior suggestedness, the first definition belongs to it; and the other is left, to be applied to the same sound as combined with a consonant.

The utter artificiality of the answer to the second objection is too obvious to need pointing out; and even the first evokes more difficulties than it removes. There is no inconsistency whatever between rules 17 and 23, and we have reason to be surprised only at the repetition in the latter of what is implied already in the former. Rule 23 has the air of being an afterthought, slipped in, because of the really close relationship between *e* and *i*, with disregard of what had been taught before. The alleged difference of degree of approximation exists clearly enough, but would be very insufficiently intimated by a mere separation of one rule into two.

ग्रोढीपसश्दार उवर्णे ॥ २४ ॥

24. In the *u*-vowels, there is approximation of the lips.

After his paraphrase of the rule, the commentator enters here upon an exposition, the intent of which is not altogether clear to me. "Here, he says, approximation is as formerly, and not mere drawing down together" (that is, of the same kind as was taught in rule 14, above, and not the *prakṣhātā*, 'protraction,' of rule 15, which is there glossed by *saṁnikṣhātā*?). "However, 'the lips drawn down together may be long'—this will be said hereafter" (by this phrase some direction given later in the treatise is

jane taḥ lakṣhaṇaṁ savyañjane tv etad iti. kuto 'yaṁ niyamah. ucyate: 'ekāra itī' sāmānyoktāu satyām ¹*prathamam avyañjana-syāi* ²*'va grahaṇaṁ mukhyam* ³*tathā sati prathamapratītes* ⁴*tasmin prathamam lakṣhaṇaṁ yujyate: savyañjane* ⁵*pāriṣeṣhyād etad iti vijñeyam.*

¹ W. G. M. -dhyāntāv. ² G. M. -vyān. ³ G. M. -tham. ⁴ G. M. ato. ⁵ B. -dhyāntābhyān nish-. ⁶ G. M. -dhyānish-. ⁷ G. M. om. ⁸ W. nyasyāi; B. nye t-. ⁹ G. M. om. ¹⁰ G. M. ekārasya. ¹¹ B. pratham av-. ¹² G. M. -man vy-. ¹³ W. sukaram. ¹⁴ G. M. -man pra-. ¹⁵ G. M. ins. tu.

24. *ucarne kārya oṣṭhōpasamhāro bhavati: atro 'pasamhārah pūrcavan na saṁnikṣhātāmātram: kim tu: saṁnikṣhātāv oṣṭhāu dīrghāu syātām itī vakshyate: evam oṣṭhāu tā 'pa-samhṛtatarāv* (ii.14) *ity atra 'pi vijñeyam. yathā: ut.... oṣṭhāyor upasamhāra oṣṭhōpasamhārah.*

¹ W. B. om.

wont to be cited; but there is no such direction as this, either in text or in commentary); "the same is to be understood in rule 14, above" (compare a similar reference to a preceding rule in the comment to ii.18). A phrase is then cited from the *Sanhitā*, containing *u* and *ū*, namely *ulākhalabudhno yāpah* (vii.2.1²).

एकान्तरस्तु सर्वत्र प्रकृतात् ॥२५॥

25. But, in all cases, with an interval of one from the preceding.

The commentary on this very obscure rule reads as follows:

By vicinage, "labial approximation" is here implied: everywhere, in the case of labial vowels, after the preceding labial approximation, a separate labial approximation is to be made, provided it have an interval of one: by this is understood having the quantity of a *mora* interposed: that, namely, has an interval of one whereof one *mora* is the interval or interposition. This is the distinctive condition of the separate labial approximation. The word "but" (*tu*) denies the necessity of the interval of one in a case where *o* [W. says, where *au* or *u*] follows. Examples are: *utpātacushmam* (i.6.1¹); *sānnīyam iti su-unīyam* (vi.2.4¹); *atho oshadhīshu* (iii.5.5² and vi.3.9²); *bāhuvor balam* (v.5.9²); *tanuvāu ghorā nyā* (v.7.3³; G. M. omit the last word); *caturhotā* (not found in the *Sanhitā*: occurs *Tāitt. Brāh.* ii.2.3²).

Objection: in *yo 'ñgum* (iii.3.4²), the *anuvāra* has a *mora* [by i.34] and the *ç* a half-*mora* [by i.37]; since, then, the quantity being a *mora* and a half, there is not an interval of one, how is the separate labial approximation assured?

Answer: it is assured by the principle "a hundred includes fifty." Where there is a *mora* and a half, there is *à fortiori* a *mora*; in virtue of this the prescribed effect is produced, but its excess does not vitiate the rule, because the word "one" excludes what does not belong to itself (?). For the same reason, the occurrence

25. *sānnidhyād oshthopasamhāra iti labhyate: sarvatr' oshthya-svareshu prakṛtād oshthopasamhārāt prthagoshthopasamhārah 'kartavyah: sa ced ekāntarah': ekāntara iti mātrākālavaryavāya' iti labhyate: ekamātrā 'ntaram vyavadhānam yasyā 'sāv ekāntarah: iti prthagoshthopasamhārasya viçeshanam, tuçabda okāraparava' ekāntaratvaniyaman' nivartayati. udāharanāni: ut: sūn-----: atho-----: bāh-----: tan-----: cat-----: nanu yo----- ity atrā 'nusevārasya mātrākālāḥ 'çakārasyā 'rdhamātrākālāḥ: evam adhyardhamātratve saty ekāntaratvābhāvāt ka-tham prthagoshthopasamhārasiddhiḥ. ucyate: çatepañcāçanniyā-yena sidhyati: adhyardhamātratve 'py' ekamātratvam sūtarām' asti: tena kāryam bhavaty adhikam tu na nishidhyate: svāyoga-vyavachedakatvād ekaçabdasya: ata eva bāh----- ity āder' na*

of the double labial in such passages as *bāhuvoḥ bālam āruvoḥ ojah* (v.5.9²: G. M. omit the last word) is not primary (or original), but its quality as *sphurita*, 'quavered,' is shown by the likeness of the example (?).

Second objection: then why is there not a separate labial approximation in the two *u*'s following the *k* and *r* of *kusurubindoh* (vii. 2.2¹), since there occurs more than a *mora* and a half of interval between them?

Answer: not so; here there is denial of separate labiality only for the two *u*'s that follow *k* and *s*, because of the absence of its necessary condition; but to that following the *r* this rule does not apply, because it is not a case of separateness from the preceding, but of separateness from the *u* that follows the intermediate *s*; this being so, there is no occurrence of the interval of one for a letter in this situation: thus there is no offense against the rule.

So far the comment; but either I have failed to apprehend its true meaning, or it has given a false interpretation to the rule, or the rule itself is destitute of intelligible significance. I must confess myself unable to see what peculiarity there should be in the utterance of two labial vowels following one another in two successive syllables with not less than a *mora*'s interval between them. No precept, so far as I know, in any of the other *Prāticākhya*s, is analogous with this, or casts light upon it.

It appears to be intimated, in the course of the answer to the first objection, that the peculiar utterance of the *u* in such words as *bāhuvoḥ* for the usual *bāhuoḥ* and *āruvoḥ* for *āruoḥ* is denominated *sphurita*. The term does not occur elsewhere; nor is any notice taken of the phenomenon, if not here. It is a well-known characteristic of *Tāittiriya* texts, but is found in fewer words than one would be apt to imagine. Besides the two just given, I have noted in the *Sanhitā* only the cases of *tanū* (*tanuvam*, e.g. i.1.8; *tanuvā*, e.g. i.1.10²) and the word *suvar*, which are often met with. Of similar resolutions of an *i*-vowel into *iy*, the cases are more nu-

*dviroshṭhyam*¹² *mukhyam*: *kiṁ tu sphuritavam*¹³ *udāharanāt vā bhāsatayā*¹⁴ *darṣitam. tarhi kus- ity atra kakārarephābhyām uttarayor ukārayoḥ katham prthagoshthopasamhāro na bhavati: adhyardhamātravyavāyasambhavāt*¹⁵. *māi 'vam: atra*¹⁶ *kakāra-sakārottarayor*¹⁷ *ukārayoḥ tādā*¹⁸ *apṛthagoshṭhatā*¹⁹: *etallakṣha- nāsambhavāt: rephād uttarasya tu*²⁰ *prakṛtāt prthaktvābhhāvān nā 'yam vidhiḥ*: *kiṁ tu*²¹ *madhyasthasakārottārād ukārāt prthaktvam: tathā saty ekāntarābhāvāḥ*²²: *tadavastha*²³ *eva 'ti lakṣaṇam idam avyabhicaritam*²⁴.

(¹) W. om. (²) G. M. -labhedavy-. (³) G. M. *arthaḥ*. (⁴) W. *śukāravakārap-*. (⁵) G. M. *ekamātrānantaratva-*. (⁶) G. M. om. (⁷) B. om. (⁸) G. M. *ekārato-*. (⁹) G. M. om. (¹⁰) W. *muttarām*. (¹¹) G. M. *ddāu*. (¹²) G. M. -*ṭhyateam*. (¹³) G. M. *sva-*. (¹⁴) W. -*haratva-*; B. -*teabh-*; G. M. -*nan tu ābh-*. (¹⁵) G. M. -*vyavādhanas-*. (¹⁶) G. M. om. (¹⁷) G. M. -*rābhyām utt-*. (¹⁸) G. M. -*van*. (¹⁹) G. M. *na prthagoshtho-*. (²⁰) *samhāratā*. (²¹) W. *u*; B. om. (²²) W. B. om. (²³) G. M. -*vāt*. (²⁴) W. -*stha*; B. -*sthā*. (²⁵) G. M. *vyabh-*.

merous, but less frequent. I have collected the following (without exhausting the Sanhitā, especially of themes in *iya*): *āgriya* (iv.5.5²), *aghniya* (i.1.1), *ācviya* (ii.2.12²), *asmadrīyaṇe* (i.4.21), *idhriya* (iv.5.7²), *dhūshniya* (iii.1.3¹), *pātriya* (iii.2.3²), *budhniya* (i.3.3), *rēshmiya* (iv.5.7²), *viçvāpsniyā* (i.5.3³), *viçvadriyaṇe* (i.7.13²), *vṛshniya* (iii.2.5²), *gṛghriya* (iv.5.5²), *sadhriyaṇe* (i.2.14²); and, of oblique cases from themes in *i* or *ī*, *indrāgniyoḥ* (i.3.12), *gāyatriyā* (iii.2.9¹), *pārshniyā* (iv.6.9²), *pr̥cniyāi* (ii.2.11⁴), *rātriyāi* (iv.4.1¹), *lakshmiyā* (ii.1.5²), *viçvāpniyāi* (iii.1.11⁴), *svādhiyam* (i.3.14⁶). None of the consonantal combinations which are thus avoided by the resolution of the *u* are such as the euphony of the Tāittiriyaśas does not tolerate: but of those which are avoided by the resolution of the *i*, only three are met with in the text—namely, *try* (e.g. i.8.22¹: ii.4.3¹), *tny* (iv.4.2²), and *çny* (v.5.6²). I have not entered deeply enough into the investigation to deduce the law, if law there be, by which the resolution is made.

अकारार्धमैकारिकारयोरादिः ॥ २६ ॥

26. The beginning of *āi* and *āu* is half an *a*.

Rules 28 and 29, below, tell of what constitutes the remainder of these diphthongs.

संवृतकरणतरमेकेषाम् ॥ २७ ॥

27. Which, in the opinion of some, is uttered with the organs more closed.

We have here another indication that, as intimated above (under ii.12), our Prāṭiśākhya does not recognize the close or neutral pronunciation of the short *a*; for, if it did so, there would obviously be no reason for referring to the opinion held by certain authorities respecting its assumption of that utterance in diphthongal combination. Some phonetists (without sufficient reason, as it appears to me) have in like manner defined the first element in our English diphthongs ("long *i*" in *aisle*, *isle*, and *ou* or *ow* in *house*, *down*) to be the neutral vowel (*u* in *but*), rather than the open *a* (of *far*). But, whatever may have been the case with the Sanskrit diphthongs, our own cannot be truly described as composed of two elements each: they are slides; and to allow the organs to remain in

26. *āikārasyaū "kārasya cā "dir akārārdham bhavati. akārasyā 'rdham akārārdham.*

27. *sāmnidhyād akārārdham iti labhyate: ekeshām mate tad akārārdham saṁvṛtakaraṇataram bhavati. saṁvṛtāni saṁnikṛtāni karaṇāni yasya tat saṁvṛtakaraṇam: atīṣayena saṁvṛtakaraṇam saṁvṛtakaraṇataram.*

B. reads *saṁvṛta* throughout.

either their first or last position long enough to make the initial or final element distinctly audible, would be an error of pronunciation. The commentator glosses *saṁvṛta*, 'enveloped, shut up, closed,' with *saṁnikṛṣṭa*, 'drawn down together, approximated.'

इकारो ज्यर्धः पूर्वस्य शेषः ॥ २८ ॥

28. Of the former, the rest is one and a half times *i*.

Of the former—that is, of *āi*; *āi* and *āu* having been mentioned together in a preceding rule (ii.26), says the commentator.

उकारस्तूत्तरस्य ॥ २९ ॥

29. But, of the latter, *u*.

That is to say, the remainder of *āu* is one and a half times *u*. To account for the word "but" (*tu*) in the rule, the commentator notes that, as the beginning of both diphthongs is the same sound, *a*, it might seem to follow that their end would be the same sound, *i*: this the "but" denies. This explanation merely intensifies and makes too precise the actual meaning of the word.

For the teachings of the other Prātiśākhya as to the pronunciation of *āi* and *āu*, see the note to Ath. Pr. i.40. As there remarked, the euphonic treatment which they receive proves their first element to have had originally more than a half-mora of quantity. If they must be limited to two moras, a better description of them would have been $1\frac{1}{2}a + \frac{1}{2}i$, and $1\frac{1}{2}a + \frac{1}{2}u$. If, as we may presume to be the case, the authors of these treatises defined their own pronunciation pretty accurately, then the *āi* and *āu*, not less than the *e* and *o*, had by their time taken on a value notably different from that which belonged to them when the euphonic rules of the language were the faithful representation of living processes.

अनुस्वारोत्तमा अनुनासिकाः ॥ ३० ॥

30. *Anusvāra* and the last mutes are nasal.

As example of *anusvāra*, the comment cites *yo 'ñcum* (iii.3.4²);

28. *pārcasyāi 'kārasye 'ty arthaḥ: adhastād' āikārāukārayoḥ saḥocaritatvāt: adhyardha ikāra āikārasya ṣesho bhavati. adhikam ardham yasyā' sāv adhyardhaḥ.*

¹ W. *adhyardhas tīvad.* ² G. M. *uccar-*.

29. *uttarasyāu 'kārasye 'ty arthaḥ: adhyardha ukāra āukāraṣesho' bhavati: yathā 'nayor ubhayor apy ādir akāra eva tad-vad ikāra eva ṣeshaḥ' prasaktaḥ: tan' nishedhati tuṣabdaḥ.*

¹ G. M. *-rasya ṣe.* ² W. B. *om.* ³ W. B. *tan.*

of the "last" or nasal mutes, *pratyāñ hotāram* (vi.3.1⁵)—to which G. M. add *prāñcam upa* (v.2.7³), and *manind* (vii.3.14).

The term *anunāsika* is interpreted by the commentator as signifying *nāsikām anuvartate*, 'it goes after the nostril'—that is to say, doubtless, 'it finds exit by the nasal passages:' an accurate definition of this class of sounds. As employed in this *Prāṭiśākhya*, *anunāsika* means simply, as adjective, 'nasal,' and its derivative noun, *anunāsikya*, signifies 'nasality, nasal utterance.' Rule 52, below, describes how such mode of utterance is produced, and in chapter xvii. (rules 1-4) is made an attempt to define the degree of nasality in the various sounds of the class. "Nasal," or *anunāsika*, by the present rule, are the *anusvāra* and the five nasal mutes, *ā, ñ, ṇ, n, m*; the same term is applied later to the nasal semivowels into which *ṇ* and *m* (v.26-28) are under certain circumstances convertible; and at v.31, x.11, xv.1,6, xxii.14, we also hear of nasal (*anunāsika*) vowels. The other nose-sounds, the *yamas* and *nāsikya* (ii.49,50, xxi.8,12-14), do not anywhere receive this title.

It is desirable to put together somewhere a comprehensive statement of the doctrines held by the *Tāittiriya-Prāṭiśākhya* respecting the nasal constituents of the alphabet it recognizes, and no more suitable place is likely to present itself than is offered here.

All nasal (*anunāsika*) sounds are uttered (ii.52) by the mouth and nose together. An *uttama*, a "last" or nasal mute, is a sound in the production of which the intonated breath escapes through the nose, while the organs of the mouth form one of those same contacts which give rise to the corresponding non-nasal mutes of the series. In *anusvāra*, on the other hand (including under that designation the nasal semivowels, of which more further on), the mouth-organs are not wholly closed, but the intonated breath finds exit through them at the same time that it passes through the nasal cavities. In all cases, then, in which the character of the nasal of a syllable is determined by that of the following consonant, the nasal will be a mute if the latter is a mute, but an *anusvāra* if succeeded by a letter not forming a contact—by a semivowel or a spirant. Respecting the phonetic character and occurrence of the nasal mutes, there has been no difference of opinion, so far as we have any information, among the Hindu phonetists of the period represented by the *Prāṭiśākhyas*; none of them has allowed a final *anusvāra* before a pause, or an *anusvāra* before a mute, either in the same or a following word. As to the phonetic value, however, of the real *anusvāra*, the nasal uttered with open mouth-organs, there was by no means the same accordance among those ancient grammarians. Some held it to be a pervading nasalization of the preceding vowel; others, a nasal addition to

30. *anusvāraḥ co 'ttamāḥ cā 'munāsikā bhavanti: nāsikām anuvartanta ity anunāsikāḥ. yathā: anusvāraḥ: yo-----: uttamāḥ ca ' : pra-----: 'prā-----: maṇ-².*

¹ G. M. ins. *yathā*. ² W. B. om.

that vowel. The former view is adopted and consistently maintained by the Atharva-Prātiçākhyā, which acknowledges nasal consonants and nasalized vowels, but no *tertium quid*. The Prātiçākhyās of the Rik and White Yajus are equally consistent in their recognition of an *anusvāra* as nasal appendage to the vowel, and the latter of them gives (Vāj. Pr. iv.147-8) detailed directions as to the quantity belonging to each element. The Tāittiriya-Prātiçākhyā adopts prevailingly the same view, but lets the other appear distinctly in some of its rules. Thus, at v.31, it is stated to be Ātreya's opinion that, when a nasal mute becomes *l*, the preceding vowel is nasalized; and, in conformity with this, xv.1 directly teaches that, after the various conversion of *m* and *n*, the vowel before them becomes nasal, the following rules adding (xv.2,3) that some authorities deny this, and direct *anusvāra* to be inserted instead: here the commentary has to reverse the obvious intent of the text, and declare the latter rules approved, and the first disapproved. Further, x.11 directs that when a vowel is combined with a nasalized vowel the result is nasal (the commentary, however, gives a different interpretation: see the rule). Once more, in xxii.14, among "heavy" syllables is reckoned one that is *anunāsika*, 'nasal.'

I very much doubt whether this difference of views is founded upon an actual difference of pronunciation; it is probably due rather to a discordant apprehension and analysis of a single mode of utterance. The same point might divide into two parties our phonetists at the present day—just as they have long been divided upon the question whether a *b* differs from a *p* in being sonant, or in being soft, or weak, or of inferior aspiration, or something of that kind. Without entering into any detailed discussion of the subject, I will simply say that I incline to side with the Atharvan school, and to believe in nasal vowels rather than in *anusvāra*. No one of the Prātiçākhyās gives an intelligible definition of the phonetic character of *anusvāra*, considered as an independent alphabetic element; if it is to be so considered, we shall hardly be able to make of it anything but a bit of the neutral vowel (*u* of *but*) nasalized, or the sound of the French *un*, and shall have to regard it as attached to the vowel much in the same way as, by us who speak English, the same sound, not nasalized is attached to most of our long vowels before an *r*—for example, in *there*, *here*, *oar*, *cure*, *fire*, *sour* (see Journ. Am. Or. Soc'y, viii.353).

Which of the two views is originally favored by the Devanāgarī alphabet does not admit of much question; the writing of *am̐ca*, for example,* with a nasal sign over the vowel of the first syllable, is an unequivocal recognition of the nasality as something affecting the vowel itself. If it had seemed to the framers of this alphabet to be a something interposed between the vowel and the following consonant, they would doubtless have

* Namely, अंश, or अंश.

found for it a sign to stand between those of the other elements. This has actually been done, out of a true regard for consistency, by the writers of the Vājasaneyi and Tāittiriya texts: for lack of a better device, they have brought down one of the usual signs of nasality from above the syllable to a position between the syllables, giving it an addition which enables it to maintain its place there *—in the Tāittiriya texts, we have the dotted crescent, with the *vi-rāma*, the usual mark for a consonant not graphically combined with a following consonant, beneath it. The scribes of the Rig-Veda seem to have been less solicitous to make their practice square with their theory. It may well be made a question, however, whether the habit, now so common, of writing *amka*, *amta*, *ambā*, for *aika*, *anta*, *ambā*, etc.,† could have grown up until the opinion had become prevalent that the nasal sign in *am̐* also represented a nasal sound which followed the vowel, and was accommodated in its special mode of utterance to its successor.‡

One more point in the theory of the nasal sounds calls for notice. The assimilation of *n* to a following *l*, and of *m* to a following *l*, *y*, or *v* (v. 26-8), is treated by the Tāittiriya, the Vājasaneyi, and the Rik Prāṭiśākhya as resulting in the production, not of *anusvāra*, but of a nasal counterpart to the semivowel—that is, the case is made analogous with that of a nasal before a mute, instead of before a spirant. Here, also, the Atharva-Prāṭiśākhya pursues an independent course, and accepts no nasal *y* or *v*, but only a nasal *l*, as product of both *m* and *n* (see Ath. Pr. ii.35). In this case, as well as in the other, we have to assume merely a difference in the theoretical explanation of an identical mode of pronunciation; and I should not only favor the Atharvan view, but should be willing to give up the nasal *l* itself, as not worth distinguishing from an ordinary case of *anusvāra*—or of nasalized vowel, if we accept this understanding of the matter. Thus much, indeed, may be allowed—that, while the absence of sonant utterance in the spirants cuts them off from sharing in a nasal quality, it might be difficult to prevent the nasality of the preceding vowel from infecting at least

* Thus, for अंश or अंश, the Vāj. S. writes अंश, the Tāitt. S. अंश.

† That is, अंक, अंत, अंबा, for अङ्क, अन्त, अम्बा.

‡ No valid objection can be raised against the, practically so convenient, imitation of this habit on the part of modern European scholars, so far as concerns the representation of an original *m* assimilated to a following consonant. To go farther than this, however, and write the *anusvāra* sign in the interior of a word for a nasal mute which is equally radical or thematic with the succeeding non nasal, and, yet more, to write it for a final *m*, which no Prāṭiśākhya allows to be pronounced otherwise than *m*, seems an indefensible practice, and one wholly to be disapproved and rejected. Of Müller's seemingly elaborate defense of his adherence to it, given in the Preface to his *Hitopadeśa*, absolutely the whole point lies in the phrases (p. xi.): "it is easier to write *amkita* than *am̐*. What applies to writing applies with still greater force to printing"—which latter consideration must be pronounced destitute of weight; since, on the contrary, we do expect our printing to be superior in accuracy to ordinary writing.

the beginning of the sonant semivowels. For the exclusion of *r* from the same treatment with the other semivowels I can discover no good reason.

The usage of the manuscripts is pretty nearly in accordance with the theories of the *Prāṭiśākhya*. For an assimilated *m*, the distinctive *anusvāra* sign is always written before *r*, as before the spirants; but before *l*, *y*, and *v* is written the sign of nasality above the preceding syllable, as before a mute. But as regards *n* before *l*, my manuscript varies with complete irregularity between treating it like *m*, as required by the *Prāṭiśākhya*, and writing the *n* unchanged, either with *virāma* or conjoined with the *l* (instances of the latter mode of treatment are about twice as frequent as of the former). The edited text more usually follows a third method, supported neither by my manuscript nor by the *Prāṭiśākhya*: it writes the *l* double, and puts a sign of nasality over the preceding syllable. This is nonsense: if two *l*'s are written, the first should be separated from the other, and should have the sign of nasality written above it. But there is no reason why this should be done in the case of a combination of *l* with *n* any more than with *m*, or than in the combination of *m* with *y* and *v*.

It only remains to add that, in my manuscripts (T. and W.) and those at Berlin and Oxford (B. and O.), the text of the *Prāṭiśākhya* follows, in regard to the treatment of the nasals as to other points of euphony, the usages of the *Tāittirīya* text, and that the citations from the latter in the commentary are also written accordingly; while the body of the commentary itself follows the methods of ordinary Sanskrit texts. In this edition, therefore, their example is followed as closely as possible: the proper *anusvāra* being represented by *ñ*, and the *m* assimilated to a mute or semivowel, by *m̐*. The two South-Indian manuscripts (G. and M.) do not distinguish these two from one another.

स्वराणां यत्रोपसंस्कारस्तत्स्थानम् ॥ ३१ ॥

31. In the case of the vowels, that is their place of production, to which approximation is made.

The term *upasaṁhāra*, 'approximation,' is glossed by *upaśleṣa-ṣaṁśah*, 'a sort of embrace'—unless, indeed, we are to read, with G. and M., *saṁśleṣaṣaṁśah*, 'disunion of embrace,' i. e., 'embrace which does not come to actual contact.'

The terms *sthāna*, 'place,' and *kāraṇa*, 'organ,' denote, as in the other *Prāṭiśākhya*s (see note to Ath. Pr. i.18), the more passive and the more active of the two parts of the mouth whose concurrence gives birth to a sound.

31. *svarāṇāṁ tat sthānam bhavati yatro 'pasamhārah syāt: upasamhāro nāmo 'paśleṣaṣaṁśah*."

¹ B. om. ² W. 'paśleṣa-; G. M. saṁśleṣaṣaṁśah.

वदुपसंहरति तत्करणम् ॥ ३२ ॥

32. That is producing organ, which makes the approximation.

Here, "in the case of the vowels" is declared to be implied from the preceding rule; *upasaṁharati*, 'approaches,' is explained by *prāpayati*, 'attains;' and, as example of a *karana*, or producing organ, reference is made to the "tip of the tongue," spoken of in rule 18 of this chapter.

अन्येषां तु यत्र स्पर्शनिं तत्स्थानम् ॥ ३३ ॥

33. But in the case of the other letters, that is place of production, where contact is made.

By this expression, the commentator says, simple embrace or union is predicated of the consonants, while above a sort of embrace (or disunion of embrace) was predicated of the vowels. The difference, he adds, between approximation and contact will be inferred by any knowing person from the force of the terms themselves. The word "but" (*tu*) is meant to exclude the vowels; or, as Māhisheya explains it, annuls for *anuvādra* and *svarabhakti* the quality of being produced by contact merely, like the other consonants. This last is a precious bit of pregnant construction; and the whole comment is more obscure than the rule itself, whose meaning and implication are sufficiently obvious.

येन स्पर्शयति तत्करणम् ॥ ३४ ॥

34. That is producing organ, whereby one makes the contact.

The commentator supplies, as subject of the verb, the noun *adhyatā*, 'reader'—or, rather, 'repeater.'

32. *svārānām iti sāmīdhyāt labhyate: svārānām tat karanam bhavati: yat svārān upasaṁharati prāpayati: 'tat karanam'. yathā: jīhvāgram ṛkāra (ii.18) ity ādi.*

¹ B. *tat sthānam*; G. M. om.

33. *svarebhyo 'nyeshām varṇānām tat sthānam yatra sparṣanam bhavet: atra vyañjanānām saṁśleshamātrām¹ kathiyate: svārānām tu² purastāt saṁśleshah³ kathitah: upasaṁhārasparṣanayoh⁴ gābdaçaktyā viçesho⁵ viduṣhā vijñeyah⁶: tuçabdo⁷ svara-nivṛttyarthah⁸: athavā⁹: anuvādrasvarabhaktyor vyañjanavat¹⁰ sparṣanamātrakatvanivartaka¹¹ iti māhisheyabhāṣhitam.*

¹ W. -çlesh-; G. M. -mātrātram. ² W. om. ³ G. -shaviçeshah; M. -shaviçeshah.

⁴ G. M. -hāra iti sparṣana. ⁵ G. M. ins. eva. ⁶ G. M. jñātavyah. ⁷ G. M. çabda.

⁸ G. M. om. ⁹ W. -nave; B. -na. ¹⁰ B. sparṣakaninamā; G. M. sparṣamātrakalan-
nīc; M. -vartata.

In these four rules is implied that distinction of opener and closer position between vowel and consonant which constitutes their essential difference (see Journ. Am. Or. Soc'y, viii.367 seq.), and which the Ath. Pr. states more fully (i.29-35:—where, in rule 33, we should read *eke sprshtam*), with specifications of degree of openness and closure which are here omitted (save so far as represented by rule 45, below).

ह्रन्मूले जिह्वामूलेन कवर्गे स्पर्शयति ॥३५॥

35. In the *k*-series, one makes contact with the root of the tongue at the root of the jaws.

Compare Ath. Pr. i.20, and the references to the other Prātiçā-khyas there given.

The locative and instrumental cases, in this and the following rules, correspond with the *yatra*, 'where,' and *yena*, 'whereby,' of rules 33 and 34, above, and point out respectively the place and organ of production of the different classes of sounds.

The singular number of *hanūmāla*, 'root of the jaws,' the commentator accounts for as used generically (*jātyapekshdyām*, 'with reference to the whole kind or class').

तालौ जिह्वामध्येन चवर्गे ॥३६॥

36. In the *c*-series, with the middle of the tongue, upon the palate.

Compare Ath. Pr. i.21, and the note upon it. The sonant aspirate of this series, *jh*, is not met with in the text.

जिह्वेण प्रतिवेद्य मूर्धनि ठवर्गे ॥३७॥

37. In the *ṭ*-series, with the tip of the tongue, rolled back, in the head.

Compare Ath. Pr. i.22, and the note upon it. Our commentary says, "by the word 'head' (*mārdhan*) is intended the upper part

34. *sāmnidhyād anyeshām iti labhyate: svarebhyo nyeshān varṇānām tat karanam bhavati: adhyetā yena ryañjanāni sparṣayati prāpayati tat karanam.*

35. *kavarga uccāryamāne jihvāmūleṇa¹ hanūmāle sparṣayati prāpayet² ity arthaḥ. hanvor mūlān hanūmālayaḥ³: tasmin⁴: jātyapekshdyām⁵ ekavacanam.*

¹ G. M. ins. *varṇān*. ² B. G. M. om. ³ W. B. om. ⁴ G. M. ins. *mūlām iti*. ⁵ W. -*kham*.

36. *çavarge kārye¹ jihvāmadhyena varṇān² tālāu spr̥çet³.*

¹ G. M. put *tālāu* here. ² M. -*nān*. ³ B. *spr̥çayet*; G. M. *sparṣayet*.

of the mouth-cavity." Perhaps we shall best remove the difficulties attaching to the use of the word "head" in describing this class of sounds, by assuming that the name *mūrdhanya*, 'capital,' had become firmly established in use as designating them, at an earlier period of phonetic science in India, when their mode of production was less accurately understood and defined; and was therefore retained by the later grammarians, who gave to it a new definition. For, that *mūrdhan* should have been taken directly and without ceremony to signify the 'dome of the palate' does not appear to me possible. As in the notes to the Atharva-Prāṭicākhya, I shall take the liberty of speaking of the *t*-sounds as "lingual"—a term, on the whole, as unobjectionable and as commonly accepted as any other.

The commentator glosses the word *pratīveshtya*, 'having rolled it back,' by "having done what? having rolled back (G. M. add in explanation *āveshtya*, 'having rolled up') the tip of the tongue, on account of its suitableness" (i. e. of the adaptedness of this position to produce the contact aimed at).

जिह्वेणा तवर्गे दन्तमूलेषु ॥ ३८ ॥

38. In the *t*-series, with the tip of the tongue, at the roots of the teeth.

Compare Ath. Pr. i.24, and the note upon it.

ओष्ठान्यां पवर्गे ॥ ३९ ॥

39. In the *p*-series, with the two lips.

The commentator explains that here the upper lip is the place of production, as the various places of production mentioned have been the upper organ; and that the under lip is the organ of production.

Compare Ath. Pr. i.25, and the note upon it.

37. *tavarge kārye jīhvāgreṇa¹ mūrdhani² varṇam spr̥ṣet³: kiṁ kṛtvā: yogyatvā⁴ jīhvāgram pratīveshtya⁵: mūrdhagabdena vak-travīcaroparibhāgo vivakshyate⁶.*

¹ G. M. put *varṇam* here. ² B. G. M. *mūrdhani*. ³ B. *spr̥ṣet*. ⁴ W. *-tvā*; B. *-tvā* taj; G. *-tvā*; M. *-tvāyogyatvā*. ⁵ G. M. *-shīveshtya*. ⁶ G. M. *-kshīta*.

38. *tavarge kārye jīhvāgreṇa varṇam dantamūleṣu sparṣayet¹.*

¹ G. M. *spr̥ṣet*.

39. *pavarge kārya oṣṭhābhyām anyonyam sparṣayet: atro¹ 'taroshṭha sthānam uttaratvasāmyād² eṣhām sthānānam: adha-roshṭha³ karaṇam.*

¹ W. *tatro*. ² B. *-rātāt sāmanyād*; G. M. *oṣṭhatva*.

तालौ जिह्वामध्यान्ताभ्यां यकारे ॥४०॥

40. In *y*, with the two edges of the middle of the tongue, upon the palate.

The Tāittiriya-Prātiśākhya stands alone in omitting to rank the semi-vowels along with the mutes, as palatal, etc., and in describing their formation throughout by special rule. Respecting *y*, see the note to Ath. Pr. i.21.

The description of the mode of production of *y*, here given, is quite accurate and sufficiently distinctive. The "edges" are mentioned, as being the parts which form contact with the palate, the central part remaining open, as taught for *i* in rule 22, above.

रेफे जिह्वाग्रमध्येन प्रत्यग्दन्तमूलेभ्यः ॥४१॥

41. In *r*, with the middle of the tip of the tongue, back of the roots of the teeth.

Pratyak is explained by the phrase, "in the interior upper portion"—that is, 'within and above'—the equivalence of *pratyagātman* and *antarātman*, 'inner soul,' being pleaded as justification.

The somewhat discordant teachings of the Prātiśākhya with reference to this sound are detailed in the note to Ath. Pr. i.28. The most note-worthy circumstance in their common treatment of the letter is that they so ignore its special relationship with the lingual mutes, and in part with the *r*-vowels: although in this treatise the definition of the latter (ii.18) is, essentially, nearly accordant with that here given for the semi-vowel. *R* could not possibly have the value which belongs to it in the Sanskrit euphonic system, if it were not a lingual semi-vowel, like the English *r*, uttered with the tip of the tongue reverted into the dome of the palate.

दन्तमूलेषु च लकारे ॥४२॥

42. Also in *l*, at the roots of the teeth.

According to the commentator, the "and" (*ca*) of this rule brings down by implication from the preceding both *jihvāgramādhyā*, 'middle of the tongue-tip,' and *pratyak*, 'back from.' It

40. *yakāre kārye jihvāmadhyāntābhyām tālāu sparṣayet. jihvāyā madhyam: tasyā 'ntāu: tābhyām jihvāmadhyāntābhyām'.*

¹ G. M. om.

41. *rephe kārye jihvāgramādhyena dantamūlebhyaḥ pratyak sparṣayet: pratyag ity 'abhyantara uparibhāga' ity arthaḥ: 'yaḥ pratyagātme 'ty' antarātmā pratiyate.*

¹ G. M. -nīropari-. ² G. M. yathā pratyagātmani.

appears obvious, however, if only from the locative case of *dantamūleshu*, that the latter item is not intended, and that we are to regard the roots of the teeth themselves (more properly, the gums close upon them) as the *sthāna*, or 'place of production,' of *l*. This, indeed, is nearly enough intimated by the final paraphrase of the comment. The really distinctive characteristic of the *l*, that it forms a contact in front, but allows the breath to escape at the sides of the tongue, is here by no means clearly brought out: rather, we are left to infer that it and the *r* are produced in the same manner, only the *r* a little further back. No one of the other treatises gives a better description (see note to Ath. Pr. i.24, where I have given the Tāttiriya definition more credit than really belongs to it).

ग्रोष्ठान्ताभ्यां दन्तैर्वकारे ॥ ४३ ॥

43. In *v*, with the edges of the lips, along with the teeth.

This rule cannot be commended for distinctness. The commentator gives it not a little of additional precision, by his paraphrase "with the two edges of the lower lip, along with the points of the upper teeth." But how comes the lower lip to have two edges? He adds, that the teeth are the place, and the lips the organ, of production. But then why does not the rule read *danteshu*, instead of the instrumental *dantāih*? It gives us two instrumentals, as if teeth and lips were joint organs, and neither of them any more "place" than the other. The lower lip, being the more passive organ, should be the "place" on which the teeth, as "organ," make their contact; but from taking this view the treatise and its comment appear to be hindered by the analogy of the other *sthāna*'s, which have uniformly been the upper of the two parts concerned in the contact. To make a good definition, the rule should read *adharoshthānte* for *oshthāntābhyām*.

Of the other treatises (as pointed out in the note to Ath. Pr. i.25), the Vāj. Pr. gives the *v* a description corresponding with this, and showing the letter to have had the precise phonetic value of our English *v*. This, of course, should not in the least stand in the way of our fully recognizing the fact that its original sound was that of our *w*. The *w* is a semi-vowel, standing in the same relation to *u* as *y* to *i*; but to call *v* a semi-vowel is a sim-

42. *cakāro 'jihvāgramadhyapratyaktvam anvādiṣati': lakṣre kārye jihvāgramadhyena' dantamūleshu pratyak sparṣayet'*: *ayam arthaḥ: lakārasya 'dantamūlapratyāsannam pratyaganta-pradeṣasthānam' iti vijñeyam*³.

(¹) G. M. *jihvāmadhyam pratyaktvaṁ cā* "karṣati. ² G. M. *-hvāmadv-*. ³ W. B. put after *vijñeyam*. (²) G. M. *-sannapradeṣa sthānam*. ⁴ G. M. *jñeyam*.

43. *vakāre kārye 'dharoshthāntābhyām uttaradantāgrāh saha sparṣayet. dantāir iti sthānanirdeṣaḥ: oshthāntābhyām iti karananirdeṣaḥ*.

ple abuse of terms. We might nearly as well call our *j* a semi-vowel, because it is written with an originally vocalic sign, and represents in the majority of cases a sound which the Romans pronounced as *y*.

स्पर्शस्थानेषूच्चाण आनुपूर्व्येण ॥ ४४ ॥

44. The spirants, in their order, are produced in the places of the mutes.

By rule i.9, there are six spirants, and as there are but five "places" of mutes, these belong to the first five spirants, as is signified by the expression "in their order:" *h*, therefore, is omitted, and its rules will be given hereafter (rules 46, 47). To this effect the commentator, who also allots the spirants to their respective mute-classes, and cites from the Sanhitā an example for each: namely, for *jihvāmāliya*, uttered in the place of a *k*-mute, *yah kāmāyeta* (ii.3.2⁴ et al.: I follow the example of all the MSS., and do not attempt to distinguish the guttural and labial spirants from *visarjanīya* by different signs); for *ç*, in the place of a *c*-mute, *madhuç ca mādharāç ca* (i.4.14, or iv.4.11¹: W. B. omit the last two words of the citation, and W. reads *manyuç ca*, which is found at iv.7.2¹); for *sh*, in the place of a *t*-mute, *aštābhyah svāhā* (vii.2.15); for *s*, in the place of a *t*-mute, *stanā uparavāh* (vi.2.11⁴); and for *upadhmanīya*, in the place of a *p*-mute, *yah pāpmanā* (ii.3.13²).

To make this rule a definition of the mode of utterance of the spirants, the one next following is to be applied to modify it. Unfortunately, both together are insufficient to give us any clear idea of the two problematical sounds, *jihvāmāliya* and *upadhmanīya*; and there is room for us to suspect them of being, like the long *l*-vowel, an artificial fabrication of the Hindu grammarians. As for the *s*, there is no question as to its value. Nor ought there to be respecting that of the *sh*, which both the explanations of the phonetists and the phenomena of Sanskrit euphony show to have been that particular sibilant (more nearly resembling our *sh* than *s*, but sufficiently distinct from either) which is uttered with the tongue reverted into the dome of the palate. It passes my comprehension how European grammarians should continue to identify

44. *ūshmāna ānupūrvyena yathākramena sparśasthāneṣu 'ccāraṇīyā bhavanti. yathā: jihvāmāliyaḥ kavargasthāne: yah k-: çakāraç cavargasthāne: madhuç³ shakārash tavargasthāne: ašt-..... sakāras tavargasthāne: stanā..... upadhmanīyaḥ pavargasthāne: yah p-: ity ānupūrvyena²: ānupūrvyān¹ niyamāt pañcasū 'shmasū 'kteshu hakāro viçishṭah⁴: tasya vidhim upariśṭād ācaṣṭe.*

¹ W. *cavargīyas*; B. *cakāras*. ² W. *manyuç*. ³ G. M. *-vyā vijñeyah*. ⁴ G. M. *-vya*. ⁵ B. *-peshah*; G. M. *varishṭah*.

it with our *sh*; and, yet more, how that absurd distinction of the lingual and palatal sibilants (of which, so far as I know, Wilson was the originator) which defines the former as the same with our *sh* in *shun*, and the latter with our *ss* in *session*, can still be repeated in the latest Sanskrit grammars. Absurd I call it, because there is really no difference at all between the pronunciation of *sh* in *shun* and *ss* in *session*. If our *sh* be found in the Sanskrit alphabet, it is the palatal sibilant *ç*, not the lingual, *sh*. The question of the value of *ç* is connected with and depends upon that of the palatal series of mutes; and upon this I have nothing more to say than I said in the note to Ath. Pr. i.21.

करणमध्यं तु विवृतम् ॥ ४५ ॥

45. But the middle of the producing organ is unclosed.

The "but" (*tu*) of this rule, we are told, is intended to annul (so far) the similarity of organ of the spirants with the mutes. This prescription of an unclosure of the middle of the organ is a rather artificial device for saving the credit of the general prescription of actual contact in all the consonants. It is nearly equivalent with the rules of the Ath. Pr. (i.30,31) upon the same subject.

कण्ठस्थानौ ह्रकारविसर्जनीयौ ॥ ४६ ॥

46. The throat is place of production of *h* and *visarjanīya*.

And, the commentator adds, they have no *karana*, or organ of production. As example of *h*, he cites *aharahaḥ haviṛdhānīdam* (ii.5.6^a), but leaves *visarjanīya* uninstanced.

The other *Prāṭiśākhya*s give a corresponding definition of the utterance of these two sounds (see note to Ath. Pr. i.19). It is too indefinite to be of any particular use to us in determining their phonetic value. But the two rules which next follow in our treatise are very interesting and instructive.

उदयस्वरादिसंस्थानौ ह्रकार एकेषाम् ॥ ४७ ॥

47. In the opinion of some authorities, *h* has the same position as the beginning of the following vowel.

Our commentator first offers the simple paraphrase of this rule

45. *teshām āshmanām karanamadhyam tu vivṛtam bhavati: sparśanām karanasāmyanivṛttiparas' tucabdaḥ. karanānām madhyam karanamadhyam.*

^a B. -*ityartham*.

46. *hakāravisarjanīyāu kaṇṭhasthānau syātām. kaṇṭha sthānam yayos tātathoktāu. anayoḥ karanābhāvaḥ. ah-----*

which he finds given by one of his three chief authorities, Vararuci, and then proceeds to exhibit his own superior acuteness by a very long, but not very important, discussion of it: a loose version is as follows:

The expression "the same position as the beginning," etc., implies a difference of position in the remainder of the vowel; but there is none such in *a*, *i*, *u*; as a vowel has but a single position, the word "beginning" is superfluous, and the desired result would be secured by saying simply "of the same position with the vowel." That is not so: a difference of position does in fact belong to the remainder of the diphthongs: the two rules (ii. 28, 29) which teach that *i* and *u* form the final elements of *ai* and *au* assure the difference of position for those two sounds; in like manner, a difference of position is to be remarked as prescribed in general grammar [though not in this treatise] for the final elements of *e* and *o*, they being included in the category of diphthongs. But again: even granting that, the utterance in the throat of this very *a* which makes the initial element of the diphthongs is taught by the rule, "the throat is the place of production of *a*, the *k*-mutes, *h*, and *visarjanīya*;" hence, as sameness of position [with the *a*, as throat-sound] is prescribed by the preceding rule, this rule is open to the charge of superfluous repetition. You must not think so, is the reply; there is a difference between the *a* which forms the beginning of *e* and *o* and an *a* standing by itself: to the latter belongs the description given above in rule 12, "the lips and jaws not too widely separated," etc.; to the other, that of rule 27, "with the organ of production more closed;" therefore, as place and organ correspond to one another, the expression "of the same position as the beginning" is to be understood as meaning "of the same place and organ as the beginning." Moreover, in the former rule the absence of an organ of production was taught, but here is implied also the presence of such; hence a difference of opinions comes to light, and not merely a superfluous repetition.

47. *ekeshām mate hakāra' udayasvarādisasthāna ātmana upari svarādisasthāno' bhavati 'ti vararucoktam' syād etat. ādinā' sasthāna ity ukte geshasya sthānāntaratvam' vaktavyam tad apy akāreḥkāroḥkāreshu nā 'sti: ' svarasyāi "kam eva 'sthānam' ity ādicabdavāiyarthyaṁ syāt: svarasasthāna' ity etāvatai 'vā 'rthasiddhir' iti: māi 'vam: sandhyakshareshu geshasya' sthānāntaropapattēḥ: ikāro 'dhyardhaḥ (ii. 28) iti sūtradvayena geshabhūtavarnavyaktāu' tayo' sthānāntaram api prasiddham eva: evam' ekārāukārayor api vyākaraṇe' geshasya sthānāntaram vihitam vijñeyam: sandhyaksharātvarīḥṣhād anayoh. nanv evam apy akūhavisarjanīyānām kaṇṭha iti sandhyaksharādāv akārasyā' pi kaṇṭhashthānatvāt tena samānasthānatve' kathyamāne' pūrvasūtroktena' pūnaruktyam asya' sūtrasya*

Any detailed criticism of this cunning argument would certainly be open to the charge of superfluity, and I shall not attempt it.

A few further examples of the occurrence of *h*, before the various diphthongs, are added: *tigmahete* (i.2.14²), *yāvatiṛ vāsāmahāi* (vii.5.2¹), *agnihotram juhōti* (i.5.9¹), *samprayatiṛ ahāu* (v.6.1²).

The acuteness of observation of the "some authorities" who have made this definition of the character of a *h* certainly deserves respectful, if not admiring, acknowledgment. It is the peculiarity of the aspiration, that it is an emission of unintonated breath through the same position of the mouth organs by which the following intonated sound receives its character: thus, the *h* of *ha* is a surd *a*, so to speak; that of *he*, a surd *e*; that of *who*, a surd *u*; that of *hue*, a surd *y*; and so on (see Journ. Am. Or. Soc'y, viii.370 seq.). The rule would have been made better by reading *udayavarna*, instead of *udayasvarādi*—"the following sound," instead of "the beginning of the following vowel"—for the assimilation is not less true of the semi-vowels and nasals than of the vowels.

पूर्वान्तस्यानो विसर्जनीयः ॥४८॥

48. *Visarjaniya* has the same position as the end of the preceding vowel.

The commentator does not tell us whether this definition is to be looked upon as, like the preceding, expressing the opinion of "some authorities," or as having the unqualified approval of the *Prātiçākhyā*. From his silence we should infer the latter, but the connection gives reason for presuming the former. He paraphrases: "*visarjaniya* is of like position—that is, of like place and organ—with the end of the vowel that precedes itself;" and adds that

*syāt. māi 'vam maṁsthāh: ekārāukārādivartino*¹⁹ *kārasya kevalasya ca viçesho 'sti: kevalasya*²⁰ *karaṇam oshṭhahanu nā 'tivyastam* (ii.12) *iti*²¹: *sandhyaksharādāu vartamānasya tu samvṛtakaraṇataram* (ii.27): *tasmāt sthānakaraṇayoh saha-caritatvād*²² *ādisasthāna ity ukta ādisamānasthānakaraṇa*²³ *iti vijñeyam. kim ca: pūrcasūtre karaṇābhāva ity*²⁴ *uktaḥ: atra tu karaṇavattoam apī*²⁵ *vidyata iti matāntaram upapadyate: na pāunaruktyam ca. tathā*²⁶: *tig: yāv-..... agn-..... sam-..... udayaḥ caḍa uttaraparyāyah*²⁷: *udayaḥ cā 'sau*²⁸ *svaraḥ ca*²⁹: *tasyā*³⁰ *dih: tena sasthānaḥ.*

¹ G. M. put before *ekeshām*. ² G. M. *udayasvar*. ³ W. B. var-. ⁴ W. *ādī*. ⁵ G. M. -*taram*. ⁶ G. M. ins. *tathā sati*. (7) W. *kasthānam evam*. (8) B. om. ⁹ G. M. *svarasya sa*. ¹⁰ G. M. om. *artha*; G. M. -*ādher*. ¹¹ G. M. -*bhūtan v*. ¹² G. M. *tasyā*. ¹³ G. M. om. ¹⁴ G. M. -*na*. ¹⁵ G. M. *sthā*. ¹⁶ G. M. *kalpy*. ¹⁷ G. M. -*voḥ*. ¹⁸ G. M. *eva tasya*. ¹⁹ G. M. -*rayor ādī*. ²⁰ W. ins. *tu*. ²¹ G. M. *nā 'tivyapasarīhrtam ca*; B. no *pasarihrtam*. ²² W. B. -*ritvād*. ²³ W. -*sthāna*. ²⁴ G. M. om. ²⁵ G. M. om. ²⁶ G. M. om. ²⁷ G. M. *udayasvarādisasthānaḥ*. ²⁸ G. M. om. *asāu*. ²⁹ G. M. ins. *udayasvaraḥ*.

here too the language of the rule is aimed at the diphthongs, since no other vowel exhibits any difference of position between its end and its beginning. His examples, again, are only of *visarjanīya* after a diphthong: they are *agneḥ* (i.1.10³ et al.), *brāhmaṇāir āyushmat* (ii.3.10³), *bāhuvoḥ balam* (v.5.9²), and *ā'yam gāuh* (i.5.3¹). In the second and third of these passages, only the first word should have been quoted, in order to exhibit the *visarjanīya*.

The teachings of the other Prātiśākhya respecting the *visarjanīya* are rehearsed in the note to Ath. Pr. i.19. All are so indefinite as really to teach us nothing respecting the phonetic value of the sound. The present rule alone gives us positive and precise information, teaching us to regard it as, like the *h*, a simple uncharacterized breathing, a kind of final *h*.

नासिक्या नासिकास्थानाः ॥ ४९ ॥

49. The nose-sounds have the nose as their place of production.

The "nose-sounds," the commentary says, are the *yamas* (xxi. 12, 13); but why the *nāsikya* (xxi. 14) should not be regarded as included among them I do not see. Any discussion of their phonetic character may be best deferred until the chapter where the rules for their occurrence are given. As examples of the nose-sounds are quoted *rukman antaram* (v.i.10³; but G. M. B. give instead *rukmantam*, ii.2.3²), *yācāṇā* (i.5.7⁴; but G. M. give instead *rājāṇā*, ii.6.2² et al.), *ātānārah* (v.6.5³), *ratnam abhajānta* (ii.6.12¹; but G. M. give instead, if it be not merely a corrupted reading, *uccā ratnam ayojanta*, which I have not found in the Sanhitā), and *pāpmānam* (i.4.41 et al.).

मुखनासिक्या वा ॥ ५० ॥

50. Or they are produced by the mouth and nose.

Respecting this alternative explanation nothing need be said at present.

48. *visarjanīya ātmanah pūrvasvarāntena sasthanah samānasthānakaraṇo bhavati: atrā'pi pūrvasvara iti sandhyaksharam ucyate: svarāntarasya' hī' sthānāntaratvābhāvāt. yathā: ag-³ brāh-----: bāh-----: ā----- pūrvasyā'ntah: tena sasthanah pūrvāntasasthanah⁴.*

¹ W. B. -ntasya. ² B. om; G. M. bhinna. ³ B. om. ⁴ B. om. ⁵ B. om.

49. *nāsikyā yamā nāsikāsthānā bhavanti. yathā: ruk-----: yā: āt: rat-----: pāp.*

50. *ta' eva nāsikyā mukhanāsikābhyām² uccāranīyā bhavanti. mukham ca nāsikā' ca mukhanāsike⁴: tatsambandhino mukhanāsikyāh. 'uktāny evo 'dāharaṇāni³.*

¹ G. M. eta. ² G. M. mukhena nāsikābhyām ca. ³ G. M. -ke. ⁴ G. M. -kam. ⁵ G. M. put after bhavanti.

वर्गवच्चैषु ॥ ५१ ॥.

51. And, in them, the organ of production is as in the series of mutes.

The "and" (*ca*) of this rule, the commentator says, brings forward, on the principle of 'the lion's look' (a distant glance backward: the phrase is used several times later in like cases), the already defined organs of production of the various mute series.

If the mouth be regarded as bearing a part in the production of the nose-sounds or *yamas*, in a way which is determined by the mode of formation of the mutes to which they are attached, it is difficult to see how their number can be restricted to four, as it is in the "list of sounds" given at the beginning of the treatise, and in the comment on rule xxi.12.

नासिकाविवरणादानुनासिकं नासिकाविवरणादानु-
नासिकम् ॥ ५२ ॥

52. Nasal quality is given by the unclosing of the nose.

Ānunāsikya is the quality of being *anunāsika* or 'nasal;' and this name, as prescribed by rule 30, above, and fully supported by the usage of the treatise elsewhere, belongs to *anusvāra* and the various nasal consonants. The definition of the manner in which the quality is communicated is quite unexceptionable; the organs of the mouth remaining in the positions already given for the various classes and single sounds, the opening of the nasal passage, and the utterance through it of a part or the whole of the emitted material, makes the corresponding nasal sound.

The commentator explains *nāsikāvivarana* by *ghrānabila*, 'hole of the nose, nasal passage,' as if *vivarana* signified the opening or cavity, instead of the act of opening or unclosing. His choice of an example also seems to betray a want of appreciation of the true scope of the rule: it is *suṣṭhokāśāṇ sumāṅgalāśāṇ* (i.8.16²).

51. *siṅhāvalokanena*¹ *vargasyo* 'kām karaṇam cakāro 'nukar-shati: *eshu*² *nāsikyeshu* *vargavat* *karaṇam bhavati. vargasye* 'va *vargavat*.

¹ G. M. -*kananyāyena*. ² G. M. (as also in the text of the rule itself) *eteshu*.

52. *nāsikāvivaranaḍ ghrānabilād* *ānunāsikyam raṅgādi kar-tavyam. yathā*¹: *suṣ*.... *ity ādi*.

iti tribhāshyaratne prāṭicākhyavivarane
dvitīyo 'dhyāyah.

¹ G. M. *nāsikāśāṇ*. ² B. *tathā*; W. om.

CHAPTER III.

CONTENTS: 1, introductory; 2-6, cases of *d* at the end of the first member of a compound, requiring to be shortened in divided text; 7, of *i* and *u*; 8-12, of final *d* of verbal forms and particles; 13-14, of final *i* and *u*; 15, of initial *d*.

अथादावुत्तरे विभागे द्रुस्वं व्यञ्जनपरः ॥ १ ॥

1. Now then—at the beginning or end of a word, a vowel, in case of separation, if followed by a consonant, becomes short as hereinafter set forth.

Matters of introductory explanation, of interpretation of the rules of the treatise, and of phonetic theory, being now for the present disposed of (for they are resumed, in a supplementary way, in some of the concluding chapters), the task of determining the readings of the *Sanhitā* is taken up. And the first subject dealt with is that of the irregular prolongations of vowels—chiefly final *a*, *i*, and *u*—which are so frequent in all the Vedic texts. In the other treatises (*Rik* Pr. vii.-ix., *Vāj.* Pr. iii.95-128, *Ath.* Pr. iii.1-25), the rules tell us in what situations a vowel originally short is lengthened: this is more in accordance with the general method of the *Prātiśākhya*s, which take for granted, upon the whole, the existence of their *śākhās* in the analyzed condition of the *padā*-text, and proceed to construct the *saṁhitā* from it. Here, on the contrary, we are told what vowels, long in the ordinary text, are to be shortened when thrown out of combination with their surroundings. Such dissolution of the continuity of the text takes place, first, in *padā*, whenever a pause—either the *avagraha* separating the two members of a compound, in its repetition after *iti*, or the longer pause that divides between two words—comes to stand between the vowel in question and the consonant which was its next neighbor in *saṁhitā*: thus, *devāyata iti deva-yate*; *avanah* (s. *avā nah*). Second, it is made in the so-called *ajā*-text, examples of which are often quoted in the sequel, and to which the rules of the treatise are in more than one instance adapted; this text is constructed by thrice repeating each pair of words—first in

1. *athe 'ty ayam adhikārah: ādāu padādāv uttare padānte ca vartamānaḥ saṁhitāyām yo dīrgho 'sau vibhāge vibhāgasamaye vyañjanaparo hrasvam āpadyate: 'vyañjanaparatecam' atra yathāsaṁhitāsthān vijñeyam. nanu dīrghaḥ kathān labhyate. 'hrasvānantarabhāvitvād devāṅikā (iii.2) 'dīgrāhaneshu plutādarcanāc ce 'ti brūmah. saṁhitāyām ity asyā 'yam arthaḥ: kāryabhājah padasyo 'ttarapadēna saha sambandhaniyamah: na tu pūrvapadēna saha sambandhaniyamah'. vibhāgo 'tra*

their natural order, then inverted, then in the natural order again: for example, *āpo hi śthā mayobhuvah* would become *āpo hi hy āpa āpo hi: hi śthā stha hi hi śthā: sthā mayobhuvo mayobhuva stha sthā mayobhuvah: mayobhuva iti mayah-bhuvah*: the treatment of the *ā* of *sthā* here illustrates the conditions of the restoration of the short vowel in such cases. Third, the same restoration takes place in the *samhitā*-text of the existing manuscripts and in the edition founded upon them, when the lengthened vowel happens to come at the end of one of those passages, of just fifty words each, into which the *anuvākas* or sections of the *Samhitā* are divided. This division the *Prāticākhyā* does not recognize—or, at any rate, does not notice—not infrequently quoting in *sandhi*, without remark, words which are separated by it (for example, under rule 13, below, *uḥmasi gamadhye*, i.3.8¹⁻², where the edited text reads correctly *uḥmasi: 1: gamadhye*).

The comment upon this rule may be loosely translated, or paraphrased, as follows:

Here *atha*, 'now then,' is an introductory heading; *ādāu* [literally, 'at the beginning'] means 'at the beginning of a word' [including, also, a separable part of a compound word]; *uttare* [literally, 'in the latter part'] means 'at the end of a word:' a vowel occupying such a position, if it be long in *samhitā*, becomes short *vibhāge*, i. e. 'in case of separation,' when followed by a consonant—that is to say, when so followed in *samhitā*. But whence is derived the limitation to a "long" vowel? We answer, from its conversion into a short, and from the non-occurrence of any protracted (*pluta*) vowels among the instances included in the rules. The limitation "in *samhitā*" implies that the word whose form is in question is placed in euphonic connection with the word that follows it; not, however, with the word that precedes it [unless, as should be excepted, its initial vowel, instead of its final, is the one liable to change of quantity]. "Separation" (*vibhāga*) is to be understood as division from the words with which it stands in natural or original connection—that is, according to the reading of the fundamental text: otherwise, in the *jaṭā*-text of the two words *sthā mayobhuvah* (see above), the *stha* would retain its long *ā* in its second repetition, because of its standing in euphonic connection with the following word: and that should not be so. The sense of the word *vibhāga* is, in case of a long initial vowel, separation from the preceding word; in case of a long final, from the

prakṛtipadāir ucyate: prakṛtir nāma yathāpāthah: prakṛtipadāir iti kim: sthā m- ity atra jaṭāyām sthaḥcābdasya dvitīyocārāṇe 'pi dīrghah prasajyeta': uttarapadēnā vibhāgābhāvāt: sa' mā bhūd iti parihārah. vibhāgapadasyā 'yam arthah: padādāu' dīrghasya pūrvapadēnā vibhāgah: padānte' dīrghasyo 'ttarapadēnā vibhāgah. vibhāge vyañjanapara iti kim: ṛt-.... ity atra mā bhūd iti: nādhāmādhārayā (iii.8) iti prāptih. samhitāyām' dīrgha iti kim: esha-.... ity atra prāptisampādanārtham:

following word. The limitation "in case of separation, if followed by a consonant" is for the sake of excluding such cases as *ṛtadhā-mā 'si* (i.3.3: in separated form, *ṛtadhāmā: asi*), which would otherwise come under the rule iii.8 [among the specifications of which, *dhāmā* is included]. The limitation "a long vowel in *saṃhitā*" is intended to bring *eka vo bharatā rājā* (i.8.10² et al.; *pada*-text, *bharatāh*) under the action of the rules; since thus, and not otherwise, is pertinence given to the word *yājyā* in rule 11 of this chapter. Undue extension of the prescription to such cases as *tvā vāyavaḥ* (i.1.1) is provided against by the rules that follow [since these specify all the cases in which it is to be applied].

The only difficulty arising in connection with the understanding of this rule, or of the interpretation of it given by the commentator, grows out of the specification *vyāñjanapara*, 'followed by a consonant.' Respecting this, we are explicitly told, near the beginning of the exposition, "the being followed by a consonant is to be understood here of the condition of things in the *saṃhitā*-text"—that is to say, any long vowel which appears in *saṃhitā* as a final, with a consonant following it, is to be regarded as falling under the rules of the chapter. This specification, then, makes the rules apply to such cases as *bharatā rājā* (the example quoted by the commentator: the *pada*-reading is *bharatāh: rājā*) and *adhā mā* (quoted under rule 9; *pada*-reading *adhāh: mā*), and they have to be specially allowed for and excepted—as is done in rules 9 and 11. It seems very strange, now, to have this implication made, requiring as a consequence that all the words which by euphonic processes come to exhibit in *saṃhitā* a long final vowel (*ā*) should be taken into consideration: but the number of cases actually needing to be guarded against in the rules on account of it is very small. For, in the first place, the question can arise only in regard to the words specially mentioned in the rules; and among these there are not many for which homophonous forms in *āh* or *āi* occur; and of these, again, only a part would occur otherwise than before a vowel, in which situation the hiatus would betray the omission of the former final element. The makers of the treatise, then, appear to have thought it safer to avoid a possible confusion of *adhā* from *adhāh* with *adhā* from *adha*, and so on, by making the rules apply in general to both cases, and specially excepting the former. And this is what they have attempted to do; and it has cost them only two additional words—*agniyā-jye* in rule 9, and *yājyāsu* in rule 11—together with an artifice of

tathā sati bharatā yājyāsu (iii.11) *iti yājyāpadānī sārthakam nā nyathā. vyāñjanam asmāt param*¹ *iti vyāñjanaparah. tvā... ity ādāv etallakṣhanasambhavād*² *atīvyāptim*³ *uttara-mūtrāḥ pariharati.*

¹ G. M. ins. *padāntā ca padānte ca yo dīrgho vyāñjanottaro vibhāge kriyamāṇe hrasyaṇi sañiyati.* ² G. M. -nam. ³ G. M. om.; G. Arasvānt-. ⁴ G. om. ca. ⁵ G. M. -dhah. ⁶ W. om. ⁷ G. M. -yate. ⁸ G. M. om. ⁹ G. M. -gaṣab-. ¹⁰ W. -ddi. ¹¹ W. -nta. ¹² G. M. ins. *yo.* ¹³ G. M. -ra. ¹⁴ G. M. eva tal. ¹⁵ W. *atiprā-*

construction under rule 8, in connection with the word *prānāh*. Without a complete *index verborum* to the *Sanhitā*, or a laboriously minute examination of the whole text with reference to this particular point, I cannot tell just how nearly successful their attempt has been; but I have, I believe, discovered at least one case which they have overlooked. At i.4.24, namely, we read *rakshā mākih* (p. *rakshāh*), and, by rule 8, the *ā* of *rakshā* should be shortened. That the section containing these words was really a part of the text for which the *Prātiśākhya* was constructed is proved by the fact that two of its peculiarities of reading are provided for in later rules (vi.5 and xi.13).

But with the interpretation thus given appears to be quite at variance the phrase containing the illustration *ṛtadhāmā'si*, where *vibhāge* and *vyāñjanapārah* are immediately connected, and made to mean 'followed by a consonant in separated text' (not *ṛtadhāmā: asi*). This I can hardly believe to be a genuine part of the commentary. The second *ā* of *ṛtadhāmā'si* cannot be said to be either final or initial: it is a combination of both: it does not furnish a case to which the rules of the chapter apply with any propriety, as the *saṁhitā* reading cannot be affected by them. If not some later meddler, then the commentator himself, has suffered himself to be scared by an imaginary difficulty, and has unnecessarily twisted the rule a little awry in order to its removal.

The specification *vibhāge*, 'in case of separation,' applies in the *Tāittirīya pada*-text more generally and more strictly than in those of the other Vedas. Where the separation of a compound is suspended on account of its further composition, the restoration of its natural form is suspended also; and we read, for example, *vīrya-vat*, but *vīryāvāt-tara*; *viçva-mitra*, but *viçvāmītra-jamadagnī*; *anu-yāja* and *anany-yāja*, but *prayāja-anāyāja*, and so on—and we shall find illustrations hereafter in connection with other changes than prolongation of vowels. Thus, also, in the full *pada*-readings, the word is given first, before *iti*, in its *saṁhitā* form, without change (except euphonic combination with the *iti*); and this part of the reading I shall accordingly usually omit in quoting the *pada*-text, setting down only the separated and restored form which follows *iti*, or the part which corresponds to the entire reading of the *Rik* and *Atharvan pada*-texts.

देवाशीकामुन्नाश्चर्तव्युनाहृदयाधोक्त्याशुद्धा ॥ २ ॥

2. *Devā, śikā, sumnā, çvā, ṛtā, vayunā, hṛdayā, aghā,*

2. *ity eteshu grahaṇeṣhu avagraheṣhu' antyaśvaro vibhāge vyāñjanapāro hrasvām āpadyate. yathā: dev-....: śik-....: sumn-....: dyāv-....: 'apy akurādi (i.52) iti vacanād' idam apy udāharaṇam': açv-....: ṛt-....: vay-....: hṛd-....: agh-....: ukth-....: āpo-....*

¹ G. M. om. ⁽²⁾ B. om. ³ G. M. sūtrād ⁴ G. M. -hartavyam.

ukthā, and *śuddhā*, as first members of a compound, shorten their final when separated.

This and the following rules, including the seventh, properly form one connected passage, with the specification *ity avagrahaḥ*, 'these, as former members of a compound,' which applies alike to them all, standing at the end.

The examples quoted from the *Sanhitā* in illustration of the rule are as follows. For *devā*: *devāyate yajamānāya śarma* (iii.5.5³: G. M. omit the last word of the citation), the only case, so far as I have noted, for *devāyant*; we have *devayate* (with short vowel) twice, at i.2.12³ and ii.5.9³; *devāyuvam* occurs ii.5.9⁶ and iv.1.1³, but *devayuh*, iii.5.11¹. For *śikā*, *śikāyate svāhā* (vii.5.11²), the only case. For *śumnā*, *śumnāyanto havāmahe* (i.5.11⁴), also alone. For *śvā*, *dyāvāprthivya śvāvit* (v.5.20): *śvā*, however, by rule i.52, includes *aśvā*, for which is quoted *aśvāvatīṅ somavatīm* (iv.2.6⁴); I have noted farther only iii.3.11¹, but feel less than usual confidence in the completeness of my excerption. For *rtā*, *rtāyavah purā 'nnam akṣan* (ii.2.5⁵: G. M. omit the last word of the citation): there are more than twenty such cases in the text, for the themes *rtāyu* (e.g. i.4.5: but *rtāyu* once, ii.2.12²), *rtāyant* (e.g. iv.2.9³), *rtāvan* (e.g. i.3.14²) and its feminine *rtāvāri* (e.g. i.1.3), *rtāvedh* (e.g. i.4.5), and *rtāsah* (iii.4.7¹: but this word reads in *padā* as in *sanhitā*). For *vayunā*, *vayunāvid eka it* (i.2.13¹ and iv.1.1¹). For *hṛdayā*, *hṛdayāvidhaḥ cit* (i.4.45¹). For *aghā*, *aghāyavo mā gandharvo viśvāvasur ādadhat* (i.2.9: G. M. omit after *gandharvah*): other cases of *aghāyu* are found at iii.3.11¹: iv.1.10³; 5.10⁴; v.7.3¹; and of *aghāyant*, ii.3.14¹. For *ukthā*, *ukthāmadānām dhenuh* (ii.4.11⁶): the same compound occurs again at iii.3.2¹ and v.6.8⁶, and *ukthāyu* at i.4.12, twice. For *śudhā*, *āpo devīḥ śuddhāyuvah* (i.3.8² and vi.3.8⁴).

इन्द्रा वद्वान्यरः ॥३॥

3. Also *indrā*, when followed by *vat*, *van*, and *vān*.

One example is quoted by the commentator for each of the three cases enumerated: *indrāvatīm apacitīm ihā 'vaha* (v.7.4³: G. M. omit after *apacitīm*), *indrāvanto marutaḥ* (iv.7.14¹), and *indrāvānt svāhā* (i.1.12); and I have noted no others. As counter-examples, he quotes: first, to show that not every long *ā* is to be shortened before the three syllables named, *ārnāvantam prathamā sīda yonim* (iii.5.11¹: G. M. give only the first two words), *asura prajāvān* (iii.1.11¹: but B. reads, I presume only by an

3. *indre 'ty asminn' avagrahe 'ntyasvaro vad van vān ity evamparo vibhāge hrasvam āpadyate. yathā: ind-.....: ind-.....: ind-..... indre 'ti kim: ārn-.....: as-.....: praj-..... evampara iti kim: ind-.....*

¹ G. M. *etasminn*. ² G. M. *om*.

error, *pratāpavān*), and *prajāvatir anamivā ayakshmāh* (i.1.1: but omitted in G. M.); second, to show that *indrā* is not altered except under the circumstances specified, *indrāvarunayor aham* (ii.5.12²). This last is a case in which no *vibhāga*, or 'separation,' would be made in any text of the other Vedas; but the *Tāittiriya pada* reads *indrāvarunayor iti 'ndrā-varunayoh*, and the example is therefore to the purpose.

चित्रा वपरः ॥ ३ ॥

4. Also *citrā*, when followed by *v*.

The illustrative passage cited is *citrāvaso svasti te pārām aṣṭi* (i.5.5⁴ and 7⁵: G. M. omit after *te*). As counter-examples, are given *mitrāvarunāu eva* (ii.1.7² et al.: p. *mitrā-varunāu*), and *citrāpārnāmāse dīksheran* (vii.4.8²)—the former to show the necessity of the restriction to *citrā*, the latter, of the restriction to sequence by a *v*. I have found no farther instances falling under the rule.

प्रस्थेन्द्रियाद्रविणाविश्वदेव्यादीर्षावीर्याविश्वावातावा-
भङ्गुराकर्णिकावृष्णिगामुगोपकसानाघासत्रावर्षापुण्यामे-
घाप्रास्वा ॥ ५ ॥

5. Also *prasthā*, *indriyā*, *draviṇā*, *viṣvadevyā*, *dirghā*, *vīryā*, *viṣvā*, *vātā*, *tvā*, *bhaṅgurā*, *karnakā*, *vṛshṇiyā*, *sugopā*, *rksāmā*, *aghā*, *satrā*, *varshā*, *pushpā*, *meghā*, *prā*, *svā*.

For each of these words, the commentator cites a single example. For *prasthā*, *prasthāvad rathavāhanam* (iv.2.5⁶), the only case. For *indriyā*, *indriyāvate purodāgam* (ii.2.7⁷): half a dozen cases of this word occur in the text, and several of *indriyāvin* (e.g. i.6.2⁴: ii.1.6³: vi.2.10⁶); the latter word, however, is not separated in the *pada*-text. For *draviṇā*, *draviṇāvataḥ kurute* (v.3.11²), the only case. For *viṣvadevyā*, *viṣvadevyāvate svātrāh* (i.4.1¹): the word occurs also at iv.1.6^{1,2}. For *dirghā*, *dirghādhiyo rakshamānāh* (ii.1.11⁴), the only case. For *vīryā*, *vīryāvantam abhimāti-shāham* (i.2.7): the same theme is found in other passages, as are also its comparative, *vīryāvat-tara* (e.g. i.7.6³), and superlative, *vīryāvat-tama* (ii.4.2¹), in which the shortening of the *ā* is not authorized by the *Prātiśākhya*, since, in the division, it does not stand next before the pause: and the *pada*-text reads accordingly. For *viṣvā*, *viṣvāmitrasya sāktam bhavati* (v.2.3^{3,4}: G. M. omit

4. *citrā ity asminn' avagrahe 'ntyasvaro vakāraparo' vibhāge hrasvam āpadyate. yathā: cit----- citre 'ti kim: mitr----- vapara iti kim: citr-----*

¹ G. M. *etasminn*. ² G. M. *vap*-. ³ G. M. *om*.

the last word): the same word occurs in other passages (iv.3.2²: v.2.3^{3,4}, 10²; 4.2²), as also in the compound *viçvāmitrajamad-agnī* (v.4.11³), where, as the division is *viçvāmitra-jamadagnī*, the *ā* is not shortened; and we have further the themes *viçvāvasu* (e. g. i.1.11¹), *viçvāvant* (iii.5.6²), *viçvārāj* (i.3.2¹), and *viçvāsah* (i.4.17; p. *viçva-sāham*). For *vātā*, *vātāvad varshan* (ii.4.7¹), the only case. For *tvā*, *tvāvato maghonah* (ii.2.12²; p. *tea-vatah*): the Rik *pada*-text does not shorten the *ā* of this word. For *bhañgurā*, *bhettāram bhañgurāvatah* (i.5.6⁴ and iv.1.2³). For *karnakā*, *sūrmī karnakāvaty etayā* (i.5.7⁶ and v.4.7²: G. M. omit the first word, W. B. the last). For *vṛshniyā*, *vṛshniyāvatas tava* (iii.5.6²⁻³). For *sugopā*, *sa sugopātamo janah* (iv.2.11²; p. *sugopā-tamah*: G. M. omit the first word): the Rik *pada* writes *su-gopā-tamah*. For *ṛksāmā*, *ṛksāmābhyām yajushā* (i.2.3³ and iii.1.1⁴). For *aghā*, *aghāgvād evāi 'nam antar eti bhātam* (iii.1.7²; p. *agha-gvāt*: G. M. omit the last two words); the Rik and Atharvan *pada*-texts write *agha-agva*: the themes *aghāyu* (e. g. i.2.9¹) and *aghāyant* (ii.3.14¹) are also found in the Saṁhitā. For *satrā*, *satrājītanī dhanajitam* (iv.1.1²; p. *satra-jitam*): the word *satrā* occurs repeatedly (e. g. i.6.12¹) uncompounded, and maintains its long final in the *pada*-text also. For *varshā*, *varshāhvām juhōti* (ii.4.10³; p. *varsha-hvām*). For *pushpā*, *pushpāvatī supippalāh* (iv.1.4⁴ and v.1.5¹⁰). For *meghā*, *meghāyate svāhā* (vii.5.11¹; p. *megha-yate*; in the same division occurs also *meghāyishyate*, which is not divided: *meghayantī* is found at iv.4.5¹). For *prā*, *prāvanebhiḥ sajoshasah* (iv.2.4³; p. *pra-vanebhiḥ*); the Rik *pada*-text writes this word *pravana*, without separation; other words beginning with *prā* are *prāsah* (e. g. i.3.14⁶; p. *pra-sahā*), *prāgrūga* (ii.1.3^{4,5}), *prāsaca* (vii.5.11¹; not divided in *pada*-text), *prākāṣa* (i.8.18; also not divided), and *prāvṛta* (iv.6.2² et al.; also not divided). And for *svā*, *svādhiyam janayat sūdayac ca* (i.3.14⁶; p. *sva-dhiyam*): but this the Rik *pada*-text writes *su-ādhiyam*.

लोकश्चेष्टा ॥ ६ ॥

6. Also *ishṭā*, after *loke* and *eva*.

The commentator cites the two cases: *saṁ amuṣmīn loka ish-tāpārtena* (iii.3.8² twice: G. M. omit the first word), and *sa tv eva 'ishtāpārte* (i.7.3³; p. *ishṭa-pārte*). Then, to show that *ishṭā* after other words remains unchanged, he quotes *prati jāgrhy enam ish-tāpārte sañ srjethām ayaṁ ca* (iv.7.13⁵; p. *ishṭa-pārte*: W. B.

5. ----- *ity eteshv avagraheshv antyasvaro vibhāge vyañja-*
naparo hrāsvam āpadyate. yathā: pras-----: indr-----:
drav-----: viçv-----: dīr-----: vīr-----: viçv-----: vāt-----:
tvā-----: bhett-----: sūr-----: vṛsh-----: sa-----: ṛks-----:
agh-----: satr-----: varsh-----: pushp-----: megh-----:
prāv-----: svā-----.

omit before *enam*, G. M. after *-pārte*); and the same mode of treatment is followed by the *pada*-text at v.7.7², which is the only other case I have noted. The ground of this difference does not appear. To show, further, that only *ishṭā* shortens its *ā* in the defined position, the passage *sākshād eva prajāpataye* (v.1.2³) is given.

शक्तीरथीविषीवाशीरात्र्योषध्याहुतीव्याहृतीस्वाहृ-
कृतीह्रादुनीशचीचितीश्रोणीपृष्टीपूत्यभीचर्षणीपर्यधीपा-
रीशत्रूविषूवमूअनूहनूसूविभू इत्यवयवः ॥ ७ ॥

7. Also *çakti*, *rathi*, *tvishi*, *vāci*, *rātri*, *oshadhī*, *āhuti*, *vyāhṛti*, *svāhākṛti*, *hrāduni*, *çaci*, *citi*, *çroni*, *pr̥ṣhti*, *pūti*, *abhi*, *carshanī*, *pari*, *adhī*, *pāri*, *çatrū*, *viṣhū*, *vasū*, *anū*, *hanū*, *sū*, *vibhū*—all these, as first members of a compound.

To the passages cited by the commentator I add, as above, notice of other cases which I have found in the text. For *çakti*, the sole instance is *çakticanto gabbhīrah* (iv.6.6³). For *rathi*, *rathī-tamāu rathinām* (iv.7.15³). For *tvishi*, *aspiñjarāya tvishimate pathinām* (iv.5.2¹: W. B. omit the last word, G. M. the first). For *vāci*, *te vācīmanta ishminah* (ii.1.11² and iv.2.11²: G. M. omit the last word). For *rātri*, *rātribhir aubhnan* (ii.4.1¹): if there are other cases, I have failed to note them. For *oshadhī*, *oshadhībhyo vekatam ālabheta* (ii.1.5³: G. M. omit the last word): I have noted half a dozen other cases, but they are not worth reporting. For *āhuti*, *āhutibhir anūyājeshu* (ii.6.9⁴). For *vyāhṛti*, *etābhir vyāhṛtibhih* (i.6.10² and v.5.5³). For *svāhākṛti*, *svāhākṛtibhyah preshye 'ty āhu* (vi.3.9³: G. M. omit the last two words). For *hrāduni*, *svāhā hrādunibhyah svāhā* (vii.4.13: G. M. omit the first word, W. B. the last). For *çaci*, *viçvā rūpā 'bhi cashte çacibhih* (iv.2.5⁴⁻⁵: W. B. omit before *cashte*). For *citi*, *citibhyām upāyan* (v.7.5⁷). For *çroni*, *çronibhyāñ svāhā* (vii.3.16²): another case is found at v.7.15. For *pr̥ṣhti*, W. B. give *pr̥ṣtibhir divam* (v.7.17), but G. M. read *pr̥ṣtibhyah svāhā* (vii.3.16¹). For *pūti*, *pūtigandhasyā 'pahatyāi* (ii.2.2⁴). For *abhi*, *abhiṛto ghr̥n-vāñ cetati tmanā* (iii.5.11¹: G. M. omit the last two words): we have also *abhīshah* at ii.3.2⁶ (p. *abhi-sahā*). For *carshanī*, *mitra-sya carshanīdhertah* (iii.4.11⁵ and iv.1.6³): another case at i.4.16. For *pari*, *vīravantam parinasam* (ii.2.12⁶: p. *pari-nasam*: compare rule vii.4). For *adhī*, *adhivāsam yā hiranyāny asmāi* (iv.6.9²: G. M. omit the last word). For *pāri*, *pārinahyasye 'çe* (vi.2.1¹: p. *pāri-nahyasya*: compare rule vii.4). For *çatrū*, *ça-*

6. *loke*: *eva*: *ity evampārva ishṭe 'ty asmin' grahaṇe' 'ntya-svaro vibhāge vyañjanaparo hrasvam āpadyate. yathā: sa m..... sa..... evampārva iti kim: prati..... ishṭe 'ti kim: sāk.....*

¹ G. M. *etasminn*. ² G. M. *avagrahe*.

trāyato hantā (i.6.5² and iv.2.1²). For *vishā*, *vishāvān vishāvan-tah* (vii.4.3⁴): another case at vii.4.8². For *vasā*, *aramatir vasā-yuh* (iv.3.13⁶). For *anā*, *anūrādhaḥ nakshatram* (iv.4.10²); we have it also in the compounds *anāyāja* (e. g. ii.6.9⁴), *anābandhya* (e. g. ii.2.9⁷), *anākāca* (e. g. v.4.1²), and *anārvj* (v.7.23). In the further compound of the first, *prayājānāyāja* (e. g. i.7.1¹; p. *prayāja-anāyājān*), the shortening is not authorized, since in it there is no division after *anā*. Appealing to rule i.53 as his authority, the commentator adds, as contemplated by the present rule, *ananā-yājām prāyanāyam* (vi.1.5²; p. *ananu-yājām*). For *hanā*, *hanā-bhāṣā svāhā* (vii.3.16¹). For *sā*, *sāyavasiniḥ manave yaçasyē* (i.2.13²): *sāyavasa* occurs more than once (e. g. i.7.5^{2,3}). For *vibhā*, *vibhādārne* (iii.5.8,9²).

The commentator notes that the specification at the end of this rule defines the whole mass of words thus far enumerated as collectively *avagraha* (i.49), 'first members of compounds.'

अवासचस्वानुदामृडावर्धाशिन्नारत्नाद्याभवामत्रायत्रा-
चरापिबानाधामाधार्याधर्षाधावर्ध्याबोधात्रातत्रामुच्चाश्च-
स्यावृणस्वाहिष्ठावंतरात्रनिघ्रायुद्धाह ॥ ८ ॥

8. Also *avā*, *sacasvā*, *nudā*, *mṛdā*, *vardhā*, *çikshā*, *rakshā*, *adyā*, *bhavā*, *bhajā*, *yatrā*, *carā*, *pibā*, *nā*, *dhāmā*, *dhārayā*, *dharshā*, *ghā*, *vardhayā*, *bodhā*, *atrā*, *tatrā*, *muñcā*, *açvasyā*, *prñasvā*, *hi shthā*, *tvañ tarā*, *janishvā*, *yukshvā*, *achā*.

Henceforth we have to do only with independent words, the category of *avagrahas*, or former members of compounds, having been exhausted by the foregoing rules. There is cited in illustration, for *avā*, *avā no deryā kṛpā* (iv.1.4¹). For *sacasvā*, *sacasvā nah svastaye* (i.5.6²). For *nudā*, *pra nudā nah sapatnān* (iv.3.12¹ thrice, and v.3.5¹). For *mṛdā*, W. B. give *mṛdā jaritre* (iv.5.10⁴), but G. M. read *mṛdā nō rudra* (iv.5.10²): I have noted no other case. For *vardhā*, *vardhā no amavac chavaḥ* (ii.6.11³). For *çik-*

7. ity eteshv avagraheshv² antyasvaro vibhāge vyañja-
naparo hrasvam āpadyate. yathā: çak-....: rath-....: sa-....:
te-....: rā-....: osh-....: āh-....: et-....: svā-....: svā-
hā-....: vig-....: cit-....: grō-....: prsh-....: pāt-....:
abh-....: mitr-....: vīr-....: adh-....: pār-....: çatr-....:
vish-....: ar-....: anā-....: ankārādi ca² (i.53) iti vacanāt
anan-.... ity etad¹ udāharanam bhavati: han-....: sūy-....:
vibh-....: ity avagraha ity anena prakāreṇo³ 'ktiḥ⁴ padasam-
udāye⁵ 'vagraho vijñeyah⁶.

¹ G. M. om. ² G. M. om. ³ G. M. sūtrāt. ⁴ G. M. ins. apy. ⁵ G. M. 'ktaḥ.
⁶ G. M. mucçayah. ⁷ B. viçeshah.

shā, śikshā no asmin puruhāta yāmani (vii.5.7⁴: W. B. omit the last two words): it is found again at iv.6.2⁵. For *rakshā, rakshā ca no adhi ca deva brāhi* (iv.5.10³ and vii.5.24; G. M. omit the last two words): the form occurs also at ii.3.14¹. I have pointed out in the note to the first rule of the chapter that a passage (i.4.24) in which *rakshā* appears as euphonic alteration of *rakshāh* before a sonant consonant ought to be somehow excepted here. For *adyā, adyā devān jushtatamah* (iv.6.7⁵): also at ii.1.11⁶: iii.4.11²: iv.6.2⁶. For *bhavā, bhavā pāyur viço asyā adabdhoh* (i.2.14¹: G. M. omit the last two words): other cases are not infrequent; see i.1.14⁴; 4.32; iii.2.5³; 4.10¹; iv.1.7²; 2.5¹; 7⁴; 4.4⁷; and likewise ii.6.12¹, where *bhavā*, standing at the end of the first division of the *anuvāka*, is situated *vibhāge*, and loses its *ā* even in the *samhitā*-text. For *bhajā, ā gomati vroje bhajā tvam nah* (i.6.12¹: W. B. begin at *vroje*): another case at iii.3.9². For *yatrā, yatrā naro marutaḥ* (iii.1.11⁶): other cases at iv.4.4²; 6.6⁴; 7². For *carā, pra carā soma duryān* (i.2.10¹). For *pibā, pibā somam indra mandatu* (ii.4.14³: G. M. omit the last word): another case at i.4.19. For *nā, ripavo nā hā debhuh* (i.2.14²⁻⁶): in connection with this word, the commentator runs off into a lengthy discussion, which I defer to the end of the note. For *dhāmā, dhāmā ha yat te ajara* (iii.1.11⁶): we have *dhāma*, plural, in *samhitā* also, at iv.6.5⁵; 7.13⁴. For *dhārayā, brhaspate dhārayā vasāni* (i.3.7¹ and vi.3.6¹): other cases at iv.1.5⁴; 7². For *dhārshā, W. B. have dhārshā mānushān adbhyaḥ* (i.3.8¹), but G. M., *dhārshā mānushān iti ni yonakti* (vi.3.6³). For *ghā, utā vā ghā syālāt* (i.1.14¹): there is another case, if my manuscript reads correctly, at iii.4.11⁶. For *vardhayā, tam agne vardhayā tvam* (iv.6.3¹): other cases are at i.5.5²; iv.2.4⁴; 7.13⁵. For *bodhā, bodhā no asya vacaso yavishthā* (iv.2.3⁴: G. M. omit the last two words). For *atrā, atrā te rūpam* (iv.6.7³): other cases are at iv.6.7²; 8². For *tatrā, tatrā ratham upa śagmam* (iv.6.6³). For *muñcā, pra muñcā svastaye* (iii.2.8³): again at iv.7.15⁷. For *agvasyā, ekas tvash-tur agvasyā vīcātā* (iv.6.9²). For *prnasvā, sapta yonē ā prnasvā ghrtena* (i.5.3² and iv.6.5⁵). For *sthā* after *hi, āpo hi sthā mayobhuvah* (iv.1.5¹: v.6.1⁴: vii.4.19⁴); and, as counter-example, to show that the correption takes place only after *hi*, *pratishthā vā ekaviñcaḥ* (v.2.3⁶ et al.). For *tarā* after *tvam, agne tvam tarā mrdhah* (iv.1.9³), with the counter-example *antaratarā taptuervato bhavati* (vi.2.2⁷: G. M. omit the last word). For *janishcā, jani-*

8. ¹ *eteshv anavagraheshv antyasvaro vibhāge vyañjana-
paro hrasvam āpadyate. yāthā: avā.....: sac.....: pra.....:
mr.....: var.....: śiksh.....: rak.....: adyā.....: bhav.....:
.....: ā go.....: yat.....: pra.....: pibā.....: rip.....: api
vikṛtam* (i.51) *apy akārādi* (i.52) *iti dvābhyām² vacanā-
bhyām prā..... ity atra hrasvādeṣaḥ kim na syāt: māi³vam:
api vikṛtam* (i.51) *iti vacanām kanthoktapadavishayam³ na tv
akārādīpadavishayam⁴: prānā⁵ ity asyā⁶ py akārādīteṣā⁷ nā*

ahvā hi janyo agne (iv.1.3⁴ and v.1.4⁵: G. M. omit *agne*). For *yukshvā*, *yukshvā hi devahātāmān* (ii.6.11¹ et al.): other cases at iv.2.9⁵: v.5.3^{1,2}. For *achā*, *achā nakshī dyumattamah* (i.5.6³ and iv.4.4³): other cases at i.7.10²: ii.2.12⁸: 6.11¹: iv.2.4² twice; 4.4² (if my MS. is correct; the Rik reads *acha*); 5.1²: 6.7⁵: but the compound *achāvāka* (vii.1.5⁶) is left undivided and unchanged.

The occasion of the commentator's delay and discussion over the word *nā* is given by the fact that the *pada*-text of the Taittiriya Sanhitā (unlike that of the Rik and Atharvan: see note to Ath. Pr. iv.39) divides the word *prānāh* thus: *pra-anāh*. Hence, when we read in the Sanhitā, as in the passage which he quotes, *prānā vā āṅgavaḥ* (vi.4.4⁴: W. B. read simply *prānā vā*, which occurs in various other places; e. g. v.3.8²), he fears that, having this division in mind, we shall be misled into believing that the specification *nā* of the present rule applies to *prānā*, because we are taught in the first chapter (i.51,52) that a word cited in any rule comes equally under that rule when phonetically altered, or preceded by *a*. He sets aside this difficulty, however, by the arbitrary *dictum* that it is not permitted to vary the same word in both ways at once—that we may accept the altered form only of a vocable which is actually quoted entire, not of one made by the prefixion of an *a* to one so quoted: hence, he infers, the present rule does not apply to [the *anā* of] *prānā*, as it begins with *a*. But a further objection is interposed: in that case, why does it not apply to the part *anā* of the compound, in which is no altered *n*? He replies, because of the absence of a long vowel in *samhitā*, in a word wearing this form—or, as would seem a better statement, because of the absence of any such word in *samhitā* as *anā* (for *anāh*) with a long vowel as its final. The second objection, in fact, is a wholly futile one, scarcely worth the trouble of bringing up and setting aside. The original difficulty is one growing out of the extension of the leading rule in the chapter to cases of final *ā* in *samhitā* where a *visarjaniya* has been lost after it (see note to rule 1). The answer has a somewhat quibbling aspect, but the rule of interpretation which it involves is in accordance with that adopted in one or two analogous cases elsewhere.

अथाग्निवाये ॥ १ ॥

9. Also *adhā*, in *agni* and *yājyā* passages.

'yam vidhih. tarhi vikrtatevābhāvād* anā ity asye' ṅgyāñcasya
kim na syād ayaṁ vidhih. evamrāpasya samhitāyām dīrghābhā-
vāt. dhā.....: brh.....: dhar.....: uta.....: tam.....: bo-
dhā.....: atrā.....: tat.....: pra.....: ek.....: sap.....:
āpo.....: hī 'ti kim: pra.....: agne.....: tvam iti kim:
ant.....: jan.....: yuk.....: achā.....

¹ G. M. ins. *ity*. ² G. M. om. ³ W. -*ktip*.; B. om. *pada*. ⁴ B. om. *pada*. ⁵ W. ins. *vā*. ⁶ G. M. *vāikṛtasyā* 'bh-. ⁷ B. G. M. om. ⁸ B. G. M. -*yāp*-.
⁹ B. G. M. om. ¹⁰ B. G. M. -*yāp*-.
¹¹ B. G. M. om. ¹² B. G. M. -*yāp*-.
¹³ B. G. M. om. ¹⁴ B. G. M. -*yāp*-.
¹⁵ B. G. M. om. ¹⁶ B. G. M. -*yāp*-.
¹⁷ B. G. M. om. ¹⁸ B. G. M. -*yāp*-.
¹⁹ B. G. M. om. ²⁰ B. G. M. -*yāp*-.
²¹ B. G. M. om. ²² B. G. M. -*yāp*-.
²³ B. G. M. om. ²⁴ B. G. M. -*yāp*-.
²⁵ B. G. M. om. ²⁶ B. G. M. -*yāp*-.
²⁷ B. G. M. om. ²⁸ B. G. M. -*yāp*-.
²⁹ B. G. M. om. ³⁰ B. G. M. -*yāp*-.
³¹ B. G. M. om. ³² B. G. M. -*yāp*-.
³³ B. G. M. om. ³⁴ B. G. M. -*yāp*-.
³⁵ B. G. M. om. ³⁶ B. G. M. -*yāp*-.
³⁷ B. G. M. om. ³⁸ B. G. M. -*yāp*-.
³⁹ B. G. M. om. ⁴⁰ B. G. M. -*yāp*-.
⁴¹ B. G. M. om. ⁴² B. G. M. -*yāp*-.
⁴³ B. G. M. om. ⁴⁴ B. G. M. -*yāp*-.
⁴⁵ B. G. M. om. ⁴⁶ B. G. M. -*yāp*-.
⁴⁷ B. G. M. om. ⁴⁸ B. G. M. -*yāp*-.
⁴⁹ B. G. M. om. ⁵⁰ B. G. M. -*yāp*-.
⁵¹ B. G. M. om. ⁵² B. G. M. -*yāp*-.
⁵³ B. G. M. om. ⁵⁴ B. G. M. -*yāp*-.
⁵⁵ B. G. M. om. ⁵⁶ B. G. M. -*yāp*-.
⁵⁷ B. G. M. om. ⁵⁸ B. G. M. -*yāp*-.
⁵⁹ B. G. M. om. ⁶⁰ B. G. M. -*yāp*-.
⁶¹ B. G. M. om. ⁶² B. G. M. -*yāp*-.
⁶³ B. G. M. om. ⁶⁴ B. G. M. -*yāp*-.
⁶⁵ B. G. M. om. ⁶⁶ B. G. M. -*yāp*-.
⁶⁷ B. G. M. om. ⁶⁸ B. G. M. -*yāp*-.
⁶⁹ B. G. M. om. ⁷⁰ B. G. M. -*yāp*-.
⁷¹ B. G. M. om. ⁷² B. G. M. -*yāp*-.
⁷³ B. G. M. om. ⁷⁴ B. G. M. -*yāp*-.
⁷⁵ B. G. M. om. ⁷⁶ B. G. M. -*yāp*-.
⁷⁷ B. G. M. om. ⁷⁸ B. G. M. -*yāp*-.
⁷⁹ B. G. M. om. ⁸⁰ B. G. M. -*yāp*-.
⁸¹ B. G. M. om. ⁸² B. G. M. -*yāp*-.
⁸³ B. G. M. om. ⁸⁴ B. G. M. -*yāp*-.
⁸⁵ B. G. M. om. ⁸⁶ B. G. M. -*yāp*-.
⁸⁷ B. G. M. om. ⁸⁸ B. G. M. -*yāp*-.
⁸⁹ B. G. M. om. ⁹⁰ B. G. M. -*yāp*-.
⁹¹ B. G. M. om. ⁹² B. G. M. -*yāp*-.
⁹³ B. G. M. om. ⁹⁴ B. G. M. -*yāp*-.
⁹⁵ B. G. M. om. ⁹⁶ B. G. M. -*yāp*-.
⁹⁷ B. G. M. om. ⁹⁸ B. G. M. -*yāp*-.
⁹⁹ B. G. M. om. ¹⁰⁰ B. G. M. -*yāp*-.
¹⁰¹ B. G. M. om. ¹⁰² B. G. M. -*yāp*-.
¹⁰³ B. G. M. om. ¹⁰⁴ B. G. M. -*yāp*-.
¹⁰⁵ B. G. M. om. ¹⁰⁶ B. G. M. -*yāp*-.
¹⁰⁷ B. G. M. om. ¹⁰⁸ B. G. M. -*yāp*-.
¹⁰⁹ B. G. M. om. ¹¹⁰ B. G. M. -*yāp*-.
¹¹¹ B. G. M. om. ¹¹² B. G. M. -*yāp*-.
¹¹³ B. G. M. om. ¹¹⁴ B. G. M. -*yāp*-.
¹¹⁵ B. G. M. om. ¹¹⁶ B. G. M. -*yāp*-.
¹¹⁷ B. G. M. om. ¹¹⁸ B. G. M. -*yāp*-.
¹¹⁹ B. G. M. om. ¹²⁰ B. G. M. -*yāp*-.
¹²¹ B. G. M. om. ¹²² B. G. M. -*yāp*-.
¹²³ B. G. M. om. ¹²⁴ B. G. M. -*yāp*-.
¹²⁵ B. G. M. om. ¹²⁶ B. G. M. -*yāp*-.
¹²⁷ B. G. M. om. ¹²⁸ B. G. M. -*yāp*-.
¹²⁹ B. G. M. om. ¹³⁰ B. G. M. -*yāp*-.
¹³¹ B. G. M. om. ¹³² B. G. M. -*yāp*-.
¹³³ B. G. M. om. ¹³⁴ B. G. M. -*yāp*-.
¹³⁵ B. G. M. om. ¹³⁶ B. G. M. -*yāp*-.
¹³⁷ B. G. M. om. ¹³⁸ B. G. M. -*yāp*-.
¹³⁹ B. G. M. om. ¹⁴⁰ B. G. M. -*yāp*-.
¹⁴¹ B. G. M. om. ¹⁴² B. G. M. -*yāp*-.
¹⁴³ B. G. M. om. ¹⁴⁴ B. G. M. -*yāp*-.
¹⁴⁵ B. G. M. om. ¹⁴⁶ B. G. M. -*yāp*-.
¹⁴⁷ B. G. M. om. ¹⁴⁸ B. G. M. -*yāp*-.
¹⁴⁹ B. G. M. om. ¹⁵⁰ B. G. M. -*yāp*-.
¹⁵¹ B. G. M. om. ¹⁵² B. G. M. -*yāp*-.
¹⁵³ B. G. M. om. ¹⁵⁴ B. G. M. -*yāp*-.
¹⁵⁵ B. G. M. om. ¹⁵⁶ B. G. M. -*yāp*-.
¹⁵⁷ B. G. M. om. ¹⁵⁸ B. G. M. -*yāp*-.
¹⁵⁹ B. G. M. om. ¹⁶⁰ B. G. M. -*yāp*-.
¹⁶¹ B. G. M. om. ¹⁶² B. G. M. -*yāp*-.
¹⁶³ B. G. M. om. ¹⁶⁴ B. G. M. -*yāp*-.
¹⁶⁵ B. G. M. om. ¹⁶⁶ B. G. M. -*yāp*-.
¹⁶⁷ B. G. M. om. ¹⁶⁸ B. G. M. -*yāp*-.
¹⁶⁹ B. G. M. om. ¹⁷⁰ B. G. M. -*yāp*-.
¹⁷¹ B. G. M. om. ¹⁷² B. G. M. -*yāp*-.
¹⁷³ B. G. M. om. ¹⁷⁴ B. G. M. -*yāp*-.
¹⁷⁵ B. G. M. om. ¹⁷⁶ B. G. M. -*yāp*-.
¹⁷⁷ B. G. M. om. ¹⁷⁸ B. G. M. -*yāp*-.
¹⁷⁹ B. G. M. om. ¹⁸⁰ B. G. M. -*yāp*-.
¹⁸¹ B. G. M. om. ¹⁸² B. G. M. -*yāp*-.
¹⁸³ B. G. M. om. ¹⁸⁴ B. G. M. -*yāp*-.
¹⁸⁵ B. G. M. om. ¹⁸⁶ B. G. M. -*yāp*-.
¹⁸⁷ B. G. M. om. ¹⁸⁸ B. G. M. -*yāp*-.
¹⁸⁹ B. G. M. om. ¹⁹⁰ B. G. M. -*yāp*-.
¹⁹¹ B. G. M. om. ¹⁹² B. G. M. -*yāp*-.
¹⁹³ B. G. M. om. ¹⁹⁴ B. G. M. -*yāp*-.
¹⁹⁵ B. G. M. om. ¹⁹⁶ B. G. M. -*yāp*-.
¹⁹⁷ B. G. M. om. ¹⁹⁸ B. G. M. -*yāp*-.
¹⁹⁹ B. G. M. om. ²⁰⁰ B. G. M. -*yāp*-.
²⁰¹ B. G. M. om. ²⁰² B. G. M. -*yāp*-.
²⁰³ B. G. M. om. ²⁰⁴ B. G. M. -*yāp*-.
²⁰⁵ B. G. M. om. ²⁰⁶ B. G. M. -*yāp*-.
²⁰⁷ B. G. M. om. ²⁰⁸ B. G. M. -*yāp*-.
²⁰⁹ B. G. M. om. ²¹⁰ B. G. M. -*yāp*-.
²¹¹ B. G. M. om. ²¹² B. G. M. -*yāp*-.
²¹³ B. G. M. om. ²¹⁴ B. G. M. -*yāp*-.
²¹⁵ B. G. M. om. ²¹⁶ B. G. M. -*yāp*-.
²¹⁷ B. G. M. om. ²¹⁸ B. G. M. -*yāp*-.
²¹⁹ B. G. M. om. ²²⁰ B. G. M. -*yāp*-.
²²¹ B. G. M. om. ²²² B. G. M. -*yāp*-.
²²³ B. G. M. om. ²²⁴ B. G. M. -*yāp*-.
²²⁵ B. G. M. om. ²²⁶ B. G. M. -*yāp*-.
²²⁷ B. G. M. om. ²²⁸ B. G. M. -*yāp*-.
²²⁹ B. G. M. om. ²³⁰ B. G. M. -*yāp*-.
²³¹ B. G. M. om. ²³² B. G. M. -*yāp*-.
²³³ B. G. M. om. ²³⁴ B. G. M. -*yāp*-.
²³⁵ B. G. M. om. ²³⁶ B. G. M. -*yāp*-.
²³⁷ B. G. M. om. ²³⁸ B. G. M. -*yāp*-.
²³⁹ B. G. M. om. ²⁴⁰ B. G. M. -*yāp*-.
²⁴¹ B. G. M. om. ²⁴² B. G. M. -*yāp*-.
²⁴³ B. G. M. om. ²⁴⁴ B. G. M. -*yāp*-.
²⁴⁵ B. G. M. om. ²⁴⁶ B. G. M. -*yāp*-.
²⁴⁷ B. G. M. om. ²⁴⁸ B. G. M. -*yāp*-.
²⁴⁹ B. G. M. om. ²⁵⁰ B. G. M. -*yāp*-.
²⁵¹ B. G. M. om. ²⁵² B. G. M. -*yāp*-.
²⁵³ B. G. M. om. ²⁵⁴ B. G. M. -*yāp*-.
²⁵⁵ B. G. M. om. ²⁵⁶ B. G. M. -*yāp*-.
²⁵⁷ B. G. M. om. ²⁵⁸ B. G. M. -*yāp*-.
²⁵⁹ B. G. M. om. ²⁶⁰ B. G. M. -*yāp*-.
²⁶¹ B. G. M. om. ²⁶² B. G. M. -*yāp*-.
²⁶³ B. G. M. om. ²⁶⁴ B. G. M. -*yāp*-.
²⁶⁵ B. G. M. om. ²⁶⁶ B. G. M. -*yāp*-.
²⁶⁷ B. G. M. om. ²⁶⁸ B. G. M. -*yāp*-.
²⁶⁹ B. G. M. om. ²⁷⁰ B. G. M. -*yāp*-.
²⁷¹ B. G. M. om. ²⁷² B. G. M. -*yāp*-.
²⁷³ B. G. M. om. ²⁷⁴ B. G. M. -*yāp*-.
²⁷⁵ B. G. M. om. ²⁷⁶ B. G. M. -*yāp*-.
²⁷⁷ B. G. M. om. ²⁷⁸ B. G. M. -*yāp*-.
²⁷⁹ B. G. M. om. ²⁸⁰ B. G. M. -*yāp*-.
²⁸¹ B. G. M. om. ²⁸² B. G. M. -*yāp*-.
²⁸³ B. G. M. om. ²⁸⁴ B. G. M. -*yāp*-.
²⁸⁵ B. G. M. om. ²⁸⁶ B. G. M. -*yāp*-.
²⁸⁷ B. G. M. om. ²⁸⁸ B. G. M. -*yāp*-.
²⁸⁹ B. G. M. om. ²⁹⁰ B. G. M. -*yāp*-.
²⁹¹ B. G. M. om. ²⁹² B. G. M. -*yāp*-.
²⁹³ B. G. M. om. ²⁹⁴ B. G. M. -*yāp*-.
²⁹⁵ B. G. M. om. ²⁹⁶ B. G. M. -*yāp*-.
²⁹⁷ B. G. M. om. ²⁹⁸ B. G. M. -*yāp*-.
²⁹⁹ B. G. M. om. ³⁰⁰ B. G. M. -*yāp*-.
³⁰¹ B. G. M. om. ³⁰² B. G. M. -*yāp*-.
³⁰³ B. G. M. om. ³⁰⁴ B. G. M. -*yāp*-.
³⁰⁵ B. G. M. om. ³⁰⁶ B. G. M. -*yāp*-.
³⁰⁷ B. G. M. om. ³⁰⁸ B. G. M. -*yāp*-.
³⁰⁹ B. G. M. om. ³¹⁰ B. G. M. -*yāp*-.
³¹¹ B. G. M. om. ³¹² B. G. M. -*yāp*-.
³¹³ B. G. M. om. ³¹⁴ B. G. M. -*yāp*-.
³¹⁵ B. G. M. om. ³¹⁶ B. G. M. -*yāp*-.
³¹⁷ B. G. M. om. ³¹⁸ B. G. M. -*yāp*-.
³¹⁹ B. G. M. om. ³²⁰ B. G. M. -*yāp*-.
³²¹ B. G. M. om. ³²² B. G. M. -*yāp*-.
³²³ B. G. M. om. ³²⁴ B. G. M. -*yāp*-.
³²⁵ B. G. M. om. ³²⁶ B. G. M. -*yāp*-.
³²⁷ B. G. M. om. ³²⁸ B. G. M. -*yāp*-.
³²⁹ B. G. M. om. ³³⁰ B. G. M. -*yāp*-.
³³¹ B. G. M. om. ³³² B. G. M. -*yāp*-.
³³³ B. G. M. om. ³³⁴ B. G. M. -*yāp*-.
³³⁵ B. G. M. om. ³³⁶ B. G. M. -*yāp*-.
³³⁷ B. G. M. om. ³³⁸ B. G. M. -*yāp*-.
³³⁹ B. G. M. om. ³⁴⁰ B. G. M. -*yāp*-.
³⁴¹ B. G. M. om. ³⁴² B. G. M. -*yāp*-.
³⁴³ B. G. M. om. ³⁴⁴ B. G. M. -*yāp*-.
³⁴⁵ B. G. M. om. ³⁴⁶ B. G. M. -*yāp*-.
³⁴⁷ B. G. M. om. ³⁴⁸ B. G. M. -*yāp*-.
³⁴⁹ B. G. M. om. ³⁵⁰ B. G. M. -*yāp*-.
³⁵¹ B. G. M. om. ³⁵² B. G. M. -*yāp*-.
³⁵³ B. G. M. om. ³⁵⁴ B. G. M. -*yāp*-.
³⁵⁵ B. G. M. om. ³⁵⁶ B. G. M. -*yāp*-.
³⁵⁷ B. G. M. om. ³⁵⁸ B. G. M. -*yāp*-.
³⁵⁹ B. G. M. om. ³⁶⁰ B. G. M. -*yāp*-.
³⁶¹ B. G. M. om. ³⁶² B. G. M. -*yāp*-.
³⁶³ B. G. M. om. ³⁶⁴ B. G. M. -*yāp*-.
³⁶⁵ B. G. M. om. ³⁶⁶ B. G. M. -*yāp*-.
³⁶⁷ B. G. M. om. ³⁶⁸ B. G. M. -*yāp*-.
³⁶⁹ B. G. M. om. ³⁷⁰ B. G. M. -*yāp*-.
³⁷¹ B. G. M. om. ³⁷² B. G. M. -*yāp*-.
³⁷³ B. G. M. om. ³⁷⁴ B. G. M. -*yāp*-.
³⁷⁵ B. G. M. om. ³⁷⁶ B. G. M. -*yāp*-.
³⁷⁷ B. G. M. om. ³⁷⁸ B. G. M. -*yāp*-.
³⁷⁹ B. G. M. om. ³⁸⁰ B. G. M. -*yāp*-.
³⁸¹ B. G. M. om. ³⁸² B. G. M. -*yāp*-.
³⁸³ B. G. M. om. ³⁸⁴ B. G. M. -*yāp*-.
³⁸⁵ B. G. M. om. ³⁸⁶ B. G. M. -*yāp*-.
³⁸⁷ B. G. M. om. ³⁸⁸ B. G. M. -*yāp*-.
³⁸⁹ B. G. M. om. ³⁹⁰ B. G. M. -*yāp*-.
³⁹¹ B. G. M. om. ³⁹² B. G. M. -*yāp*-.
³⁹³ B. G. M. om. ³⁹⁴ B. G. M. -*yāp*-.
³⁹⁵ B. G. M. om. ³⁹⁶ B. G. M. -*yāp*-.
³⁹⁷ B. G. M. om. ³⁹⁸ B. G. M. -*yāp*-.
³⁹⁹ B. G. M. om. ⁴⁰⁰ B. G. M. -*yāp*-.
⁴⁰¹ B. G. M. om. ⁴⁰² B. G. M. -*yāp*-.
⁴⁰³ B. G. M. om. ⁴⁰⁴ B. G. M. -*yāp*-.
⁴⁰⁵ B. G. M. om. ⁴⁰⁶ B. G. M. -*yāp*-.
⁴⁰⁷ B. G. M. om. ⁴⁰⁸ B. G. M. -*yāp*-.
⁴⁰⁹ B. G. M. om. ⁴¹⁰ B. G. M. -*yāp*-.
⁴¹¹ B. G. M. om. ⁴¹² B. G. M. -*yāp*-.
⁴¹³ B. G. M. om. ⁴¹⁴ B. G. M. -*yāp*-.
⁴¹⁵ B. G. M. om. ⁴¹⁶ B. G. M. -*yāp*-.
⁴¹⁷ B. G. M. om. ⁴¹⁸ B. G. M. -*yāp*-.
⁴¹⁹ B. G. M. om. ⁴²⁰ B. G. M. -*yāp*-.
⁴²¹ B. G. M. om. ⁴²² B. G. M. -*yāp*-.
⁴²³ B. G. M. om. ⁴²⁴ B. G. M. -*yāp*-.
⁴²⁵ B. G. M. om. ⁴²⁶ B. G. M. -*yāp*-.
⁴²⁷ B. G. M. om. ⁴²⁸ B. G. M. -*yāp*-.
⁴²⁹ B. G. M. om. ⁴³⁰ B. G. M. -*yāp*-.
⁴³¹ B. G. M. om. ⁴³² B. G. M. -*yāp*-.
⁴³³ B. G. M. om. ⁴³⁴ B. G. M. -*yāp*-.
⁴³⁵ B. G. M. om. ⁴³⁶ B. G. M. -*yāp*-.
⁴³⁷ B. G. M. om. ⁴³⁸ B. G. M. -*yāp*-.
⁴³⁹ B. G. M. om. ⁴⁴⁰ B. G. M. -*yāp*-.
⁴⁴¹ B. G. M. om. ⁴⁴² B. G. M. -*yāp*-.
⁴⁴³ B. G. M. om. ⁴⁴⁴ B. G. M. -*yāp*-.
⁴⁴⁵ B. G. M. om. ⁴⁴⁶ B. G. M. -*yāp*-.
⁴⁴⁷ B. G. M. om. ⁴⁴⁸ B. G. M. -*yāp*-.
⁴⁴⁹ B. G. M. om. ⁴⁵⁰ B. G. M. -*yāp*-.
⁴⁵¹ B. G. M. om. ⁴⁵² B. G. M. -*yāp*-.
⁴⁵³ B. G. M. om. ⁴⁵⁴ B. G. M. -*yāp*-.
⁴⁵⁵ B. G. M. om. ⁴⁵⁶ B. G. M. -*yāp*-.
⁴⁵⁷ B. G. M. om. ⁴⁵⁸ B. G. M. -*yāp*-.
⁴⁵⁹ B. G. M. om. ⁴⁶⁰ B. G. M. -*yāp*-.
⁴⁶¹ B. G. M. om. ⁴⁶² B. G. M. -*yāp*-.
⁴⁶³ B. G. M. om. ⁴⁶⁴ B. G. M. -*yāp*-.
⁴⁶⁵ B. G. M. om. ⁴⁶⁶ B. G. M. -*yāp*-.
⁴⁶⁷ B. G. M. om. ⁴⁶⁸ B. G. M. -*yāp*-.
⁴⁶⁹ B. G. M. om. ⁴⁷⁰ B. G. M. -*yāp*-.
⁴⁷¹ B. G. M. om. ⁴⁷² B. G. M. -*yāp*-.
⁴⁷³ B. G. M. om. ⁴⁷⁴ B. G. M. -*yāp*-.
⁴⁷⁵ B. G. M. om. ⁴⁷⁶ B. G. M. -*yāp*-.
⁴⁷⁷ B. G. M. om. ⁴⁷⁸ B. G. M. -*yāp*-.
⁴⁷⁹ B. G. M. om. ⁴⁸⁰ B. G. M

The commentator's first care is to define what parts of the *Sanhitā* are styled *agni* and *yājyā*. The former name, he says, designates those *mantras* which celebrate *Agni*—namely, the fourth *kānda*: by the latter are intended the concluding *anuvākas*, or sections, of every *pragṇa*, or chapter, from the beginning of the *Sanhitā* to the third *pragṇa* of the fourth *kānda*, inclusive; and, besides, the eleventh *anuvāka* of *pragṇa* six, *kānda* two (i. e. i.1.14; 2.14; 3.14; 4.46; 5.11; 6.12; 7.13; 8.22: ii.1.11; 2.12; 3.14; 4.14; 5.12; 6.11,12: iii.1.11; 2.11; 3.11; 4.11; 5.11: iv.1.11; 2.11; 3.13—in all, twenty-three *anuvākas*). The name *agni* does not occur again: the *yājyās* are the subject of further prescription below, in rules iii.11, ix.20, xi.3. The compound *agniyājyā* (neuter singular) is justified by a simple reference to Pāṇini's rule (ii.2.29) defining a copulative compound.

The passages cited in illustration of the rule are *adhā hy agne kratoh* (iv.4.4⁷), *adhā ca naḥ garma yacha dribarhāh* (iv.5.10⁸: G. M. omit the last word), *adhā te sunnam imāhe* (ii.6.11⁴), and *adhā yathā naḥ pitaroh* (ii.6.12⁴: W. B. omit the last word): I have noted no other cases. As counter-example, to show the necessity of the restriction imposed in the rule, is quoted *adhā me 'ti tad vishnave 'ti prāyachat* (ii.4.12⁴: W. B. omit *prāyachat*), where *adhā* stands for *adhāh*: see, for the bearing of the exception, the note upon the introductory rule of the chapter.

कुत्रादक्षिणेनास्वेनादन्तनाजगामारुहेमाविद्वर्ध्यामाच-
कृमाक्षामास्त्रोमाभरेमावर्षयथेरयथारियापायायामिञ्चया-
जनयथाज्ञयतोक्षितावतायाताशृणुताकृणुताविभृता ॥ १० ॥

10. Also *kuṭrā*, *dakshinenā*, *svenā*, *hantanā*, *jagāmā*, *ruhemā*, *vidmā*, *rāhyāmā*, *cakrmā*, *kshāmā*, *starimā*, *bharemā*, *varshayathā*, *irayathā*, *ārithā*, *pāthā*, *athā*, *siñcathā*, *janayathā*, *jayatā*, *ukshatā*, *avatā*, *yātā*, *ṣṇutā*, *kṛṇutā*, *bibhrtā*.

The commentator's illustrative passages are: for *kuṭrā*, *kuṭrā cid yasya samrtāu* (ii.1.11³: G. M. omit the last word). For *dak-*

9. *agniḥ ca yājyā cā 'gniyājyam'*: *tasmin'*: *cā 'rthe dvandva it' samāsah*. *agnir ity agniprakāśakamantrā' lakshyante*: *catvṛthakānda ity arthah*: *ubhā vām indragñā* (i.1.14¹) *prabhṛty agnir vṛtrāṇi* (iv.3.13¹) *paryantāḥ praçnottamānūvākā yājyāsamjñā bhavanti yukshvā hi* (ii.6.11¹) *ity anuvākaḥ ca 'atra vishaye' 'dhe ty asmin' grahaṇe ntyuscāro vibhāge' vyañja-naparo hrāsvam āpadyate*. *yathā*: *adhā hy.....adhā ca.....adhā te.....adhā y.....agniyājyā iti kim*: *adhā m.....*

¹ G. M. -jye. ² G. M. -iāc. ³ G. M. om. ⁴ B. -çaman-. ⁵ G. M. om. ⁶ G. M. etasmin. ⁷ G. M. om.

shinena, dakshinena vasani patih sindhānām asi (iii.4.11⁴: G. M. omit after *vasani*). For *svena, svena hi vṛtraṇ garasā jaghantha* (vii.4.15: B. omits the last word; G. M. the last two). For *hantā, tapasā hantā tam* (iv.3.13⁴). For *jagāmā, ā jagāmā para-syāh* (i.6.12⁵). For *ruhemā, asravantīm ā ruhemā svastaye* (i.5.11⁵). For *vidmā, vidmā te agne tredhā trayāni vidmā te* (iv.2.2¹: G. M. stop at *agne*, thus instancing only one of the two cases; there are two more in the same verse); also at i.7.13³: ii.6.11⁴. For *rdhyāmā, rdhyāmā ta ohāih* (iv.4.4⁷). For *cakrmā, cakrmā kac canā "gah* (iv.7.15⁶): other cases at i.8.3: ii.6.12²: iv.1.11¹: 6.8³. For *kshāmā, kshāmā rerihad vīrudhaḥ* (i.3.14²: iv.2.12²: G. M. omit the last word): other cases at ii.6.12⁴: iv.7.12³. For *starimā, sushtarimā jushānā* (v.1.11²): here the application of rule i.51 becomes necessary. For *bharemā, añho-muce pra bharemā manishām* (i.6.12²: G. M. omit the last word). For *varshayathā, yūyam ershtīm varshayathā parishinoh* (ii.4.8²: W. B. omit the first word). For *irayathā, ud irayathā marutah* (iii.4.8²). For *ārithā, yoner udārithā yaje tam* (iv.6.5⁴). For *pāthā, kshayē pāthā divo vimahasah* (iv.2.11²). For *athā, athā somasya prayati yuvabhyām* (i.1.14¹: G. M. omit the last word): other cases are numerous, namely i.1.13¹ twice; 5.5², 11²; 6.4² twice; 7.13⁴: ii.3.14²; 6.12²: iii.1.11²; 4.11⁶: iv.2.1⁴, 4⁴, 5², 6¹, 2²; 6.3⁴ twice; 7.13⁵; and, as I doubt not, at the end of iii.2.11², where, however, the present *samhitā*-text reads *atha*, because the word stands *vibhāge*. For *siñcathā, yatrā nāro marutah siñcathā madhu* (iii.1.11⁶). For *janayathā, āpo janayathā ca nah* (iv.1.5¹: v.6.1⁴: vii.4.19⁴). For *jayatā, upa pre 'ta jayatā nara sthirāh* (iv.6.4⁴: G. M. omit the last word). For *ukshatā, ā ghṛtam ukshatā madhucarnam* (iv.3.13⁶). For *avatā, asmān u devā avatā haveshu* (iv.6.4⁴): another case at iv.2.6³. For *yātā, devā rathāir yātā hīranyayāih* (iv.7.12¹: G. M. omit the first word). For *ṛnutā, marutah ṛnutā havam* (iv.2.11²). For *kṛnutā, samvatsarāya kṛnutā brhān namah* (v.7.2⁴). Finally, for *bibhṛtā, mātē 'va putram bibhṛtā sv enam* (iv.2.3²: W. B. begin at *putram*).

भरता याज्यासु ॥११॥

11. Also *bharatā*, in *yājyā* passages.

10. ity' eteshv anavagraheshv' antyasvaro vibhāge
 vyañjanaparo hrāsvam āpadyate. yathā: kutrā....: da-
 ksh....: svenā....: tap....: āj....: asr....: vidmā....:
 rdhy....: cakṛ....: kshā....: susht....: añh....: yū-
 yam....: ud....: yoner....: kshaye....: athā....: ya-
 trā....: āpo....: upa....: ā....: asmān....: devā....:
 mar....: sam....: mā....

¹ G. M. om. ² W. aug.; G. M. om.

Which are the sections called *yājyā* has been pointed out above, under rule 9.

The cited passages are: *bharatā vasuvittamam* (iii.5.11⁴), *bharatā jātavedasam* (iii.5.11¹), and *pāryam vaco gñaye bharatā brhat* (iii.2.11¹: G. M. omit the first two words), which are all that the text contains. As counter-example, to show the necessity of restricting the change to *yājyā* passages, is quoted *esha vo bhāratā rājā* (i.8.10², 12²), where *bharatā* stands for *bharatāh*. If the text contained a *bharatā* as instrumental of the participle *bharant*, it would come more properly under the action of the rule, and would have a better right to be specifically excluded; but I have not found such a form anywhere. Respecting *bharatā* as standing in *samhitā* for *bharatāh*, see what is said in the note to the first rule of this chapter.

अत्ताभवतानदत्तातरतातपताजुहुतावोचतामुचताच-
ताधुष्याज्ननयावर्तयासादयापारयादीयाहुराभरापाससादा-
सृजातिष्ठयेना ॥ १२ ॥

12. Also *attā*, *bhavatā*, *anadatā*, *taratā*, *tapatā*, *juhutā*, *vocatā*, *amuñcatā*, *ṛtā*, *ghushyā*, *janayā*, *vartayā*, *sādayā*, *pārayā*, *diyā*, *harā*, *bharā*, *apā*, *sasādā*, *srjā*, *tishthā*, and *yenā*.

The cited passages are: for *attā*, *attā haviñshi* (ii.6.12²). For *bhavatā*, *ādityāso bhavatā mṛdayantaḥ* (i.4.22 and ii.1.11⁴). For *anadatā*, *samprayatir ahāv anadatā hāte* (v.6.1²: W. B. omit the first word). For *taratā*, *suvo ruhānās taratā rajāñsi* (iii.5.4²: G. M. omit the first word). For *tapatā*, *gharman na sāmān tapatā surktibhiḥ* (i.6.12²: W. B. O. [O. begins in the comment to this rule] omit before *tapatā*). For *juhutā*, *pitre juhutā viçvakarmāne* (iv.6.2⁶). For *vocatā*, *viçe devāso adhi vocatā me* (iv.7.14²: G. M. omit to *adhi*). For *amuñcatā*, *padi shītām amuñcatā yajatrāḥ* (iv.7.15⁷). For *ṛtā*, *ayasmayam vi ṛtā bandham etam* (iv.2.5²). For *ghushyā*, *parushparur anu ghushyā viçasta* (iv.6.9²). For *janayā*, *manur bhava janayā dānyam janam* (iii.4.2², 3⁷). For *vartayā*, *tābhir ā vartayā pināḥ* (iii.3.16¹). For *sādayā*, *sādayā yajñān sukṛtasya yonau* (iii.5.11² and iv.1.3²). For *pārayā*, *agne tvam pārayā navyo asmān* (i.1.14⁴: all but W. omit the last word). For *diyā*, *brhaspate pari diyā rathena* (iv.6.4¹⁻²: the text reads *diya*, as the word stands before the division between the first and second fifty of the section): another case is iii.1.11⁶. For *harā*, *nihāram in ni me harā nihāram*

11. *bharatā ity asmin¹ grahanē² 'ntyasvaro yājyāvishaye³ vībhāge vyañjanaparo hrāsvam āpadyate. yathā: bhar-----: bhar-----: pār----- yājyāsv itī kim: esha-----*

¹ G. M. *etasmin*. ² B. *avagrahashe*. ³ G. M. *yājyāyam*, and put before the preceding word.

(i.8.4¹). For *bharā*, *mā no mardhīr ā bharā dadhi tan nah pra dāgushe* (i.7.13³: O. omits after *bharā*; B. G. M. after *dadhi*): there is no other case, *bharā* at i.3.14² in the Calcutta edition being an erratum. For *apā*, *duro na vājaṇ grutyā apā vrdhi* (ii.2.12⁶: W. B. omit the first two words). For *sasādā*, *agnir hotā ni sha sādā yayiyān* (i.3.14¹ and iv.1.3⁴: G. M. omit the first word): there is another case at iv.6.2¹, requiring, like the others, the application of rule i.51. For *srjā*, *srjā vrshtīm divah* (ii.4.8², 10²): there are other cases at ii.4.8²: iii.5.5², 10¹: iv.1.8². For *tishthā*, *tishthā devo na savitā* (iv.1.4²): other cases at iii.1.4¹: v.2.1⁴, and perhaps also at iv.1.2³, where the word ends a division of the *anuvāka*. For *yenā*, *yenā sahasraṁ vahasi* (iv.7.13⁴ and v.7.7²).

उग्रमसीक्रयीकृधीश्रुधीयदी ॥ १३ ॥

13. Also *uḡmasī*, *krayī*, *kṛdhī*, *śrudhī*, and *yadī*.

The quoted examples for these words, being the only ones which the text contains, are as follows. For *uḡmasī*, *te te dhāmāny uḡmasī gamadhye* (i.3.6¹⁻²: W. B. O. omit the first three words): here, as *uḡmasī* stands at the end of a division, or *vibhāge*, its *i* is short in the accepted text. For *krayī*, *rudra yat te krayī param nāma* (i.8.14²). For *kṛdhī*, *kṛdhī sv asmān aditeh* (iv.7.15²: W. B. O. omit the last word). For *śrudhī*, *imam me varuṇa śrudhī havam* (ii.1.11⁶). For *yadī*, *yadī bhūmim janayan* (iv.6.2⁴).

सूतूनमिथूननू ॥ १४ ॥

14. Also *sū*, *tū*, *nū*, *mithū*, *makshū*, and *ū*.

The cited passages are as follows: for *sū*, *mō shū na indra* (i.8.3). For *tū*, *ā tū na upa gantana* (i.5.11⁴⁻⁵): there are two other cases, i.7.13²: ii.2.12², both after *ā*. For *nū*, *etaṇanya nū rane* (iv.6.12²). For *mithū*, *gātrāny asinā mithū kdh* (iv.6.9⁴: G. M. omit the first word). For *makshū*, *makshū devavato rathah* (i.8.22²). For *ū*, a part of the manuscripts give two examples,

12. *eteshe anavagraheshe¹ antyascaro² vibhāge vyañ janoparo hrascam āpadyate. yathā: attā..... ād..... sampr..... suvo..... ghar..... pitre..... viḡve..... padī..... ayas..... par..... man..... tābh..... sād..... agne..... bṛh..... nih..... mā..... duro..... agnir..... srjā..... tish..... yenā.....*

¹ W. av.; G. M. grahaṇeshu. ² O. begins here.

13. *ity¹ eteshv² anavagraheshe³ antyascaro vibhāge vyañjanoparo hrascam āpadyate. yathā: te..... rudra..... kṛdhī..... imam..... yadī.....*

¹ G. M. om. ² G. M. eshe. ³ W. av.; G. M. om.

asmābhir ā nu praticakshyā 'bhāt (i.4.33: wanting in G. M.), and *ārdhva ā shu na utaye* (iv.1.4²: W. B. O. omit the first word, G. M. the last): other cases are found at i.5.11²: ii.5.12²: iii.5.10¹: iv.1.10²: 6.5²: v.1.5²: vii.1.18²: 6.17².

व्युत्पूर्व आननुदात्तो ञ्नुष्मवत्यनूष्मवति ॥ १५ ॥

15. Also *ān*, when unaccented, and preceded by *vi* or *ut*, in a word containing no spirant.

This rule applies simply to the compounds *vyāna* and *udāna*, in which the long *ā* of the radical syllable is treated by the *pada*-text as the effect of an irregular prolongation. The words are instanced by the commentator in their full *pada*-form, *vyānāye 'ti vi-ānāya* (iii.5.8 et al.), and *udānāye 'ty ut-ānāya* (iv.2.9¹ et al.). In the same manner, *prānāya* and *opānāya* are divided into *pra-ānāya* and *apa-ānāya*. As regards the treatment of this group of compounds, the different *pada*-texts are somewhat inconsistent and somewhat conflicting. The Atharvan *pada* (see Ath. Pr. iv.39) divides *vi-āna* and *sam-āna*, without correction of the radical *ā*, but leaves *prāna* and *opāna* undivided. The Rik *pada* does not divide *prāna*: I do not know that any of the others are Rik words. The White Yajus, again (Vāj. Pr. v.33,36), divides *apa-āna* and *sam-āna*, but not *prāna*. The consistency of the Tāittiriya *śākhināḥ* is to be commended; less, perhaps, their assumption that the *ā* of *āna* is a mere Vedic irregularity, requiring restoration to a correcter form. They also, it may be remarked, divide *prānātha* (iv.1.4¹) into *pra-anātha*.

The commentator goes on to cite counter-examples, proving the necessity of the restrictions imposed by the rule. To show that *ān* is to be shortened only after *vi* and *ut*, he gives *yad āncus tene 'yam* (vii.3.1²: W. B. O. omit the last word), and *paryānīyā hovanīyasya* (vii.1.6²). To show that only *ān*, not *ā* followed by any other consonant, is shortened, he quotes *yad rukmanī vyāghā-rayati* (v.2.7²), and *udānāya pṛthivīm jiradānuḥ* (i.1.9²: G. M. omit the last word). To show that the *ān* must not be accented, he gives *viśvākarmā vyānat* (iv.2.10²), and *nēshṭaḥ pātnīm udānāya* (vi.5.8²). Finally, to show that the presence of a spirant in the word prevents the correction, we have *pathā madhor dhārā vyānaguh* (v.7.7²: all but W. omit the first word), and *ud ānīshur mahir iti* (v.6.1²).

The question is now in point, how complete is this rehearsal of the cases of prolonged vowels occurring in the Sanhitā; or, how closely does the *pada*-text which it assumes correspond with that

14. ity' eteshv' anavagraheshv' antyāsvaro vibhāge
vyāñjanoparo hrāscam āpadyate. yathā: mo..... ā.....
eta..... gā..... mak..... asm..... ārdhva.....

¹ G. M. om. ² G. M. *etshv*. ³ W. *an*; G. M. om.

found in the existing *pada*-manuscripts? As regards the latter point, I am unable to speak with certainty, of course, without the possession of a *pada*-manuscript, and its careful examination throughout; but so much as this I can say—that, having referred a liberal selection of the most questionable cases to Dr. Haug at Munich, for verification in his *pada*-texts, no instance of a discordance between these and the *Prātiçākhyā* has come to light. Among the cases referred were several in regard to which I was beforehand very confident that I had caught the authors of the *Prātiçākhyā* in fault. Thus *yojā*, in the refrain *yojā nṛ indra te hari* (i.8.5^{1,2}) which is shortened to *yōja* in the *pada*-texts both of the Rik (by Rik Pr. vii.7) and the White Yajus (by Vāj. Pr. iii.106), remains *yojā* in that of our *Sanhitā*. Again, *eva* occurs six times in our text with its final lengthened (viz. at i.8.22²: ii.1.11²: iv.2.9²; 3.13²; 7.15⁷: v.2.8³), as it does also not infrequently in the other Vedic texts (as noticed and provided for in their *Prātiçākhyas*: see Rik Pr. vii.12,19; viii.20: Vāj. Pr. iii.123: Ath. Pr. iii.16, note, L.I.c.): but the *Tāittiriya pada* reads in each case *evā*. Once more, in the passage *tava dharmā yuyopima* (Rig-Veda vii.89.5; Ath. Veda vi.51.3; *Tāitt. Sanh.* iii.4.11⁶), the *pada*-texts of the Rik and Atharvan read *dharma* (I do not find that the case is noted in the Rik Pr.; in the Ath. Pr. it would fall under the comprehensive rule iii.16), while that of our *Sanhitā* has *dharmā*, like the *saṁhitā*-reading.

I will add, as received from the same quarter, a few words respecting which a question might naturally arise as to how they were treated in the *pada*-text. Separated, without correction of the long vowel at the end of their first member, are *uttarā-eat* (v.4.8⁵), *sahasā-van* (i.6.12⁶), *malmalā-bhavant* (i.4.34), *vṛshā-kapī* (i.7.13²), such copulative compounds as *indrā-varuṇayohi* (ii.5.12²) and *agnā-vishnū* (i.1.12), and *ārṇā-mradas* (i.1.11¹): while, nevertheless, we have *ārṇa-mradas* at i.2.2², the *pada*-reading agreeing in both cases with that of the *saṁhitā*: where the Calcutta edition gets its authority for reading *ārṇāmmradas* and *ārṇāmmradas* is more than I can imagine).

15. *vī 'ty evampūrva utpūrvo vā 'n ity esha 'svaro 'nudātto 'nāshmaraty' āshmarahite pade vartamāno vyañjanaparāḥ padā-dāu vartamānatvāt pūrvapadena' vibhāge sati hrasvam āpadyate. yathā: vyānāye 'ti vi-anāya: udānāye 'ty ut-anāya. evampūrva iti kim: yad-----: pary-----: nakārah kimarthah: yad-----: udā-----: anudātta iti kim: viçv-----: nesh-----: anāshmarati 'ti kim: pathā-----: ud-----.*

*iti tribhāshyaratne prātiçākhyavivarane
tṛtīyo 'dhyāyoh'.*

¹ G. M. ins. *dkāra*. ² W. *āshm*. ³ G. M. *-de*. ⁴ G. M. add *prīkṣhṇāya namah*.

Not separated, and therefore, of course, without correction of the vowel, are such words as *rtāshāt* (iii.4.7¹) and *turāshāt* (i.7.13⁴), also *trashtimant* (i.2.5²), *anyādrç* (i.8.13²), *ubharyādāt* (ii.2.6²), *arātiyant* (i.6.1¹) and *arātivan* (vii.4.15), *atikāça* (i.2.2²) and *prākāça* (i.8.18), *avāçrñga* (ii.1.8³) and *prāçrñga* (ii.1.3¹: I doubt not: my information is deficient for this word), *upānah* (v.4.4⁴), *nivāra* (iv.7.4²) and *nihāra* (iv.6.2²), and *purāravaḥ* (i.3.7¹).

There is not, as in the other Vedic texts, any restoration of a theoretically correct short vowel which is not strictly a final or initial: thus we read in *pada*-text, for example, *vāvrðhe* (i.4.20), *sāsa-hat* (i.3.14⁷), and *ushāsam* (iv.4.4²).

Many of these items constitute striking peculiarities of the Tāittiriya *pada*, and its careful study and comparison with the other works of its class would undoubtedly bring to light much that is curious.

CHAPTER IV.

CONTENTS: 1-4, introductory; 5-54, rehearsal of cases of *pragrahas*, or uncombinable final vowels.

अथ प्रग्रहाः ॥ १ ॥

1. Now the *pragrahas*.

A simple heading to the chapter, and explained as such by the commentator. The same subject is treated by the other Prātiçākhyas, at Rik Pr. i.18-19, Vāj. Pr. i.92-98, Āth. Pr. i.73-82. It occupies here a great deal more space, because the Tāitt. Pr. avoids on principle the mention of grammatical categories in its rules, and is at infinite pains to catalogue, word by word, what the other treatises dispose of summarily, by classes. A rule in a later chapter (x.24) teaches that all the vowels here rehearsed and defined as *pragraha* are exempt from euphonic combination. The term *pragraha* is peculiar to this treatise, the rest using instead *pragrñhya*.

नावग्रहः ॥ २ ॥

2. No former member of a compound is *pragraha*.

As the former member of a separable compound (*avagraha*: i.49) is regarded and treated as an independent *pada*, the rules declaring certain final vowels *pragraha* would apply to the finals

1. *athe 'ty ayam adhi-kārah: pragrahā ucyanta ity 'etad' adhi-kṛtaṁ veditavyam ita' uttaraṁ yad vakshyāmaḥ.*

(¹) W. om. (²) G. M. om.

of such members, but for this prescription to the contrary. The commentator cites rules 5, 6, 36, 37, 49 of the chapter as needing the restriction of their application here made, and quotes from the *Sanhitā* in illustration *tanānapād asuraḥ* (iv.1.8¹: the *tanā* of *tanā-napād* would otherwise be *pragraha* by rule 5), *agoargham yajamānam* (vi.1.10¹: *ago-argham* would fall else under rule 6), *agnīshomāu mā* (ii.5.2²: it is implied that the *pada*-text would write *agnī-somāu*, bringing the word within the sphere of rule 36; such compounds are not divisible in the other Vedic texts), and *dvedve puronuvākye kuryāt* (ii.2.9²: the *pada* writes *dve-dve*, so that both members would be declared alike *pragraha* by rule 49). The present precept is therefore declared to be one making exceptions in advance to the rules specified.

अतः ॥३॥

3. Only a final is *pragraha*.

Or, as the commentator paraphrases, the end of a word is entitled to the designation *pragraha*. He cites, as example, the phrase *devate samrddhyāi* (ii.1.9³). The necessity of the rule, he explains, arises out of the fact that the following rules, in part—for example, rules 5, 6, 33—describe certain letters or syllables as *pragraha* without farther limitation, and it is desirable to specify that they bear that character only when final. This in answer to the criticizing inquiry “whether a letter not final can also be *pragraha*?”—that is, as I understand it, whether this predicate is not in the nature of things restricted to finals? But now a yet more troublesome objection is raised. The limitation to finals, urges the interpellator, is otherwise assured; for the word *api* of the next rule, in the sequel of this one, brings into action the principle “continued implication is of that which is last” (i.58). The objection is wholly futile and inept, both as implying that false interpretation of the rule appealed to to which attention was directed in the note upon it, and as attributing to *api* a mysterious force to which it can lay no claim whatever. Instead, however, of showing the

2. *avagrahaḥ pragraho na bhavati: akāraḥ* (iv.5): *okāro 'sāñhito 'kāravyañjanaparaḥ* (iv.6): *gnī* (iv.36): *na hi-paraḥ* (iv.37): *dve* (iv.49) *iti vakshyate: etad' uddiṣya puras-tādopavādo 'nena vidhīyate. yathā: tan-.....: ago-.....: agn-.....: dve-.....: avagraha' iti jātyapekshāyām ekavacanam.*

¹ W. -ti; B. O. om. ² G. M. tad. ³ G. M. om. ⁴ G. M. na 'v.

3. *padasyā 'ntaḥ pragrahasañjño bhavati. yathā: dev-..... atrā 'ha: kim apadānto 'pi pragrahaḥ syāt. atro 'cyate: akāraḥ* (iv.5) *ity aviṣeshena vakshyati: okāro 'sāñhito 'kāravyañjanaparaḥ* (iv.6) *iti: cī yatpraparaḥ* (iv.33) *itica: apadāntasyo 'kārasyāu 'kārasya cīcābdasya vā pragrahatvam' mā bhūd iti.*

objector to the door, the commentator proceeds elaborately to confute him. "We reply, not so: specification of finality is appropriate where there is a congeries of several letters; here, on the other hand, there is indication of a single letter. If the matter in question were the euphonic alteration or elision of *ā* and the other letters treated of, a final would be designated in virtue of the principle quoted: but here it is a simple case of application of the term *pragraha*, not of an affected nor an affecting letter: hence continued implication has no force."

इतिपरो अपि ॥३॥

4. It is followed by *iti*.

This is the interpretation of the commentator, who declares that the "also" (*api*) brings in by implication, from the first rule of the preceding chapter, the specification *vibhāge*, 'in case of separation,' or in the *pada* and other artificially divided texts. As example, he cites *ubhe iti* (i.4.22 et al.: G. M. add *devate iti*, ii.1.9³ et al.).

If such be its real meaning, the rule is a very anomalous one, as giving a single direct prescription respecting the mode of construction of the secondary texts. These are elsewhere only referred to or implied, in a more indirect manner. I should therefore prefer to translate 'even when followed by *iti*'—that is to say, a word here defined as *pragraha* in the ordinary text has that character also in the other texts before *iti*, not being combined with the latter.

उकारः ॥५॥

5. A long *ā* is *pragraha*.

nanu siddham evāi 'tat: etatsūtraṣeshabhāta' uttarasūtre² 'piṣa-bdenā 'nvādego 'ntyasya (i.58) eva kāryanirvāhāt³. ne 'ti brāmah: anekavarṇasamudāye hy antyateam⁴ upopannam: ayam punar ekavarṇanirdeṣaḥ: ākārah (iv.5) ity ādivarṇasya yāu vikāralopāu tayor⁵ 'nvādego 'ntyasya (i.58) ity amenā 'ntyah: pragraha ity uktam⁶ pragrahasamjñāmātram⁷: na tu⁸ nimittam nimitti vā: tasmād anvādego na prasarati.

¹ G. M. *grahayam*. ² B. O. *-ṣeṣhe*; G. M. *-bhāt*. ³ G. M. *ottarasūtra sū-*. ⁴ G. M. *vāhakah*. ⁵ B. O. *anta-*. ⁶ G. M. *ins. eva*. ⁷ G. M. *'ntyapratyaya uktam*. ⁸ G. M. *-ha itī sam-*. ⁹ B. O. *om.*

4. *apiṣabdhāḥ sīnhāvalokanena 'thā¹ "dāv uttare vibhāge (iii.1) ity atra vibhāgapadam² anvādicati: so 'yam pragraho vibhāga itiparo bhavati. yathā: ³ ubhe iti. itipabdhāḥ paro yasmād asāv itiparah.*

¹ G. M. *-gam*. ² G. M. *ins. devate iti*.

The commentator adds the limitation "if long in *pada*-text," the final *ā* is universally *pragraha*; referring, in justification, to the cases treated of above, in rule iii.14, of an *u* irregularly lengthened in *samhitā*. His examples are *hanū vā ete yajñasya* (vi.2.11³: W. B. O. omit the last word), *vāsantikāḥ rṭā gukraḥ ca* (iv.4.11¹: W. B. O. omit after *rṭā*), and *harinasya bāhū upastutām janima tat te arvan* (iv.2.8¹: G. M. omit the last four words; the others, the first word).

ओकारो ऽसाक्षितो ऽकारव्यञ्जनपरः ॥ ६ ॥

6. Also an *o* which is not the product of euphonic combination, if followed by *a* or a consonant.

Of words exhibiting in *pada*-text, as well as in *samhitā*, a final *o*, there are (apart from the theme *go*, which occurs only as first member of a compound, and therefore, by rule 2 of this chapter, does not require to be regarded in the determination of *pragrahas*) two classes, the one composed of vocatives from themes in *u*, the other of words whose final *a* or *ā* is combined with the particle *u*. The present rule deals, in general, with the former class; the one next following, with the latter class. The right of the vocatives in *o* to be treated as *pragrahas* is a very dubious one, and is not unequivocally supported by the *Prātiśākhya*; for to say that such words are *pragraha* before *a* or a consonant is not to distinguish them perceptibly from the euphonic *o* which comes from a final *as*; since this also is not capable of combination with a consonant, and does not necessarily absorb a following initial *a*. The only instances in which a vocative in *o* exhibits a *pragraha* character are the three which are cited under the next rule (i.4.27: v.7.2⁴: vi.5.8³); the cases in which it is regularly changed to *av* before other vowels than *a* are much more numerous: namely, before *ā*, at i.4.39: ii.2.12⁴; 6.11¹: vi.4.3³; before *i*, at ii.2.12⁸; before *u*, at i.2.13² twice; 6.12²: iii.2.10¹; before *e*, at ii.4.12³. I have noted but two cases in the text where such an *o* stands before initial *a* without absorbing it; they are found at i.3.8¹, 14⁷. And there are the same

5. *ākārah padāntaḥ sarvatra pragraho bhavati: padasamaye vartamānaḥ. yathā: hanū-----: vās-----: har----- padasamaye vartamāna iti kim: sātānāmithāmākṣhāḍ' (iii.14) ity ādi.*

¹ G. M. omit after *mithā*.

6. *asāmhitā okāro 'kāroparo vā' vyañjanaparo vā pragrahaḥ syāt. yathā: vād-----: vish----- asāmhitā iti kim: so-----: 'pra----- evampara iti kim: vish----- samhitānimittāḥ sāmhitāḥ: na sāmhitō 'sāmhitāḥ: akāraḥ ca vyañjanam cā 'kāravyañjane: te pare yasmāt sa tatho 'ktaḥ.*

¹ G. M. om. ⁽²⁾ W. B. O. om.

number of cases—namely, at ii.5.12⁵ and vi.4.3⁴—in which it causes the elision of a following *a*.

The commentator's citations in illustration of the rule are *vad-mā hi sāno aśi* (i.3.14⁷), and *vishno havyaṇ rakshasva* (i.1.3). To show the necessity of the limitation *asānhitah*, he cites *so 'bravit* (ii.1.2¹ et al.), and *pra so agne* (iii.2.11¹: omitted, however, by W. B. O.), where *so* is the *sānhitā* reading for *saḥ*; and, to show that the prescribed quality belongs to the vowel only before *a* or a consonant (the *lacuna* of W. B. O. extends through this explanation), he gives us *vishnav e 'hi 'dam* (ii.4.12³).

For the teachings of the other Prāṭiśākhyas respecting this class of asserted *pragrahas*, see the note to Ath. Pr. i.81.

समरुद्यपित्पूर्वश्च ॥ ७ ॥

7. As also, when preceded by *s*, *m*, *h*, *d*, *th*, and *pit*.

The *anuvṛtti* of this rule is even more blind and equivocal than usual. Instead of bringing down either the subject or predicate of the one preceding, we are to bring down both, only with the exclusion of one of the modifications included in the former. The meaning is, that an original *o*, preceded as here specified, is *pragraha* even when followed by other vowels than *a*. The commentator is in error in saying that *ca* implies *okārah* from above; he should have said *okaro 'sānhitah*.

As above remarked, this rule chiefly concerns the class of *pragrahas* composed of words whose final vowel, *a* or *ā*, is combined with the particle *u*. Of these, *atho* is vastly the most numerous, occurring about two hundred and fifty times in the *Sānhitā*. Before *a* it is met with twenty times, always without occasioning elision; before other vowels, twenty-nine times, always uncombined. Along with it, *tatho* is had in view by the rule, as presenting a final *o* after *th*: it is found but once, in the passage cited by the commentator (see below). The only word showing *o* after *s* is *so*, found only in two passages, as noted below. After *m*, we have *o* both in *mo* (in two passages, once before *sh*, at i.8.3; the other is cited by the commentator) and in *imo*, which latter is found only before *a* (iv.3.13⁶), and so does not necessarily come within the purview of the rule. The other words of the class occur before consonants alone, and are, therefore, here made no account of: they are *o* (once, i.4.33), to

7. *pūrvoktaparanimittābhāve 'pi kāryavidhānārtham okāram vīcinashṭi: cakāra okāram anvādicati. sa: mā: ha: da: tha: pit: evampūrvō 'sānhitā okāro 'kārayaṇjanābhyām anyaparo 'pi pragraho bhavati. yathā: so..... mā..... upa..... indo..... tatho..... sa..... evampūrvā iti kim: 'gat..... asānhitā iti kim: pra.....*

(⁶) B. om.

(i.2.5² and vi.1.8³) and *uto* (five times), *upo* (four times), and *pro* (i.7.13³).

Of the remaining specifications of the rule, the *h* is made for but a single case of the exclamation *ho*, which the commentator quotes: *upahātāñ ho ity āha* (ii.6.7²); the *d* is for the vocative *indo*, which occurs twice: *indo indriydvatah* (i.4.27), and *indo ity āha* (vi.5.8³); the commentator quotes the latter passage; the *pī* is for the vocative *pīto*, only found once, as cited: *sa no mayobhaddh pīto ā vicasva* (v.7.24³; W. B. O. omit the first three words). These three, as was noted under the preceding rule, are the only instances which the Sanhitā affords of vocatives in *o* showing an uncombinable quality.

The commentator's explanation of the rule is "the *o* is here specially distinguished in order to the prescription of its quality even in the case of absence of the sequent determining circumstances before stated." As examples of words whose ending is combined with *u*, after the consonants specified, he gives *so evāi 'shāi 'tasya* (ii.2.9⁷; 5.5²), *mā bher mārō mo eshām* (iv.5.10¹), and *tatho eva 'ttare nir vapet* (iii.4.9⁷; W. B. O. omit after *uttare*). His counter-examples are *ṣatakrataḥ ud vañcam iḥa* (i.6.12³; G. M. omit *iḥa*), and *pra so agne* (iii.2.11¹); but G. M., which have given the latter passage under the preceding rule, here substitute for it *mā so asmāñ avahāya* (v.7.9¹); their separate application is manifest.

The treatment by the Prātiśākhya of words ending in *o* is awkward and bungling to a degree quite rare or wholly unknown elsewhere in its rules. We should be justified in inferring from its statements that *o*, *to*, *uto*, *upo*, and *pro* were not regarded as *pragrahas* at all, nor the vocatives in *o* except under the conditions and in the places specified, and that (if the commentator's explanation of rule 4 is accepted) they are not written with *iti* in the *pada*-text: while, doubtless, in every *pada*-text of the Black Yajus, as in those of the other Vedas, each word is treated uniformly, whether it happen to exhibit its uncombinable quality in *sanhitā* or not. Through the rest of the chapter, it will be noticed, the words mentioned are defined as *pragrahas*, without regard to the circumstances in which they may stand in the text.

अथैकारेकारौ ॥ ८ ॥

8. Now follow cases of *e* and *i*.

This is a heading for the remainder of the chapter, excluding all other vowels than final *e* and *i* from the action of its rules. The words exhibiting such finals are, of course, mainly duals, and are by the other treatises simply defined as such, with immense saving of trouble.

8. *athe 'ty ayam adhikārah: ekārekārāu pragrahatvena vidhiyate' ity etad' adhikṛtaṁ veditavyam.*

¹ G. M. *ekāra ikārah*. ² W. O. *-yate*; B. *-yayate*; G. M. *viśishyata*. ³ G. M. om.

अस्मे ॥ १ ॥

9. *Asme* is *pragraha*.

The example cited by the commentator is, according to W. B. O., *asme te bandhuh* (i.2.7); according to G. M., *sampatte gor asme candrāni* (also i.2.7). Neither exhibits in *samhitā* the *pragraha* quality of the word, as is done at i.7.13² and elsewhere: *asme* is not uncommon in the *Sanhitā*, occurring twenty-nine times.

वे इत्यनिग्यान्तः ॥ १० ॥

10. Also *ve*, when not the final member of a separable compound.

The office of the word *iti* in this rule is differently explained by the two versions of the commentary: W. B. O. say that it indicates the quality of a separable cited word (they mean, doubtless, of an inseparable); G. M., that it indicates *pragraha* quality. Each interpretation is as good, and as worthless, as the other. The commentary is not infrequently at much pains to put some special, even wonderful, significance into *iti* when found in a rule; and generally with as little acceptable result as here.

The pronoun *ve* occurs seven times in the *Sanhitā* (at i.3.14²; 4.46¹; iii.1.11²; 5.10¹; iv.2.7²; 6.5⁴; vi.1.8⁵), exhibiting its *pragraha*-quality in *samhitā* only once (at iv.2.7²). The commentator's instance is *ve kratum api* (iii.5.10¹; G. M. omit *api*); and his counter-instance, to show the necessity of the restriction imposed in the rule, is *anāgāstve adititve turāśah* (ii.1.11⁶; G. M. omit *turāśah*), where the *padu*-text reads *anāgāh-ve* : *aditi-ve*.

देवते उभे भागधे उर्ध्वे विशाखे शृङ्गे हने मेथेतृषोतृष्ये कनी-
निके यार्थे शिवे चोत्तमे द्वा उत्तरे शिप्रे रथं तरे वत्सरस्य द्वेपे वि-
द्वेपे विषु द्वेपे स दोह विधाने अधिषवणे अहोरात्रे धृतव्रते स्तुत-

9. *asme ity asmin' grahane 'ntyasvaraḥ pragraho bhavati. yathā: asme.....*

¹ G. M. *etasmīn*.

10. *itiṣabda inḡyagrahaṇatvam' dyotayati: aninḡyāntas tve ity eṣa ṣabdaḥ pragraho bhavati. yathā: tve..... aninḡyānta iti kim: anā----- inḡyasyā 'nta inḡyāntaḥ: ne 'inḡyānto 'ninḡyāntaḥ.*

¹ G. M. *pragrahatvam*. T. W. B. O. write *inḡy-* throughout.

शस्त्रेऽक्सामेऽत्रेऽर्पितेऽवतेऽपूर्तेऽप्रतेऽविधृतेऽनृतेऽअहिदे-
वदुतेऽपूर्वजेऽकृणुध्वंसदने ॥ ११ ॥

11. Also *devate*, *ubhe*, *bhāgadhe*, *ūrdhve*, *viçākhe*, *çrūge*, *ene*, *medhye*, *trunc*, *trdye*, *kaninike*, *pārçve*, *çive*, *co 'ttame*, *evo 'ttare*, *çipre*, *rāthamtare*, *vatsarasya rūpe*, *virūpe*, *vishurūpe*, *sadohavirdhāne*, *adhishavane*, *ahorātre*, *dhr̥tavr̥ate*, *stuta-çastre*, *rksāme*, *akte*, *arpite*, *rāivate*, *pūrte*, *pratte*, *vidhr̥te*, *anr̥te*, *achidre*, *bahule*, *pūrvaje*, *kṛṇudhvañ sadane*.

For the *pragrahas* catalogued in this rule—all of them dual cases of feminines and neuters—the commentator quotes illustrative passages as follows. For *devate*, *devate samr̥ddhyāi mātram* (ii.1.9²: the last word in G. M. only). For *ubhe*, G. M. have *achidre bahule ubhe: vyacasvatī sañvasāthām* (iv.1.3²); but W. B. O., blunderingly, *ime eva rasenā 'nakti* (vi.3.11³: B. O. have *ubhe* for *ime*): the word occurs also in other passages. For *bhāgadhe*, *bhāgadhe bhāgadhā asmāi* (ii.5.6⁶): also in the preceding division of the same *anuc̥ka*, and at v.5.9². As counter-example, to show that *dhe* (itself a *pada*, *bhāga-dhe*) would not have answered the purpose alone, we have *agna udadhe* (v.5.9¹: *pada*-text, *uda-dhe*). For *ūrdhve*, *ūrdhve samidhāv ā dadhātī* (ii.6.6³ and vi.2.1⁶). For *viçākhe*, *viçākhe nakshatram* (iv.4.10²): and as counter-example, to show the necessity of including the *vi* (of *vi-çākhe*), we have *tasmint sahasraçākhe*, stated to be found "in the text of another school." About a score of such alleged citations from "another text," assumed to have been had in view by the authors of the *Prātiçākhyā* in constructing their rules, are given in various parts of the commentary (five of them in the comment upon this rule): they will be put together, and their bearing discussed, in an additional note at the end of the work. For *çrūge*, *antarā çrūge tam devatāh* (vi.2.8⁴: only G. M. have *devatāh*): the word also occurs at i.2.14⁷. The next two words, *ene* and *medhye*, occur in the same passage, *medhye evāi 'ne kurōti* (vi.2.9¹), which the comment quotes, in W. O. giving *medhye* last, after the rest, by way of justifying the order in which the two words stand in the rule: but B. G. M. read the whole passage as it stands in the text, and G. M. make the rule read correspondingly *medhye ene* (T. has, like the others, *ene medhye*). *Ene* is also found in one or

11. *etāni padāni pragrahasamjñāni' syuḥ². yathā: dev-
.....: achid-.....: bhāg-.....: bhāge³ iti kim: agna-.....: ār-
.....: viç-.....: vī⁴ 'ti kim: tas-.....: iti çākḥantare⁵: ant-.....:
ev-.....: me-.....: asam-.....: sam-.....: yad-.....: pār-.....:
pit-.....: vik-.....: ce⁶ 'ti kim: sam-.....: tatho-.....: eve⁷ 'ti
kim: nāi-.....: pit-.....: yad-.....: samv-.....: sam-.....:
vish-.....: vatsarasyavivishv⁸ iti kim: arā-.....: 'rāpaçabdasya*

two other passages (iv.6.24; vi.2.9¹ again; 3.9⁶). For *trane*, *asam-trane hi hanū atho khalu* (vi.2.11³: only G. M. have the last two words). For *trāye*, *samtrāye dhṛtyāi* (vi.2.11³). For *kaninike*, *yad atirātrāu kaninike agnishtomāu yat* (vii.2.9¹: W. B. O. begin at *kan-*): the same word occurs twice more in the next division. For *pārgve*, *pārgve parahsamānah* (vii.3.10³): it is found a second time in the same division. For *give*, *pitarah somyāsah give no dyāvāprthivī* (iv.6.6⁴: W. B. O. begin at *give*). For *co'ttame*, *vikarṇm co'ttame upa dadhāti* (v.3.7³: only G. M. have the last two words): and, to show the necessity of the *ca*, *samvatsaraṁ saṁpādya'ttame māsi* (vii.5.3¹). For *eco'ttare*, *tatho evo'ttare nirvapet* (iii.4.9⁷): and, to show why *eca* had to be included in the rule, *nāi'ti shodacy uttare tena* (vii.1.4³: only G. M. have *tena*). For *gipre*, *pītvā gipre acepayah* (i.4.30: W. B. O. begin with *gipre*). For *rathamtare*, *yad brhadrathanitare anvarjeyuh* (vii.5.3²: only G. M. have *yad*): the same compound occurs in several places elsewhere. For *vatsarasya rūpe*, *samvatsarasya rūpe āpnuvanti* (vii.5.1⁴). For *virāpe*, *samanasā virāpe dhāpayete* (iv.1.10⁴; 6.5²; 7.12³). For *vishurāpe*, *vishurāpe ahanī dyāvurivā'si* (iv.1.11²: W. B. O. stop with *ahanī*). The necessity of including in the rule, besides the *pada rūpe*, the words *vatsarasya*, *vishu* (of *vishu-rāpe*), and *vī* (of *vī-rāpe*) is proved by the citation of *arākshitam dṛṣṭa ā rūpe annam* (iv.3.13²), where *rāpe* is locative: and the commentary adds the remark (wanting, however, in the South-Indian MSS.), "the separate specification of the word *rāpa* is to be looked upon as for the sake of distinct enunciation." For *sadohavirdhāne*, *sadohavirdhāne eva sam minoti* (ii.5.5⁶): the compound occurs twice more, at vi.2.6²; 5.1⁵. To justify the inclusion of *sadah*, the commentator quotes *uparavā havirdhāne khāyante* (vi.2.11¹); but the case appears to him one not to be so easily disposed of, and he enters into an elaborate discussion of it, which I defer to the end of this note, in order not to interrupt the connection. For *adhishavane*, *hanū adhishavane jīvā* (vi.2.11⁴): it is also found in the preceding division of the same section, and at iv.7.8¹. The *adhi* is justified by reference to *savanesavane bhi grhnāti* (vi.4.11⁴; 6.11³). For *ahorātre*, *ahorātre prā'viṣan* (i.5.9⁷): the word occurs not infrequently elsewhere. The passage *atirātre pagukāmasya* (vi.6.11⁴) is given to account for the inclusion of *ahah*; this implies, of course, that the Tāittiriya *pada*-text treats the word as a separable compound, *ahah-rātre*. For *dhṛtavrata*, *dyāvāprthivī dhṛtavrata āvinā devī* (i.8.12²: G. M. omit the last

pratiṣeṣhanam uccāraṇavispaṣṭārtham' drashtavyam': *sad- ----: sada iti kim: up- ----. nanu padagrahaṇeshu pa-*
dam gamyeta (i.50) *iti sāmartyād 'dhavirdhāne ity ekopada-*
syāi 'va kāryasiddhiḥ: sadahpadam vyartham. māi 'vam: pa-
dagrahaṇe sthālāntare'' bhinnarūpasya'' sambhāvanāyām' vi-
ṣeṣhanam sārthakam bhavati'': *bhinnarūpatevābhāve tu codyam*
etad bhavet''. *nanu tarhi devate iti padagrahaṇasya sthālāntare''*

word); and, to account for the inclusion of *dhṛta*, *yasya vrate pushtipatīḥ* (iii.1.11³). For *stutaḥgaṣṭre*, *stutaḥgaṣṭre evāi'tena duhe* (v.6.8⁶; G. M. omit the last word): it occurs again at vii.3.13. This time, resort is had to "another text" (*gākhāntaram*) for a passage to explain why the rule does not say simply *gaṣṭre*: it is *ūrdhve gaṣṭre pratishṭhite*. For *ṛksāme*, *ṛksāme vāi devebhyaḥ* (vi.1.3¹): the word is found twice in this division, and also at vi.5.9²; 6.7⁴. Here, again, a passage in "another text," *brahma sāme pratishṭhite* (G. M. omit the last word, and B. O. omit the *sā* of *sāme*), is appealed to in justification of the *ṛk*. For *akte*, *purāravā ghr̥tenā'kte vṛṣhanam dadhāthām* (i.3.7¹ and [except *purāravāḥ*] vi.3.5²: W. B. O. omit the first word, B. also the last). For *arpite*, *dyāvāprthivī bhuvaneśho arpite* (iv.7.13²: only G. M. have the first word). For *rāivate*, *gākvararāivate sāmāni* (i.8.13² and iv.4.2³): the same compound is found again at iv.3.2². For *pārte*, the different recensions give different examples: W. B. O. have *iṣṭāpārte sañ srjethām* (iv.7.13⁵); G. M., *iṣṭāpārte kṛnutāt* (v.7.7²): I have noted no other cases: for the treatment of the word in the *pada*-text see the note to iii. 6. For *pratte*, *pratte kāmam annādyam duhāte* (v.4.9²: G. M. omit the last word). For *vidhṛte*, again, W. B. O. have *vidhṛte sarvatoḥ* (vi.4.10³), and G. M. *tasman nāsikayā cakshuṣi vidhṛte samāni* (ii.3.8²), and the *vi* is justified by an alleged citation from "another text," *agnī-dhṛte* (G. M., however, omitting the *agni*, thus leaving it to be understood that the simple word *dhṛte* is found elsewhere not *pragraha*). For *ante*, *satyānte avapaṇyan* (v.6.1¹). For *achidre*, *achidre bahule ubhe* (iv.1.3²: only G. M. have *ubhe*), which answers also for *bahule*: it is the only passage containing either word. For *pūrvaje*, *pūrvaje pitarā navyasibhiḥ* (iv.1.11⁴: W. B. O. omit the last word): another passage beginning with the same word is the subject of rule 23 of this chapter. Once more a word, *prathamaje*, is cited from "another text," in order to explain why the rule does not say simply *je* (since the *pada*-text writes *pūrvaje*). For *kṛnudhvañ sadāne*, finally, we have the sole passage in which it occurs, *gīrbhiḥ kṛnudhvañ sadāne rtasya* (iv.1.11⁴: G. M. omit *rtasya*), with the counter-example *apāni teā sadāne sādāyāmi* (iv.3.1: G. M. omit the last word), to show the necessity of *kṛnudhvam*.

To return, now, to the long word *sadohavirdhāne*. The objection is raised, that its part *sadah* is unnecessary, and that it would

so ma.... *iti bhinnarūpatvād*¹³ *viśeṣaṇena bhavitavyam*: *tac ca nā'sti. ucyate*: *devate ity akhaṇḍapadasyaī 'va kāryavidhānād atra viśeṣaṇam na yujyate*: *akhaṇḍavidhānam*¹⁴ *iti katham pratiyate*: *te ity asya te mā patam* (iv.42) *ity ādinā prthakkarandā iti brāmah*: *nāi*¹⁵ *'vañ havirdhāne*¹⁶ *ity asyā*¹⁷ *'khaṇḍatvādyotakam*¹⁸ *kimcid apy*¹⁹ *asti yena sadahpadavāyarthyam ālambate*²⁰. *hanā*....: *adhī'ti kim*: *sav*....: *aho*....: *ahar iti kim*: *atī*....: *dyāv*....: *dhṛte 'ti kim*: *yasya*....: *stu*

have been sufficient to say *havirdhāne* simply; for rule i.50 teaches us that, in citations of *padas*, the cited *pada* alone is to be understood, not any collocation of words or letters phonetically equivalent with it: and *havirdhāne* is here a single *pada* (the compound being divided *sadaḥ-havirdhāne*, while its latter member, occurring by itself as a non-*pragraha*, is written *haviḥ-dhāne*, and so is a congeries of two *padas*). It is replied: not so; a distinctive addition is properly made to a cited *pada*, in case of its occurrence in a different form in another passage; though the objection would hold good, were it not for such occurrence in a different form. But this explanation is not suffered to pass without challenge. In that case, retorts the objector, a distinction ought to be added to *devate*, because it occurs elsewhere in a different form (made up of two independent words), as in *soma deva te matividāḥ* (iii.2.5^{2,3}); and no such addition is made. The answer is, that no distinction need here be applied to *devate*, because its treatment is defined as of an undivided word: and, if you ask how its indivisibility is established, we reply that rule 42, below, treats of *te* as a separate *pada* in the various situations in which it is *pragraha* [whence the inference is clear that it is here an inseparable part of the word *devate*]; while there is nothing whatever to show in like manner the indivisibility of *havirdhāne*, and so to prove the addition of *sadaḥ* superfluous. The implication is, that if the *pada dhāne* happened to be described elsewhere as *pragraha* after certain other *padas*, of which *haviḥ* was not one, then we could be sure that *havirdhāne* here meant a single undivided *pada*, and its mention by itself would be enough; while, as things are, one cannot be certain that its part *haviḥ* is not, like the *vi* and *vishu* of *virāpe* and *vishurāpe*, a distinctive addition.

अमीचक्षुषीकार्णोदिवताफल्गुनीमुष्टीधीनाभीवपाश्र-
पणीअरुनीज्ञन्मनीमुन्निनीसामनीविष्णवीरेक्षवीदर्वी-
द्यावापृथिवी ॥ १२ ॥

-----: *stute 'ti kim: ārdh----- iti śākhāntare: rks-----: rg iti kim: brah----- iti śākhāntare: pur-----: dyāv-----: śāke-----: isht-----: prat-----: vidh-----: vī'ti kim: agn- iti śākhāntare: "saty-----: ach-----: pārve-----: pārve 'ti kim: prath- iti śākhāntare: "gīr-----: kṛṇudhvam iti kim: apām-----*

¹ O. *praghyas*. ² G. M. *bhavantī*. ³ G. M. *bhāgadhe*. ⁴ G. M. *viśakhe*. ⁵ G. M. *raṇā*. ⁶ W. O. *vatsaraviv*. ⁷ G. M. om. ⁸ B. *paṣ vi*; W. O. *tha*. ⁹ G. M. om. ¹⁰ MSS. *sthāl*. ¹¹ W. *patvan*. ¹² B. G. M. om. ¹³ G. M. om. ¹⁴ B. *sthāl*. ¹⁵ W. B. O. *abh*. ¹⁶ B. O. *aditav*. ¹⁷ W. B. O. *mā*. ¹⁸ W. B. O. *sadaḥ*. ¹⁹ W. *asā*; B. *ā*; O. om. ²⁰ W. B. O. ins. *na*. ²¹ W. B. O. *tathā*. ²² B. *nibhyate*; O. *nibhyate*; G. M. *opadyate*. ⁽²³⁾ B. om.

12. Also *amī, cakshuṣhī, kārshnī, devatā phalgunī, muṣhī, dhī, nābhī, vapācraṇāni, ahaṇī, janmāni, sumnīni, sāmāni, vāishnavī, āikshavi, darvī, dyāvāprthivī*.

The illustrative passages cited under this rule are as follows. For *amī*, according to W. B. O., *amī vā idam abhāvam* (iii.3.7¹); but according to G. M., *amī tvā jahati* (iii.2.11²): I have noted elsewhere only vi.1.5⁴. For *cakshuṣhī*, *cakshuṣhī vā ete yajñasya* (ii.6.2¹ et al.: G. M. omit *yajñasya*): the word occurs about a dozen times. For *kārshnī*, *kārshnī upānahāv upa muñcate* (v.4.4⁴; 6.6¹: G. M. omit the last two words). For *phalgunī*, *pitaro devatā phalgunī nakshatram* (iv.4.10¹): again in the next division of the same section. To show the necessity of including *devatā* in the rule, is given *yad dvitīyaṁ sā phalgunī* (ii.1.2²). For *muṣhī*, *muṣhī karoti vācam* (v.2.1⁷ and vi.1.4³: G. M. omit *vācam*). For *dhī*, *pradhī tāv ukthya madhye* (vii.4.11²: G. M. omit *madhye*). For *nābhī*, *rajatanābhī vāicradevāu* (v.5.24). For *vapācraṇāni*, *vapācraṇāni pra harati* (vi.3.9⁶): it occurs also in the fourth division of the same section. As counter-example, to explain the presence of *vapā* in the rule, is given, "from another text," the compound *paçucraṇāni* (or, as G. M. read, *bhasma-craṇāni*): our Sanhitā has *paçucraṇānam* at iii.1.3². For *ahaṇī*, *ahaṇī dyāvur itā 'si* (iv.1.11³). For *janmāni*, *ubhe nī pāsi janmāni* (i.4.22). For *sumnīni*, *sumnāya sumnīni* (i.1.13³). For *sāmāni*, *sāmāni pratishṭhityādi* (iv.4.2³): also at i.8.13². For *vāishnavī*, *valagahanāu vāishnavī bhānn asi* (i.3.2²: only G. M. have the last two words). For *āikshavi*, *āikshavi tiragci* (vi.2.1⁸ twice). For *darvī*, *darvī grīnisha āsani* (ii.2.12⁷ and iv.4.4⁶). For *dyāvāprthivī*, *dyāvāprthivī eva svena* (ii.1.4⁷): the word is frequently found elsewhere. The commentator gives us here also a counter-example, *mahī dyāvuh prthivī ca nah* (iii.3.10² et al.: G. M. omit *ca nah*), as if the inclusion of *dyāvā* required justification: but, in ordinary Vedic usage (I have omitted to inform myself in season respecting that of the Tāittiriya *pada*-text), *dyāvāprthivī* is inseparable, and therefore itself a single *pada*.

पूर्व ॥ १३ ॥

13. As also, the preceding word.

That is to say (by the application of rule i.58), the word preceding the last one mentioned in the rule next above, or *dyāvāprthivī*.

12.¹ *etāni padāni pragrahasamjñāni syuh². yathā:*
amī.....: caksh.....: kārsh.....: pit.....: devate 'ti kim:
yad.....: muṣh.....: pra.....: raj.....: vap.....: vape 'ti
kim: paç.....: itī çākhāntare: ah.....: ubhe.....: sum.....:
sām.....: val.....: āiksh.....: dar.....: dyāv.....: dyāve
'ti kim: mahī.....

¹ G. M. ins. *iti*. ² G. M. O. *bhavantī*. ³ W. B. O. om.

vi. The examples given are *yāvati dyāvāprthivī mahitvā* (iii.2.6¹), and *āvinne dyāvāprthivī* (i.8.12²: G. M. invert the order of the two citations): I have noted only two other cases of the application of the rule, at ii.2.12⁶; 6.7⁵.

न रुन्धे नित्यम् ॥ १४ ॥

14. But not *rundhe*, in any case.

The case intended to be excluded is quoted by the commentator: *paṣān evā 'va rundhe dyāvāprthivī gacha svāhā* (vi.4.1³: W. B. O. omit the first three words and the last). The specification *nityam*, 'constantly, in all cases,' is intended to exclude also the operation of any other rule under which *rundhe* might chance to fall: for example, in *rundhe yadā sahasram* (ii.1.5²), where, as preceding *yadā*, it would otherwise be *pragraha* by rule 38 of this chapter. I have noted no other case.

हुरीसहुरीसहृतीकल्पयन्तीआपृषतीआहुती ॥ १५ ॥

15. Also *hari*, *sahuri*, *sahūti*, *kalpayanti*, *ā prshati*, and *āhuti* are *pragraha*.

The cited examples are as follows. For *hari*, *hari te yuñjā prshati abhātām* (iv.6.9⁴: G. M. omit the last two words): it occurs in toward a dozen other passages. For *sahuri*, *sahuri saparyāt* (iv.2.11¹); and the counter-example, to show the necessity of the *sa*, *tam āhuri hwayante* (but O. reads *tām*, B. *hwayate*, and G. M. *ahuri vācayati*), claimed to be found "in another text." This would imply, of course, that the *pada*-text reads *sa-huri*—as is in fact the case. For *sahūti*, *sahūti vanatām girah* (ii.3.14¹); and, as counter-example, for the same purpose as the last, *hāti punar juhōti* (but G. M. read *manur* for *punar*), also from "another text." For *kalpayanti*, *adhvaram kalpayanti ārdhvam yajñam* (i.2.13²: G. M. omit the first word, and W. B. O. the last): another case is found at vi.2.9³. For *ā prshati*, the passage already quoted for *hari*, *yuñjā prshati abhātām* (iv.6.9⁴); and, to justify the *ā*, the counter-example *prshati sthālaprshati* (v.6.12). For *āhuti*, *purodāgam ete āhuti juhōti* (i.5.2³⁻⁴: G. M. omit the first two words, W. B. O. the last): nearly the same phrase occurs again at

13. *cakāreṇā 'nvādishtadyāvāprthivī ity asmāt pārvo 'pī 'kāra ekāro' vā padāntaḥ pragraho bhavati. yathā: yāv----- āv-----*

¹ G. M. *etasmāt*. ² G. M. put before *ikārah*.

14. *rundhe ity antyasvaro' dyāvāprthivī ity etasmāt pārvo 'pī na pragraho bhavati: paṣān----- nityaḥ padāḥ prāptyantara-nishedhārthaḥ: rundhe-----: vidādī* (iv.38) *prāptiḥ*.

¹ W. *antass-*; B. O. *antaḥ sv-*. ² O. *vidādvādv itī*.

i.5.4⁴. To account for the *ā* in this word, G. M. simply cite *huti* as found in "another text:" but W. B. O. give the phrase *huti tasmād evāh* (but W. O. read *hāti*, and B. *dhāti*: W. also has *vivā iti* instead of *evā iti*).

पूर्वश्च ॥ १६ ॥

16. As also, the preceding word.

Namely *ete*, occurring before *āhuti* in the passage already quoted: *purodācam ete āhuti* (i.5.2²: W. B. O. here omit the first word).

वाससीतपसीरोदसी ॥ १७ ॥

17. Also *vāsasī*, *tapasī*, and *rodasī*.

The examples are: *vāsasī iva vivasānāu* (i.5.10¹: the word is also found at i.8.18); *sākshād eva dikshātapasī ava rundhe* (vi.1.1²: the compound occurs again in the same division: only G. M. have the first two words); and *ime vāi rodasī tayoh* (v.1.5⁴: G. M. have dropped out *vāi*): the word is not rarely met with elsewhere.

परश्च ॥ १८ ॥

18. As also, the following word.

The passage contemplated by the rule is, as cited in the comment, *anv indrañ rodasī vāvaçāne* (i.7.13¹): there is, I believe, no other falling under it.

15. ----- ¹ *eteshv antyasvarah² pragrahaḥ syāt³: harī-----*
sah-----: se 'ti kim: tam----- iti gākhāntare: sah-----: se 'ti
kim: hāti----- iti gākhāntare: adhva-----: yuñjā-----: 'e 'ti
kim: prśh-----: puro-----: e 'ti kim: huti----- iti gākhāntare.

¹ G. M. *ins. ity.* ² B. O. *antyaḥ sv.* ³ G. M. *bhavatī.* ⁴ G. M. *ākāreṇa.*

16. *cakārānvādeçād¹ āhuti ity etasmāt pārva² ikāra ekāro vā padāntaḥ³ pragraho bhavati. yathā: pur-----*

¹ G. M. *-anvādishta.* ² G. M. *om.*

17. ¹ ----- *ity etāni pragrahasamjñāni bhavanti.* *yathā:*
vās-----: sāk-----: ime-----

¹ G. M. *eshv antyasvarah² pragraho bhavati.*

18. *cakārānvādishtarodasi¹ ity etasmāt para² ikāra ekāro vā padāntaḥ³ pragraho bhavati. yathā: anv-----*

¹ G. M. *-ād rod ro-.* ² G. M. *om.*

व्यचस्वतीभरिष्यन्तीनःपृथिवी ॥ १९ ॥

19. Also *vyacasvatī*, *bharishyanti*, and *naḥ pṛthivī*.

The examples are: *vyacasvatī sam vasāthām* (iv.1.3²); *agnim antar bharishyanti jyotishmantam* (iv.1.3²: G. alone has the last word); and *dyāvā naḥ pṛthivī imān sidhram* (iv.1.11⁴). The needed counter-example for the last is supplied by *rejate agne pṛthivī makhebhyaḥ* (iv.1.11⁴).

येअप्रथेतामुर्वीतिअस्ययंकन्दसीहिन्दस्वतीतिआचरन्तीअ- न्तरैतासु ॥ २० ॥

20. Also in the verses beginning *ye aprathetām*, *urvī*, *te asya*, *yam krandasī*, *chandasvatī*, *te ācarantī*, and *antarā*.

The commentator cites only the beginning of each verse, as a word with *pragraha* final occurs at or near the beginning in every case. Thus: *ye aprathetām amitebhiḥ* (iv.7.15⁶: there are three other cases of *pragrahas* in the verse): with the counter-example *ye te panthānaḥ* (vii.5.24), to show that *ye* alone would not have defined the verse; *urvī rodasī varivah* (iv.7.15⁶: G. M. omit the last word: three cases, besides *rodasī*, already disposed of by rule 17); *te asya yoshane* (iv.1.8²: one more case: the *te* is therefore made no account of in rule 42, below): with the counter-example *te vardhanta svatavaso mahiteand* (iv.1.11³), to show the necessity of *asya*; *yam krandasī avasā* (iv.1.8²: contains two other cases): and, as counter-example, for a like purpose, *yam agne pṛtsu martyam* (i.3.13²); *chandusvatī ushasā* (iv.3.11¹: it contains seven cases); *te ācarantī* (iv.6.6²: also seven cases): with *te no arcanto havanagrutah* (i.7.8²) as counter-example, to prove that *te* alone would not be enough; and, finally, *antarā mītrāvaruṇā carantī* (v.1.11²: with four cases).

नोपस्ये ॥ २१ ॥

21. But not *upasthe*.

19. 'eteshv' antyāsvarah' padāntah' pragraho bhavati. yathā: vyac-.....: agn-.....: dyāvā.....: na iti kim; rej-.....

¹ G. eshv. ² B. -tyah sv-. ³ G. om. ⁴ M. om.

20. etāsv ṛkshv ikāra ekāro' vā padāntah' pragraho bhavati. yathā: ye.....: aprathetām iti kim: ye te.....: urvī.....: te.....: asye 'ti kim: te 'v-.....: yam.....: krandasī iti kim: yam.....: chand-.....: te ā-.....: ācarantī iti kim: te no.....: ant-.....

¹ G. M. put before *ikāro*.

That is to say, *upasthe* is exempted from the action of the preceding rule: it occurs but once in the verses forming the subject of that rule, namely in *mâte 'va putram bibhrtām upasthe* (in the verse beginning *te ācaranti*, iv.6.6²: W. B. O. give only the last two words). To show that *sthe* would not have sufficiently defined the exception (*upa-sthe*), the commentator quotes *ye pratishthe* (*prati-sthe*) *abhavatām* (from the verse beginning with *urvi*, iv.7.15⁶).

इरावतीप्रभृत्या दाधार ॥ २२ ॥

22. Also in the passage beginning with *irāvati*, and ending with *dādāhā*.

The passage in question is found at i.2.13², and contains six *pragrahas*, whereof one, *rodasi*, needs no further provision than was made in rule 17, above; it also contains a word in *e*, *manave*, which is not *pragraha*, being excepted by rule 54. The commentator quotes its beginning, *irāvati dhenumati hi bhātām*.

पूर्वजेप्रभृत्यायम् ॥ २३ ॥

23. And in the passage beginning with *pūrvaje* and ending with *ayam*.

Of this passage, found at ii.6.7⁵, the commentator quotes the first four words. In order to the better understanding of the following discussion, I set it down here in full, along with the word that precedes it: *hwayate pūrvaje rtāvari ity āha pūrvaje hy ete rtāvari devī devoputre ity āha devī hy ete devoputre upahāto 'yam*. It contains ten *pragraha* endings, of which, however, two (*pūrvaje*) fall under rule 11, above. The word *ā*, 'as far as,' in the rule, is declared here to exclude the two limiting words mentioned (com-

21. *etāsv ṛkshā 'pasthe ity antyasvarah' padāntah' pragraho na bhavati. yathā: māt----- upe 'ti kim: ye-----*

¹ B. O. *antah sv.* ² G. M. om.

22. *irāvati-prabhṛti 'rāvati iti' śabdām ārabhyā "dādāhā dādāhā-śabdaparyantam" ikāra ekāro vā padāntah' pragraho bhavati. yathā: irā-----*

¹ G. M. om. ² W. B. O. *paryantam*.

23. *pūrvajeprobhṛtyayamparyantam' ikāra ekāro vā padāntah' pragraho bhavati. yathā: pūr----- āpādam' madyādāyam vartate. nanu pūr----- ity ārabhyā 'yam----- ity etatparyantam sthālam' etatsūtravishayaḥ' kim na syāt. ucyate: bhavatkaksha upabandhāntah'pātivāt' kṛṇudhvāñ sadane (iv.11) iti grahanasya' vāiyarthyaṁ 'syāt: tan' mā bhād iti: tasmād*

pare Pāṇini ii.1.13)—an arbitrary restriction, directly opposed by the analogy of the preceding rule; intended, doubtless, to relieve the treatise of the reproach of declaring the word *pūrvaje* a *pragraha* by two separate rules; but this is a small gain, since the same word occurs a second time in the passage, and cannot there be reached by any such device.

A protracted, not to say tedious, discussion now arises, respecting the sufficiency and propriety of the rule as stated. The first objection is: how do we know that the passage had in view by the rule is not that which begins with *pūrvaje pitarā* (iv.1.11⁴) and ends with *ayam purobhuvāḥ* (iv.3.2¹: B. O. omit *bhuvāḥ*). Because, it is answered, the special citation (in rule 11) of *kr̥ṇudhvāṇ sadane* (iv.1.11⁴), which occurs within the limits mentioned, would in that case be rendered superfluous. Objection second: the word *pūrvaje*, at any rate, is useless, it having been already made *pragraha* by rule 11; the rule should read "beginning with *vari*" (the concluding *pada* of the separable compound *ṛta-vari*). This, too, is repelled: the rule reads as it stands because *vari* occurs twice in the passage, and the question would arise where the defined limit should be understood to be: moreover, as we are taught (i.25) in case of doubt to take the nearest, we should have to assume as intended the latter of the two, as being nearer to the other specified limit: in which case we should arrive at the untoward result that the *pragraha* character of the first *vari* would not be established at all. But now the objector triumphantly retorts, that there are also two instances of *pūrvaje*, and a like doubt as in the supposition last made would arise as to the identity of the one cited, and a like untoward result as was pointed out in connection therewith. Not so, is the defense: *pūrvaje* is not design-

etat sthalam etatsūtravishayo na bhavati. nanv atra pūrvajegrahaṇam anarthakam: pūrvajekr̥ṇudhvāṇsadane (iv.11) *iti tatrāi 'eo 'ktatvāt: "kim tu" variprabhṛty' etāvatāi 'vā 'lam. ne 'ti brūmah: varigrahaṇadvayasambhavāt: kutra vā 'vadhiniyamatvena¹² svikāra¹³ iti saṁdehaḥ syāt: kim ca: āsannaṁ saṁdehe* (i.25) *iti vacanād uttarāvadhisaṁnikṛṣṭo¹⁴ deitivyavarigabda eva svikartavyaḥ: tathā sati pūrvavarigabdasya¹⁵ pragrahatecām na syāt: tac cā 'nisṭam. nanu bhavanmāte 'pi pūrvajadvayasambhavāt kutra vā grahaṇam iti saṁdehaḥ samānah: kim ca: yuktyuktam¹⁶ anisṭam ca¹⁷ samānam¹⁸. mātī 'vam: pūrvaje iti padam atra kāryabhāktvena¹⁹ no 'cyate²⁰ yena pāunaruktyam bhavet: kim tu pūrvaj cā 'sau jepadav ca pūrvaje: etatprabhṛti 'ty²¹ upalakshakatvena²² 'cyate²³. nanu tarhy²⁴ upahūta iti padam atikramyā 'yam ity avadhivena kimartham²⁵ ucyate: upahūta iti padānām bāhulye²⁶ 'py āsannaṁ saṁdehe* (i.25) *iti vacanād prāthamikasyāi 'va grahaṇasiddhiḥ²⁷. mātī 'vam²⁸: upahūta iti padagrahaṇe²⁹ tatra³⁰ gāuravadoshah:*

nated by the rule as a word possessing the defined quality—which would indeed be a superfluous repetition (in view of rule 11); but it means 'the former *je* of the two,' and is given merely as a convenient limit to count forward from! Again: why, at the end of the passage, is *ayam* pitched upon as limit, to the neglect of *upa-hātah*; for, though this word is found several times in the immediate sequel, yet, in virtue of the principle already appealed to, "in case of doubt, take the nearest" (125), its first occurrence would be distinctly enough the one intended. This also is disallowed: to quote the whole compound word *upahātah* (*pada*-text, *upa-hātah*) would be to incur the charge of excess; and as for *upa* by itself, the first member of the compound, though it be a *pada*, its *pada* quality is of secondary rank, while that of *ayam* is primary [the latter being a complete word, but the former only a somewhat artificially separated portion of such]; hence, on the principle "where there is a primary, a secondary is not in place," it was proper to cite *ayam*. The answer, however, suggests the further objection that, on the same principle, the first limit is unsuitable [*je* being also a fragment of a word; and its predecessor *hwayate* should have been taken instead]. That cannot be made good, is the reply; for there is a want of suitability in the primary word suggested: if you take the primary *hwayate*, then, on the supposition that the definition of limits is to be understood inclusively [*ā* being susceptible of both an inclusive and an exclusive interpretation], this word [as it ends in *e*] will appear to be cited as a *pragraha*: which is wrong. And if you urge that rule 54 of the chapter annuls this false inference, we reply that, on the principle "not to touch filth is far better than to wash it off," it is better not

*upe 'ty etāvanmātrasyā "dibhātasyā" 'ñcasya²¹ padatvaṁ gāu-
nam: ayam ity asya tu²² mukhyam: mukhye sambhavati na gau-
nam iti nyāyād ayam iti yuktam grahaṇam. nanv etenāi 'va
nyāyena "dyāvadhē²³ anupapannatā. nā 'yam pakshaḥ: mu-
khyasambhavābhāvāt²⁴: tathā hi: hwayata iti mukhye svikṛte
'bhividhinyāyena tasyā 'pi grahaṇam²⁵ syāt: tāt cā 'nishtam:
ate samānapade (iv.54) iti vacanād etad²⁶ anishtam na²⁷ bha-
vati 'ti²⁸ cet: prakṣātanād dhī paṅkasya dārād asparṇanam
varam iti nyāyād dhwayata ity uccārya tasya nishedhakathanād
api tadannuccāraṇam eva ramanīyam²⁹. iti mukhyasambhavā-
bhāvo 'vasta³⁰ eva: tasmād asmint sūtre 'nupapattileṇa nā 'sti.*

¹ W. O. -ti āyam-; B. -ti āyam-. ² B. O. G. M. om. ³ G. M. ins. idam. ⁴ B. O. om. ⁵ B. O. sūtr-; G. M. -yath-. ⁶ W. ins. pūrvaje. ⁷ W. pragrahasya. ⁸ W. B. O. om. ⁹ G. M. om. ¹⁰ B. om. ¹¹ W. B. pūrvāri-. ¹² W. vidhi-; G. M. -dhritvena. ¹³ G. M. svikṛiyata. ¹⁴ G. M. uktāv-. ¹⁵ G. M. ins. ca. ¹⁶ W. O. yuktivyuktam; G. M. yad uktam. ¹⁷ G. M. om. ¹⁸ B. O. tulyam. ¹⁹ B. O. -tee. ²⁰ B. om. ²¹ G. M. om. ²² G. M. -kṣhanat-. ²³ G. M. om. ²⁴ G. M. kim. ²⁵ B. om. ²⁶ G. M. ins. iti. ²⁷ G. M. -dheh. ²⁸ G. M. om. pada. ²⁹ G. M. sūtra. ³⁰ W. G. M. om. ³¹ W. 'ñcābdasya; G. M. 'ñgyāy-. ³² G. M. om. ³³ B. O. -dyapadasya. ³⁴ O. G. M. -khye r-. ³⁵ G. M. pragrahatevam. ³⁶ G. M. tad. ³⁷ G. M. om. ³⁸ G. M. om. ³⁹ W. svar-; B. O. varam. ⁴⁰ G. M. tadav-.

to quote *hwayate* at all than to quote it and then make it the subject of an exception. The case, then, is one where no suitable primary word is to be found; and not the slightest charge of impropriety can be maintained against the rule as given.

Both parties to this controversy are about equally open to the charge of hair-splitting absurdity; but the objector must be acknowledged to have the right of it so far as this—that the rule is really ambiguous, considering the presence of the two words *pārçaje*. That *pārçaje*, as used in it, means 'the former *je*,' I do not at all believe.

इमे गर्भमुपैव रसेनपरः ॥ २३ ॥

24. Also *ime*, when followed by *garbham*, *upa*, and *eva rasena*.

The passages referred to are: *yad ime garbham adadhātām* (iii.4.3²: G. M. omit the last word), *ime upāvartsyataḥ* (vi.1.3¹), and *ime eva rasena 'nakti* (vi.3.11³). Two counter-examples are given: one to show the necessity of *rasena* after *eva*, *ima eva smāti lokāḥ* (ii.4.10²), and one to show in general the need of specifying the situations in which *ime* is *pragraha*, *adhvartavyā vā ime devāḥ* (iii.2.2³).

क्रूरमापः सन्नूत्रं हज्जितेषु च ॥ २५ ॥

25. As also, in the sections beginning with *krūram*, *āpah*, *sajāḥ*, and *brahma ja*.

That is to say, *ime* in the sections specified is always *pragraha*, even when otherwise followed than by the words mentioned in the preceding rule. The commentator quotes the beginning words of each section, and a single example from each: thus, from the section *krūram iva vāi* (v.1.5: only G. M. have the last two words), *rodasyor ity āhe 'me vāi rodasī* (v.1.5⁴: the only case in the sec-

24. *ime ity antyasvaro garbhaḥ: upa: eva rasena: evamparaḥ padāntaḥ¹ pragrahaḥ syāt. yathā: yad..... ime..... ime..... rasene 'ti kim: ima..... evampara iti kim: adhv.....*

¹ G. M. om.

25. *ime iti caçabdo¹ 'nvādiçati: krūram: āpah: sajāḥ: brahma ja: 'eteshv anucākeṣhv ime ity antyasvaraḥ pārvoktaparānimit-tābhāve² 'pi pragraho bhavati. krū..... ity atra yathā: rod..... āpo..... ity atre 'me.....³ saj..... ity atra yathā: etaga..... brah..... ity atra yathā: na.....: je 'ti kim: brah..... ity atra traya..... ity asya⁴ pragrahatvam mā bhād iti.*

¹ G. M. put before *ime*. ⁽²⁾ W. jāñeṣhu. ³ G. M. om. para. ⁴ B. O. om. ⁵ B. O. G. M. om. ⁶ B. om.; G. M. atra.

tion: B. O. begin the citation at *ime*); from the section *āpo varuṇasya patnayah* (v.5.4: G. M. omit the last word), *ime ero 'pa dhatte* (v.5.4¹: there are two more cases in the following divisions); from the section *sajār abdaḥ* (v.6.4: G. M. omit the last word), *etapa ime aṇvā saṁvatsarah* (v.6.4¹: the only case: only G. M. have the first word); from the section *brahma jajñānam* (v.2.7), *na hi 'me yojushā 'ptum arhati* (v.2.7⁴: the only case: B. O. omit the last word). The last calls for a counter-example, to show the need of including in the rule the syllable after *brahma*: there is another section beginning *brahmavādino vadanty adbhīḥ* (ii.6.5: B. O. omit *adbhīḥ*), which contains an *ime* not *pragraha*: *traya ime lokāḥ* (ii.6.5²: only G. M. have *trayah*).

पूर्ण च ॥ २६ ॥

26. As also *pūrṇe*.

The *ca*, 'and,' in this rule merely brings down the heading of the last *anuvāka* named in the one preceding. In that *anuvāka*, *pūrṇe* is *pragraha*: to wit, in *pūrṇe upa dadhāti pūrṇe evāi 'nam* (v.2.7⁴); but not elsewhere, as for example in *yo vāi pūrṇa āśīncati* (vii.5.6¹).

दृढे ॥ २७ ॥

27. Also *dr̥dhe* is *pragraha*.

The restrictions imposed in previous rules no longer hold good: *dr̥dhe* is *pragraha* wherever met with. The example given is *yena dyāur ugrā pṛthivī ca dr̥dhe* (iv.1.8²). There is another case at iii.2.4².

ग्रीचक्रे पपगे ॥ २८ ॥

28. Also *ghnī* and *cakre*, when followed by *p*.

26. *caṣabdo brahmajajñānam ity anuvāḍipati: pūrṇe ity antya-svaro brahmajajñānam ity anuvāke pragraho bhavati. yathā¹: pūrṇe..... 'asminn anuvāka² iti kim: yo.....*

¹ B. O. G. M. om. ² B. O. *brahmaja*.

27. *dr̥dhe ity asminn¹ antyasvarah sarvatra² pragraho bhavati. yathā³: yena.....*

¹ B. O. om. ² B. O. om. ³ B. O. G. M. om.

28. *ghnī: cakre: ity¹ ete pade papare pragrahe² bhavataḥ. vār.....: cakre..... papare iti kim: yad.....: sam.....: ghnīcakre iti kim: pak.....: ye..... pakārah³ paro yābhyān te papare.*

¹ G. M. om. ² G. M. *-gṛhye*. ³ W. *paḥ*.

The examples are: *vārtraghnī pārāmāse* (ii.5.2⁵); *cakre prsthāni* (vi.6.8¹): I have noted no other cases. We have then two pairs of counter-examples, to show that these words are *pragraha* before *p* only, and only these words before *p*: the first pair are *yad virūpayā vārtraghnī syāt* (vi.1.6⁷) and *samidhāna cakre nicātam* (i.2.14²: only W. has *tam*); the second, *çakā bhāumī pāntrah* (v.5.18) and *yeshām içe paçupatīh* (iii.1.4¹⁻²).

न्वती ॥ २९ ॥

29. Also *nvati*.

Two examples are cited: *omanvati te 'smīn* (ii.6.9⁵: G. M. omit the last two words), and *vr̥dhanvati amāvāsyāyām* (ii.5.2⁵): also a counter-example, proving that *vati* alone would not have been sufficient: *karnakāvaty etayā* (v.4.7²).

पपरो न ॥ ३० ॥

30. But not when followed by *p*.

The case here excepted—the only one, so far as I have noticed—is *mūrdhanvati pūronuvākyā bhavati* (ii.6.2²: G. M. omit the last word).

समीची ॥ ३१ ॥

31. *Samīci* is *pragraha*.

For this word, G. M. cite *samīci retah siñcatah* (v.5.4²); B. O. cite *paçcāt samīci tābhīh* (v.2.3⁵); W. gives both passages. The word is met with a dozen times or more in the *Sanhitā*.

नपरो न ॥ ३२ ॥

29. *nvati ity antyasvarah¹ pragraho bhavati. yathā²: om----- vr̥dh----- nakāreṇa kim: karṇ-----*

¹ B. *antaḥ s-*; O. *antas-*. ² B. O. G. M. *om*.

30. *sāmnidhyān nvati iti¹ labhyate: paparo nvati ity² antyasvarah³ pragraho na bhavati. yathā⁴: mār-----*

¹ O. *om*. ² B. *om*. ³ B. *antaḥ s-*; O. *antas-*. ⁴ B. O. G. M. *om*.

31. *samīci ity antyasvarah¹ pragraho bhavati. yathā²: sam----- paç-----*

¹ B. *antas-*; O. *antyaḥ s-*. ² B. O. G. M. *om*.

32. *sāmnidhyāt samīci iti labhyate: na khalu samīci ity antyasvaro nakāraparah¹ pragraho bhavati. yathā²: sam-----*

¹ G. M. *om*. ² W. G. M. *om*.

32. But not when followed by *n*.

The case excepted is *samīci nāmā 'si* (v.5.10¹). I have noted no other.

ची यत्प्रपरः ॥ ३३ ॥

33. *Ci* is *pragraha*, when followed by *yat* or *pra*.

The passages had in view by this rule are: *āikshavī tiraçē yad āçvanālah* (vi.2.1⁵: W. O. omit the first word, G. M. B. the last; and B. has the citation out of place, after the next but one), and *prāci pretam adhvaram* (i.2.13² and vi.2.9³); besides two other cases before *pra* at vi.2.1⁵; 3.9⁶. The commentator gives in addition a number of counter-examples: to show that *cī* is not always *pragraha*, *prāci diçām* (iv.3.3¹ et al.: but W. B. O. read instead *yā prāci dik*, which is not to be found in the *Sanhitā*: *prāci dik*, without *yā*, occurs at several places, e. g. iv.3.6²); to prove the necessity of the *t* of *yat* and the *r* of *pra*, *gāur ghṛtāci yajño devān jigāti* (ii.5.7⁴: only G. M. have the last two words) and *tasmāt paçcāt prāci patny anv āste* (v.3.7³: only G. M. have the first two words); to indicate that other endings than *cī* are not *pragraha* in the situations specified, *yad agnir vajra ekādaçinī yad agnāu* (v.5.7¹: only G. M. have the first three words) and *prajanane prajananañ hi vāi* (i.5.9¹: only G. M. have the last two words).

आन्महो ॥ ३४ ॥

34. Also *ān mahī*.

The passage is *mahān mahī astabhāyat* (ii.3.14⁶). Elsewhere, *mahī* is not *pragraha*: e. g. in *mahī dyāuh prthivī cā naḥ* (iii.3.10² et al.: G. M. omit the last two words); and even after *n* preceded by any other vowel than *ā*: e. g. in *vayunāvid eka in mahī devasya* (i.2.13¹ and iv.1.1¹⁻²: G. M. omit the last word).

पती श्रुतिः ॥ ३५ ॥

33. *cī ity antyasvaro yatparaḥ praparo vā pragrahaḥ syāt'. yathā: āiksh-.....: prā-.....: evampara iti kim: prā-.....: takārarephābhyām kim: gāur-.....: tas-.....: cī 'ti kim: yad-.....: praj-.....*

¹ G. M. *bhavati*. ² G. M. *om*.

34. *ān ity etadvigishṭe mahāgrahaṇe 'ntyasvaraḥ pragrahaḥ syāt'. yathā: mah-.....: ān iti kim: mahī-.....: ākāreṇa kim: vay-.....*

¹ G. M. *bhavati*.

35. Also the combination of sounds *pati*.

The commentator explains: wherever there is *ṛuti*, i. e. 'hearing,' of *pati*, there we are to understand a case of *pragraha*-quality. Hitherto we have been dealing only with *padas*, or complete individual words; but the *i* of *pati* is uncombinable, even when that audible combination is only a part of a *pada*. The selected examples are, first, *deāu pati vindate* (vi.6.4³) and *ṣubhas pati idam aham* (iii.2.10²: only G. M. have the last word), where *pati* is a *pada*; then *yam āgirā dampati vāmam aṇutaḥ* (iii.2.8⁴: only G. M. have the first two words) and *priyam indrābrhaspati* (iii.3.11¹), where it is part of a *pada*: there are a few other cases.

It is remarked at the end of the comment, that, from this rule on, parts of words are also subjects of prescription of *pragraha*-quality.

ग्री ॥ ३६ ॥

36. Also *gnī*.

I have noted a number of cases of *gnī* as dual of *agnī* and its compounds. The commentator gives two: *antarāgnī paṇḍām* (i. 6.7¹), and *viṣvāmitrajamadagnī vasishthena* (iii.1.7² and v.4.11³).

न द्विपरः ॥ ३७ ॥

37. But not when followed by *hi*.

The case excepted is that of *gnī* occurring as nominative singular feminine of *āindrāgna*: *āindrāgnī hi bārhaspatyā* (v.5.6²). The commentator pleads the occurrence of *indrāgnī havāmahe* "in another text," as justification of the rule, in saying "by *hi*," instead of "by *h*." But we may question whether the justification is not officious and uncalled for.

वीड्वारौकृष्णाश्चरावोयदापरः ॥ ३८ ॥

35. *pati ity asya yatra yatra ṛutiḥ¹ ṣṛavanam asti tatra tatra pragrahatvaṁ viññeyam. yathā: dvāu..... ṣubh..... ṛutir iti kim: yam..... priy..... ity ādāv apī² padāikadeṣe pragrahatvāya³.*

¹ G. M. om. ² G. M. om. ³ G. M. -*team*.

36. *gnī iti pragraho bhavati¹. yathā: ant..... viṣv.....*

¹ G. M. om. ² G. M. om.

37. *gnī iti sāmīnidhyāḥ labhyate: na khalu gnī iti¹ padānto hi-paraḥ pragraho bhavati². yathā: āindr..... evampara iti kim: indr..... iti śākhāntare.*

¹ G. M. ins. *apī*. ² G. M. om.

38. Also an *i* or *e* followed by *vid*, *dvārāu*, *kṛṣṇaḥ*, *carā-rah*, and *yadā*.

The quoted passages under this rule have each its counter-example. The first is *dhishane vidā sati vīdayethām* (i.4.1²), a double case; and, to show that *vī* alone would not have been enough, *āpaḥ ca me vīrudhaḥ ca me* (iv.7.5¹). Next, *devī dvārāu mā mā* (iii.2.4⁴), with *dvādaśa sam padyante dvādaśa* (i.5.7³), to prove the need of the *rāu* of *dvārāu*. Again, *yajñāyā 'tishthamāne kṛṣṇo rūpaṁ kṛtvā* (vi.1.3¹; only G. M. have the first word; they also omit the last two words, while B. O. omit *kṛtvā*); and *cātevale kṛṣṇavishānām prā 'syati* (vi.1.3²; G. M. omit the last two words) justifies the *ḥ* of *kṛṣṇaḥ*. Again, *vivasānāu ye carā-vāḥ* (i.5.10¹), with *rāye ca naḥ svapatyāya deva* (v.5.4⁴; G. M. omit *deva*) to show that *ca* alone would not have been enough: to prove that more than *car* or *carā* is needed, the commentator does not attempt. Finally, we have *ajanan nannamāne: yade 'dām tāḥ* (iv.6.2⁴; only G. M. have *ajanan*). To this is raised the question whether *yatante*, as coming before *yad ā-* in *greniḥ yatante yad ākshishur divyam* (iv.6.7⁴; only G. M. have the first word), is not also *pragraha*? The answer is an appeal to rule i.50, "in citations of *padas*, a *pada* only is to be understood:" but how we are to know that an integral *pada* is meant to be signified by *yadā*, any more than by *vid*, the commentator does not inform us.

न ज्ञे ऽह्ने नित्यम् ॥३१॥

39. But not *jñe* and *ahne*, under any circumstances.

The passages quoted in illustration of the rule are *varunāya rājñe kṛṣṇaḥ* (v.5.11), and *vanaspatinām enyahne kṛṣṇaḥ* (v.5.15; only G. M. have the first word): these are both exceptions to the preceding rule, and are the immediate occasion of the

38. 'ity evampara' ikāra ekāro vā ' pragraho bhavati'.
yathā': dhish-.....: dakāreṇa' kim: āpaḥ-.....: devī-.....: rāv
iti kim: dvād-.....: yaj-.....: visargena kim: cāt-.....: viv-
.....: rāva iti kim: rāye-.....: aj-.....: namu' gre-..... ity
atra pragrahatvaṁ kiṁ na syāt. padagrahaṇeṣu padaṁ
gamyeta (i.50) itī vacanān na bhavati' 'ti brūmah.

¹ G. M. *eshu pureshu*. ² G. M. *ina. padāntah*. ³ G. M. *om*. ⁴ W. G. M. *om*.
⁵ G. M. *vid itī*. ⁶ G. M. *om*. ⁷ G. M. *atra*. ⁸ W. *pravartate*; G. M. *om*.

39. *jñe*: *ahne*: *ity* ' etayor antyasvaro nityam pragraho na
syāt. yathā': var-.....: van-.....: vīdādi (iv.38) prāptir ana-
yoh. nityaḥ abdaḥ prāptyantarapratibandhakah'. yathā': yaj-
.....: gamayatobhavataḥ (iv.52) ity ādinā prāptiḥ: sva-
.....: somāyasva (iv.48) itī prāptiḥ.

¹ G. M. *om*. ² B. O. *-pratishedh-*; G. M. *prāptyānishedh prayojanakah*. ³ G. M. *om*.

introduction here of this one. But the addition of *nityam*, 'constantly, in all cases,' excepts the same words from the action of any other rule: for example, of rules 52 and 48, which would otherwise apply in the passages *yajñe pi kartor iti tāv abratām* (ii.6.7¹) and *svarājñe novāhāu* (v.6.21).

आकारिकारपूर्वस्तु बहुस्वरस्य ते वे ॥४०॥

40. *Te* and *the*, however, are *pragraha* in a word of more than two syllables, if preceded by *ā* or *e*.

The class of words here aimed at, of course, is composed of second and third persons plural of present and perfect tenses middle of verbs. The commentator quotes several instances: *etasmin vā etāu mrjāte yo vidvishāṇayoh* (ii.2.6¹⁻²: only G. M. have the first three words, and they omit the last word); *ṣukrā manthināu grhyete* (vi.4.10¹); *prā prthivyā riricāthe divaṣ ca* (iv.2.11¹: only G. M. have the first and the last two words); and *drñhanā yam nudethe* (iv.7.15²). Then, to justify the requirement of a preceding *ā* or *e*, we have given us *ā vṛcayate vā etad yajamānah* (iii.3.8¹: G. M. omit the last word); of a polysyllabic word, *tat pravāte vi shajanti* (vi.4.7²: see under i.48) and *yad ete grhyante* (iii.3.6¹); the restriction to the endings *te* and *the*, *anūcyamāna ā sādāyati* (ii.2.5⁷, 11¹).

As to the special significance of *tu*, 'however,' in this rule, two of our commentator's three chief authorities, Vararuci and Māhishēya, are reported by him as at variance. The former maintains that it indicates the cessation of regard had to the words specified in rule 38 as occasions of *pragraha*-quality; the latter, that it prescribes the annulment of continued implication of the exceptions mentioned in rule 39, and of what was there signified by the word *nityam*. Vararuci's view is declared the better one, and with good reason—unless, indeed, we prefer to ascribe to the word a general change of subject, from mention of individual words to the description of a class.

40. *bahusvarasya padasya sambandhī te iti the iti vā* * "kārapārca ekārapārco vā pragraho bhavati. yathā: *et*.....: *ṣukr*.....: *pra*.....: *drñh*.....: *evampārca iti kim: ā vṛc*.....: *trīṇi*.....: *bahusvarasye 'ti kim: tat*.....: *yad*.....: *tethe iti kim: anūc*.....: *vīdādi* (iv.38) *nimittasāpekshatānīvartakas tu ṣabda iti vararucipakṣaḥ: māhishēyapakṣas tu vakshyate*²: *pārcasātrotkanishedhanīyaṣabdojñāpītanuvṛttiṃ*³ *nivārayati*⁴ *'ti*⁵: *tatra*⁶ *vararucimataṃ ruciram. bahavaḥ svarā yasmin tad bahusvaram: tasya. atra svaraṣabdopādānāc*⁷ *ca*⁸ *bahuṣabdena cyaktibhedo vijñeyah.*

¹ W. -dhiya. ² G. M. ins. *ṣabdah*. ³ G. M. *ucyate*. ⁴ G. M. -dham nit. ⁵ G. M. *vār*. ⁶ G. M. om. ⁷ G. M. *atra*. ⁸ W. *bahusvaraṣabdopādānātā*; B. O. *bahusvararūpaṣabdena upādānātā*. ⁹ W. B. O. om.

The commentator's final remark as to *bahusvarasya* is obscure to me.

न शार्यति ॥४१॥

41. But not *çaryâte*.

Namely, in the passage *çaryâte apibah sutasya* (i.4.18: G. M. omit the last word). An exception to the preceding rule, by express mention of the excepted word.

ते मापातंनमश्नमभिवायुर्गर्भमुपाहस्तुपरः ॥४२॥

42. *Te* is *pragraha* when followed by *mâ pātam*, *namaḥ*, *enam abhi*, *vāyuh*, *garbham*, *upa*, *ahas*, and *tu*.

The passages, as quoted by the commentator, are: *vām ā rabhe te mātām ā'sya* (i.2.2¹⁻²: only G. M. have the first three words), with *te mātām yajñe* (iii.2.4¹), to show the necessity of including *pātam* in the rule; *pūnas te: namo gñaye pratividdhāya* (i.5.10¹: only G. M. have the last word), with *te na vy ajayanta* (v.4.1¹), to prove that *na* alone would not have been enough; *te enam abhi sam anahyetām* (ii.5.6⁵), with *ta enam bhishajyanti brahmanah* (ii.3.11⁴: W. omits the last word), to justify the inclusion of *abhi*; *te vāyur vy avāt* (iii.4.3¹), with *te vācāṣ striyam* (vi.1.6⁵), to show why the *yuh* of *vāyuh* was needed; *te garbham adadhātām* (iii.4.3¹), without any counter-example to prove that *ga* would not have answered the purpose; *te upā mantrayanta* (vi.1.3¹); *te ahorātrayoh* (vi.1.3¹); *te tv āva nō'tsrye ity āhuḥ* (vii.5.7¹: G. M. omit the last two words), with *te te dhāmāny ugmāsi* (i.3.6¹), to show that *t* not followed by *u* is not enough to determine the *pragraha* quality. Then, as further counter-examples, we have *te devāḥ* (i.4.10¹ et al.) in proof that *te* is not *pragraha* before other words than those here mentioned; and *brhad ukṣhe namaḥ* (i.4.26), *amushmiṇ loka upa çere* (v.3.7²), and *yanti*

41. *çaryāta ity antyasvarah¹ pragraho na² bhavati. yathā: çār----- pārçasūtraprāptāu³ satyām kanthoktanishedho⁴ 'nena⁵ vidhīyate.*

¹ B. -yah s. ² O. om. ³ G. M. -treṇa pr.; B. -tre pr. ⁴ G. M. -ktyā n. ⁵ G. M. om.

42. *'----- evamparas te iti çabdah pragrahaḥ syāt. yathā: vām-----: pātām iti kim: te-----: pūnas-----: ma iti kim: te-----: te e-----: abhi 'ti kim: ta-----: te v-----: yur iti kim: te v-----: te ga-----: te u-----: te ah-----: te tv-----: ukā-rena kim: te te-----: evampara iti kim: te ā-----: te iti kim: brh-----: am-----: yanti-----.*

¹ W. B. O. ins. te. ² G. M. om.

vā ete savanādye 'hah (vii.5.6²), showing that only *te* is *pragraha* in the situations defined.

These are not all the instances found in the *Sanhitā* of *te* as *pragraha*; one was disposed of by rule 20 above, and at least one or two others come under the action of other rules of this chapter.

अनुदात्तो न नित्यम् ॥ ४३ ॥

43. But not when unaccented, under any circumstances.

That is to say, even in such a situation as would bring it otherwise under the preceding rule. The example quoted is *bāhubhyām uta te namaḥ* (iv.5.1¹): if the text contains others, I have failed to notice them. The specification *nityam* has its usual force, as suspending the application of all rules to the contrary, wherever found: for example, that of rule 52, below, in the passage *namas te astv āyudhāya* (iv.5.1⁴).

एते तनुवौवैसमेवहियज्ञपदिष्टकपरः ॥ ४४ ॥

44. *Ete* is *pragraha* when followed by *tanuvāu*, *vai sam*, *eva*, *hi*, *yajña*, *pad*, and *ishtak*.

The passages, as quoted by the commentator, are: *tasyāi 'te tanuvāu* (v.7.3²); *ete vai samvatsarasya cakshushī* (ii.5.6¹: G. M. omit the last word), with *ete vā idāyāi stanah* (i.7.1²: G. M. omit the last word) as counter-example, showing that before *vai* not followed by *sam* the word is not *pragraha*; *sa ete eva namasyann upā 'dhavat* (ii.5.6²: only G. M. have the first word, and they omit the last two); *ete hi devānām* (ii.5.6⁶: another case at vii.5.7¹); *cakshushī vā ete yajñasya* (ii.6.2¹ et al.: compare also the nearly identical passage vi.2.11²); *yajñasya hy ete pade atho* (v.1.6²⁻⁴: W. omits the first word); and *yad ete ishtake upadadhāti* (v.3.5²). Counter-examples would have been in place to show that, in citing the last three fragments of words, the rule had taken no more than just what was sufficient for its purpose; but

43. *mā pātam ityādiparo 'pi te ity antyasvaro' 'nūlātto nityam pragraho na bhavati. yathā: bāh----- nityam iti kim: lakṣhaṇāntaraprāptasyā 'pi pratishedho' yathā syāt: na----- gamayatobhavataḥ* (iv.52) *ity ādinā' prāptiḥ.*

¹ O. -yah sv. ² G. M. om. ³ G. M. nish. ⁴ O. G. M. om.; B. antya.

44. ¹ ----- *ity evampara ete ity antyasvarah² padāntah³ pragraho bhavati. yathā: tas-----: ete-----: sam iti kim: ete-----: sa-----: ete-----: cak-----: yaj-----: yad-----: 'evampara iti kim: atha-----: ete iti kim: man-----: push-----: agre-----: sapt-----⁴*

¹ B. O. ins. etc. ² O. -yah s. ³ G. M. om. ⁴ W. B. O. om.

they are not furnished. The general counter-examples under this rule, like those under the last but one, proving that only *ete* is *pragraha* before the words specified, and *ete* itself before them only, are given by G. M., but omitted in the other manuscripts: they are *atha katama ete devā iti* (ii.6.9³), *manuta evāi 'nam etāni* (v.5.6¹), *pushkaraparne hy enam upaṣṛitam* (v.1.4⁴: MSS. -*gru-**tim*), *agre yajñapatiṁ dhatta* (i.1.5¹), and *saptame pade juhoti* (vi.1.8¹).

परश्च द्वयोः ॥ ३५ ॥

45. As also, the letter following the two last mentioned.

The "two" of the rule are *pad* and *ishtak*; and the commentator makes the further obvious specification that the letter following them is *pragraha* only when they themselves follow *ete*, as prescribed in the preceding rule. He quotes the passages referred to: *yajñasya hy ete pade atho* (v.1.6.3⁴: W. omits to *pade*, B. O. to *ete*), and *yad ete ishtake upadadhāti* (v.3.5²); adding, to show the necessity of the limitation made by him, the counter-examples *saptame pade juhoti* (vi.1.8¹), and *tasyās te devī 'shtake* (iv.2.9²).

स्यःपरः ॥ ३६ ॥

46. Also one followed by *sthaḥ*.

There is a natural reason for this rule, *sthaḥ* being a dual verb, and so, apt to be preceded by a dual noun. I have noted near a dozen cases in the text; the one cited in illustration by the commentator is *vishnoḥ śnyaptre sthaḥ* (i.2.13³). To show that *stha* instead of *sthaḥ* would not answer, is given *etasmīn loke stha yu-śhmāns te 'nu* (iii.2.5⁶: only G. M. have the first two words, and they omit the last three).

परश्चोभयोः ॥ ३७ ॥

47. As also, one following them both.

Following, namely, a *sthaḥ* and a preceding *pragraha* word: for example, *gilpe sthas te vām ā rabhe* (i.2.2¹: but this citation is wanting in G. M.), and *dr̥dhe sthaḥ ṣṭhire samīet* (iii.2.4³). A counter-example, of a word following *sthaḥ* only, is *vr̥shanāu stha urvaḥ* (i.3.7¹).

45. *nimittina upari vartamānayoh padishtakḥpadayoh' para'*
'ikāra ekāro vā' pragraho bhavati. yathā: yaj-....: yad-....
nimittina upari vartamānayor iti kim: sapt-....: tas-....

¹ B. O. *drayoh padishtak ity etayoh cakāraṇvādishtayoh*; G. M. *pat ishtaka ity etayoh cakāraṇvādishtayoh dvayoh*. ² B. O. *parata*. ³ G. M. *om*.

46. *stha ity evampara ikāra ekāro vā padāntaḥ pragraho bhavati. yathā: vish-.... visargeṇa kim: et-....*

The commentator then proceeds to point out that the difference in phraseology between this rule and the last but one—*dvayoh*, 'two,' being used in the one, and *ubhayoh*, 'both,' in the other—indicates a difference of meaning. Above, the two affecting causes (*nimitta*) specified in the preceding rule, each along with the word affected by it (*nimittin*), were intended; here, on the other hand, the two aimed at are an affecting and an affected word.

सोमायस्वैतस्मिन् ॥ ४८ ॥

48. Also in the section beginning *somāya sva*.

The section in question is v.6.21: it was necessary to add *sva*, in order to distinguish it from that beginning *somāya pitṛmate* (i.8.5). It contains thirteen *pragrahas*, of which the commentator cites several together: *avi dve dhenā bhāumī* (v.6.21¹: G. M. omit *bhāumī*): three of these, however, would be disposed of by the three rules next following.

दे ॥ ४९ ॥

49. Also *dve*.

This word, which occurs about forty times in the *Tāittiriya* text, is, of course, always *pragraha*. The commentator cites two instances: *dvedve sam bharati* (i.6.8²), and *yad dve naçyetām* (ii.6.3³).

परश्च ॥ ५० ॥

47. *cakārānvādishtayoh pārvasūtroktanimittanimittinor ubhayoh para ikāra ekāro vā padāntaḥ pragraho bhavati. yathā: gil-.....: dṛḍhe-..... ubhayor iti kim: vṛsh-..... paraç ca dvayor (iv.45) iti¹ vācya ubhayor iti çabāntaram² arthāntarajñāpakam³: nimittisahitayoh⁴ pārvasūtroktayor nimittayoh paraḥ pragraho bhavati: paraç ca dvayor (iv.45) iti sūtrārthaḥ: atra tu⁵ sūtre nimittanimittinor⁶ ubhayoh paraḥ pragrahaḥ syād iti viçeshād⁷ bhedo vijñeyah.⁸*

¹ G. M. pārvekta-. ² B. ins. kim ca; O. ins. ca. ³ G. M. -araprayogah. ⁴ G. M. -kah. ⁵ G. M. -llas-. ⁶ G. M. om. ⁷ G. M. -ttinimittayoh. ⁸ B. -shaya; O. -shena; G. M. vishaya. ⁹ G. M. drashtavyah.

48. *somāya svarājñe (v.6.21) ity asminn anuvāka ikāra ekāro vā padāntaḥ pragraho bhavati. yathā: avi-..... ity ādi sve 'ti kim: somāya pitṛmate (i.8.5) ity atra mā bhād iti.*

49. *dve ity antyasvaraḥ padāntaḥ¹ sarvatra pragraho bhavati. yathā: dve-.....: yad-.....*

¹ G. M. om. ² G. M. om. ³ G. M. O. om.

50. As also, the following word.

The comment instances but one case, a double one: *dve gukle dve kṛṣṇe mārḍhanvatih* (v.3.14: G. M. omit the last word). Of such the text contains more than a dozen, but they are not worth referring to in detail.

एकव्यवेतो ऽपि ॥५१॥

51. Likewise the next but one.

The *api*, 'likewise,' in this rule is explained as bringing forward *dve* from the last rule but one; another application of the "principle of the frog's leap." The cited examples are *dve hy ete devate* (ii.1.9²: but G. M. omit this citation), and *dve vā devasatre* (vii.4.5¹). By rule i.48, *devasatre*, though a divisible compound (*pada*-text, *devasatre iti deva-satre*), is reckoned as but a single *pada* for the purposes of this precept: another like case, *dve savane gukravati* (vi.1.6⁴), was expressly quoted as an illustration under the former rule. At vi.6.4³ (*dve jāye vindate*) is a case where the action of the rule is suspended by a later one, iv.54.

गमयतोभवतोऽनूकारात्परंतनूयदकरोत्कुर्यादिष्टिघ्व-
तांप्रवर्तास्तास्तभीतांवाचयतिविभृतस्ताग्निं गायत्रंताभ्या-
मेवोभाभ्यामवात्तरंपर आ षष्ठात् ॥५२॥

52. Before, and within six words of, *gamayatah, bhavatah* (except when it follows *ū*), *tanū yāt, akarot, kuryāt* (in *ishṭi* passages), *abrūtām, pra varta, āstām, stabhñitām, vācayati, bibhṛtas ta, agniṁ gāyatram, tābhyām eva, ubhābhyām, and avāntaram*.

Of the words here specified, some are duals, and so would naturally have other duals, with *pragraha* endings, in their vicinity; in other cases, the collocation is purely accidental.

The *ā* in the rule is declared to be intended this time "inclusively" (*tena saha*, 'along with the specified limit: 'compare the scholiast to Pāṇini ii.1.13); and the necessity of the specification

50. *cakāro dve ity anvādigati: dve ity etasmāt para ikāra ekāro vā padāntaḥ pragraho bhavati². yathā³: dve.....*

¹ O. *asmāt*. ² B. O. *syāt*; G. M. om. ³ G. M. om.

51. *ekavyaveto¹ 'pi dve ity etasmāt para ikāra ekāro vā padāntaḥ pragraho bhavati². yathā³: dve.....: dve..... ekena padena⁴ vyaveta⁵ ekavyavetaḥ. apiṣabdo dve ity anvādigati maṇḍākaphutinyāyena.*

¹ B. O. *vahito*. ² G. M. om. ³ G. M. om. ⁴ G. M. om. ⁵ W. *vyavahita*.

"within six words" is explained as arising from rule i.30, which would limit the meaning of "before" to 'the word standing next before.' This involves a misinterpretation of the rule referred to, which was made for quite another purpose (see the note upon it). No such special and technical ground is needed to justify the terms of the present rule, which are of obvious and incontestable propriety.

The commentator's example for *gamayataḥ* is *te evāi 'nam prātiśthām gamayataḥ* (ii.1.4⁷): I have noted no other case. For *bhavataḥ*, he gives *uttarāvati bhavataḥ* (v.4.8⁵); with the counter-example *dikshante 'ntanāmānāv rtā bhavataḥ* (vii.4.8¹); to show the necessity of the restriction imposed by the rule in the case of this word. There are quite a number of other passages where *bhavataḥ* assures the *pragraha*-quality to words in its neighborhood: I have noted ii.2.2³, 11.4⁵; 3.2⁶, 3⁵, 4.3.4, 8²; iii.1.7², 9³; 5.4⁴; v.4.6³; 5.1²; vii.1.4³; 2.1² twice. With regard to the limitation *anākārāt*, the commentator remarks that although simple absence is the primary significance of its negative prefix, yet another meaning is here assumed, in accordance with the requirements of the case: that is to say, "after a not-*a*" is to be understood as 'after any letter but *a*.' For *tanā yat*, we have *ete vāi mahāyājñasyā 'ntye tanā yat* (ii.2.7⁵: I have found no other case); and, as counter-example, to justify the inclusion of *yat*, *paripataye tvā gṛhṇāmi tanūnaptre teḍ* (i.2.10²: only W. has the last word). For *akarot*, *budhnavati agravati yājyānuvākye akarot* (ii.3.4²: another case at ii.2.8⁵). For *kuryāt*, *mānavi rcāu dhāyye kuryāt* (ii.2.10²: another case at ii.3.3⁵); with the counter-example *agnaye dātre purodācam aṣṭākapālaṁ kuryāt* (ii.5.5²), to explain the restriction to *iṣṭi*-passages. The *iṣṭis* are defined as being "the three *praṇas* beginning with the tenth, but excepting their final *anuvākas*" (which have before received the designation *yājyā*): that is to say, ii.2.1-11; 3.1-13; 4.1-13. There are other passages besides the one quoted proving the necessity of the restriction in question: thus v.4.7⁷; vii.5.5¹. For *abrātām* is cited *te abrātām varam vṛnāvahāi* (ii.5.2⁵, 6⁵: another case at v.2.3³). For *pravarta*, *havirdhāne prāci pravartayeyuḥ* (iii.1.3¹); with the counter-

52. *gamayataḥ*: *bhavato 'nākārāt*: *ākāravatyatiriktavarnāt param bhavata iti*¹: *yady apy abhāvo mukhyārthas tathā 'pi tad anyārthatā svikṛtā lakṣhyānusārāt*: *tanā yat*: *akarot*: *kuryād iṣṭiṣhu*: *iṣṭayo*² *daṣamādayas trayāḥ praṇā uttamānuvāka-varjitāḥ*³: *abrātām*: *ity evampara ā shasṭhāt padāt pārvo vartamāna ikāra ekāro vā padāntaḥ pragraho bhavati*⁴. *abhividdhāv ayam ākāraḥ*: *tena sahe 'ty abhividhiḥ*. *yathā*: *te*..... *utt*..... *anākārāt param iti kim*: *diksh*..... *ete*..... *yad iti kim*: *pari*..... *budh*..... *mān*..... *iṣṭiṣhu iti kim*: *agn*..... *te*..... *hav*..... *varte 'ti kim*: *te*..... *ime*..... *vāci*..... *utt*..... *te*..... *te 'ti kim*: *manm*..... *ete*..... *gāya*

example *te 'dityāñ sam adhriyanta tvayā pra jānāme 'ti* (vi.1.5¹: G. M. end at *pra*), to show why *varta* was added to *pra*. For *ātām, ime vāi sahā 'stām* (iii.4.3¹: another case at iv.3.10²). For *stabhnītām, vāṅvadevāgnimārute ukthe aryathayanti stabhnītām* (iv.4.2³). For *vācayati, uttame ādumbari vācayati* (v.1.10^{2,3}). For *bibhr̥tas ta, te eva yajamānasya reto bibhr̥tas tasmāt* (v.6.8⁴); with the counter-example *manmahe yāv ātmanved bibhr̥to yāv* (iv.7.15⁵), to show that *bibhr̥taḥ* alone would not have answered the purpose of the rule. Doubtless the single case is provided for in this rule rather than in 42, above, because there are cases of *ta eva* in the *Sanhitā* which it would have made trouble to distinguish properly from this one. For *agnim gāyatram, ete dadhāte ye agnim gāyatram* (vi.3.5²); with the counter-example *sadhashe gnim purishyam* (iv.1.3¹), to show that the addition of *gāyatram* was needful. For *tābhyām eva, ete vāi yajñasyā 'ñjasāyanī sruti tābhyām eva* (vii.2.1²; 3.5², 7², 9²; 4.1³, 2⁴, 4²). With reference to this passage, the commentator raises the difficulty that *ete*, one of the words intended to be determined as *pragraha*, is not within six words of *eva*, one of the two words specified in the rule as conditioning its *pragraha*-character within that distance; but he declares it of no account, since what is within reach of any part of the assigned cause (*nimitta*) is within reach of that cause in its entirety. For, he says, in common life also, a quality belonging to a part is ascribed to the whole which contains that part: for example, people say "Devadatta has an ear-ring," when it is really his ear that has the ring. Truly a most lucid and convincing illustration! The necessity of the *eva* is proved by the counter-example *apa hañsy agne tābhyām patema* (iv.7.13¹: G. M. omit the last word). For *ubhābhyām, ye dve ahorātre eva te ubhābhyām* (vii.4.4²). Finally, for *avāntaram, uterjye ity āhur ye avāntaram* (vii.5.7¹); with the counter-example *sañ te 'va te hedah* (ii.5.12¹), to prove that *ava* would not have been enough alone.

न ग्रामीवर्चसीमिथुनीमासेल्लोकेधत्ते ॥ ५३ ॥

53. But not *grāmi, varcasi, mithuni, māse, loke, dhatte*.

tram iti kim: sadh-----: ete----- atra padadvayam ekam' nimittam ity' etepadam'' uddiçyā'' shashthanijamabhañgoprasaṅga itī cet: ''nā 'yam bhañgoprasaṅga''': nimittdīkadecasya shashthatvopapatteh sakalasyā 'pi nimittasya'' shashthatvam upapadyate: loka' py avayavadharmenā 'vayavino 'pi'' viçeshasiddheh: tathā hi: karṇe kuṇḍalam dhārayantaṁ kuṇḍali devadatta itī vadanti. eve 'ti kim: apa-----: ye-----: ut-----: antaram iti kim: sañ-----: ā shashthād itī kim: para ity uttarah (i.30) itī paribhāshayā 'nantarasyāi 'va paratvam syāt: tan mā bhād itī.

¹ G. M. ins. *padam* nañ. ² G. M. *-tāh*. ³ G. M. *-kārya*. ⁴ G. M. ins. *nāma*. ⁵ G. M. *-karañtāh*. ⁶ G. M. om. ⁷ W. B. O. *ste*. ⁸ G. M. *etan*. ⁹ O. *eve 'ty*. ¹⁰ O. *etat p*. ¹¹ B. O. *māi 'vam pras*; G. M. om. *bhañga*. ¹² W. O. *-syā 'pā*. ¹³ B. O. G. M. om.

These are words which, occurring within six of those mentioned in the last rule, would be *pragraha* if not thus specially excepted. The commentator quotes the passages in which they occur, as follows: *grāmy eva bhavati ganavati yājyānuvākye bhavatah* (ii.3.3³); another nearly identical case is found at ii.2.11⁴); *brahmanavarcasy eva bhavaty ubhayato rukmāu bhavatah* (ii.3.2³); *athā mithunā bhavatah* (vi.5.8⁶); *pārnāmāse prā yachāt tāv abratām* (ii.5.2³); *loke pratitishthanto yanti deāu shodahāu bhavatah* (vii.4.11³); and *dhatte jyotishmantāv asmā imāu lokāu bhavatah* (ii.6.2⁴).

अतो समानपदे नित्यमवे चावे च ॥ १४ ॥

54. Nor *ate*, in a single word, nor *ave*, under any circumstances.

After paraphrasing the rule, in a way which shows that he regards the specifications "in a single word" and "under any circumstances" as both alike referring to each of the "parts of words" mentioned, the commentator proceeds to cite illustrative passages, as follows: *ava rundhate tirātrāv abhito bhavatah* (vii.2.6³; 4.1³, 2³, 3⁶); another nearly identical case is found at vii.4.5⁴); *abhyāhvayate vajram enam abhi pra vartayati* (iii.2.9^{1,7}); and *anātātāya dhṛṣṇave: ubhābhyām uta te namaḥ* (iv.5.1⁴; B. O. omit the last word, and G. M. the last two). To show the necessity of specifying that *ate* should form part of a single word, he quotes *ena te ubhābhyām* (vii.4.4³). The limitation *nityam*, 'under any circumstances,' is explained in the usual manner, as intended to exclude the operation of other rules besides the one (iv.52) here especially aimed at: for the appropriate examples we are referred to the comment upon rule i.59, where they are given in connection with the illustration of another point.

53. ----- *etesho' antyasvaro gamayato bhavata ityādiparo 'pi pragraho na bhavati. yathā: grā-----: brah-----: atha-----: pār-----: loke-----: dhatte-----.*

¹ G. M. *esho*. ² G. M. *om*.

54. *nishedham cakāro 'nvādiçati. ate: ave: ity anayoḥ padāi-kadeçayor antyasvarah samānapade vartamāno gamayato bhavata ityādiparo 'pi nityam pragraho na bhavati. yathā: ava-----: abhy-----: anā-----: samānapada iti kim: eva-----: atra nityaçabdah prāptyantaraparihārthah. udāharanam² upabandhas tu deçāya (i.59) iti sūtre³ prasaṅgād uktam. samānam ca tat padam ca samānapadam: tasmint samānapade.*

iti tribhāshyaratne prātiçākhyavivarane
caturtho 'dhyāyah.

¹ O. *om*. ² G. M. *iti soddā-*. ³ W. *sūtreṇa*. ⁴ G. M. *om*.

This finishes the rehearsal of the words with *pragraha*-endings contained in the *Sanhitā*. As to the economy of the method of their rehearsal—whether it would have been possible to state the facts in fewer or briefer rules—I cannot speak with confidence: it would be, certainly, a thankless task to endeavor to recast them in an improved form. Nor can I, without a *pada*-manuscript, or a much more thorough and detailed study of the text, with the aid of a commentary, than it has been in my power to make, judge absolutely the success of the method followed. It appears, however (with exception of the equivocal treatment of the words in *o*, pointed out under rule 7), to be complete: my excerption of the text has shown me no *pragraha*-endings in *i* and *e* which are not duly taken account of, nor any case of final *i* or *e* not *pragraha* as involved in the general rules of the chapter without being duly excepted by special precept. One or two words whose endings are treated as uncombinable without being *pragraha* are disposed of in another chapter (x.18).

CHAPTER V.

CONTENTS: 1-2, introductory, relation of *pada* and *saṃhitā* texts; 3, order of application of rules; 4-8, anomalous insertions of a sibilant and *d*; 9-10, anomalous conversions of *r* and *h*; 11-19, anomalous omissions of *r*, *s*, *h*, *m*, and *yā*; 20-24, treatment of final *n* and *t* before palatal letters; 25-26, before *l*; 27-31, of final *m* before a consonant; 32-33, of final *h*, *t*, *n* before sibilants; 34-37, of initial *r* after consonants; 38-41, of initial *h* after consonants.

अथ संहितायामेकप्राणभावे ॥ १ ॥

1. The following rules apply in combined text (*saṃhitā*), within the compass of a single breath.

This is an introductory heading to the main part of the *Prātīkhyā*—the rules for the construction of the euphonically combined text (*saṃhitā*) from its presupposed material, the *pada*-text, where

1. *athe 'ty ayam adhikārah: saṃhitāyām ekapraṇabhāva ity etad adhikṛtaṃ veditavyam ita uttaram yad vakshyāmaḥ. saṃhitāte 'ti ko 'rthaḥ: nānāpadasaṃdhānasaṃyogaḥ' (xxiv.3) iti 'sūtreṇo 'ktaḥ' saṃhitārthaḥ: paraḥ saṃnikarshaḥ saṃhitāte 'ti vāiyākaraṇāḥ pathantī. ekasamutthaḥ prāṇa ekapraṇaḥ: tasya bhāvas tadbhāvaḥ: tasmin: ity ātreya matam. anyathā 'pi samāsah saṃgachate: ekapraṇena bhāvyate janyata uccāryata ity ekapraṇabhāvaḥ: eno 'chvāsena yāvaṇ uccāryate vedabhāgas tāvaṇ ekapraṇabhāva ity arthaḥ: ata evā 'vāsne padavi-*

each word stands separate, as if occurring independently. It is a rule of far-reaching force, applying through many chapters (for an attempt to define precisely how far, see the comment to xxiv.2). The matters treated in the first two chapters—the mode of utterance of elementary sounds, definitions, general explanatory precepts, and the like—were with propriety first disposed of; the separate rehearsal of the *pragraha*-endings, made in chapter iv., is more questionable, but defensible on the ground that those endings exhibit their *pragraha* character also in the *pada*-text, before *iti*: but the exclusion of the vowels irregularly protracted in *samhitā*, as rehearsed in the third chapter, is quite anomalous (see note to iii.1).

The commentator defines *samhitā* by quoting a later rule (xxiv.3), which declares it to be “the union of separate words in euphonic combination;” referring at the same time to the rule of Pāṇini (i.4.109), as the account of it given by “the grammarians.” For *ekapranabhāve* he first gives us Ātreya’s simple paraphrase; but then goes on to explain it more fully, as “that which is brought about, generated, uttered, with a single breath; such portion of the Veda, namely, as is uttered by the help of one expiration”—the condition of *pada*, or separated and euphonic independent words, recurring with the pause that follows the expiration. That is to say, if the repeater of the text has to pause to take breath where there is no regular *avasāna*, or pause of interpolation (such as separates the *pādas* of a verse: its length is taught in rule xxii.13), his last word is thrown out of *sandhi* with the next, and the end of the one and the beginning of the other must assume their *pada* form.

Now is interposed an objection: of what use are the two specifications “in combined text” and “within the compass of a single breath”? the former is enough by itself. To this it is replied: if the latter specification were not made, then no pause after a *pada* would be authorized in the continuous *samhitā* arrangement: and if the other were not made, then that respecting the single breath would apply also to the *pādas*; hence doubt would arise as to where any direction to be given would have force: there is, therefore, good reason for the double specification.

dhih. nanu samhitāyām ity etāvatai 'vā' lam: ekapranabhāva itī vā ubhayārambhaṇena¹ kim. ucyate²: ekapranabhāva ity anārabhyamāṇe pravr̥ttasya samhitāvidheḥ padāvasānatōm̐ ne 'shyate: samhitāyām ity anārabhyamāṇe tu padesho 'py ekapranabhāva upapadyate itī³ vakshyamāṇam⁴ kāryam kva⁵ bhavati⁶ 'ti saṁdehaḥ syāt: tasmād⁷ asmin⁸ ubhayārambhaṇe⁹ prayojanam asti.

¹ B. O. -nayoga. ² G. M. sūtrokta. ³ G. M. samhitā 'ty ar-. ⁴ W. B. G. vādyat-. ⁵ G. M. bhāṣanti. ⁶ W. om. ⁷ B. O. om. eva. ⁸ B. O. -bhāṇa; G. M. -bhāṇe. ⁹ G. M. om. ¹⁰ G. M. om. ¹¹ B. G. M. -na. ¹² B. O. G. M. kura vā. ¹³ G. M. tadā. ¹⁴ G. M. tas-. ¹⁵ O. G. M. -bha; W. B. -bhāṇa.

यथायुक्तादिधिः सा प्रकृतिः ॥२॥

2. Separation from the text as combined—that is the fundamental text.

I cannot but believe the intent of this precept to be the same with that of the rule which begins the second chapter of the Rik Pr., *samhitā padaprakṛtiḥ*, 'the *pada*-text is the foundation of the *samhitā*:' but such intent is not readily and distinctly deducible either from the rule itself or from its commentary. The latter explains that hereby is taught the *prakṛti*, or proper form, of *samhitā*, the reason being that a later rule (xxiv.5) prescribes as necessary to be understood, among other things, "*prakṛti, vikrama, krama*." An arrangement which does not deviate from the *pada*-text as constituted, taken as supreme, that is to be regarded as the fundamental text. By way of illustration is then quoted the whole series of passages falling under the action of rule x.13, below; passages in which the fundamental or *pada* form of certain words is maintained, against the ordinary rules of euphonic combination: they are *śadā uṣy urvi cā 'si* (i.1.9^a), *dhanvann iva prapā asi* (ii.5.12^a), *sahasraśya pramā asi* (iv.4.11^a: G. M. put this citation before the preceding one), *pra budhniyā irate* (iv.3.13^a), *jyā iyañ samane* (iv.6.8^a), *ā pūshā etu* (ii.4.5^a: W. B. O. omit this), and *aminanta evdih* (iii.1.11^a). No explanation is attempted of the bearing of these examples upon the principle which is laid down in the rule now in hand: we may suppose it to be that, the application of the rules of *sandhi* being denied in the case of these particular words, they remain in *samhitā* in their regular or natural shape as shown in *pada*-text—*prakṛtyā*, as it is elsewhere termed. And in this office of the precept is to be seen the real ground of its statement, rather than in a provision against the requirements of xxiv.5.

The grand difficulty in this exposition lies in its quiet postulation of *avicalitah*, 'unremoved, not deviating,' as connective between *vidhiḥ* and *yathāyuktāt*. I would sooner recur to the etymologic meaning of *vidhi*, 'disposal, putting apart,' and empha-

2. *prakṛtiḥ samhitāsvarūpam aneno 'cyate: prakṛtir vikramah kramah* (xxiv.5) *iti vijñeyatvavidhānāt*. *yathāyuktāt yathāsthītāt padapāthāt kātasthāt avicalito 'yo vidhiḥ sā prakṛti-samhitā vijñeyā: vidhir vidhānam prakṛtir ity arthah. yathā: sva-----: dhan-----: sah-----: pra-----: jyā-----: ā pū-----: ami-----: atra sūtre padānām parasparānvayo mahābhāshyavacanāc' ca' vijñeyah: tac ca vocanām tā varṇaprakṛtayah* (ii.7) *ity atra pāthanti: evam atra 'pi svaritayor madhye yatra nīcam* (xix.1) *ity ādāu mantavyam.*

¹ W. vijñeyatvavidhāt; B. teena vi.; G. M. jñeyatvena vi. ² G. M. -thāvas-

³ G. M. -cillīte. ⁴ W. B. O. -tik s-. ⁵ G. M. om. ⁶ G. M. -canena. ⁷ G. M. om.

⁸ O. G. M. pāthitām. ⁹ G. M. anyatrd.

size its prefix *vi* sufficiently to make it take an ablative adjunct, meaning 'separation from [the state] as combined;' and I have so translated above, though far from being confident that I have found the true solution of the difficulty. Neither *vidhi* nor its synonym *vidhāna* occurs elsewhere in the text, although both are frequent in the commentary (see Index), usually with the meaning 'rule, prescription;' not infrequently also 'arrangement, disposal.'

The commentator concerns himself finally with the gender of *sā*, which, he says, comes under the rule already once quoted from the *Mahābhāṣya* in explanation of a like case (under ii.7); and he points out further that the same principle applies elsewhere—for example, in xix.1.

तत्र पूर्वपूर्व प्रथमम् ॥३॥

3. And here, that which comes first is first taken.

That is to say, in the construction of the *samhitā* text, both the words to be treated and the rules to be applied must be taken up in their order, as they stand in the text and in the *Prāṭicakhyā* respectively. A variety of instances are given to illustrate the working of the principle. First, in *bhaksha: ā: ihi* (iii.2.5¹), the first two words are first combined, according to x.2, and then their result, *bhakshā*, is combined with *ihī*, by x.4, making *bhakshe* "hi, the true reading; whereas, if the second combination had been first made, forming *e'hi*, this would have coalesced with *bhaksha* into *bhakshāi'hi*—which (though in itself, as may well be claimed, the preferable reading) is unauthorized and incorrect. This exemplifies the application of the rule to the order in which words are to be treated; for its application to the use of rules there are three examples. The first concerns the production of the *samhitā*-reading *shannavatyāi* (vii.2.15) from the *pada*-reading *shatnavatyāi*: it is accomplished by the successive application of vii.2, which prescribes the conversion of *n* to *ṇ* after *shat*, and of viii.2,

3. *tatra samhitāvidhāne pūrvapūrvam padam sūtram ca prathamam kartavyam. yathā: bhaksha: ā: ihi: ity atra dīrghañ samānākshare* (x.2) *iti dīrghah: 'bhakshā: ihī: iti sthita ivarṇapara ekāram* (x.4) *ity ekāre kṛte bhakshe "hi 'ti bhavati: anyathāi'hi 'ti kṛtvā bhakshaṣabde' samdhīyamāne bhakshāi'hi 'ti syāt: tac cā 'niṣṭam: pūrvapadakartavyatva etad udāharanam. pūrvasūtrakartavyatve pī vadāmaḥ: yathā: shattriṅgrāmanishpūrvah* (vii.2) *iti nakārasya ṇatve kṛta uttamapara uttamam savargīyam* (viii.2) *ity anena takārasya ṇatve kṛte' shannavatyā iti bhavati: anyatho 'ttamapara uttamam* (viii.2) *iti sūtre prathamam pravrṛte sati' shannavatyā iti syāt: tac cā 'niṣṭam. tathā: vaṭṭh' svayamabhi-gūrtāye 'ty atra ṣanākārapūrvac ca takārah* (v.33):

which changes *t* before *n* to *n*: if, on the contrary, the latter rule had been applied first, changing *shat* to *shan*, the former would no longer have had force at all, and the reading would have stood *shannacatyāi*. The next case is that in which the words *vat* and *svayamabhiḡartāya* come together (iii.2.8¹ seven times: G. M. read *vashat* for *vat*, doubtless by a clerical error). Here, v.33 requires the insertion of a *t* between the *t* and *s*, and this inserted *t* is then, by xiv.12, made *th*; so that we are finally to read *vatth svay*: if the latter conversion were first made, the reading would turn out instead *vatth svay* (since v.33 would not then apply at all, but to the combination *thsv* would be prefixed a *t* of duplication, by xiv.1.5: the manuscripts, as usual in such cases, do not give these complicated readings altogether correctly: and W. B. even make the blunder of substituting at last *vat svāhā*, apparently having in mind *-vāt svāhā*, in the same division). Once more, in the passage *imam: vi: syāmi* (i.1.10² and iii.5.6¹), we are first to convert the *s* of *syāmi* to *sh* by vi.4, and then to duplicate the *sh* by xiv.1, making *vi shshyāmi*: if the duplication were first performed, making *vi ssyāmi*, then, by rule vi.4, we should have to read *vi shsyāmi*. Of the three examples thus given, only the first has to do with the form of the text as given in the manuscripts, since these very sensibly ignore the rules for duplication which make up the bulk of the fourteenth chapter of our treatise.

So far as regards the taking up of words for combination in their natural order, the Rik Pr. (ii.2) and Ath. Pr. (iii.38) have rules of like force with the present one.

त्रपुमिथुपूर्वः शकारश्चपरः ॥ ३ ॥

4. After *trapu* and *mithu* is inserted a *ç* before *c*.

prathama ūshmaparo dvitīyam (xiv.12) *iti sūtradevayam prasaktam: tatra pūrvevāt śanakārapūrvag ca takāra*¹ *ity etad eva prathamam kartavyam*²: *anyathā* ³*vatth svayam iti*⁴ *syāt: tac cā 'nishtam. athavā: imam vi shshyāmi* ⁵*'tyatro 'pa-sarganishpūrvo 'nuddatte pade* (vi.4): *svrapūrvam vy-añjanam* ⁶*'divarṇam vyañjanaparam* (xiv.1) *iti sūtra-devayam*⁷ *prāptam: tatra dvitvasūtre* ⁸*'prathame kārye sati*⁹ ¹⁰*vi shsyāmi*¹¹ *'ti syāt: tan mā bhād iti shatevam eva prathamam kartavyam.*

pūrvampūrvam iti ¹²*'vipsā sarvathāi*¹³ ¹⁴*'cam artham samarthayati*¹⁵.

¹ G. M. ins. *tena*. ² W. -*dena na*. ³ G. M. om. ⁴ W. B. O. om. ⁵ G. M. om. ⁶ B. O. *sati*. ⁷ W. O. -*ma*. ⁸ G. M. om. ⁹ W. B. O. om. ¹⁰ G. M. *vashath*; B. *vota*; O. *vatt*. ¹¹ G. M. om. ¹² O. M. put before *prathamam*. ¹³ W. B. *vat svāhe* ¹⁴*'ti*; O. *vat svayam iti*; G. M. *vashath svayam iti*. ¹⁵ G. M. om. ¹⁶ G. M. -*trāṇ*. ¹⁷ G. M. *prathamam kṛte*. ¹⁸ G. M. ins. *imam*. ¹⁹ B. G. M. *shyāmi*. ²⁰ G. M. *vipsā sarvathāi* ²¹*'tad dha 'yam iti samarthaniyam*; B. *vipsā sarvathāi* ²²*'cam arthayati*. ²³ O. *sarvathāi*.

The passages are *sisan ca me trapu ca me* (iv.7.5¹), and *mithu ca carantam upayāti* (iv.7.15²): the existing *pada*-text reads *trapu* and *mithu*, as this rule would lead us to expect. But the right of *trapu* to be recognized as an independent word by the side of *trapu* is assured by the derivative adjective *trāpusha*, and the close analogy of *manu*, *manus*, *mānusha*.

The commentator adds a couple of counter-examples: one, *viḥu ca me prabhu ca me* (iv.7.4¹⁻²), to show that not every *u* has a *c* added before *c*; the other, *asinā mithā kaḥ* (iv.6.9⁴), to show that the insertion is only made before *c*, after the words specified.

सुपूर्वश्च चन्द्रपरः ॥ ५ ॥

5. As also after *su*, before *candra*.

The example quoted by the commentator is *suçandra dasma viçpate* (iv.4.4⁶): the word occurs once more, at ii.2.12⁷. The *pada*-text reads *su-candra*. Counter-examples are: *pra candra-mās tirati dirgham āyuh* (ii.4.14¹: G. M. omit the last two words), and *ā mā suçarite bhaja* (i.1.12): their application is obvious.

संपूर्वः सकारः कुरुपरः ॥ ६ ॥

6. After *sam* is inserted *s* before *kuru*.

The commentator's example is *yajamānaḥ saṅskurute* (v.6.6⁴ and vi.5.5²). The *pada*-text reads *sam : kurute*. Counter-examples are *purodācāṇ alaṁ kuru iti* (vi.3.1²: G. M. have a *lucuna* involving this passage), and *saṅkṛtya chāḍakasāman bhavati* (v.4.12³). The text has further *saṅskṛtya* and *saṅskṛta*, but (as is also implied in rule xvi.26) they are read in the *pada*-text as in *saṁhitā*, without division, or ejection of the intruded *s*.

अकुर्व च प्रत्ययात्परः ॥ ७ ॥

4. *trapu : mithu : evampūrvaḥ çakāra āgamo bhavati caparah¹. yathā : sis----- : mith----- evampūrva iti kim : vi----- : evampara iti kim : as-----*

¹ G. M. cakārap-

5. *cakāraḥ çakāram anvādiçati : supūrvaḥ çakāra āgamo bhavati candraparah. yathā : suç----- evampūrva iti kim : pra----- : evampara iti kim : ā mā----- sv ity esha çabdaḥ pārvo yasmād asāu supūrvaḥ.*

¹ G. M. om.

6. *sam ity evampūrvaḥ sakāra āgamo bhavati kuruparah. yathā : yaj----- evampūrva iti kim : pur----- : evampara iti kim : saṁ----- kuruçabdaḥ paro yasmād asāu kuruparah.*

¹ G. M. om. (9) G. M. om.

7. And before *akurva*, after the augment.

The passage is, as quoted by the commentator, *ta ishūṇ sam askurvata* (vi.2.3¹); the *pada*-text reading *sam: akurvata*. The counter-example is *agnihotraṁ vratam akurvata* (iii.2.2²). As *pratyaya* occurs nowhere else in the treatise, we cannot tell whether it signifies distinctively 'augment,' or, as in other of the Prāti-ṣākhya, 'affix' in general. The commentator gives a scholastic explanation of the term, as indicating "that whereby the consonants are added unto, are made distinct."

नीचापूर्वो दकार उच्चापरः ॥ ८ ॥

8. After *nīcā* is inserted *d* before *uccā*.

The passage is *madhyān nīcād uccā* (ii.3.14⁶); and the *pada*-text actually reads *nīcā: uccā*. This is a proceeding to which it would be hard to find a parallel in the *pada*-texts of the other Vedas. To write *madhyena* for *madhyāt* just before would be in itself quite as defensible. As counter-examples, we receive *lokam yanty uccāvaca* 'hni' (vii.4.3⁶), and *nīcā tam dhakshi* (i.2.14²).

At the end of the comment is made the remark "the above are cases of insertion" (*āgama*, 'accession'). The matter of irregular conversions is next taken up.

असंपूर्वो ञ्मृकारः ॥ ९ ॥

9. After *asam*, *ṛ* becomes *ar*.

The passage in which this anomalous change is made is *grhānām asamartyāi* (iii.3.8²), where the *pada*-text has, as the rule implies, *asam-ṛtyāi*. Here, again, we cannot praise the work of the *pada* text-maker. Nor is the rule of unexceptionable form, for the commentator is obliged to specify that the *asam* intended is one not made up of the parts of two words (not *-a sam*); else such passages as *kalyāṇī rūpasamrddhā* (vii.1.6⁶), and *vahī hy esha*

7. *cakārah sampārvatvam*¹ *āgamaṁ*² *cā*³ 'nvādiṣati. *akurva* 'ce'ti' *grahāṇe pratyayāt paraḥ sakāra āgamo bhavati sampārvaḥ. yathā: ta----- pratyayo nāmā 'kāra ucyate: pratiyanta' abhivyañyante vyañjanāny anene 'ti pratyayaḥ. sampārca iti kim: agn-----*

¹ G. M. -rvam. ² G. M. sakārag-. ³ G. M. om. ⁴ W. ca; O. G. M. iti. ⁵ B. O. pratyayante; G. M. pratyayante.

8. *nīcāpūrvo dakāra āgamo bhavaty uccāparaḥ. yathā: madh----- evampārca iti kim: lok-----: evampara iti kim: nīcā-----*

āgamā etc.

¹ G. M. O. om.

saṃrddhyāi (ii.2.2¹) would be included. As counter-example, to show that *r*, not a syllable containing *r*, is liable to the specified conversion, is quoted *asamtr̥ne hi hanā* (vi.2.11²: G. M. omit *hanā*).

अवग्रह आशीर्धुःसुवरिति रेफं परः सकारः पका-
रम् ॥ १० ॥

10. Of *ācīh*, *dhūh*, and *suvaḥ*, when first members of a compound, the *visarjaniya* becomes *r*, and a following *s* becomes *sh*.

The word *avagraha* in this rule is the locative *avagrahe*, says the commentator, and applies to each of the specified words taken separately. He supplies *visarjaniya*, the omission of which, or of some other word answering the same purpose, is rather a serious defect in the rule. The illustrative passages quoted are *ity ācīr-padaya reā* (vi.2.9⁴; the *pada*-text reads *ācīh-padayā*), *dhārshāhāv anagrā* (i.2.8²; p. *dhūh-sāhāu*), and *dadhishe suvarshām jihvām agne* (iv.4.4¹; p. *suvaḥ-sām*: W. B. O. omit the first word of the citation, G. M. the last). The necessity of the specification "when first members of a compound" is shown by the counter-example *ye devā devasuva stha te* (i.8.10²: p. *deva-suvaḥ*: G. M. omit the first two words and the last). *Ācīh* shows the same irregular combination also in *anācīrkena* and *sācīrkena* (i.6.10⁴), but these words are not treated as divisible by the *pada*-text. The commentator goes on to point out the rules to which exceptions are established by this one: viii.23 would require *ācīshpadayā*, and ix.2

9. *asam ity evāmpārva r̥kāro 'ram vikāram āpadyate. yathā: gr̥h----- tatra¹ nimittam ekapadastham² vijñeyam: anyathā kaly-----: vahi-----: ity ādāv api bhavet. r̥kāra iti kim: asām-----.*

¹ G. M. O. atra. ² B. -dasamsthān.

10. *avagraha iti saptamyantam padam ācīshprabhṛtibhiḥ prayekam abhisambadhyate. ācīh: dhūh: suvaḥ: ity' eteshe avagrahesu visarjaniyo repham āpadyate: ebhyaḥ² paro yadi sākāro³ vartate tarhi shakāram⁴ āpadyate. yathā: ity-----: dhūr-----: dadh----- avagraha iti kim: ye----- kakhapakāraparaḥ⁵ (viii.23) ity anenā⁶ "cīshpadaye 'ti prāptam: 'aghoshaparas tasya sasthānam āshmanam⁷ (ix.2) iti dhūssāhāu⁸ suvaśām⁹ ity ca prāptam: tadubhayabhaṅgāyā¹⁰ 'yam ārambhah. iticabda eśhām evāi¹¹ 'sha viśesho nā¹² 'nyeshām iti prakāravāci.*

¹ G. M. om. ² G. M. tebh-. ³ G. M. put before *yadi*. ⁴ G. M. so 'pi shatvam. ⁵ G. M. om. ⁶ G. M. om. paraḥ. ⁷ G. M. om. ⁸ W. om. ⁹ B. O. om. ¹⁰ B. O. *dhūhs*. ¹¹ B. O. *suvaḥs*.

dhāṣādhāu and *suvaśām* (or, as it is customary to write them, *dhāṣādhāu* and *suvaśām*: only G. M. are conscientious about giving the double sibilant, as demanded by the *Prāticākhya*). The *iti*, he remarks finally, signifies that only the words mentioned, and no others, are intended—that is to say, it has no particular meaning at all. It would be well if he always as frankly acknowledged the insignificance of this word where it occurs in the rules.

अथ लोपः ॥ ११ ॥

11. Now for cases of omission.

An introductory rule or heading, having force as far as rule 10, below, inclusive.

इपूर्वी मकारः ॥ १२ ॥

12. A *m* is dropped, when preceded by *im*.

The passage aimed at is *im 'andrá suprayasaḥ* (iv.1.8²; p. *im*: *mandrá*): it is the only one of its kind in the text. The *Vājasaneyi-Saṁhitā* reads in the corresponding passage (xxvii.15) *im mandrá*. To treat the loss of a *m* here as suffered by the second word instead of the first is most arbitrary and unreasonable. The particle *im* is reduced to *i* in quite a number of *Rik* passages, and before other letters than *m*: they are duly noted in the *Prāticākhya* (*Rik* Pr. iv.36). A series of counter-examples is added by our commentator: *imam me varuna* (ii.1.11⁶) shows that *m* is not dropped after another *m* in general; *agnim mitram varunam* (ii.1.11⁴), that *m* after short *i* does not exercise the specified effect; *imkdrāya svāhe 'mkrāya* (vii.1.19¹), that *im* elides no other consonant than *m*. The yet farther restriction is applied, that *im* here is a *pādagrahaṇa*, 'the citation of a complete *pada*;' for otherwise there would be an elision of a *m* in such cases as *prthivīm mā hiṁśiḥ* (iv.2.9¹): G. M. add the further example *uta gravaśā prthivīm mitrasya*, which I am unable to find in the *Sanhitā*.

तनुपूर्व उदात्तयोर्वकारः ॥ १३ ॥

11. *athe 'ty ayam adhikārah: lopa ity etad adhikṛtam veditavyam ita uttarām gad vakshyāmaḥ. ayam adhikāras tishṭhanty ekayā* (v.19) *itisātraparyanto veditavyaḥ*.

12. *makāra im ity evampūrvo lupyate. yathā: im..... evampūrva iti kim: imam.....: dirghena kim: agn..... im iti pādagrahaṇam: itarathā prth..... ity ādāu makāro lupyeta. makāra iti kim: im.....*

¹ G. M. om. ² W. -hacarṇaḥ. ³ G. M. anyathā. ⁴ G. M. -yate; and add tac cā 'niṣṭā. ⁵ W. -rapara.

13. A *v* is dropped when preceded by *tu* or *nu*, in case these are accented.

It is when the particle *vāi*, or *vāva*, follows *tu* and *nu* that this anomalous mutilation is made. The commentator quotes *sa tv 'dī yajeta* (ii.6.6³ and vii.1.3¹; p. *saḥ*: *tu*: *vāi*), and in *nv 'ā upastirnam ichanti* (i.6.7²; p. *it*: *nu*: *vāi*). The same *sandhi* of *tu* and *vāi* is not infrequent elsewhere (the passages are i.7.1⁴, 6²; ii.2.4³; 5.4¹; iii.2.9²; 3.9²; 5.1²; v.5.9⁴; vi.4.3¹; vii.2.10³); that of *nu* and *vāi* is comparatively rare (only at i.5.9² twice); that of *tu* and *vāva* I have found only once, at vii.5.6³. Here, again, it would seem better to regard the final *u* as suffering elision, instead of the initial *v*. The specification "if accented" is explained as intended to exclude such passages as *anu vrtrahatyē* (i.6.12¹; 7.13¹), where *anu* would fall under this rule by i.52 (even if the *nu* here, like the *im* in the preceding rule, were regarded as a *padagrahanam*). Other counter-examples, of obvious intent, are *idam vām āsye haviḥ* (iii.3.11¹), and *pra tu janayati 'ti* (i.7.2⁴) and *vidusho nu yajñam* (i.3.13¹⁻²).

उत्पूर्वः सकारो व्यञ्जनपरः ॥ १४ ॥

14. A *s* is dropped after *ut*, when a consonant follows.

The commentator's example is *praty uttabdhyāi sayatvāya* (vi.6.4⁶; p. *ut-stabdhyaī*). This is, so far as I have discovered, the only case in the *Sanhitā* from the root *stabh*: similar forms from *sthā* occur variously (*anūthāya*, iii.4.10³; *upothāya*, vii.1.6³; 5.15¹⁻²; *utthāsyant*, vii.1.19²; *utthita*, vii.1.19³; 2.9³; and *utthāna*, vii.2.1⁴ thrice). As counter-examples are given *jagatsthā devāḥ* (ii.1.11⁴), *utkrañsyate svāhā* (vii.1.19³), and *utsādena jihvām* (v.7.11).

This familiar *sandhi* is also the subject of Ath. Pr. ii.18, and Vāj. Pr. iv.95.

एषस्य इति च ॥ १५ ॥

15. Also *eshah*, *saḥ*, and *syah*.

13. *tu*: *nu*': *ity evampūrvo vakāro lupyate tayos tunvor udāt-tayoh sator iti vibhajya viyogo³ vijñeyah. yathā: sa tv..... in nv..... udāttayor iti kim: anu..... apy akārādi (i.52) iti prāptih: evampūrva iti kim: 'idam..... vakāra iti kim': pra..... vid..... tuç ca nuç ca tunā': tāu pūrcāu yasmāt sa ta-thoktah.*

¹ B. O. *nu*, as also B. in the rule itself. ² G. M. *vinīy*. ³ B. *om*. ⁴ G. M. *tunu*.

14. *vyañjanaparah sakāra utpūrvo lupyate. yathā: praty..... vyañjanam asmāt param iti vyañjanaparah. evampūrva iti kim: jag..... sakāra iti kim: ut..... evampara iti kim: ut.....*

Here the *ca*, 'also,' is declared to continue the implication of "when a consonant follows" from the preceding rule. The *iti* is added for the sake of clearness; it shows the final *visarjanīya* of *syah*, and attributes it by analogy to each of the other words also. What indicates that this final *visarjanīya* is the letter which is to suffer elision is not so evident. The illustrative examples are *esha te gāyatrāḥ* (iii.1.2¹), *sa te jānāti* (i.2.14²⁻³; but G. M. substitute *sa topo tūpyata*, iii.1.1¹), and *esha sya vāji* (i.7.8³). The counter-example, showing that the omission occurs only before a consonant, is *dama evā syāi sha upa tishthate* (i.5.7⁴), where, if the *h* of *eshaḥ* were lost by this rule, x.5 would require the reading *esho pa*.

The corresponding rules in the other treatises are Rik Pr. ii.4, Vāj. Pr. iii.15, 16, Ath. Pr. ii.57.

नासः ॥ १६ ॥

16. But not *asah*.

Namely, in the passage *hṛtsvaso mayobhān* (iv.2.11²; p. *hṛtsu-asah*), which would otherwise fall under the preceding rule for *sah*, by i.52.

इद्विद्मइमान्शनौषधीःपरः सः ॥ १७ ॥

17. And *sah*, when followed by *id u*, *id agne*, *imām naḥ*, *enā*, *oshadhīḥ*.

These are the cases in the Sanhitā where, after the regular loss of the final of *sah*, its vowel is irregularly combined with the one that follows, against rule x.25. Such cases in the other Vedic texts are treated at Rik Pr. ii.33, 34, and Vāj. Pr. iii.14. The commentator quotes the passages affected, as follows: *se 'd u hotā so adhvarān* (i.1.14⁴; B. O. omit the last word; G. M. the last two), *se 'd agne astu* (i.2.14³), *se 'mām no havyadātīm* (iv.6.6⁶), *sāi 'nā nīkena* (iv.3.13² and 6.1⁵) and *sāu 'shadhīr anu rudhyase* (ix.2.3³, 11²). The first two need counter-examples, to show that *it* not followed by *u* or *agne* does not coalesce with *sa*: they are *sa ij*

15. *vyaktivishaya' itigabdah pratyekam esha ity ādin' visarjanīyāntān' dyotayati: cakāro vyañjanaparātām anvādicati. eshaḥ: sah: syah: eshu ' visarjanīyo vyañjanaparo lupyate. yathā: esha....: sa....: esha....: evampara itī kim: dama*

¹ G. M. -tiśiṣṭa; O. -tiśiṣṭa. ² G. M. -nām. ³ G. M. -yāntātām. ⁴ G. M. ins. padeshu. ⁵ G. M. om.

16. *asa ity asmin' grahaṇe visarjanīyo vyañjanaparo na lupyate. hṛt....: apy akārādi (i.52) itī prāpter' nishedhah'.*

¹ G. M. etas. ² G. M. -tiḥ. ³ G. M. om.

janena (ii.3.14³) and *sa id deveshu gachati* (iv.1.11¹). The third also wants a counter-example, to prove the need of *nah* after *imām*; it is found in *sa imām abhy amṛgat* (v.5.2⁴). Finally, to show that only *sah* undergoes the prescribed effect before the words specified in the rule, we have *paro divā para enā* (iv.6.2²).

अवग्रह इत्येकम् ॥ १८ ॥

18. Also *ity ekam*, when *ekam* is the former member of a compound.

The passage aimed at is *pāpīyānt syād ity ekāikaṁ tasya juhuyāt* (v.1.1²: but as given by W. O., without the first two words, it is also found again at v.4.5³: G. M. omit *juhuyāt*); and the *pada*-text actually reads *ekam-ekam*. The case is akin with that which forms the subject of the next rule. Two counter-examples are given, to justify the terms of the rule: they are *ardhukaṁ syād ity ekam agre 'tha* (vi.2.3⁵: only G. M. have the first two words), and *yad ekamekaṁ sambharet* (i.6.8²).

तिष्ठत्येकया सपूर्वः ॥ १९ ॥

19. Also *tish'hanty ekayā*, along with the preceding letter.

The commentator quotes the passage: *tish'hanty ekāikayā stutayā* (vii.5.8⁴); the *pada*-reading is *ekayā-ekayā*. As counter-example, where the same word remains unmutilated, is given *samānānām karoty ekayāikayo 'tsargam* (vi.1.9⁴: only G. M. have the first word).

In this rule and the foregoing are noted, but at the same time ignored, the first occurrences of the compound *ekāika*, which (see the St. Petersburg Lexicon) is not very rare in the *Çatapatha Brāhmaṇa* and later.

17.¹ *evamparah sahkāra*² *ity atra visarjanīyo lupyate. yathā: se 'd.....: se 'd..... v³ agna ity ābhyām⁴ kim: sa.....: sa.....: se.....: na iti kim: 'sa.....: sād.....: sād.....: sa iti kim: paro.....*

¹ G. M. *ing. iti.* ² W. B. O. *sakāra*; G. M. *sa.* ³ W. B. *id*; G. M. O. *u.* ⁴ B. O. *etābhyām.* ⁵ A lacuna in B., to near the end of the comment on rule 18.

18. *itiçabdaricishṭa ekam ity asminn avagrahe makāro lupyate. yathā: pāp..... avagraha iti kim: ardh.....: itiçabdaricishṭa iti kim: yad.....*

¹ G. M. *om.* ² End of the lacuna in B.

19. *tishṭhantiçabdaricishṭa ekaye 'ty asmin grahaṇe 'ntyo' varṇah sapūrvah pūrvasahito lupyate. yathā: tish..... tishṭhanti 'ti kim: sam..... pūrvēṇa saha vartata iti sapūrvah.*

¹ G. M. *-yāsvaro.* ² O. *om.*

The terms in which the rule is expressed show that, from rule 15 on, the implication has been of a "final" letter as liable to the effect prescribed. We have reason to be surprised that it was not distinctly stated when first made.

नकारः शकारं चपरः ॥ २० ॥

20. A *n*, when followed by *c*, becomes *ç*.

The commentator's illustrative examples are *ahñç ca sarvān jambhayan* (iv.5.1²), *ṛtāñç ca tasya nakshatriyām ca* (vii.1.3²: G. M. omit *ca*), and *karnāñç cā 'karnāñç ca* (i.8.9³). The counter-examples, to show that only *n* is so changed, and *n* itself only before *c*, not before other palatal mutes, are *çam ca me* (iv.7.3¹) and *tāñ chandobhir anu* (i.5.9⁷: G. M. omit *anu*).

The nature of the conversion taught in this rule, and of the kindred ones forming the subject of rules vi.14 and ix.20, as being a historical, not a euphonic process, has been sufficiently explained and illustrated in the note to Ath. Pr. ii.26. At the same place will be found noted the usage of the other Vedic texts as regards the *sandhi* ñç: the Atharvan and the Vājasaneyi-Saṁhitā make it uniformly, the Rik only occasionally. In the Tāittiriya-Saṁhitā it is prevailingly usual: I have noted thirty-nine examples of it, against the eight exceptions mentioned in the next rule.

The definition of the *sandhi*, of course, is not complete without the aid of rules xv.1-3, which teach that, where *n* has been converted into a sibilant, the preceding vowel is nasalized, or has *anusvāra* added to it. A better course, according to our understanding of the history of the phenomenon, would be to teach the insertion of a *s* (or *visarjanīya*) and the change of *n* to *anusvāra* before it: but the makers of the Prātiçākhyas concern themselves much less about the theoretical accuracy than the mechanical aptitude of their rules.

नायन्नैरयन्नाध्रुवन्ननडान्धृणीवान्वाहणानेवास्मिन् ॥ २१ ॥

21. But not the *n* of *āyan*, *āirayan*, *ārdhnavan*, *anaḍvān*, *ghṛnīvān*, *vāruṇān*, and *evā 'smin*.

The passages are: *lokam āyañ catasrah* (v.2.3⁴), *yām āirayañ*

20. *çakāraparo*¹ *nakārah çakāram āpadyate. yathā*²: *ah*.....: *ṛt*.....: *kar*..... *nakāra iti kim*: *çam*.....: *capara iti kim*: *tāñ*..... *cah*³ *paro yasmād asāu caparah*.

¹ G. M. *caparo*. ² O. om. ³ G. M. O. *çakārah*.

21. *eteshu*¹ *grahāṇeshu nakārah çakāram nā 'padyate caparo 'pi. yathā*²: *lo*.....: *yām*.....: *loka*.....: *anaḍ*.....: *ghṛn*.....: *vār*.....: *evā*..... ²*evē 'ti kim*:³ *asm*.....

¹ G. M. *eshu*. ² G. M. O. om. ³ B. om.

candramasi (i.1.9³), *loka ārdhnuvaṇ caruṇā 'smiṇ* (v.5.1⁵: only G. M. have the first word), *anadvāṇ ca me dhenuṇ ca me* (iv.7.10²), *ghrñvāṇ cetati tmanā* (iii.5.11¹), *vāruṇāṇ catuṣṭhkapālān nir va-pet* (ii.3.12¹: only W. has the last two words), and *evā 'smiṇ cak-shur dhattah* (ii.2.9²⁻⁴; 3.8²). *Evā 'smiṇ* is found once more, in a slightly different connection, at ii.3.8¹: the others occur only in the passages cited. A counter-example, *asmiṇṇ cā 'mushmiṇṇ ca* (vii.3.4^{1,52}) is given to prove the need of specifying *eva* before *asmiṇ*.

By rule 24, below, the *n* in all these cases is assimilated to the *c*, and should be so written in the text. My own manuscript of the *Sanhitā*, in fact, follows the authority of the *Prāṭicākhya*, and represents the assimilated nasal in the same manner as an assimilated *m*, except in a single case (*ārdhnuvaṇ car-*). The Calcutta edition, however, in the part hitherto published, gives *n c* only once (i.1.9³), and everywhere else *n c*.

तकारश्चकारश्च शचहपरः ॥ २२ ॥

22. A *t*, when followed by *ç*, *c*, or *ch*, becomes *c*.

The form assumed by initial *ç* after this assimilation is taught in rules 34–37, below.

The commentator's examples are: *tac chaṇḍyoḥ* (ii.6.10^{2,2-2}), *tac cā 'daduḥ* (vii.1.5³), and *tac chāṇḍasām chandastvam* (v.6.6¹). He proceeds to point out that the *ç*, *c*, and *ch*, all mentioned in the rule as upon the same footing, are to be understood as original (not the products of previous euphonic processes), that being their chief or primary value: otherwise the mention of *ç* at all would be superfluous; since, the *ç* being (by v.34) ordered changed to *ch* after a mute, it would be enough for this rule to say "when followed by *c* or *ch*." Moreover, if the later rule were applied, then, after it, the application of the earlier rule would not be suitable (*svarasa*, 'having its own proper flavor; the word is not used elsewhere), as it would constitute an offense against the third rule of this chapter.

22. *çacachaparas takāraç cakāram āpadyate. yathā: tac.....: tac.....: tac..... atra çacachapara iti sāmānyoktānām' nimit्तानām' prakṛtitvaṇ' vijñeyam: mukhyatvāt: tatra' prakṛta-vāikṛtayoḥ prakṛtam' mukhyam: anyathā çakāragrahaṇavācīyarthāt: kuto vācīyartham: sparçapūrvah çakāraç çakāram* (v.34) *iti çakārasya chatve kṛte takāraç cakāram çachapara' ity etāvatai' va siddher' iti brūmah. kiṁ ca: parasūtre pravṛtte sati paçcāt pūrvasūtraprasaraṇam na svarasam': tatra pūrvampūrvam prathamam* (v.3) *iti niyamabhaṅgaprasaṅgāt*¹⁰.

¹ G. M. B. O. -nyeno 'kt. ² W. O. prant. ³ G. M. prakṛtitva. ⁴ G. M. om. ⁵ G. M. -tatvam. ⁶ G. M. -yoc ca. ⁷ G. M. B. çacacha. ⁸ G. M. siddh. ⁹ G. M. bhavati. ¹⁰ G. M. nyāyabh.

नयरो ङकारम् ॥ २३ ॥

23. When followed by *j*, it becomes *j*.

The cited example is *taj jayānām jayatvam* (iii.4.4): rather superfluously, a counter-example is also given: *tat pravāte* (vi.4.7²).

नकार एतेषु ङकारम् ॥ २४ ॥

24. A *n*, before the same letters, becomes *ñ*.

As *eteshu* is plural, we are obliged, having recourse to that which lies nearest, to regard as implied the letters pointed out in the last two rules as requiring certain changes in those that precede them: that is to say, *ç*, *c*, *ch*, *j*. These are, in fact, the whole class of palatals, since *ñ* never occurs at the beginning of a word, nor, indeed, in any independent position, and since *jh* is found nowhere in any Vedic text. The dental *n*, then, never maintains itself before a palatal, but is assimilated to it. The other treatises teach virtually the same doctrine: see note to Ath. Pr. ii.11.

The commentator's illustrative example for *n* before *ç* (where, to complete the combination, rule 34 below has also to be applied) is *tenāi 'vāi 'nān chamayati* (iii.4.8⁴). As for *n* before *c*, he points out that the rule applies only to the cases where the *n* does not become *ç* by v.20, as excepted by v.21, and quotes again one of the examples given under the latter rule, *lokam āyañ catasrah* (v.2.3⁴). Before *ch*, he gives the phrase already quoted as counter-example under v.20, *tān chandobhir anu* (i.5.9⁷); and before *j*, *aparāpam ātman jayate* (iii.5.7⁹). As general counter-example, finally, he gives *tānt subdhān* (ii.4.1¹), where *n*, coming before *s*, is treated in a quite different manner.

The occurrence of *n* before *ch*, which does not once happen in the Atharvan, is found not less than nine times in the Taittiriya-Saṁhitā. My own MS. reads every time *nch*, combining the dental nasal with the palatal aspirate. The Calcutta edition, at the only place which it contains as yet, reads *ñch*.

23. *sāmnidhyāt takāra iti labhyate: japarā takāro jakāram āpadyate. yathā: taj----- evampara iti kim: tat-----*

¹ G. M. om.

24. *eteshu iti bahuvacanānirdeṣāt pratyāsannam evā 'napekshya' sātradvayastheshu paranimitteshu sampratyayaḥ²: tasmād eteshu iti: çacachajeshu³ parata⁴ ity arthaḥ: nakāro ñakāram āpadyate. yathā: te----- çatvāpattāu nishiddho⁵ yo nakārah so 'tra coparatvena vishayikriyate. lok-----: tāñ-----: apa----- evampara iti kim: tānt-----*

¹ W. -rdiç. ² G. M. 'navek-. ³ G. M. praty-. ⁴ W. O. -chabhujeshu. ⁵ W. para; G. M. parashu. ⁶ G. M. om. ⁷ G. M. B. O. put after *yo*.

The combination of final *n* with initial *j*, producing, according to all the phonetic text-books (with trifling exceptions: see note to Ath. Pr. ii.17), *nch*, is decidedly of more common occurrence. But here, too, my own MS. reads, with but a single exception among the cases which I have noted, *nch*: the Calcutta text is inconsistent with itself, now giving *n̄* (as at ii.2.12³), now *n* (as at i.3.9¹).

Final *n* is found yet more frequently before initial *j*, or some scores of times in all. As regards its method of writing the combination, my manuscript is about equally divided between *nj* and *n̄j*. The Calcutta text is equally wavering; and there is no approach to consistency between the two authorities, or to recognizable principle in either: in both alike, the variation seems wholly accidental and arbitrary.

Such being the case, I think it clear that a careful editor of the *Tāittiriya-Saṁhitā* ought to disregard, as of no authority or consequence, the variations, or the unanimity, of his manuscripts upon all these points, and to adopt uniformly the reading prescribed by the *Prāticākhya* (either *n̄* or *n*), wherever a final *n* comes to stand before a palatal mute.

लपरो लकारम् ॥ २५ ॥

25. Both *l* and *n*, when followed by *l*, become *l̄*.

The dual *laparāu* indicates that the *l* and *n*, already treated of, are the letters aimed at in this rule, says the commentator. He cites as examples *yāl lohitam parāpatāt* (ii.1.7²: G. M. omit the last word), and *trīṇ lokān ud ajayat* (i.7.11³: only G. M. have *ud ajayat*). The combination of *n* and *l* is finished by the next rule, and will be further remarked upon in the note thereto.

नकारो ञ्नुनासिकम् ॥ २६ ॥

26. The *n* becomes nasalized *l̄*.

As the nasal quality of *n* itself is already established by rule ii.30, explains the commentator, it could not properly be defined here again as nasal. Hence the *anunāsikam* of the present precept must be understood as qualifying the *l* of like position into which the *n* is converted: this *l̄* is to be a nasal *l̄*. No additional example is given, the combination having been illustrated under the preceding rule.

There are in the *Tāittiriya-Saṁhitā* over a hundred cases of the meeting of final *n* with initial *l*, and in fully two-thirds of them

25. *devācanasāmarthyād' gṛhitāu prakṛtāu' lakāranakārdū lakāram āpadyete' laparāc. yathā': yāl....; trīṇ..... lak' paro yābhyān tāu laparāc.*

¹ G. M. -*thya*. ² G. M. om. ³ MSS. -*yate*. ⁴ G. M. om. ⁵ G. M. *lakārah*.

my MS. reads *n* simply, without attempting any accommodation of the two sounds to one another. In the remaining cases, it treats the *n* in the same way as it would treat a *m*, substituting for it the ordinary *anusvāra* dot over the preceding *akṣara*. The Calcutta text varies between *n* and *ñ*. Here, as in the cases treated above, there seems to be every reason why an editor should follow one consistent method, as the irregularities of the manuscripts have no ground but accident—and, not less certainly, the method prescribed by the *Prāticākhya* is the one better entitled to be followed. As to the way in which the nasal *l* shall be represented, there may be some question. As I have already mentioned (note to ii.30), I cannot think that the designation of the Calcutta edition is at all to be commended, since it properly implies the insertion of an *anusvāra* between the preceding vowel and a doubled *l*, and thus quite distorts the character of the combination—except as this is viewed by *Ātreya*, as noted in a later rule (v.31). The method followed in my MS., on the other hand, is theoretically unobjectionable, since there is no phonetic difference recognized, or to be recognized, by phonetic theory between the combination of *n* and *l* and that of *m* and *l*: it has only the practical inconvenience of not distinguishing to the eye these two combinations—and this is of very small account, since there can be few if any cases where the least ambiguity would result. If the nasal *l* is to be written separately, it should properly have the *virāma* beneath and the sign of nasality over it. That is to say, one ought always to print either अस्मिन् लोके or अस्मिं लोके, not अस्मिंलोके.

In romanized text, as the assimilated *m* is represented by *m̐*, so, by an analogous method and for the sake of convenient distinction, the assimilated *n* may be very suitably represented by *n̐*; and this is the sign with which I have chosen to write it, both before *l* and before the palatals.

All the *Prāticākhyas* (see note to Ath. Pr. ii.35) agree in converting both *n* and *m* before *l* into a nasal *l*.

मकार स्पर्शपरस्तस्य सस्थानमनुनासिकम् ॥ २७ ॥

27. A *m*, when followed by a mute, becomes the nasal of like position with it.

The commentator's examples are *yañ kāmāyeta* (i.6.10⁴ et al.), *gañ ca me* (iv.7.3¹), *tañ te duṣṣakṣāh* (iii.2.10²), and *tañ prat-*

26. *anusvārotthamā' anunāsikāḥ* (ii.30) *iti nakārasya' nūnāsikatve siddhe' punar atra' pi tatkāthanam anupapannam: tasmād atra lakṣaṇayā nakāro nāma tatsthāno lakāra' ity arthah: asāv' anunāsikam bhajate'. pārvoktam eco' dāharanam.*

¹ W. *nann anundard*. ² G. M. *ins. 'pi*. ³ G. M. *nak*. ⁴ G. M. *ins. lakāro*. ⁵ G. M. *bhajeta*.

nathā (i.4.9). Of *m* before a lingual he is able to give no example, as such a concurrence is not to be found in the *Sanhitā*: add to

ग्रन्तस्यापरश्च सवर्णमनुनासिकम् ॥ २८ ॥

28. Followed by a semivowel, it becomes a nasal of like quality with it.

From the class of semi-vowels is excepted *r*, by the next rule. Examples are given for the others, as follows: *saṁyattā āsan* (i.5.1² et al.), *suvarṇam lokam* (i.5.4⁴ et al.), *saṁvatsarah* (i.5.1² et al.: the *pada*-text, like that of the Atharvan, reads *saṁvatsarah*, while that of the Rik leaves the word undivided). No attempt is made in the manuscripts or the printed text of the *Sanhitā* to give a special representation to these nasal semi-vowels standing for an assimilated *m*: it is left to be understood that the sign of nasality over the preceding *akṣara* stands for a nasal letter of like quality with the following consonant in the case of the semi-vowels, just as in that of the mutes, provided for by the preceding rule. Nor are the manuscripts of the *Prāṭicakhyā* and its commentary any more particular—saving that G. M. usually write, instead of *my*, the combination *yy*, without any sign of the nasality of the first *y*.

Only the Ath. Pr. disagrees with our treatise in its treatment of *m* before the semi-vowels, acknowledging no nasal *y* or *v*, but a *l* alone (see note to Ath. Pr. ii.35).

The commentator explains the word *anunāsika*, 'nasal,' in the rule, by *anunāsikadharmavigīṣṭa*, 'distinguished by nasal quality,' but afterward raises a difficulty over it, in terms which imply that he regards it as a noun, 'a nasal,' asking, how we are to understand it here as equivalent to *sānunāsika*, 'combined with nasality.' As it is, in fact, originally and properly an adjective, signifying 'possessed of nasal quality,' and is constant-

27. *sparṇaparo makāras tasya sparṇasya sasthānam anunāsikam* bhajate. yathā: *yam*---: *gam*---: *taṁ*---: *tam*---. *saṁānam sthānam yasyā 'sau sasthānaḥ*: *taṁ*: *sparṇaḥ paro yasmād asau sparṇaparaḥ*.

¹ W. om. ² G. M. om. ³ B. G. M. om.

28. *cakāro makāram anuḍiṣati: antasthāpāro makāras tasyā antasthāyāḥ savarṇam sadṛṣam anunāsikam* anunāsikadharmavigīṣṭam bhajate. yathā: *yam*---: *su*---: *sa*---. *nāne anunāsikam ity anena sānunāsikam* ²*katham labhyate*. *ucyate: 'nītarām parihārah'*: *yato dharmavācakah* ³*gabdo dharmaṇam* ⁴*api* ⁵*kathayati: 'śuklaḥ paṭo nilam utpalam ity ādicat'*.

¹ B. O. om. ² W. om.; O. *ity anena sānunāsikam katham upalambhāmaḥ*; G. M. *sakalam upalambhāmaḥ* yathā. ³ O. om. ⁴ W. *dharmega*. ⁵ W. *avika*; O. *ari*. ⁶ G. M. ins. yathā. ⁷ G. M. *ādi*.

ly so used and applied in the *Prāticākhya*, the difficulty is worse than hair-splitting; it is a downright perversion. The answer by which it is met is a quibble worthy of being matched with it: "because a word expressing a quality also designates the object possessing that quality; as, for example, when we say 'a white cloth,' 'a blue lotus.'" As if the words "white" and "blue" strictly applied to the color alone, and did not just as properly mean 'of white color,' 'of blue color'!

न रेफपरः ॥ २९ ॥

29. But not when followed by *r*.

R being also a semi-vowel, *m* would be converted into a corresponding nasal before it by the previous rule, but for this special exception. The instances given of the treatment of *m* before *r* are *prā samrājām prathamam adhvārānām* (i.6.12²; G. M. have only the first two words), and *sāmrajyāya sukrātuh* (i.8.16¹). They are particularly ill selected, as neither case comes under the action of the preceding rule; they fall, rather, under xiii.4, and are, in fact, the two passages there given as examples of the peculiar treatment of *sām* before *rāj*. We ought to have, instead, such passages as *pratyushtaṁ rakshaḥ* (i.1.2¹), *vī vayan ruhema* (i.1.2²)—which, of course, are of exceedingly frequent occurrence in the *Sanhitā*.

The omission of *m* before *r*, and the nasalization of the preceding vowel, or the insertion of *anusvāra* after the latter, are taught below, in rules xiii.2, xv.1–3. The written and printed texts are consistent in their recognition of the mode of combination thus prescribed, always setting the proper *anusvāra* sign before *r*, while before *y*, *l*, *v* they write the assimilated *m* just as before the mutes.

यवकारपरश्चैकेषामाचार्यणाम् ॥ ३० ॥

30. Nor, according to some teachers, when followed by *y* or *v*.

The authorities referred to, of course, would leave the *m* to be treated before these letters as before *r*, and would acknowledge no

29. *antasthātēād rephaparasyā' pi makārasya tatsavarṇānunanāsikaprāptir' anena nishidhyate: na khalu rephaparo' makārah pūrvoktam bhajate. yathā: pra..... sām..... rephah paro yasmād asāu rephaparah.*

¹ G. M. *rephasya tatp.* ² G. M. *-kāpattih prāptā.* ³ G. M. *-pakāro.* ⁴ G. M. *om.*

30. *cakāro nishedhānvādeṣakah': prakṛto' makāra ekeshām ācāryānām pakṣhe yakāraparo vā' vakāraparo' vā na savarṇam anunāsikam bhajate. yathā: sām: sām.*

¹ G. M. *-ākarshakah.* ² W. B. *prāk.* ³ B. O. *om.* ⁴ B. *om.* ⁵ G. M. *om.*

nasal semi-vowel save *l*. Their opinion is again quoted in connection with the rule respecting the actual treatment of *m* before *r* (xiii.3), and the commentator there calls attention to the fact that the "some teachers" spoken of are the same with those here noticed: who they are, he does not attempt to tell us. The view held by them is the same with that taken by the Atharva Prātiçākhyā, as pointed out above (see Ath. Pr. ii.35, and the note upon it); but, until we know much more than we do at present of the history and mutual relations of these phonetic treatises, it would be highly venturesome to conclude that the authors of this Prātiçākhyā had here in mind the other one and its authors.

I find it difficult to discover any good phonetic reason why the assimilation of *m* should not yield a like result before all the semi-vowels, and why, if we are to admit an *anusvāra* at all, it would not find a particularly appropriate place as representing the sound into which *m* might naturally pass before *y*, *r*, *l*, and *v*.

As examples, are repeated *sainvatsarah* and *sainyattāh* (see under rule 28, above).

उत्तमलभावात्पूर्वे ञ्नुनासिक इत्यात्रेयः ॥ ३१ ॥

31. Ātreya holds that, when a nasal mute becomes *l*, the previous vowel is nasalized.

As has been pointed out above, Ātreya's view of the combination is the one represented accurately by the mode of writing adopted in the Calcutta edition. It is not elsewhere supported in the Prātiçākhyas. Its quotation here seems a little unprepared, or the expression of it given in the rule imperfect, as we have been directed to convert *m* and *n*, not into *l*, but into a nasal *l*. One might think, too, that it would be in better place at the beginning of chapter xv., where certain other differences of opinion on kindred points are rehearsed.

The commentator gives Ātreya the title of *muni*, 'sage,' instead of *ācārya*, 'teacher.'

To illustrate the sage's style of making the combination, he cites *trīṇ lokān* (i.7.11¹) and *suvarṇaṇ lokam* (i.5.4² et al.); but not one of the manuscripts of the commentary takes the pains to write the extracts as they should be written, to serve their purpose as illustrations. Finally, he adds the caution that "this rule and the preceding are not approved."

उपूर्वः ककारः सप्तकारपरः ॥ ३२ ॥

31. *uttamasya nakārasya makārasya vā labhāvāl lakārāpatteḥ pūrcasvaro 'munāsiko bhavati 'ty ātreya nāma munir manyate. yathā: trīṇ.....: suv..... uttamayor labhāva uttamalabhāvah³: tasmāt.*

sūtradevayam etad anisṭam.

¹ G. M. put before *nak*. ² G. M. om. ³ G. M. om.

32. After *ñ* is inserted a *k* before *s* and *śh*.

The commentator's examples are *pratyāñk somo atidrutah* (i.8.21: but G. M. have instead *sadrūk samānūh*, ii.2.8²), and *pratyāñk śhadaho bhavati* (vii.4.2²; O. G. M. omit *bhavati*). As counter-examples, showing that the insertion is made only under the circumstances specified, he gives *pratyāñ hotāram* (vi.3.1²), and *tat savituh* (i.5.6⁴ et al.) and *tat śhodagī* (vi.6.11¹).

The combinations here treated of are not otherwise than rare in any Vedic text. In the Taittiriya-Saṃhitā I have found no other instance of the meeting of *ñ* and *śh* than the one quoted; of *ñ* before *s*, besides the two here given, occur two others, at vi.3.1⁶ and iv.4.4⁷⁻⁸; but, in the latter passage, the division of the section into half-centuries falls between the two letters, as the text is at present written, and prevents the exhibition of the *sandhi*. Neither the Calcutta edition (so far as yet printed) nor my manuscript makes in any of these passages the insertion required by the Prāticākhya: and it may properly enough be considered a question whether the latter's authority ought to be followed in a matter of this character, any more than in regard to the duplications which form the subject of chapter xiv. Nevertheless, considering the phonetic reasonableness of this particular insertion, and its close analogy with that of *t* between *n* and *s* (see the next rule), I should myself decidedly incline to write *ñk s* and *ñk śh*. The manuscripts of the commentary, it should be remarked, try to follow the directions of the rule, W. B. O. reading *ñks*, and W. O. *ñkśh* (with the *k* and *śh* united in the usual sign for *kśh*); while G. M. even yield to the requirement of xiv.12, and give us *ñkhs* and *ñkhsśh*. This last is a refinement which no one, probably, would care to see introduced into our printed texts.

As is shown in detail in the note to Ath. Pr. ii.9, the teachings of the Ath. Pr. and Vāj. Pr. are virtually in agreement with those of our own treatise as regards the insertions prescribed in this rule and the next, while the Rik Pr. merely mentions them as enjoined by some authorities.

टनकारपूर्वश्च तकारः ॥ ३३ ॥

33. After *t* or *n* is inserted a *t*.

The examples given for these combinations are *vashatt sevāhā* (vii.3.12 nine times), and *vidvānt somena yajate* (iii.2.2²); and, in order not to be without an illustration for the collision of *t* with *śh*, one is dragged in from the *jātā*-text: *anāyājāu śhatt śhad anāyājāu anāyājāu śhat* (vi.6.3²): to which G. M. even add, from the

32. *sakāraparah śhakāraparo vā kakāra āgamo bhavati nāpārvaḥ yathā: praty-...: praty-...: evampara iti kim: praty-...: evampārva iti kim: tat-...: tat-...*

¹ G. M. ins. ed.

same source, *tānt subdhānt subdhāns tāns tānt subdhānt* (ii.4.12). Counter-examples are *śad vā ṛtavah* (iii.4.8^o), and *tān rudrā abruvan* (v.5.2^o).

The final lingual *t* occurs before *s*, according to my notes upon the text, in ten other passages (iii.2.8¹ eight times: iv.4.8¹; 6.1⁴; v.4.3⁴, 4²; 5.2⁶; vi.2.3⁴; 6.3³; vii.1.5¹; 4.10²); and my MS. does not once employ the intermediate *t*. The manuscripts of our commentary, however, all introduce it; and this time B. abets G. M. in converting it into *th*, by rule xiv.12. The combination is without doubt a very troublesome one, in the demand it makes upon the tip of the tongue: but whether the transition is helped by the intrusion of a *t* is a much more serious question—and one to exercise and gratify the subtlety of a Hindu phonetist. The Ath. Pr. also requires *tts* (ii.8), but the Rik Pr. (iv.6) only notices the mode of *sandhi* as enjoined by certain teachers.

It is indeed true that the strict letter of the rule requires a *t* to be inserted between a *t* and *śh*, as illustrated by the commentator from the *jatā*-text. But it would be wholly preposterous to suppose that the authors of the Prāṭiśākhya intended to teach any such insertion—which would convert the consonant combination from one wholly natural and easy to one in a high degree harsh and difficult, if not absolutely impossible. They evidently relied on the non-occurrence of *śh* after *t* anywhere in the Saṁhitā for the annulling of that part of the rule's prescription—either having no regard to a *jatā*-text, or overlooking the fact that in it the two letters would come in contact.

Twice in the Tāittiriya text we have a final *t* before an initial *śh* (at v.5.2⁶; vii.5.6²). Although their collision might seem to call for mediation in somewhat the same manner as that of *t* and *s*, the Prāṭiśākhya makes no special provision for it, and the manuscript text simply combines the two letters.

The meeting of final *n* with initial *s*, the other case contemplated by the rule, is very frequent (there are sixty instances in the first two *kāṇḍas*: I have not collected them through the whole text). Neither the printed text nor my manuscript is absolutely faithful in inserting the prescribed *t*; yet I have found but six cases in the whole Saṁhitā in which the latter omits it; and out of the seven passages in *kāṇḍas* i. and ii. where the former leaves it out, my manuscript confirms the omission in only one. As the requirement of the Prāṭiśākhya receives so much support from the usage of the scribes, and also accords with the prescriptions of the Ath. Pr. (ii.9) and Vāj. Pr. (iv.14), there can be no question that it ought to be followed by an editor of the Tāittiriya Veda.

33. *cakārah sashakārāv anvāḍiḡati: takārapārvo vā nakārapārvo vā takāra āgamō bhavati sashakāraparah. vash-
vid-...: anā-...: tānt-...: evampara iti kim: śhaḍ-...:
tān-...*

स्पर्शपूर्वः शकारश्चकारम् ॥ ३४ ॥

34. A *ç* preceded by a mute becomes *ch*.

The commentator gives only an example of a *ç* converted into *ch* after *t*, the *t* at the same time becoming *c* by rule 22, above: *çarac chrâutri* (iv.3.2²). He adds a counter-example, *âçuh çigânah* (iv.6.4¹). The occurrence of any other final mute than *t* and *n* (for which an example is given above, under rule 24) before initial *ç* is very rare (excepting *m*, for which see the following rule); and it is properly only after a dental, or after a dental or lingual, that the conversion here prescribed has good phonetic ground—namely, in the coalescence of a *t*-sound and a *sh*-sound into the compound sound of our *ch* in *church* (see note to Ath. Pr. ii.17). There is one case of a preceding *t* (i.3.14⁶), where my MS. reads, as the Prâtishākhya directs, *t ch*, while the Calcutta text has *t ç*. A single case of preceding *p* is treated of below, in rule 36.

न मकारपूर्वः ॥ ३५ ॥

35. But not when preceded by *m*.

By this rule, says the commentator, is annulled the conversion of *ç* to *ch* after *m*, which would otherwise be in order (according to the preceding rule), since *m* is a mute. He instances *sañçitam me* (iv.1.10² and v.1.10²) and *sañçavā ha* (i.7.2¹). Being thus specially exempted from the operation of the foregoing rule, this combination, of course, falls under xiii.2 and xv.1-3, and the *m*, as before other spirants, becomes *anuscāra*. An objection is raised against the pertinence of the present precept, on the ground that xiii.2 directs the omission of *m* before a spirant, and that hence there could arise no occasion for any such conversion of *ç* into *ch* as is here contemplated and guarded against. The reply, however, is a very easy one; that, by rule 3 of this chapter, the requirement of the conversion into *ch*, as it is stated earlier, would have to be applied first, and that the result of so doing would be to pro-

34. *çakāraç çakāram āpadyate sparçapārvaḥ*. *yathā*: *çarac*..... *evampārva iti kim*: *âçuh*..... *sparçah pārvo yas-mād asdu sparçapārvaḥ*.

¹ G. M. puts first. ² W. G. M. om.

35. *makārapārvaḥ çakāraç çakāram nā* "padyate. *yathā*: *sañ*.....: *sañ*..... *sparçatvān makārasya 'tatpāreç' çakāre prāptam chatvām anena nishidhyate. nane etad anupapannam*: 'atha *makāralopah*' (xiii.1): *rephoshmapārah* (xiii.2) *iti makārasya lopavidhānān na çakārasya chatvāpattinimittam asti* 'ti. *māi 'eam*: 'chatvāpādakam malopāpādakāt pūrcam: *atus*' tatra *pārvampārvam prathamam*' (v.3) *iti nyā-*

duce, in the passage already quoted, the reading *sañchitam me brahma*; which is wrong.

पकारपूर्वश्च वाल्मीकिः ॥ ३६ ॥

36. Nor, according to Vālmiki, when preceded by *p*.

There is but a single case in the Sanhitā of *p* before *ç*, namely the one here quoted by the commentator, *anushtup çhārādī* (iv.3.2²): so my manuscript reads, according to the requirement of rule 34, above. Vālmiki thinks it would be better to read *anushtup çhārādī*—and I presume we shall have little hesitation in approving his opinion.

व्यञ्जनपरः पौष्करसादेर्न पूर्वश्च जकारम् ॥ ३७ ॥

37. Nor, according to Pāushkarasādi, when followed by a consonant; and a preceding *n*, in that case, does not become *ñ*.

This translation is made in accordance with the commentator's exposition. One might be tempted to understand the last part of the rule otherwise, not regarding the continuance of the negative as implied from the other part; translating 'and a preceding *n* becomes *ñ*;' but, besides the authority of the comment against it, this would be a mere repetitious enactment of the rule already given above (v.24). The inquiry is raised, how we know that *pār-vaḥ*, 'the preceding letter,' means here 'a preceding *n*.' The reply is, because only *n* is liable to conversion into *ñ*, and annulment is only made of that which would, without direction to the contrary, be liable to take place.

The examples given to illustrate this peculiar view of Pāushkarasādi are *ādityān smaçrubhāḥ* (v.7.12), and *pāpīyān çreyase* (i.5.7⁴). The edition has *pāpīyān çhreyase* in the latter passage, in accordance with the approved rules of the Prāticākhya; but my MS. seems to have been written by a sectary of Pāushkarasādi at this point (namely, in the margin: a line or two of the context was omitted just here by the original scribe). In the former, I

*yena chatvam eva pūrvam*¹⁰ *kartavyam syāt: tathā sati makāra sparças*¹¹ *tatpare*¹² *çakāre chatvam*¹³ *āpanne sañ-*.... *iti syāt: tan mā bhūd ity etat sūtram upapannam eva.*

(¹⁰) B. om., excepting *lobavidhānān na*. (¹¹) G. M. -*vasya*. (¹²) G. M. -*rasya*. (¹³) G. M. put before *prāptam*. (¹⁴) G. M. O. om. (¹⁵) G. M. put before *astī*. (¹⁶) G. M. -*ttatvān*. (¹⁷) G. M. *chatvāpādakasya sūtrasya malopasya ca chatvāpādakasyai* 'va sapūrvatvāt. (¹⁸) W. B. O. om. (¹⁹) G. M. om. (²⁰) B. -*ça*. (²¹) G. M. *tasye* 'ti makāre ñakaram. (²²) B. *pare*.

38. *çakārah pratishedhārthakah*¹: *vālmiker matē pakārapār-vaḥ*² *çakāraç çakāram*³ *nā*⁴ *padyatē yathā: an-*....

(¹) B. G. M. -*dhākaraçhakah*. (²) G. M. *paçā*. (³) G. M. *chatvam*.

find the reading *ādityān chmagrūbhīh*, which would satisfy neither side. There is one other case of the collision of *n* with *gr* (at vi.6.7²), where I find read *n chr.* So also, at v.7.1² my MS. has *n che*; and at vii.3.14, *n chy*. These are the only instances, I believe, which the text affords of the combinations contemplated by the rule.

The commentator, at the end, declares this rule and the preceding not approved, and with reason: the evident intent of the treatise is that the conversion of initial *g* to *ch* shall take place in all the cases falling under rule 34.

प्रथमपूर्वो हकारश्चतुर्थं तस्य सस्थानं प्रान्निकीण्ड-
न्यगौतमपौष्करसादीनाम् ॥ ३८ ॥

38. According to Plākshi, Kāuṇḍinya, Gāutama, and Pāushkarasādi, a *h* preceded by a first mute becomes a fourth mute corresponding with the latter.

The examples of this, the approved and customary combination of an initial *h* with a final surd mute, are, as given by the commentator, *arāg ghy enām* (vi.3.3¹), *śarad dhavā ācāsyā* (v.3.12²: G. M. omit *ācāsyā*), and *tad dhiranyam* (v.4.2³ and vi.1.7¹). In giving the first two quotations, W. O. G. M. (following a vicious and indefensible mode of combination, which occasionally appears even in carefully written Vedic manuscripts, and has incautiously been admitted into some edited texts) write *ghgh* and *dhgh* instead of *ggh* and *dgh*; and in the latter of them my MS. of the Sāhita does the same (see the note to xiv.5). As counter-examples, establishing the restrictions imposed by the rule, we have *pratyāṅ hotāram* (vi.3.1⁵), *vāk ta ā pyāyatām* (i.3.9¹), *vashat te* (ii.2.12⁴); and, in W., *ā tishthipat te* (iv.6.9⁴), but in all the other MSS. *tat te* (i.3.9¹ et al.).

This is one of several instances in which the Prāticākhyā, instead of stating first, categorically, its own doctrine, and then mentioning others at variance with this, puts forward the conflicting views of different authorities, without appearing itself to decide in favor of any one against the rest. The commentator here points out (at the end of the chapter) that the present rule presents the accepted doctrine of the treatise, the three that follow being dis-

37. pāushkarasāder mate vyañjanaparāḥ cakāra sparṣapāro
'pi chateam nā "padyatē: cakārapāro nakāraḥ ca nakāram nā
"padyate. yathā: ād----- pāp----- pārva ity ukte nakāra
iti katham labhyate. ākārapattir asyāi 've 'ti brāhmaḥ: prasak-
tasyāi 'va' hī pratishedhāt. vyañjanam asmāt param iti vy-
añjanaparāḥ.

nāi 'tat sūtradvayam iṣṭam.

¹ W. om. ² G. M. om. eva. ³ B. O. om. ⁴ G. M. -dhah.

मीमांसकानां च मीमांसकानां च ॥४१॥

41. As also, according to the Mīmāṃsakas.

The especial mention, in a separate rule, of the agreement of this school with the view of Āitiyāyana and his abettors, is made, says the commentary, with an honorific intent.

He adds, as was above remarked, that rules 39 to 41 are disapproved.

CHAPTER VI.

CONTENTS: 1-5. conversion of *s* and *h* into *śh*; 6-13, exceptions and counter-exceptions; 14, insertion of *s* between final *a* and initial *t*.

अथ षकारः सकारविसर्जनीयौ ॥१॥

1. Now for conversions of *s* and *visarjaniya* into *śh*.

An introductory heading to the rules of this chapter—excepting the last rule.

स्वानासोद्व्यापोक्ष्यमुकमूमोप्रोत्रीमह्यविपद्यग्र-
हपूर्वः ॥२॥

2. A *s* is converted into *śh* when preceded by *svānāso divi*, *āpo hi*, *ayam u*, *kam u*, *ū*, *mo*, *pro*, *tri*, *mahi*, *dyavi*, *padi*, or a former member of a compound.

The illustrative passages, as given by the commentator, are as follows: *uta svānāso divi shanto agneḥ* (i.2.14⁷: only O. has *agneḥ*; B. omits both that and the preceding word): with the

41. *caḥārah pūrvoktavidhim anvāḍigati: mīmāṃsakānām cā 'ntarāgamamatān sammatam. pūrvoktam eva 'dāharanam. mīmāṃsakānām pājārtham prthaksātrārāmbhah.*

nāi 'tat sūtratrayam iṣṭam.

*iti tribhāshyaratne prātiśākyavivarane
pañcamo 'dhyāyaḥ.*

⁷ G. M. om. to here.

1. *athe 'ty ayam adhikārah: sakāravisarjaniyāu śhakarām āpadyete ity etad adhikṛtaṁ veditavyam ita uttarām yad cak-shyāmaḥ.*

counter-example *ṛtīyasyām ito divi soma āsit* (iii.5.7¹), to show the powerlessness of *divi* to effect the change except after *svānā-sah*. Then *āpo hi shthā mayobhuvah* (iv.1.5¹; v.6.1⁴; vii.4.10⁴): only G. M. have the last word): the necessity of *āpo* is shown by the counter-example *na hi svah svān hinasti* (v.1.7¹). Next *ayam u shya pra devayuh* (iii.5.11¹), and *kam u shvid asya senayā* (ii.6.11²): with the counter-example *tad u soma āha* (iv.2.8¹), to prove that *u* changes *s* only after *ayam* and *kam*. For *ā*, the example is *ūrdhva ā shu na ātaye* (iv.1.4²: only G. M. have the first word): the other passages in which it exerts a like influence upon an initial *s* are i.5.11⁵; iii.5.10¹; iv.6.5⁶; v.1.5²; vii.1.18²; 4.17². For *mo*, the only passage is the one quoted, *mo shā na indra* (i.8.3). For *pro*, only *pro she asmāi puroratham* (i.7.13⁵). For *trī*, only *trī shadhasthā* (ii.4.11² and iii.2.11¹). For the three remaining words, also, the text affords only the single examples given by the commentator: *mahi shad dyuman namaḥ* (iii.2.8²), *ya upa dyavi shtha* (ii.4.14⁵), and *padi shītām amuñcatā yajatrāḥ* (iv.7.15⁷: G. M. omit the last word). To the prescription conveyed in the last item of the rule, which seems to demand that every *s* beginning in *pada*-text the latter member of a compound should be changed to *sh*, rule 7, below, makes the very important general exception "not after a consonant or an *a*-vowel;" it means, then, that *s* is so changed after the *i*, *u*, and *r* vowels and the diphthongs. The commentator illustrates only one or two of the cases in which the conversion would be required: *hañsah gucishad vasuh* (iv.2.1⁵; p. *guci-sat*: only G. M. have the first word), *ayā viśthā janayan* (i.7.12²; p. *vi-sthā*: only G. M. have *ayā*), and *goshṭomām dvitīyam* (vii.4.11¹).

I have collected from the Sanhitā all the words coming under the operation of this part of the rule, concerning the initial *s* of the latter member of a compound (just about a hundred in number, and some of them of quite frequent occurrence), but I do not think the list worth the trouble of giving here. So far as regards the Prāṭicākhya and its relation to them, the important point is to determine whether its rules and exceptions precisely cover them—and I have to say that I have not succeeded in discovering any want of exact adaptedness to them. There is a single participle, *anusthita*, whose unaltered *s* is unnoticed and unprovided for in the chapter, but it occurs only as final member of a compound, *viśhvanusthitaḥ* (ii.4.12^{3,4,5}; p. *viśhnu-anusthitaḥ*), and so, not being itself separated into its constituents, is exempted from the action of the present rule.

2. *ity evampārvo vagrahapārvaḥ ca sukārah shakāram āpadyate. yathā: uta.....: svānāsa' iti kim: ṛt-.....: āpo.....: āpa iti kim: na.....: ayam.....: kam.....: ayanākam iti kim: tad.....: ūrdh.....: mo.....: pro.....: trī.....: mahi.....: ya.....: padi.....: hañs.....: ayā.....: go.....: avagrahaḥ pārvo yasmād asād avagrahapārvaḥ.*

¹ W. B. svāna.

असदामासिञ्चश्च ॥ ३ ॥

3. Also *asadāma* and *asiñcan*.

The "also" (*ca*) in this rule implies, the commentator says, that the words mentioned are preceded by an *avagraha*, according to the final specification of the preceding rule: else such passages as *ajāyān gharman prā 'siñcan* (v.4.3²) would fall under the prescribed action. The examples are *yena kāmēna nyashadāme 'ti* (vii.5.2¹; p. *ni-asadāma*), and *mitrāvaruṇāv abhyashiñcan* (i.8.11; p. *abhi-asiñcan*). The rule is given, we are told, for the purpose of ordaining that, in the case of these two words, the conversion into *sh* after an *avagraha* takes place even notwithstanding the interposition of an *a*. Why not, then, puts in an objector, say "even when *a* interposes," without specification of the words concerned? Because, is the reply, the rule would then apply to such cases as *hr̥tsvaso mayobhāt* (iv.2.11³; p. *hr̥tsu-asah*).

उपसर्गनिष्पूर्वे अनुदत्ते पदे ॥ ४ ॥

4. Also in an unaccented *pada*, when a preposition or *nis* precedes.

This rule can apply only to unaccented verbal forms, since they alone can be technically *anudatta* throughout, having the *anudatta* sign written under every syllable. In any compound beginning with a preposition like *pāri*, for instance, having an acute on the first syllable and an enclitic *svārīta* on the second, the syllables of the other member of the compound would not have the *anudatta* accent, but the *pracaya*: such would fall under rule 2 of this chapter. The word *pada* in the rule, we are told, is intended to specify the text: "a word which is *anudatta* throughout in the *pada*-text" is what the *Prāticākhya* means—it being, in fact, impossible that any word should be so accented in *samhitā*-text.

The commentator's examples are, for prepositions, *açmann āramjam iti pari shiñcati* (v.4.4¹), *imam vi shyāmi* (i.1.10² and iii.5.6¹), *sāmrañyēnā 'bhi shiñcāmi* (i.7.10³ twice, and v.6.3³; but B. O. read *shiñcati*, I presume by a copyist's blunder, as I find no such phrase in the text), *yajamāne prati shthāpayanti* (vi.1.4²), and *nī shasāda dhrtavrato varuṇah* (i.8.16¹; only B. O. have *varuṇah*);

3. *asadāma*: *asiñcan*: *ity etayoh sakārah shakāram' āpadyate. yathā: yena----- mitr----- cakāro 'vagrahapūrvatvānvādeçakah'. anvādeçenā 'nena' kim: aj----- avagrahapūrvatve 'py' akāreṇa vyaveta ity ayam ārambhah. nanu lāghavād akāravayaveto 'pi 'ty etāvatāi 'vā 'lam: kaṇṭhoktyā kim. ucyate: hr̥t----- ity ādāu mā.bhād iti.*

¹ G. M. *shatvam*. ² W. B. and O. p. m. om. *pūrva*. ³ B. O. G. M. om. ⁴ G. M. *sati*.

for *nis*, *ni śtanihi duriṭā* (iv.6.8⁷: all the manuscripts of the comment, along with my manuscript of the *Sanhitā*, read thus, as required by ix.1: compare the similar cases noted under rule 13, below). A number of counter-examples are given, showing the effect of absence of any one of the conditions contained in the rule: they are *sadane sīda samudre* (iv.3.1), *brhataḥ garmani syām* (iv.1.5¹), *vi śmataḥ surucaḥ* (iv.2.8²: G. M. omit this example), and *abhi sacanā pāhi* (i.4.10,11).

The cases coming under this rule are not so numerous but that it may be worth while to report them. Of verbal forms after *adhi* I have found none; after *abhi*, I have noted *abhi shyāma* (i.4.46³), and forms of *abhi śhiñcāmi* (i.7.10³ et al.) and *abhi śhunomi* (iii.1.8²); after *prati*, forms of *prati śthāpayāmi* (i.7.5² et al.), and *prati śtobhanti* (ii.2.12³); after *pari*, forms of *pari śhicye* (iii.3.11¹ et al.), and *pari śthāt* (i.7.13³); after *vi* (besides that quoted under rule 13, below), *vi śhajanti* (vi.4.7²), and forms of *vi shyāmi* (iii.4.11⁶); after *ni* (besides the one under rule 13), *ni śhaśāda* (i.8.16¹ et al.), and forms of *ni śhidāmi* (iii.5.11⁴ et al.). Such cases as *ni-śhādāyati* (v.3.7²), where the preposition, losing its accent before the accented verbal form, is combined with the latter in the *pada*-text, belong under rule 2, above. The same is the case with *vyātishajet* (vi.6.4² et al.), where the verb has two prepositional prefixes, and is therefore written in combination with them (*vi-ātishajet*), and with altered sibilant. But for this circumstance, we should require a separate and special treatment of the word; for *ati* is by this *Prāticākhya* (i.15) excluded from the list of *upasarga*, 'prepositions,' and so could not by the present rule cause the alteration of an initial *s* of a root. *Anu* is also thus excluded, whence the passage *anu śthana* (v.6.1³) does not fall under the rule, and the retention of its dental sibilant needs no specific authorization. It is the only case, so far as I have discovered, in which the restriction of the class of prepositions to half its usual number has any bearing upon the objects of this rule.

रासःसप्तेऽग्निर्विदुर्महिःपायुभिर्वेःसुमतिर्माकिरोयुरायुरा-
भिःसधिर्नकिस्तकारपरो नित्यम् ॥५॥

5. Also the *visarjaniya*, when followed by *t*, of *agniḥ* preceded by *rāsaḥ* or *sapṭe*, and of *niḥ*, *viduḥ*, *midhuḥ*, *pāyubhiḥ*,

4. *sarvānudātte pada vartamanah sakāra upasargapārvo nishpārvo vā shatvam āpadyate. yathā: aḥm-----: imām-----: sām-----: yaj-----: ni-----: etāny' upasargapārvānī. nishpārvam api: ni sh-----: evāmpārva iti kim: sad-----: brh-----: sarvānudātta iti kim: vi-----: abhi-----: pada iti kim: kālārtham: padakāle' nudātta ity arthaḥ.*

¹ G. M. etc. ² G. M. -rgd. ³ W. -kd a.

veh, *sumatih*, *mâkih*, *iyuh*, *âyuh*, *âbhih*, *sadhih*, and *nakih*, under all circumstances.

This is, the commentator remarks, a rule establishing exceptions in advance to rule 2 of the ninth chapter, which would require in every case *s* instead of *sh*. The examples are: for *agnih*, *avidushtarâsah*: *agnish tad vicvam* (i.1.14⁴) and *medhyas ca sapte*: *agnish tvâ* (v.1.11¹); with a counter-example, *varshishthe adhi nâke 'gnis te tanuvam* (i.1.8: only G. M. have the first two words), to show that *agnih* becomes *agnis* after other words than the two specified in the rule. For *nish*, *nish tapâmi goshtam* (i.1.10¹). For *viduh*, *vidushtarañ sapema* (ii.5.12⁵; p. *viduh-taram*), and also, in virtue of rule i.52, *avidushtarâsah* (i.1.14⁴; p. *aviduh-tarâsah*): *vidushtarañ* occurs at ii.6.11¹. For *mîdhuñ*, *mîdhushtama givatama* (iv.5.10⁴; p. *mîdhuñ-tama*). For *pâyubhih*, *pâyubhish tvañ gîvebhih* (i.4.24): with the counter-example *tasmâd aśvas tribhis tishthâñs tishthati* (v.4.12¹: only G. M. have the first two words), to show that the quotation of *bhih* (of *pâyubhih*) alone as *nimitta* would not have answered the purpose. For *veh*, *gocce vesh tvañ hi yajvâ* (iv.3.13⁵). For *sumatih*, *sumatish te astu bādhasva* (i.4.45¹: only G. M. have the last word): and, to justify the text in quoting *sumatih* (p. *sumatih*) in full, instead of *matih* simply, we receive an asserted quotation from "another text," *pramatis te devânām*. For *mâkis*, *mâkish te vyathir â dadharshît* (i.2.14²). For *iyuh*, *iyush te ye pûrvatarâm apaśyan* (i.4.33). For *âyuh*, *âyush ta âyurdâ agne* (ii.5.12¹: only G. M. have *agne*): we have *âyush te* again at i.3.14⁴. For *âbhih*, *âbhish te adya gîrbhih* (iv.4.4⁷: G. M. omit the last word). For *sadhih*, *apsv agne sa-*

5. *râsah*: *sapte*: 'ity etâbhyâm vicishite 'gnir ity asmin' *grahane*: *niñ*.....^{1,2}..... *nakih*: *ity eteshu visarjanîyas takdraparâñ shakâram* 'âpadyate'. *yathâ*: *avid*.....: *medh*.....: *etâbhyâm vicishita iti kim*: *varsh*.....: *nish*.....: *vid*.....: *apy akdrâdi* (i.52) *iti vacanâd avidushtarâsa ity apy udâhara-nam*: *mî*.....: *pây*.....: *pâyv* 'iti kim': *tasm*.....: *gocce*.....: *sum*.....: *sv iti kim*: *pram*..... *iti çâkhântare*: *mâk*.....: *iyush*.....: *âyush*.....: *âbhish*.....: *apsv*.....: *nakish*..... *nityaçabdah kimarthañ*: *rkâra rephavati* (vi.8): *avagrahañ* (vi.9) *iti nishedham* 'vakshyati': *avidur* 'ity atra visarjanîyasyâ 'vagrahashtatvât shatvam na syât: tan mâ bhâd iti: kanthoktir 'vidur ity asyâi 'va' na tv avidur ity asye 'ti-dâurbalyât: tat-samrakshañârtho nityaçabdah prayujyate.

aghoṣhaparas tasya sasthanam (ix.2) *ity asya puras-tâd apavâdo 'yam*.

(1) (2) W. transposes, breaking *mîdhuñ* in the middle. * G. M. *etasmîn*. * G. M. *shatvam*. * W. O. -*yur*; G. M. -*yubhir*; B. corrupt. * G. M. *pratishedho*. * G. M. *vid*. * G. M. *ins. apî*. * G. M. *ins. shatvam*.

dhish tava (iv.2.3², 11²). And for *nakish*, *nakish tam ghnanti* (ii.1.11⁴): *nakish tam* is found also at i.8.22⁴.

The final specification of the rule, *nityam*, 'under all circumstances,' is explained as intended to assure the inclusion in the rule of the word *aviduṣṭarāśah* (i.1.14⁴), already quoted, which would otherwise be liable to exclusion by the operation of rules 8 and 9, below. The word *viduḥ* itself, we are told, is all right, because of its specific mention in the text, but a little additional force is needed to bring in *aviduḥ* as its hanger-on. The explanation is by no means of the most satisfactory character, but I have nothing to suggest in its place. We have already once (see note to iii.8) had a case arising under i.52 treated as demanding a special handling.

अथ न ॥ ६ ॥

6. Now for exceptions.

An introductory heading, of force in the rules that follow (through rule 13).

अवर्णव्यञ्जनशकुनिपलृप्तुमृत्पुमल्लिप्तुवृद्धस्यतिपूर्वः ॥ ७ ॥

7. Excepted is a *s* preceded by an *a*-vowel, a consonant, *ṣakuni*, *patni*, *rtu*, *mṛtyu*, *malimlu*, or *brhaspati*.

The bearing of the first two items of this rule on those which precede it has been noticed under rule 2. The commentator's examples are, for a preceding *a*-vowel, *antarikṣhasad dhotā* (i.8.15² et al.: only G. M. have the second word) and *ā siñcasva* (i.4.19: but G. M. omit the passage), of which one falls as an exception under rule 2, the other under rule 4; and, for a preceding consonant, *ṛkāme vāi* (vi.1.3¹). Then, for the words specified, we have *ṣakunīśādēna* (v.7.14), *patnīśāmyājānām* (ii.6.10⁴: G. M. read *-yājāh*, which is found twice in the same division of the same section, but not elsewhere), *rtuṣṭhās tasya* (v.7.6⁶: the same compound is found at v.5.8¹), *mṛtyuśāmyuta iva* (i.5.9⁴: only G. M. have *iva*), *nāi*

6. *athe 'ty ayam adhikārah: ne 'ty etad' adhikṛtam veditavyam ita uttaram yad vakṣhyāmah*².

¹ G. M. om. ² W. *vadayāmah*.

7. *avarṇapūrvō vyañjanapūrvag ca ṣakuni.... brhaspati: ity' evampūrvag ca' sakārah śakāram' nā "padyate. yathā: ant-....: avagrahapūrvatvāt 'prāptih: 'ā siñ-....: upasarga-pūrvatvāt prāptih²: ṛk-....: ṣak-....: patn-....: rtu-....: mṛt-....: nāi-....: brh-....: 'avagrahapūrvatvād eśām prāptih³.*

¹ O. om. ² G. M. om. ³ G. M. *śatvam*. ⁴ G. M. *ins. eśām*. ⁵ G. M. om. ⁶ G. M. om.; W. adds *sa viśasyah: avagrahapūrvatvāt prāptih*.

'nam malimhusenā vindati (vi.3.2⁶: only G. M. have the first two and the last words), and *brhaspatiutasya te* (i.4.27 and vi.5.8³); all of which, as the commentator points out, are cases falling under the last specification of rule 2, respecting the conversion of initial *s* of the latter member of a compound.

ऋकाररेफवति ॥ ८ ॥

8. Also in a word containing *r* or *r*.

The commentator gives one example of each case, the former constituting an exception under rule 4, the latter under the last specification of rule 2: *vi srjate gāntyāi* (i.7.6⁷), and *tasmāt sa visarasyah* (vi.2.9⁴, 10⁷: only G. M. have *tasmāt*).

Of other words falling under this rule, I have noted *parisrutam* (i.8.21), *visarjanam* (i.1.5²), *bahusācari* (iii.1.11⁴), and *gosatram* (vii.5.1¹). Compare the nearly corresponding rules of the other treatises, Rik Pr. v.11, Vāj. Pr. iii.81, Ath. Pr. ii.102, 106.

अवग्रहः ॥ ९ ॥

9. Also in the former member of a compound.

We should expect the word *avagraha* in this rule to be put in the locative case, so as to accord in construction with the preceding rule; and I have translated it as a locative. Its being a nominative makes the commentator some trouble: he declares *avagraha* here equivalent to *avagrahastha*, 'standing in *avagraha*,' and quotes as corresponding and customary expressions "the stages cry out," "the fat one knows," where "those occupying the stages," "the soul inhabiting a fat body," are really meant.

The occasion for such a precept as this arises out of rule 4, above, which provides for the conversion into *sh* of the initial *s* of a word wholly *anudatta*, after a preposition. It was aimed, as is there pointed out, at unaccented verbal forms. But the former members of compounds which are accented on the latter member

8. *ṛkāraḥ ca rephaḥ ca ṛkārarephāu: tāv asmint sta ity ṛkāra-rephaveat: tasmin pade vartamānaḥ sakārah shakāraṇi nā "pad-yate. yathā: vi.....: upasargapūrvatvāt prāptih: tasm-----: avagrahapūrvatvāt prāptih.*

¹ G. M. *śhatam*. ² G. M. om. ³ W. B. O. om. ⁴ W. om.

9. *avagrahasthaḥ sakārah shakāraṇi nā "padyate: upasarga-pūrvac ca: avagraha ity avagrahastho lakshyate: mañcāḥ kro-ḡanti 'ty atra, mañcasthāḥ: 'sthālo jānāti 'ti sthāladehasthaḥ. udāharāṇāni: tāsy-----: mukh-----.*

¹ G. M. *śhatam*. ² W. -*ca*; G. M. *visarjanīyaḥ*. ³ W. *sat*. ⁴ G. M. change place with *avagraha*. ⁵ B. O. *labhy-*. ⁶ G. M. ins. *yathā*. ⁷ G. M. ins. *yathā*. ⁸ B. O. om. *iti*.

would also come under the rule, as being *anudatta* throughout, and also entitled to the designation *pada*, 'word,' equally with completely independent vocables: hence the necessity of providing for their exclusion from its action. The commentator illustrates with a couple of examples: *tāsyāṁ devā' ādhi saṁvāsantah* (iii.5.1¹), and *mākhāṁ yajñā nām abhī saṁvidāné* (v.1.11²: only G. M. have the first word). W. B. O. introduce a third, between the other two, namely *abhī sām agachantē 'ti* (ii.5.3⁷); but, as is shown by the accentuation and division, it does not fall under either the fourth rule or this, and has evidently come in by somebody's blunder.

It is very possible that the Sanhitā contains other cases requiring the application of this rule; but if so, they have escaped my notice.

सवस्थानम् ॥ १० ॥

10. Also in *sava* and *sthānam*.

The cited passages are *agnisavaḥ cityaḥ* (v.6.1⁵), *anusavanam purodācān* (vi.5.11⁴ and vii.5.6⁴), *savanesavane 'bhī grhnāti* (vi.4.11⁴; 6.11³), *prasavāya sāvitrah* (vi.6.5²: G. M. omit the last word; and the whole example is a blunder, since there is nowhere a rule requiring the lingualization of the sibilant in *prasavāya*), and *gacha gosthānam* (i.1.9^{1,2}).

The word *sthānam* being cited with its special case-ending, the rule would not apply to such forms as *sthānah*, *sthāni*, which in fact occur in the compound *pratishthāna* (e. g. i.7.6⁶; ii.4.4¹), with their sibilant converted to *sh*. *Sāva*, however, having no case-ending, falls under rule i.22, and is employed as "part of a word, in order to the inclusion of a variety of cases," as the comment duly points out, and as his selected examples illustrate.

न धिपूर्वे ॥ ११ ॥

11. But not when *dhi* precedes.

The examples are *adhishavanam asi* (i.1.5²: W. omits this example), *adhishavane jihvā* (vi.2.11⁴), and *adhishthānam āram-*

10. *sava*: *sthānam*: *ity' etayoḥ sakārah shakāram' nā "pad-yate. save 'ti padāikadeṣo bahūpādānārthaḥ'. agn-----: anus-----: sav-----: pras-----: gacha-----.*

¹ G. M. om. ² G. M. *shatvanā*. ³ B. *bahūnām padānām arthaḥ*.

11. *sava*: *sthānam*: *ity ayoh' sakāre' dhipūrve' nishedho na prasarati. yathā: adh-----: adh-----: adh----- dhi 'ty ayaṁ varṇah' pūrvo yasmād asāu dhipūrvah: tasmin.*

¹ B. G. M. *etayoh*. ² G. M. *sakārasya pūrva*. ³ G. M. put first. ⁴ W. om.

bhanam (iv.6.24). There are no other words illustrating the rule, although *adhishavana* occurs in one or two other passages.

Considering that an appended specification constituting a rule often applies only to the last word given in the preceding rule (e.g. iv.13.16), it might well enough have seemed advisable to the authors of the *Prātiśākhya* to read here *dhīpūrvayoh*, in the dual, instead of *dhīpūrve*.

संतानिभ्यःसताभिःसंमितास्तनास्तीतस्त्वशःसक्सनि-
सनिःसनीःसभेयःसत्त्वासस्ययि ॥ १२ ॥

12. Also in *sañtānebhyah*, *saptābhih*, *saṃmitām*, *stanām*, *sitam*, *spaṣaḥ*, *sak*, *sani*, *saniḥ*, *saniḥ*, *sabheyah*, *sattvā*, and *sasyāyāi*.

The examples, as quoted by the commentator, are as follows. For *sañtānebhyah*, *parisañtānebhyah svāhā* (vii.4.21). For *saptābhih*, *trisaptābhih paṇḍitāmāyā* (v.2.62: G. M. have only the first word). For *saṃmitām*, *vedisaṃmitām minoti* (v.6.82). For *stanām*, *devastānām karoti* (v.1.64). For *sitam*, *anusitam vapati* (v.2.55). For *spaṣaḥ*, *tanūpānāḥ pratipaṣaḥ* (v.7.31). *Sak* is declared a part of a word, implying a variety of forms: for example, *paṇḍit prajñasaktho bhavati* (ii.1.32), *prajñasakthās trayo hāimantikāḥ* (v.6.23: G. M. omit the last word), *prajñasaktham ā labheta grāmakāmāḥ* (ii.1.32: G. M. O. omit the last word), and *prajñasakthāya svāhā* (vii.3.18): I have noted no other cases, and should regard *saktha* as (by i.22) the preferable form for the *grāhana* in the rule. For *sani*, *tasmād etad gosani* (vii.5.22); for *saniḥ*, *asi stanayitnusanir asi* (iv.4.62: G. M. omit the first word); for *saniḥ*, *vr̥sh̥tisaniḥ upa dadhāti* (v.3.12, 101): *gosaniḥ* is found also at iii.2.57, and *vr̥sh̥tisaniḥ* at iv.4.62. As it would satisfy all these cases to cite *san* alone, in the character of part of a word (like *sak*, above), the commentator inquires why that was not done, and the citation of whole words avoided; and he brings up in reply *mrdhā vā esho bhishanno yasmāt samāneshe anyah greyān uta* (ii.4.23: all but W. stop at *-shanno*), and *nishannāya svāhā*.

12. *eteshu sakārah shakārah nā* "padyate. yathā:
pari.....: *tri*.....: *vedi*.....: *dvi*.....: *anu*.....: *tan*.....:
sag iti padāikadeṣo bahūpādānārthah: yathā: *paṇḍ*.....: *praj*.....:
praj.....: *praj*.....: *tas*.....: *asi*.....: *vr̥sh*.....: "sann
ity etāvatai 'va' siddhe kim akhilapadapāthena: mrdhā.....:
nish.....: *ity* ādāu mā bhūd iti: *sus*.....: *abhis*.....: *sus*.....:
"sattvasaṃtānebhyah ity etayor upasargapūrvatvāt prāptih:"
"sarveshām" anyeshām avagrahapūrvatvāt prāptih".

¹ G. M. *esku*. ² G. M. *shatvan*. ³ W. B. O. *san ity*; G. M. *sani 'ty*. ⁴ G. M. *om. eva*. ⁵ G. M. *om. padat*. ⁶ W. *sattvasasyāyā ity ayor upasargavagrahapūrv*; B. O. *sañtānebhyah svāhā*: *ity etayor up*. ⁷ W. *om*. ⁸ G. M. *om*.

(vii.1.19¹), as examples of the alteration of *san*. *Sani* would not cover all the cases; and the treatise makes no provision for the citation of a theme ending in *i*, or any other vowel than *a*, as representative of all the forms derived from that theme. For *sa-bheyah* is quoted *susabheyo ya evam* (vii.1.8¹: G. M. omit *evam*). For *sattvā*, *abhisattvā sahojāh* (iv.6.4²: all the MSS. read everywhere, in text, commentary, and *Sanhitā*, *sattvā*). And for *sasyāyāi*, *susasyāyāi supippalābhyah* (i.2.2³).

All these are exceptions under rule 2, being cases of compounds whose second member begins with *s*, after a vowel other than an *a*-vowel. The commentary tries (with much discordance between the different manuscripts: see the various readings below) to claim two of them as exceptions under rule 4; but there is no ground for so doing.

न स्वर्गस्यर्धास्तरिमसाहस्रसारथिस्फुरत्तीस्तुब्ज्योति-
रायुश्चतुःपूर्वस्तो ॥ १३ ॥

13. But not in *svara*, *spardhāh*, *starima*, *sāhasra*, *sārathih*, *sphuranti*, *stubbh*, and in *sto* when preceded by *jyotih*, *āyuh*, or *catuh*.

Of these words, the first six constitute counter-exceptions under rule 8, which excepted words containing *r* or *r* from the conversion of their initial *s* into *sh*. The examples, as quoted by the commentator, are as follows: *amba ni shvara* (i.4.1² and vi.4.4³); *vi shpardhāh chandah* (iv.3.12³)—these two, it is noted, are cases under rule 4, of unaccented verbal forms after a preposition—*su-shṭarimā jushānā* (v.1.11²); *dvishāhasram cinvīta* (v.6.8²: G. M. omit *cinvīta*), and *trishāhasro vā asāu lokah* (v.6.8²: G. M. omit after *vāi*)—both forms are, we are made to observe, included in the citation of *sāhasra* by its theme-ending *a*, according to rule i.22: other forms do not occur in the *Sanhitā*, nor these elsewhere than in the two divisions quoted from—*kāmayate sushārathih* (iv.6.6²); and *vishphuranti amitrān* (iv.6.6²).

The next case is a very anomalous one, being the conversion of *s* into *sh* after *a*, contrary to the first specification of rule 7. The phrase is *sastup chandah* (iv.3.12²; p. *sa-stup*). Compare similar cases as noted in *Ath. Pr.* ii.95.

The combination of *sto* with the three words mentioned, although

13. *stup*: *ity eteshu sakārah*: *jyotih*: *āyuh*: *catuh*:
evampārvaś ca 'sto *ity atra sakāra ṛkārarephavati* (vi.8):
avarṇavyaṇjana (iv.7) 'iti co 'ktam' nishedham nā "padyate:
kiṁ tu shatvam pratipadyate: *iti pratiprasavārtho 'yam nakā-*
rah. yathā: *amba*....: *vi sh*....: *upasargapūrvatvād anayoḥ*
prāptih: *sust*....: *grahanasya ca* (i.22) *iti vacanād akā-*
ragrhitam 'sāhasragrahaṇam anekārtham: *yathā*: *dvish*....:

not quite regular, has nothing strange in it. The final *visarjanīya* of the first member of the compound is lost by ix.1, and the sibilant is treated as it would be had no *h* been present. The examples are *jyotiṣṭomaṃ prathamam* (vii.4.10¹.11¹), *dyuṣṭomaṃ tṛtīyam* (vii.4.11¹), and *catuṣṭomo abhavat* (iv.3.11²): *jyotiṣṭoma* and *catuṣṭoma* occur in a number of other passages, which it is not worth while here to rehearse. The exception this time is to the second specification of rule 7, according to which the consonant *h* at the end of the former member of the compound would prevent the lingualization of the sibilant. Of course, according to the theory of the *Prātiśākhya* (by v.3), the lingualization is first performed, giving *jyotiṣṭoma* etc., and then, by ix.1, the *visarjanīya* disappears, making *jyotiṣṭoma*, as all the manuscripts, of comment and *Sanhitā*, constantly read.

The commentator remarks the fact that, from *starīma* on, the cases are such as fall under the last specification of the second rule of this chapter. He then adds, as counter-examples under *sto*, *yad akṣhṇayāstomīyāḥ* (v.3.3¹), *catustanām karoti* (v.1.6⁴), and *jyotiṣ tv 'ā asya* (ii.2.4⁵: but G. M. omit this example).

There are a few other words which we might expect to see included among those forming the subject of this rule. Such is *barhiṣad* (iv.6.1⁴ et al.), i. e. *barhiḥ-sad*: but the Rik and Atharvan *pada*-texts adopt the omission of the final *h* as part of their own reading, and the *Tāittirīya* (p. *barhiḥ-sad*) does the same, so that the irregularity of the word lies outside the *Prātiśākhya*. Such, again, are *duṣṭara* (iv.4.12²) and *duṣṭarītu* (iv.4.12¹), provided that, as seems to me probable (compare note to Ath. Pr. ii.85), they are regarded as compounds of *duh* with *stara* and *starītu*. But these words are written by the *pada*-texts of the other Vedas *du-stara* and *dustarītu*, and the *pada*-text of the *Tāittirīya-Sanhitā* reads *duṣṭara* and *duṣṭarītu*, so that there is no reason for their peculiar phonetic form being noticed by the *Prātiśākhya*. Once more, *triṣṣhamṛddhateāya* (ii.4.11⁵) would call for inclusion here, but that the addition of the suffix *tea* at its end annuls the separation which would otherwise be made of the first element of the compound, *triḥ*, and the word stands in *pada*-text *triṣṣhamṛddhateāya*, and so does not require alteration in *sanhitā*.

तद्वास्तस्मिंलोकान्विद्वास्तास्त्रीन्युष्मानूधान्म्वका-
नृतूनश्मन्कृण्वन्पितृननान्कपालास्तिष्ठन्वायुदत्तेनेमि-

triṣh.....: *kām*.....: *vish*.....: *sash*.....: *jyot*.....: *dy*.....: *cat*.....: *starīmādinām eṣhām avagrahapārvatvāt prāptiḥ*:
jyotirādipārvatvena kim: *yad*.....: *sto iti kim*: *cat*.....: *jyot*.....

¹ G. M. om. ² G. M. ity addi. ³ W. B. om. ⁴ W. B. O. om.

देवात्सवनेपशूस्तकारपरः सकारं प्राकृतो नित्ये प्रा-
कृतो नित्ये ॥ १३ ॥

14. In *tarhān*, *tasmin*, *lokān*, *vidvān*, *tān*, *trīn*, *yushmān*, *ūrdhvān*, *ambakān*, *ṛtān*, *açman*, *kṛvān*, *pitṛn*, *anān*, *kapālān*, *tish'han* when accented on the first syllable, *nemir devān*, and *savane paçūn*, an original *n*, followed by a *t*, becomes *s*, when the *t* is a constant one.

There seems to be no particular reason why this rule is introduced here, instead of anywhere else in the work, as it has no relation with the rest of the contents of the chapter. It is a complete rehearsal of the cases in which the old *s*, with which most Sanskrit words in *n* originally ended, is retained under the protection of a following initial *t*. The combination, of course, is historically identical with that of *n c* into *ñc*, treated of in the preceding chapter (v.20: see the note upon that rule). The "conversion" of *n* into *s*, as the treatise chooses to state the case, involves, by xv.1-3, the prefixion of *anusvāra* to the sibilant.

The examples quoted by the commentator are as follows. For *tarhān*, *çatatarhañs trñhanti* (i.5.7⁶ and v.4.7⁴). For *tasmin*, *tasmñs tvā dadhāmi* (i.6.5¹; 7.5¹). For *lokān*, *imān eva lokāñs tīrvā* (iii.5.4³): there is another case of *lokāñs* at ii.3.6¹. For *vidvān*, *ya evaṁ vidvāñs trāidhātaviyena yajate* (ii.4.11⁴; G. M. stop with *-yena*: the *Tāittiriya-Saṁhitā* has *paçukāmo* before *yajate*, which W. B. O. have doubtless dropped out by an oversight). For *tān*, *kaksheshv aghāyavas tāñs te dadhāmi jambhayoh* (iv.1.10³: only G. M. have the first two words, and they omit the last one): *tāñs* is also found at ii.4.11⁴; iii.1.9⁵; iv.1.10² twice; vi.3.1⁴ twice; 4.10³⁻⁴. For *trīn*, *trīñs trcān anu* (ii.5.10¹). For *yushmān*, *yushmāñs te'nu* (iii.2.5⁶): we find *yushmāñs* again at vii.1.5². For *ūrdhvān*, *yān ūrdhvāñs tān upabdimataḥ* (iii.1.9¹: only G. M. have the first word). For *ambakān*, *tryambakāñs trtiyasavanam akuroata* (iii.2.2³; G. M. omit the last word). For *ṛtān*, *ṛtāñs tanvate kavayaḥ prajānatih* (iv.3.11³; G. M. omit after *tanvate*). For *açman*, *açmāñs te kshut* (iv.6.1¹ and v.4.4¹). For *kṛvān*, *punaḥ kṛvāñs tvā pitaram yuvānam* (iv.7.13⁵: only W. has the last word). For *pitṛn*, *oja iti pitṛñs tantur iti* (v.3.6¹:

14. ādyudātte tishthanagrahaṇe..... eshu' grahaṇeshu
prākṛto nakāraḥ padasamaye³ vartamānas takāraparah sakāram
āpadyate. yathā: çat-----: tasm-----: imān-----: ya-----:
kaksh-----: trīñs-----: yush-----: yān-----: tryam-----: ṛt-----:
-----: açm-----: punaḥ-----: oja-----: prāṇ-----: api vikṛ-
tam (i.51) iti vacanād etad bhavati: dvād-----: tribh-----:
ādyudātta iti kim: na-----: apy akārādi (i.52) iti prāptih:
nem-----: nemir iti kim: jāt-----: mādḥ-----: savana iti kim:

only G. M. have the first two words). For *anān*, *prānāns tasyā 'ntaryanti* (vii.1.3¹; p. *pra-anān*): here rule i.51 is invoked to show that the lingualized *n* does not render the citation inoperative. For *kapālān*, *dvādaśakapālāns tṛtīyasavane* (vii.5.8⁴). For *tishthan*, *tribhis tishthaṅs tishthati* (v.4.12¹): as counter-example, proving the necessity of the requirement as to accent, we have *na praty atishthan tā vasuko 'si* (v.3.6²; G. M. omit *na*), which would fall under the operation of the present rule by i.52. For *nemir devān*, *nemir devāns team paribhār asi* (ii.5.9³; G. M. omit *asi*); with the counter-example *jātavedo vapayā gacha devān tvañ hi* (iii.1.4⁴; G. M. omit the first word), to show that *devān* is so treated only after *nemih*. For *savane paçān*, *mādhyandine savane paçāns tṛtīyasavane* (iii.2.9²; G. M. omit the first word); with the counter-example *prajām paçān tenā 'vardhata* (vii.4.3²), to prove the need of *savane* in the rule. Then, as general counter-example, to bring out the fact that *n* is thus converted into *s* only before *t*, we have *tasmin prajāpatir vāyuh* (vii.1.5¹): G. M. add also *lokān dravināvatah* (v.3.11²). And finally, the commentator proceeds to explain and illustrate the limitations "an original (*prākṛta*) *n*" and "a constant (*nitya*) *t*," given in the rule. An original *n* is one which is not the product of euphonic processes, but is read in the *pada*-text: in *tām tena gamayati* (v.7.3³), then, where the *m* represents a *n*, produced by the assimilation of *m* to the following *t* (by v.27), the rule has no force. A constant *t*, in like manner, is one which is found in all forms of the text, and not in *saṁhita* alone: hence, in *vidānt somena yajate* (iii.2.2³), the *t* which is introduced (by v.33) between *n* and *s* does not cause the conversion of the *n* into *s*. The *t* in this case, to be sure, is (by xiv.12) to be turned into *th* (and is so written in the citation by W. G. M.); but, as the rules of the treatise (by v.3) have to be applied in their order, the danger of misapprehension upon the point in question requires to be guarded against: for a *t* inserted by authority of the fifth chapter might assibilate a nasal according to the sixth, before it was itself turned into an innocuous *th* by the fourteenth.

The cases in which the insertion of *s* between *n* and *t* is made in the Tāittiriya-Saṁhitā are thus seen to number only thirty-one. On the other hand, the cases of the collision of *n* and *t* without interposition of *s* are very numerous: I have noted about two hundred

praj-.... takārapara iti 'kim: tasmin-.... lokān-.... prākṛta iti kim: tām-.... vāikṛto 'yam nakāro 'makāra sparṣaparah (v.27) *iti prāptatvāt: nitye takāra' iti kim': vidv-.... anityo 'yam nakāro yatah padasamaye nā 'sti.*

takārah paro yasmād asāu tathoktah'.

*iti tribhāshyaratne prātiçādkhyavivarane
shashtho 'dhyāyāh.*

¹ B. O. *eteshu*. ² G. M. *nitye pade*. ³ B. om. ⁴ G. M. *aprākṛto*. ⁵ G. M. *ins. yatah padasamaye nā 'sti*. ⁶ G. M. om. ⁷ G. M. *takāraparah*.

and eighty, and presume that I may have overlooked here and there others, so that there would be in all ten times as many instances of the omission as of the insertion. In the Atharva-Veda (see second marginal note to Ath. Pr. ii.26) the condition of things is quite different: while the whole number of collisions is much less (only ninety-five), the sibilant is introduced in considerably more than two-thirds of them (in sixty-seven cases, against twenty-eight). The comparison is of some interest in its bearing upon the question of the relative age of the two texts.

CHAPTER VII.

CONTENTS: 1-12, cases of the conversion of *n* into *ṇ*; 13-14, of *t* and *th* into *ṭ* and *tḥ*; 15-16, exceptions to the conversion of *n* into *ṇ*.

अथ नकारो णकारम् ॥ १ ॥

1. Now for conversion of *n* into *ṇ*.

An introductory heading, stating the subject of the chapter (with the exception of rules 13 and 14). We have treated here all the cases with which the Prāṭiśākhya has properly to deal, as arising in the process of conversion of *pada*-text into *saṃhitā*: chapter thirteen (rule 6 seq.) takes up the occurrence of *n* in a different way, determining every instance in which that letter is found in the whole *Sanhitā*.

पुषूकृधिसुवःसमिन्द्रास्थूर्युरुवाःषट्त्रियामनिष्पूर्वः ॥ २ ॥

2. *N* becomes *ṇ* when preceded by *shu*, *shū*, *kr̥dhi suvaḥ*, *saṃ indra*, *asthūri*, *uru*, *vāḥ*, *shat*, *tri*, *grāma*, or *niḥ*.

The commentator's illustrative examples are as follows. For *shu*, *ūrdhva ū shu naḥ* (iv.1.4² and v.1.5³: O. omits the first word); and, as counter-example, *gr̥heshu naḥ* (ii.4.5¹), where *shu*, not being a complete word, does not (by i.50) lingualize the nasal: but G. M. omit this passage and the accompanying explanation. For *shū*, *mo shū na indra* (i.8.3). The commentator points out

1. *athe 'ty ayam adhikārah: nakāro ṇakāram āpadyata ity etad adhikṛtaṃ veditavyam ita uttaram yad vakshyāmaḥ.*

2. *evampūrvo nakāro ṇakāram āpadyate. yathā: ūrdh-....: 'gr̥h-.... ity atra ṇatvaṃ na bhavati padagrahaṇeshv (i.50) iti vacanāt: mo-....: suṣū ity etayor yadā shatvaṃ nā 'sti tadā ṇatvanishedhārtham vāikṛtagrahaṇam: ya-*

that *shu* and *shā* are cited in the rule in their altered form (not as *su* simply, which, by i.51, would include them both) in order to indicate that where their consonant is not lingualized they do not lingualize the following nasal; and he quotes in illustration *su na ūtaye* (iv.1.4²) and *sā na indra* (i.8.3). Both these passages are the same which have been already quoted to illustrate the conversion, and G. M. O. very properly put them into the form of another text (apparently a *krama*), reading *su nah: na ūtaye*, and *sā nah: na indra*. *Shu* converts *n* to *n* also at iv.6.5⁶. For *kr̥dhi suvāh*, the passage is *brahmanā kr̥dhi suvar na çukram* (ii.2.12⁶: O. omits the first word: the Calcutta edition has the false reading *na*); and the necessity of *kr̥dhi* is shown by the counter-example *svāhā suvar nā 'rkah svāhā* (v.7.5²: O. omits the first word). For *sam indra*, *sam indra no manasā* (i.4.44¹); and *vartaye 'ndra nardabuda* (iii.3.10¹) shows that *indra* when not preceded by *sam* does not exercise the prescribed influence. For *asthāri*, *asthāri no gārhapatyāni santu* (v.7.2¹: only O. has *santu*). For *uru*, *uru nas kr̥dhi* (ii.6.11³ and vi.3.2²): there is another like case at iv.7.14². For *vāh*, *tasmād vār nāma vo hitam* (v.6.1³: G. M. omit the last two words). For *shot*, *shannavatyāi svāhā* (vii.2.15). For *tri*, *trinava stomo vasānām* (iv.3.9¹: G. M. O. omit the last word): the word *trinava* is found in a considerable number of other passages. For *grāma*, W. B. give *grāmanī rājanyah* (ii.5.4⁴), but G. M. O. have instead *grāmanīyam prā 'pnuvanti* (vii.4.5²): the word is found once more, at iv.4.3¹. For *nir*, *nir nenijati tato 'dhi* (vii.2.10²: G. M. omit the last two words); and *nir no rayim* (ii.2.12³) is added, to show that *nir*, without *visarjanīya*, has no alterant force. *Nir nenikte* (vii.2.10⁴) and *nirñij* (iv.6.8¹) are the only other cases I have noted for *nir*.

ह्रस्वाद्यमानं च ॥३॥

3. Also in *hanyāt* and *upyamānam*.

That is to say, after *nir*, the last of the words given in the preceding rule. The passages are: *yoner garbham nir hanyat* (v.6.9¹:

thā: su.....: sā.....: brah.....: kr̥dhi 'ti kim: svāhā.....: sam.....: sam iti kim: vart.....: asth.....: uru.....: tas- mād.....: shan.....: tri.....: grām.....: nir.....: visargena kim: nī.....

¹ G. M. om. ⁽²⁾ G. M. om. ³ O. *shushā*.

3. *cakāro nishpūrvatvam anvādiçati: nirçabdottarayor¹ hanyāt upyamānam ity etayor grahanayor² nakāro nakāram³ āpad- yate. yathā⁴: yon.....: nir..... anvādeçah kimarthah: na*

¹ G. M. -*bdasyo 'ti*; O. *nishpūrvayor*. ² G. M. om. ³ W. *nakātavam*; B. *pa- tsam*. ⁴ G. M. om.

O. omits the first word), and *nirupyamānam abhi mantrayeta* (i.6.8²: O. omits the last word). A counter-example, showing *hanyāt* without altered *n*, is *na ni hanyān na lohitaṁ kuryāt* (ii.6.10²).

पारिपरिपरीप्रपूर्वः ॥ ३ ॥

4. Also after *pāri*, *pari*, *pari*, and *pra*.

The illustrative citations of the commentator are *pāriṇahyasye* "pe (vi.2.1¹), *pari no rudrasya* (iv.5.10⁴), *vīravantam parīna-sam* (ii.2.12⁶), and *pra no devī sarasvatī* (i.8.22¹: O. omits the last word). For *pāri* (p. *pāri-nahyasya*: compare iii.7) there is no other case; nor for *pari* (p. *pari-nasam*: compare iii.7); for *pari*, I find only *pari nayati* (ii.3.4³ et al.). But for *pra* the examples are quite numerous: we have *pra nah* at i.5.11⁴; 6.4²; 7.10² twice: ii.5.12¹; iii.1.11²; 3.11⁴; iv.2.6⁵; v.5.7²; vii.4.19⁴; *pra nāmā-ni* at iv.3.13⁶; forms of *pra nayāmi* at i.6.8¹ et al., of *pra nude* at ii.1.3⁵ et al.; *prānīdāya* at i.3.5; *prānīyamānoḥ* at iv.4.9¹; *pra nenekti* at vi.2.9¹; *prānī* at ii.5.9², *prānīti* at i.4.18 and *su-prānīti* (but p. *su-prānīti*) at i.5.11⁵ et al., *prānetar* at iii.5.11², and *prānava* at iii.2.9⁶. *Parānuttī* occurs only in composition (vi.2.3²; p. *bhrātr̥vya-parānuttīdī*).

अवर्णव्यवेतो ऽपि ॥ ५ ॥

5. And that, even when an *a*-vowel intervenes.

The word "even" (*apī*) here brings down by implication, according to the commentator, the words in the preceding rule from *pari* on—that is to say, virtually, *pari* and *pra*, for there is no case of *pari* exercising such an effect. The examples for *pari* are *agram pary anayat* (ii.3.4³: all but O. omit *agram*: I find besides only *pary anayan*, at vi.5.7²), and *paryāntīyā havantīyasya* (vii.1.6⁶). For *pra*, we have *prānāya svāhā* (vii.1.19¹; p. *pra-anāya*), and *anu prā nyāt prathamām* (v.5.5²; p. *pre ti anyāt*: only O. has *anu*). The occurrence of *prāna* is very frequent: of other cases, I have noted only *prā nudatā* at vi.2.3², and *prā nudanta* at vi.4.10³⁻⁴—where, however, the lingualization of the *n* is suspended in our text, as at present constituted, by the intervention

4. *evampārvo nakāro nakāram āpadyate. yathā: pāri-
.....: pari.....: vīr.....: pra.....*

¹ G. M. O. om.

5. *apiṣabdaḥ paryādy' anvādiṣati: paryādipārvo' nakāro
avarṇavyaveto 'pi natvam bhajate. yathā: agram.....: pary-
.....: prān.....: anu..... avarṇavyaveta iti kim: pari.....
pra.....*

¹ B. pāri. ² G. M. O. -ādeṣakāḥ. ³ B. pāri. ⁴ G. M. āpadyate. ⁵ G. M. O. om.

between the preposition and the verb of the pause which separates the third and fourth divisions of the section.

A couple of counter-examples are given, to show us that the intervention of a letter of any other complexion than *a* prevents the change of nasal: they are *pari minuyât sapta* (v.2.6³: G. M. omit the last word), and *pramīnāna vratāni* (i.1.14⁴).

वाहनउद्यमानोयानमयन्यवेनवच्च ॥ ६ ॥

6. Also in *vāhanah*, *uhyamānah*, *yānam*, *ayan*, *yavena*, and *van*.

According to W. B. O., the *n* becomes *n* in these words "when they are preceded as implied by the word 'also' (*ca*)," the commentary failing to tell us what this implication is. G. M., however, confess that *pra* only is brought forward (from rule 4): which is a marked departure from the ordinary usage of the treatise, since in the intermediate rule *pra* and *pari* were both distinctly understood. The commentator omits, not to say avoids, noticing the irregularity. Perhaps he would be justified in claiming that *pari* and *pari* are never found preceding the words specified in the rule, and that therefore it makes no difference whether they be regarded as implied or not: still, even that consideration would not wholly excuse the want of accuracy and consistency. The examples are: for *vāhanah*, *pravāhaṇo vahniḥ* (i.3.3; p. *pra-vāhanah*); to this, W. adds a counter-example, to show that, after any other word than *pra*, *vāhanah* remains unchanged—namely *havyavāhanah* *ṣvātro* 'si (i.3.3): B. tries to do the same, but only succeeds in repeating one of the counter-examples of the last rule, *pari minuyāt* (v.2.6³), which is not at all in place here. For *uhyamānah*, *prohyamāṇo* 'dhipatiḥ (iv.4.9: p. *pra-uhyamānah*). For *yānam*, *prayānam* *anv* *anya* *id* *yayuh* (iv.1.1²; p. *pra-yānam*: O omits the last three words, G. M. the last two). *Ayan* is declared a part of a word, including a number of cases, of which G. M. give only three, *tasmād ādityaḥ prayāṇīyaḥ* (vi.1.5¹; p. *pra-ayanīyaḥ*: O. omits *tasmād*), *prayāṇīyam kāryam* (vi.1.5^{2,5}), and *prayānam pratishthām* (i.6.11¹; p. *pra-ayanam*); while W. B. O. add two others, *prayāṇīyasya puronucākyaḥ* (vi.1.5⁵), and *prayāṇīye* 'han (vii.2.8¹). There are a number of other passages for *prayāṇīya*; and *prayāna* occurs again at i.6.11² and vii.1.13, besides its compounds,

6. ----- *eteshu*¹ *grahāṇeshu cakārākṣhapārveshu*² *nakāro* *ṇatvam bhajate. yathā: prav*-----: 'pre 'ti kim: *havy*-----: 'proh-----: pray-----: *ayann iti padāikadeṣo bahūpādānārthah: tasm*-----: *prāy*-----: *prāy*-----: 'prāy-----: *prāy*-----: 'pray-----: 'vann iti padāikadeṣo bahūpādānārthah: 'yadi-----: 'āhav-----: *anvādeṣena kim: asi*-----: *uday*-----

¹ G. M. *eshu*. ² G. M. *-shaprapārvo*. ⁽³⁾ G. M. om; O. om. the example. ⁽⁴⁾ G. M. *ity ādi*. ⁽⁵⁾ G. M. O. B. om. ⁽⁶⁾ O. om.

suprāyana (v.1.11²; p. *su-prāyandh*) and *agnishtomaprāyana* (vii.2.9¹; p. *agnishtoma-prāyandh*). For *yavena*, *prayavēna pañca* (iv.3.11²; p. *pra-yavēna*). *Van*, again, is (by W. alone) declared a part of a word, intended to include many cases: only two are given, *yadi vā tāvat pravāṇam* (ii.4.12¹), and *dhavanīyāt pravāṇaṁ syāt* (vi.2.6⁴), nor have I found any other, except the compound *purastātpravāṇaḥ* (v.3.1⁵; p. *purastātpravāṇaḥ*). Finally, we have a couple of counter-examples, showing the necessity of the implication from the preceding rule: they are *asīhavyavāhanah* (i.3.3), and *udayanam veda* (i.6.11²).

प्रापूर्वञ्च ॥ ७ ॥

7. As also, when preceded by *prā*.

The "also" (*ca*) of this rule brings forward from the preceding rule only the word last mentioned there, namely *van*. The example is *pravāṇebhiḥ saḥśhasaḥ* (iv.2.4³; p. *pra-vāṇebhiḥ*: compare iii.5). I have noted no other case.

इन्द्रोऽयजुःपूर्व एनंकेन ॥ ८ ॥

8. Also *enam* and *kena*, when preceded respectively by *indrah* and *ayajuh*.

There is nothing in the rule meaning 'respectively,' and if *enam* were found anywhere in the text preceded by *ayajuh*, or *kena* by *indrah*, their *n*'s would doubtless require lingualization: yet the evident intent of the precept is as translated. The passages are *indra enam prathamah* (iv.6.7¹), and *yad ayajushkena kriyate* (v.1.2¹; p. *ayajuh-kena*: G. M. O. omit *yat*). I find no other cases falling under the rule: there are, however, one or two other forms, analogous with the latter of those here contemplated, which we might expect to find treated in the same way, namely *anācīr-kena* and *sācīrkena* (i.6.10⁴); but they are written by the *pada*-text without division of *ācīrkena*, or restoration in it of the dental *n* (thus: *anācīrkena*, and *sa-ācīrkena*).

Counter-examples are added: to show that *enam* and *kena*, when otherwise preceded, retain their dental nasals, *rudra enam bhātvā* (iii.4.10²), and *brahmavādīnāḥ kena tad ajāmi* 'ti (vii.4.10²: G. M. O. end with *kena*); to show that *indrah* does not exercise a lin-

7. *cakārākṣhṣṭe*¹ *vann iti grahane nakārah pre* 'ty *evampārvo natvam bhajate. yathā*: *prāv*.....

¹ W. B. -*shṭa*; O. *cakāro* 'nēddishṭo. ² G. M. om.

8. *indrah*: *ayajuh*: *pūrcayor*¹ *enam*: *kena*: *ity etayor nakāro natvam bhajate. yathā*: *indra*.....: *yad*..... *evampārva iti kim*: *rudra*.....: *brah*.....: 'enamkenē' 'ti *kim*: *indro*.....'

¹ G. M. O. *ity evampārva*. ² G. M. O. om. ⁽¹⁾ W. om. ⁴ B. *kenē*.

gualizing effect upon other words, *indro neshad ati* (v.7.2²: B. omits *ati*; W. omits the whole example).

नृश्रीपूर्वा मनाः ॥ १ ॥

9. Also *manāh*, when preceded by *nṛ* or *śrī*.

The examples are *nṛmanā aśasram* (i.3.14⁵ and iv.2.2¹: W. reads *yantri* instead of *aśasram*, but doubtless by a copyist's blunder, for *nṛmanā yantri* is not found in the *Samhitā*), and *śrīmanāh gatapayāh* (iv.6.3²); with the counter-example *sumanā upāgahi* (iii.3.11⁵). Of *śrīmanāh* I find no other example; *nṛmanāh* occurs also at iv.2.2¹ (a second time) and vii.1.12.

अङ्गानामोनेगानिगानांग्यानियमेन ॥ १० ॥

10. Also *aṅgānām*, *one*, *gāni*, *gānām*, *gyāni*, and *yāmena*.

These words in *samhitā*, says the commentator: that is to say, in the only cases in which they occur as *padas*, they take *n* in the combined text. The passages are: *yat tryaṅgānām samavadyati* (vi.3.10⁶; p. *tri-aṅgānām*: only G. M. O. have *yat*, and O. omits the last word), *āyushi durone* (i.2.14²; p. *duh-one*: the *pada*-texts of the Rik and Atharvan do not separate this word), *ati durgāni eigvā* (i.1.14⁴; p. *duh-gāni*, like the other Vedas), *purogānām cakshushe* (iii.2.4⁴; p. *purah-gānām*), *svargyāny āsan* (v.3.5³; p. *svah-gyāni*), and *antaryāmenā ntar adhatta* (vi.4.6¹; p. *antah-yāmena*: O. omits the last word). I have found no second example for any of these words, although there may be occurrences of *durone* which I have overlooked.

रषःपूर्वा हवन्यङ्गेहन् ॥ ११ ॥

11. Also *havanī*, *ahne*, *han*, when preceded by *r* or *shah*.

The cited examples are: *agnihotrahavanī ca* (i.6.8³; p. *agnihotra-havanī*); *śarady aparāhne* (iii.1.2⁵; p. *apara-ahne*: the Atharvan has *apara-ahnah*); and further, for *han*, which is declared to be a part of a word, involving several cases, *rakshohanam* (i.2.14⁶ et al.; p. *rakshah-hanam*: O. omits this example), *vāish-*

9. *nṛ*: *śrī*: *ity*¹ *evampūrvo manā ity atra nakādro natvam bhajate. yathā*²: *nṛm*-----: *śrīm*----- *evampūrva iti kim*: *sum*-----

¹ G. M. om. ² G. M. om.

10. ----- *eteshu*¹ *nakārah samhitāyām natvam bhajate. yathā*: *yat*-----: *āy*-----: *ati*-----: *puro*-----: *sv*-----: *antary*-----

¹ G. M. O. *eshu*. ² W. G. M. O. om.

navī rakshohanāu (i.3.2²; G. M. omit the first word), and *vṛtra-hanam purāṇidaram* (iii.5.11⁴ and iv.1.3³; p. *vṛtra-hanam*: G. M. omit the last word). For *han*, besides the compounds here quoted, which are found repeatedly in other passages, the *Sanhitā* affords us also *avīrahanāu* (i.2.8²; p. *avīra-hanāu*); for the other two words I know of no additional examples. Counter-examples are given, namely *sāhna evā 'smāi* (vi.6.11⁴; p. *sa-ahne*), and *valagahanah* (i.3.2¹ et al.).

There is good ground for questioning the correctness of the commentator's interpretation of *ra* in the rule as signifying the letter *r* (*repha*), and not the syllable *ra*. In none of the examples given are the words specified directly preceded by *r*, and it is not at all in accordance with the usage of the treatise to describe as "having *r* before it" a word preceded by another word containing *r*. All the versions of the comment, however, unite in this interpretation, and it is farther assured by the quotation of the rule above, under i.19, as a case in which *r* is called *ra*, instead of *repha*. It looks as if G. M. had made a blundering attempt to remedy the difficulty by reading the third word *ahan* instead of *han*, and also by understanding *shah* to mean 'the letter *sh*' (see the various readings, below), thus parallelizing the two specifications. The attempt, however, is an abortive one, only issuing, if carried out, in a host of new difficulties. I have made the translation of the rule conform to the requirements of the comment, but with much misgiving, having hardly a doubt that the meaning properly is 'when preceded by *ra* or *shah*.'

रूपवी मयान्यनी ॥ १२ ॥

12. Also *mayāni* and *anī*, when preceded by *ru*.

The passages are *dārumayāni pātrāni* (vi.1.7²; p. *dāru-mayāni*: O. omits *pātrāni*; G. M. omit the whole example), and *tve vasāni purvanika hotah* (i.3.14²⁻³; p. *puru-anika*: O. omits the first two words, G. M. the last): *purvanika* is found also at

11. *havanī: ahne: han: eshu² grahaṇeshu nakāro rephapārvaḥ 'sha ity' evampārvo³ vā natvam bhajate. yathā: agnih-----: gar-----: hann⁴ iti padāikadeṣo bahāpādānārthaḥ: raksh-----: vāish-----: vṛtr----- evampārva iti kim: sāhna-----: val.*

¹ W. O. *havanī*. ² G. M. *ahan*. ³ W. *evan*. ⁽⁴⁾ G. M. *shakāra*. ⁵ W. B. *ekamp*; G. M. *pārvo*. ⁶ G. M. *ahann*.

12. *mayāni: anī: ity atra rupārvo nakāro² natvam bhajate. yathā: 'dārum-----' tve----- evampārva iti kim: yāni-----: agnaye-----: repahagrahaṇena kim: svan.*

¹ W. O. *anī*, as also (with T.) in rule; G. M. *anika*, as also in rule. ² G. M. O. put after *atra*. ³ W. G. M. om. ⁽⁴⁾ G. M. om.

iv.4.4⁵. As counter-examples are given *yāni mṛṇmayāni śā-kṣhāt tāni* (vi.4.7³: B. omits the last word, G. M. O. the last two), *agnaye nīkavate* (i.8.4¹ et al.), and *svanikasamdr̥k* (iv.3.13¹).

वाघापूर्वस्तट् ॥ १३ ॥

13. After *vāghā* and *sh*, *t* is changed to *ṭ*.

The passage for *vāghā* is given by O. as *dārvāghātas te* (v.5.15¹); all the other MSS. have only the first word, in its complete *pada*-form, *dārvāghāta iti dāru-āghātaḥ*. The same word forms the subject of Vāj. Pr. iii.47. As counter-example, showing that *ta* does not become *ṭa* after *ghā* except when the latter follows *vā*, we have *praghāta adityānam* (vi.1.1³⁻⁴). For the conversion of *t* to *ṭ* after *sh* is quoted *āyush ṭa āyurdā agne* (ii.5.12¹: G. M. omit the last word, O. the last two), whose *sh* depends on rule vi.5, above. O. adds a counter-example for this second part of the rule also, namely *agnis te tejah* (i.1.10² and vii.5.17).

यश्च ठम् ॥ १३ ॥

14. Also *th* to *ṭh*.

The cited example is *goshtham mā nirmṛksham* (i.1.10¹: W. B. omit the last word); to which O. alone adds *prati shṭhāpayanti* (vi.1.4²). As counter-example is given *gacha goshthānam* (i.1.9^{1,2}).

न तकारपरः ॥ १५ ॥

15. But not when *t* follows.

The commentator explains the connection of this rule by pointing out that the two preceding do not come under the introductory heading of the chapter—that is to say, that they deal with a subject unconnected with the rest of its contents—and that hence they are regarded as dropped out, and the present exception does not apply to them, but to the foregoing rules, for conversion of *n* into *ṇ*. This is well enough, though not a little awkward, as concerns the status of rule 15; but we should like to hear what he had to say in defense of the intrusion of rules 13 and 14 thus into

13. *vāghā: ity evampūrvāḥ śhakārapūrvāḥ¹ ca takārash ṭakāram bhajate². yathā: dārv-----: āyush----- ve⁴ 'ti kim: pragh-----: 'shapūrvā iti kim: agnis-----³*

¹ G. M. om.; O. om. *kāra*. ² O. *āpadyate*. ³ W. G. M. om. ⁴ W. *vdghā*; B. *vāghāta*. ⁽⁵⁾ Only in O.

14. *cakārash shapūrvatvākarshakah¹: thakārash śhakārapūrvash² thakāram bhajate. yathā: gosh-----: 'prati-----³ evampūrvā⁴ iti kim: gacha-----*

¹ G. M. *śhakārap*; O. *tvādeṣakah*. ² O. om. *kāra*. ⁽⁵⁾ Only in O. ⁴ O. *shap*.

a chapter where they do not belong, and where they sorely disturb the natural and desirable connection. Considering their near relation to the rules of the preceding chapter, they might better have been added there as an appendix; or else put at the head of chapter vii., before its general *adhikāra*.

Only a single illustrative example is quoted, namely *pary antarikshāt* (iii.1.10²), where rules 4 and 5 of this chapter combined would require *an* at the beginning of the second word, but for the exception here made.

This precept is an anticipation of one of the items of xiii.15, below, and might properly enough be looked upon as open to the charge of *punarukti*, or unnecessary repetition, which the treatise so carefully shuns, and the commentator not seldom labors hard to remove. It is characteristic of the method of the Tāittiriya-Prāṭiśākhya that it does not attempt to state the real *nimitta* or occasion of the lingual *n* in the words rehearsed here, although it does so, fully and distinctly, in rule xiii.6, where the subject of the occurrence of *n* in the interior of a word is taken up.

नह्यतिनूनंनृत्यन्त्यन्योन्याभिरन्यान्यत्तश्चात्तश्च ॥ १६ ॥

16. Nor in *nahyati*, *nūnam*, *nrtyanti*, *anyaḥ*, *anyābhiḥ*, *anyāni*; nor when final.

The *ca* in this rule indicates the continuance of the exception. These words, and a final *n*, are not subject to the rules given in the chapter for the substitution of lingual *n*. The commentator quotes as follows. For *nahyati*, *vāsasā paryānahyati* (vi.1.11²; p. *pari-ānahyati*: O. omits the first word): he notes that the case constitutes an exception to rule 5. For *nūnam*, *pra nūnam pār-ṇavandhuraḥ* (i.8.5¹: O. omits the last word). For *nrtyanti*, *pari nrtyanti* (vii.5.10). For the three cases of *anya*, *prā 'nyah gaṇsati* (vii.5.9³), *prā 'nyābhiḥ yachaty ane anyāni mantrayate* (v.1.6⁴: O. omits *pra* in all these three examples, and in this, along with G. M., the last three words; B. omits the last word), and *prā 'nyāni pātrāni* (vi.5.11^{1,2}): the commentator remarks that all these (since *nahyati*) are cases of exceptions under rule 4. He then proceeds to raise the question why the three complete words

15. *vāghāśhādividhir' anadhikṛtatvād utpannapradhvāṁsi: tasmād atra' nā 'yam nishedhaḥ': 'kim tu' prakṛto' natvavidhir anena viśayikriyate. takāraparo nakāro natvaṁ nā 'padyate. yathā: pary.....: pāriparipariprapārvaḥ* (vii.4): *avar-ṇavyaveto 'pi* (vii.5) *ity etābhyām' prāptiḥ.*

¹ W. O. *vāghādī*. ² G. M. *tatra*. ³ B. *viçeshah*. ⁴ O. om. ⁵ W. O. *prak-*
⁶ W. B. *ādibhyām*.

16. *nishedhākarshakaḥ cakārah': eṣu' grahaṇeṣu nakārah padāntaḥ ca' natvaṁ na bhajate'. yathā: vās.....: avar-ṇavyaveto 'pi* (vii.5) *iti prāptiḥ: pra.....: pari.....: prā*

are quoted in the rule, instead of the syllable *an*, which would include them all; and makes the very obvious answer, that it is on account of the passage *anu prā 'nyāt prathamām* (v.5.5²), already quoted under vii.5. Finally, as example of final *n* exempt from conversion, he cites *vr̥trahañ chāra vidvān* (i.4.42), remarking that it is a case otherwise falling under rule 11.

The exception of a final *n* from becoming *ṇ* is also one of those made below, in rule xiii.15, for the class of cases to which that chapter relates.

I have not discovered in the *Sanhitā* any case of a lingual nasal arising in the conversion of *pada*-text into *saṃhitā* which is not duly provided for in this chapter.

CHAPTER VIII.

CONTENTS: 1-4, conversion of a final surd mute to sonant or nasal; 5-7, of *h* to *r*; 8-15, conversions of *h* to *r* after *a* and *i*; 16-22, treatment of *h* before *r*; 23-35, conversion of *h* to *s* or *śh* before *k*, *kh*, or *p*.

अथ प्रथमः ॥ १ ॥

1. Now for changes of first mutes.

That is to say, of surds unaspirated, or *k*, *c* (only *c* nowhere occurs as a final), *t*, *t*, and *p*. The force of this heading only reaches, as the commentary points out, through rule 4—hardly far enough, one would think, to make a separate introductory rule necessary.

.....: *prā*.....: *prā*.....: *pāripāripāripapārvah*¹ (vii.4) *ity eshām* *prāptih*. *ann ity etāvātā* *siddhe* *'nyonyābhiranyāni* *'ti kim* *pratipadapāthena*²: *anu*..... *ity atrā* *'nena*³ *nishedho*⁴ *na*⁵ *prasarat*⁶. ⁷*padānto nakāra ṇatvañ na bhajate: yathā*⁸: *vr̥tra*.....: *rashahpārvah* (vii.11) *iti prāptih*.

iti tribhāshyaratne prātiṣādkhyavivarane
saptamo 'dhyāyah.

¹ B. G. M. O. put first. ² B. O. *eteshu*. ³ G. M. om.; O. adds *nakāro*. ⁴ G. M. *dpadyate*. ⁵ G. M. O. om. ⁶ W. B. om. *prapārvah*. ⁷ G. M. *eteshān*. ⁸ G. M. O. *-patit* *'va*. ⁹ O. puts before *kim*. ¹⁰ O. *nai* *'sha*. ¹¹ G. M. *pratish*. ¹² G. M. O. om. ¹³ G. M. *-iv itī*. ¹⁴ B. O. om.; G. M. *padāntaḥ ca*.

1. *athe* *'ty* *'ayam adhikārah*¹: *prathama* *'ity etad* *adhikṛtān* *veditavyam ita uttaram* *yad vakshyāmah*: ² *visarjanīya* (viii.5) *paryanto*³ *yam adhikārah*.

¹ W. *adhikārārthah*. ² G. M. om. ³ O. ins. *atha*. ⁴ O. *itistatrapa*.

उत्तमपर उत्तमः सवर्गीयम् ॥२॥

2. A first mute, followed by a last mute, becomes a last mute of its own series.

The examples selected by the commentator to illustrate this mode of combination are *vān ma āsan* (v.5.9²), *shannavatyāi svāhā* (vii.2.15), and *tan mahendrasya* (vi.5.5³). For the conversion of *p* into *m* he is able to offer no instance, as none occurs in the *Saṁhitā*. As counter-examples, showing that only a nasal causes the conversion, and causes it only in a "first" mute, he brings up *vāk ta ā pyāyatām* (i.3.9¹: only G. M. have the last word), and *imām no vācam* (vi.4.7³).

All the *Prātiśākhya*s join in treating this conversion as necessary, not as alternative with conversion into a sonant (see note to *Ath. Pr.* ii.5).

तृतीयः स्वरधोषवत्परः ॥३॥

3. Followed by a vowel or a sonant consonant, it becomes a third mute.

The examples are *ṛdhag ayād ṛdhag uta* (i.4.44²), and *yad vāi hotā* (iii.2.9¹).

ककुच्च मकारपरः ॥४॥

4. Also in *kakut*, when *m* follows.

Namely, in the passage *kakudmān pratārtir vājasātamaḥ* (i.7.7²; p. *kakut-mān*: G. M. O. omit the last word). As counter-examples are given *ya unmādyet* (iii.4.8⁴: G. M. O. omit *yah*), and, according to W. B., *kakut trayastriṅgaḥ* (vii.2.5³); for which G. M. O. substitute *kakuc chandah* (iv.3.12²). The commentator

2. *uttamaparaḥ prathamah* ¹ *savargīyam uttamam āpadyate. yathā: vān-----: shan-----: tan----- evampara iti kim: vāk-----: prathama iti kim: imām----- uttamah paro yasmād asāv uttamaparaḥ.*

¹ G. M. O. ins. *dtmanah*. ² G. M. om.

3. *svaraghoshavatparaḥ* ¹ *prathamah savargīyam tṛtīyam āpadyate. yathā: ṛdhag-----: yad-----: ity ādi. svarāḥ ca ghoshavantāḥ ca svaraghoshavantāḥ: te pare yasmād asāv* ² *sa ta-thoktah.*

¹ B. om.; G. M. O. *svaraparo ghoshavatparaḥ ca*. ² G. M. O. om. ³ G. M. om.

4. *kakud ity asmin grahaṇe 'ntyo varṇo' makāraparaḥ* ³ *cakā-rākṣhām savargīyam* ⁴ *tṛtīyam āpadyate*. *yathā: kakud-----*

notices, finally, that the present rule establishes an exception to rule 2 of this chapter.

अथ विसर्जनीयः ॥ ५ ॥

5. Now for changes of *visarjaniya*.

Departing a little from his stereotyped mode of explanation of *atha*, the commentary declares it in this rule to cause *visarjaniya* to be understood, in the character of that respecting which something is to be enjoined (*lakshya*), in the precepts that follow; and he adds that this understanding is to remain in force as far as rule 10 of the next chapter.

रफमेतेषु ॥ ६ ॥

6. *Visarjaniya* becomes *r* before the classes of sounds last mentioned.

The examples are *tad agnir āha* (iv.2.8¹), and *āgīr ma ārjam* (iii.2.8²; O. omits *ārjam*); with the counter-example *agniḥ ca ma indrag ca me* (iv.7.6³). The commentator points out that it is the plural form of the pronoun (*eteshu*, literally 'before those') in this rule that shows the implication of the vowels and sonant consonants, in the character of following causes (*paranimitta*), since those are the only things which have been mentioned above (namely, in rule 3). That is doubtless so; still, the reference must be regarded as an unusually blind one, involving a "frog-leap" (*maṇḍūkaptuti*) over two intervening obstacles, of which one is a general heading, that changes entirely the subject under treatment.

kakud iti kim: ya..... evampara iti kim: kakut..... makārah paro yasmād asū makāraparah. uttamapara uttamāṇ savargīyam (viii.2) *ity asyā 'pavādo 'yam.*

¹ G. M. *takāro*. ² W. *makārah*. ³ G. M. O. put after *trītiyam*. ⁴ W. *prōpyate*.
⁵ G. M. om.

5. *athaḥabādo visarjanīyam lakshyatvenā 'dhikaroti 'ta uttaram yad ucyate'. atha svaraparo yakāram* (ix.10) *ity avadhibhūto 'yam adhi-kārah.*

¹ G. M. *vakshyāmah*.

6. ¹ *svareṣhu ghoshavatsu ca² parato³ visarjanīyo repham āpad-yate. yathā⁴: tad..... āgīr..... eteṣh⁵ iti bahuvacanāntasya sarvanāmano⁶ nirdeṣāt svaraghoshavatām paranimittānām upādānam⁷: teshām eva prakṛtatoāt. eteṣh⁸ iti kim: agniḥ.....*

¹ G. M. ins. *eteṣhu*. ² G. M. om. ³ O. *pareṣhu*. ⁴ G. M. O. om. ⁵ W. B. *svareṣhu*. ⁶ W. O. *sarvanāma*; B. *-nāmīno*. ⁷ G. M. *-nāt*.

न रेफपरः ॥ ७ ॥

7. But not before *r*.

R, although a sonant consonant, and therefore included in the preceding rule, requires a different treatment in the final *visarjanīya* before it. What this different treatment is, is pointed out farther on in the chapter (rule 16 seq.). The examples here given are *suvo rohāva* (i.7.9¹), and *ahorātre* (i.5.9² et al.: W. O. add *pārçve*, but there is no such collocation of words in the *Sanhitā*, and I suspect the word to be a corrupted reading for *prāvīçan*, which follows next at the place referred to).

ह्वारभार्वाह्वारविभरजीगरकरनत्तर्विवःसुवःपुनरहरहः-
प्रातर्वस्तःशमितःसवितःसनुतस्तनुतस्तोतर्हीतःपितर्मी-
तर्त्यष्टरेष्टर्नेष्टस्वष्टः ॥ ८ ॥

8. *Visarjanīya* becomes *r* in *hvāh*, *abhāh*, *vāh*, *hāh*, *abibhāh*, *ajigah*, *akah*, *anantah*, *vivah*, *suvaḥ*, *punaḥ*, *aharah*, *prātah*, *vastah*, *çamitah*, *savitah*, *sannutah*, *stanutah*, *stotah*, *hotah*, *pītah*, *mātah*, *yashṭah*, *eshṭah*, *nesṭah*, and *tvaṣṭah*.

With this rule begins the detail of the cases of an original *r* after *a* and *ā*, which is protected and brought to light by a following sonant letter, being treated in quite a different manner from an original *s*, although both *r* and *s* are represented, as finals, by the indifferent *visarjanīya*. The commentator points out at the end the rules to which these cases constitute exceptions, namely ix.7,9,10. His illustrative examples are as follows. For *hvāh*,

7. *rephaparo visarjanīyo repham nā "padyate. yathā": suvo*
.....: *ahor*.....: *ghoshavattvād rephasya pūrvavidhiprāptih.*
rephaḥ paro yasmād asāu rephaparah.

¹ G. M. om.

8. ¹.....: *eteshu¹ visarjanīyo repham āpadyate svaraghoṣhavat-*
parah². yathā: mā.....: *yonāv*.....: *vār*.....: *mā me*.....:
ab.....: *osh*.....: *dev*.....: *"karāvar anudātte paḍe"* (viii.9)
iti³ vakshyati: tenāi⁴ 'vāi⁵ 'taḍ⁶ api sidhyaty⁷ apy akārādi (i.52)
iti vacanāt: iti cet: māi⁸ 'vam: anudātte kaḥṣabde tad bhavati:
idam tv anyasvarārtham iti⁹: yathā¹⁰: arvā.....: *"ādyudāttas*
tv idam¹¹. yajña.....: *antar anādyudātte* (viii.10) *iti vak-*
shyati: tasmād ankārādi ca¹² (i.53) iti vacanāt sidhyati: iti
cet: "māi¹³ 'vam¹⁴: anādyudātte tad bhavati: ādyudāttārtham¹⁵
"idam grahaṇam¹⁶. ca.....: *suvar*.....: *punar*.....: *ahar*

according to W. B., *mā hvār mitrasya* (i.1.4¹); but, according to G. M. O., *mā hvār vasūnām* (i.1.3): I have found the word only in these two sections. For *abhāh*, *yonāv abhār ukhā* (iv.2.5²). For *vāh*, *vār nāma vo hitam* (v.6.1³). For *hāh*, *mā me pra hār asti vā idam* (ii.4.12⁴; vi.5.1⁵; only G. M. have the last two words): the word is found also at ii.4.12⁶; 5.2⁷. For *abibhah*, as the only passage where it occurs (ii.5.1²) does not exhibit in *samhitā* the final *r*, we have the *ajāta*-text quoted, namely *abibhas tam tam abibhar abibhas tam*. *Ājigah*, for the same reason, is treated in the same way in W. B. O., namely *oshadhīr ājigar ājigar oshadhīr oshadhīr ājigah*: *ājigar ity ājigah* (iv.6.7⁸); but G. M. read simply *oshadhīr ājigah*. For *akah*, *devātrā 'kar ājakshīrena* (v.1.7⁴; G. M. omit the last word): it is found also at i.3.14² twice; 5.2⁵; ii.4.9²; 5.7¹; iii.1.10³; 4.10⁴; iv.1.2⁴; v.2.1⁴, 8⁷; vi.4.8¹. As for this *akah*, the commentator supposes the objection raised that rule 9, which teaches that *kah* and *āvah* change *h* to *r* in an unaccented word, combined with rule i.52, which would extend the force of that rule to *kah* with *a* prefixed, is sufficient to cover the cases of its occurrence, without separate mention in the present rule; but he denies the pertinence of the objection, on the ground that the specification here made includes all instances of *akah*, without regard to their accentuation—for example, *ākah* at iv.1.2⁴, which is accented on the first syllable, but exhibits *r* in its *ajāta*-reading, *ārvā 'kar ākar āroḍ' rōḍ' kah*. For *anantah*, *yajñaparusho nantari tyāi* (v.2.5⁶). A precisely similar objection is suggested to this word also, on the ground of rules viii.10 and i.53 combined; and it is similarly repelled, by reference to the difference of accent: *ānantar* has the acute on the first syllable, which rule 10 forbids. For *vivah* is given, again in *ajāta*-text, *ca vivar vivah ca ca vivah*: *vivar iti vivah* (iv.2.8²; only Ō. has the final repetition of *vivah*: the Atharvan reads *vi vah*, as two separate words, in the corres-

-----: *ahārahār*¹⁸ (viii.13) *ity anīgyānto nishidhyate*¹⁹: *evam-rūpasya*²⁰ *nā 'yam niyamah*²¹. *prātar*-----: *doshā*-----: *'grtañ*
-----: *deva*-----: *ārāc*-----: *stanutar*²² *iti śākhāntare: etañ*
-----: *hotar*-----: *marut*-----: *pṛthivi*-----: *agne*-----: *agīy*
-----: *neshtaḥ*-----: *śivas*-----: *svaraghoshavatpara iti kim:*
ab-----: *punas*-----: *avarṇapūrvas tu lupyate* (ix.9) *iti*
kvacit lopaprāptih: *atha svaraparo yakāram* (ix.10) *iti kva-*
cid yatevaprāptih: *okāram aḥ sarvo 'kārāparah* (ix.7) *iti*
*kvacid otevaprāptih*²³: *tā etāḥ prāptih*²⁴ *pratisheddhuṃ hvārabhār-*
ādīyārambhah.

⁽¹⁾ Ō. *eshu*; G. M. *hvār abhār vār hār ity ādī*. ⁽²⁾ G. M. om. *svara*. ⁽³⁾ G. M. om. ⁽⁴⁾ W. om. ⁽⁵⁾ G. M. *kar anuddātātrena*. ⁽⁶⁾ Ō. om. *eva*. ⁽⁷⁾ W. *tad*. ⁽⁸⁾ Ō. puts after *vacand*. ⁽⁹⁾ G. M. om; Ō. *api*. ⁽¹⁰⁾ G. M. O. om. ⁽¹¹⁾ W. *idyudāttasva-rārthah*; G. M. O. *ayam for idam*. ⁽¹²⁾ Ō. om. ⁽¹³⁾ G. M. *na*; Ō. om. ⁽¹⁴⁾ B. *-āttam*; G. M. O. *-āttas*. ⁽¹⁵⁾ G. M. *tv ayam*; Ō. *tv ayam iti gr-*. ⁽¹⁶⁾ G. M. add *svar*. ⁽¹⁷⁾ W. *-dhyeta*; G. M. *-shedhita ity*. ⁽¹⁸⁾ G. M. *ayam nishedhah*. ⁽¹⁹⁾ B. om. ⁽²⁰⁾ G. M. *san-*. ⁽²¹⁾ Ō. om. ⁽²²⁾ W. G. M. O. *-ptih*.

ponding passage, iv.1.1). For *suvaḥ*, *suvar asi suvar me yacha* (v.7.6²: O. omits the last word): the numerous passages in which this word occurs it would be quite useless to rehearse. For *punaḥ*, *punar āsadya sadanam* (iv.2.3³: O. omits the last word): this, too, is of too frequent occurrence to be worth detailed reference. For *aharahā*, *aharahar havirdhānindm* (ii.5.6³): the same repetition of *ahā* is found further at i.5.9⁶ twice,⁷; ii.5.6⁶. In connection herewith is made the remark that *ahā* when not at the end of a separable compound is the subject of rule 13, below; but that that rule does not apply to a case like the one here in hand. For *prātaḥ*, *prātar upasadaḥ* (vi.2.3³): *prātaḥ* is found also at i.4.7: ii.1.2⁵; 5.6³; iii.1.7¹; 3.8⁴; 4.10¹; vi.4.2¹. For *vastaḥ*, *doshā-vastar dhiyā vāyam* (i.5.6²; p. *doshā-vastaḥ*): also at i.2.14⁴. For *çamitaḥ*, *çtan havish çamitar iti trishatyāḥ* (vi.3.10¹: only G. M. have the first word, only O. the last). For *savitaḥ*, *deva savitar etat te* (iii.2.7¹): the word is found also in about a dozen other passages. For *sanutaḥ*, *ārde cid dvēshaḥ sanutar yuyotu* (i.7.13⁵). For *stanutaḥ* we are simply referred to "another text" (*çākhāntara*): but G. M. read *sanutar*, and omit *stanutar* in the rule itself. For *stotaḥ*, *etan stotar etena* (vii.4.20). For *hotaḥ*, *hotar yavishtha sukrato* (i.2.14⁵: O. omits the last word): also at i.3.14³; 6.2²; iv.3.13²: v.1.4⁵; vi.3.8²; 4.3³. For *pitaḥ*, resort is had to the *jaṭā*-reading, since the only passage (iii.3.9¹) in which the word occurs does not bring to view the *r*: thus, *marutām pitaḥ pitar marutām marutām pitaḥ*. For *mātaḥ*, *prthivi mātār mā mā hiṁsīḥ* (iii.3.2²: O. omits the last word). For *yashtaḥ*, *agne yashtar idam namah* (i.1.12). For *eshtaḥ*, again a *jaṭā*-reading, *açy' eshtar eshtar açyā 'ciy' eshtaḥ* (i.2.11¹): its treatment before the word which follows it in *sāmhita* is the subject of rules 18–22 of this chapter; that of the preceding word, of x.14. For *neshtaḥ*, once more the *jaṭā* is drawn upon, *neshtaḥ patnīm patnīm neshtar neshtaḥ patnīm* (vi.5.8⁶). For *trashtaḥ*, finally, *çivas trashtar ihā⁸ guhi* (iii.1.11²: O. omits the last word): also at i.3.7¹, 10¹; iii.1.11¹; vi.3.6², 11².

The commentary adds a couple of counter-examples, illustrative of the fact that these words show their *r* only before a vowel or sonant consonant: they are *abibhas tam bhātāni* (ii.5.1²), and *punas te mām 'shām* (iv.7.14³).

कारावरनुदत्ते पदे ॥ १ ॥

9. Also in *kaḥ* and *āvaḥ*, in an unaccented word.

The cited examples are: *mithuyā kar bhāgadheyam* (i.3.7²), and

9. *kaḥ*: *āvaḥ*: *ity etayor visarjanīyaḥ padakāle 'nudātte' pade vartamānaḥ svaraghoṣavatporo repham āpadyate. yathā*:
mīth-..... suruco..... anudātta iti kim: ko-..... 'āvo-.....
evampara iti kim: adhi-.....

¹ G. M. -tta. ² G. M. om. ³ O. om.

suruco vena āvah: āvar ity āvah (iv.2.8²: G. M. O. omit *surucāh*). For *āvah* I find no other example; *kāh* occurs further at i.4.45¹: ii.2.12¹. As counter-examples, *kō 'syē 'ṣvarāh* (ii.6.7¹), and *ā'vo vā'jeshu yām jundā'h* (i.3.13²: G. M. omit the last two words; O. omits the whole passage) show the necessity of the specification respecting accent; while *adhipām akah samashtyāi* (vi.1.7³) shows that the *r* appears only before a sonant letter. This last example, it may be remarked, is brought under the action of the rule by i.52: it would be an example also under the preceding rule; compare what is there said in connection with the cited word *akah*.

अन्तरनाद्युदात्ते ॥ १० ॥

10. Also in *antah*, except when accented on the first syllable.

The cited examples are: *antār agne rucā' teām* (iv.1.9³: 2.1⁵), *agnīm antār bharishyānti* (iv.1.3²: O. omits the first word), and *antaryāmē maghavan* (vi.4.6³: but O. omits the example—reasonably enough, since it is given again later in this very comment, in illustration of a special point). It were to no good end to rehearse the other cases of occurrence of so common a word. To show the necessity of the restriction respecting accent, the commentator quotes *eshō 'ntō 'ntam manushyāh* (vii.2.7²), where we have the noun *ānta*, which the rule was especially constructed to avoid including. To prove, again, the continued implication of "followed by a sonant letter," is given *antās te dādhami* (i.4.3 and vi.4.6¹⁻²). Then the comment proceeds to justify the form in which the restriction respecting accent is made in the rule: it might have been said, "when accented on the last syllable;" but then the rule would have applied only under those circumstances; whereas now is included the case when the word is not accented at all, as in *antarcedi mithundā'u* (vii.5.9⁴: p. *antah-vedī*) and *antaryāmē maghavan* (vi.4.6³, as above: but G. M. omit). The mode of statement selected, however, it may be remarked, has this inconvenience—that it renders necessary the separate specification, in rule 8, of *anantah*, because that combination, where it occurs, happens to be "accented on the first syllable" (see note to rule 8). It would appear to admit of question, in-

10. *antar ity 'asmin padē 'nādyudātte visarjanīyah svaragho-
shavatparo repham āpadyate¹. yathā²: antar..... agnim.....
antar..... anādyudātta iti kim: esho.....: evampara iti kim.
antas..... 'antodātta iti vaktavye³ bahusvaratvam bahāpādā-
nārtham⁴: anyathā tv' antodāttasyāi⁵ 'va syāt⁶: antarv.....: an-
tary..... ādāv udātto yasya tad ādyudāttam: nā 'dyudāttam
anādyudāttam: tasmin.*

(¹) G. M. *etasmīn*. (²) G. M. *āpnoti*. (³) G. M. *om*. (⁴) G. M. *om*. (⁵) W. O. *-thah*.
(⁶) B. *om*. (⁷) G. M. *hy*.

deed, whether *ānantah* was not fairly included in the present rule, since the *antah* part of it, at any rate, is not "accented on the first;" but the treatise chooses to avoid so nice a question of interpretation, and to take the safe side.

आवृत्परः ॥ ११ ॥

11. Also a *visarjanīya* followed by *āvrt*.

The quoted examples are *jinvar āvrt svāhā* and *ugnar āvrt svāhā* (both ii.4.7¹: B. has *bhīmar* for *ugnar*; O. reads in each case *āvrt*, according to the requirements of rule xiv.12). Other instances in the same and following divisions of the same section are *bhīmar āvrt*, *veshar āvrt*, *grutar āvrt*, and *bhūtar āvrt*. The anomalous combination does not occur elsewhere.

इतिपरो अपि ॥ १२ ॥

12. And likewise when *iti* follows.

The word *api* in this rule, we are told, brings forward the implication of "a *visarjanīya* followed by *āvrt*." According to the commentator's exposition, further, the rule is intended to apply to the *jaṭā* repetition of *grutaḥ* with its predecessor *iti*: as, *iti grutaḥ grutar iti 'ti grutaḥ* (ii.4.7²). Nor do I see of what other interpretation it is capable, although it seems strange that the irregular conversion of *h* into *r* should be retained in the *jaṭā*-reading of this word only, and not of the others, where repeated with their respective predecessors. It is clearly implied that we are to read, for example, in the first case falling under the preceding rule, *varshan jinvo jinvo varshan varshan jinvaḥ*.

As counter-example, showing the necessity of the implication signified by *api*, we receive *rtubhir havanagrutaḥ* (ii.4.14³: G. M. O. omit the first word; G. M. add *havam*, but no such word follows in the *Sanhitā*, and the addition is doubtless a copyist's error—possibly growing out of the attempt to repeat the compound, in its *pada* or *jaṭā* form). Here both the *pada*-text (as the word is a compound) and the *jaṭā* (as it stands before a pause) would read *havanagruta iti havana-grutaḥ*, the ordinary *sandhi* being made of *grutaḥ* and *iti*.

अर्द्धारक्षुः सुवरनिंग्यान्तः ॥ १३ ॥

11. *āvrt ity evam paro visarjanīyo repham āpnoti. jinv----- ugn-----*

12. *apiçabda āvrtparam¹ visarjanīyam anvedīçati: asāu visarjanīya itiparo repham āpnoti. iti gr----- anvedeçāḥ kim-arthāḥ: rtu----- itih² paro yasmād asāv itiparaḥ.*

¹ W. O. -*paro*; G. M. -*para*. ² W. B. *iti*; O. *itiçabdaḥ*.

13. Also in *ahāh*, *ahah*, and *suvaḥ*, except at the end of a separable word.

There is a well-established difference of reading in the text itself of this rule. T. and W. read the last word *anīngyāntāḥ*, as plural, to agree with the three words mentioned, or else with the three cases of *visarjanīya* which they present; and at the beginning of the comment, both in W. and in O., is seen an attempt to explain the word as a plural—not, however, consistently carried out in either. As both readings are equally acceptable, I have adopted the one which is best supported.

The examples given in illustration of the rule are *ahār jātave-dā vicarshanīḥ* (iii.2.5⁴: O. omits the last word), *ahar māṇsena* (v.7.20: but G. M. substitute *aharbhājo vāi*, vii.4.5¹), and *suvar devān aganma* (i.7.9²: O. omits the last word): and, as counter-examples, first, to show that the *h* in the words specified, when they stand as final members of compounds, is treated in the usual manner, *abhipūrvam tryahā bhavanti* (vii.3.9² et al.; p. *tri-ahāḥ*: O. omits the first word), *pratyah tryaho bhavati* (vii.3.5³ et al.; p. *tri-ahah*: but B. has dropped out the whole example, and G. M. O. substitute, O. with omission of the first word, *pratyah shad-aho bhavati*, vii.4.2⁵), and *devasuva atha te* (i.8.10²: but W. B. O. give simply the *pada*-reading of *devasuvaḥ*, namely *devasuva iti deva-suvaḥ*, since thus alone is the word put into circumstances which show its *h* not to be convertible into *r*); and second, to show that the conversion takes place only before sonant letters, *prāya-ṇīyam ahas tasmāt* (vii.2.8¹: O. omits the first word), and *suvaḥ ca mārddhā ca* (i.7.9¹ and iv.7.11²).

The commentator then proceeds to give an explanation, so far as *ahāḥ* is concerned, respecting the virtual intent of the rule, which, he says, is meant to establish an exception for that word when the final member of a compound; since the inclusion of *hāḥ* among the words cited in rule 8 would, under the operation of the often-quoted rule i.52, be authority sufficient for turning *ahāḥ* into *ahār* before a sonant letter. Upon this he next imagines the objection to be raised, that the reading in this rule also, as well as the other, should have been *hāḥ*, *ahah* being then included along with it according to the principle referred to; and thus the liability to reproach for over-doing the explicitness of the rule would be avoid-

13. *ahāḥ*: *ahah*: *suvaḥ*: *eteshu' visarjanīyo' nīngyāntāḥ' eva-raghoshavatparo repham āpnoti'. yathā': ahār.....: ahar.....: suvar..... anīngyānta iti kim: abhip.....: praty.....: dev..... evampara iti kim: prāy.....: suvaḥ..... hvārabhār (viii.8) * ādisātre hār ity anena grahaṇenā 'hāḥgabdasya' 'py akārādi (i.52) iti vacanād rephasiddhau satyām atra punarvacanam īngyāntasyā 'hāḥgabdasya pratishedhārtham. nanv atrāi 'va' hār iti vaktavyam: apy akārādi (i.52) iti vacanena kār-yasiddheḥ: na tu tadgauravāpatteḥ*: iti cet: māi'vam: anīng-*

ed. But he replies, reasonably enough, that, as the rule says "when not the final member of a separable word," it is to be inferred that the words specified do occur as such members: and with *hāh* that is not the case; wherefore the distinction would be meaningless with reference to *hāh*. And it would be a poor enough side to take, and altogether unworthy of approval, to give a direction which did not apply to a word itself, but only to that word with *a* prefixed. Hence the quotation is made in proper form.

Just as long a discussion might have been raised with equal reason over *ahāh* and *suvaḥ*, both of which are also included in the former rule. So far as *ahāh* is concerned, indeed, it is easy to see that this is the general rule, applying to the cases of occurrence of that word in the main, with a specific restriction; and that *ahar-ahāh* in rule 8 is a sort of exception in advance, made for a single case which would otherwise fall under this restriction (since, in *ahāh-ahāh*, the second *ahāh* is in fact the final member of a compound). But I am unable to discover any justification of the way in which *suvaḥ* is treated: it is made the subject of two general rules, to the one of which a needed restriction is attached, to the other, not. For *ahāh* and *suvaḥ*, the present rule should, it seems, have taken distinctly the form of an exception merely: *nā 'hāh-suvar iṅgyāntāu*; 'not, however, *ahāh* and *suvaḥ*, when final members of compounds;' and *ahāh* should have been separately treated, or else included with them and a further counter-exception added.

न भिर्यापरः ॥ १४ ॥

14. Not, however, when followed by *bhiḥ* or *bhyām*.

There is violation of the ordinary usage of the *Prāṭicākhya* in this rule also. The only one of the words mentioned in the preceding rule which is found with the case-endings *bhiḥ* and *bhyām* following it is *ahāh*; and hence, to it alone the present precept applies. We should expect it, therefore, in accordance with the principle of which i.58 is an expression, to have been placed last in the trio of which it forms a member. The commentator does not remark upon the irregularity, but simply points out that the

yānta ity ukter¹ iṅgyāntatvam¹⁰ iti¹¹ sambhāvaniyam: tac ca hār ity evamrūpe¹² grahaṇe nā 'sti 'ty¹³ atre 'dān viśeṣaṇam anarthakam syāt: tathā 'py¹⁴ evamrūpe mā bhād iti¹⁵: "kim tv¹⁶ akā-rādītve bhavati 'ti jaghanyaḥ pakṣaḥ: na tu saralāḥ: iti sūtre¹⁷ 'hār¹⁸ iti grahaṇam upayujyate.

¹ O. *eshu padeshu*. ² W. -yd. ³ W. *anīgyāntāḥ*; O. -tā. ⁴ O. *āpnuvanti*. ⁵ G. M. O. om. ⁶ G. M. ins. *ity*. ⁷ G. M. 'vā. ⁸ O. *tatra gauravadeshap*-. ⁹ G. M. *tatra gauravadeshap*-. ¹⁰ W. *ukter*; G. M. O. *ukte*. ¹¹ G. M. -*antam*. ¹² G. M. O. *api*. ¹³ G. M. O. -*pa*. ¹⁴ W. om. *iti*. ¹⁵ G. M. O. *sati*: a better reading. ¹⁶ O. om. ¹⁷ G. M. om.; O. *kim tv apy*. ¹⁸ G. M. O. *sutarām*. ¹⁹ MSS. *ahār*.

circumstances of the case restrict the application of the rule to *ahah*, and gives as examples *uttarāir ahobhiḥ caranti* (vii.5.14; G. M. Ō. omit the last word), and *gam ahobhyām iti nī nayati* (vi.3.9¹).

अश्नुश्च सर्वेषाम् ॥ १५ ॥

15. Also not in *añhah*, as all agree.

Some authorities, namely, the commentator informs us, accept this word as containing an *anusvāra*, others not; but all alike regard it as an exception under rule 13 (and therefore not liable to have its final *visarjanīya* converted into *r* under any circumstances). Those who accept the *anusvāra* still regard the word as falling under the action of rule 13, in virtue of the principle "a nose-sound occurring in the interior of a word is no bar to the application of a rule; hence it performs the offices of letters while itself only a quality" (if this be, in fact, the meaning of the second line of the verse, of which I am by no means confident; the readings of the manuscripts are here somewhat discordant, without being mutually explanatory). The first words of this verse were quoted in the comment on rule i.1, in connection with the discussion as to whether *anusvāra* was a concrete thing or a quality (see p. 8), and were credited to the Çikshā—which, however, in the form in which we now possess it, neither contains such a passage, nor seems to furnish a connection in which it should naturally be introduced. I should question the sober verity of the considerations whereby the commentator tries to justify the rule. It is hardly credible that *añhah* and *ahah* should be fairly identified by any authorities. And *anusvāra* is not a *nāsikya*, but an *anu-nāsika*, in the view of this treatise every where. It might be bet-

14. *sāmnidhyena¹ labdhaḥ² pūrcasūtrokto visarjanīyo³ bhirbhyām⁴ evamparo⁵ na repham āpnoti. arthād ahar ity atra visarjanīyah parigrhyate: itaratrasthitasyāi⁶ camparatvābhāvāt. yathā: utt-----: gam-----*

¹ G. M. Ō. -dhyāt. ² W. labhyah. ³ W. ins. na. ⁴ O. ins. ity. ⁵ G. M. paro.

15. *cakāro¹ nishedham ākarshatī²: añha ity asmin³ grahaṇe visarjanīyo na repham āpnoti: ahārahar (viii.13) iti prāptiḥ. atra⁴ grahaṇe kecid anusvāram ichanti⁵ 'kecin ne⁶ chanti: sarveśhām⁷ teshām esha⁸ nishedho bhavati: anusvāram ichadbhir api prāptir evam pratipādyatē⁹:*

vidher madhyasthanāsikyo na virodho¹⁰ 'bhavet smṛtaḥ¹¹:

tasmāt karotī¹² kāryāni varṇānām¹³ 'dharma eva¹⁴ tv iti. yathā¹⁵: añha-----: añho-----

⁽¹⁾ G. M. Ō. -dhākarshakah. ⁽²⁾ G. M. etasmin. ⁽³⁾ O. asmin. ⁽⁴⁾ G. M. om. ⁽⁵⁾ G. M. eva. ⁽⁶⁾ G. M. -pady-. ⁽⁷⁾ B. -dhi. ⁽⁸⁾ B. bhavet: sataḥ; G. M. bhaved yataḥ. ⁽⁹⁾ B. G. M. kurvanti. ⁽¹⁰⁾ W. dharmāṇas. ⁽¹¹⁾ G. M. om.

ter to regard the specific-exception of *añhah* as simply a sort of supererogatory effort at extreme explicitness, intended to guard against the confusion with *ahah*, even by a blunderer, of another word which was, indeed, definitely different from it, but different by only so inconspicuous an element as the nasalization of a vowel.

The illustrative examples are *añha indram evā 'ñhomucam* (ii.2.7⁴: but O. writes ---- *eva: añhomucam*, as if the latter word were a separate citation: it is found in other passages), and *añhomuce pra bharema* (i.6.12³: but O. substitutes *añhomuce purodāgam*, ii.2.7⁴).

अनवर्णपूर्वस्तु रेफरो लुप्यते ॥ १६ ॥

16. But, when not preceded by an *a*-vowel, *visarjanīya* followed by *r* is omitted.

The commentator's example in illustration of the action of this rule is *revatī ramadhvam* (i.3.7¹ et al.; p. *revatīh*); and he adds as counter-examples, first, to show the necessity of the restriction "not preceded by an *a*-vowel," *yo rudro agnau* (v.5.9³), and again, to show that the omission takes place only before a *r*, *revatīr naḥ sudhamādah* (ii.2.12³; 4.14⁴). This exhausts the evident intent of the rule: the *tu*, 'but,' which the latter contains, merely indicates the transition to a new and diverse subject; it intimates no distinction between the classes of cases in which the *visarjanīya* represents a *s* on the one hand and an original *r* on the other; and all the cases of final *ah* and *āh* are left to be treated alike, as prescribed by the rules given hereafter (ix.7-10)—*ah* being changed to *o*, and *āh* to *ā*. This truly represents the usage of the *Sanhitā*: the latter does not contain (if the special case which forms the subject of rules 18-22, below, be excepted) a single instance of *ah* converted into *ā* before *r*: the occurrence before *r* of *ah* standing for original *ar* is very rare, and the product is always *o*: besides the cases of *ahorātre* (*pada*-text, *ahah-rātre*), I have

16. *avarṇād anyasvarapūrvo rephaparo visarjanīyo lupyate. yathā: rev----- evampūrva iti kim: yo-----: evampara iti kim: rev----- tuṣabdhārambhād avarṇapūrvo 'pi hvārabhār* (viii.8) *ādīnām visargo lupyate pūrcasvaraḥ ca dīrgham āpadyate. yathā: rukmo----- tarhi suvo----- ity atra lopadīrghāu kim na syātām. deiruktatvād iti brāmaḥ. tat katham. hvārabhār* (viii.8) *ādisutre³: ahārahahsuvar* (viii.13) *ity atra ca. nane ahorātre ity atra katham ocam. anyārthena grahaṇasāmāthyene 'ti brāmaḥ. tat katham. ahorātre dhr̥tavrata³* (iv.11) *ity evamrūpasāmyād³ ahorātrābhyām ahorātrayor³ ity ādi vijñeyam³. 'evam ced adhishavane* (iv.11) *iti grahaṇasāmāthyenāi 'va³ 'śatve siddhe¹¹ 'na dhi-
p̄trve* (vi.11) *iti 'nishedhanishedhena virodhaḥ¹¹. satyam: sa-*

only found four instances of *suvaḥ* before forms of *ruh*; namely *suvo ruhānāḥ* (iv.1.2⁴; 7.13¹), *suvo rohāva* (i.7.9¹), and *suvo rokshyāmi* (i.7.9¹). The other Prātiçākhyas (Rik. Pr. iv.9, r. 28, 29; Vāj. Pr. iv.34; Ath. Pr. ii.19, iii.20) convert *ah* to *ā* in like circumstances; and at least the Rik and Atharvan afford several instances of the *sandhi*.

So much for the rule and its meaning. The commentator, unfortunately, has found occasion to give it a forced and false interpretation; it leads him into a nest of difficulties, through which he flounders as best he can, coming out at the end with much discredit. There happens to be a single passage (or, if there be another, I have not noticed it) where a word with original final *r* follows in the *Sanhitā* a word beginning with *r*—namely *rukmo antah* (iv.1.10⁴⁻⁵; 6.5²; 7.12³)—and, of course, in the inversions of the *ajāta*-text, comes to stand before its predecessor. The accepted *ajāta*-reading, it appears (as given in full by the commentator), is *rukmo antar antā rukmo rukmo antah*, the analogy of the Rik and Atharvan usage being followed in the treatment of *antah*. In order, now, to find authority for this reading, the commentator declares that *tu*, 'but,' in the rule signifies that, even when preceded by an *a*-vowel, the words specified in rule 8 and its successors lose their *visarjanīya* and lengthen the preceding vowel. This is an attribution of portentous pregnancy of meaning to the particle such as is not very infrequently made, rarely with more evident falsity than here. The objection is immediately suggested—why, in that case, does not *suvaḥ* in *suvo rohāva* (i.7.9¹), lose its *h* and lengthen its *a*? Because, is the acute reply, it has been mentioned twice, once in rule 8, and once in rule 13. What possible connection is to be discovered between this repetition and the use to which he would fain put it, he does not give himself the trouble to inform us: he takes care to raise only such difficulties as he conceives himself able to remove. The next which it pleases him to evoke is—how is the *o* of *ahorātre* to be explained? We rather

vaçabdasya 'dhishavane iti grahaṇasāmarthyena¹ shatvaṁ sidhyatu: sthānaçabdasya katham sidhyet: grahaṇādisāmarthyābhāvāt²: tasmāt tadartham³ tāvat⁴ sūtram sārthakam iti⁵ tadartham eā drashtavyam⁶: tadartham ce⁷ 'ti guḍajihvikānyāyah⁸: tathā hi: grahaṇasāmarthyād⁹ iti¹⁰ gamanikāmātram¹¹: kañthoktis tu viçeshah: tataḥ savaçabdartham¹² sūtram iti bhāvaḥ¹³.

avarṇād anyo 'navarṇah: asāu pūrvo yasmāt sa tathoktah. rephah paro yasmād asāu rephaparah.

¹ B. G. M. O. om. ² W. B. G. M. om. ³ W. B. ins. *aharahaḥ* itī. ⁴ W. B. O. om. ⁵ O. *adhishavaye*. ⁶ G. M. *pragrahe evaṁrūpasāmarthyād*. ⁷ G. M. *-tre*. ⁸ B. *jāyam*. ⁹ O. *nanu anyārthena grahaṇendī 'va*. ¹⁰ G. M. om. ¹¹ O. *siddhiḥ*. ¹² B. ins. *nishiddhe*. ¹³ O. *shatvanishedanishedho na vidheyah*; B. *nishedho na iti virodhah*. ¹⁴ B. *-ndām*. ¹⁵ B. *artham*; G. M. *tadavastham*. ¹⁶ G. M. *vā tat*. ¹⁷ G. M. O. *samtoṣṭavyam*. ¹⁸ G. M. *ve*. ¹⁹ G. M. *gula*. ²⁰ O. *-thyam*. ²¹ O. om.; G. M. *i*. ²² G. M. *kam*. ²³ G. M. *savasthānaçab*; O. adds *apī*. ²⁴ G. M. *gāvah*.

expect to hear him reply—because *ahah* also is twice mentioned, in the same two rules with *suvaḥ*. But no; we do injustice to the tenderness of his exegetical conscience, in supposing him capable of such gross arbitrariness of interpretation, when in rule 8, instead of *ahah*, *aharahah* is read. He alleges instead the competency of a form cited for another purpose (compare Rik Pr. i.13, r. liv,55): we have read in rule iv.11 *ahorātre*, where the *pragrahas* are under treatment, and this suffices, by analogy of form, to determine the reading also of *ahorātrābhyām* and *ahorātrayoh*. If this be so, it is next retorted, then, as the *sh* of *adhishavane*, which is cited in the same rule, is assured by the citation itself, rule vi.11, prescribing the *sh*, in the way of an exception to an exception, is out of order. That is true, the commentator confesses: but, granting that the *sh* of *sava* is established by the previous mention of *adhishavane*, how is that of *sthāna*, the other word specified in the same rule, established? the rule is therefore to be deemed of force so far as relates to that word, and to be regarded as intended for it. Of what follows, not all is clear to me: it appears that the rule is, after all, defended as it stands, on “the principle of sugar-candy and little tongue” (i. e. as merely giving more than is absolutely required of what one cannot receive too much of, as the palate of candy—?): for to establish the reading on the authority of a previous citation is only doing just what will answer (? *ga-manikā* occurs in only one other passage, the comment on i.18, and I find nowhere any thing that explains its use), while specific mention is a distinction; hence the rule has a meaning as applied to *sava* also: such is the understanding.

The commentator might much better, surely, have acknowledged that his text-book had omitted to provide for the special case of *jaṭa*-reading which has caused all this trouble, than have forced it within the contemplation of the rules at such cost.

दीर्घं च पूर्वः ॥ १७ ॥

17. And the preceding vowel is made long.

The “and” (*ca*) in the rule is declared to signify that the lengthening of the vowel takes place only when *visarjanīya* has been omitted. The cited examples are *rurā rūdraḥ* (v.5.19), *tittirī rohit* (v.5.16), and *vishnū rūpaṁ kṛtvā* (vi.2.4²: only G. M. have the last word). As was noticed in the comment upon the preceding rule, there is no such case of *ah* changed to *ā* before *r*, except the one forming the special subject of the following rules.

17. *tasmād rephaparavisarjanīyāl lupatā pārvo 'pi' yaḥ svarō hrasvaḥ sa ca dīrgham āpadyate. yathā: rurā.....: tittirī.....: vishnū..... yadā 'visarjanīyasya lopas tadāi 'ca dīrghatvām yathā syād ity evamarthaḥ caṣabdaḥ.*

¹ O. om. ² G. M. om. ³ G. M. O. ins. *tasya*.

एष्टश्च ॥ १८ ॥

18. As also, in *eshtah*.

This word has been already mentioned, in rule 8, as one of those whose final *h* is liable to become *r*. It is here made the further subject of a special rule, because it is the only case in the *Sanhitā* of *ah* changed to *ā* before *r* (see the note to rule 16). The passage in which it occurs is *eshtā rāyah* (i.2.11¹ and vi.2.2⁶).

We have seen, however, that the commentator has felt obliged to give a false interpretation to rule 16, and one which renders superfluous the present rule, as applying to a case already included under that one. He is well aware of the objection to his interpretation thence arising, and himself points out that *eshtā rāyo rāya eshtar eshtā rāyah* (only W. gives this) is a case analogous with *rukmo antar antā rukmo rukmo antah* (W. B. omit the last two words), and that the loss of *h* and lengthening of *a* in *eshtah* is an effect of the *tu* in rule 16; but he does what he can toward removing the objection by alleging that the detail of discordant opinions which is to follow (in the next four rules) renders it more desirable to cite the case specially, in order that it may be understood to what those opinions apply. This is a tolerably ingenious subterfuge—but, after all, only a subterfuge.

निकेपाम् ॥ १९ ॥

19. Not so, according to some authorities.

The commentator gives two alternative explanations of this rule—both, however, as he notices, leading to the same reading of the phrase under question. Vararuci, namely, holds that, in the view of some, the rule denies the conversion of *h* to *r* in *eshtah*, and therefore also the prolongation of the *a*; whence, by the general rule ix.8, the word would become *eshṭo* (in analogy with all the other cases in the text of *ah* before *r*). Māhisheya, however, understands that some are said to deny that the *h* of *eshtah* is liable to conversion into *r* before another *r*—that is to say, he makes the rule establish so far an exception under rule 8 rather than rule

18. *eshtar ity asmin grahane visarjanīyo rephaparo* 'varṇa-pārvo 'pī' lupyate'. *yathā*: *eshṭā*..... 'caṣabdo lopadīrghayor ākarshakaḥ'. *navo etad anupapannam: hvārabhār* (viii.8) *ādyantahpātivād eshtar ity asya*: '*eshṭā*.....' *rukmo* *itvat*: *anavarṇapārvās tu* (viii.16) *ity atra tuṣabdena' lopadīrghasiddhau*. 'māi 'cam': *vakshyamānamatabhedācra-yatvajñāpanāya grhitam etad upapannataram: iti parihārah*.

¹ W. B. *rephah*. ² O. om. ³ G. M. ins. *pārvaḥ ca dīrghah*. ⁴ G. M. om. ⁽⁵⁾ G. M. *-ghāv ākarshati*, and put at the beginning. ⁽⁶⁾ B. G. M. O. om. ⁷ W. *iti*; G. M. *iti padam*. ⁸ G. M. *ṣabde*. ⁹ B. *-ghaṣṭuleḥ*; G. M. O. *-ddhe*. ⁽¹⁰⁾ W. B. O. om.

18. There can be little question that Vararuci's explanation is the true one.

In rule 21, below, we have yet another mode taught of arriving at the same result as regards the reading.

द्वावुत्तमोत्तरीयस्य रेफम् ॥ २० ॥

20. According to Uttamottariya, two become *r*.

Here, again, there are two interpretations, Vararuci giving one, Māhisheya the other. The former says that, in the opinion of the specified authority (*śākhin*, 'holder of a *śākhā* or recension of the sacred text'), the *visarjanīya* of *eshta* and the following *r* both become *r*—that is, as I should think it ought to mean, both fuse together into a single *r*: thus, *eshtarāyah*—but none of the manuscripts give this reading in illustrating the case: see the various readings below. Māhisheya, on the other hand, regards the individual referred to as owning the portentous name Dvāvutamottariya, and as holding that the *h* of *eshta* becomes *r* before *r*, making *eshtarāyah*.

Vararuci here maintains, in my opinion, his usual superiority over Māhisheya, as regards both the plausibility of the name assumed and the admissibility of the reading taught; and I have accordingly made my translation conform with his interpretation.

It is interesting to note the uncertainty of the tradition within reach of the commentators as to the personality of the authorities quoted by the Prâtichākhyā.

सांकृत्यस्योकारम् ॥ २१ ॥

21. According to Sāṅkṛtya, the *visarjanīya* becomes *u*.

And this *u*, by x.5, unites with the preceding *a* to form *o*, so that the reading of the passage is *eshto rāyah*, as it is according

19. *ekeshām mata eshtar iti visarjanīyo rephaparo na lupyate: ata eva pūrvavaradīrghābhāvaḥ ca: kim tu ghoshavatparaḥ ca* (ix.8) 'ity oṭvam'. *yathā: eshto rāyah. vararuciviracitam etat: māhisheyabhāshitam tv' evam: eshtar iti visarjanīyo rephaparo 'repham nā' "padyata iti. siddharāpam ubhayoh samānam.*

⁽¹⁾ W. om. ² G. M. om. ³ G. M. ca. ⁽⁴⁾ G. M. na repham āpnōti. ⁵ O. om. na.

20. *uttamottariyasya śākhino¹ mata eshtar iti visarjanīyas² tatparo rephaḥ ca dvāv utāu repham āpadyete. yathā: eshtar³ rāyah. ayam artho vārarucoktaḥ⁴: māhisheyoktas tu dvāvutamottariya iti kasya cin nāma: tanmata eshtar⁵ iti visarjanīyo rephaparo repham āpadyate: ⁶ eshtar⁷ rāya iti⁸.*

¹ O. -nor. ² G. M. -yaḥ ca. ³ B. G. M. -tā; O. -tār. ⁴ W. B. O. var-. ⁵ W. B. eshta rāya. ⁶ O. ins. yathā. ⁷ B. G. M. -tā. ⁸ G. M. O. om.

to the "some authorities" quoted in rule 19, above. This is pointed out by the commentator; who, however, declares that the reference to *Sāṃkrtya* in a separate place shows that he is not one of the people there spoken of. B. specifies (probably by a copyist's blunder) that the exposition given of the meaning of the rule is to be credited to *Māhisheya*.

उच्यस्य सपूर्वः ॥ २२ ॥

22. And, according to *Ukhyā*, along with the preceding letter:

That is, *eshtar* becomes *eshṭu*, the *h* and its predecessor *a* coalescing into *u*. This is the only exposition given by W. and O. But G. M. and B., strangely agreeing for once to differ from the rest, ascribe this understanding of the meaning of the rule to *Māhisheya*, and report *Vararuci* as holding it to signify that the *h* of *eshṭah*, with its predecessor, becomes *r*. This last version of the *sandhi* seems little better than nonsense, and neither of the MSS. gives a reading to correspond.

The commentator declares, finally, that, in this net-work of alternative views, the first rule only (viii.18) is approved. In accordance herewith is the reading of the edited text and of my manuscript, *eshṭā rāyah*.

The most interesting circumstance connected with this waste of half a dozen rules over the reading of a single word, is the indication afforded of the anomalousness of the combination as a phenomenon belonging to the *Tāittirīya-Saṃhitā*, while it is in other Vedic texts a natural and usual thing.

कखपकारपरः पमकारपूर्वः समवग्रहः ॥ २३ ॥

21. *sāṃkrtyasya mata eshtar iti visarjantiyo rephapara ukāram āpadyate*¹. *tata² uvarṇapara okāram (x.5) iti otvam. yathā³: eshto rāyah. asya ca nāi⁴ keshām (viii.19) ity asya⁵ deḡabhedād bhedaḥ: siddhodāharaṇam⁶ samānam.*

¹ B. adds *iti māhisheyoktam*. ² G. M. om. ³ W. B. G. M. om. ⁴ G. M. O. ins. ed. ⁵ G. M. O. ins. tu.

22. *ukhyasya mate rephapara¹ eshtar iti visarjanīyah pūrva-varṇena saho² kāram āpadyate: iti māhisheyoktam³. yathā⁴: eshtu⁵ rāyah. vararucoktam⁶ tv eshtar iti visarjantiyo rephaparaḥ pūrvena saha repham āpadyata iti⁷. yathā⁸: eshtā⁹ rāyah¹⁰. pūrvena saha vartata iti sapūrvah.*

asmin vikalpajāle¹¹ prathamam eshtaḡ ca (viii.18) iti sūtram eve¹² shtam.

¹ G. M. om.; O. puts after *iti*. ² W. om.; O. *iti*. ³ G. M. om. ⁴ B. -to; G. M. -ta. ⁵ W. O. om. ⁶ B. var-. ⁷ G. M. om. ⁸ G. M. om. ⁹ M. om. ¹⁰ B. -rd.

¹¹ W. jāle.

23. At the end of the former member of a compound, before *k*, *kh*, or *p*, *visarjanīya* becomes *sh*—or *s*, if preceded by *a*.

The commentator notes the fact that, as a different following occasion is here introduced, the implication “followed by a vowel or a sonant consonant,” which has so long been in force (namely, since rule 3 of this chapter), comes to an end. His illustrative examples are: *atho havishkṛtānām eva* (vi.4.3²: O. omits *eva*), *grasitām nishkṛhidati* (vi.1.9¹: O. omits the first word), *bahishpa-vamāna upasadyah* (vi.4.9²: O. omits the last word), *namaskārāir evāi ’nam* (v.5.7⁴: O. omits *enam*), and *pathaspathah paripatim* (i.1.14²: O. omits the last word). As counter-example, to show that the *h* must end the first member of a compound, not an independent word, we have *pushpavatīḥ prasūvatīḥ* (iv.2.6¹), and *namaḥ pitrbhyo abhi* (iii.2.8³: only G. M. have *abhi*).

This is a general rule, applying to almost all the compounds in the *Sanhitā* which show a final *h* before an initial *k*, *kh*, or *p* of the second member. A few exceptions are mentioned farther on (rules 32, 33).

आविर्निरिउःशचतोऽपसोत्वरिपोऽद्दसोऽतिदिवोवि-
चतोऽश्मनस्तमसः ॥ २४ ॥

24. Also in *āvih*, *nih*, *idāh*, *ṣaṣvatah*, *apasah*, *deva rishah*, *añhasah*, *ati divah*, *viṣvatah*, *aṣmanah*, and *tamasah*.

This rule, the commentator remarks, relates to words which are not first members of compounds. His examples are: for *āvih*, *āvish kṛnushva* (i.2.14²). For *nih*, *ghṛtaṁ nish pibati* (ii.3.11⁵):

23. *atra paranimittaviṣeṣaṇād’ etatparyantā’ svaraghoṣhavat-parānuvṛttir’ mantavyā. avagrahāntavartā’ visarjanīyah kakāra-khakārapakāraparah shakāram āpadyate: akārapūrvāḥ cet sakāram. yathā’: atho.....: gras.....: bahish.....: namas.....: pathas..... avagraha iti kim: push.....: namaḥ..... kakāraḥ ca khakāraḥ ca pakāraḥ ca kakhapakārāḥ: te’ pare’ yas-mād asāv’ tathoktaḥ. akāraḥ pūro yasmād asāv akārapūrvāḥ.*

¹ G. M. -shād. ² W. etāvatp-. ³ G. M. -paratvān-. ⁴ W. -havatara; B. -ha; G. M. -havarti. ⁵ G. M. om. ⁶ O. etc. ⁷ G. M. parā. ⁸ G. M. O. sa.

24. ¹..... *eshu’ visarjanīyah kakhapakāraparo’ yathāvihi-tam’ bhajate. yathā’: āvish.....: ghṛtaṁ.....: idas.....: ṣaṣv.....: apasas.....: uror.....: deve ’ti kim: sa.....: añhasas.....: ati.....: ati’ ti kim: divah.....: viṣv.....: tvam.....: ud.....*

anavagrahārtho ’yam ārambhah.

⁽¹⁾ G. M. dvirādīshu vidyamāno. ⁽²⁾ G. M. ins. hi shakāram akārapūrvāḥ cet sakāram iti. ⁽³⁾ G. M. -thāsāh-. ⁽⁴⁾ G. M. O. om.

of *nish* before *p*, I find besides only *nish padgeran* (vii.3.10²); before *kh*, *nish khidati* (ii.2.10⁵); before *k*, the cases are more numerous, with forms of *kri* (e.g.v.5.7²), and *kram* (vi.4.10²⁻³: doubtless; the separation of the divisions prevents the exhibition of the *sandhi*); cases of *nih* with accented forms of verbs in *k* are yet more frequent, but come under the preceding rule, not this one. For *idāh*, *idās padē sam idhyase* (ii.6.11⁴ and iv.4.4⁴: O. omits the last two words): on the other hand, we have *idāyāh padē at* vi.1.8². For *ṣaṣvatah*, *ṣaṣvatas kar haste* (ii.2.12¹). For *apasah*, *apasas pāre asya* (iii.2.11²: O. omits *asya*). For *deva rishah*, *uror ā no deva rishas pāhi* (i.4.45²: O. omits to *deva*); with *sa rishah pātunaktam* (i.2.14⁷; 5.11¹⁻²) as counter-example, to show that the prescribed effect takes place only after *deva*. For *añhasah*, *añhasas pātu vāyuh* (iii.2.4³: only O. has *vāyuh*): another case is found in the same division, *añhasas pātum*. For *atī divah*, *atī divas pāhi samāvartan* (i.8.14²: G. M. O. omit after *pāhi*); with *divah prsthān svar gated mīgrāh* (iv.6.5¹: only B. has the last word; O. omits the last three) as counter-example, to show that the prescribed effect takes place only after *atī*. For *viṣvatah*, *viṣvatas pari havāmahe* (i.6.12¹: G. M. omit the last word): other cases occur at i.5.3²; ii.1.11¹; 3.14¹; iii.1.11⁴; iv.2.1^{3,34}; 3.13² (in the various repetitions of only two phrases, always before *pari*); and, as first member of a compound, hence falling under the preceding rule, at iv.6.2⁴: an exception is noted in a later rule (viii.32). For *aṣmanah*, *tvam aṣmanas pari paṣyantah* (iv.1.7⁴ and v.1.8⁶: only O. has the last word, and it omits the first two).

कृधिपिन्वपथेपरः ॥ २५ ॥

25. Also before *kr̥dhi*, *pinva*, and *pathe*.

The examples are: *uru nas kr̥dhi* (ii.6.11²), *apas pinva* (iv.3.4²), and *saprathā namas pathe* (iv.7.13²: G. M. omit the first word). For *pinva* and *pathe* I find no further examples; but *s* before *kr̥dhi* occurs also at i.4.2 (where the edition has the false reading *h*), 3: iv.2.9⁴; 5.10²; v.7.6³⁻⁴; vi.3.2²; 4.5⁴.

न सक्रघकारपरे ॥ २६ ॥

26. But not when *s*, *kr*, or *gh* follows.

25. ----- *evamparo visarjanīyo yathāvidhim¹ bhajate. yathā²: uru..... apas.....: sapr-----*

¹ O. -vīhitam. ² G. M. O. om.

26. *sakraghe¹ 'ty evampare sati kr̥dhyādau² visarjanīyo yathā-vīhitam³ nā 'padyate. yathā⁴: tād.....: ṣam..... rephena kim: uta.....: uru-----*

¹ W. adds *kāre sati*. ² O. -ādī. ³ G. M. -vīdhim. ⁴ W. B. G. M. om.

By its terms, the rule means that the prescription of the preceding rule becomes void when either of the words there mentioned is followed as here specified; but the cases of its application, so far as I am aware, all concern *kr̥dhi*. The commentator's illustrations are: *tān ma āmanasaḥ kr̥dhi svāhā* (ii.3.9¹: only W. has the first two words, and it omits the last one), *gam ca nah kr̥dhi: kratve dakshāya* (iii.3.11⁴: O. omits the last word), and *uru kshayāya nah kr̥dhi: ghr̥taṁ ghr̥tayone* (i.3.4¹: G. M. O. omit the last word); and to the second of these there is a counter-example, *uta no mayas kr̥dhi kshayadvirāya* (iv.5.10²), to show that only *kr*, not *k* alone, gives occasion for retention of the *h*. The words *āmanasaḥ kr̥dhi svāhā* occur again at ii.3.9²: I find no other cases to be specified in addition to those quoted by the commentator.

पत्नविपतीपतेपतयेपतिष्यतिपरः ॥ २७ ॥

27. Also before *patnī ve*, *patī*, *pate*, *pataye*, *patih*, and *patim*.

The examples are: first, *brahmanas patnī vedim* (iii.5.6¹), with a counter-example, to show that the word *patnī* must be followed by *ve*, *retodhāḥ patnī va ity āha* (vi.5.8⁴: but O. reads *indriyāvataḥ patnīvantam*, i.4.27); further, *śubhas pati idam aham* (iii.2.10²: only O. has *aham*), *vāstosh pate prati* (iii.4.10¹), *pracyavasva bhūvas pate* (i.2.9 and vi.1.11⁴), *vācas pataye pavasva* (i.4.2), *vācas patir vācam* (i.7.7¹), and *vācas patim vigvakarmānam ātaye* (iv.6.2⁵: G. M. O. omit the last word). The inquiry is now raised, why it was necessary to give all these words in detail, instead of comprehending them all in *pat*, and in reply is quoted the passage *divaṁ gacha svāḥ patā* (iv.1.10³ and v.1.10⁴).

The cases of retention of *s* before the cases of *pati* are so numerous, that it would be highly convenient to be able to dispose of them at once by quoting in the rule the theme *pati*; but such a proceeding is permitted (by i.22) only with themes ending in *a*. I add the other combinations of this class which I have noted from the *Sanhitā*: *manasas pati* (i.1.13²; 4.44³), *pathas pati* (i.1.14²), *brahmanas pati* (i.5.6⁴: ii.1.57), *jyotishas pati* (i.5.11¹: iv.4.4⁶), *śavāsas pati* (ii.2.12⁷), *jagatas pati* (ii.4.5¹), *sadasas pati* (ii.6.8²: iii.2.4⁴), *śatinas pati* (ii.6.11¹: iv.4.4¹), *nabhasas pati* (iii.3.8^{3.6}), and *yas patih* (iv.7.14³). We have the genitive *patēḥ* in *br̥has-patēḥ* (i.7.8⁴), but, as the *pada*-text reads *br̥has-patēḥ*, the word does not fall under this rule: *tapaspati* (i.2.10²; p. *tāpah-patih*)

27. *evamparo visarjanīyo yathāvihitam¹ bhajate. ya-thā²: brah-.....: va iti kim: reto-.....: śubh-.....: vāst-.....: pra-.....: vāc-.....: vāc-.....: vāc-..... pad ity etāvatai³ 'va siddhe 'pratipadapāṭhena kim⁴: divaṁ.... ityādinishedhār-tha⁴.*

¹ B. G. M. -vidhiṁ. ² G. M. O. om. ³ G. M. -thaḥ kimārthaḥ; O. -tho. ⁴ O. -ddau n.

belongs in the same category. Of the words quoted by the commentator, *bhuvāṣ pati* occurs again at i.7.10², and *vācāṣ pati* at ii.6.8^{1,2}.

दिवःसहसस्यरिपुत्परः ॥ २८ ॥

28. Also in *divaḥ* and *sahasah*, before *pari* and *put*.

The cited examples are *divas pari prathamam* (i.3.14⁵ and iv.2.2¹), *divas putrāya sūryāya* (i.2.9: O. omits the last word), and *sahasas putro adbhutaḥ* (iv.1.9²). We have *sahasas putram* also at iv.4.4³, and *divas pari* at iii.3.3² and iv.2.10⁴; one case of *divaḥ pari* is excepted by rule 34, below. As counter-examples, are given *divaḥ prthivyāḥ pary antarikshāt* (iii.1.10² et al.: W. B. O. omit *divaḥ*, which is better, as this is used just below to illustrate another point), *parushahparushah pari* (iv.2.9²), and *putraṣaḥ putrān uta viśvāyushaḥ rayim* (iv.6.9⁴: G. M. O. have only the first two words), to show that only the words specified show *s* before *pari* and *put*; and *divaḥ prthivyāḥ pari* (iii.1.10² et al.: G. M. omit *pari*, which is better this time), to show that those words show it only in the circumstances stated.

Put is declared a part of a word, involving more than one case.

रायस्योपरः ॥ २९ ॥

29. Also in *rāyah*, before *po*.

The commentator's examples are: *paçavo vāi rāyas poshaḥ* (v.4.6²), *saṁ ahaṁ rāyas posheṇa* (i.7.9²), *çāntanuvāya rāyas poshāya* (iii.2.5¹: G. M. omit the first word and add *bṛhate*, which makes the reference belong to iv.1.10²), and *rāyas poshasya daditārah syāma* (iii.2.3¹: only O. has the last word). As counter-examples, he gives *vibhuḥ posha uta tmanā* (iii.1.11²), to show that the rule applies to no other word than *rāyah* before *po*, and *eshṭā rāyah pre'she bhagāya* (i.2.11¹: G. M. omit the first word),

28. *divaḥ: sahasah: ity ayoṛ¹ visarjanīyah pariputparo² yathāvidhim³ bhajate. divas.....: divas pu.....: sah.....: anayor iti kim: divaḥ.....: par.....: puṣ.....: evampara iti kim: divaḥ.....: anekārthatvāt⁴ puṣ iti padāikadeṣaḥ.*

¹ B. anayoh; G. M. etayoh. ² G. M. pari: put: ity evamparo; O. do. except ity. ³ G. M. O. -vīdhim. ⁴ B. G. M. O. -rthah.

29. *rāya iti atra visarjanīyah po ity evamparo yathāvidhitam¹ bhajate. yathā: paçavo..... po iti padāikadeṣo bahāpādānārthah: saṁ.....: çānt.....: rāyas.....: rāya iti kim: vibhuḥ.....: ²po ity okāreṇa kim³: ⁴eshṭā.....*

¹ G. M. -vīdhim. ² G. M. O. om. ³ G. M. okārah kimarthah. ⁴ B. om. to yathā in comment to next rule.

to show that only *po*, not *p* when otherwise followed, calls out the prescribed effect in *râyah*.

I have not attempted to note the numerous instances of the occurrence of *râyas posha* in the Sanhitâ. In the derivative *râyas-poshavani* (i.2.12²; 3.1²), where the division is before *vani*, the *pada*-text, according to its custom, leaves the *s* of *râyas* unchanged (reading *râyasposha-vani*).

नमस्करोपरः ॥ ३० ॥

30. Also in *namah*, before *karo*.

The examples illustrating the action of the rule are *sanivatsarena namas karomi* (v.5.7³), and *ubhayibhyo namas karoti* (ii.6.9²; O. reads *karomi*); counter-examples, showing the uselessness of either specification of the rule without the other, are *namah kapardine ca* (iv.5.5¹, 9¹; W. omits *ca*; O. omits the example), and *ekahâyanâd enah karoti* (vi.6.3¹).

Other instances of *namas karoti* are found at v.5.5¹, 7²; vi.3.8⁴; and of *-vatsarena namas karomi* at v.5.7³ twice, 7⁴ twice.

The printed text has *greyasas karat* and *vasyasas karat* (but, by a strange inconsistency, immediately after, *pâçumatah karat*) at i.8.6²; but, as these combinations are unauthorized by the Prâtichâkhyâ, and not supported by my manuscript, I do not doubt that the readings are erroneous.

वमुष्कारपरः ॥ ३१ ॥

31. Also in *vasuh*, before *k*.

The passage is *sa idhâno vasush kavih* (iv.4.4⁵), and I have found no other. Counter-examples, of obvious application, are given: *viprah çuciḥ kavih* (i.3.14⁶; 5.5³), *mayi vasuh puro vasuh* (iii.2.10²), and *viçvâvasuh pary amushnât* (vi.1.6⁵, 11⁵; B., which is quite defective just along here, omits the first word).

नाधरंविश्वतोऽन्तर्जातोविविश्रुःपरुःपुनः ॥ ३२ ॥

30. *nama ity atra¹ visarjanīyah karo ity evamparo yathāvihitam² bhajate. yathā³: saṁv----- ubhay----- 'karo iti kim: namah-----' 'nama iti kim: ekah-----'*

¹ G. M. O. om. ² G. M. -vidhim. ³ G. M. O. om.; B. omits to here. ⁽⁴⁾ O. om. ⁽⁵⁾ G. M. put before *ubhay*; B. puts after *ubhay-----*, and om. *karo iti*.

31. *'vasur ity atra visarjanīyah kakāraparo yathāvihitam² āpadyate³. yathā⁴: sa----- vasur iti kim: viprah-----: evam-para iti kim: mayi-----: viçvā-----*

⁽¹⁾ B. om. ² G. M. -vidhim. ³ G. M. O. *bhajate*. ⁴ G. M. O. om.

32. Not in *adhvaram viçvatah, antah, jatah, viviçuh paruh,* and *punah*.

These words constitute exceptions under the foregoing rules. The commentator specifies in each case under which rule the exception falls. The first example is *yajñam adhvaram viçvatah paribhār asi* (iv.1.11¹: O. omits the first word, W. B. the last): an exception under viii.24, which would require *viçvatas*; W. B. O. remark that the distinctive addition of *adhvaram* effects the exception, and W. O. add the counter-example *indram vo viçvatas pari* (i.6.12¹). For *antah*, the example is *mahādevam antahpārçvena* (i.4.36: O. omits the first word): an exception under rule 23, *antah* being first member of a compound. For *jatah*, *bhūtasya jatah patir eka āsit* (iv.2.8²: O. omits the first word, and alone adds *āsit*; G. M. omit *ekah* also): an exception under viii.27. For *viviçuh paruh*, *yā āviviçuh paruhparuh* (iv.2.6³); with the counter-example *parushparur amughushyā viçasta* (iv.6.9³: only G. M. have the last word). For *punah*, finally, *punahpunar hy asmāt* (vi.5.13⁴: only G. M. have *asmāt*). Both these last are exceptions under viii.23.

The versions of the comment to this rule are more than usually discordant, all being defective except W. and O., and even these having suffered considerable disarrangement. For the details, see the various readings below.

धषवति ॥ ३३ ॥

33. Nor before a word containing *dh* or *sh*.

"By vicinage," says the commentator, is understood a negative, in this and in the next following rule. The meaning of the rule is that, when a word containing either of the letters *dh* or *sh* follows the *visarjanīya*, the latter is not liable to conversion into *s* or *sh*, as required by the foregoing precepts. The examples given are

32. ----- *eteshām¹ visarjanīyo yathāvihitam² na bhajate³. yathā: yajñam-----: āvirnir⁴ (viii.24) iti prāptih: 'adhvaraviçeshanān niṣṛtīh': 'adhvaram iti kim: indr-----: mahā-----: 'kakhapakāra (viii.23) iti prāptih: bhāt-----: patnī-vepatī⁵ (viii.27) iti⁶ prāptih⁷: 'yā-----: viviçur⁸ iti kim: parush-----: punah-----: kakhapakāraparah⁹ (viii.23) ity anayoḥ prāptih.*

¹ G. M. *ity eteshu*. ² G. M. *-vidhim*. ³ G. M. O. *āpadyate*. ⁴ G. M. O. om. ⁵ G. M. add *idam*. ⁶ G. M. om. ⁷ B. G. M. om.; W. O. put next before *viviçur* *iti kim*. ⁸ B. om. ⁹ O. om. *pati*; G. M. *patishpatim*. ¹⁰ O. *ity ādinā*. ¹¹ W. B. O. put after *mahā-----*. ¹² G. M. *-ruḥ parur*. ¹³ G. M. O. om. *parah*.

33. *sāmnidhyād atra¹ paratra ca² nañārtho labhyate. dhag³ ca shag⁴ ca dhashāu: tāv asmint sta iti dhashavat: tasmin dhashavati⁵ pade parabhūte sati⁶ pārvo visarjanīyo⁷ yathāvihitam⁸*

bahihparidhi skandāt (ii.6.6² and vi.2.8³: the same divisions contain each a second example of the compound), *purushahpurusho nidhanam* (vi.6.3²: the same division contains a second example of the compound), and *ubhayatahksnūr bhavati* (v.1.1⁴). I have noted besides only *parushahparushah pari* (iv.2.9²). That the word containing *dh* or *sh* must follow the *visarjanīya*, not be the one that itself ends in that letter, is shown by the counter-examples *adhaspadam kṛnute* (iv.7.13³), and *ṛtasya jyotiṣhas patim* (i.5.11¹).

परिवाप्रपरः ॥ ३४ ॥

34. Not before *pari vā* or *pra*.

The examples are *rocanaḥ divah pari vājeshu* (iv.2.11¹: only G. M. have the first word)—with the counter-example *divas pari prathamam* (i.3.14⁵ and iv.2.2¹), to show the need of citing *vā* after *pari*—and *tasmād itahpradānam devāh* (iii.2.9⁷: O. omits *devāh*). Of these, the first is an exception under viii.28; the other, under viii.23. There is yet another passage, *bahihprāno vāi manushyah* (vi.1.1⁴), which needs to be brought under the rule; and the commentator accordingly declares that the quotation of *pra* in this rule with short *a* is intended to connote *prā* also—just as, in a rule of the next chapter (ix.24), *athā* connotes *atha* also, by a converse principle. This, however, suggests a difficulty: why then is not rule vii.7, prescribing for *prā* an effect which had already been

nā "padyate. yathā": bahih-----: puru-----: ubhay-----: kakhapakāra⁹ (viii.23) iti prāptih. parabhūta iti kim: adhas-----: ṛtasya-----¹⁰

¹ G. M. ins. ca. ² G. M. O. ins. sūtre. ³ G. M. O. dhakdraç. ⁴ G. M. O. shakāraç. ⁵ B. G. M. O. om. ⁶ O. om.; G. M. pūrvas-. ⁷ G. M. -vidhīn. ⁸ B. G. M. O. om. ⁹ B. -rapara. ¹⁰ W. adds *tasmān iti nidhīste pūrvasya. parivāpravarah.*

34. *pari vā: pra:* ¹ *evamparo visarjanīyo yathāvihitam² nā "padyate. rocanaḥ-----: ve 'ti kim: divas-----: tasmād-----: pre 'ti hrasvagrahanam dīrghasyā 'py upalakṣaṇam:* ³ *yatho 'dathāparaç ca* (ix.24) *iti dīrghagrahanam hrasvasyo 'palakṣaṇārtham⁴. tarhi prāpārvaç ca* (vii.7) *iti sūtram vyartham: praçabdasyā⁵ 'nuvṛttasyāi 'va dīrghopalakṣhakatvād⁶: iti cet: ucyate: pratyakṣagrhītasya⁷ 'vo 'palakṣhakatvam⁸ nā 'nu-kṛṣhtasye 'ti vijñeyam: tathā hi: vāhanauhyamānaḥ* (vii.6) *ity atra⁹ cakāreṇa praçabdas tatrā 'nukṛṣṭah: atra tu¹⁰ parivā-prapara¹¹ ity¹² upalakṣhakatvam¹³ bhavati. tathā satī 'dam āpy udāharanam: bahih-----.*

¹ G. M. ins. ity. ² G. M. -vidhīn. ³ B. ins. ⁴ here, as well as below, in its place. ⁵ G. M. O. -nam; B. hrasvop-. ⁶ G. M. ins. eva. ⁷ G. M. -kṣhanatvād; O. dīrghagrahanasyop-. ⁸ G. M. -tad. ⁹ G. M. om. ¹⁰ G. M. vā-. ¹¹ G. M. ins. pra-para iti pratyakṣagrahītatvād; O. ins. pratyakṣagrhītatvād. ¹² G. M. -kṣhaṇam.

prescribed for *pra*, a superfluity? Because, is the reply, such connotation is only proper in the case of a word directly cited, not of one that is brought forward by implication merely: and in rule vii.6 the *pra* was thus brought forward [from rule 4], in virtue of the *ca*, 'and,' contained in the rule: whereas here the *pra* is expressly mentioned. This seems a case of rather questionable interpretation.

न निर्ण निः ॥३५॥

35. Not so with *nih*.

That is, as the commentator explains it, the exception established by the preceding rule does not hold good in the case of *nih*, which is treated as prescribed in rule 24, even before *pra*. The cases instanced in illustration of the rule are both of a doubtful character: the one is a *jaṭā*-reading, *prāñcāu nir nish prāñcāu prāñcāu nih* (vi.4.10²), the other an extract from the ending of the same *anuvāka* (vi.4.10), *ātmanā parā nish pra śukraśocishā*, these words being those which end respectively the first four divisions of the *anuvāka*. We shall find other quotations of the endings later; and their appearance is at least decisive of the recognition by the commentator of the breaking up of the *anuvākas* into divisions of fifty words each, whatever we may have to believe respecting its recognition by the *Prātiśākhya*. We are not, however, to take for granted that even the commentator accepted the division as now made in our manuscripts, involving a suspension of continuity of the *samhitā*-text after each fiftieth word: there was probably at first a mere enumeration made, with an expression of its results at the end of the *anuvāka*. The endings, as may be seen in the Calcutta edition, are carefully accented, and written according to the rules of combination as laid down by the *Prātiśākhya*. The same rules are followed in the *jaṭā*-text; and hence, as (by rule vii.2, above) *nih* converts the following initial *n* into *ṇ* in *samhitā*, so does it also in the repetitions of the *jaṭā* (*nir nish*). As a yet farther consequence, it has the same effect in the rules of the *Prātiśākhya*, and I have therefore accepted the reading *na* instead of *ṇa* in the repetition of the present rule, although it is supported only by T. and W.

35. *nir ity atra visarjanīyasya¹ praparatve² 'pi shatvanishedho na bhavati: shatvam eva bhavati 'ty arthaḥ. prāñ-.....: ātm-.....*

*iti tribhāshyaratne prātiśākhyavivarane³
aṣṭamo 'dhyāyāḥ.*

¹ O. -nīyāḥ. ² O. prapare. ³ O. ina. prathamapracne.

CHAPTER IX.

CONTENTS: 1-6, treatment of final *h* before initial surd letters; 7-10, treatment of final *ah* and *āh*; 11-15, of final diphthongs before initial vowels; 16-17, of the particle *u*; 18-19, duplication of final *ā* and *u*; 20-24, conversion of final *da*, *in*, *ūn*, to *dā*, *iār*, *ūār*.

॥ १६ ॥ नि नि न ॥
 उष्मपरो षोषपरे लुप्यते काण्डमायनस्य ॥ १ ॥

1. *Visarjaniya*, when followed by a spirant which has a surd letter after it, is dropped, according to Kāṇḍamāyana.

The commentator, after a brief paraphrase of the rule, gives a couple of examples to illustrate its working: namely, *catustanām karoti* (v.1.6⁴; p. *catuh-standām*), and *vāyava stho pāyava stha* (i.1.1). The mention of Kāṇḍamāyana is declared to be made on account of a difference of views: others, namely, hold that *h* is dropped before a spirant that is followed by a sonant letter as well, as *adbhya svāhā* (i.8.13³), *ye çuklā syus tam* (ii.3.1²; W. B. omit *tam*), *yo hatamānā svayampāpah* (ii.2.8³; O. omits *yo*; G. M. omit *pāpah*), and *dānakāmā me prajā syuh* (ii.2.8²; 3.4¹; O. omits the first word; G. M., the first two). I am not sure that I understand the consideration further alleged, in view of which it is decided that "the rule is all right;" it appears to be that, reference having thus been made to a discordance of views, those words will be hereafter specified in which there is omission made under any other prescription—but what this refers to, I am unable to see.

Every MS. that I have reads *ghoshaparo* as second word in the rule: but the comment so plainly implies the reading *-pare*, and the sense so obviously requires it, that I have ventured its adoption.

Although the prescription here given is put upon the authority of an individual, it is pretty evidently to be regarded as definitely

1. *uṣmaparo visarjanīyah kāṇḍamāyanasya mate lupyate tasminn uṣmany aghoṣavatpare* sati. *yathā: catu-..... vāy-..... kāṇḍamāyanagrahaṇam*² *vikalpārtham: anyeṣhām mate ghoṣavatpare* py *uṣmani visarjanīyo lupyate: yathā: adbhya..... ye..... yo..... dāna-..... evaṁ ca vikalpācraṇam*³ *sati lakṣaṇāntaragataim*⁴ *yeshu padeshu lupyate tāni padāni vakṣhyāma*⁵ *iti vacanam saralam bhavati.*

uṣmā paro yasmād 'asāv uṣmaparah': na ghoṣavān aghoṣah: asāv' paro yasmāt 'sa tathoktaḥ': tasminn aghoṣapare,

¹ G. M. O. om. *sat*. ² G. M. -*yanasya gr.* ³ W. -*cravane*; O. -*crayagrahaṇe*; G. M. -*lpāntare*. ⁴ W. O. -*nātara-*. ⁵ G. M. O. *prav-*. ⁶ G. M. *sa tatho 'ktaḥ*. ⁷ G. M. om. ⁸ G. M. om.

adopted and taught by the *Prātiçākhyā*, and is usually (not without occasional exceptions) conformed to by the edition of the *Sanhitā*, and by my manuscripts both of that and of the *Prātiçākhyā* and its commentary. I have, therefore, treated it as peremptory, and have everywhere governed by it the readings I have accepted. The same omission is prescribed by the *Rik* and *Vājasaneyi Prātiçākhyas*, but not by the *Atharvan* (see *Ath. Pr.* ii.40, note).

अधोपरस्तस्य सस्थानमूष्माणम् ॥ २ ॥

2. Followed by a surd letter, it becomes the spirant of like position with that letter.

The commentator's examples are: *yaz kāmāyeta* (ii.1.2^a et al.; O. reads *-yate*); *agnīç ca me* (iv.7.6¹: O. omits this and the next example), *ulākaç çaçah* (v.5.18), *agnis te tejah* (i.1.10^a and vii.5.17: O. leaves out *te*), and *yap pāpmanā grhītaç* (ii.1.3^a, 4^a: W. leaves off the first word; G. M. O. omit the last).

The requirements of this rule are by no means complied with by the manuscripts, nor have I followed them in the present work. In the first place, no manuscript that I possess, or have ever seen, attempts to represent any such sounds as the *jihedmāliya* and *upadhmanīya* (see i.9), or *ç* and *q*; for these, *visarjanīya* is universally substituted, as if the sect of *Āgñivegya* and *Vālmiki* (see rule 4, below) had supplanted all its rivals; and, in the second place, the agreement to leave *visarjanīya* unchanged before a sibilant (according to the view of the authorities referred to below, in rule 5) is nearly as general. In my MS. of the *Sanhitā*, I have noted about thirty cases of conversion to a sibilant, in place of unchanged retention, and they are nearly all in a single limited neighborhood (in iv.5), where a different scribe has developed his originality a little. As is hinted above, in the introduction, however, G. and M. make with great regularity the assimilation of *h* to the following sibilant; O. does it not infrequently; the others, almost never.

I have put together, in the note to *Ath. Pr.* ii.40, a statement of the variously conflicting views respecting the treatment of *h* before the different classes of surd letters held by the different *Prātiçākhyas*, or referred to in their rules; and it is unnecessary to repeat it here. The sole point upon which all authorities agree is the conversion into *ç* and *s* before palatal and dental mutes respectively—and this is also the only point left unquestioned by the rules which follow here in our treatise.

न क्षपरः ॥ ३ ॥

2. *aghoshaparo visarjanīyas tasyā 'ghoshasya sasthanam āshmanam bhajate. yaz.....: 'agnīç.....: ulā.....: agnis.....: yaç.....*

(*) O. om.

3. But not when followed by *ksh*.

That is to say, *visarjanīya* remains unchanged before *ksh*, the preceding rule for its conversion to *jihvāmūliya* being annulled. There is nothing corresponding to the usage here prescribed in either of the other treatises. The commentator quotes a number of examples: *manah ksheme* (v.2.17), *ubhayataḥkshnūr bhavati* (v.1.14: W. B. omit *bhavati*: the *visarjanīya* was exempted from conversion into *s* before the *k* by viii.33), *ghanāghanah kshobhanah* (iv.6.41), *pūrvā 'rshṭuḥ kshīyate* (iii.1.71), and *dyāuḥ kshāmd reriḥat* (iv.2.12: O. omits the last word).

कपवर्गपरश्चाग्निविशेषवाल्मीक्योः ॥ ३ ॥

4. Nor, according to Āgñiveṣya and Vālmiki, when followed by a guttural or a labial mute.

The two authorities here specified (the commentator calls them "holders of a *śākhā*, teachers"), it appears, reject altogether the *jihvāmūliya* and *upadhmānīya*, since they prescribe the retention of *visarjanīya* in the only situations where those problematical sounds are liable to arise. The commentator quotes a couple of illustrative passages: *yaḥ kāmāyeta* (ii.1.2⁵ et al.), and *agnih paçur āsit* (v.7.26: O. has dropped out what follows *agnih*). Then, to show that on other points these heterodox persons accept our rule 2, he cites *madhuç ca mādhaveç ca* (i.4.14 and iv.4.111), *manas tatvāya* (iv.1.11: but B. substitutes *namas talpyāya*, iv.5.91), *āçuç çicānah* (iv.6.41), *yas somam vamiṭi* (ii.3.2⁶).

उष्मपर एवैकेषामाचार्याणाम् ॥ ५ ॥

5. According to some authorities, not when followed by a spirant, and only then.

I believe there can be no real doubt as to the meaning of this rule, although it is not very explicitly interpreted by the commen-

3. *kshaparo visarjanīyaḥ pūrvavidhīm na bhajate. yathā*: *man*-----: *ubhay*-----: *ghanā*-----: *pūrv*-----: *dyāuḥ*-----: *kshakārasya* 'ghoshavattvāt praptiḥ.

¹ G. M. O. om.

4. 'cakāro nishedham ākarshati. āgñiveṣyavālmīkyoḥ' *śākhīnor ācāryayor* mate *kavargaparah pavargaparo vā* pūrvavidhīm 'nā' *padyate*. *yaḥ*-----: *agnih*-----: *kakāraç ca pakāraç ca kapāu*: *tayor vargāu* kapavargāu: *tāu parāu yasmāt sa tathoktaḥ. evampara iti kim*: *madhuç*-----: *manas*-----: *āçuç*-----: *yas*-----.

(¹) G. M. om.; O. *çaçabdo nañākarshakah*: *āgn*-. (²) O. om. (³) O. *kapavargaparo visarjanīyaḥ*. (⁴) O. *na bhajate*. (⁵) O. *kavargaç ca pavargaç ca*.

tator, and although G. M. O. omit the negative in the interpretation (I presume, by a copyist's blunder only). Some authorities, who do not, like Āgñiveya and Vālmiki, refuse to accept the *jīhvāmāliya* and *upadhmanīya*, nevertheless deny the doctrine of rule 2 to this extent—that they prescribe the retention of *visarjanīya*, not its assimilation, before a sibilant. Thus, they would write *āṣuḥ ṣiṣānaḥ* (iv.6.4¹). G. M., as is their constant custom, write here *āṣuḥ*; and so does O., as is its common, though far from invariable, usage: but this means nothing; for we have no good reason to expect the manuscripts of the commentary to conform themselves in any such case to a reading which will truly illustrate the matter in hand; they simply make the *sandhi* in the manner usual with them: for example, under rule 2, no MS. attempts to indicate the *ḥ* and *ṣ*, and W. B. give the *h* instead of the sibilant before the sibilant.

If we reject this interpretation, our sole alternative is, so far as I can see, to hold that some authorities would accept rule 2 only so far as it relates to *h* before a sibilant, but would retain *h* every where else, even reading *agnih te tejah*, *agnih ca me*. This seems altogether inadmissible. Yet we must acknowledge that it is to some extent favored by the commentator's selection of counter-examples, namely *manas tatvāya* (iv.1.1¹: but B. substitutes again *namas tatpyāya*, iv.5.9¹) and *yah kāmayeta* (ii.1.2² et al.). According to our preferred interpretation, there would be no particular reason for quoting the former of these, since the combination it illustrates has been made a question by no one: according to the other, it would be required (in the form *manah tatvāya*), to show what these dissidents held should be done in such a case.

न ब्राह्मिब्राह्मणयोः ॥ ६ ॥

6. Not according to Plākshi and Plākshāyana.

The natural interpretation of this rule would seem to be, that Plākshi and Plākshāyana are not of the number of those who hold the objectionable doctrine of the last rule, or of the last two rules. If, however, I rightly apprehend the commentator, he declares it

5. *ekeshām ācāryānām mata āshmapara eva visarjanīyah pārvavidhim na¹ bhajate. yathā: āṣuḥ..... evakāreṇa kim: manas.....² yax.....³*

¹ G. M. O. om. ² G. M. O. om. ³ G. M. om.

6. *kapavargopara¹ āshmaparaḥ ca visarjanīyah plākshi-plākshāyanayoḥ śākhinoḥ² pakṣhe na khalu pārvavidhim bhajate. yah..... yax..... āṣuḥ..... evampara iti kim: manas.....*

¹ *kapavargādi sūtratrayam anishṭam.*²

¹ O. *kapavargoparaḥ pavargoparaḥ ca.* ² G. M. om. ³ G. M. prefix *evam*, and put the whole at the end of the comment on the preceding rule; they also omit rule 6.

to mean "in the opinion of these two authorities, it does not—that is, *h* does not follow the prescription of rule 2 either before a guttural or palatal mute or before a spirant." This is equivalent to a ratification of rule 4, and a ratification or rejection of rule 5, according as we adopt the one or the other of the two interpretations proposed for the latter; and it is, in my view, quite unsuited to the connection. The discordant explanations of some of the other views of designated authorities given in the rules of the treatise show us that the commentators had not in all cases, at least, any certain knowledge by tradition of the matters referred to, but simply interpreted as well as they were able the notices of their text-book—and we have the same right as they in this respect. If the particular point here under discussion were of more practical consequence, I should be inclined to go into a fuller discussion of it; as the case stands, it has perhaps cost us already more words than it is worth.

The commentator illustrates by repeating several of the quotations already given—namely *yāh kāmāyeta* (ii.1.2^a et al.), *yāh pāpmanā* (ii.1.3^a et al.), *ācuh ṣiṣānah* (iv.6.4¹): these as direct examples; as counter-example, according to W. O., *manas tatvāya* (iv.1.1¹), for which B. once more substitutes *namas talpyāya* (iv.5.9¹), while G. M. read *agnic ca me* (iv.7.6¹)—the readings of which, as regards the *visarjanīya*, each manuscript gives in its usual fashion (except that W. has this time *ācuhṣ ṣiṣānah*, by a blundering divergence in the wrong direction), so that we are deprived of any farther aid from that quarter to the understanding of the rule.

Finally, rules 4–6 are declared not approved.

श्रोकारमः सर्वे ङ्कारपरः ॥ ७ ॥

7. *Ah*, the whole of it, when followed by *a*, becomes *o*.

The commentator's cited examples are *preddho agne* (iv.6.5^a and v.4.7^a), *samiddho añjan* (v.1.11¹), and *so 'bravit* (ii.1.2¹ et al.). He then enters into a long exposition intended to prove the necessity of the specification *sarvāh*, 'the whole of it,' in the rule. Without it, we are told, the reading *samiddho añjan* (in the second example given) would not be established: for, by 1.56, alteration and omission concern only a single letter; hence, if *sarvāh* were omitted, only the final *visarjanīya* would be converted to *o*; this, with the preceding *a*, would become *āu* by x.7; the *āu* would

7. *aḥsarvo visarjanīya* 'otvam' bhajate 'kāraparah': *aḥsarva ity akāreṇa sahe* 'ity arthah. pre-----: sam-----: so----- *aḥsarva iti kim: samiddho añjann iti na sidhyet: kim tu varṇasya vikāralopāv* (i.56) *iti visarjanīyamātrasya syād otvam: tata okārdūkārāparah* (x.7) *ity āukāre kṛta āukāra āvam* (ix.15) *ity āvādeṣah: tathā sati samiddhāv añjann iti syāt. 'yad vā: ' svaraparo yakāram* (ix.10) *iti yatvam* *

be converted into *av* by ix.15, and the final reading would be *samiddhā añjan*. Or, again [supposing the present rule not to be given], the *visarjaniya* would become *y* by ix.10, the *y* would be dropped by x.19, the preceding *a* would be exempted from further combination by x.25, and the *samhitā*-reading would turn out *samiddha añjan*.

The Ath. Pr. (ii.53) avoids the same difficulty by prescribing the conversion of the *h* into *u*, which then combines with the preceding *a* into *o*. The other treatises (Rik Pr. ii.12; Vāj. Pr. iv.42) treat the combination in the same manner as our own. What becomes of the following *a* is taught in the eleventh and twelfth chapters.

घोषवत्परश्च ॥ ८ ॥

8. Also when followed by a sonant consonant.

Only one example of this combination is cited, namely *mā no mitro varuṇaḥ* (iv.6.8¹: G. M. O. omit the last word).

The commentator raises against this rule the objection that, as prescribing the same thing with the one preceding, it should not have been made a separate rule at all; and, in reply, he promises that the exposition of the meaning of *tu* in the next rule shall explain the reason of the proceeding.

अवर्णपूर्वस्तु लुप्यते ॥ ९ ॥

9. But *visarjaniya*, when preceded by an *a*-vowel, is omitted.

In these rules, from 7 to 10 inclusive, the *anuvṛtti*, or continuance of implication, is intricate and irregular in an unusual degree, and even beyond the measure of what ought to be tolerated. The implication of *visarjaniya* being made all the way from viii.5 to

bhavati: tasmīṅca lupyete tv avarṇapūrvāu yavakārāv (x.19) iti yakāre¹ lupte paraṣ ca paraṣ ca (x.25) iti² kāryāntarāprasiddheḥ³ samiddha⁴ añjann ity syāt: tan mā bhūd ity⁵ evam arthah⁶: aḥsarva⁷ ity uktam.

¹ G. M. om., and ins. app. ² G. M. okāram. ³ G. M. put at the beginning. ⁴ G. M. sahito visarjaniya. ⁵ O. sidhyati. ⁶ B. G. M. om. ⁷ G. M. kin ca; O. kin tu. ⁸ G. M. O. ins. aḥ. ⁹ G. M. O. ins. vā. ¹⁰ G. M. O. om. ¹¹ O. ins. sūtreṇa. ¹² G. M. prasakte; O. prasaktiḥ tathā sañ. ¹³ W. -ādho; B. -ddhāu. ¹⁴ G. M. om. ¹⁵ G. M. O. om.; B. om. evam. ¹⁶ B. om. aḥ.

8. *cakāra¹ okāram aḥsarvaṁ cā² nvādicati. aḥ³ sarvo ghosha-
vatpara⁴ oṭvam bhajate. yathā: mā . . . nanu vidhāu samāne
prthakkarāṇam⁵ anarthakam iti cet: uttarasūtre tuṣṭadvayākhyā-
nenā⁶ sphuṭīkarishyata⁷ iti parihārah.*

¹ G. M. put next before nvādicati. ² O. om. ³ G. M. O. raṣ ca. ⁴ G. M. O. om. ⁵ G. M. -kārak-. ⁶ G. M. -khyāne. ⁷ W. O. -shya.

ix.10 (as pointed out in the comment to viii.5); rule 7 of this chapter ought to teach that “*visarjaniya*, when preceded by *a*, becomes *o* along with the latter, when *a* follows:” instead of which a new subject, “the whole syllable *ah*,” is introduced there; and *visarjaniya*, being thus replaced by something else in rules 7 and 8, ought to drop out of view altogether, or, if needed further, to be distinctly specified over again. But we find it implied without specification in the present rule; and, further, the being followed by a sonant consonant is brought down “by vicinage” from rule 8, while the *tu*, ‘but,’ the commentator says, merely annuls the being followed by *a*, as specified in rule 7. This is little less than absurd: if the sequence of *a* was to be annulled at all, it should have been so in rule 8—or, rather, it was annulled by rule 8, and needs to be made no further account of. The *tu* is here, as often elsewhere, a simple sign of a change of subject, and the commentator’s attempt to give it a precise significance is—also, as often elsewhere—a failure. Our rule means, by its terms, that *ah*, *āh*, and *āḥ* lose their *h* before a sonant consonant; only, as *ah* was already specially provided for by rule 8, it virtually applies only to *āh* and *āḥ*. The statement is thus made more general than is needed for the case in hand, because the whole implication of “preceded by any *a*-vowel” is needed for rule 10, which is to teach that *ah*, *āh*, and *āḥ* before a vowel—here, again, with the exception of *ah* before *a*, already provided for—convert their *h* into *y*, preliminary to dropping it altogether, by x.19. But rule 10 presents a more anomalous combination of two heterogeneous matters into one precept than is easily to be paralleled elsewhere in the *Pratīṣākhya*. It is really made up of two independent parts: one, *atha svaraparāḥ*, ‘Now then, when followed by a vowel,’ which is an introductory heading having force through this chapter and the next; the other, *visarjaniyo yakāram*, ‘*h* becomes *y*,’ and their combination is made in order that the implication of *visarjaniya* and also of *avarṇapūrva* may be made from what precedes, and may not require to be distinctly stated.

The commentator’s examples of the application of the rule are *devā gātucidāḥ* (i.1.13³; 4.44³; vi.8.2³), and *vicityāḥ somāḥ na vicityāḥ iti* (vi.1.9¹; *somāḥ* for *somāḥ*, by protraction from *somāḥ*: G. M. omit the last two words, O. the last three). He adds, as his exposition of the connection of the rule, that the express spe-

9. *avarṇapūrvo ghoshavatparas tu¹ visarjaniyo lupyate: hrasvapūrvasyāu² ‘kāra’ eva dīrghapūrvasya³ pīṭhapūrvasya eva lopah. yathā: devā..... viḥ..... akāram ah sarvo⁴ ‘kāraparāḥ* (ix.7) *ity akāraparatvam pratyakṣam tuḥabdena nivartyā⁵ ‘nūmānikam ghoshavatparatvam porigṛhyate sāmīdhyāt: asyā⁶ ‘nūvartanam eva ‘bhīṣtam atre⁷ ti pūrvasūtradvayaḥ⁸ prthak-karanam.*

¹ W. ins. *saḥ*. ² B. G. M. *vīḍrā*. ³ B. *rea*; O. *ghā*. ⁴ G. M. *trāṣya*.

cification of sequence by *a*, made in rule 7, is annulled by the word *tu*, and that an inferential sequence by a sonant consonant is assumed by vicinage [from rule 8]; and that the implication here of the latter only is the reason why rules 7 and 8 are given independently of one another. That is to say, such is the easiest way of arriving at the result desired, that the *h* of *dh* and *as**h* is not directly dropped before *a*, but passes through the intermediate step of conversion into *y*, as before the other vowels.

अथ स्वरपरो वकारम् ॥ १० ॥

10. When followed by a vowel, it becomes *y*.

That is to say, *visarjanīya* does so, if preceded by an *a*-vowel (rule 9)—except in the case of *dh* followed by *a* (rule 7). And, as is intimated by the prefixion of *atha*, the specification "followed by a vowel" is of force also in the following rules (through chapter x.). I have remarked in the preceding note upon the anomalousness of this rule, as striving to fuse into one the winding-up of one subject and the introduction of another. It has not seemed possible to render the *atha* excepting by a longer and more tedious paraphrase than I was willing to introduce; accordingly, I have left it out in translating the precept.

The commentator's examples are *āpa undantu jivase* (i.2.1¹; G. M. O. omit *jivase*), *tā abruvan* (ii.3.5²; 5.1³), and *anvārabhyās iti* (vi.3.8¹; *anvārabhyās* for *anvārabhyāśh*, by protraction from *anvārabhyah*); and he gives further, as counter-examples, *āpo varuṇasya* (v.5.4¹; a not unexceptionably selected example, since *āpah* even before a vowel might not follow the present rule), and *agnir ekākshareṇa* (i.7.11¹; a case under viii.6, as the preceding under ix.8).

This conversion of *visarjanīya* into *y* is only the preliminary step to its complete loss, by rule x.19. The same course of conversion is followed by the Atharvan and Vājasaneyi Prātiśākhya (Ath. Pr. ii.41; Vāj. Pr. iv.36), but not by that of the Rik (ii.9,10).

एकारो ज्यम् ॥ ११ ॥

11. *E*, before a vowel, becomes *ay*.

10. 'athaśabdo 'dhikārārthaḥ': svarah paro yasmād asāu svaraparāḥ. ita uttaram yad ucyate svarapara ity evam tatra nimittatvenā 'dhikṛtaṁ veditavyam'. sāmniḍhyād avarṇapūrva iti labhyate: svaraparo visarjanīyo 'varṇapūrvo' yakāram āpadyate. yathā: āpa..... tā..... anvā..... svarapara iti kim: āpo..... avarṇapūrva iti kim: agnir.....

⁽¹⁾ G. M. āthe 'ty ayaṁ adhikārah; O. -kārah. ⁽²⁾ O. so 'yam. ⁽³⁾ G. M. vakshyāmaḥ. ⁽⁴⁾ G. M. O. jñātavyam. ⁽⁵⁾ O. om. pūrva. ⁽⁶⁾ G. M. put before svarapara. ⁽⁷⁾ O. yatvam. ⁽⁸⁾ O. om.

Of which, then, the *y* is lost by x.19, leaving only *a*; and this, by x.25, is not liable to further combination. The commentator's examples are *ima evā 'smāi* (ii.4.10²), and *ta enam bhishajyanti* (ii.3.11⁴).

ओकारो ऽवम् ॥ १२ ॥

12. *O* becomes *av*.

The example is *viṣṇav e 'hi 'dam* (ii.4.12³). For the further treatment of the *v* thus produced, see x.19 and the following rules.

नाकारयो ॥ १३ ॥

13. But not, in either case, when followed by *a*.

The dual number of the attribute in this rule, we are told, sufficiently shows that the two letters *e* and *o*, last mentioned, are its subject. There are two different rules in the treatise applying to the case of a final *e* or *o* coming to stand before initial *a*—namely rule 11, above [or rule 12], and rule xi.1, which directs that the latter shall be elided—and, since the rules of this chapter are of paramount force, as preceding the other, the present precept is required in order to annul them.

The commentator's examples are *mā te asyām* (i.6.12⁵), *samidho añjan* (v.1.11¹), and *te 'bruvan* (ii.5.1² et al.).

ऐकार आयम् ॥ १४ ॥

14. *Āi* becomes *āy*.

11. 'visrahto visarjanīyah'. *idam*² *idānim ucyate: svaraparāḥ padānta*³ *ekaro 'yam iti vikāram āpadyate. ima.....: ta.....*

⁽¹⁾ G. M. *visargo nirvṛtāḥ*; O. *visargo vinirgataḥ*. ² G. M. om. ³ W. -*tah*; B. -*te*.

12. *svapararāḥ*¹ *padānta okaro 'vam iti*² *vikāram āpadyate. yathā:* *viśh-.....*

¹ G. M. *svarāḥ*. ² B. G. M. O. om. ³ W. B. G. M. om.

13. *dvivacanasāmartyagrhītāḥ*¹ *ekārāukārāv akāraparāḥ*² *pārvavidhīm*³ *na prāpnutaḥ. yathā:* *mā.....: sam.....: te.....: ity ādāv ekāro 'yam* (ix.11) ⁴ *lupyate tv akāra ekārāukārapārvaḥ* (xi.1) *iti*⁵ *sātradevayam prasaktam: tatā 'pi pārvatvat prabalaṁ*⁶ *yatpavidhīm nisheddham ayam ārambhaḥ. akārah paro yābhyām tāv akāraparāḥ.*

¹ B. G. M. O. -*thyāt gr-*; and G. M. O. add *sannihitāḥ*. ² G. M. O. om. ³ G. M. om. *pārva*. ⁴ G. M. om. ⁵ G. M. ins. *iti ca*; O. ins. *iti*. ⁶ G. M. O. ins. *ca*. ⁷ O. ins. *ekāraṣya*.

The example is *āśmāha eva māu dādāyāu māsāu* (vii.5.2¹; B. omits the last word, G. M. O. the last two).

To complete the *sandhi*, also, which is the subject of this rule and its successor, rule x.19 is needed.

ग्रीकारः घ्रावम् ॥ १५ ॥

15. *Āu* becomes *āv*.

The example is *āhān anadātā hate* (x.6.1²).

उकारोऽपृक्तः प्रकृत्या वकारोऽन्तरे ॥ १६ ॥

16. An *u*, uncombined with a consonant, remains unchanged, and *v* is inserted between it and the following vowel.

The definition of *apṛkta* was given above, at i.54, and such a word was directed to be treated both as initial and as final (i.55). This rule makes an exception for the particle *u*, which becomes *uv* before a vowel—which, moreover, never occurs after an *a*-vowel except as combined with it, forming part of the class of *pragrahas* in *o* which were treated above, in rules iv.6,7. The examples given are *sa uv ekaviṇṣavartanih* (iv.3.3²), and *adanty uv evā'sya mānushyāh* (ii.3.7³): I have noted further only iv.6.9⁴, but am not sure that I have been careful to mark all the cases. As counter-examples, *svapatyāya deva* (v.5.4⁵; p. *sv-apatyāya*) shows that the *u* must be *apṛkta*, and *bhakshe 'hi* (iii.2.5¹), that no other *apṛkta* vowel than *u* is thus treated.

न तत्तस्मात्साहितः ॥ १७ ॥

17. But not in *sāhita*-text, after *tat* and *tasmāt*.

The passages are *tad v āhur utsriyam* (vii.5.7¹; O. omits after *āhur*), and *tasmāt v āpyam* (vi.1.11⁶). So far as I have observed, these are the only instances which the text affords of *u* following

14. *svaraparāh padānta' dīkāra āyam vikāram āpadyate. yathā: āśām*-----

¹ B. G. M. -nte. ² G. M. O. om.

15. *'āukārah padāntah' svaropara' āyam vikāram āpadyate. yathā: ahān*-----

¹ B. -nte. ² G. M. insert the order. ³ G. M. O. om.

16. *apṛktasāṅghāka' 'ukārah svaraparāh' prakṛtyā 'vatish-
thate: avikṛto' bhavati 'ty arthah: ukārasvarayor antare 'vakā-
raḥ cā 'gamo' bhavati. yathā: sa.....: adanty..... apṛkta
iti kim: sva.....: ukāra iti kim: bhak*-----

¹ G. M. -jāa. ² G. M. ukārasvāh. ³ G. M. -kāro. ⁴ O. vakārag. ⁵ W. B. G. M. om.

a consonant and preceding a vowel. Compare the similar rules in the other treatises (Rik Pr. ii.28; Vāj. Pr. iv.87; Ath. Pr. iii.36). The preceding precept being thus annulled with reference to these two cases, they fall under the general rule x.15, and the *u*, like any final, is converted into *v*. To show the bearing of the specification *sāmhita*, 'in combined text,' the commentator gives us the two passages in *pada* and *krama* form: thus—*tat: u: āhuh: tad u: uv āhuh: āhur uterjyam* (but G. M. O. give simply the first two *krama-pada*'s), and *tasmāt: u: āgyam: tasmāt u: uv āgyam* (here only W. has the statement in *pada*). It thus appears that the combination with the preceding consonant is indispensable to the treatment of the *u* as here prescribed; failing that, it falls under the preceding rule, and becomes *uv*.

ऋत्वपूर्वो उकारो द्विवर्णम् ॥ १८ ॥

18. A *ṛ*, when preceded by a short vowel, is doubled.

That is to say, when another vowel follows—the heading *atha svaraparah* (ix.10) still continuing in force. The commentator adds also "when occurring at the end of a *pada*," as he has done in his paraphrase of the preceding rules: this is a matter of course, as we are dealing only with the conversion of *pada*-text into *sāmhita*. His illustrative examples are *nyāññ agñih* (v.5.3²), and *tam u tvā dadhyaññ rāhīh* (iv.1.3² and v.1.4⁴; only G. M. have the first two words). That the preceding vowel must be short, he shows by *parāñ ā vartate* (iii.2.9⁷ and vi.3.8³); that a vowel must follow, by *sadrūk samānāñ syāt* (ii.2.8⁶; only O. has the last word; only B. G. M. have the inserted *k*, required by v.32, and G. M. convert it to *kh*, by xiv.12), and *pratyāññ śhaḥ-ahāh* (vii.4.2⁵; here all have the *k*, but only G. M. make it *kh*).

17. *tat tasmād ity' etābhyāñ sāmhita ukāro 'pṛktaḥ pūrva-ādhīm nā 'pnōti': prakṛtyāvasthānañ vakāraḥ' ca nā bhavati 'ty arthah. tad....: tasmād....: ivarnokārāu yavakārāve (x.15) iti daḡame 'syā' vidhīr vakshyate'. tat tasmāt sāmhita iti kim: tat....: tasm-....*

¹ G. M. om. ² G. M. "padyate; O. prāpn-. ³ G. M. O. -rāgamāḥ. ⁴ O. -ma. ⁵ B. *tasya*. ⁶ O. ins. *tasya purastādapavādo 'yam*.

18. *'svaraparo śakārah padāntavartī hrasvapārvo' dvivarnam 'bhajate. yathā: nyāññ....: tam....: hrasvapārva-iti kim: par-....: svarapara-iti kim: sad-....: praty-....: hrasvapārvo yasmād asāu hrasvapārvaḥ: deḡayor varṇayoh samāhāro dvivarnam.*

(1) G. M. arrange *hr- sv- pad- śak-*. (2) G. M. O. ins. *deḡayam*. (3) G. M. om.

नकारश्च ॥ ११ ॥

19. As does also a *n*.

The *a* in this rule brings down, we are told, the preceding cause of duplication and the duplication itself. The cited examples are *nir avapann indrāya* (ii.4.2²), and *abruvann r̥dhnavat* (i.5.1²). The counter-examples, given for the same purposes as those under the preceding rule, are *niravapan yāny eva purasāt* (ii.4.1²: O. omits the last two words), *omanvati te smin* (ii.6.9⁵: O. omits the last word), *yān agnayo 'nvatapyanta* (iii.2.8³: O. omits the last word; G. M. omit the whole example), and *vidvān etam agniṁ cinute* (v.6.5²). The commentator does not give himself the trouble this time to inquire why two rules are furnished to prescribe a single process: the reason is, evidently, because continued implication of *n* only is desired in the rules that follow.

अनितिपरो ग्रहोऽव्याप्यापृथग्रहणवर्णिवेधीकारो-
कारपूर्वो रेफमाकारपूर्वश्च यकारम् ॥ २० ॥

20. In *graha*, *ukhya*, *yājyā*, *prsthya*, and *hiranyavarṇiya* passages, a *n* preceded by *i* or *ū* becomes *r*, preceded by *ā* becomes *y*, except before *iti*.

The remainder of the chapter is occupied with rules respecting these conversions of a final *n* after *ā*, *i*, and *ū* before an initial vowel—conversions of which the original ground is the same with that which causes the combinations *ñca*, *ñst* to result from the collision of *n* with *c* and *t* (v.20, vi.14), namely the partial retention of an original *s* which followed the *n* as part of the declensional termination of the word. See note to Ath. Pr. ii.27 for a full statement of the teachings of the other Prātiçākhyas respecting them. The conversion of *n* to *y* is equivalent to its omission, since the *y* is dropped by x.19. Rules xv.1-3 are also needed to complete the combinations intended, by the nasalization of the preceding vowel, or the insertion of *anusvāra* after it.

19. *cakārah pūroanimittam' dviteyam cā 'nvādigati. hrasva-pūrvo nakāro dvivarnam' bhajate' svaraparāh. nir-----: abruvann-----: evampara iti kim: nir-----: oman-----: evampūrva iti kim: yān-----: vid-----*

¹ G. M. *pūrvoktan*. ² G. M. O. *dviteyam*. ³ G. M. *āpadyate*.

20. *grahokhyādishu' vishayeshu ikārapūrva akārapūrvo vā cakārākṛshṭo nakāro 'niti para' itivyatiriktasvaraparā' repham āpadyate: akārapūrvaḥ ced yakāram. graho nāma caturo 'nvā-*

As in other similar cases, the commentator, after his preliminary paraphrase of the rule, proceeds first to define the passages of the *Sanhitā* designated by the titles it contains. By *graha* is meant the fourth chapter of the first book, excepting its last four sections—or i.4.1–42. By *ukhya*, the first two chapters of the “*Agni*” book (see iii.9), excepting their final sections (which are *yājyā*)—or iv.1.1–10; 2.1–10. The *yājyās* have been already defined (iii.9, note), as the concluding sections of all the chapters to book fourth, chapter third, together with ii.6.11. By *prsthya* are intended nine sections, pointed out by the citation of the first words of each: they are iv.4.12; 6.6–9; 7.15; v.1.11; 2.11; 2.12. *Hiranyavarṇīya* designates only a single section, v.6.1. Examples are then given from each set of passages. From *graha* passages, we have *jahi catrāṇr āpa mrdho nudasva* (i.iv.42), and *maruṣcāṇr indra vṛshabhah* (i.4.19; G. M. O. omit the last word): there are four other cases, at i.4.20 twice, 21.41. From *ukhya* passages, *ye vā vanaspatīṇr anu* (iv.2.8³), and *madhumāṇr astu sārjyah* (iv.2.9³): there are ten others, at iv.1.3³ twice, 9^{2,3}, 10^{2,4}; 2.4^{2,5}, 9² twice. From *yājyā* passages, *rtāṇr r̥tapatē yajē ha* (iv.3.13⁴; only O. has the last two words), to which W. B. O. add *amavāṇr ibhena* (i.2.14¹); but for this G. M. substitute *madhumāṇr indriyāṇr* (iii.1.10²), which is not in a *yājyā* passage at all, but falls under the next rule: I have noted more than thirty other cases, namely at i.1.14⁴; 2.14²; 3.14³; 4.46²; 5.11²; 6.12⁴; 7.13^{4,5}; ii.1.11⁵ thrice; 2.12^{3,5}; 3.14^{2,6}; 6.11¹ thrice⁴ twice, 12^{1,2}; iii.1.11¹ thrice, 7; 2.11³ twice; 4.11²; 5.11²; iv.2.11³; 3.13^{2,3,4} twice. The same passages contain five exceptions, which are duly provided for in rules 23 and 24, below. From *prsthya* passages, the examples are *catrāṇr anapavyayantah* (iv.6.6²) and *jaghanāṇr āpa jighnate* (iv.6.6²): other cases at iv.6.7⁵, 9⁴ twice; 7.15⁷; v.1.11⁴. Finally,

*kān' varjayito'ā "daḍe grāvā" (i.4.1¹) iti praṇah: agnikāṇḍa-
syā "dyam praṇadvayam uttamānuvākavarjam ukhyam' ākhyā-
yate: uktā yājyāh: samid diṣām (iv.4.12¹) jimatasyā
(iv.6.6¹) yadākrandah (iv.6.7¹) mā no mitrah (iv.6.8¹) ye
vājinam (iv.6.9¹) agner manve (iv.7.15¹) samiddho aṇjan
(v.1.11¹) gḍyatrī (v.2.11¹) kas tvā (v.2.12¹) ity anuvākanava-
kam' prsthīyam iti pathyate': hiranyavarṇāḥ (v.6.1¹) ity
anuvāko hiranyavarṇīyah. "grāhe yathā:² jahi.....: mar.....
ukhye: ye.....: madh..... yājyāsu: rtāṇr.....: ama.....
prsthīye: catr.....: jagh..... hiranyavarṇīye: agnīṇr.....:
saro..... anitipara iti kim: abhy.....: idā..... grahādī-
sho iti kim: trīn.....: paṇān.....: tān.....*

iti paro yasmād asāv itiparah: ne 'tiparo 'nitiparah.

¹ G. M. read *grā* throughout. ² B. om. ³ G. M. O. *ity etasmād anyasvar-*; B. *iti 'ty etad asmad anyas-*. ⁴ G. M. O. *'ntyanuv-*. ⁵ G. M. *-vā si*. ⁶ G. M. O. *ins*, *ity*. ⁷ G. M. *anuvākah*. ⁸ W. O. *pachyate*; G. M. *pathyante*. ⁹ G. M. om.

from the *hiraṇyavarṇīya* section, *agnīr apsushadah* (v.6.1²), and *sarodā agnī* (v.6.1²), which are the only cases. Counter-examples, of *n* not converted as here prescribed, because occurring outside the passages specified, are *trīṇ imān lokān iti* (vii.3.2¹), *pa-gān evā vā rundhe* (v.1.1¹ et al.), and *tān indro ntaryāmenā ntar adhatta* (vi.4.6¹: G. M. O. omit the last two words). And the bearing of the specification "except before *iti*" is illustrated by examples from the *krama* and *pada* texts, namely *abhyavartanta dasyān: dasyān iti dasyān* (i.6.12²: *dasyān* is thus repeated, as being the closing word of the *anuvāka*; but W. O. omit this repetition, which exhibits the very point requiring illustration, and B. adds only *iti dasyān* to the first *dasyān*), and *idāvān iti idāvān* (iii.1.11¹: *samhitā*-reading, *idāvān eśahā*). Any general examination of the aspect of this mode of combination in the Taittirīya text I defer to the end of the chapter.

मर्त्यानुदयानमृतान्दुर्यानसोमपूर्वः सोऽस्मानविमानो-
मान्मधुमान्द्विष्मान्भूतमानर्षिचिकिवानिडावान्कन्नी-
वान्वाणवान्हिप्यस्वान्वशान्विद्वानमित्रानरान्योषा-
न्महाश्च ॥ २१ ॥

21. Also in the words *martyān*, *ud ayān*, *amrtān*, *duryān* not preceded by *soma*, so *asmān*, *avimān*, *gomān*, *madhumān*, *haviṣmān*, *kūtamān* before any vowel belonging to the text, *cikivān*, *idāvān*, *kakshivān*, *bānavān*, *hi payasvān*, *vaçān*, *vidatrān*, *amitrān*, *arān*, *poshān*, and *mahān*.

The *ca* in this rule, says the commentator, brings down from the preceding rule the specification "except before *iti*;" but we might fairly claim that it involves all the specifications there made excepting the restriction to certain passages: this exception the comment duly notes: "this and the rules that follow have a general application, without regard to special portions of the text."

The illustrative examples are: for *martyān*, *martyān āveçya* (v.7.9¹). For *ud ayān*, *ud ayān ājasram* (iv.6.3²): with a counter-example, *vayobhīr evā yān ava rundhe* (v.2.10¹), to show that

21. *eteshu grahaneshu nakāro 'nitiparo 'yakāram*
āpadyate. *anūtiparatvākarshako 'yam cakārah*. *vishayān' anā-*
drtya sarodārtho 'yam itah param ārambhah. *yathā: mart-*
....: ud ay....: ud iti kim: vayo....: ud....: bhād....:
nā somapārvaḥ: duryān ity atra nakārah somapārvo yatvaṁ nā
'padyate: pra....: so....: so iti kim: indro....: avi....:
gom....: madh....: avigomadhv' iti kim: paçu....: hav-
....: kūtamān ārshe': kūtamān ity atra nakāra 'ārshe seare

the *ut* before *ayān* needed to be quoted along with it. For *amṛtān, ud aśthān amṛtān anu* (i.2.8¹). For *duryān, bhadrān duryān abhye* ^{hi mām anuvratā nyu} (i.6.3¹: G. M. O. omit *mām* etc.); there are two other cases, at i.2.13¹: vi.2.9¹; and a single exception, *pra eard soma duryān adityāh* (i.2.10¹), quoted by the commentator in justification of the restriction "not preceded by *soma*." For *asmān, so asmān adhīpatān karotu* (i.6.8¹ and iii.2.7²): another example is at v.7.9¹; and *asmān* becomes *asmān* also at i.6.12⁴, but in virtue of the preceding rule. The counter-example, showing the necessity of prefixing *so* in the rule, is *indro asmān asmin deitīye* (iii.1.9²: W. B. omit the last word). For *avimān, avimān arvi* (i.6.8¹; 7.6¹: iii.1.11¹: but the last case falls under the preceding rule also). For *gomān, gomān agne* (i.6.8¹; 7.6¹: iii.1.11¹—that is to say, in the same phrase with *avimān*). For *madhumān, madhumān indriyāvān* (iii.1.10²). Next follows a counter-example, intended to show why *mān* would not have been enough of itself to include the last three words, without the prefixed parts *avi, go,* and *madhu*: it is *paṣumān eva bhavati* (vi.2.6¹ et al.). Then, for *havishmān, havishmān ā vicāsati* (i.3.12): the word occurs a second time in the same section, and also at vi.4.2⁴. For *hātāmān, devahātāmān ity ukhāyān juhōti* (v.5.3¹: W. B. omit the last word): it is found again, in like form, in the succeeding division of the section. The specification "before any vowel belonging to the text (*ārsha*, 'coming from the *rshis*')," is declared to be meant as an annulment of the restriction, "except before *iti*," made in the preceding rule. And, to show that the *n* remains unchanged before a vowel not forming part of the fundamental text, is given the *pada*-reading *devahātāmān iti deva-hātāmān*. There is added further a remark which looks like a gloss that has worked its way into the text: "the specification 'before what comes from the *rshis*' has force in both directions, after the fashion of the crow's eye [Molesworth says, the crow is regarded as having a single eye, which shifts from one eye

*pare*¹ *yatvam āpadyate*²: *dev*.....: *ārsha iti kim*: *dev*.....:
¹ *ārshagrahaṇasāmarthyād itiparatve* "*pi*" *yatvam bhavati*: *ārsha iti kakākshivad*³ *ubhayatra sambadhyate grahokhyādima-*
*hānparyantam*⁴: *ārshasvayampātha*⁵ *ity arthah, cikit*.....:
idāv.....: *kak*.....: *vig*.....: *idākakshibāne*⁶ *ti kim*: *ras*
: *sam*.....: *hi* *ti kim*: *arj*.....: *ārsha itiparatvād dev*.....:
*itivād yatvaprāptir higrahanena nishidhyate*⁷. *stuto*.....: *su-*
vid.....: *amit*.....: *arān*.....: *posh*.....: *agne*.....

¹ For *asomapūrvah*, G. M. read *ity eṣa nakāras somapūrvco 'nusedran na* "*pad-*
yate"; B. O. *na som*-, as do T. G. M. in the rule itself. ² G. M. O. *eshu*. ³ G. M.
yatevam bhajate. ⁴ G. M. om. *ayam*. ⁵ G. M. *midhān*. ⁶ W. *sarvo rtho*. ⁷ W. B.
iti. ⁸ G. M. *drītan*. ⁹ W. O. *avimādhv*. ¹⁰ W. adds *cikītvān*. ¹¹ G. M. O.
ārshasvaroparo. ¹² W. *nāśadyate*; B. *bhavati*; G. M. O. *bhajate*. ¹³ G. M. ins. *ity*.
¹⁴ G. M. *pare*. ¹⁵ G. M. ins. *hātāmān ity ukhāyān ity atra*. ¹⁶ W. O. *kaksh*; G.
 M. *kshinyayena*. ¹⁷ W. B. om. *māhān*. ¹⁸ B. *ārshah sv*; G. M. *ārshabhāvan*.
¹⁹ G. M. *idādivicēshena*. ²⁰ G. M. O. *pratiśh*.

ball to the other, as it is needed]—namely, from the beginning of the preceding rule to the end of the present one.” This appears to mean that an *iti* belonging to the sacred text itself would admit the conversion of the *n* before it, in any case falling under these two rules. The opinion is doubtless a sound one; but, to prove its expression pertinent here, we require an example showing that there is a passage in the text requiring its application: and none such is furnished us; on the contrary, the addition of *ārshē* to *hātamān* alone implies that none is to be found. The example for *cikiteān* is *cikiteān anu manyatām* (iii.1.4¹: O. omits the last word). For *idāvān*, *idāvān eshaḥ* (i.6.6⁴; also at iii.1.11¹; but this is a case falling under the preceding rule). For *kakshivān*, *kakshivān āgijāḥ* (v.6.5³). For *bānavān*, *viṣalyo bānavān uta* (iv.5.1⁴: O. omits the first word). Next we have again a counter-example, *rasavān eva bhavati* (ii.2.4⁵), showing that, of words ending in *vān*, only those preceded as here specified undergo the prescribed effect. For *hi payasvān, sam asrkshmahi: payasvān āgā ā'gamam* (i.4.45², 46²: only O. has *sam*; and G. M. O. omit the last two words): the necessity of the prefixed *hi* is shown by the counter-example *ārjavān payasvān ity āha* (i.7.3⁴). Here, however, is a case of *payasvān* before an *iti* which comes from the *rshis*, and therefore might seem to require the reading *payasvān*, like *hātamān* in the passage *devahātamān ity ukhāyām* (v.5.3¹)—according to the extension made above of the natural and obvious meaning of *ārshē*; but the commentator declares that the mention in the rule of *hi* as necessary preceding word prevents the conversion of *n* to *y* in the passage: it is, to be sure, a case of *payasvān* before *iti*, but not of *hi payasvān*. For *vacān*, the example is *stuto yāsi vacān anu* (i.8.5¹). For *vidatrān*, W. O. give *suvidatrān apī 'ta* (i.8.5²), while G. M. have instead *suvidatrān avīsi* (ii.6.12³): B. is defective here, dropping out the last part of this quotation, and the first part of the next (reading *suvidatrān apabādhamānāḥ*); G. M. are in the wrong this time, for the passage they quote falls under the preceding rule. For *amitrān*, *amitrān apabādhamānāḥ* (iv.6.4²): an exception is provided for in the final rule of the chapter. For *arān*, *arān ivā 'gne nemih* (ii.5.9²: O. omits the last word). For *poshān*, *poshān apushyat* (vii.1.9). For *mahān*, *agne mahān asi* (ii.5.9¹): another case at i.4.20.

इन्द्रोमेऽकवृद्धमिहायिवगन्मेडेन्यानायनिष्ठश्चाचर्वकुर्व-
तादृद्धदितिरयेऽधरात्सपन्नानत्तंपरश्च ॥ २२ ॥

22. Also a *n* followed by *indro me*, *akah*, *ūdhvam*, *ihā*, *apy etu*, *aganma*, *idenyān*, *āyajishthah*, *ā ca*, *rtu*, *akurvata*, *aduhāt*, *aditih*, *agre*, *adharānt sapatnān*, and *alam*.

22. *ity evamparo nakāra 'ākārapārvo yatcam' apadyate.*
cakāra' ākārāpūrvatvākārshakah. yathā: sap-....: ma iti kim:
yush-....: nigr-....: yāy-....: agne-....: dīrghena kim:

The implication here, the commentator tells us, is of a *n* preceded by *ā* only: he does not explain why, but would have a right to appeal to the mention of *ān* last in rule 20, and the exclusion of any other cases than those of a final *ān* in rule 21. His examples are as follows. For *indro me, sapatnān indro me* (i.1.13¹; 6.4²; iv.6.3⁴); with a counter-example, *yushmān indro 'ornita* (i.1.5¹), to illustrate the need of specifying *me*. For *akah, nigrābhenā 'dharān akah* (i.1.13¹; 6.4²; iv.6.3⁴; that is to say, in the same passage as the preceding: O. omits the first word). For *ādheam, yāyam devān ādheam* (i.3.8²; O. omits the first word). For *ihā, agne devān ihā "vaha* (i.3.14²; 5.5²; iv.6.1²); with a counter-example, *yajñiyan ihā yān hācāmahe* (i.5.10²; only W. has the last word), to show that the *nimitta* in this case is *ihā*, not *iha*. For *apy etu, gharma devān apy etu* (i.5.10⁴; B. omits *gharmah*: again at i.6.3²); with the counter-example, *vidvān api janyeshu* (vi.1.6⁶), to show that *api* without *etu* does not cause the conversion. For *aganma, svar devān aganma* (i.7.9²). For *idenyān, idāmahāi devān idenyān* (ii.5.9⁶). For *āyajishthah, devān āyajishthah svasti* (iv.3.13¹; 6.1²; O. omits the last word). For *ā ca, devān ā ca vakshat* (iv.6.3⁴ twice, and v.4.6⁶ twice); but this example is omitted by G. M., and they also omit the item *ā ca* in the rule itself. A counter-example, *yān ā vaha uçatah* (i.4.44²; G. M. omit the last word), is given by all but O.: in G. M., it should show that *ā* causes *ān* only when followed by *yajishthah*; in W., only by *yajishthah* and *ca*; but W. states the occasion for it in the same manner as G. M., and B. alone sets it in its proper relation to both the foregoing examples. For *rtu*, the example is, in W. B., *vājo devān rtubhih* (iv.7.12²), but G. M. O. give instead *yebhir devān rtubhih* (i.1.14⁴): I have found no other case. For *akurvata, vittvā kāmān akurvata* (i.5.9²). For *aduhat, yajño 'surān aduhat* (i.7.1¹). For *aditih, vivasvān aditih* (i.5.3³). For *agre, agnis tān agre* (iii.1.4²): we have also *vāyus tān agre* in the same division. For *adharān, anyān adharānt sapatnān* (iii.2.8⁶); with a counter-example, *bhrātreyān adharān pādayāmi* (iii.5.3¹). For *alam, purodācān alam kurv iti* (vi.3.1²). Finally, to show that the rule applies only to *ān*, *paridhān akurvata* (vi.2.1⁵⁻⁶).

The comment closes with an exposition which I must confess that I do not fully understand. It is evidently intended to determine the readings which the words treated in these rules shall have in *ajāṭ*-text; and it furnishes abundant illustrations, in reference to the form of which, however, there is not a little difference between the different recensions: G. M. O. generally citing the passage first

yajñ.....: *ghar*.....: *eto iti kim*: *vidvān*.....: *svar*.....:
idā.....: *devān*.....: *'devān*.....: *'yajishthac ce 'ti kim*: *yān*
: *vājo*.....: *vit*.....: *yajño*.....: *vivas*.....: *agnis*.....:
anyān.....: *sapatnān iti kim*: *bhrā*.....: *puro*.....: *anvāde-*
cah kimarthah: *pari*.....: *tattatpadagrahaṇe kartavye parapa-*
dagrahaṇam 'anārshe 'pi saṁhātāvidhāv' agraḥaṇasya' ca' ya-

in its *samhitā*-form, and adding only a single *sandhi* from the *jaṭā*-text, while W. B. give the complete *jaṭā*-readings, and only those. The former quote first *amartyo martyān āveṣa* (v.7.9¹), and add *martyān amartyah*; W. gives *amartyo martyān martyān amartyo martyān*, and *martyān āveṣa* "veṣa martyān martyān āveṣa"; B. only the latter (and, blunderingly, treats it as *amartyān āveṣa*, throughout); next, G. M. O. have *ud asthām amrtān anu*: *amrtān asthām* (i.2.3¹); W. B., *amrtān anu anu amrtān amrtān anu*. Then, in illustration of a second point, we receive two more examples: G. M. O. read *agne vimān agre*: *avimān agne* (i.6.6⁴ et al.), for which W. B. substitute *agne vimān avimān agne* 'gne vimān'; and G. M. O., again, *ud ayān ajasram* (iv.6.3²); O. this time adding the full *jaṭā*-reading *ud ayān ayān ud ud ayān*, which G. M. also seem to mean to give (they actually have only *ayān ud ayān*); while W. B. set down the *jaṭā*-form of the other pair of words: *ayān ajasram ajasram ayān ayān ajasram*. Yet once more, two examples for a third point close the tale: in G. M. O. *agnis tān agre*: *tān agni* (iii.1.4²), in W. B. *tān agre* 'gre tāns tān agre'; and, this time in all alike, *anyān adharān* *anyān anyān adharān* (but G. M. have, doubtless by a copyist's blunder, *anyān* the second time, before *anyān*). It will be seen that the two versions are in part inconsistent with one another as regards the special points of combination to which they direct attention; and I am not able to make out what are the three classes of cases meant to be distinguished. The three points which one would most naturally think of as needing to be noticed are, perhaps, first, the occurrence of a word like *amrtān* before itself—thus, *amrtān amrtān*—in the *jaṭā* repetition; second, its occurrence before a preceding word (not its defined or natural *nimitta*) when that word begins with a vowel—thus, *amrtān asthām*; and third, its occurrence in *jaṭā* before the word which causes its alteration in *samhitā*—thus, *amrtān anu*—if, indeed, this last can be regarded as requiring any special prescription. Or, the second and third cases might be expected to concern the treatment respectively of a word, on the one hand, like *martyān*, which is itself quoted in the rule as suffering the prescribed change (which is at the same time *grahana* and *nāimittika*, or *nāimittikaṁ grahanam*), and might therefore naturally be inferred to be liable to the change under all circumstances before a vowel; and one, on the other hand, like *anyān*, which is pointed

tvam syād iti nāimittikasya ca nimittāpekshatvāt. grahanasya yathā: amartyo.... ud.... evaṁ nāimittikagrahanasya: agne.... ud.... evaṁ grahananāimittikasya³: agnis.... anyān.... evaṁ sarvatra nakārasya yakārotpattir¹⁸ drashṭavyā.

⁽¹⁾ B. om. ⁽²⁾ G. M. O. *yakāram*. ⁽³⁾ G. M. om. ⁽⁴⁾ O. om.; W. G. M. read *yajishtha iti kim* etc. ⁽⁵⁾ G. M. a. ⁽⁶⁾ O. *-dhāne*; B. *-dhānasye*. ⁽⁷⁾ B. om. ⁽⁸⁾ G. M. O. om. ⁽⁹⁾ G. M. O. *-pasya nāi*. ⁽¹⁰⁾ G. M. *nakā*.

out by means of the quotation of the following word *adharān* (which is itself, therefore, *nāimittika*, while *adharān* is *grahana*; or which is *grahanādimittika*, 'undergoing a prescribed effect under the influence of a quoted word'), and which one might suppose changeable only before that word. It is in accordance with this latter explanation that the last two pairs of examples are taken, the one from under rule 21, the other from under rule 22. At any rate, the general conclusion appears to be pretty well assured, that a word which shows a final *ñ* in *samhitā* shows it also in *jaṭā* before a following vowel of whatever kind. This is markedly different from its treatment in *pada*, where, by the initial specification of rule 20, its power of conversion to *ñ* is lost altogether: and even in *jaṭā* (as was shown in the note to iii.1), an altered letter usually exhibits its *samhitā* form only under the specific circumstances which condition that form in *samhitā*-text.

न रश्मीञ्ज्पयान्यमान्यतङ्गात्समानानचान्यज्ञीयान्॥२३॥

23. The *n* of *raçmin*, *çrapayān*, *yamān*, *pataṅgān*, *samānān*, *arcān*, *yajiyān* remains unchanged.

All these are words occurring in the passages respecting which the comprehensive prescription of rule 20 was made; needing, therefore, to be specifically exempted from its action. The commentator quotes the phrases in which they occur, as follows: *pu-ru-trā ca raçmin anu* (iv.1.2^a), *aditiḥ çrapayān iti* (iv.1.5^a), *su-ya-mān ātaye* (iv.7.15^{a,b}), *pataṅgān asandītaḥ* (i.2.14^a), *samānā samānān uçann agne* (iv.3.13^a; only G. M. have the first word), *arcān indra grāvānāḥ* (i.6.12^a; G. M. have dropped out all but *arcā*), and *yajiyān upasthe mātuh* (i.3.14^a; O. omits the last word). The first two are from *ukhya* passages, the third from a *prsthya*, the rest from *yājyā*—as is noted also by the commentator (but G. M. omit these notices, save the first). Under the second, he further suggests the objection that, as the word following *çrapayān* is *iti*, the case might seem not to fall under the rule (since this expressly says "except before *iti*"); but he urges in reply that the word *ārshe* in rule 21 (that is to say, of course, according to his

23. 1. *eteshu*¹ *grahāneshu nakārah svaraparo pi na kha-
lu repam yakāram² vā bhajate. yathā³: puru-....: adī-....:
ukhyatvād anayoh prāptiḥ⁴. nanv adī-....: asye⁵ tiparatvād
eva nishedhe sati grahanam anartham⁶: iti cet: ārshe itiparatvād
punah prāptiḥ: tan mā bhūd iti brāmaḥ. su-....: prsthya-
prāptiḥ⁷. pataṅ-....: yājyātēvāt⁸ prāptiḥ⁹. sama-....: ar-
cān-....: yaji-....: 11eshām api sāt¹⁰ ca prāptiḥ¹¹.*

(¹) G. M. *raçmin ity aditiḥ*; O. *esha* for *eteshu*. (²) G. M. *vā yakāram*. (³) B. *tathā*; the rest om. (⁴) G. M. *ptinishedhe*. (⁵) G. M. *atra*. (⁶) G. M. O. *thakam*. (⁷) O. om. *iti*. (⁸) G. M. om. (⁹) G. M. om. (¹⁰) O. *ins, asye*. (¹¹) G. M. om.

"crow's eye" interpretation) gives the former precept authority over it, which requires to be annulled.

उद्यापरश्चोद्यापरश्च ॥ २४ ॥

24. Nor a *n* followed by *ut* or *athā*.

The phrases to which this rule relates are, as quoted by the commentator, *amitrān un nayāmi* (iv.1.10²), and *vidvān athā bhava* (iii.2.11²⁻²; our *samhitā*-text has *atha*, because the word stands *vibhāge*, at the end of a division of the section: see rule iii.10 and note): I have noted no other cases. The commentator gives a counter-example to the former, showing why *ut* could not have been extended to *uta*, but needed to stop at the consonant (*hal*): it is *trīṇr uta dyān* (ii.1.11²). Such a counter-example is quite out of the usual course, and very superfluous: the example itself would be counter-example enough; the substitution of *uta* for *ut* would have excluded the very passage aimed at. Of the two phrases, the one comes from an *ukhya*-passage, the other from a *yājyā*: the commentator might better have spent his spare energy in telling us this.

What remains of the comment to this rule is not altogether free from difficulties. First the statement is made that the word *athā* in it implies also *atha*, with short *a*; in illustration, W. repeats, without change, *vidvān athā bhava*; B. gives the same twice over; only O. has, in *krama*-text, *vidvān atha: athā bhava*—which is doubtless correct, and shows the *krama*-reading (along, we may suppose, with the *jaṭā*) to be the matter aimed at. That the now accepted *samhitā*-reading—*vidvān atha: २: bhava*—is contemplated, is not at all to be assumed. Both the statement and its illustration are wanting in G. M.: and this, although those manuscripts contain, under viii.34, the reference to it in advance there made. In regard to what follows, also, the recensions are considerably at variance. The *jaṭā*-text is again under

24. *ut: athā: ity evamparo nakāro yathāvihitān 'rephaṁ yakāraṁ vā nā 'padyate. ' yathā: amit----- halmātreṇa' kim: trīṇr----- vidv----- 'dīrgho 'tra hrasvopalakṣaṇam api: yathā: vidv-----' 'yathāsamhitāstham' 'eva nimittān' svakāryaṁ karoti' 'nishedharāpam' 'yathā: amit----- vidhir apy' 'evaṁ yathāsamhitāsthanimitta evaṁ sarvatra bhavaty' 'ato' 'vocāma' 'so----- asm-----: evamādi veditāryam.*

*iti tribhāṣhyaratne prātiṣākyavivarane
navamo 'dhyāyah.*

(1) W. B. O. *atha*. (2) G. M. O. put after *opadyate*; G. M. *rephaṁ va yatoṁ vā*.
3 G. M. ins. *cakāro nishedhakarṣah*. 4 G. M. O. om. 5 G. M. O. *ut itī*. (6) G. M. om.; B. om. *yathā*; O. om. *api: yathā*. 7 G. M. ins. *ity atra*; O. ins. *atra*. 8 G. M. O. *-stha*. (9) G. M. *nimittān eva sambhavati*; O. *nimittān eva sarvatra bhavati*. 10 W. B. *-tte*. (11) G. M. om. 12 O. ins. *vidhirāpam vā*. 13 W. *itī*. (14) O. only *yathā*. 15 W. *atho*. 16 G. M. ins. *yathā*.

treatment; and it appears to be laid down that any word has in that text the same form as under analogous circumstances in *samhitā*, whether it fall under an exception or under a rule. Then, as example of an exceptional word, is given, as established by the present precept, *amitrān ud ud amitrān amitrān ut* (iv.1.10⁵), *amitrān* retaining its *n* throughout; and again, as examples falling under the more general rule, *so asmān asmānt sa so asmān: asmān avahāyā 'vahāyā 'smān asmān avahāyā* (v.7.9¹: under rule 21).

So far, now, as I have been able to discover, the teachings of the *Prāticākhya* in rules 20-24 of this chapter precisely correspond with the conditions of the known *Tāittiriya* text: I have not found in the latter a single case of final *ān*, *īr*, *ūr* which they do not duly notice, nor an exception to the more general rules which is not provided for. Of course, my observation is more to be trusted upon the former point than upon the latter.

The *sandhi* here treated of is comparatively unusual in our *Samhitā*, as it is in those of the other Vedas. According to my count, there are (including repetitions) 115 cases of *ān* (including also one at iv.8.6⁷, omitted above), 5 of *īr*, and 4 of *ūr*—in all, 124; while, of final *ān* remaining unchanged before a vowel, I have noted down over 450 instances (and probably not without overlooking a score or two), of *īn*, about 150, of *in*, 16, and of *in*, 4—in all, about 620, or not less than five times as many. The numerical relation in the *Atharva-Veda* is probably nearly the same. See the end of the note to *Ath. Pr.* ii.27.

CHAPTER X.

CONTENTS: 1-9, combination of final and initial similar vowels, and of final *a* or *d* with initial vowels and diphthongs; 10-12, resulting accentuation and nasalization; 13, special cases of uncombinable final *i*; 14, of elision of final *a*, *d* before initial *e* and *o*; 15-17, combination of final *i* and *a* vowels, and resulting accentuation; 18, special cases of uncombinable final *i*; 19-23, elision of final *y* and *e*; 24-25, uncombinable final vowels.

अथैकमुभे ॥ १ ॥

1. Now for the coalescence of two vowels into one.

An introductory heading to the whole chapter. The commentator paraphrases: "both syllables become one form, of the same kind."

1. *athe 'ty ayam adhikārah: ubhe akshare ekam rūpam sajātīyam' āpadyete' ity etad adhikṛtaṁ vedītavyam ita uttaram yad vakshyāmaḥ.*

¹ O. puts before *rūpam*. ² MSS. -yata.

दीर्घः समानान्तरे सवर्णपरि ॥ ३ ॥

2. In the case of a simple vowel, followed by a similar vowel, the product is long.

For the terms *samānākshara* and *savarna*, see rules i.2.3, where they are defined. The grammatical construction of the rule is not simple, or easily made homogeneous with that of its predecessor. The commentator brings it out thus: "there being a simple vowel, followed by one that is of like nature with itself, these two, being put in the relation of predecessor and successor, become a single long vowel." His examples are *tvācam grhṇishvā ntaritā rakshah* (i.1.8: only O. has the first word; only G. M. the last), *rāśānā 'si ndrānyāi* (i.1.2²), and *sūpasthā devo vanaspatih* (i.2.2³: only G. M. have the last word).

अथावर्णपूर्वे ॥ ३ ॥

3. Now for cases in which an *a*-vowel stands first.

A new sub-heading, having force as far as rule 9, inclusive. The word *avarṇapūrve* is explained by the commentator after the manner of a *karmadhāraya* compound, as meaning 'that which is both an *a*-vowel and first,' but I do not see how such a construction can be defended; we have, rather, to understand *akshara*, and make the meaning analogous with that of rule 2: "when there is a syllable that has an *a*-vowel before it."

इवर्णपरि एकारम् ॥ ४ ॥

4. When an *i*-vowel follows, the product is *e*.

The commentator explains *ivarnapare* in the same manner as *avarṇapūrve* in rule 3. The interpretations might hold good, if *pūrva* and *para* were taken substantively; but they are not so used anywhere in the treatise. His chosen example is *ne 'shtir bhava-*

2. *samānākshara ātmanah savarnapare sati pūrvāparibhāte 'ete ubhe' dirgham ekam' āpnutah. yathā: tvāc-----rās-----sūp----- savarnam param yasmāt tat' savarnaparam: tasmin'.*

¹ G. M. *pūrvah parah te*. ² W. O. ins. *eaty*. ³ G. M. ins. *akshara*. ⁴ W. om.; G. M. *adhikam*. ⁵ B. *āpnoti*. ⁶ G. M. O. om. ⁷ W. om.; O. *latrat*. ⁸ W. B. O. om.

3. *'athe 'ty ayam adhikārah: avarṇapūrve' sati 'ty' etad adhi-krtam veditanyam ita uttarām yad vakshyāmah. 'idam adhikā-rāntaram' upasargapūrva āram (x.9) iti paryantam. avarṇaś cā 'śū pūrvag cā 'varṇapūrvah: tasmin'.*

⁽¹⁾ O. om. ² O. *vate*. ³ W. om. *ity*. ⁽⁴⁾ G. M. *ayam adhikāra*. ⁵ O. adds *avar-*
napūrve.

ti (ii.5.5²: W. reads *neshtu*); and O. alone adds *mahendraya* (v.5.21; p. *mahā-indrāya*).

उवणपर ओकारम् ॥ ५ ॥

5. When an *u*-vowel follows, the product is *o*.
The commentator's single illustrative example is *isha* two 'rje
tvā (i.1.1).

एकारिकारपर एकारम् ॥ ६ ॥

6. When *e* or *ai* follows, the product is *ai*.
The examples are *sam brahmanā prcyasvāi kalāya wāhā*
(i.1.8: O. omits the last word), and *somāindrā bahhrulātāmāh*
(v.6.15; p. *soma-āindrāh*).

The commentator again very elaborately explains *ekārāikāra-*
pare as a *karmadhāraya* compound, formed upon *ekārāikāra* as a
dvandva; and remarks that the same explanation applies also in
the following rule.

ओकारैकारपर ओकारम् ॥ ७ ॥

7. When *o* or *au* follows, the product is *au*.
The examples are *brahmāudānam pacati* (not found in the Tāit-

4. *avarṇapūrva ivarṇapare ca sati te ubhe akshare'ekāram*
āpnutah. ne 'sh-....: mah. ivarṇaḥ cā'sau 'paraḥ ce 'varṇa-
paraḥ': tasmin

5. *avarṇapūrva uvarṇapare ca sati te' ubhe akshare'okāram*
āpnutah. ishē-....

¹ G. M. O. om. ² O. om.

6. *avarṇapūrva ekārāikārapare ca sati te ubhe akshare' pār-*
vāparibhāte' āikāram āpnutah. sam-.... som-.... ekāraḥ
cāi'kāraḥ cāi'kāraikārau: tayor' samāhāra ekārāikāram: 'sam-
āhāre dvandvaḥ: 'tao ca tatparam cāi'kāraikāraparam karm-
dhārayah: tasminn ekārāikārapare. evam uparitan pi sūtre
samāsaḥ.

¹ G. M. om. ² O. om. ³ G. M. *pārāpare* and 'put before *akshare*. ⁴ G. M.
om. ⁵ O. om. ⁶ O. *tanasūtre* 'pi.

7. *avarṇapūrva okārāikārapare ca sati te ubhe akshare' āikā-*
ram āpnutah. brah-.... dām-....

¹ G. M. O. om. ² G. M. O. om. ³ G. M. add *uktas samāsaḥ*.

tīrīya Sanhitā, although it is read at Tāittīrīya Brāhmaṇa i.1.9³: we have *brahmāudanam pacet* at v.7.3¹, and *brahmāudanam apacat* at vi.5.6¹: O. omits *pacati*, leaving the citation such as might have come from either passage), and *dāmnā 'pāu 'mbhan* (ii.4.13).

अरम्कारपरे ॥ ८ ॥

8. When *r* follows, the product is *ar*.

The examples are *ardharca ekām* (i.6.10⁵), and *āgneyya red 'gnīdhram* (iii.1.6¹; p. *āgneyyā: red*).

I have not noticed a single example in the Tāittīrīya Sanhitā of that retention of *r* unchanged after *a* and *ā*, only with correption of the latter, which is the rule in the Rik and Vājasaneyi Sanhitās, and which appears also in the Atharva-Veda, though against the authority of its Prātiçākhyā (see Ath. Pr. iii.46 note).

उपसर्गपूर्व आरम् ॥ ९ ॥

9. If a preposition precedes, the product is *ār*.

The commentator points out that, as the implication "when an *a*-vowel stands first" is still in force from rule 3, this virtually means "if a preposition ending in *a* or *ā* precedes;" *r*, of course, is inferred from the preceding rule. According to the list of prepositions given at i.15, then, *ā*, *pra*, *ava*, and *upa* would be the only words authorized to form with initial *r* the *vrddhi* vowel instead of the *guṇa*, *parā* and *apa* being excluded. The commentator brings up but one example from the text, namely *upā rchatī* (i.5.9⁶: G. M. read *upā rchaty askandāya*, which I do not find anywhere: we have *askandāya* after other words at i.5.8⁵: ii.5.8⁶: vi.3.8^{1,3}, the last time following *upā 'syati*; possibly this text was in the mind of the scribe who added *askandāya* in the comment on the present rule); he gives another from the *jatā*-text, *rtavyā upo 'pā rtavyā rtavyā upa* (v.3.1¹; 4.2¹), and, further, as counter-example, showing that only a preposition ending in *a* or *ā* produces the prescribed effect, *vyrddham vā etat* (v.1.2¹ et al.: O. omits the last word). Additional cases of the same combination, with *ā* and *ava*, are quoted under rule 10 (at the end); if the text affords yet others, I have failed to note them. Nor have I observed any cases of the different treatment of *parā* and *apa* before *r*; so that here also I do not discover any reason for the strange restriction of the class of prepositions made at i.15.

8. *avarṇapārva ṛkārapare ca sati te' ubhe akshare' aram iti vikāram āpnutaḥ. ardh-----: āgn-----*

¹ O. om. ² G. M. O. om.

9. *avarṇapārva ity anuvartate': tasmād upasargapārva ity aviṣeṣhavarṇāntoktāv' avarṇānto 'yam' upasargas tasyāi 'va grahanam: ṛkārah sāmniidhyāi labhyate. upasargapārva ṛkārapare*

उदात्तमुदात्तवति ॥ १० ॥

10. When an acute enters into the combination, the result is acute.

That is to say, as the commentator points out, when the first constituent, or the second constituent, or both constituents, have the *udatta* accent, their combination is *udatta*. He gives a long list of examples in illustration of the working of the rule, promising that they shall exhibit the whole series of vowel-combinations just prescribed, from the second rule to the ninth, with all possible conditions of accentual combination. Thus, *savitā prā rpayatu* (i.1.1; p. *prā*: *arp*: W. reads *-yati*) *brāhma yachā pā gne* (i.1.7¹; p. *yacha*; *āpa*), *yājyāi ed nam* (ii.3.5²; p. *yājyā*: *ā*: *evā*: *enam*: the pada-manuscripts have *ē ti* for *ā*; and so with the other prepositions), *pāshā dhatta* (i.5.1²; p. *pāshā*: *ā*: *adhatta*: W. B. read *-tte*), *divi ca cākshuh* (i.3.8² and ii.2.9⁴; p. *divi*; *iva*: for this accent, which is opposed to the teachings of all the other *Pratīcākhyas*, see under rule 17 of the present chapter), *adyā vāsu vasati ti ndro hi devānām* (ii.5.3⁷; p. *vasati*: *iti*: *indrah*: O. reads at the end *ndram eva*, which I do not find anywhere in the *Sanhitā*), *māitravarun ty āha* (ii.6.7⁴; p. *-n*: *iti*). The question is then raised, whether the word *sānnīyam* (vi.2.4¹) does not fall under this rule, since it exhibits a coalescence into one syllable of two vowels, whereof one is acute; but the reply is made, that a special rule in a later part of the chapter (r. 17) prescribes for it the circumflex. The examples are continued: *rēto dadhātā t saktthyōh* (vii.4.19¹; p. *dadhātu*: *āt*), *vānaspātayō nā t tishthanti tān* (vii.4.8³; p. *ānu*: *ūt*: only G. M. have *tān*), and *tā dikshā pā dadhata* (v.5.5⁴; p. *dikshā*: *āpa*: G. M. omit *tā*). So many are examples of the combination of two similar simple vowels into a long vowel: the rest illustrate the cases of coalescence in which *a* or *ā* precedes. They are *sē mā m no havyādā-*

ca sati te ubhe akshare āram iti vikāram āpnutah. upā-----: r̥t----- avarnāntopasargaviṣeṣaṇena kim: vy̐r----- upasar-
gaḥ cā sū pūrvag co pasargapūrvah: tasminn upasargapūrvē.

¹ G. M. O. om. *anu*. ² W. *viṣeṣāvar*; B. *viṣeṣhoktā yathā*; G. M. *aviṣeṣhoktā* *pī*. ³ O. *aviṣeṣhoktā* *apī*. ⁴ O. om. *ayam*. ⁵ G. M. om. ⁶ B. G. M. O. om. ⁷ G. M. O. *upas*; G. M. B. *-sheṇa*. ⁸ B. om. ⁹ G. M. om.

10. *udāttadharmaviṣiṣṭe varṇe pūrvataḥ parata ubhayato vā sthite sati te ubhe apy ekādeṣam āpanne udāttadharmakam āpnutah. udātto syā stī ty udāttavān: tasminn udāttavati. samānāksharam ārabhya sarvasmād ekibhāve yathākramam udāt-tānudāttasvaritapūrva ubhayor udātte vo dāharaṇāni darṣayishyāmaḥ. sav-----: brah-----: yāj-----: pāsh-----: div-----: adya-----: māt-----: namu sānnīyam ity atro dātte-nāi kadeṣe sati kim na syād ayam vidhiḥ: udāttapūrvādhikāre*

tām (iv.6.6²; p. *sāh*: *tām* 'mā compare rule v.17), *tām glhē d agnir* *ordhā* (ii.6.11²; p. *gha*: *it*: only G. M. have the last word), *savanamukhēsavanamukhe kāryā* 'tē (vii.5.5²; p. *kāryā*: *it*: B. omits the first *savanamukhe*), *sē d u hōta* (i.1.14²; p. *sāh*: *it*: compare rule v.17; W. B. omit the last word); so many are examples under rule 4. Now follow those under rule 5: *prākṣhitam gopāyati* (vii.1.12; p. *prākṣhitam*: G. M. omit this example), *arjā sthō* 'rjanv eva bhakshyā' (i.5.6²; p. *stha*: *arjam*: O. omits the last word), *svayāśhō d bhakṣhānam* (i.2.8²; p. *svayāśhā*: *it*: G. M. omit this example also), and *imā eva pṛ dhatte* (v.2.7²; 5.3²; p. *evā*: *api*). The examples under rule 6 are *nā i nam pratyāśhanti* (i.5.9²; p. *nā*: *enam*), *eka eva yajetā i kuh* (vii.2.10²; p. *yajeta*: *ekah*), *dīthā i kam rathā nam* (vii.2.1²; p. *dīthā*: *ekam*), *yān nā i kār rācānd m* (vi.6.4²; p. *nā*: *ekam*), *indriyām evā i indrēna* (vi.6.5²; p. *evā*: *āindrēna*), *vi hē tād avā iryatē 'ti* (vii.1.5²; p. *ava*: *ā iryata*), and finally, from the *jatā*-text, *devēbhya d indhā i ndha devēbhya devēbhya d indha* (ii.5.9¹; but G. M. give only the *samhitā*-reading, *devēbhya d indhā*). To illustrate rule 7, we have *kshatrāsya cāu jāse juhomi* (iii.3.1²; p. *cā*: *ōjase*: B. O. omit the last word), *svā hā u shadadhīyah* (ii.8.13²; p. *svā hā*: *ōsh-*), *sā u shadhīr ānu rudhyase* (iv.2.3², 11²; p. *sāh*: *ōshadadhī*: another case under rule v.17; G. M. omit the last word), *prā u kshih kēnā pā it* (ii.6.5¹; p. *prā*: *āukshih*: G. M. omit the last word), and *aravā ha smā hā u pavacih* (vi.1.9²; p. *aha*: *ā upavacih*). Under rule 8, again, fall *āgnevyā red gndhram* (iii.1.6¹; p. *āgnevyā*: *red*), *sā vā syā rddhīh* (vi.6.10²; p. *asya*: *rā ddhīh*), *d indhā rshishtutah* (ii.5.9¹; p. *d indhā*: *rshishtutah*), and *evā rshir asvadayat* (v.1.10¹; p. *evā*: *rshih*). Under rule 9, finally, we have *d rtim d rchati* (i.5.2⁵ et al.; p. *d*: *rchati*), and *avā rchaty enām āvāram* (ii.6.3²; p. *ava*: *rchati*).

अनुनासिके अनुनासिकेम् ॥ ११ ॥

II. When a nasal, the result is nasal.

The commentator quotes rule xv.6, which declares it to be the *saty ābhāve ga* (x.17) *itī sūtreṇa sacritasya vigeshavidhānāt itī brāmaṇa rōta* *evam samānākshara saṁhitāyām ekibhāvō nyatra pi drashtavyah*, *evam avarna pārvate pi vakshyate*: *se*.....: *tām*.....: *sav*.....: *sē d*.....: *pro*.....: *arja*.....: *svā*.....: *ime*.....: *nā*.....: *eka*.....: *athā*.....: *yan*.....: *indr*.....: *deve*.....: *ksha*.....: *svā*.....: *sāu*.....: *prāu*.....: *arav*.....: *agn*.....: *sā*.....: *d indha*.....: *eva*.....: *art*.....: *avā*.....: *evamādī*.

¹ W. prop. ² B. G. M. *nam*. ³ O. *amim*. ⁴ G. M. *upāsargantam*. ⁵ (9) G. M. *udattāntadattavaritānām pārvate ca parate ca udattāgor udattāto ca yathakramam*. ⁶ O. *prā*. ⁷ G. M. *nāhā eva soti*. ⁸ G. M. *vidhinā*. ⁹ W. B. *ve*. ¹⁰ G. M. *vā*. ¹¹ W. *nyā*. ¹² G. M. *car*. ¹³ G. M. *hā*. ¹⁴ G. M. *dagah*.

opinion of some authorities that final simple vowels, not *pragrahas*, are nasal; and he states that the present precept has reference to them: if such a nasal vowel, being acute, enters into a combination of the kind above described, the resulting single syllable is nasal. Examples, he says, are those already given. And he adds that the rule is not approved.

I cannot at all believe this to be the true interpretation. The rule seems, on the other hand, to belong to and represent the same view of the nature of a syllable ordinarily regarded as containing *anuvāra*, which appears so unequivocally at xv.1; and to mean that when such a syllable, being looked upon as one containing a nasal vowel, instead of a vowel with succeeding *anuvāra*, enters into combination with another vowel (of course, a preceding one), the result is also nasal. Thus, for example, *yah* with *anūm* would make *yo 'nūm*; *svāhā* and *anśābhyām* (vii.3.16¹⁻²); *svāhā 'śābhyām*.

स्वरितानुदात्तसंनिपाते स्वरितम् ॥ १२ ॥

12. When circumflex and grave are combined, the result is circumflex.

The examples of this accentual result of combination, as given by the commentator, are as follows: *kanyē 'va tunnd'* (iii.1.11²; p. *kanyā*: *iva*), *chavīm chavyō 'pākrīyā svāhā* (v.7.20²; p. *chāvīyā*: *upā-d'krīyā*: G. M. O. omit *svāhā*), *yājyāi 'shā vāi sap-tāpādā śākrī* (ii.6.2⁵; p. *yājyā*: *eshā*: G. M. O. end with *'shā*), and *ātha kvā 'syā havanī' yā āi* (v.7.4²; p. *kvā*: *asyā*: O. omits the last two words). He then goes on to point out that the word *svarita*, "circumflex," being used in the rule without any distinctive sign, we are to understand the "constant" (*nitya*) or "independent" circumflex (see rule xx.2) to be intended. For this alone arises at the time of production of letters and syllables, elements of words; but the other kinds of circumflex arise after the time of origin of words, in connection with the euphonic combination of

11. *apragrahāḥ samānākṣharāṇy anunāsikāṇy eke-śhām* (xv.8) *ity ekeśhām matam: tān uddiśyā 'yam vīdhiḥ. tas-minn' udāttavaty amunāsike pūrvataḥ parata ubhayato vā śhīte saty' ubhe' akṣhare amunāsikadharmam ekam āpnutah. ūktāṇy eva 'dāharāṇāni.*

'etad anishtam.

¹ O. om. ² B. G. M. O. om. ³ G. M. O. *goshāni*: B. *ekāni*. ⁴ W. *tasmād*. ⁵ G. M. O. ins. te. ⁶ B. O. ins. *opy*. ⁷ G. M. om.: O. ne 'dām, *sūtram ishtam*.

12. *svaritānudanāyoh samnīpāta ekādeṣe saty ubhāv api tāu svaritam āpadyete. yathā: kan.....: chav.....: yāj.....: atha..... iha svaritasyā' 'vīśeshena' grahane nityasvarita eva' grhyate: tasya svaritasya' vyanjanānām akṣharāṇām ca' padd-*

syllables and words, by the requirement of such rules as xiv.29 and xii.9; and therefore primary quality belongs only to the "constant" circumflex: whence, by the rule "when a general statement is made, that which is primary should be regarded as intended," it is proper that the constant circumflex should be here understood. In such cases, then, as *āthā 'bravīt* (iii.2.11²), where the long *ā* resulting from the combination of the final *a* of *ātha*, which has the enclitic circumflex (by xiv.29), with the initial *a* of *abravīt*, which is grave, has itself the enclitic circumflex, this is not in virtue of the present rule, but falls under the same general rule (xiv.29) that prescribes the enclitic circumflex.

To this effect the commentator: and, whatever we may think of the argument by which he attempts to prove that *svarita* in the rule means only *nitya svarita*, we shall not question the soundness of his conclusions.

न धामापासिपरोबुध्नियाज्यापूपामिनन्तार्ये ॥ १३ ॥

13. Exceptions are *dhā*, *mā*, and *pā*, when followed by *asi*; also *budhniyā*, *jyā*, *ā pūshā*, and *aminantā*—before a vowel belonging to the text.

That is to say, these words constitute exceptions, not to the last rules respecting accentuation, but to those which prescribe the combination of a final *a* or *ā* with the following initial vowel. The commentator cites the passages in which the first three occur before *asi*, as follows: *svadhā asy uroī* (i.1.9³), *sahasrasya pramā asi* (iv.4.11²: O. omits the first word), and *dhānvann iea prapā asi* (ii.5.12⁴: O. omits the first two words). I have also noted, for *dhā*, *varcodhā asi* (i.2.1¹), *dhā asi svadhā asi* (ii.6.4⁴), and *abhidhā asi* (vii.1.11¹); for *mā*, *pratimā asi*, *vimā asi*, and *unmā asi*, all in the same section and division (iv.4.11²) with *pramā*, as quoted; and, for *pā*, *vratapā asi* (i.1.14⁴; 2.3¹; vi.1.4⁶) and *akshushpā asi* (i.2.1²). To explain the added specification "when followed by *asi*," the *pada*-readings are quoted for us, namely *svadhe*

vayavānām utpattikāla eva sambhavāt: anyeshām tu padotpat-
tikālād* ārdhcam aksharānām padānām ca** samhitāyām udāt-
tāt paro 'nudāttah* (xiv.29) *iti vidhānāt tasminn anudāt-
te pārva 'udāttah svaritam* (xii.9) *ity ādi** ca: tasmān
nityasyādi'va mukhyatvam: sāmānyoktāu ca** satyām mukhye
sampratyaaya iti tasyādi'va svikāro yuktah: athā.... ity ādāv
ekādēcasyo 'dātānantarabhāvitvād' udāttāt paro 'nudāttah
svaritam* (xiv. 29) *ity anenāi'va svaritatvam vijñeyam.*

* G. M. *ekam āpūtah*. * G. M. om. * W. O. *-sya*. * B. *-shana*; G. M. *-shanam eva*. * O. om. * B. *-ta*; G. M. *sa*; O. *sarva*. * W. om. * G. M. *ca*. * G. M. *paro*; O. *aparo*. ** W. om.; G. M. O. *vā*. (***) G. M. *udāttam*. ** O. om. ** W. om. ** G. M. O. *-ndant*.

'*ti* *sva-dhā* (only W. has *sva-dhā* in the repetition), *prame* '*ti* *pra-mā*, *prape* '*ti* *pra-pā* (O. omits the readings of *pramā* and *prapā*). Further, to explain the final specification *ārshe*, 'before a vowel belonging to the text,' W. gives next the *jatā* readings of *svadhā asi* and *prapā asi*, namely *svadhā asy asi svadhā svadhā asi*, and *prapā asy asi prapā prapā asi*; O. has only the former, and substitutes for the latter *dhruvā 'si dharunā* (iv.2.9¹; 3.7²), which would be in place as a counter-example showing that other words than those specified in the rule are not treated as it prescribes before *asi*, but is not introduced as such, and does not make its appearance at all in the other versions; B. also has only the former (reading at the end *svadhā 'si*), and adds *evam ādi*, 'and so on.' G. M. give no *jatā*-readings at all here, but pass directly from the *pada*-readings to the quotations illustrating the remaining words of the rule, namely: *pra budhniyā irate* (iv.3.13³; G. M. omit *pra*); *dhanvañ jyā iyam* (iv.6.6¹⁻²; only G. M. have the first word); *ā pūshā etv ā vasu* (ii.4.5¹), with a counter-example, *tam pūshā 'dhatta* (i.5.1²), to show that *pūshā* after any other word than *ā* is not uncombinable; and *ā te suparnā aminanta evāih* (iii.1.11³; G. M. omit the first two words, O. the first three). Now the question is asked again, "why is it said, 'when a vowel from the text follows?'" and W. B. O., having settled the point already so far as *dhā*, *mā*, and *pā* were concerned, reply by quoting the *jatā*-readings of the other four words, each with its successor, thus: *budhniyā irata irate budhniyā budhniyā irate* (but B. reads *budhniye* "rate, and O. *budhnye* "rate, the last time), *jyā iyam iyam jyā jyā iyam* (B. O. again have *jye* "yam at the end), *pūshā etv etu pūshā pūshā etu* (B. O. again *pūshāi* "tu in the third repetition), and *aminanta evāir evāir aminantā 'minanta evāih* (B. O. once more *aminantāi* "evāih to close with). G. M., however, who have the application of *ārshe* in the first part of the rule still to illustrate, give us here a most liberal series of extracts from the *jatā*-text: first, for *asi svadhā* (i.1.9³ or ii.8.4⁴), namely *asi svadhā svadhā asy asi svadhā*; then for *svadhā asi*, as set down above (with *svadhā 'si* at the end, like B.; but it seems a merely accidental coincidence, for in all the other cases the third pair of words reads like the first, with the hiatus); for *iva prapā*, *iva prapā prapā 've 'va prapā*; for *prapā asi*, as above reported from W.; for *pra budhniyā*; for *budhniyā irate*, as in W.; for *dhanvañ jyā*; for *jyā iyam*, as in W.; for *ā pūshā*, *ā pūshā pūshā* " " *pūshā*; for *pūshā etu*, as in W.; for *suparnā aminanta*, *suparnā aminantā 'minanta suparnā aminanta*; and for *aminanta evāih*, as in W. From all this illustration, we seem authorized to draw the inference that the words mentioned in the rule as having

13. *dhā*: *mā*: *pā*: 'eteshv³ antyasvara ārshe³ pāthe³ 'siparah:
budhniyā: *jyā*: *ā pūshā*: *aminanta*: eteshv³ antyasvara ārshe³
svaraparah pārvavidhim na prāpnoti. yathā: *sva*-----: *sah*-
 -----: *dhan*-----: *asipara iti kim*: *sva*-----: 'pra-----: pra-

endings exceptionally uncombinable in *samhitā*, nevertheless combine with *iti* in *pada*-text, and also exhibit their uncombinable quality in *jaṭā* only, before the words whose sequence calls out that quality in *samhitā*—*pāśhā*, for example, uniting with its predecessor *ā* into *pāśhā*, and *aminanta* with itself into *apinanta* 'minanta' (only, if we may trust the example given, *śaṣṭhā* being held apart from its predecessor *asi*, because this happens to be the same word with its successor; and it is by no means impossible that the manuscripts are in the wrong upon this point). But this would be quite sufficiently intimated by the single restriction *ārāhe*, without adding *asi* also; and that the latter is specifically intended to apply to the *pada*-readings, and the former to the *jaṭā*, is not easily to be believed. The *asi* would have best reason to be introduced because the words mentioned occur also before other vowels, with which they enter into combination—only, to be sure, I have not noted any cases in which they do so.

एष्टरेतेनेमत्रोद्गन्तोऽपरा लुप्यते ॥ १३ ॥

14. When followed by *eshtah*, *etana*, *eman*, *odman*, *oshtha*, or *evah*, an *a*-vowel is elided.

That the elision mentioned in the rule is of an *a*-vowel is a consequence of the continued implication of the introductory rule x.3, above—although, as the commentator fails to point out, that implication was interrupted by rules 10-12, and was expressly stated at the outset to remain in force through rule 9. The passages contemplated are quoted by the commentator, as follows: *aciy' eshtā rāyāh* (i.2.11¹), *camitāra upetana* (iii.1.4², 5²), *apām te' eman' sādāyāmi* (iv.3.1), *apām te' odmant' sādāyāmi* (iv.3.1: G. M. O. omits *sādāyāmi* in both these citations), *śaḥ' oshthābhyām* (vii.3.16¹), *upayānam adharen' oshthēna* (v.7.12: O. omits the first word), and *nir aminat' evaḥ chandah* (v.3.5⁴: O. omits the last word). These are, so far as I have discovered, all the cases of application of the rule that the text contains. The commentator notes that rule i.22, which allows a theme ending in *a*, quoted in a rule, to stand for its various derivative forms, is the warrant for regarding *oshthābhyām* and *oshthēna* as involved in *oshtha*. The

-----¹ *ārsha iti kim: sva*-----² *pra*-----³ *dhan*-----⁴ *ā pā*
-----⁵ *ākārah kimarthaḥ: tam*-----⁶ *ā te*-----⁷ *ārshasvarapa*
*ra*⁸ *iti kim: budh*-----⁹ *jyā*-----¹⁰ *pā*-----¹¹ *am*-----

¹ O. ins. *ity*. ² B. G. M. *eshv*. ³ B. G. M. *sha*. ⁴ B. *pāthakāle*. ⁵ B. G. M. O. *eshv*. ⁶ G. M. *śhapathā*. ⁷ B. G. M. O. om. ⁸ O. om. ⁹ G. M. om. ¹⁰ B. *evam, idi*; O. *dhru*-----¹¹ G. M. om. ⁽¹⁾ G. M. *ākāreṇa kim*. ⁽²⁾ O. om. *para*.
(12) See the note, above.

14. *ity avamparo 'varno' lupyate: athā 'varnapārve*
(x.3) *ity anuvartandā' avarna' iti labhyate. aḥi*-----¹ *gami*-----
apām-----² *apām*-----³ *śvāh*-----⁴ *oshthāḥabdasya sarvāvasta*

same two cases were given by him in illustration of the previous rule (see note to i.22). As general counter-examples, to prove the implication of "an *a*-vowel," we have *ṣṭyoshthah*, *ṣṭibhrūḥ* (v.6.14), and *ṣṭyoshthāya svāhā* (vii.3.17).

उवर्णोकारौ यवकारौ ॥ १५ ॥

15. An *i*-vowel and *u* become respectively *y* and *v*.

Here, the commentator tells us, the implication "preceded by an *a*-vowel" ceases, but the implication "followed by a vowel" has force—which implication comes all the way from rule 10 of the preceding chapter. The rule says *ukāra*, "short *u*," instead of *uvarṇa*, "an *u*-vowel," because long *ū* has already (by iv.5) been declared *pragraha*, and protracted *ū* is made uncombinable below (by x.24). The examples are *abhy aśhāt* (iv.2.8¹), *āty apyāma* (i.3.14²), and *ā pāshā etv ā vasu* (ii.4.5¹).

उदात्तयोश्च परा ञ्मुदात्तः स्वरितम् ॥ १६ ॥

16. And, when they are acute, a following grave becomes circumflex.

The word "and" (*ca*), we are told, brings down from the preceding rule the "*i*-vowel and *u*," there described as suffering a certain effect. The examples given of the production of this kind of circumflex accent, later (xx.1) described as the *kṣāḍipra*, are *vy evā'i nēnā pāri dhatte* (v.3.11³: only G. M. have the last two words), and *apav āgne* (iv.2.11³). As counter-examples, we have first *nīcā tām dhakshy atasām* (i.2.14²) and *mādhv agnā u jhōti* (ii.3.2⁴), to show that unless the converted vowels are acute, no circumflex appears; and then, to prove that the following vowel must also be grave, *tād yād rey ādhy akshārāni* (ii.4.11⁵: G. M. omit the first word), *sā tv 'ā i yajeta* (ii.6.6⁵ et al.: G. M. omit this whole example), and *in nō 'ā āpastirnam ichānti* (i.6.7³):

śya grahaṇam bhavati grahaṇasya ca (i.22) *iti vacanāt: upay-*
----- *nir*----- *'avarṇo lupyata' iti kim: ṣṭy*----- *ṣṭy*-----

¹ G. M. -*ṇapūro*. ² W. -*tamaninād*; G. M. -*tamanah*. ³ G. M. -*avarṇapūro*.
⁴ B. -*ṇapūro* I.; O. -*ṇalopā*; G. M. -*ṇapūro*.

15. *avarṇapūrvādhikāro nirvrttaḥ: svaraparādhikāras tu var-*
tate: atha svaraparo yakāram (ix.10) *iti pūrvādhikyē pra-*
krāntah. īvarṇokārāu padāntāu svaraparāu yathāsāmkhyenā
yavakārāv āpadyete. abhy----- *āty*----- *ā pā*----- *dirgha-*
śya pragrahavidhānt pūtasya sāmāhinishedhād ukārasya kārō-
taratvaṃ kṛtam: icarṇokārāu yavakārāv iti.

¹ W. puts after the next word. ² G. M. -*khyam*. ³ G. M. -*ekar*.

compare, for the peculiar *sandhi* in these last two examples, rule v.13.

उभावे च ॥ १७ ॥

17. Also when *ū* is the product of the combination.

The "also" (*ca*) of this rule is interpreted as implying that, as in the case of the combination last considered, the first element going to form the *ū* must be acute, and the second grave. As examples of the combination and its accentual result are given *sūn-nyam iva* (vi.2.4¹; p. *sū-nnyam*), *sūdgātā* (vii.1.8¹; p. *sū-ud-gātā*), and *māsū 'tīshthan* (vii.5.2²; p. *māsū: ut-*); to which G. M. add *dikshā 'padādhāti* (v.5.5⁴; p. *dikshā: upa-dā-*). The only other case of the kind which I have noted in the Sanhitā is *sūpa-sadanah* (vii.5.20; p. *sū-upasadanah*). The commentator adds a couple of counter-examples: the first, *sūpasthā' devāh* (i.2.2³; p. *sū-upasthā'h*), shows that the former *u* must be acute; the other, *tā' dikshā 'pā' dādhatā* (v.5.5⁴), that the latter *u* must be grave.

A later rule (xx.5) gives this particular variety of the circumflex accent the name *praglishta*.

None of the other Vedic texts has an accentual usage corresponding with this. Indeed, there is not in the Atharvan a single case of a combination of two *u*'s such as is here contemplated, nor has any from the other Vedas come to my notice; if such there be, they are left to follow the general analogy of combinations of acute and grave into one homogeneous vowel (as illustrated under rule 10, above), the acute element raising the other to its own pitch and making the result acute. On the other hand, an exception to this general analogy is made in the other Sanhitās (and duly explained in their Prātiśākhya: see Rik Pr. iii.7, Vāj. Pr. iv.132, Ath. Pr. iii.56) in favor of the coalescence of two short *ē*'s into a long *ē*; if the former be acute and the latter grave, they produce together a circumflex. Of such a combination, I have

16. *caḥārah pūrcasātroktaṇimittindv' 'ivarnokārāv anvādicati: udāttayor' ivarnokārayohi paro 'nudāttag ca' svaritam āpadyate. vy-----: apsv----- udāttayor iti kim: nīcā-----: madhv-----: paro 'nudātta iti kim: tā d-----: sa-----: in-----*

¹ G. M. *ūno* 'pi. ² G. M. *om*. ³ O. *om*.

17. *caḥārah pūrvodāttatvānvākarshakāh: 'parasyā 'nudāttatvam anvādicati ca'. pūrvēno 'dātena parasyā 'nudāttasyo 'bhāve kriyamāno' svaritam jāniyāt. yathā: sūn-----: sūd-----: mā-----: 'dik-----: pūrvēno 'dātena kim: sūp-----: parasyā 'nudāttasye 'ti kim: tā-----*

¹ B. O. *pūrvasyo 'd-*; O. *tvānuk-*; G. M. *pūrvodāttatvā paratodnudāttatvā ed 'kar-shati*. ² G. M. *om*; O. *om. ca*. ³ G. M. *om*. ⁴ W. B. O. *om*.

noted about thirty cases in the *Tāittiriya* text (examples, one in each book, are i.3.6²: ii.1.3¹: iii.5.5²: iv.1.6²: v.1.7²: vi.1.1⁶: vii.5.7⁴); the accentuation is throughout acute, as we should expect.

न श्येती मिथुनी ॥ १८ ॥

18. Exceptions are *cyeti* and *mithuni*.

That is to say, these words are exceptions to rule 15—and, being thus exempt from the conversion there prescribed, and there being no other rule requiring their alteration, they remain unchanged, as if they were *pragrahas*. The examples are *gyāitena cyeti akuruta* (v.5.8¹: O. omits the first word; *cyeti* occurs also in the next division of the same section, though not before a vowel), and *na mithuni abhavan* (v.3.6²: B. omits *na*). The latter word is found in two other places—at iii.4.9¹ and vi.5.8⁶—exhibiting the same uncombinable quality; and in the latter place it has been made (at iv.53) the subject of special exception as not a *pragraha*. The *pada*-text, in fact, writes both words as if no peculiar character belonged to them.

लुप्येते त्वर्णपूर्वा यवकारौ ॥ १९ ॥

19. But *y* and *v* are elided, when preceded by an *a*-vowel.

The word “but” (*tu*) in this rule, the commentator says, annuls the application of the rule to any other *y* and *v* than such as are the products of prescribed euphonic processes, and makes these alone the subjects of its action. As a *y* or *v* can never occur as final except by euphonic conversion, the particle has no very useful office to fill, according to the interpretation. Evidently enough, it is used here, as elsewhere in the treatise where a specific force is sought for it by the comment, simply as indicative of a sudden change of subject.

Vastly the largest class of cases falling under the rule is that in which, by ix.10, a *visarjaniya* has been converted into *y* after *a*, *ā*, *āḥ* before another vowel than *a*. In illustration of this class, the commentator quotes *āpa undantu* (i.2.1¹), *dhruvā asmin gopatāu* (i.1.1: G. M. O. omit the last word), and *na vicinityāz iti* (vi.1.9¹). The next class consists of cases of final *e* and *āi*, converted into *ay* and *āy* by ix.11,14: the examples are *ima evā 'smāi* (ii.4.10²), and *āsāmahā eve 'māu* (vii.5.2¹). Yet another class embraces the endings in *ān* of which the *n* was turned to *y* (with nasalization of the *ā*, or with *anusvāra* added, by xv.1–3) according to the rules at the end of the last chapter (ix.20–24): the selected example is *martyāñ āviveṣa* (v.7.9¹). But the rule teaches also the

18. *cyeti: mithuni: ity etayor antyasvaro yathāvihitam' yatoam nā 'padyate. yathā: gyāi-----: na-----*

¹ O. om. ² W. G. M. O. om.

elision of final *v*; and O. boldly gives examples for this, as well: namely, *vāyav ishtaye* (ii.2.12³; W. adds *durone*), and *ahāv aha-duta* (v.8.12), although the text, by a usage which the comment ratifies under the next rule but one (x.21), retains the *v* in such cases, and it is retained by O. in these very phrases given to illustrate its omission. W. has only the former of the two, foolishly prefixing to it (*avarnapārva iti kim*, 'why is it said, "when an *a*-vowel precedes"?' The other manuscripts pass the point without notice here, leaving it to be settled under rule 21. The true counter-examples for this precept, showing that the elision takes place only after an *a*-vowel, are given by all alike: they are *abhy asthāt* (iv.2.8¹), and *hrtvasah* (iv.2.11²).

नोव्यस्य ॥ २० ॥

According to Ukhyā.

20. Not so, according to Ukhyā.

Ukhyā denies that *y* and *v* are omitted in any case; and would therefore read *āpay undantu, imay eva, martyāny ā*, and so on.

वकारस्तु साकृत्यस्य ॥ २१ ॥

21. Not *v*, according to Sāṃkṛtya.

The connection of this rule is somewhat anomalous, but its meaning is sufficiently evident. Sāṃkṛtya dissents from the principle laid down in rule 19, like Ukhyā; "but" (*tu*) his dissent does not go the whole length of the latter's; according to him, only *v* is "not" elided. As the commentator has it, the fact that this rule teaches an exception is inferred, "by vicinage," from its predecessor: its *tu* is intended as an annulment of the opinion of former teachers. And he declares that it alone is approved, while the two that precede (the former of them, of course, only so far as it is inconsistent with this) and the two that follow (B. O. omit this) are rejected. The examples are those already given by a part of the MSS. under rule 19, namely *vāyav ishtaye durone* (ii.2.12³:

19. *avarnapārvaṁ sparaparāṁ yakāravakārāṁ lupyete, ya-thā: āpa-----: dhru-----: na-----: ima-----: āśā-----: vāy-----: ahāv-----: mart-----: evampārvaṁ iti kim: abhy-----: hrt-----: tuṣabda itarāṁ yavakārāṁ nivartayann ādeṣa-prāptayor evā nāyor lopaviśhayatvaṁ dyotayati. avarnah pārvo yābhyāṁ tāv avarnapārvaṁ.*

G. M. *yaśāḥ*. ¹ W. ins. *avarnapārva iti kim*. ² Only in O. ³ G. M. *avar-nap*.

20. *ukhyāya¹ śākhinā² pakṣe³ varnapārvaṁ⁴ yavakārāṁ nā lupyete. uktāny evo dāharāṇi.*

¹ G. M. ins. *mate*. ² G. M. *mate*. ³ O. *pārva*. ⁴ B. om. G. M. have mixed together to some extent this and the following comment.

W. B. omit this example; O. puts it after the other one, and leaves off *durone*), and *ahāv anādātā* (hate (v. B. 12: O. omits *hate*).

This is rather the most striking example afforded us of the overriding by the commentary of the obvious intent of the *Prātiśākhya* itself. The usage of the existing *Tāittiriya* text is on the side of the comment: we have a similar resolution of the final *a* of vocatives into *an*, with retention of the *v*, nt. v. 2. 13² twice; 4. 39; 6. 12³; ii. 2. 12⁴; 4. 12⁵; 6. 11⁶; iii. 2. 10⁷; vi. 4. 3⁸. Of *an* as result of final *au* before a vowel, I have failed to collect the examples; but had there been any cases of the omission of the *v*, I think I should not have omitted to observe and note them.

उकारौकारपरौ लुप्यते माचाकीवस्य ॥ २२ ॥

22. According to *Mācākiya*, both are omitted when followed by *u* or *o*.

Instead of *Mācākiya*, the southern manuscripts have, both in the rule and in the commentary, *Māyikāya*.

All the manuscripts of the commentary declare that "respectively" (*yathāsaṁkhyam*) is to be understood in the rule—that is to say, that it directs us to drop *y* before *u*, and *v* before *o*; but their examples do not support this interpretation, and it is palpably a false one. It is difficult to believe that the rule itself is not corrupted, and that it ought not to read *ukārāukāraparō lupyate*, 'v is dropped before *u* or *o*' (it does not occur in the text before *u*); for, while we can discover no phonetic reason for the omission of *y* before a labial vowel, there is a very obvious difficulty in the utterance of *v* (or *u*) before *u* (no real Sanskrit word begins with *vu*, nor can I recall it in the interior of a word except as the rare result of *sandhi*); and, as thus amended, *Mācākiya*'s view would accord with the accepted doctrine of the *Rik Prāt.* (ii. 9–11), and with one mentioned, though not adopted, by the *Vāj. Pr.* (iv. 125).

The illustrative examples given are in part those which have appeared already, even more than once, under the preceding rules:

21. *sāmnidhyān nishedho labhyate. sāmkrtyasya mate 'varṇa-pārvo vakāro na lupyate; yakāras tu lupyata eve 'ty arthaḥ. 'vāy-----' ahāv----- pārvo cāryamaṭanivartakas tu cābāḥ.*

sūtram idam eve 'shtam: na tu pārvo cāryam¹ paravo cāryam² ca.

¹ W. B. om.; O. puts after the other example. ² O. *pārvasūtrad*. ³ B. O. om.

22. *yakāravakārāv avarṇapārvoṇ ukārāukāraparōṇ lupyete yathāsaṁkhyam¹ mācākiyasyā² cāryasya mate³. āpa----- yā----- evamparāv iti kim: tā----- vāy----- lupyete iti 'ha punarārambhāḥ pārvasūtradvayasthitanāṇāḥ⁴ sambandhaḥ caṅkā-nirākaraṇārthaḥ⁵.*

¹ O. om.; G. M. after *mate*. ² G. M. *māyikāsyā*, as in the rule itself. ³ B. G. M. *matenā*. ⁴ W. *-tajanana*; B. *-tājana*; O. *-tananaḥ*. ⁵ O. om. *caṅkā*; W. *-tham*.

āpa undantu (i.2.1¹), and *yā oshadhayah* (iv.2.6⁴⁻⁵: so W. B.; but G. M. O. give instead *yā jāta oshadhayah*, iv.2.6¹); to which O. adds an example for *v*, namely *ṣatakṛataḥ ut* (i.8.12³: it ought, in illustration of the rule, to read *ṣatakṛata ut*), putting it between the other two. Counter-examples are *ta enam bhishajyanti* (ii.3.11⁴: we are to understand, apparently, that Mācākiya would read *tay enam*), and *vāyav ishtaye* (ii.2.12⁵).

The commentator remarks in conclusion that the repetition of *lupyete* in the present rule (it was read above, in rule 19) is intended to remove all suspicion of the continued implication of the negative which forms a part of the two preceding rules.

लेशो वात्सप्रस्यैतयोः ॥ २३ ॥

23. According to Vātsapra, they are imperceptibly uttered.

It might admit of question whether the "they" here spoken of are final *y* and *v* in general, or only *y* and *v* followed by *u* and *o*, as specified in the last rule. As things stand, the use of the demonstrative *etayoh* rather favors, though not unequivocally, the latter interpretation, and it is the one adopted by the commentator. But if the preceding rule be restored to what we have suggested above as its more probable original form, then the *etayoh* will be very well in place here as referring to *y* and *v* in general; and this interpretation is supported by the fact that the Ath. Pr. (ii.24) and Pāṇini (viii.3.18) ascribe a like opinion to another grammarian, Cākatāyana, whose peculiar views upon the subject are likewise hinted at by the Vāj. Pr. (iv.126). As the meaning of *leṣa* is defined to be *luptavaḥ uccāraṇam*, 'utterance as if omitted,' there is not much for the two opposing parties to contend about.

न प्लुतप्रग्रहौ ॥ २४ ॥

24. Exceptions are protracted and *pragraha* vowels.

Such, namely, are exempt from the rules of combination—and not merely those given in this chapter, but also such as are found elsewhere: for example, at ix.11,12. There is nothing about the

23. 'vātsaprasya mata etayor² yakāravakārayor³ avarṇapāvayor leṣaḥ syāt. leṣo nāma luptavaḥ⁴ uccāraṇam. etayor ity ukārāukāraparāu nirdiṣṭi. uktāny evo⁵ dāharaṇāni.

(1) B. om., along with the rule. (2) Only in W. (3) G. M. O. yavak-. (4) B. -tam.

24. 'na khalu plutaḥ pragrahaḥ ca¹ saṁdhividhim bhajete². yathā: astu..... te..... ityādividhāu nishiddhe³ nyasmiṇṇ ca⁴ nārābhyamāne⁵ prakṛtvaḥ⁶ bhavati.

(1) G. M. plutaḥ ca pragrahaḥ ca etāu na khalu. (2) W. B. O. -jate. (3) G. M. 'rabh-. (4) O. tyā.

rule pointing out that it has a bearing so extensive. Only one example is given for each class: *astu hīs ity abratām* (vii.1.6¹), and *te enam abhi* (ii.5.6²).

The commentator points out, as he did not take the trouble to do under rule 18 of this chapter, that, the rules of combination being thus suspended with reference to these two classes, and no other rule being given about them, they remain in their natural condition.

All the Prāticākhyas have rules equivalent to this (Rik Pr. ii.27; Vāj. Pr. iv.84; Ath. Pr. iii.33: in the note to Ath. Pr. i.73 I overlooked the present precept of the Tāittirīya-Prāticākhya); none assumes that the pronouncing a vowel to be *pragraha* exempts it, *eo ipso*, from phonetic combination.

परश्च परश्च ॥२५॥

25. Also the remaining vowel.

That is to say, the vowel remaining after the omission of the final *y* or *v* is, like those mentioned in the preceding rule, exempt from farther combination. According to the commentator, the "also" (*ca*) of the rule brings forward "*y* and *v*," the fact of their constituting an exception is inferred from the neighborhood of the preceding rule, and *paraḥ* means 'another,' and qualifies *sandhih* understood: "no further combination takes place." This seems to me inadmissible, as there has been no suggestion of any such word as *sandhi*. Perhaps *para* may be better understood of the vowel "following" the *y* and *v* of which the chapter has been treating. It needs, at any rate, some violence to bring in the rule with the meaning which it is evidently intended to bear: no one would have any right to guess, from its form and position alone, at what it is aimed.

The commentator's examples are *āpa undantu* (i.2.1³) and *agra imam* (i.1.5⁴). In reply to the objection that it would be enough to state the implication of the rule as "where an omission has taken place" instead of "an omission of *y* or *v*," he brings up *se 'd u hotā* (i.1.14⁵), *sāi 'nā 'nikena* (iv.3.13² et al.), and *sāu 'sha-dhih* (iv.2.3³), as examples of an elision of a final which does not prevent the further combination of its predecessor and its successor under the rules of this chapter.

25. cakārākṛṣṭayor yavakārayor lope sati paraḥ 'sandhih na bhavati.' yathā: āpa.....: agra..... sāmniidhyān nishedho labhyate. nanu lope sati 'ty' etācatāi 'vā 'lam: yavakārayor iti kim. se 'd.....: 'sāi.....: 'sāu.....: ity adī.

iti tribhāshyaratne prāticākhyavivarane
daṣamo 'dhyāyah.

¹ G. M. sandhividhin na bhavate. ² G. M. om. ³ W. om. iti. ⁴ O. om. ⁵ O. adds prathamapraṇe.

CHAPTER XI.

CONTENTS: 1, initial *a* elided after *e* or *o*; 2-18, exceptions, cases of retention of initial *a* after *e* or *o*; 19, dissident view as to the nature of the elision.

लुप्यते वकार एकारैकारपूर्वः ॥ १ ॥

1. But *a* is elided when preceded by *e* or *o*.

The subject of the omission or retention of initial *a* after final *e* or *o*, and of the accent thence arising, occupies the whole of this chapter and of the one next following, the cases of retention being mostly rehearsed in this. No attempt is made, here any more than in the treatment of other similar matters in the work, to effect a real classification—much less, an explanation—of the facts dealt with. Nor have I, on the other hand, drawn up such a classification, as I did for the Atharva-Veda (see Atharva-Prātiçākhyā, under rule iii.54). Doubtless, if drawn up, it would show nearly the same state of things to prevail in the Tāittiriya as in the Atharvan text: namely, that the elision is the greatly prevailing, almost exclusive, usage in the prose passages; while, in the metrical passages, the *a* is more usually retained where the metre requires its retention, and omitted where the metre requires its omission—although with numerous exceptions, of which the most regular is that the *a* is dropped in writing at the beginning of a *pāda*, where, of course, it was always retained in metrical utterance. The general subject of the relation of the written and spoken texts to one another in regard to this special point is well worth an elaborate investigation, founded on all the Vedic texts.

For the word “but” (*tu*) in the rule is given an alternative explanation. Some, the commentator says, regard it as suspending the force of the exceptional rule x.24: others, as marking the discontinuance of the general direction “followed by a vowel,” which has been in action since ix.10. As in other like cases heretofore, we have no good reason for applying it to any particular rule or phrase; it merely marks an abrupt transition to a new subject, somewhat exceptional in its relations to the principles already laid down. The subject was, however, anticipated and provided for in rule ix.13.

1. *ekārapārva okārapārvo vā 'kāro' lupyate. yathā: te.....*
"so....." tuçabdo na plutapragrahāv (x.24) iti nishedhasam-
bandhavidhiṁ¹ nivarṭayati 'ti kecit: svaraparādhikāraṁ nivar-
yati² 'ty apare saṁgirante. 'ekāraç cāu 'kāraç cāi 'kārau³ kārau:
ekārau⁴ kārau pāre⁵ yasmāt sa tathoktaḥ.

¹ all the MSS. *akāro*. ² G. M. om. ³ B. om. ⁴ G. M. *-bandhi*; O. *-bandham*.
⁵ G. M. *nivarṭayati*. ⁶ in W. only. ⁷ B. om. ⁸ G. M. *yasya*.

To illustrate the rule, only two phrases, both of frequent occurrence, are quoted: namely *te 'bruvan* (ii.5.1² et al.) and *so 'bravīt* (ii.1.2¹ et al.).

In the other *Prāticākhyas*, the apparent loss of initial *a* after *e* or *o* is treated as an absorption of it into its predecessor, or a unification of the two. See *Ath. Pr.* iii.53 and note, and rule 19 of this chapter, where a somewhat similar view seems suggested.

All the MSS. excepting B. read in the rule *ekdraokārapūrah*; and, where the rule is quoted (i.81 and ix.13), we have six cases of this reading against three of *ekdrāuk*. But the former is simply an instance of the usage, so common in the commentary (see above, p. 4), of separating, for the sake of clearness, the elements of compound words, or otherwise disregarding the rules of *sandhi*.

अथालोपः ॥ २ ॥

2. Now follow cases of non-elision.

The rest of this chapter is occupied with an enumeration of the cases in which initial *a* is retained. First, in rule 3, a number of passages are specified in which non-elision is the rule, and elision (as determined by the rules of the next chapter) is exceptional; then, in the following rules, more isolated cases are disposed of.

धातारातिरुपवात्तपेयनुष्टुप्शेनायोव्यधुवन्नितिरियमेव-
सायामिर्धूरुद्रप्रथमोपोत्तमविकर्षविकृत्यहिरण्यवर्णी-
ययाज्यामहापृथ्वे ॥ ३ ॥

3. The *a* is not elided in the following sections: those beginning with *dhātā rātiḥ* and *upa*; those styled *vājapeya*; those beginning with *jush'a* and *cyenāya*; those styled *ukhya*; those beginning with *dhruvakshitiḥ*, *iyam eva sā yā*, and *agnir mārddhā*; the first and the next to the last of the *rudra* chapter; and those styled *vikarsha*, *vihavya*, *hiranyavarṇīya*, *yājyā*, and *mahāpr-shīthya*.

Here are pointed out not less than seventy-three sections or *anuvākas*, in which *a* is not elided (except in the cases specified in the rules of the next chapter). Those designated by the annotation of their first words are i.4.44; 5.5: iii.1.10; 2.8: iv.3.4, 11; 4.4. The *vājapeya* sections are six, namely i.7.7-12. The *ukhya* sections (as pointed out above, under ix.20) are twenty, namely iv.1.1-10; 2.1-10. The *rudra* chapter is iv.5, containing eleven sections;

2. 'athe 'ty ayam adhikārah: alopa ucyata ity etad adhikṛtaṁ veditavyam ita uttarāṁ yad vakshyāmaḥ. 'na lopo 'lopaḥ: lopābhāva ity arthaḥ.

(1) G. M. om. (2) all MSS. na lopah alopah.

those here referred to, then, are iv.5.1,10. The name *vikarsha* belongs to five sections, namely iv.6.1-5. Three sections, iv.7.12-14, are styled *vihavya*. The *hiraṇyavarnīya* section (as shown under ix.20) is v.6.1. The *yājyās* have been repeatedly the subjects of prescription in earlier chapters (iii.9,11; ix.30); they are twenty-three sections, namely i.1.14; 2.14; 3.14; 4.46; 5.11; 6.12; 7.13; 8.22; ii.1.11; 2.12; 3.14; 4.14; 5.12; 6.11,12; iii.1.11; 2.11; 3.11; 4.11; 5.11; iv.1.11; 2.11; 3.13. The *mahāprsthya* sections, finally, are the first six of those which (as seen under ix.20) bear the name *prsthya*; they are iv.4.12; 6.6-9; 7.15.

Section i.4.44 is quoted by its two first words, instead of by *dhātā* only, according to the commentator, because of the occurrence in another *çākhā* of a section beginning *dhātā devebhyo 'surān* (G. M. omit *asurān*). Again, iv.3.4 is quoted by *dhruvakshitih*, instead of by *dhruva* (the first *pada* of *dhruvakshitih*, i.48), because *dhruva* (by i.22) would include *dhruvah*, and there is another section beginning with this word, and containing cases of elision, *dhruvo 'sī dhruvo 'hañ sajāteshu bhāyāsam* (ii.3.9¹: only G. M. have the last two words), which would otherwise be violations of the rule. Yet again, to quote iv.3.11 by *iyam* simply would not answer, because i.2.4 begins with *iyam te çakra tanūr*, and contains a case of elision, *sagarbhyo 'nu sakhā sayāthyah* (i.2.4²: only O. has the last word; G. M. omit the example). But why quote by so long a phrase as *iyam eva sā yā*, of which the last two words are unnecessary? To this objection there is an alternative answer: some say that it is for the benefit of the dull-minded; others, that it is intended to include a verse which, though occurring in another place (at i.4.33), is a remainder to this, and which contains the case of non-elision *o te yanti ye aparishu paçyān* (i.4.33: G. M. O. omit *paçyān*). Now it is true that the single verse constituting i.4.33 is of kindred subject with iv.3.11, and in the Rig-Veda forms part of the same hymn (i.113) with parts of the latter; and it is also true that the combination *ye aparishu* is not otherwise authorized by the Prātiçākhyā; but it is, of course, little less than absurd to assert that an excessive

3. 'dhātārātir ity' ādishe anuvākeshe ekārāpārva okārāpārvo vā 'kāro na lupyate. 'dhātā rātir (i.4.44) ity atra yathā:³ nīdh-....: rātir iti kim: dhātā devebhyo 'surān iti çākhāntare. 'upaprayanto adhvaram (i.5.5) ity atra yathā:³ āre-....: deva savitāḥ prā suva (i.7.7) ity 'ādi shodānuvākānām' vājapeyasamjñā: 'atra yathā:³ te no-....: te agre-....: jushṭo vāca (iii.1.10) 'ity atra yathā:³ yas-....: 'yo-....: 'çyenāya 'patvane (iii.2.8) ity atra yathā:³ namaḥ-....: viçve-....: ukhye yathā:³ çṣṇv-....: namo-....: dhruvakshitir (iv.3.4) 'ity atra yathā:³ viçve-....: ūrmir-....: 'kshitir iti kim: dhruve 'ty 'akārāntasya yadī¹³ grahaṇam syāt¹¹: dhruvo-....: ity atra bhaved¹³ iti.¹⁴ iyam eva sā yā (iv.3.11) 'ity atra¹⁵:

quotation of the beginning of the one *anuvāka* has any right, or can have been intended, to include the other. The right of i.4.33, it may be remarked, to stand in the text to which our *Prāticākhya* applies, is assured by the contemplation of others of its phonetic phenomena by rules found elsewhere (most unequivocally by vi.5); its case of non-elision would seem to have been overlooked by the makers of the treatise, but discovered by the commentators, some of whom have tried to force it violently within the ken of their rules. It is necessary to quote iv.4.4 by two words, because i.6.3 also begins with *agnih*, and in it we find *yo me 'nti dāre 'rātīyati* (i.6.3¹: the example is wanting in G. M.). Finally, instead of *prsthya* passages, the *mahāprsthya* are specified, because of such cases as *prthivi te 'ntarikshena* (v.2.12²: the *anuvāka* is *prsthya*, but not *mahāprsthya*).

The commentator cites one or more examples from each of the sections or sets of sections which the rule specifies, as follows. From the section beginning *dhātā rātiḥ* is taken *nidhipatir no agnih* (i.4.44¹); it contains three more cases, and one exception. From that beginning with *upa* comes *āre asme ca* (i.5.5¹); it contains six other cases, and one exception. From the *vājapeya* sections, *te no arvantāḥ* (i.7.8²) and *te agre aṣvam ā 'yuñjan* (i.7.7²); they contain eleven examples, and eleven exceptions. The section beginning with *jushta* yields *yas te aṅguh* (iii.1.10¹), and O. alone adds *yo drapso aṅguh* (iii.1.10¹); there are two other cases, and no exception. From the *gyenāya* section, *namah pitrbhyo abhi* (iii.2.8³) and *viṣve arapā edhate* (iii.2.8⁴); there are four other cases, and two exceptions. From the *ukhya* sections, *ṣṇvanti viṣve amrtasya putrāḥ* (iv.1.12: only W. has *putrāḥ*) and *namo astu sarpebhyah* (iv.2.8³); they yield seventy-five cases, and forty-five exceptions. From the section *dhruvākshitiḥ* are cited the only two examples, *viṣve abhi ṣṇvantu* (iv.3.4²) and *ūrmir drapso apām asi* (iv.3.4²: only G. M. have *asi*); there are no exceptions. From the section beginning *iyam* etc. are taken *ketum kṛvāne ajare* (iv.3.11¹: G. M. omit *ketum*) and *trayo gharmāso anu* (iv.3.11¹); there are three other cases, and one exception. The

ketum.....: *trayo*.....: *iyam ity* ¹²*etāvātāi 'vā 'lam*:¹⁸ *iyam te gakra tanūr* (i.2.4) *ity* ¹⁷*atra sag*....: *ity atra mā bhād iti*: *sā ye 'ti padadvayam*¹⁷ *mandadhiyām pratipattiyartham iti kecit*: *anye te anyathā kathayanti*: *asyā 'nuvākasya geshabhātā* ¹⁹*ya rḡ*¹⁵ *anyatra sthitā sā 'pi* ¹⁹*svikartavye 'ti*¹⁹: *o te*.....: *agnir mūrdhā* ²⁰*diva* (iv.4.4) *ity atra yathā*²⁰: *sa*.....: *enā*.....: *mārdhe 'ti kim*: *agnir mā durishṭād* (i.6.3) *ity atra* ²¹*yo me*.....²¹ *rudrapraṇasya prathamopottamānuvākayor yathā*²²: *namo*.....: *drāpe*.....: *uta*.....: *uttamasya pārvataḥ*²³ *sañni-kṛṣṭa upottamah. aṣmann ūrjam* (iv.6.1) ²⁴*ity atrā 'nuvāka-pāñcasya*²⁴ *vikarshasamjñā*: *tatrā*²⁵ *'nyam*.....: *pāvako*.....: *vājo naḥ sapta pradiṣa*²⁶ (iv.7.12) *ity atrā*²⁷ *'dyanuvākatra-*

first example here is not well chosen, since the *e* of *krneāne* is *pragraha*, and *pragrahas* are not contemplated in the general rules for elision: see xii.8 and note. From the *agnir mūrdhā* section, *sa yojate arushah* (iv.4.4⁴) and *enā vo agnim namasā* (iv.4.4⁴: O. omits *namasā*); there are three other cases, and one exception. From the specified sections of the *rudra* chapter are taken *namo astu nilagricāya* (iv.5.1²), *drāpe andhasas pate* (iv.5.10¹), and *utā mā no arbhakam* (iv.5.10²); they afford fourteen cases, and five exceptions. From the *vikarsha* sections, *anyam te asmat tapantu* (iv.6.1^{2,3}: only W. has *tapantu*) and *pāvako asmahyam* (iv.6.1¹ etc.); there are thirty-three cases, and ten exceptions. From the *vihavya* sections, *vigve adya marutah* (iv.7.12¹: O. omits *marutah*) and *vigve devāso adhi vocatā me* (iv.7.14²: only O. has *vigve*); ten cases and five exceptions. The *hiranyavarṇīya* section affords three cases only, of which one is cited, *eko devo apy atishthat* (v.6.1²). The *yājyā* sections afford a hundred and twenty-nine cases, with thirty-eight exceptions; the selected examples are *supathā rāye asmān* (i.1.14²; repeated at i.4.43¹) and *kāmena kṛto abhy ānat* (i.1.14²: W. B. O. end with *abhi*). From the *mahāprsthīyas*, finally, come *vivasvad vāte abhi nah* (iv.4.12⁴) and *somo adhi bravitū* (iv.6.6⁴: O. adds *no dīm*, doubtless for *no dītiḥ*, which follows in the text); they contain thirty-eight cases and nine exceptions.

This rule, accordingly, disposes at one stroke of three hundred and fifty-one cases of the retention of *a*; but it is at the cost of creating a formidable body of exceptions, a hundred and thirty-one in number, which have to be provided for by the counter-rules of the next chapter—while, once more, a considerable number of the cases falling under the rule have to be individually specified, partly in that chapter and partly in the two following rules of this, as exceptions under the counter rules. It is a complicated process, but it successfully attains at last its purpose.

yasya vihavyasamjñā: tatra²² vigve....: vigve..... hira-
yavarṇīye²³ yathā²⁴: eko..... yājyāsu yathā²¹: supathā.....
kāmena..... samid diçām (iv.4.12) *jīmātasya* (iv.6.6)
yad akrando (iv.6.7) *mā no mitro* (iv.6.8) *ye vājinam*
(iv.6.9) *agner manve* (iv.7.15) *itī²⁵ shannām eṣhām²⁶ anuvā-*
kānām mahāprsthīyasamjñā: tatra²⁷ vivasvad.....: somo
.....: mahe'ti kim: pṛthivī.....

(1) W. B. -rāti 'ty. (2) G. M. *kramago 'dāharanāni*. (3) G. M. *upa* only. (4) G. M. *ādinidhi shannām an-*. (5) G. M. *tatra*. (6) G. M. *om*. (7) In O. only. (8) G. M. *om*; W. omits *yathā*. (9) G. M. *om*. (10) G. M. *om*. (11) G. M. *kṣitigrāhānam*; O. adds *tadā* after *syāt*. (12) O. *etāvamātrasya*. (13) G. M. *mā bhūd*; O. *api bhavet*. (14) O. *om*. (15) G. M. *om*; O. adds *yathā*. (16) G. M. *ukte*; B. adds *kim anyāḥ*; O. *etāvatā 'laṇ kim ebhi*. (17) G. M. *atrā 'pi 'ty adhikopādānam*. (18) W. O. *yā rg*; G. M. *yā rk*; B. *yām rg*. (19) W. B. *svikaroti*; O. adds *yathā*. (20) G. M. *om*. (21) G. M. *mā bhūd itī*. (22) G. M. *om*. (23) W. *pūrvah*. (24) G. M. *itī praçnasya āditah pañcānu-vikānām*; O. *add for atra*. (25) O. *tatra yathā*. (26) G. M. *om*. (27) G. M. O. *om. atra*. (28) G. M. *om*; O. *yathā*. (29) G. M. -*ṛṣāh*. (30) G. M. *om*. (31) G. M. *om*. (32) B. *om*. (33) G. M. put before *shannām*. (34) O. *ins. yathā*.

अश्नुसोश्नुतिरनिष्टतोऽवत्वस्मानवद्यादहनि च ॥४॥

4. Also in *añhasaḥ*, *añhatih*, *anishtṛtaḥ*, *avantv asmān*, *avadyāt*, and *ahani*.

The cases of non-elision referred to are as follows: for *añhasaḥ*, *pramuñcanto no añhasaḥ* (iv.3.13⁵); for *añhatih*, *pari dveshaso añhatih* (ii.6.11²); for *anishtṛtaḥ*, *vardhatām te anishtṛtaḥ* (iv.1.7²); for *avantv asmān*, *te avantv asmān* (ii.6.12³), with a counter-example, *te no 'vantv pitaro haveshu* (ii.6.12⁴: only G. M. have *haveshu*), to prove the necessity of giving *asmān* along with *avantv* in the rule; for *avadyāt*, *mitramaho avadyāt* (i.2.14⁶); and for *ahani*, *gucih gukre ahany ojasinā* (iv.4.12¹: G. M. O. stop at *ahani*). All of them occur in passages which are the subject of the preceding rule, and the commentator points out that the "also" (*ca*) of the rule brings forward the implication of those passages, and that to any of the words specified, if occurring elsewhere in the text, the rule does not apply; citing as example *sa evāi 'nam pāpmano 'ñhaso muñcati* (ii.2.7⁴: all but G. M. stop at *añhasaḥ*). At first sight, then, the rule appears to be a superfluous repetition of part of the cases involved in the preceding one; in fact, however, its value is that of a rehearsal of exceptions under rule xii.4, which teaches that even in the sections above specified, an *a* before a *y*, *v*, *n*, or *h*, if those letters be followed by a vowel, is elided. The only thing calling for explanation about the matter is the connection in which the counter-exceptions are given, which is, to say the least, quite peculiar.

अनु घर्मासत्रायोमर्तीरथस्त्वोदत्तेवातःपूर्वः ॥५॥

5. Also in *anu*, when preceded by *gharmāsaḥ*, *āpaḥ*, *marṭaḥ*, *rathaḥ*, *tvah*, *datte*, and *vātaḥ*.

This rule belongs, in part, in the same category with the preceding, as pointing out cases in which the *a* of *anu* is retained according to rule 3 of this chapter, notwithstanding the prohibition of rule xii.4; but in part it is of a more general character, since the last two cases lie outside the sections specified in rule 3.

4. ¹ *cakāro dhātārātir* (xi.3) *ityādivishayānvādeṣakāḥ*: *añhasaḥ*..... *ity eteshu grahaṇeshu dhātārātirityādisthaleshv*² *ekāropārvo vāu*³ *'kāropārvo vā*³ *'kāro na lupyate. yathā*: *pram*.....: *pari*.....: *vardh*.....: *te*.....: *asmān iti kim*: *te no*.....: *mitr*.....: *gucih*..... *yavanahaparavād*⁴ (xii.4) *eshu prāpyamānapoṣeshv*⁵ *'alopo 'yan*⁶ *vihitaḥ. anvādeṣaḥ kimarthaḥ*: *sa*.....

¹ G. M. ins. *eteshu grahaṇeshu*. ² G. M. -*disthaleviṣh*. ³ B. adds *antarvartishu*; G. M. -*jāpattishu*; O. -*javartishu satu*. ⁴ G. M. O. om. *vā*. ⁵ O. om. ⁶ G. M. O. om. ⁷ W. -*ratv*; G. M. -*hasvarapar*. ⁸ G. M. ins. *satu*. ⁹ W. om.; B. na.

The commentator explains the phraseology used as signifying that the words rehearsed, having their final *visarga* [with the preceding *a*] converted to *o* [of course, excepting *datte*], have the office of preceding causes—that is, of producing an effect upon the word that follows them; but he gives no hint of the partial suspension of the implication made in the preceding rule; intimating rather, that the cases rehearsed are all of them exceptions under rule xii.4. He quotes the passages, as follows: *trayo għarmāso anu* (iv.3.11¹), *tasmād āpo anu sthāna* (v.6.1²), *yadā te marto anu* (iv.6.7³), *anu tvā ratho anu* (iv.6.7³), *piyati tvo anu tvah* (iv.2.3⁴; only G. M. have the last word), *gukram ā datte anuhāya jāryāi* (iii.2.2²; G. M. O. omit *jāryāi*), and *dhanus tad vāto anu vātu te* (v.5.7^{2,4}; O. ends with *anu*). To show that other words than *anu* are not relieved from the action of xii.4, he gives us *amushmiṇ loke vāto bhi pavate* (v.4.9⁴; all but G. M. begin at *vāto*); and further, to show that *anu* retains its *a* only after these words, *anu gāvo nu bhagah kaninām* (iv.6.7³; only G. M. O. have the last word).

I have noted ten cases in which the *a* of *anu* is elided under the operation of rule xii.4.

अभिवाचयश्च ॥ ६ ॥

6. Also (after *vātoḥ*) in *abhi vātu* and *apah*.

The *ca*, 'also,' here brings down as *pūrvanimitta* simply *vātaḥ*, the word last specified in the preceding rule. The cases have nothing to do with xi.3: they are *mayobhār vāto abhi vātā srāh* (vii.4.17¹; G. M. omit the first word, and they alone have the last), and *yad vāto apo agamat* (vii.4.20: O. omits *agamat*); and, as counter-examples, the commentator quotes *vāto bhi* (v.4.9⁴) to show the necessity of giving *vātu* after *abhi* in the rule, and *ava rundhe po gre bhīryākarati* (vi.4.3²; G. M. omit the last two words) to attest the implication conveyed by the *ca*.

अन्वगमश्च ॥ ७ ॥

5. *atra visargāntānām oṭvam āpannānām pūrvanimittatvam¹ iti² vijñeyam: għarmāsaḥ..... ity ecampūrva anu ity atrā akāro na lupyate. yathā: trayo³..... tasmād..... yadā..... anu..... piyati..... gukram..... dhanus⁴..... anu iti kim: amushmiṇ..... ecampūrva iti kim: anu..... yavana-haparatanishedhārtho⁴ 'yam ārambhaḥ.*

¹ W. G. M. -mittam. ² O. omi. ³ a lacuna in B. ⁴ G. M. yavanahasavarapa-; O. -shedhanishegartho.

6. *ekāro vāta ity anvādicati: abhi vātu: apah: ity etayor akāro vātaḥpūrvo na¹ lupyate. mayo..... vātu iti kim: vāto..... yad..... anvādegena kim: ava.....*

¹ G. M. ina. khalu. ² G. M. put before *vātu* etc.

7. Also (after *apah*) in *anu* and *agamat*.

Here, again, the *ca*, 'also,' brings forward only the last word in the preceding rule, namely *apah*—and what is more, gives that word a new character, changing it from *nimittin* to *nimitta* or affecting cause. Of this the commentator takes no notice, and we are doubtless to regard it as quite in order, and as merely adding another to the formidable list of uncertainties involved in the curious system of *anuvṛtti* or continued implication. The passages had in view are *apo anv acārisham* (i.4.45², 46²: B. reads *āpo adyā 'nv*, which is the version of the Rig-Veda, i.23.23) and *apo agamad indrasya* (vii.4.20); as counter-example, is given *paçavo 'nā 'd āyan* (ii.1.5¹), to prove the implication of *apah*.

आपःपूर्वे ऽद्विषानपादस्मान् ॥ ८ ॥

8. Also in *adbhih*, *apām napāt*, and *asmān*, when preceded by *apah*.

The passages are *sam āpo adbhir agmata* (i.1.8), *devīr āpo apām napāt* (i.2.3²: vi.1.4⁹; 4.3³), and *āpo asmān mātaraḥ cundhantu* (i.2.1¹: O. omits *cundhantu*). The necessity of specifying *napāt* after *apām* is shown by *vārunīr āpo 'pām ca* (ii.1.9²), and the restriction to preceding *apah* by *so 'smān pātu* (v.5.5¹).

रायेसइन्द्रःपूर्वश्चाकारपरे ॥ ९ ॥

9. In *asmān*, also, if followed by *a*, when *rāye*, *saḥ*, and *indrah* precede.

The *ca*, 'also,' again brings down the word last mentioned in the preceding rule. The passages for *saḥ* and *indrah* are *mā so asmān avahāya* (v.7.9¹) and *indro asmān asmin dvītiye* (iii.1.9²: O. omits *dvītiye*): and other cases of *asmān* after *saḥ* are to be found at i.6.6⁴ and iii.2.7². As counter-examples, are given *so 'smān pātu* (v.5.5¹), to show that the *asmān* must be followed by *a*; and *smo 'smān amutra* (vi.6.1⁴: all the MSS. of the commentary have the false reading *so 'smān*; such a phrase would be precisely out of place here as illustration), to show that it is only

7. *apa iti cakāro 'nvādiçati: anu: agamat: ity etayor akāro 'na khalv' apahpārvo lupyate. apo anv.....: apo ag..... evampārva iti kim: paçavo.....*

① G. M. O. om. *khalv*, and put *na* next before *lupyate*.

8. *adbhih..... eteshv' akāra āpahpārvo na lupyate. sam.....: devīr.....: napāt iti kim: vārunīr.....: āpo..... evampārva iti kim: so.....*

¹ G. M. *eshv*; O. *eshv grahaṇeshv*.

after the words specified that *asmān*, even before *a*, remains unmutated.

The other case, that of preceding *rāye*, makes more difficulty, since the *saṁhitā* contains no passage in which *asmān*, when itself followed by *a*, has *rāye* before it. The commentator first declares the passage had in view to belong to another text (*śākhā*); but adds, as an alternative explanation, that the precept relates to the *jaṭā*-text, where we read *rāye asmān asmān rāye rāye asmān* (i.1.14²; 4.43¹). He proceeds further to say that, in case any one objects that in the *saṁhitā* form of the passage the example does not hold good, since *asmān* is not there followed by *a* (it reads *rāye asmān vigāni*), he shall reply that the case is one falling under i.61. It is there taught, namely, that a passage of three words or more, if repeated in the text, reads as it read on its first occurrence: now the one in question first appears in i.1.14, which is a *yājñyā* section, and hence the *a* of *asmān* is retained by xi.3; at i.4.43, then, its retention is assured. But then there ought to be no necessity for specially establishing its retention in *jaṭā*, any more than in any other case where an *a* is retained in *saṁhitā*. This difficulty the commentator evidently perceives, although he does not state it; for otherwise the *jaṭā* explanation would have satisfied him, and he would never have thought of suggesting another *śākhā*. The difficulty really remains unsolved, and a serious one: either there was a blunder on the part of the makers of the treatise, or a passage not contained in the present *Sanhitā* was contemplated by them: I incline to think the former more likely.

तेपूर्वी ज्ञान्धोऽशुरग्रे ॥ १० ॥

10. Also in *adya*, *andhaḥ*, *añcuḥ*, and *agne*, when *te* precedes.

The commentator quotes the passages, as follows: *paṇum paṇupate te adya* (iii.1.4¹: W. O. omit *paṇum*), *upo te andhaḥ* (i.4.4 and iii.4.2¹), *añcunā te añcuḥ* (i.2.6: B. omits the example), and *yat te agne tejas tena* (iii.5.3²: only B. has *tena*). Counter-examples are, first, to show that only these words keep their *a* after *te*, *te 'gnaye pravate* (ii.4.1²: B. has a corrupted reading, *te enam*, and W. a *lacuna* to the end of the comment, putting in place of it an example from under the next rule, *tena tvā "dadhe 'gne aṅgiraḥ*),

2. *cakārākṛṣṭe 'smāngrahāṇe 'kārapare sati' vartamāno' karo rāye sa indra ity' evampūrvo na lupyate. rāyepūrvasyo 'dāharaṇam śākhāntare: 'atha vā' jaṭāyām bhavati: rāye..... yathā-saṁhitāyām 'no 'dāharaṇam akāraparato'ābhāvāt' tarhī katham alopa' iti keci': tripadaprabhṛtipunaruktatvād iti brāmaḥ. mā indro..... akārapara iti kim: so..... evampūrva iti kim: smo..... akāraḥ paro yasmāt¹² tad akāraparam¹³: tasmin.*

¹ in W. only. ² G. M. put before *'kārapare*. ³ G. M. O. om. ⁽⁴⁾ O. om. ⁵ G. M. O. ins. *ta*. ⁶ W. O. *-patvābhe*; G. M. *-parābhe*. ⁷ O. *tathā*; G. M. add *tadd*. ⁸ G. M. *lopa*. ⁹ G. M. O. *cet*. ⁽¹⁰⁾ W. *tad akān*; G. M. *akāraparaḥ*.

and second, to show that these words do so only after *te*, *prathamō 'ṅu skandati* (iii. .8³: only B. has *skandati*).

Of *agne* after *te*, the text presents eighteen other cases: namely i.2.11² twice; 4.43²; 5.2⁴, 3², 4³; 6.6²; 7.6⁴; iii.4.10³; 5.3² (a second case): v.4.7³; 7.4¹, 6³, 8¹ three times: vi.2.2⁷; 6.1².

मेपूर्वश्च ॥ ११ ॥

11. In *agne*, also, when preceded by *me*.

Only *agne*, the last word of rule 10, is brought down into this. The commentator quotes *yan me agne asya* (i.6.2¹, 10²: W. B. omit *asya*) and *imā me agna ishtakāḥ* (iv.4.11^{3,4} and v.4.2⁴); and there is another case in iv.4.11⁴. He adds, as usual, a number of counter-examples, of obvious intent: they are *tena tvā "dadhe 'gne aṅgīrah* (i.2.12¹: O. omits *aṅgīrah*), *prānaç ca me 'pānaḥ* (iv.7.1¹), and *tad açakam tan me 'rādhi* (i.6.6³).

अस्याश्चिनापरा च ॥ १२ ॥

12. As also, in *asya*, *açvinā*, and *aparā*.

That is to say, when these words follow *me*. The passages are *viyantu devā havisho me asya* (i.5.10³: O. begins at *devā*), *punar me açvinā yuvam cakshuḥ* (iii.2.5⁴: W. B. omit the last word, O. the last two), and *yad vā me aparāgatam* (vi.6.7²).

नःपूर्वा ऽसदग्निरधानमोऽभ्यस्मिन्नद्यपयि ॥ १३ ॥

13. Also in *asat*, *agnih*, *agha*, *antamah*, *abhi*, *asmin*, and *adya pathi*, when preceded by *naḥ*.

The examples are *supārā no asat vaçe* (i.2.3¹ and vi.1.4⁴), *ayam no agnir varivah* (i.3.4¹ and i.4.46³; there is another case of *no agnih* at v.7.9¹), *rakshā mākir no aghaçaṇsa içata* (i.4.24 and

10. *adya*..... *eteshv*¹ *akāras ta ity evampūrvo na lupyate. yathā: paçum*.....: *upo*.....: ²*añçunā*.....³ *yat*..... *eteshv iti kim: 'te*.....: *tepūrva iti kim: prathamō*.....⁴

¹ O. *eshu*. ² in W. only. ³ B. om. ⁴ W. om., and ins. *tena ted* etc.

11. *'cakāro 'gna ity anvādiçati: mepūrvo 'gna ity atrā 'kāro' na lupyate. yathā: yan*.....: *imā*..... *mepūrva iti kim: tena*.....: *anvādeçena*² *kim: 'prānaç*.....⁴ *tad*.....

¹ B. *cakārāçrahte saty agna ity asmin akāro ma ity evampūrvo*; G. M. the same, omitting *sati*; O. the same, omitting *sati* and the second *iti*. ² in W. only. ³ O. *ça iti*. ⁴ O. om.

12. *mepūrva iti cakāro 'nvādiçati: asya*..... ¹ *eteshv*² *akāro mepūrvo na lupyate. vi*.....: *punar*.....: *yad*.....

¹ G. M. ins. *iti*. ² O. *eshv*.

iv.6.6⁴: G. M. O. omit *icāta*), *agne tvam no antamah* (i.5.6² and iv.4.4⁸), *svistim no abhi vasiyah* (iii.1.9²: G. M. O. omit *vasiyah*), *gikshā no asmin* (vii.5.7⁴), and *tebhīr no adya pathibhih sugebhī rakshā ca naḥ* (vii.5.24: all but W. end with *pathibhih*). The necessity of including *pathi* in the rule is shown by *no 'dya vam vasati 'ti* (ii.5.3⁶⁻⁷). Other counter-examples, of obvious intent, are *tasmād aṇvād gardabho 'sattarah* (v.1.2¹: G. M. omit the first two words), so *'gnir jātah* (v.1.4¹), *uttarato 'ghāyur abhidāsati* (v.7.3¹: B. O. omit the last word), *te 'sminn āchanta* (vii.2.10¹), *namo 'gnaye 'pratividdhāya* (i.5.10¹: the example is found only in G. M.), and *te naḥ pāntu te no 'vantu* (i.2.3¹; 8.7¹: iv.3.3²).

नमःपूर्वा अग्नेभ्योऽग्नियाय ॥ १३ ॥

14. Also in *agre*, *aṇvebhyah*, and *agniyāya*, when preceded by *namah*.

The passages are *namo agrevadhāya ca* (iv.5.8¹), *namo aṇvebhyo 'ṇapatibhyah* (iv.5.3²: B. omits the last word; the whole example is wanting in W.), and *namo agniyāya ca* (iv.5.5²). Counter-examples are *apo 'gre 'bhivyāharati* (vi.4.3²) and *namo 'gnaye 'pratividdhāya* (i.5.10¹).

आविन्नःसोमःपूर्वा अग्निपरः ॥ १५ ॥

15. Also when *āvinnaḥ* or *somaḥ* precedes and *agni* follows.

It may be made a question whether the rule should not read *gniparah* (without sign of omission), and mean 'also an *a* preceded by *āvinnaḥ* or *somaḥ* and followed by *gni*.' But the authority of the comment (see below) is decidedly, though not unequivocally, in favor of what I have given, and the construction, though a peculiar one, has its analogies elsewhere in the treatise (compare x.4 etc.). The further difficulty remains, however, that the only passages in the text to which the rule can apply read *agnih*, in the nominative singular, after the two words specified, so that there appears to be no reason why we should not have simply '*gnih*', instead of '*gniparah*'. This the commentator does not fail to perceive,

13. *asat..... eteshv akāro na ity evampārvo na lupyate. yathā': supārā.....: ayam.....: rakshā.....: agne.....: svi-
shṭim.....: gikshā.....: tebhīr..... pathi 'ti kim: no.....
naḥpārva iti kim: tasmād.....: so.....: uttarato.....: te.....
eteshv iti kim: 'namo.....² te.....*

¹ in W. only. ² in G. M. only.

14. '*agre.....¹ eteshv akāro namahpārvo na lupyate. namo
.....: 'namo aṇv.....² namo agni..... namahpārva iti
kim: apo.....: eteshv iti kim: namo 'gn.....*

¹ O. om. ² W. om.

and accordingly—resorting, as we cannot well help saying, to one of his usual subterfuges—he declares *agni* (or, according to W. B. O., *gni*) “a part of a word, intended to include a number of cases occurring in another *çākhā*,” not going so far, however, as to quote any of these cases. I suspect *gniparah* to be either a corruption of *gniḥ*, or originally intended as equivalent with it.

The passages are *āvinno agnir gr̥hapatih* (i.8.12²) and *somo agnir upa devāh* (iii.2.4¹); and the commentator adds counter-examples, so *gnir jātah* (v.1.4¹) and *āvinno 'yam asāu* (i.8.12²).

धीरासोऽदब्धासश्कादशासम्प्रीणांपुत्रःशार्यतिष्ठाठःपि-
तारःपृथिवीयज्ञासतेयेगृह्णाम्यग्रेवाःश्वपज्ञेसस्फानोयु-
वयोयःपृष्ठेपतिर्वीगोशुष्मःपुवःसमिद्धम्पभःपाथोवचोव-
र्षिष्ठेनुषाणोयोरुद्रोवृष्णःपूर्वः ॥ १६ ॥

16. Also *a* is retained when preceded by *dhīrāsah*, *adabdhāsah*, *ekādaçāsah*, *r̥shinām putrah*, *çāryāte*, *ashādah*, *pitārah*, *pr̥thivī yajñe*, *āsate ye*, *gr̥hṇāmy agre*, *vāñ eshah*, *yajñe*, *sañsphānah*, *yuvayor yah*, *pr̥sthe*, *patir vah*, *go*, *çushmah*, *puvah*, *samiddhah*, *r̥shabhah*, *pāthah*, *vacah*, *varshishthe*, *jushāno*, *yo rudrah*, or *v̥rshnah*.

The passages had in view are quoted as follows: *tām dhīrāso anudrya yajante* (i.1.9³: G. M. O. omit the last word); *adabdhāso adabdhāmyam* (i.1.10² and iii.5.6¹); *ekādaçāso apsushadah* (i.4.11); *r̥shinām putro adhirāja eshah* (i.3.7²: G. M. O. omit the last word), with a counter-example, *yasya putro 'jātah* (i.5.8³; 7.6³), to show the need of including *r̥shinām* in the *nimitta*; *yathā çāryāte apibah* (i.4.18: G. M. omit *yathā*); *ashādho agniḥ* (i.5.10¹⁻²); *tvatpitāro agne devāh* (i.5.10²: G. M. O. omit *devāh*); *pr̥thivī yajñe asmin* (i.6.5¹), with a counter-example, *te mā 'smin yajñe* (iii.2.4¹), where, as only W. B. point out, the *jātā*-text shows the mutilation of *asmin* after *yajñe* not preceded by *pr̥thivī* (thus, *asmin yajñe yajñe 'sminn asmin yajñe*); *adhyāsate ye antarikshe* (iii.5.4³), with *ye pr̥thivyān ye 'ntarikshe* (iv.5.11²: only O. has the first *ye*) as counter-example; *mayi gr̥hṇāmy agre agnim* (v.7.9¹⁻²), with *ashtāu kṛte 'gre 'bhi shunoti* (vi.4.5¹: O. omits *shunoti*) as counter-example; *idāvāñ esho asura* (i.6.6⁴ and iii.1.11¹), with *çukra esho 'nto 'ntam manushyah* (vii.2.7²: O. stops at

15. *āvinnaḥ: somah:* ¹ *evampūrvo 'kāro 'gniparo* ² *na lupyate: agnē 'ti padāikadeçah çākhāntare bahūpādāmārthaḥ. āvinno: somo..... evampūrva iti kim: so.....: evampara iti kim: āvinno.....*

¹ G. M. ins. *ity.* ² G. M. *agni ity evamparah akāro*; B. *akārah agniparo.* ³ W. B. O. *gni.*

'ntam) to show the need of *vān*; *itah prathamam jajñe agnih* (ii.2.4⁵: only G. M. have *itah*; without it, also i.3.14⁵): see what is said of this passage, and of the rule as fixing its reading, under i.61; *sañsphāno abhi rakshatu* (iii.3.8²), as counter-example to which, to show that *sphānah* in the rule would not have been enough, is given *gayasphāno 'gnishu* "from another *çākhā*," but the genuineness of the reason is open to doubt; *yuvayor yo asti* (iii.5.4¹) with *yo 'psu bhasma praveçayati* (v.2.2⁵: only O. has the last word) to prove the need of *yuvayoh*; *nākasya prsthē adhi rocane dīcah* (iii.5.5³: G. M. O. omit *dīcah*; another nearly identical case at iii.5.4¹); *yajñapatir eo atra* (v.7.7¹), with *na eo 'bhāgāni havyam* (v.1.1¹: O. omits *havyam*) as counter-example; *goargham eva somam karoti* (vi.1.10¹: O. omits *-mam karoti*; *goargha* occurs twice more in this section, and at v.2.9⁴ we have *goaṣṭva* twice), to which, by rule i.52, *agoargham* (vi.1.10¹ three times) is to be added as further example; *uchushmo agne yajamānāyai 'dhi* (i.6.2²: only G. M. have *edhi*, and O. omits also the preceding word; there is a second case, of *niçushmah*, in the same division); *agrepuvo agrevavah* (i.1.5¹); *samidddho aījan* (v.1.11¹: and we have *samidddho agne* at i.6.6²; 7.6⁴; ii.5.8⁶), without any counter-example to show that *iddhah* would not have been enough to answer the needs of the rule; *dyām rshabho antariksham* (i.2.8¹: O omits *dyām*, and G. M. have, like the Calcutta edition, the false reading *yām*); *priyam pātho apī 'hi* (iii.3.3³ three times); *ugraṁ vaco apā 'eadhīm* (i.2.11²: another nearly identical case in the same division); *varshishthe adhi nāke* (i.1.8 and i.4.43²); *jushāno aptur ājyasya vetu* (i.3.4¹ and vi.3.2²: G. M. omit *vetu*); *yo rudro agnāu yah* (v.5.9³: G. M. O. omit the last word), and, as counter-example, *yad upatrñhyād rudro 'sya* (vi.3.9³: but O. reads *açñiyād* for *upa-trñhyād*, which makes the reference to i.6.7⁴); and, finally, *vṛshno aṣvosya saṁdānam asi* (ii.4.7², 9⁴: O. stops at *aṣvosya*, which would make the reference include also vii.4.18² twice; and there are further cases of retention after *vṛshnah* at i.4.2 and vi.4.5³).

16. *dhīrāsah*..... *evampūrvo na' khalo' akāro lupyate*.
yathā: tān.....: *adab*.....: *ekād*.....: *rshinām*.....: *rshinām iti kim: yasya*.....: *yathā*.....: *ash*.....: *tvat*.....:
prthivī.....: *prthivī 'ti kim: te*.....: *'ity atra jatāyām: adhy*.....:
āsata iti kim: ye.....: *mayi*.....: *grhnāmī 'ti kim: ash*.....:
idāvāñ.....: *vān iti kim: çukra*.....: *itah*.....: *sañs*.....:
sam iti kim: gayasphāno 'gnishu iti çākhāntare: yuvayor.....:
yuvayor iti kim: yo.....: *nākasya*.....: *yajña*.....:
patir iti kim: na.....: *go*.....: *apy akārādi* (i.52) *vacamād*¹
agoargham 'iti eo 'dāharanam: uchushmo.....: *agrepuvo*.....:
samidddho.....: *dyām*.....: *priyam*.....: *ugraṁ*.....:
varsh.....: *jushāno*.....: *yo*.....: *ya iti kim: yad*.....:
vṛshno.....

¹ O. puts next before *lupyate*. ² O. om. ³ G. M. O. om. ⁴ G. M. O. om. ⁵ O. *iti prāptih*. ⁶ O. om.

अरतिमस्ययज्ञस्यातिद्रुतोऽतियत्यनृणोऽविष्यन्नमीवो-
 ज्ञेध्वर्चिर्जीतानज्यानिमद्भियाश्चम्वाल्यर्वन्तमस्त्वृणोद-
 द्धिरोऽप्सुयोऽस्वस्वभायदच्युतोऽश्वमनिरस्यभिरशिधेदङ्गे-
 ऽग्निय ॥ १७ ॥

17. Also in *aratim*, *asya yajñasya*, *atidrutah*, *ati yanti*, *anṛṇah*, *aviṣhyan*, *anumivah*, *anneshu*, *arcih*, *ajitān*, *ajyānim*, *ahnīyāh*, *ambāli*, *arvantam*, *astu*, *akṛnot*, *aṅgirah*, *apsu yah*, *askabhāyat*, *acyutah*, *açvasanih*, *asthabhih*, *açiçret*, *aṅge*, and *aghniya*.

The passages had in view are quoted by the commentator as follows, with such counter-examples as are needed to justify the inclusion of more than one *pada* in any case: *mūrdhānam divo aratim prthivyāh* (i.4.13 and vi.5.2¹: O. begins at *divoh*, and it alone has *prthivyāh*); *yan me agne asya yajñasya* (i.6.2¹, 10²), with the counter-example *ete syā 'mushmīn* (vi.1.10³); *pratyauk somo atidrutah* (i.8.21: all the MSS. here insert the *k* before *somo*, as required by v.32, and G. M. even convert it to *kh*, according to xiv.12); *paçyanto ati yanti* (iii.2.2¹), and, as counter-example to both these last examples, *nai 'nañ somo 'ti pavate* (vi.5.11⁴: O. begins at *somo*); *tad agne anṛṇo bhavāmi* (iii.3.8²: O. omits *bhavāmi*); *na yavase aviṣhyan* (iv.4.3²); *svāvego anamīvo bhavā nah* (iii.4.10¹: B. O. omit *bhavā nah*); *ye anneshu vividhyanti* (iv.5.11¹: O. omits the last word); *jātavedo yo arcih* (v.7.8¹); *çarado ajitān* (v.7.2³); *teshām yo ajyānim* (v.7.2²); *tiroahniyā mā suhutāh* (vii.3.13: O. omits *suhutāh*); *ambe ambāli* (vii.4.19^{1,2} twice, ³ twice); *yo arvantam jighāṁsati* (vii.4.15: O. omits the last word); *bahis te astu bāl iti* (iii.3.10²: O. stops at *astu*; the text furnishes eleven other cases of *astu* with *a* retained, at i.2.3³; 4.45¹; 8.14²: iii.1.14⁴; 2.5⁷, 8²: v.5.9³ twice; 7.2⁴, 4^{5,4}); *ita indro*

17. *aratim*.....¹ *eteshe akāro 'na khalo' ekārapārva okāra-pārva vā lupyate. yathā'*: *mūrdh*.....: *yan*.....: *yajñasye 'ti kim: ete*.....: *pratyauk*.....: *paçy*.....: *drutoyanti 'ty ābhyām' kim: nai*.....: *tad*.....: *na*.....: *svāv*.....: *ye*.....: *jāta-vedo*.....: *çarado*.....: *teshām*.....: *tiro*.....: *ambe*.....: *yo*.....: *bahis*.....: *ita*.....: *agnē*.....: *yo*.....: *ya iti kim: açvo*.....: *yo*.....: *madāya*.....: *yo*.....: *sanir iti kim: açvebhyo*.....: *indro*.....: *bhīr' iti kim: 'çam*.....: *ity atra' jātyām'*: *asthabhyo*.....: *varuṇo*.....: *aṅge*.....: *aghniye 'ty akāragrhitah padāikadeço bahūpādānārthah: etāni*.....: *yad*.....: *payo*.....

¹ G. M. om. the enumeration, and ins. *iti*. ² G. M. om. *khalo*, and put *na* next before *lupyate*. ³ G. M. O. om. ⁴ B. *tābhyām*; G. M. *etābhyām*. ⁵ B. G. M. *asthabhīr*. ⁶ O. om. ⁷ B. om.

akṛnot (i.1.12); *agne āngiro yo'syām* (i.2.12¹: there is another case in the same division, and one at vi.2.7²); *yo apsu ya osha-dhīshu* (v.5.9³), with the counter-example *agvo 'psu bhasma*, v.2.2³); *yo askabhāyad uttaram* (i.2.13⁴: G. M. O. omit *uttaram*); *mudāya raso acyutah* (i.2.6); *yo bhaksho ācāsanih* (iii.2.5⁷), and, as counter-example, *ācābhya 'cāpatibhyaḥ ca* (iv.5.3²: only O. has *ca*); *indro dadhico asthabhir iti* (v.6.6³: O. omits *iti*), and a counter-example from the *jatā*-text of the passage *cam asthabhya majjabhya 'sthabhya 'sthabhya majjabhya* (G. M. give simply *majjabhya 'sthabhya*); *varuṇo agicret* (i.8.10²); *ānge-ānge nī dedhyat* (i.3.10¹ and vi.3.11²: it would have been better to include in the example the preceding word *prāno*, to show that the first *ānge*, as well as the second, furnishes an example under the rule; there is another like pair of cases, after *apāno*, in i.3.10¹); and finally, it is explained that the quotation of *aghniya* with final *a* makes it (by i.22) a part of a word, intended to include a variety of cases, and three such cases (being all that the text contains) are quoted: namely *etāni te aghniye nāmāni* (vii.1.6³), *yad āpo aghniyā varuṇe 'tī cāpāmahe* (i.3.11: B. omits the last word; G. M. O. the last three), and *payo aghniyāsu hrtsu* (i.2.8¹: O. omits *hrtsu*, which would make the citation include also vi.1.11³). This exposition seems to prove that the proper reading at the end of the rule is *aghniya*, and I have ventured to adopt it, though all the MSS. (except T., which is ambiguous, running rules 17 and 18 together in *sandhi*) give *aghniyā*. *Aghniyā* would answer as including *aghniyāsu*, but it would not include also *aghniye*.

अधर स्वरपरे ॥१८॥

18. Also in *adhvara*, when a vowel follows [the *r*].

The examples given in illustration of the rule are *satyadhar-māno adhvarā* (i.2.12), *havishmān devo adhvarah* (i.3.12), and *upaprayanto adhvaram ity āha* (i.5.7¹). In regard to the last of them, it is remarked that rule i.61 is not of force for it, since the conditions imposed by that rule do not arise in it. The rule, namely, directs that a passage of three words or more, being repeated in the text, is to be read as where it first occurred; now *upaprayanto adhvaram* was found at i.5.5¹, where the retention of the *a* comes under rule 3 of this chapter; but here only two

18. *adhvara ity asmin' grahaṇe svarapare 'vartamāno 'kāro 'na khale' ekārāukārapūrvo' lupyate. satya-.....: havishmān: upa-.....: atra' tripadaprabhṛti* (i.61) *nyāye na prasarati*²: *tallakshaṇāsambhavāt. svaropara iti kim: çug-.....: andho-.....*

¹ G. M. *etamin*. ² O. ins. *satī*. ³ G. M. om. ⁴ G. M. O. *ekārapūrva okārapūrvo* *vā*; G. M. adds *na*; B. adds *vā*. ⁵ M. *tatra*. ⁶ B. *sarati*.

words, instead of three, are cited in the repetition. As counter-examples, showing the value of the restriction "when a vowel follows," are given *çug vā agnih so 'dhvāryum* (v.6.2⁴) and *andho 'dhvāryuh syāt* (v.1.3¹ and vi.1.8²: O. alone has *syāt*, and, without that addition, the phrase is found also at v.1.3²). This proves that what is to be "followed by a vowel" is the *r* of *adhvara*; but how that meaning is conveyed by the terms of the rule is not easy to discover. The MSS. are at variance as to the reading of the first word of the rule, T. W. B. O. giving *adhvara*, and G. M. *adhvare*, between which I am at a loss to decide confidently, because neither of them appears to be what is wanted. But I prefer *adhvara*, both because it is better supported, and because it is not the usage of the treatise to put in a case-form the words or themes which it cites from the text.

An additional case falling under the rule is *ūrdhvo adhvarah* (i.1.12); and yet others (as i.5.5¹ twice, and, doubtless, i.4.46²⁻³), to which it would else apply, are disposed of under the general rule xi.3.

स पूर्वस्यार्धसदृशमेकेषामर्धसदृशमेकेषाम् ॥ ११ ॥

19. In the opinion of some, it becomes half-similar with its predecessor.

This is a very blind precept, and we are permitted to doubt whether its purport is interpreted aright by the commentary; in which, moreover, there are peculiar and unintelligent variations of reading. What letter is the subject of the rule—the elided *a*, or the non-elided? The comment says the latter (although the majority of MSS. blunderingly say the "non-protracted" instead), and states that it acquires a quantity similar to half a *mora*, or becomes one and a half *moras* long. It is added, that no special examples are given, because such would not bring to light any difference (? only O. has the reading that means this: W. B. omit the "not;" G. M. are unintelligible). This appears to me quite unsatisfactory. The distinct demonstrative *sa* in the rule ought to point back to something distinctly stated above, and that is the

19. *yo 'yam akāro 'luptaḥ sa pūrvasyāi 'kārasyaū 'kārasya' vā 'rdhamātrasadṛçaṃ' kālam bhajata ity ekeshām ṛshinām matam*: 'adhyardhamātraḥ syād ity arthaḥ. uktāny eva 'dāharaṇāni viçeshādarçanāt'. ardhena sadṛço 'rdhasadṛçaḥ': tam ardhasadṛçaṃ¹⁰.

iti tribhāshyaratne prātiçākhyavivarāṇa ¹¹

ekādaço 'dhyāyaḥ. ¹²

¹ W. B. O. *aplutaḥ*. ² G. M. *ekāraokārapūrvasya*. ³ W. -*trasi sad-*; G. M. -*trāsad-*. ⁴ G. M. *labhata*. ⁵ O. *acāryāyām*. ⁶ O. om. ⁷ W. O. -*trasyām*; B. G. M. -*tra syād*. ⁸ W. B. -*shadar-*; G. M. *darçanāt*. ⁹ G. M. *yaḥ*. ¹⁰ O. om. ¹¹ O. in *prathamapragne*. ¹² G. M. add *çriçhādyā namaḥ*.

akāra which in rule 1 is said to be dropped after certain “predecessors.” We have had no *akāra alupta* spoken of, but only cases of *alopa* of *akāra*. And it seems to be taught here, in accordance with the doctrines of all the other Prātiçākhyas (see note to Ath. Pr. iii.53), that some regard the *a* as (not elided, but) so absorbed into the preceding diphthong as to become assimilated to, or identified with, the latter half of that diphthong. We may with plausibility conjecture the rule to be a later addition to the original substance of the chapter.

CHAPTER XII.

CONTENTS: 1-8, elision and non-elision of initial *a* after final *e* or *o* in exceptional and special cases; 9-11, resulting accent.

अथ लोपः ॥ १ ॥

1. Now for cases of elision.

This is a general heading to the chapter (that is to say, to its first eight rules); which, as the commentator points out, has for its sphere of action the passages specified in rule 3 of the preceding chapter. This is a matter of course: the general rule (by xi.1) being elision, there can be need of an additional authority for elision only where that rule is contravened by another of opposing character, and of wider application than to specific cases only.

असि ॥ २ ॥

2. The *a* of *asi* is elided.

The examples given are *suparno* ¹*si garutmān* (iv.1.10⁵; 6.5²; v.1.10³; O. omits the last word) and *pratho* ¹*si prthivy asi* (iv.2.9¹; O. stops at ¹*si*). The elision is not infrequent in this word, usually occurring in the little prose phrases which are inserted among the verses in the sections concerned; I have noted eighteen other cases: but they are hardly worth detailed reference.

न गर्भः संनद्धो यमो भद्रः पूर्वः ॥ ३ ॥

1. *athe* ²*ty ayam adhi-kārah*: *akārasya lopa ucyata ity etad adhi-kṛtām veditavyam ita uttarām yad vakshyāmaḥ. dhātārā-tir* (xi.3) *ityādivishayo* ¹*yam adhyāyārambhaḥ*¹.

¹ G. M. *etadadh-*.

2. *asi* ²*ty asminn akāro lupyata ekārāukārapārvaḥ*¹. *yathā*²: *suparno*.....: *pratho*.....

¹ G. M. -*rso* ed. ² in B. only.

3. But not when *garbhah*, *saṁnaddhah*, *yamah*, or *bhadrāḥ* precedes.

The examples quoted by the commentator are *garbho asy osha-dhānām* (iv.2.3³), *saṁnaddho asi vīdayasva* (iv.6.6⁵), *asi yamo asy ādityah* (iv.6.7¹: G. M. O. omit the last word), and *tvam bhadro asi kratuh* (iv.3.13¹). There is another case of *asi* after *garbhah* at iv.1.4², which is then repeated at v.1.5², the *a* standing this time unelided by rule i.61.

As usual, the commentator thinks it necessary to account for the inclusion of the double *pada sam-naddhah*, instead of simply *naddhah*, in the rule. Some, he says, quote as counter-example *upanaddho 'surah* (iv.4.9); but its propriety is questionable, since the passage does not fall under xi.3, and moreover, there is no *asi* in it (O. has the good sense to pass without notice this most absurd suggestion); and the valid counter-example is to be sought in another *śākhā*. We have here an unusually clear example of the arbitrary way in which the plea *śākhāntare* is resorted to, in order to avoid the attribution of a slight inconsistency to the treatise-makers.

यवनहरः स्वरपरेषु ॥३॥

4. *A* is elided before *y*, *v*, *n*, and *h*, when these are followed by a vowel.

The examples given are *hiraṇyacrāgo 'yo asya pādāḥ* (iv.6.7⁴: O. omits *pādāḥ*), *vanaspate 'vā sṛjā rarāṇah* (iv.1.8³: O. omits *rarāṇah*), *vareṇyo 'nu prayānam* (iv.1.10⁴), and *jambhayanto 'hiṁ vṛkām* (i.7.8²: O. omits *vṛkām*). These are but specimens selected from among a considerable number of cases: namely, before *y*, two; before *v*, nineteen; before *o*, fourteen (all but three of them, cases of *anu*, the counter-exceptions to which form in part the subject of xi.5); before *h* (which, as the counter-exceptions noted in xi.4 show, includes also *ñh*), five; in all, forty. To show the necessity of the restriction "when these are followed by a vowel," are cited *śukraṁ te anyat* (iv.1.11²) and *agre ahnāñ hitaḥ* (iv.1.3⁴: O. omits *hitaḥ*).

There is a well-established difference of reading here in the rule itself: T. B. G. M. have *yavanaha svarapareshu*, only W. and O. adding *para* (which I have amended to *paraḥ*) after *ha*. So also,

3. *garbhah*.....¹ *evampūrvaḥ sāmīnidhyāl labdhe 'sī' 'ty as-min grahaṇe' 'kāro ' na' lupyate. garbho*.....: *saṁnaddho*.....: *'sam iti kim: upan*..... *iti kecid udāharanti: tac cint-yam: dhātārātir* (xi.3) *ityādyantaḥpātivābhāvād asiḥabdā-darṣanāc 'ca: mukhyaṁ tu' śākhāntare vijñeyam pratyudāhara-ṇam². asi*.....: *tvam*.....

¹ G. M. ins. *ity.* ² W. *tasmīn asi.* ³ B. O. om. ⁴ G. M. ins. *ekapūrva okra-pūrvo vā.* ⁵ B. om. ⁶ O. simply *udāharaṇam śākhāntare.* ⁷ W. *cā 'mukhyaṁ kīntu.*

where the rule is quoted under i.21, W. alone (there is no O. for that part of the work) introduces *para*; under xi.4 and 5, W. and B. alike have *yavanahaparatca* etc., but the testimony as to the rule is equivocal, since *para* might well have been added there by way of exposition instead of quotation. I have, as usual, followed W., although not without suspicion that the *para* is a gloss, introduced to help the otherwise blind and inaccurate phraseology of the rule—which latter, however, is not altogether discordant with the usage of the treatise elsewhere.

The exceptions under this rule, instead of being rehearsed after it, as is the general habit of the *Prātiçākhyā*, are given in rules 4 and 5 of the preceding chapter, and, in the latter rule, mingled with instances of a wholly different character. Here, then, a particular specification of cases already included under a general rule is regarded as insuring against inclusion in a more general statement of exceptions under that rule. I believe that the treatise offers no other example of this canon of interpretation.

उकारग्रपर उदात्तः ॥ ५ ॥

5. Before *j* and *gn*, *a* is elided if acute.

The examples are *ojo 'jāyathāh* (i.6.12⁴) and *gucih pāvaka vandyo 'gne* (i.3.14⁵); and the counter-examples, of *a* unaccented remaining unelided, are *nā tatṛshānō ajārah* (iv.6.1²) and *nidhi-pātir no agnīh* (i.4.44¹). There is, as the examples show, a real reason in the accent: *ājāyathāh* and *agne* are both words that are accented only at the beginning of a *pāda*, where (as remarked under xi.1) the elision of *a* is an almost universal rule. All the other cases of elision before *gn* (nine in number) are of the same kind; not, however, those before *j* (only two).

मोवचोदधानस्येपूर्वश्च ॥ ६ ॥

6. Before *gn*, also when preceded by *maḥ*, *vacah*, *dadhānah*, and *sthe*.

The *ca*, 'also,' of this rule, brings down simply *gn* from its predecessor, the intent being to point out the cases where the *a* of *agni* is elided even when unaccented. *Maḥ*, it is stated, is a part

4. 'yakāravakāranakārahakāraparo 'kāro' lupyate teshu yakā-rādishu svarapareshu satsu. hiraṇ-.....: vanas-.....: vareṇyo
.....: jambh-..... svaraparesho³ iti kim: gukraṁ-.....: agre
.....⁴

¹ G. M. ina. ekāraakārapūrva akārah. ² G. M. om. ³ O. -para. ⁴ G. M. add evam ddi.

5. jakāraparo¹ gnaparaç cā 'kāra' udātto lupyate. ojo-.....: gucih-..... udātta iti kim: na-.....: nidhi-.....

¹ G. M. jakāraç ca. ² O. puts after udātto.

of a word, so given for the sake of conciseness, and including the two cases *aṅgirasvad aḥe 'mo 'gnim* and *aṅgirasvad bharishyāmo 'gnim* (both iv.1.2²: O. omits *aṅgirasvad* in each). The other passages had in view by the rule are *vaco 'gnaye bharatā brhat* (iii.2.11¹: O. omits the last two words), *dadhāno 'gnir hotā* (iv.1.3⁴), and *sadhasthe 'gnim purishyam* (iv.1.3¹: O. omits *purishyam*). To prove the implication of *gn* only, is given *sadhasthe adhy uttarasmin* (iv.6.5³; 7.13⁴: v.7.7²: O. omits).

By xi.16, *vacah* does not as a general thing elide the following *a*; but there is no clashing between the two rules, as they have reference to different parts of the text.

अभ्यावर्तिन्नूपमपि दधाम्यद्यान्वदितिः शर्मन्नेर्निक्षामग्र-
यः प्रयोऽस्माकमस्मेधत्ताश्चाश्रुतिरश्यामामार्यमन्नस्म-
त्याशानस्मिन्यज्ञेऽस्ताव्यथमानानभिद्रोहमधायदोऽथोऽदु-
ग्धाश्चरिष्टाश्चरथाश्चर्चत्यन्तरस्यामन्नस्थानायाङ्गिरस्वदकरम्

॥ ७ ॥

7. The *a* is elided in *abhyāvartin*, *apūpam*, *api dadhāmi*, *adyā 'nu*, *adītiḥ çarma*, *agneḥ jīhvām*, *agnayaḥ paprayaḥ*, *asmākam*, *asne dhātta*, *açmā*, *açvā* wherever found, *açyāma*, *amā*, *aryaman*, *asmatpācān*, *asmin yajñe*, *astā*, *avyathamānā*, *abhidroham*, *adhāyi*, *adaḥ*, *atho*, *adugdhāḥ*, *arishṭāḥ*, *arathāḥ*, *aranti*, *antar asyām*, *atra stha*, *annāya*, *aṅgirasvat*, and *akaram*.

The commentator gives an example for each specification of the rule, with counter-examples for every case in which more than one *pada* is taken, as follows: *agne 'bhyāvartin* (iv.2.1²), and, as counter-example, *kāmena kṛto abhy ānad arkam* (i.1.14²: G. M. omit the last word, O. the last two); *bhadraçoce 'pūpam deva* (iv.2.2³: only W. has *deva*); *agne 'pi dadhāmy āsye* (iv.1.10²), and, as counter-example, *baddho opikaksha āsani* (i.7.8³: O. omits the last word); *anu no 'dyā 'numatiḥ* (iii.3.11³: iv.4.12⁵; 7.15⁵), and, as counter-example, *pra tat te adya çipivishṭa nāma* (ii.2.12⁵: O. ends with *adya*, and G. M. substitute another passage,

6. *gnapara iti cakāro jñāpayati: mah..... ity evampūrvō gnaparō 'nudātto 'py' 'akāralopo bhavati.* yathā²: aṅgi-----: ma ity 'atra padāikadeçagrahanam' saṅkshepārtham: aṅgir-----: vaco-----: dadhāno-----: sadhasthe----- 'anvādeçāḥ kimarthaḥ.³ sadh----- gnaparasyā 'kārasya⁴ 'nudāttārtho 'yam ārambhaḥ.*

(¹) in W. only. (²) G. M. O. *akāro lopyate*. (³) in W. only. (⁴) G. M. *apadagrahanam*. (⁵) G. M. *anvādeçena kim*; O. om., along with the following example. * in W. only.

namely *viçve adya marutah*, iv.7.12¹); *adhi bravitu no 'ditiḥ garma yachatu* (iv.6.6⁴; G. M. O. omit the first two words), and, as counter-example, *yathā no aditiḥ karati* (iii.4.11²; only O. has *karati* [reading it *karat*]; G. M. substitute a *jaṭā* reading, *aditir no no aditir aditir nah*, without anything to show whether it is put forward as the *jaṭā*-text of this passage, or of another, occurring at iv.6.9⁴, where the *samhitā* likewise reads *no aditiḥ*); *adhvaram no 'gner jihvām abhi grṇitam* (iv.1.8²; B. omits the last word, O. the last two, G. M. the last and first), and, as counter-example, *vratā dadante agneh* (iv.1.8²); *te no 'gnayah paprayah* (i.7.7²), and, as counter-example, *purishyāso agnayah prācanebhīḥ* (iv.2.4³; G. M. omit the last word); *naro 'smākam indra* (iv.6.6⁷; there are two other cases, at iii.2.8⁶ and iv.6.4³); *viçve 'sme dhatta* (i.4.44²), with the counter-example *dravinām vājo asme : vājasya mā* (iv.7.12¹; only B. has *mā*, and G. M. O. end at *asme*); *pari vṛndhi no 'gmā bhavatu nas tanāḥ* (iv.6.6⁴; G. M. end with 'gmā, and only O. has the last two words); for the phonetic complex *açvā*, however followed, *vṛshapānayo 'çvā rathebhīḥ* (iv.6.6²; O. omits after 'çvā), *pracetaso 'çvān* (iv.6.6⁵), and *bharanto 'çvāye 'va* (iv.1.10¹; O. omits this example), with two counter-examples, *cashālām ye açvayūpāya takshati* (iv.6.8²; O. alone has the last word, and it omits the first) and *kshatraṁ no açvo vanatām* (iv.6.9⁴; O. omits *vanatām*), to show that *açva* would not have answered the purpose instead of *açvā*; *vājayanto 'gyāma dyumnā* (i.3.14³; G. M. omit *dyumnā*); *punas te 'māi 'shām* (iv.7.14³); *ye te 'ryaman* (ii.3.14⁴); *te 'smatpācān* (iv.3.13⁴), with the counter-example *anyāṁ te asmat tapantu* (iv.6.1^{3,5}; v.4.4⁵; only O. has *tapantu*); *yah pitā te 'smin yajñe* (ii.6.12⁶), with the counter-example *te asmin javam ā 'dadhuḥ* (i.7.7²); *prasitīm drūṇāno 'stā*

7. *abhyācartin*..... *eteshv akāro lupyate ekārāukārapārvaḥ*¹.
yathā: *agne*.....: *ācartinn*² *iti kim: kāmēna*.....: *bhadra-*
goce.....: *agne*.....: *dadhāmī*³ *'ti kim: baddho*.....: *anu*.....:
anv iti kim: pra.....: *adhi*.....: *garma* *'ti kim: yathā*.....:
adhv.....: *jihvām* *iti kim: vratā*.....: *te*.....: *paprāya* *iti*
kim: purish.....: *naro*.....: *viçve*.....: *dhatte*⁴ *'ti kim: drav-*
.....: pari.....: ⁴ *açve* *'ty asya*⁵ *yatrayatra çrutis*⁶ *tatratatra*
lopaḥ: vṛsha.....: *çrutir* *iti kim: prace*.....: *bhar*.....: *dīr-*
ghagrahaṇēna ¹ *kim: cashālām*.....: *kshatraṁ*.....: *vājay-*
.....: punas.....: *ye*.....: *te*.....: *pācān* *iti kim: anyāṁ*.....:
yah.....: *yajña* *iti kim: te*.....: *prasitīm*.....: *mā*.....: *jane*
.....: droham *iti kim: brhas*.....: *upa*.....: *ye*.....: *ma-*
hyam.....: *çūra*.....: *pūrve*.....: *ye*.....: *gāya*.....: *abhi*
.....: asyām *iti kim: rukmo*.....: *ye*.....: *sthe* *'ti kim: tva-*
shtā.....: *rāyas*.....: *prthivyāḥ*.....: *aham*.....

¹ G. M. put before *lupyate*, and add *vā*. ² G. M. O. om. ³ W. *abhyā-*. ⁴ O. ins. *açvā çrutīḥ*. ⁵ G. M. O. om. ⁶ G. M. *çrāyate*. ⁷ G. M. ins. *iti*.

'*si* (i.2.14¹; O. omits *prasitim*); *mā suparno 'cyathamānā* (iv.2.9¹); *jane 'bhidroham manushyāh* (iii.4.11⁶; O. omits *manushyāh*), with a counter-example, *brhaspate abhiḥaster amuñcah* (iv.1.7⁴; only W. has *amuñcah*); *upa prā 'gāt sumanme 'dhāyī manma* (iv.6.8³; all but O. begin at *sum-*, and G. M. end with '*dhāyī*'); *ye 'do rocane divah* (iv.2.8³; O. omits *divah*); *mahyam agne 'tho sīda* (iv.1.9³; 2.1⁵); *gāra nonumo 'dugdhāh* (ii.4.14²); *pārve 'rishtāh syāma* (iv.7.14²; all the MSS. read *-shītā*); *ye pavayo 'rathāh* (i.6.12⁶; only G. M. have *ye*); *gāyatrino 'rcanty arkam* (i.6.12²⁻³; only G. M. have *arkam*); *abhi gāguco 'ntar asyām* (iv.1.9³; another case at iv.2.3³), with the counter-example *rukmo antar vi bhāti* (iv.1.10⁴⁻⁵ et al.); *ye 'tra stha purānāh* (iv.2.4¹), with the counter-example *tvastā no atra varivah* (i.4.44¹); *rāyas posho 'ndāya tvā* (i.7.9²; O. omits *tvā*); *prthivyāh sadhashe 'ngirasvat* (iv.1.6^{1,2} four times; other cases at iv.1.1^{3,4} three times); and *aham tebhyo 'karam namah* (iv.5.1²).

गार्हमानोजायमानोद्देतयोमन्यमानोवनस्पतिभ्यःपते-
स्त्रिधस्तपसःस्वधावोभामितोज्ञयत्रायोज्धर्योक्रतोपूर्वः

॥ ८ ॥

8. An *a* is elided when preceded by *gāhamānah*, *jāyamānah*, *hetayah*, *manyamānah*, *vanaspatibhyah*, *pate*, *sridhah*, *tapasah*, *svadhāvah*, *bhāmitah*, *agnayah*, *āyo*, *adhvaryo*, and *krato*.

The quoted passages are *gāhamāno 'dāyah* (iv.6.4²); *jāyamāno 'hnām ketuh* (ii.4.14¹); *hetayo 'nyam asmāt* (iv.5.10⁵); *manya-māno 'martyam* (i.4.46¹); *vanaspatibhyo 'dhi sambhrtām* (iv.6.1¹; O. omits the last word), with the counter-example *namah pitrbhyo abhi* (iii.2.8³); *annapate 'nnasya* (iv.2.3¹ and [by i.61] v.2.2¹); *niho ati sridho 'ty acittim* (iv.1.7³; O. omits the first two words); *tapaso 'dhi jātah* (iv.2.10⁴); *deva svadhāvo 'mrtasya dhāma* (iii.1.11⁶; O. omits the first word and the last), with the counter-example *anyā vo anyām avatu* (iv.2.6³; O. omits the last word); *bhāmito 'mītrasyā 'bhidāsatah* (i.6.12⁵; O. omits the last word); *yān agnayo 'nvatapyanta* (iii.2.8³; O. omits *yān*); *agne 'dabdhdāyo 'gītātano* (i.1.13³; O. omits *agne*); *adhvaryo 'ver apāsh* (vi.4.3⁴; O. ends at '*veh*'); and *ṣatakrato 'nu te dāyī* (ii.5.12⁵).

A special explanation is required for the passage in which *agnayah* occurs, since the following *pada* is *anu*, which might seem to

8. *gāhamānah*..... *ity evampūrvo* 'kāro lupyate. *yathā*:
gāh.....: *jāy*.....: *hetayo*.....: *many*.....: *vanas*.....:
vanaspati 'ti kim: *namah* : *anna*.....: *niho*.....: *tapaso*
.....: *deva*.....: *svadhe* 'ti kim: *anyā*.....: *bhāmito*.....:
yān... : *ukārasya vakāravikriyāyām vyañjanaparo nakāra* 'iti
yavanaha (xii.4) *nishedhābhāvad alope prāpte tadapavādo*

fall under xii.4.² Its inclusion here is necessary, because in *saṁhitā* the word becomes *anv*, so that its *n* is no longer "followed by a vowel," as required by that rule. The question might arise, whether rule i.51 would not, at any rate, cause *anv* to be implied along with *anu*; but the commentator does not raise it, and the course taken by the treatise is evidently the more reasonable and safer one.

The last three cases which the rule deals with are of a peculiar character, and quite different from all the rest falling under this chapter, being those in which a final *pragraha* or uncombinable vowel elides an initial *a*, either in the passages specified in xi.3 (like the last of the three) or elsewhere (like the other two). This the commentator points out, and declares that in every other instance the *a* remains after a *pragraha*. I have already noticed (under iv.6,7) what the usage of the text is after *pragrahas* in *o*: that, against the two cases here mentioned of *a* elided after a vocative in *o*, there are but two in which the *a* remains; but that after a final *o* containing the particle *u* we have twenty-one cases of *a* retained, and no case of its elision. The passages where *a* is retained after an *e* that is *pragraha*, I have omitted to note: but there is a considerable number of them, including many (e. g. i.4.30: ii.5.6³: vi.3.5³: vii.5.3²: the commentator cites a single one, *ime aṣṣinā saṁvatsarah*, v.6.4¹) where the retention is not otherwise authorized: so that inability to cause elision is unquestionably involved in the very character of a *pragraha* vowel, according to the view of the treatise, and needs not to be expressly stated. At this we have a right to be surprised, especially for two reasons: first, that it is thought necessary to teach (see x.24) that *pragrahas* are not liable in general to combination with the initial vowels that follow them; and secondly, that according to this treatise there is no combination of the initial *a* with the preceding *e* or *o*, but an actual loss of it, leaving the *e* or *o* unaffected (except sometimes as to accent). But the essential character of the *pragraha* vowels, the reason of their peculiar treatment, and the proper significance of the term by which they are called, are obscure points as yet in Hindu phonetics and nomenclature.

It remains to inquire how complete and accurate is the enumeration by the *Prāṭiśākhya* of the cases of elision or non-elision of *a* occurring in the *Tāittiriya Saṁhitā*. I have, in looking through the *Sanhitā*, carefully considered every case with reference to the rules of the treatise, and the result is that, apart from *ye aparīṣhu*

'yam, agne....: adhvaryo....: gatakrato....: atra yavanaha (xii.4) ityādināi 'va lope siddhe punar asya grahaṇam niyamārtham: āyo 'dhvaryo' krato ity etatpadatrayapūrvasyāi 'cā' 'kārasya' lopo na tv itarapragrahapūrvasye' 'ti: yathā: ime.....

¹ G. M. -vas te. ² G. M. O. om. ³ B. -rapara. ⁴ O. adh-. ⁵ B. om. ⁶ O. kāra. ⁷ B. itaratra pr-.

(i.4.33) already treated of under xi.3 (p. 244), I have found only two cases of *a* retained which are not accounted for: namely *ardho asthāt* (v.2.1⁵; R-V. x.1.1) and *so agnih* (v.2.3²; R-V. vii. 1.16); and both these I suspect to fall under i.61, I having failed to note the previous occurrence of the passages. Of cases explained by i.61 there is a considerable number; only, as was remarked under that rule (see p. 47), there are three among them to which, if the commentator's forced interpretation of its terms be admitted, it cannot be made to apply. Of cases of elision of *a* unaccounted for, I have found none. Of course, my examination of the *Sanhitā*, having been made by the help of a single *samhitā* manuscript, is not to be credited as absolutely accurate: yet I have a good deal of faith in the trustworthiness of its result.

तस्मिन्ननुदात्ते पूर्व उदात्तः स्वरितम् ॥ १ ॥

9. When the elided *a* is grave, the preceding diphthong, if acute, becomes circumflex.

All the *Prāticākhyas*, and the usage of the known Vedic texts, are in accord upon this point (see note to *Ath. Pr.* iii.55). To the particular circumflex hence resulting, the treatise gives later (xx.4) the name *abhinihata*; the others call it *abhinihita*. The examples given are *tē 'bruvan* (ii.5.1³ et al.) and *sē 'bravīt* (ii.1.2¹ et al.).

The representation of the tone of the elided *a* in the resulting accent of the eliding diphthong, of course, favors the view that regards it as absorbed into the latter, rather than elided.

उदात्ते चानुदात्त उदात्तम् ॥ १० ॥

10. When it is acute, the preceding diphthong, if grave, becomes acute.

This, also, is a universal usage. The commentator quotes two examples: *āva rundhatē 'satram vā'i* (vii.3.8¹; O. omits *ava*) and *ānnapatē 'nnasya* (iv.2.3¹ and v.2.2¹).

स्वरितश्च सर्वत्र स्वरितश्च सर्वत्र ॥ ११ ॥

11. As also, in every case, if circumflex.

The commentator explains *ca*, 'also,' as bringing down *udātte*,

9. *yam*¹ *adhikṛtyā* *'yam* *prabandha* *uktas* *tasminn*² *akāre* *'nu-*
dātte *lupte* *sati* *pūrva* *ekāra* *okāro* *vo* *'dāttah*³ *svaritam* *āpadyate*.
*yathā*⁴: *tē*: *sē*

¹ G. M. *ayam*. ² G. M. *asm-*. ³ G. M. put next after *pūrva*. ⁴ in B. only.

10. *tasminn*¹ *evā* *'kāra* *udātte*² *lupte* *sati*² *pūrva* *ekāra* *okāro* *vā*
'nudātta *udāttam* *āpadyate*. *yathā*⁴: *ava*: *anna*

¹ O. *asm-*. ² O. puts next after *eva*. ³ O. om. ⁴ in O. only.

'when the elided *a* is acute,' from the preceding rule, and *sarvatra*, 'in every case,' as signifying 'whether the circumflex be independent or enclitic.' His examples are *bheshajām gāvē 'śvāya* (i.8.6¹) and *ōjō 'jāyathāh* (i.6.12⁴), where the final syllables of *gāve* and *ōjah* have the enclitic circumflex by xiv.29, and *ātho 'kthyō 'thā 'tirātrāh* (vii.1.5⁴: G. M. O. omit the first word), where the final syllable of *ukthyāh* has the independent circumflex before the elision.

We might perhaps also fairly conclude that *sarvatra* implies an inclusion of the case treated of in rule 9, and virtually teaches that a final circumflex, eliding an initial grave, is still circumflex.

With this chapter ends the first *praçna*, or section, of the treatise. The division into *praçnas* is a purely external and formal one, and (as I gave notice would be the case, in the Introductory Note to the Atharva Prātiçākhyā) is made no account of in this edition. References made to the succeeding chapters by section and chapter will easily be found by adding twelve to the number of the chapter as given.

CHAPTER XIII.

CONTENTS: 1-3, loss of *m*, before semivowels and spirants; 4, its retention before *rājan* etc.; 5-15, details of the occurrence of *ṣ*, otherwise than as the result of *sandhi*; 16, interchange of *ḍ* and *ḷ*.

अथ मकारलोपः ॥ १ ॥

1. Now for the omission of *m*.

11. *udātta iti caçabdo jñāpayati: tasminn¹ akāra udātte² sati sarva³ ekāra okāro vā svarita udāttam āpadyate. bheshajām ----- ojo ----- sarvatre 'ti vacanān nityasvarito⁴ 'pi tathāi⁵ 'va tad vidhānam syāt: atho -----*

iti tribhāshyaratne prātiçākhyavivarane

dvādaço 'dhyāyāh.

'iti prathamāh praçnah.⁶

¹ O. *asm.*. ² G. M. ins. *lupte*; O. ins. *ca lupte*. ³ O. *sarvatra*; G. M. *sarvatra-ethita*. ⁴ O. *-ritasyā*. ⁵ O. om.; G. M. *prathamapraçnas samāptāh. hariḥ om*; *çubham astu om*; W. adds *1 hari hi om*, and, as prelude to the next section, *çriga-ṇçāya namaḥ. hariḥ om*; B. adds *hariḥ om*.

1. *athe 'ty ayam adhikārah: makāralopa¹ ucyata ity etad adhi-kṛtaṁ veditavyam² ita uttaram yaḍ vakshyāmaḥ³. makārasya lopo makāralopaḥ⁴.*

¹ O. *-rasya l.*. ² W. B. om. ³ B. om.

A general heading, of which, however, the force extends but a very little way (through rule 4). The subject is a supplement to that treated at v.27-31, where we are told what is done with *m* before a mute, or before any other semivowel than *r*.

रेफोष्मपरः ॥ २ ॥

2. A *m* is omitted, when followed by *r* or a spirant.

This omission of *m* is accompanied, according to xv.1-3, by the nasalization of the preceding vowel, or else the insertion of *anusvāra* after it. Respecting the relation of these alternative views to one another, see the note to ii.30. The definition of the *m* as lost or omitted accords best with the former view: it is sufficiently logical and consistent to say that the consonant is lost and the vowel nasalized; if, however, an *anusvāra*, as a separate vocal element, is to take the place of *m* after the vowel, the only acceptable form of statement must be that the *m* is directly converted into *anusvāra*. This form of statement is in fact adopted by the Rik (iv.5) and Vāj. (iv.1) Prāṭicākhyas, which acknowledge an *anusvāra*, while the other is rightly preferred by the Ath. Prāt. (ii.32, i.67), which holds the theory of the nasalized vowel: our own treatise, as was pointed out above (p. 68), trims between the two views.

The commentator's examples are *pratyushtaṁ rakshaḥ* (i.1.2¹ et al.), *sañcitam me brahma* (iv.1.10²: v.1.10²), *tañ shad ahāni* (v.5.2⁶), *sañsam id yvase vṛshan* (ii.6.11⁴: iv.4.4⁴: only G. M. have *vṛshan*), and *tvañ ha yad yaviṣṭhya* (ii.6.11¹). Counter-examples are given: to show that *m* before other letters is not dropped, *idaṁ vām āsye* (iii.3.11¹); to show that the dropped *m* must be a final, *tasmāt tāmra āpah* (vi.4.2⁴). The commentator, namely, has quietly introduced the limitation *padāntah*, 'when final,' into his explanation of the rule, without pointing out whence he derives it: it comes, in fact, only from the general scope of the treatise, which thus far, having the relation of *pada* and *samhitā* texts under treatment, has dealt almost exclusively with final and initial letters.

यवकारपरश्चिकेषामाचार्याणाम् ॥ ३ ॥

3. As also, according to some teachers, when followed by *y* or *v*.

2. *rephaparaḥ*¹ *co*² "shmaparaḥ *ca* *padānto*³ *makāro* *lupyate*. *yathā*: *praty*.....: *sañ*.....: *tañ*.....: *sañ*.....: *tvañ*.....
¹*evampara* *iti* *kim*: *idaṁ*.....: *padānta* *iti* *kim*: *tasmāt*.....
rephaḥ *co* "shmanāḥ⁴ *ca* 'rephoshmanāḥ: *te* *pare*⁵ *yasmāt* *sa* *tathoktaḥ*.

¹ W. *rephaḥ*. ² O. om. *ca*. ³ B. -*nte*. ⁴ G. M. om. ⁵ O. om. ⁶ G. M. O. -*md*.
⁷ B. G. M. O. *rephoshmanāḥ* *tāu* *parāu*.

The authorities here quoted are, as the commentator does not fail to point out, the same with those referred to above, in v.30, where we were taught that some teachers hold *m* not to be assimilated to a following *y* or *v*, any more than to *r*. The accepted teaching of the treatise, however, is (v.28-9) that *m* before *y*, *l*, and *v* becomes a nasal counterpart to those letters respectively: whence the present rule is pronounced unapproved. For the bearings of the discordant doctrine, see note to v.30.

The examples are *tvāñ yajñeshv idyah* (i.1.14⁴; 2.3.1²: O. omits *idyah*) and *tañ vā etañ yajamānah* (v.6.9²: O. omits the last word): the ordinary and approved reading would be *tvām*, *tañ*, and *etañ*—as all the MSS. in fact read, neglecting the illustration of the opinion set forth in the rule. A counter-example is given, *yam kāmāyeta* (i.6.10⁴ et al.).

न सश्मामिति रापरः ॥ ३ ॥

4. But not the *m* of *sam* and *sām*, when followed by *rā*.

This is a precept applying only to the two words *samrāj* and *sāmrajya*, and in the other Prātiśākhya (see note to Ath. Pr. ii.36) these words or the root *rāj* are particularly specified; since, however, the syllable *rā* does not chance to occur in the Tāittiriya Saṁhitā except in these words after *sam* or *sām*, there is no inaccuracy in the more general statement as here made. The examples of the occurrence of the words in question selected by the commentator as illustrations are *pru samrājam* (i.6.12³) and *sāmrajyāya sukratuh* (i.8.16¹: O. omits *sukratuh*). As counter-examples, we have *ṣaṇ rājann ośadhībhyah* (iii.2.3¹) to show that no other words

3. *yakāraparo¹ vakāraparo vā makāro lupyata ity ekeshām² matam: ya evā³ sya pañcamādhyāye⁴ savarṇāpattim⁵ pratishedhayanti⁶ teshām evāi⁷ sha lopavidhir iti tām anvādicati cakārah siṅhāvalokanena⁸. yathā: tvām.....: tañ.....: evampara iti kim: yām..... yakāraḥ ca vakāraḥ ca yavakārāu: tāu parāu yasmāt sa tathoktāh.*

¹ *etat sūtram anishṭam.*⁷

¹ G. M. ins. ed. ² G. M. O. ins. *dcāryānām*. ³ B. G. M. *-mānuvāke*. ⁴ B. *savarṇam agre vartinah*; G. M. *-papatip*. ⁵ W. B. *-dhanti*. ⁶ O. *-kāṁnyāyena*. ⁷ G. M. O. *nāi 'tat sūtram iṣṭam*.

4. *'re 'ty' evamparaḥ¹ samsām ity etayor grahaṇayor² makāro na lupyate. yathā³: pra.....: sām.....: sām sām iti kim: ṣaṇ.....: rāpara iti kim: sañrarāṇah. padāntaḥ ca vy-añjanaparaḥ prākṛta (xiv.28) iti⁴ vakshyamānam⁵ dvitva-nishedham itiḥabdo⁶ nivārayati: tasmād atra dvitvasiddhiḥ.*⁷

¹ the MSS., as usual in such a case, *rā ity*. ² G. M. put at beginning; O. om. *grahaṇayor*. ³ in G. M. only. ⁴ O. om. ⁵ G. M. *-ṣa*. ⁶ G. M. *-tuḥ*. ⁷ G. M. add *itiḥabdas sām sām ity anayor eve 'ti samarthayati*.

retain an unchanged *m* before *rā*, and *sañrarāṇaḥ* (i.4.44¹) to show that only *rā*, not *ra*, effects the retention.

According to W. B. O., the particle *iti* in the rule is intended to deny the application to the word here had in view of rule xiv.28, respecting duplication, and to assure the duplication of the *m* before the *r*. But G. M. insert *tu*, 'but,' in the rule after *iti*, ascribing to it the effect just defined, and making the *iti* simply signify that the words mentioned, and no others, are the subjects of the rule. And G. (not M.) writes the examples accordingly, *samnrājam* and *samnrājyāya*. That this bit of constructive interpretation is a pure figment of the commentators does not need to be pointed out; respecting its occasion and bearing, see the note to xiv.28. I have adopted the reading of W. etc., which is presumably the older and more genuine: in the comment on xiv.28, even G. M. agree with the others in making *iti* the bond of connection between the two rules.

अथ वर्णानाम् ॥ ५ ॥

5. Now of individual sounds.

According to the comment on rule xxiv.2 (see the note to that rule), we have here one of the main division lines of the treatise. Thus far, from the beginning of the fifth chapter, we have had to do chiefly with the combination of separate words or *padas* into connected text; now we turn to the determination of individual letters, which are read alike in both forms of text. That the intention of the treatise-makers recognized so grand a transition here may be doubted; but that the change is one of some importance is not questionable.

ऋकार्कार्षपूर्वो नकारो णकारश्च समानपदे ॥ ६ ॥

6. Within the same word, a *n* preceded by *r*, *ṛ*, *r*, or *sh*, becomes *ṇ*.

5. *athe 'ty ayam adhiḥkārah: varṇānām saṁhitā vakshyate' ity etad adhiḥkṛtaṁ vedīṭavyam: 'atha vā:² athaḥabdash³ padasaṁhitānishedhakah.⁴*

¹ O. *ucyate*. ² G. M. *om*. ³ B. *ḥabdash*. ⁴ B. *-tāyām nish-*.

6. *saṁānapada ekopada ṛkāṛarkāṛarephashakārapūrvō¹ nakāro nakāram² āpadyate³. tribhīr-----: tvañ-----: esha-----: kṛshṇo-----: 'evampūrva iti kim: devānām-----⁴ samānapada iti kim: ebhīr----- samānam ca tat padam ca samānapadam: tasmin.*

O. has a *lacuna*, beginning with *-napade* at the end of the rule, and ending with *tribhīr ṛ-* in the first example. ¹ G. M. *ṛkāṛareph-*. ² G. M. *ṇakam*. ³ B. G. M. *āpnoti*. ⁴ O. *om*.

Already, in a previous chapter (vii.1-12,15,16), we have had detailed all the cases in which a *n* is changed to *ṇ* in the course of the combination of words into phrases, in the conversion of *pada* into *saṃhitā*; now, the treatise sets out to account for every single *n* occurring in the whole text. And the present is the leading general rule, involving, with the extensions and restrictions imposed later, by far the greater number of cases.

The commentator's examples are *tribhīr ṛṇavā jāyate* (vi.3.10⁵: O. has a *lacuna*, involving the beginning of this citation), *tvāñ hotṛnām* (iv.3.13⁴), *esha vā rco varṇah* (vi.1.3¹: but W. has instead *esha vā ahno varṇah*, vi.1.3¹⁻²), and *kṛshno 'si* (i.1.11¹); his counter-examples are *devānām vā antām jagmushām* (vii.5.8¹: but G. M. have only *devānām*, which of course is found in various places; and O. omits altogether), where none of the lingual letters specified comes before a *n*, and *ebhīr no arkāih* (iv.4.4⁷: O. omits *arkāih*), where the *r* is in another word than the *n*. All these are cases in which the alterant letter immediately precedes the altered.

व्यवेतो ऽपि ॥ ७ ॥

7. Even though other sounds are interposed.

Rule 15, below, puts a restriction upon this, pointing out what letters may not intervene between the affecting and the affected letter. The examples are *aparaguerknam dahati* (v.1.10¹: W. B. omit *dahati*; O. inserts *ha* between the other two words), *ātman evā 'ramanām kurute* (vi.5.11⁴: only O. has the first two words, and it omits the last), *adhishavanam* (i.1.5²: but G. M. O. have *adhishavane*, iv.7.8 or vi.2.11⁴), and *kṛshamāṇah pratishthākāmah* (iii.4.3³).

हिरण्मयम् ॥ ८ ॥

8. Also in *hiraṇmayam*.

The only passage in which the word occurs is quoted by the commentator: *hiraṇmayam dāma dakṣiṇā* (ii.4.13: O. omits *dakṣiṇā*). The intent of the rule is to establish in advance a counter-exception to the exception "not when followed by a mute," made in rule 15, below.

7. *uktanimittapārvo nakāro 'nyena* ¹ *'vyaveto* ² *'pi* ³ *'vyavahito* ⁴ *'pi* *ṇatvam āpnoti. yathā:* *ap-----: ātmann-----: adhi-----: kṛsh-----*

¹ G. M. ins. *varṇena*. ² W. O. om. ³ G. M. om. ⁴ in O. only.

8. *hiraṇmayam ity asmin grahaṇe nakāro 'ṇatvam āpnoti'. yathā:* *hiraṇ----- spargapara* (xiii.15) *iti² vakshyamāna-pratishedhasya⁴ pratiprasavārtham idam sūtram.*

¹ G. M. *nakāram āpadyate*. ² in B. only. ³ O. om. ⁴ O. *-nasya pr-*.

पाणिगणपुण्यकण्वाणगाणवाणवेणुगुणमणिप्रवादेषु पूर्वः ॥ १ ॥

9. Also, in the inflectional and derivative forms of *pāṇi*, *gaṇa*, *punya*, *kaṇva*, *kāṇa*, *gāṇa*, *bāṇa*, *veṇu*, *guṇa*, and *maṇi*, the first nasal is *ṇ*.

The word *pravāda* is not found elsewhere in our treatise or its commentary. From the latter's explanation and use of it we derive for it a meaning somewhat different from that which, according to Regnier (note to Rik Pr. ii.39), it bears in the Rik *Prāticākhya*. The latter makes it mean 'theme;' in our comment, on the other hand, it evidently signifies a derived form of a theme, in any gender or case, in composition, or in extension by secondary suffix; and I have translated it accordingly. So far as I can see, however, the same signification belongs to it in most of the passages of the Rik Pr. also, and Regnier's exposition of its use calls for revision.

There is an abrupt change of implication here, without any intimation of it in the terms of the precept itself; it is only at the end of rule 14, below, that we find the word *prākṛtāḥ*, which we must understand as applying to rules 9-14—a kind of footing instead of heading (*adhikāra*): see another like case in the third chapter, rules 2-7 (note on iii.2). In this connected paragraph of rules we have an enumeration of the words in which a *ṇ* is "original," and hence found equally in all the forms of the text.

The examples are *supāṇiḥ svaṅguriḥ* (iii.1.11⁴: iv.1.6³: O., in this and the two following examples, has only the first word), *vṛṣhapānayo 'gṛāḥ* (iv.6.6³), and *hiraṇyapāṇim ūtaye* (i.4.25: ii.2.12²): the text contains half a dozen other examples of the *pravāda*s of *pāṇi*;—*gaṇānāṁ tvā gaṇapatiḥ havāmahe* (ii.3.14³: O. omits the last word), *gaṇā me mā vi tṛṣṇan* (iii.1.8²), *gaṇena gaṇam* (v.4.7⁷), and *dāreḍmitraḥ ca gaṇaḥ* (iv.6.5⁶): the cases,

9. *pāṇi* 'tyādiḥ *abdhānām* ¹ *pravādeshu pārvaḥ prathamō nakāraḥ prakṛtyāi* ² *'va veditavyaḥ. prakarṣheṇa vādah* ³ *pravādah* ⁴: *līṅga-vibhaktibhedasamāsasataddhitādibhir* ⁵ *nirdeṣa* ⁶ *'ity arthaḥ. yathā*: *sup*-----: *vṛṣhap*-----: *hiraṇ*-----: *gaṇānāṁ*-----: *gaṇā*-----: *gaṇena*-----: *dāre*-----: *punya*-----: *sā*-----: *kaṇvā*-----: *tasyāi*-----: *akarṇayā*-----: *gāṇap*-----: *viṣalyo*-----: *veṇur*-----: *veṇunā*-----: *yad*-----: *yathā*-----: *maṇinā*-----: *'nanu gaṇaḥ abdhānāṁ pravādatvād gāṇagrahaṇam ayuktam*: *'māi 'vam*: *'ganapṛavādatve sati tad bhavet*: *kiṁtu gaṇapatiḥ abdhānāṁ pravādo 'yam. pārva iti kim*: *gaṇ*-----: *veṇ*-----: *maṇ*-----: *'ityādiḥ* ⁷ *'ttarasya* ⁸ *'natvam mā bhād iti.*

¹ G. M. -*adhināṁ grahaṇānām*. ² W. -*daḥ*. ³ W. -*vādah*; G. M. om. ⁴ W. om. *bheda*. ⁵ W. *nirdeṣitā*. ⁶ G. M. om. ⁷ G. M. om. ⁸ W. *icam*. ⁹ G. M. O. -*ra-nakārasya*.

compounds, and derivatives of *gana* are found by dozens in the *Sanhitā*;—*punyo bhavati vasantam* (i.6.11⁴: O. omits the last word) and *sā mā sarvān punyān* (vii.1.7¹): *punya* occurs in five other passages, once (iii.3.8⁵) in composition;—*kaṇvā abhi prā gāyata* (iv.3.13⁷: O. ends with *abhi*): there are two other cases of declensional forms;—*tasyāi kāno yā datah* (ii.5.1⁷: O. alone has the last word, and it omits the first; G. M. end with *kānaḥ*) and *akarnayā 'kānayā 'ḥlonayā* (vi.1.6⁷: only W. has the last word): there is no other case;—*gānapatyān mayobhūr e 'hi* (iv.1.2²: O. has only the first word; only G. M. have the last two): I have noted but one other case;—*viśalyo bānavān uta* (iv.5.1⁴: O. omits the first word): we have a declensional case of *bāna* at iv.6.4⁵;—*venur vāinavi bhavati* (v.1.1⁴: O. omits the last word), *venunā vi mimate* (v.2.5²), and *yad venoh sushiram* (v.1.1⁴): there are a couple more of cases;—*yathā guṇe guṇam* (vii.2.4²): we have elsewhere only *dviguna*, at v.2.5^{2,3}; and *maninā rāpāni* (vii.3.14): elsewhere only *manivāla*, at v.6.13. To explain the limitation *pūrvah*, 'the first nasal,' in the rule, the commentator quotes parts of passages already given—namely *gānānām tvā*, *venunā vi*, and *maninā rāpāni* (but O. omits the second example, and the second word of the third)—in which the *pravādas* exhibit a second nasal which is dental. He raises the objection, moreover, that the mention of *gāna* in the rule is unnecessary, since the word is a *pravāda* of *gāna*; but replies that the word (*gānapatya*) aimed at is a *pravāda* of *ganapati*, not of *gāna*. It is true, now, that *gānapatyāt* stands one degree farther removed from *gāna* than does, for instance, *ganapatibhyah*, or than would *gānikah* if it occurred in the text; yet we should hardly have expected it on that account to receive a different treatment.

पणिपणिंवीयमाणः ॥ १० ॥

10. Also in *paṇi*, *paṇim*, *viyamānaḥ*, and *ānyoh*.

The passages are *agne deva paṇibhir viyamānaḥ* (i.1.13²: only G. M. have the last word), *paṇim goṣhu starāmahe* (ii.6.11²: O. omits the last word), *viyamānaḥ : taṁ ta etum* (i.1.13²: O. has only the first word; G. M. read *-nas tam* etc., neglecting the pause of division between the two words), and *ānyoh kavikratum* (i.2.6¹). These words are said to be made a separate rule of because there is no longer any inclusion of *pravādas* or derived forms.

द्वर्गपरः ॥ ११ ॥

11. Also before a lingual mute.

10. ¹ *paṇi 'tyādigrahaneshu' nakārah prakṛtyāi 'va veditavyah. apravādārtho 'yam ārambhah. agne-----: paṇim-----: vīy-----: ānyoh-----.*

¹ O. prefixes the whole series of words. ² O. -*ādishu*; G. M. -*ādishu gr.*

The examples are *ṣitikanthāya ca* (iv.5.5¹: but G. M. have instead *ṣitikanthāya svāhā*, which I do not find in the text, not even at vii.3.17, where a number of similar expressions are read) and *kandūyeta pāmanambhāvukāh* (vi.1.3⁸: O. has the first word only). The combinations *nt* and *ndh* do not occur in the Sanhitā.

चङ्कुणफणत्स्थूणीहिणुयाद्विणोतिकौणयोऽणिष्ठाउल्ब-
णमुगणाश्रुतिश्रुपुणीकावाणिजायाणवश्चाट्णारस्थाणुतू-
णवेवोणायामशोणयापणेतवाणीःकल्याणीकुणपंवाणः-
शतशोणाश्रुतिर्धाणिकामेणी ॥ १२ ॥

12. Also in *caṅkuna*, *phaṇat*, *sthānāu*, *hiṇuyāt*, *hiṇoti*, *kāu-neyah*, *anishthāh*, *ulbanam*, *uganā* wherever found, *cupuṇikā*, *bāñjāya*, *anavaḥ ca*, *ātnārah*, *sthānum*, *tūnave*, *vināyām*, *aḥlo-ṇayā*, *paṇeta*, *vāṇih*, *kalyāṇī*, *kuṇapam*, *vāṇah ṣata*, *ṣoṇā* wherever found, *dhāṇikā*, and *m eṇi*.

The passages aimed at are quoted by the commentator as follows: *avabhṛtha nicaṅkuna niceruh* (i.4.45²: all but O. omit *niceruh*, which would allow the passage to be found also at vi.6.3⁴; O. omits *avabhṛtha*): *nicaṅkuna* occurs a second time in i.4.45²; *anvāpanīphanat* (i.7.8³); *āyāsthānāv uditāu* (i.8.12³); *bhrātrīyāya pra hiṇuyāt* (ii.2.6⁵: O. begins with *pra*); *evā'smāi pra hiṇoti* (ii.2.6⁵); *rajanō vāi kāuṇeyah* (ii.3.8¹); *ye 'nishthās tān* (ii.5.5²); *yojñā ulbanam kriyate* (iii.4.3⁷), and also, by i.53, *anulba-nam* (at iii.4.3⁶); *āvyādhinir uganā uta* (iv.1.10²: the example is wanting in W.) and *uganābhyas trñhatibhyah* (iv.5.4¹: O. omits the last word); *varshayanti cupuṇikā nāmā 'si* (iv.4.5¹: only W. has the first word, and it omits the last); *mantrine bāñjāya kakshānām pataye* (iv.5.2²: B. G. M. omit the first word, G.

11. 'tavarge pare' nakārah² prakṛtyāi 'va veditavyah. ṣiti-
-----: kand-----: tavargah paro yasmāt sa tathoktah.

(1) B. G. M. -rgaparah; O. -rgaparo vā. (2) G. M. put after 'va.

12. caṅkuna----- eshu nakārah prakṛtyāi 'va veditavyah.
avabh-----: anv-----: aya-----: bhrāt-----: evā-----: ra-
jano-----: ye-----: yajña-----: yatrāyatra ṣrutir uganāgraha-
nasya' tatrātatra natvam karanīyam: 'āvyā-----: ugan-----:
varsh-----: mantrine-----: priy-----: ce 'ti kim: anavaḥ
-----: etaṁ-----: ya-----: yā-----: aḥloṇayā-----: paṇe-----:
indram-----: kalyāṇī-----: purushak-----: vāṇah-----: ṣate
'ti kim: 'rtāv-----: ṣoṇā-----: 'ṣrutir iti kim: ṣoṇāya-----:
ni-----: vanas-----: makāreṇa kim: ubhay-----

¹ G. M. O. put before *yatra*. (2) W. om. (3) O. om. (4) O. om.

M. the last, W. O. the last two); *priyāṅgavaś ca me 'navas ca me* (iv.7.4²: G. M. omit the first word, O. the first three), with a counter-example, *anavas te ratham* (i.6.12⁰), to prove the need of *ca* in the citation; *etañ vāi para ātūrah* (v.6.5²); *ya sthānuḥ hanti* (vii.3.1¹): we have *yajñasthānu* twice at vi.1.2⁴; *yā tānave yā vīndyām* (vi.1.4¹); *aglonayā 'saptacaphayā kṛināti* (vi.1.6⁷: only O. has *kṛināti*); *panetā 'goargham* (vi.1.10¹); *indram vānir anūshata* (i.6.12²); *kalyānī rūpasamṛddhā sā syāt* (vii.1.6⁶: only O. has the last two words): *kalyānī* occurs in one or two other passages: *purushakunapam aṅvakunapam gāuh* (vii.2.10²: only O. has *gāuh*): we have *kunapam* as independent word at vii.2.10²; *vānah śatatantur bhavati* (vii.5.9²), with a counter-example, to show the necessity of adding *śata* in the rule, *ṛtāvānaś caya-mānā ṛnāni* (ii.1.11⁵: only G. M. have *ṛnāni*; O. omits the example: *vānah* is a *pada* in the word as divided, *ṛta-vānah*); *ṣoṇā dhr̥shnū nṛcāhasā* (vii.4.20: W. B. end with *dhr̥shnū*) and *ṣoṇāya svāhā* (vii.3.18: O. omits the example, along with the specification of the point it illustrates), the only examples of *ṣoṇa* that the text contains; *nī jalguliti dhānikā* (vii.4.19³); and *vā-naspatinām enī* (v.5.15: O. reads *enya*), with a counter-example, to show that the word only occurs after a *m*, *ubhayata enī syāt tad āhuḥ* (vii.1.6⁵: G. M. O. end with *syāt*).

अवग्रहो वृषण्हीर्षण्ब्रह्मण्क्षण्चर्मण्चर्षण् ॥ १२ ॥

13. As final of the former member of a compound, *n* is found in *vṛshan*, *śirshan*, *brahman*, *akshan*, *carman*, and *carshan*.

The term *avagraha*, we are told, is here taken in the sense of *avagrahasṭha*. The same interpretation has been given before (under vi.9); and the whole use of *avagraha* in the treatise verges toward an equivalence with its derivative. Only T. O. change the *ṣ* of *śirshan* to *ch* after *n*; but, as this is in accordance with the teaching of the Prātiśākhya (v.34), I have adopted it.

The examples quoted by the commentator are *vāto apām vṛshan-vān* (ii.1.11¹: O. omits *vāto*), *śirshanvān medhyo bhavati* (vii.5.25¹), *brahmanvanto devā āsan* (vi.4.10¹: W. B. omit *āsan*), *akshanvate svāhā* (vii.5.12¹), and *carmanvate svāhā* (vii.5.12²): we have *vṛshan-* also at ii.5.8⁴: iv.1.2¹: vii.5.5¹; *śirshan-* at vii.5.12¹; and *brahman-* at v.7.8³ and vi.4.10¹ (a second time). As counter-examples, to show that the *n* occurs in these words only before a

13. *vṛshanṇ ityādigrahaneshv' avagraho nakārah prakṛtyāi' va veditavyah. vāto-----: śirsh-----: brahm-----: aksh-----: 'carm-----: 'carshaṇgrahanasya' śākhāntare 'vijñeyam udāharanam': mitrasya---- iti kecid udāharanti²: tan na sādhu: anto 'lopād (xiii.15) iti vakshyamānapratishedhapratiprasavārtham uktatvād eśhām grahaṇānām carshanādhṛta ity atra' nakārasya padāntatvābhāvāt. athavā: ṛkārarkārarashā' (xiii.6)*

pause of division, he gives (the whole subject is omitted in O.) *vrshann agne vigvāny ariya ā* (iv.4.4⁴), *tasmāt saptaçirshan* (v.1.7¹), *brahman vigam vi* (ii.3.3⁵: G. M. omit *vi*), *akshann amīdanta* (i.8.5²), and *paçānām carman* (vi.1.9²).

This disposes of all the *avagrahas* cited in the rule save *carshan*. No such *pada* as *carshan* is to be found in the Tāittiriya-Saṁhitā, nor, so far as has yet come to light, in any other Vedic text; nor does the word seem like one that could anywhere occur. One cannot help surmising that its presence in the rule may be by a blunder merely, it being, perhaps, an unintelligent repetition of *carman*. But, by whatever hap or mishap it found its way in, it is now an accepted part of the text, and has to be dealt with. And the commentator first creeps out of the difficulty through the hole to which he usually betakes himself in a like case, asserting that the passage aimed at is read in another text (*çākhā*). He then proceeds to state that "some quote as here referred to the passage *mitrasya carshanīdhṛtaḥ çravaḥ* (iii.4.11⁵ and iv.1.6³: O. omits *çravaḥ*): this is not good, since the words are quoted in the rule by way of antecedent exception to an exception [to rule 6] which is to be made farther on, by the words 'nor when final, nor by the omission of *a*' (rule 15); and in *carshanīdhṛtaḥ* the *n* is not final. Or: others are of opinion that the words in question are specified for the sake of removing any doubt which might arise as to whether the *n* in them were a product of alteration under rule 6 of this chapter; and, in this aspect, the citation of *mitrasya carshanīdhṛtaḥ* is to be approved." The logic of this final conclusion I entirely fail to see: for no question can possibly arise as to whether the *n* of *carshanīdhṛtaḥ* falls under rule 6; that it does so is palpable and undeniable.

As we should expect, considering the way in which the Prātiçākhyā treats the cases, these words are read with *n* in the *pada*-text also: namely *vrshan-vān*, *brahman-vantah*, and so on. The same is the case in the *pada*-texts of the Rik and the Atharvan (see Ath. Pr. iv.99).

ऋषषषषषषषषषष चति प्राकृताः ॥ १४ ॥

14. Also in *rññ*, *shññ*, *shñ*, *mñ*, and *rāvñ*—these are original.

The application of the term *prākṛtāḥ*, 'original,' in this rule is, as was pointed out above (under rule 9), to all the cases rehearsed in rules 9-14.

"*diprāpter atra nakāro vāikṛta iti çaḥkānirākaraṇārtham etāni grahaṇānī'ty anye manyante: tathā sati mitrasya carshanīdhṛta ity udāharaṇam ramanīyam. "avagraha" iti kim: vrshann tasmāt brahman akshann paçānām avagrahastho "vagraha iti lakshyate."*

¹ W. -*ye*; G. M. -*dishu gr.* ⁽²⁾ O. om. ⁽³⁾ B. om. ⁴ W. -*shan-*; ⁽⁵⁾ G. M. om.

⁶ W. -*haraṇām*. ⁷ G. M. om. ⁸ G. M. *çkārā*. ⁹ B. *anena*. ⁽¹⁰⁾ O. om. ¹¹ W. -*ha-sthā*. ¹² G. M. put next before *lakshyate*.

The commentary, after pronouncing the citations of the rule "parts of words, intended to include a number of cases," quotes examples, as follows: *svayamātrannām upa* (v.2.8¹; 3.2¹, 7⁴; 5.4²: O. omits *upa*), *asamtrñne hi hanū* (vi.2.11²: O. omits *hanū*), and *svayamātrññā jyotiḥ* (v.7.6²): I have noted *ññ* elsewhere only in *anāchēññam* (v.1.7⁴): *abhishanno yasmāt* (ii.4.2²), *nishannāya svāhā* (vii.1.19¹: only G. M. have this example), and *daṣamāsā nishannā āsan* (vii.5.11², 2¹: O. omits the first word); *pūshno rañhyāi* (i.3.10²), *pūshnā sayujā saha* (iv.1.2² and v.1.2⁴: only G. M. have *saha*), and *pūshne prapathyāya svāhā* (vii.3.15: G. M. O. omit *svāhā*): I have noted further only *pūshña* (i.8.9² et al.); *aryamne caruṁ nir vapet* (ii.3.4¹ twice, ²: G. M. O. stop at *caruṁ*): I find besides *sutrāmne* (i.8.9² et al.) and *ñmna* (i.7.13²), which last, however, the rule was not specially intended for; finally, *dadhikrāvno akāriṣham* (i.5.11⁴ and vii.4.19⁴: O. omits *akāriṣham*) and *ā grāvnaḥ* (vi.3.2³: O. omits this example): further cases of *dadhikrāvan* and *grāvan* are met with in the text showing the combination *vn*; I have noted no other words in which it occurs. Counter-examples, showing that *vn* follows *rā* only, would have been easy to furnish: thus, *rāyasposhadāvne*, at i.2.10¹.

Cases of quite various and discordant nature are here thrown together. Most unequivocally calling for treatment in the Prātiçākhyā, in order to determine their reading, are the three passages in which *sanna* is altered to *shanna* after *abhi* and *ni*, since (as quoted by the commentator below) the *padu*-text restores the original form of the word, reading *abhishanna ity abhi-sannaḥ* etc. Its *s* is converted to *sh* according to vi.2, but there is no authority excepting here for the change of *nn* to *ññ*; chapter vii. does not deal with this, because it takes up only those cases in which the alterant cause and the altered nasal are found in different *padas*; and rule 6 of the present chapter does not apply to it because its first *n* is protected (according to xiii.15) by being "followed by a mute," and its second *n* by "having a lingual mute interposed." The case of *trñna* is akin with this, only with the important difference that the alteration of its nasals lies beyond the ken of the Prātiçākhyā, the *ññ* being read in every text. The remaining three all fall under rule 6 of this chapter, but they require specification because they are also covered by one of the exceptions in rule 16; for they exhibit, as compared with their

14. *atra' sātre padāikadeçā ete' bahupādānārtham uktāḥ: ṛññādishv eshu' ca' nakārāḥ prākṛtā eva vijñeyāḥ. svay-----: asam-----: svay-----: abhish-----: nish-----: daṣa-----: pūshno-----: pūshñā-----: pūshne-----: aryamne-----: dadhi-----: ā-----*

prākṛtaçabdo 'yam pānyādishv eva carshanparyanteshu mukhyāḥ: catasṛshu sañhitāsu natvasadbhāvāt': ṛññe' 'ty ādishu tu' na mukhyāḥ: kiñtu prāptyabhāve 'pi' natvaprapañārthaḥ. tathā hi: ṛññādāu pūrvaṇnakārasya¹⁰ sparçaparavān nishedhaḥ:

themes (*aryaman*, *-krāvan*, *grāvan*), a "loss of *a*" (*alopa*): compare what is said of this *alopa* below.

As regards the application of the term *prākṛta*, 'original,' their discordance is more essential, and, indeed, irreconcilable. In *ṛṇna*, to be sure, the cerebral *n*'s are as original as in the words specified by rule 13, since, in all alike, the alteration is an accomplished fact in all the forms of text, although ultimately referable to the cause laid down in rule 6. But the last three cases, although also read alike in all texts, are introduced here as counter-exceptions to rule 15, and their *n* is no more original than is that of any other of the words falling under rule 6. And finally, there is no sense whatever in which the lingual nasals of *-shaṇṇa* are "original." To call them all original, then, seems even more than a looseness or inaccuracy in the use of that term: it is a blunder.

The commentator perceives the difficulty, and attempts to remove it by a lengthy passage of special pleading. The term *prākṛta*, he says, is *mukhya*, 'of primary value' or 'of full force,' as applied to the words beginning with *pāni* (rule 9) and ending with *carshan* (rule 13), since in them the lingualized nasal is found in all the four *samhitās*; but in *ṛṇn* and the rest it is not *mukhya*, but is simply intended to authorize the nasalization even in the absence of a rule prescribing it. Thus, namely: in *ṛṇn* etc. (i. e. in *ṛṇn* and *shaṇṇ*), the first nasal constitutes an exception (under rule 6) as being followed by a mute (rule 15); the other nasal, as having a *ṣ*-mute between it and the altering cause (rule 15). In *shn* and *mṇ*, again [why not in *rāvn*?], the nasal falls under the exception touching the loss of *a* (rule 15). And if it be objected that the lingualization is assured by the competency of the citation—still [it is answered], the implication is avoided that the occasion of the citation is the originality of the *n* [?]. Moreover, the word *ca*, 'also,' in the rule, being used in the sense of subsidiary adjunction (*anvācaya*), shows the lingualization to be not of primary value; if it were primary, it would be found in all the four kinds of text; but it is not so found; for we read in *pada*-text *abhishanna ity abhi-sannah* and *nishannāye 'ti ni-sannāya*. And since, from the words *pūshan* and *aryaman*, which end in *n*, such forms as *pūshno rañhyāi* and *aryamne carum* are read in the *varṇa*-text, therefore the conversion into *n* (all but O. say "non-conversion into *n*") in

"*itarasyo 'ttamasya'*" *ṣavargīyavyavahitāt*¹²: *shṇamṇagraha-*
*nayos tv alopād iti nishedhah. grahanasāmarthyād eva*¹³ *natvaṃ*
*sidhyati 'ti cet: evaṃ svabhāvatvam eva grahanasyā 'pi'*¹⁴ *mūlam*
*iti parihārah. kim ca: anvācaye*¹⁵ *vartamānaḥ cakāro 'py eteshu*
*natvam amukhyam*¹⁶ *iti dyotayati: mukhyam*¹⁷ *cet: catasṛshu*
*samhitāsu vidyeta*¹⁸: *na cā 'tra vidyate: tathā hi: abhishanna*
*ity abhi-sannah: nishannāye 'ti ni-sannāya: ity atra*¹⁹
padasamhitāyām: pūshann aryamann iti nakārāntaṣabda-
yoh: pūshno rañhyāi: aryamne carum: ity ādi siddharā-
*patvād*²⁰ *atra varṇasamhitāyām etatsāhacaryād ekasūtrasthāyor*²¹

varna-text is to be inferred also for *run* and *shann* (O. says *rān*) in virtue of association with the others, they being found in the same rule with them; for all who understand the rules of affairs hold that the determination of equivocal classes is made by mention in connection with words unequivocal. Therefore the meaning of *prākṛta* (all but O. say *prakṛti*) as defined by us is alone acceptable.

By comparison with the explanations given above, it may readily be seen how much of reason there is in all this talk. The commentator raises an obscuring dust about the difficulty, but does not at all remove it. The *mukhyatvam* of the term *prākṛta* as here applied is more easily disproved than its *mārkatvam*.

न पुम्नो ऽग्निर्युष्मानीतो ऽतो ऽतोपात्स्पर्शपरो व्यवा-
येषु शसचटतवर्जयिषु ॥ १५ ॥

15. But not in *shumna*, *agni*, and *yushmānīta*; nor when final; nor after the omission of an *a*; nor when followed by a mute; nor when *ç*, *s*, or a palatal, lingual, or labial mute intervenes.

It would be rather more in accordance with the ordinary usage of the treatise to make five distinct rules of the five independent and unconnected specifications which are here crowded together into a single precept: in fact, we should be guilty of no great violence if we were to divide it into five, affixing to each its own (independently constructed, as if for an independent rule) portion of the comment. But in that case, at any rate, the first rule should read *na shumno'gnir yushmānītaḥ* (not '*gnir*'). It is not unobjectionable as it stands, since we should expect the first and third complete *padas* to be quoted as they stand in the text, and the second, which is only a fragment of a *pada*, to be distinguished as such from a possible *agnih*. As to the first, moreover, there is a difference of reading among the MSS. of the text: only T. W. have *shumno*; B. O. have *sumno*; G. M. have *sushumno*; and, as is seen below, even W. has *sumnaḥ* in the reiteration of the rule by the comment. G. M., it may be added, read *vyavāyishu* for *-yeshu* in the last specification.

apy²³ ṛṇaśaṇṇayor²⁴ varṇasamhitāyām natvabhāvo²⁴ manta-
vyah: prasiddhapadasamabhiṣyāhāreṇa²⁵ 'prasiddhapadārtha-
samarthanam²⁶ arthaçāstravidāḥ²⁷ sarve khalu svikurvate. tasmād
asmadukta eva yuktaḥ prākṛtaçabdārthaḥ²⁸.

¹ G. M. om.; O. *asmin*. ² O. om. ³ B. *eteshu*. ⁴ O. om. ⁽⁵⁾ in G. M. only. ⁶ G. M. *-sambhavāt*. ⁷ O. *ṛṇa* i. ⁸ G. M. put after *na*. ⁹ G. M. O. om. ¹⁰ O. *-nana-*
kāra. ⁽¹¹⁾ G. M. O. *utirasya*. ¹² W. B. *savarg*; G. M. *tavarg*-(?). ¹³ O. *evā*.
¹⁴ W. om. *api*. ¹⁵ G. M. *atra yo*. ¹⁶ B. G. M. *mukh*; O. *anumu*. ¹⁷ G. M. *-yaç*.
¹⁸ B. G. M. *vidyate*. ¹⁹ O. om. ²⁰ O. om. *rūpa*. ²¹ W. *-yo*; B. *-trayor*; G. M.
-trasthitayor. ²² W. om. ²³ O. *ṛṇaśaṇṇayor*. ²⁴ W. B. G. M. *-tvabh*; O. *eva*
yatasaḍbhā. ²⁵ W. G. M. *-ṇa*, but W. inserts a sign of omission before the follow-
ing *pr*. ²⁶ B. *-dārthan*; G. M. *-dārthan na bhavati*. ²⁷ B. *sarvaçā*; G. M. *niya-*
man çi. ²⁸ W. B. G. M. *prakṛtiç*.

Under the first part of the rule, the passages aimed at are quoted as follows: *sushumnah sūryaraçmih* (iii.4.7¹), *indrāgnibhyām tvā sayujā* (iv.4.5¹: G. M. omit *sayujā*; the *pada*-reading is doubtless *indrāgni-bhyām*, so that the *r* and *n* are *samānapade*, as required by rule 6), and *yushmānito abhayaṁ jyotiḥ* (ii.1.11⁶: only *ō* has *jyotiḥ*; from its inclusion here, the word must remain undivided in *pada*-text, though in that of the Rīg-Veda [ii.27.11] it is read *yushmā-nītaḥ*).

Examples of final *n* not lingualized are *pitṛn haviṣe attave* (ii.6.12¹) and *pra mṛñhi çatrān* (i.2.14²).

The precept touching the omission of an *a* has reference, so far as I can discover, only to the oblique cases of *vr̥trahan*, of which two (and I have failed to note any others) are cited, namely *vr̥traghna indrāya tvā* (i.4.1¹: *ō* omits the example) and *vr̥traghna stomāḥ* (iv.7.15¹)—for the derivative adjective *v̥ratraghna* (ii.5.2³ et al.) can hardly be aimed at; and yet, the authority of this rule is needed to establish the dental *n* in this word also, which would otherwise fall under rule xiii.6. The mode of definition of the cases here intended is in very remarkable contrast with the usage elsewhere of the treatise, which, as has been repeatedly pointed out, differs from the other Prāticākhyas especially in avoiding all reference to grammatical categories, forms, and derivations, and defining the words to which its rules relate simply by external circumstances of position and surroundings in the text. And this departure from its custom is a quite unfortunate and ill-judged one: for, in the first place, it renders necessary a part of the specifications of the preceding rule (namely *shn*, *mñ*, and *rāvñ*), which really lie outside the province of the treatise, and have no good reason to be mentioned; and, in the second place, as the commentator points out, it involves an inconsistency with the general subject of the chapter, which has to do with conversions arising *samānapade*, 'within the limits of the same *pada*,' while in *vr̥tra-ghnaḥ* etc. the affecting cause is in one *pada* and the nasal to be affected in another. The commentator explains that the intent is, by a far-reaching glance backward (literally, 'a lion's look'), to lay down a further example to a rule in the seventh chapter, where the restriction *samānapade* is not in force: *ghnaḥ* etc., namely, are altered forms of *han*, whose

15. *shumnah¹: agnih²: yushmānītaḥ: eteshu³ nakāro natvaṁ nā "padyate: sush-.....: indrā-.....: yushm-..... antaḥ⁴ padānto nakāro natvaṁ nā "padyate: pitṛn-.....: pra-..... alopād akāralopāt⁵ paro "pi nakāro natvaṁ nā "padyate: "vr̥tra-.....: vr̥tra-..... nanv atra nimittanimittinor bhinnapadasthateād vishamo dṛṣṭāntaḥ: satyam: sūhāvalokananyāyena⁶ prathamapraçne⁷ saptamādhyāye⁸ çeshodāharanarāpena⁹ ghatate: tatra ca samānapadanīyamo¹⁰ nā "sti: ghna ity asya hançabdavikṛtateād¹¹ "rashaḥpūrvo havanī¹² (vli.11) "ti prāptih. "sparçaparo nakāraç ca¹³ natvaṁ nā "pnoti¹⁴: samkr-.....: ava-.....*

nasal, by vii.11, is liable to lingualization. But *han*, by the usage of the treatise, signifies 'the syllable or audible complex of sounds *han*,' not 'the theme *han* and its derivatives;' and, as the text contains no example of the combination *ghn*, it would have been easy to exempt *n* from lingualization *ghakārāt*, 'after *gh*.'

The cited examples of *n* remaining unchanged when followed by a mute are *saṅkṛandano 'nimishah* (iv.6.4¹: O. has the first word only), *ava rundhe tārpyam* (ii.4.11⁶: O. omits the last word), and *nakhanirbhinnam* (i.8.9¹).

The commentator then proceeds to enter into a long discussion of more than usual subtlety and obscurity, of which I am by no means confident that I apprehend the meaning. The point aimed at, indeed, seems quite clear: by xiv.4, the *n* of such a word as *pārṇa* is to be doubled, making *pārṇna*; here, then, is a case where the first *n* is "followed by a mute" (*sparṣaparah*), and so would seem to have its lingual character forbidden by the present rule. The reasonable reply to so hair-splitting and impertinent an objection would appear to be that, a duplication being ordered by the treatise, the product can be nothing but *nn*, since *nn* would be no duplication at all. The commentator, however, prefers to get around the difficulty by limiting the word *sparṣa*, 'mute,' as here used, to one which is not the product of express prescription (?). For in *pārṇā paṣcāt* (iii.5.1¹ et al.) there is duplication, making *pārṇnā* (not one of the MSS. writes the duplication), the one *n* being prescribed by xiv.4, the other being its occasion or root (*mūla*). With this, O. prudently ends; the other MSS. go on to explain "express" (? *prasiddha*) by referring to the word *nakhanirbhinnam*, already quoted above, as, with its like, also exhibiting an instance of occasion of prescription. This word, namely, falls under rules xiv.4,5 (becoming thereby *nakhanirbbhinna*); and in rule 5 the term "succeeded by a consonant" (*vyāñjanottara*) is used in a different sense from "followed by a consonant" (*vyāñjanapara*); the meaning of which will be there explained at full length (as we shall find to our cost, in one of the obscurest discussions of the entire treatise). The appositeness of the whole reference I do not understand.

Finally, examples are quoted of the suspension of nasalization by

nakha..... *sparṣo 'trā'* ¹*prasiddhalakṣhaṇavishayo*¹⁸ *vivakshyate*¹⁹: *anyathā*²⁰ *pārṇā paṣcāt ity ādāu nateam na syāt: rephāt param ca* (xiv.4) *iti hi prasiddham*²¹ *lakṣhaṇam tanmūlam ca*²² *pārṇne 'ty atra dvitvam.* ²³*prasiddhapadena kim* ²⁴: *nakhanirbhinnam ity ādāv api katham cī'*²⁵ *lakṣhaṇamūlateam sambhavati. kim tal lakṣhaṇam iti cet: dvitīyacaturthayor* (xiv.5) *ity atra sūtroktavyāñjanottarayor*²⁶ (xiv.5) *iti vāco yuktyantaram iti brūmah: tasya lakṣhaṇam tatrāi 'ca sphuṭikarishyate*²⁷ *mahatā prabandhena*²⁸. *sparṣaḥ paro*²⁹ *yasmād asāu sparṣoparah.* ³⁰*śasacātavargīyeshu* ³¹*vyavadhāyikeshu*³²

an intervening *ç* or *s*, or a palatal, lingual, or dental mute: namely *raçanām ā datte* (vi.3.6³), *agne rasena tejasā* (i.4.46²: only G. M. have *tejasā*), *rocante rocanā divi* (vii.4.20: O. omits *rocante*), *somañ rājānam* (i.7.10¹ et al.), *prakrīdinaḥ payodhāḥ* (iv.3.13⁷), *pṛtanā jayāmi* (iii.5.3^{1,2}), and *janaprathanāya svāhā* (iii.2.8¹: only O. has *svāhā*; G. M. have the false reading *-pradhā*-, and O. has dropped out a part of the word, giving *jananāya*).

In the note to Ath. Pr. iii.94, I have pointed out the physical reason why these sounds, by their interposition, prevent the lingualization of the nasal: they are, all of them, such as call into action for their utterance the tip of the tongue, throwing it out of adjustment for the lingual contact. The tendency which the history of Aryan language in India exhibits toward the conversion of dentals into linguals shows itself most actively in the case of the nasal: the tongue, being rolled back into the position of lingual articulation by the utterance of *r*, *ṛ*, *ṛ*, or *sh*, hangs suspended there, as it were, and makes the next nasal contact lingual, unless the tendency is satisfied by the intermediate production of such a contact, or frustrated by the transfer elsewhere of the articulating organ.

The Prāticākhya's enumeration of the cases of occurrence of the lingual nasal is, so far as I have been able to determine, complete. No one of the other treatises undertakes such an enumeration.

पृत्तस्वरात्परो लो उं पौष्करसादेः पौष्करसादेः ॥१६॥

16. In the opinion of Pāuṣkarasādi, *l* after a mixed vowel becomes *ḍ*.

The mention of Pāuṣkarasādi (O. has everywhere Pāuṣkarasādi), the commentator says, is out of respect, and not because the rule is not a peremptory one. "Mixed vowel" is a term which is not elsewhere employed by the treatise, nor does the latter contain anything that should intimate an explanation of its meaning. The comment glosses it by 'the sound *r*.' it appears, then, that *r* is thus styled, from having its vocalic quality "mixed" with consonantal, namely, with the *r*-sound. The other Prāticākhyas (see

satsu nakāro natvañ nā "padyate: yathā²²: raçanām.....: agne.....: rocante.....: somañ.....: prakrī.....: pṛtanā.....: jana.....: ṛkārarkārā (xiii.5) "diprāpteḥ²³ pratishedho²⁴ 'yañ vihītaḥ.

¹ W. B. O. *sumnah*; G. M. *sushumnah*. ² W. O. *agni*. ³ O. *eshu*; G. M. *eshu grahaneshu*. ⁴ W. B. *tataḥ*. ⁵ W. B. O. om. ⁶ O. om. ⁷ G. M. *-kanena*. ⁸ O. om. ⁹ G. M. *-yāya*. ¹⁰ W. O. *viçesh-*. ¹¹ G. M. O. *-datvanī-*. ¹² G. M. *-bādādhikr-*. ¹³ G. M. *draṣṭaḥ pūrvo bhavati*. ¹⁴ G. M. ins. *sparcaparāḥ*. ¹⁵ G. M. om. ¹⁶ G. M. *"padyate*. ¹⁷ B. G. M. *tra*. ¹⁸ B. *-viçeshayor-*. ¹⁹ O. *vikshyate*; G. M. *pi vā vyjyate*. ²⁰ W. B. *yathā*; G. M. *athā 'pi*. ²¹ O. *-ddha*; W. *pratisiddha*. ²² W. *ce 'ti*; O. om. ²³ O. om. ²⁴ W. B. O. ins. *ca*. ²⁵ W. O. *etal*. ²⁶ B. *sūtravy-*; G. M. *sūtre vy-*. ²⁷ G. M. *spuṣṭik-*. ²⁸ W. *pūrvo*. ²⁹ G. M. ins. *vyavādgishu*. ³⁰ B. ins. *vyavādgishu*. ³¹ G. M. O. om. ³² in W. only. ³³ G. M. *-tiḥ*. ³⁴ W. O. *pratinīsh-*.

note to Ath. Pr. i.37) directly define it as so composed. The *l* liable to the change into *d* is called in the comment *duḥḥlishta*, 'ill joined;' i. e., I presume, 'of difficult articulation' (G. M., to be sure, seem to apply this title the first time to the *d* instead of *l*, and only O. attaches it the second time clearly to the *l*, the others' readings being corrupt; yet there can hardly arise a doubt as to its true connection); it is, of course, the lingual *l* which forms an acknowledged part of the alphabet of the Rig-Veda (Rik Pr. i.11-2, r. 52 etc.). But no such articulation belongs to the alphabet accepted by this treatise—although, on the strength of the present rule alone, it is crowded into that alphabet by the commentator under rule i.1. Nor does the edition of the Śaṅhitā, nor do the MSS., so far as known to me, make any use of a lingual *l*. As for the MSS. of the Prāticākhya and its comment on this rule, B. O. write the ordinary *l* throughout; W. alternates irregularly between the two; G. M. and T. have the lingual letter only. As regards the binding force of the rule, the commentator is right so far as this—that a *d*, not *l*, is read of necessity in the words to which it relates; but that this is, to the makers of the Prāticākhya, the result of alteration of an original *l* there is no reason to believe; the euphonic exchange of the two letters is not less strange to the Tāittirīya text than to the Vājasaneyi (of the Mādhyandina *śākhā*; see Vāj. Pr. iv.143, viii.45) and Atharvan; and the rule is really *pājartham* only, and an intrusion into our treatise of something foreign to its system.

The commentator first gives his own explanation and illustration of the precept. As example of the operation of the rule, he cites *mṛdāti* "dr̥ṣe (i.1.14³); and, as counter-example, to show that the change is made only after a "mixed vowel," he has nothing better to offer than an alleged passage "from another text," *nalām plavam*. For, in such words as *īditaḥ* (i.1.11¹), *pravodhum* (i.1.14³), *idāyāḥ* (i.2.5¹), *ayād* (i.4.45²), *hedah* (i.5.11³), *ṛāushad* (i.6.11¹), where the Rig-Veda reads regularly the lingual *l* and its aspirate, the Tāittirīya-Śaṅhitā maintains the *d*, not less firmly than after *ṛ*. This, the commentator goes on to say, is an interpretation (but the term he uses is *pāṭha*, properly 'reading' or 'ver-

16. *pr̥ktasvarād ṛkārāt paro² lakāro duḥḥlishtasamjñiko³ ḍakāram āpadyate: pāuṣkharasāder⁴ mate⁵. mṛdāti..... pr̥ktasvarād iti kim: nalām plavam⁶ iti⁷ śākhāntare. pāuṣkharasāder⁸ grahaṇam pājartham⁹ 'na tu vikalpārtham'. mār̥dhasthānatayā duḥḥlishtaladakārayoh¹⁰ sādṛṣyam¹¹ asti 'ti vyākaraṇānusāri¹² sūtrapātho 'yam: katham anusāritvam iti cet: 'tathā hi¹³: sthāne 'ntaratamaḥ: sthāne prāpyamānānām¹⁴ antaratama¹⁵ ādeḥ bhavati 'ti.*

sūtrasya¹⁶ pāthāntarom apī¹⁷ vyākhyāyate: pr̥ktasvarāt paro lo ḍam¹⁸ pāuṣkharasādeḥ¹⁹: atra samānapada²⁰ ity asyā 'nūvartanam vijñeyam: pāuṣkharasādeḥ śākhinaḥ²¹ samānapade pr̥kta-

CHAPTER XIV.

CONTENTS: 1-7, duplication of one of the members of a group of consonants; 8, duplication of *ch*, *kā*, and *bh*, in certain cases; 9-11, insertion between a surd spirant and mute; 12-13, aspiration of a surd mute before a spirant; 14-28, exceptions to the rules for duplication, and discordant views of certain authorities respecting them; 29-33, occurrence of the enclitic circumflex.

स्वरपूर्व व्यञ्जनं द्विवर्णं व्यञ्जनपरम् ॥ १ ॥

1. A consonant preceded by a vowel is doubled, if followed by a consonant.

The intricate and obscure subject of duplication in consonant-groups is treated at more length in this than in the other Prātiçākhyas (compare R. Pr. vi.1-3; V. Pr. iv.97-114; A. Pr. iii.26-32; also Pāṇini viii.4.46-52), but chiefly on account of the liberal citation here made of the discordant views of various teachers respecting it. The doctrines of the treatise itself are mainly in accordance with those of the rest. This first and leading principle, that the first consonant of a group is doubled, is stated in equivalent terms by all. The principal restrictions to its application are, as stated below, that *r*, *h*, *z*, *φ* (rule 15), and a letter doubled, or a mute followed by another of the same series (rule 23), are exempted from duplication. For the details, see the following rules.

Of course, in applying the rules for duplication, we have to assume the form of the consonant-groups as determined by the other precepts of the Prātiçākhyas—treating *visarjaniya*, for example, as is prescribed in the ninth chapter, and making the insertions pointed out in the fifth (v.32,33 etc.). And further, to finish the matter, the rules for *yama*, *nāsikya*, and *svarabhakti* (xxi.12-16) must be duly taken into account.

In an additional note to the Atharva Prātiçākhyas, I gave a complete list of the consonant-groups of the Atharva-Saṁhitā, with the forms which they come finally to assume under the laws of combination. It has been necessary to prepare a similar one for the Tāittirīya-Saṁhitā, in testing the reach and bearing of the rules of the present treatise: but the scheme is hardly worth giving in full.

1. *svarapūrvam vyañjanam¹ vyañjanaparam² dvicarnam āpad-yate. yathā: uru..... evampūrva iti kim; tat..... evampara iti kim: uru..... vyañjanam iti kim: pra..... svarah pārvo yasmāt⁴ tat³ svarapūrvam: vyañjanam asmāt param iti vyañjanaparam: devayor varṇayoh samāhāro dvicarnam.*^{*}

¹ G. M. put next before *dvicarnam*. ² O. *param*. ³ G. M. om. ⁴ W. ins. *asau*. ^{*} B. om. ^{*} O. adds *svarapūrvam iti kiñ; prajananañ: padbhyāñ..... vyañjanaparam iti kiñ: ugañd uta: vyañjana iti kiñ: prañjanāñ.*

The commentator offers a single example, *uru prathasva*, i. e. *uru pprathasva* (i.1.8 et al.: the MSS. of the comment only very rarely and irregularly write the groups in their duplicated form, so as to illustrate the rules of the chapter), and adds counter-examples: first, to show that the consonant is liable to duplication only after a vowel, *tat pravāte* (vi.4.7²: hardly a well-chosen example, since, though the *p* of *pra* is this time unchanged, the *t* before it must be doubled, *tatt pr-*; a *pra* after a pause would have answered better); second, that the duplication takes place only before a consonant, *urukṛd uru nah* (ii.6.11³); third, that only a consonant, not a vowel, in the defined position, is duplicated, *praṅgam uktham* (iv.4.2¹). O. appends a new set of counter-examples, as if a part of a new exposition; namely *prajananam* (i.5.9¹), *padbhyāṁ dce savane* (vi.1.6⁴: an ill-chosen example, containing cases of duplication as well as of its omission), and *uganā uta* (iv.1.10²).

लवकारपूर्व स्पर्शश्च पौष्करसादेः ॥ २ ॥

2. Likewise, according to Pāuṣkaraśādi, a mute preceded by *l* or *v*.

The commentator declares that the *ca*, 'likewise,' in this rule brings down from the one preceding the being preceded by a vowel, and duplication. The former part of the defined implication is at least otiose, since *l* and *v* never occur in the Sanhitā before a mute, except as themselves preceded by a vowel: *v*, indeed, is found in combination only with the nasal mutes, *n* and *ṇ*; *l*, in the groups *lk*, *lg*, *lp*, *lb*, *lbh*, *lm*, and *lpy*. The examples quoted are *kalpān juhoti* (v.4.8⁵) and *vibhūdāvne* (iii.5.8^{1,92}: all save B. actually read this time *-dāvne*, with doubled *n*). According to the interpretation given to the next rule, the worthy Pāuṣkaraśādi does not regard the duplication of the mute after the semivowel as suspending the duplication of its predecessor also, by rule 1; and he would accordingly read *kallppān* and *-dāvne*; and this part of his doctrine is, as we shall see, declared unapproved.

Counter-examples are given: *kalyānī rūpasamrddhā* (vii.1.6⁶: to be pronounced *kallyānī*, or, by rule 21, *kalyānī*) and *vāyavyam* (i.8.7¹ et al.: to be made *vāyavyam*), to show that no other letter than a mute is thus doubled; and *kāgmān chakabhiḥ* (v.7.23) and *tasmād etat* (vi.3.11⁶), instancing other consonants than *l* and *v*, with the following mute not doubled: in these words, the sibilant

2. *pāuṣkaraśāder¹ mate lakarapūrvo² vakārapūrvo vā sparṣo³ dvicarnam āpadyate⁴. kalpān..... vibh..... svarapūrca-
tvaṁ dvitvaṁ cā⁵ 'nvādiṣati cakārah⁶. 'sparṣa⁶ iti kim: kaly-
.....: vāy..... evampūrva iti kim: kāḥ.....: tasm.....⁷ lakā-
raḥ ca vakāraḥ ca lavakārau⁸: tāu pūrvāu yasmāt sa tathoktaḥ.*

¹ O. pauskar-, as also in the rule. ² B. G. M. ins. ed. ³ O. dvitvaṁ āpnoti.

⁴ G. M. put at beginning of clause. ⁵ O. om. ⁶ G. M. sparṣapara. ⁷ W. O. lakā-avak-.

is itself doubled (except by Hārīta, rule 18), a first mute of the same series with the nasal is inserted before the latter (rule 9), and between the two mutes a *yama* (xxi.12); so that we have as final result the formidable combinations *ccppm* and *sppm*.

The Rik Pr. (vi.2) also requires a double mute after *l*, and the Vāj. Pr. (iv.99) after any semivowel—which last is equivalent with our rule, since *y* is never followed by a mute.

We have a right to be surprised at the introduction of this and the rule next following before rule 4, since the duplication they teach is analogous to that after *r*, and of secondary importance to it.

स्पर्श द्वैकेषामाचार्याणाम् ॥३॥

3. According to some teachers, the mute only.

That is to say, in the combinations just treated of, the mute is duplicated, but not the preceding semivowel also; and we are to read *kalppān* and *vibhādānne*.

According to the commentator, this rule represents the approved usage in the *śākhā*. It seems very strange to find such approved usage laid down in the Prātiśākhya merely as the *dictum* of certain authorities. But a rule (xiv.7) is given below, without any restriction, which plainly implies the validity of the present one.

रेफात्परं च ॥४॥

4. Also a consonant that follows *r*.

The *r* itself being, by rule 15, not liable to duplication. This is the rule second in importance in the whole system, and is found in all the Prātiśākhyas and in Pāṇini. The Ath. Prāt. (iii.31), the Vāj. Prāt. (iv.98), and Pāṇini (viii.4.46) ascribe the same effect to *h* as to *r*; and it is strange that our treatise, which is so liberal in its citation of discordant opinions, makes no reference to one so well supported as this. After *h* we find in the Sanhitā only the three nasals specified in rule xxi.14 as requiring the insertion of a *nāsi-kyā*, and the three semivowels *y*, *r*, *v*; *r*, on the other hand, forms numerous groups as first member: I have noted twenty-four of two consonants, forty-three of three consonants, and five of four consonants; a few of them are exempted from duplication by rules 16, 20-23. The cited examples are *arcanty arkam arkināḥ* (i.6.12³:

3. *ekeshām* ¹ *mate lavakārapārva*² *sparṣa*³ *eva devicarnam*⁴ *āpnoti*⁵: ⁶*aneuā* ⁷*vadhāraṇena sūtrāntarārambhanena ca pāuṣh-karasādimate lavakārayoḥ ca devitam asti*⁸ *'ti gamyate*⁹.

*idam eva sūtram iṣṭam na tu pūrvam*¹⁰. *pūrvoktāny*¹¹ *evo* ¹²*dā-haraṇāni*.

¹ G. M. O. ins. *ācāryāṇām*. ² B. -*roṣ* ca; G. M. put after *eva*. ³ G. M. -*ṣapara*, as also in the rule. ⁴ O. *devitam*. ⁵ G. M. O. *āpadyate*. ⁶ O. om. ⁷ O. *sūtram*. ⁸ O. *ukt*.

i. e. *arceanty arkkam arkkinah*), *arkyena vāi* (vii.5.9¹: i. e. *arkk-yena*: wanting in O.), and *ūrg vā udumbarah* (v.1.10¹ et al.: i. e. *ūrgg vāi*).

The *ca*, 'also,' of the rule, according to the commentator, implies duplication, and precedence of the *r* by a vowel (bringing down *svarapūrva* from rule 1). The question is raised by an objector whether sequence of the consonant following the *r* by another consonant (in virtue of *vyāñjanaparam* in rule 1) is not also implied: but such sequence is declared not obligatory; and it is pointed out that later rules (15,16), exempting a consonant in *pausa*, and a spirant before a vowel, from duplication after *r*, prove that the present rule prescribes duplication also where no consonant follows, and where a vowel follows; since there would be no propriety in denying by a special rule what had not been already enjoined by a general rule. In support of his assertion that the *r* must be preceded by a vowel, the commentator cites the word *tryambakam* (i.8.6²), in which he says that the *y* must not be doubled: and he fortifies his claim by appealing to Pāṇini's rule (viii.4.46), which expressly restricts duplication after *r* and *h* to cases in which these letters follow a vowel (G. M. add the remark that in Pāṇini also no implication of *vyāñjanaparam*, 'followed by a consonant,' is found). The Vāj. Pr. (iv.102) makes an equivalent restriction explicitly. The groups are not numerous in the Tāttirīya-Saṁhitā in which a *r* that does not stand first is followed by a consonant, and the only consonant so following is *y*: the combinations are *jry*, *try*, *ūtry*, *ttry*, *ntry*, *stry*, and *tstry*.

This finishes the proper exposition and illustration of the rule; but the commentator suffers himself to be enticed into a lengthy and tedious refutation of a trivial suggestion which some one has been impertinent enough to make. There are those, he says, who

4. *rephāt param*¹ *vyāñjanam*² *deivarṇam āpadyate*³: ⁴ *yathā*: *arc*-----: ⁵ *arky*-----: ⁶ *ūrg*----- *svarapūrvadvitvayor ākar-shakaḥ cakārah*. *nanu*⁷ *vyāñjanaparadvākarshakaḥ kim na syāt*: *ne*⁸ *'ti brūmah*: *niyamābhāvāt*: *tathā hi*: *avasāne*⁹ (xiv.15) *ūshmā svarapara* (xiv.16) *ity etannishedhadvayena rephāt pa-rasya*¹⁰ *vyāñjanasya*¹¹ *vyāñjanaparadvābhāve*¹² *svarapūrvatve*¹³ *'pi deitvam asti*¹⁴ *'ti niṣciyate*¹⁵: *aprasaktapratishedhānupapattē*¹⁶. *svarapūrvadvānvādegeṇa*¹⁷ *kim*: *tryambakam* *ity ādāu mā bhūd iti*: *kim ca*: *'aco rahābhyaṁ dve iti*¹⁸ *pāṇinīyasātreṇa*¹⁹ *'pi svarapūrvatve saty eva*²⁰ *deitvam vidhiyate*: *'tasyā*²¹ *'yam arthah*: *aca uttarāu yāu rephahakārāu tābhyām uttarasya yaro dve bhavata*²² *iti*.²³

*kecid evam ācuh*²⁴: *svarapūrvādiḥ abhavad rephapūrvam iti vācye*²⁵ *vāco*²⁶ *yuktyantaram arthāntaram samarthayati*²⁷: *ahar*----- *ity ādāu*²⁸ *vāikṛtarephād*²⁹ *uttarasya*³⁰ *'na syād deitvam*³¹ *iti*. *tad etadudhyayanaviruddhopaddhatim adhyāste*³²: *vayam tu va-*

maintain that the analogy of *searapūrcam* in rule 1 would require *rephapūrcam*, 'preceded by *r*,' to be employed here (instead of *rephāt param*, 'following *r*'), and that the difference of phraseology intimates a difference of meaning—namely, that a consonant coming after a *r* which is the product of euphonic alteration, as in *ahar devānām āsīt* (i.5.9²: only W. B. have *āsīt*), is not doubled. But this, he replies, enters upon a path which is at variance with the reading of this *śākhā*; and he proposes himself to set forth the true ground of the different term employed. If *rephapūrcam*, namely, were used, the rule would be liable to the suspicion of meaning the direct opposite of its real intent, since *rephapūrcam* admits of being understood as *rephāt pūrcam*, 'preceding *r*.' And if it be retorted that this false implication is of no account, since the case it would involve is already provided for in the first rule of the chapter, and the present rule would be a mere useless repetition, and that the avoidance of such repetition is of itself enough to refute the implication—then the farther reply is made, that that is not sound doctrine, in view of the principle stated in the verse "non-contact with mud is far preferable to the washing of it off;" and the teacher uttered the rule in its form as given, with the intent that not even a particle of suspicion of wrong meaning should find occasion from it.

There is no good reason to suppose that the author of the treatise, in saying *rephāt param*, intended to do anything more than use a lawful discretion in the selection of his phraseology. The ambiguity which the commentator ascribes to the other reading is suffered to pass in numberless other cases. The more desirable cleanliness of him who has incurred no need of ablution has been referred to once before (under iv.23), in a case somewhat similar.

dāmo vāco yuktyantaraprayojanam: rephapūrcam ity ukte viruddhavigraheṇā²⁹ sūtram saṁdigdham syāt: rephāt pūrcam rephapūrcam³⁰ iti: bhavato³¹ esha³² vigraha iti cet: adhyāyādisūtreṇā³³ tad gatam iti³⁴ pāunaruktyam asya sūtrasya³⁵ "padyate: nanu pāunaruktyabhayād eva viruddhavigraham nivārayāmah³⁶: ne 'yam saralā vṛttiḥ: prakṣālanād dhī³⁷ pañkasya dūrād asparṣanam varam iti³⁸ nyāyād³⁹ atra viruddhaśaṅkāleṣo 'pi nā 'vakāṣaṁ labhatām iti vāco yuktyantareṇa sūtram ācāryaḥ provāca.

¹ G. M. ins. ca. ⁽²⁾ O. *dvaitam āpnoti*. ³ G. M. ins. *searapūrcam dvaitayor ākar-
śhakaḥ cakārah na tu vyañjanap-ratadkarśhakah*. ⁴ in G. M. only. ⁽⁵⁾ O. om.
⁽⁶⁾ G. M. *cakāro* only. ⁽⁷⁾ G. M. *atha na* (xiv.14) *ity uttaraniśedhādāhikāre ava-
sānavisarjanīyafihvāmālīyopadhmanīyāḥ* (xiv.15). ⁸ W. O. *paraḥ ca*.
⁹ W. B. om. ¹⁰ W. B. *-vena*; O. *-bhāne*; G. M. om. ¹¹ G. M. *-raparato*; O. om.
¹² O. *gomyate*; G. M. *nīccaye katham*. ¹³ G. M. *śtasya pra-*. ¹⁴ O. *-rvāne*. ⁽¹⁵⁾ G.
M. om. ¹⁶ W. O. *evam*. ¹⁷ G. M. ins. *tat katham: aco rahābhyān dec*. ¹⁸ G. M.
asy-. ¹⁹ G. M. *sta*. ²⁰ G. M. add *tatratā 'pi vyañjanaparatoḥprasaktir na dṛṣyate*.
²¹ O. *śhuk*. ²² B. om. ²³ W. om.; G. M. *rephāt param iti vāco*. ²⁴ G. M. *-yati 'ti*
arthāntarasya 'dāharanam ucyate. ²⁵ G. M. *atra*. ²⁶ W. om. *vāikṛta*. ⁽²⁷⁾ G. M.
vyañjanasya dvaitam na syād. ²⁸ O. *-asita*. ²⁹ W. *viruddhāve iti grahaṇena*; G. M.
O. *-hane*. ³⁰ W. B. *pūrcam*; O. corrupt. ³¹ W. B. *bhavaty*. ³² G. M. *esha*. ³³ G.
M. *tatah*. ³⁴ O. *-ma iti cet*. ⁽³⁵⁾ G. *pañke 'ti*; B. om. *varam*. ³⁶ G. M. *-yenā*.

द्वितीयचतुर्थयोस्तु व्यञ्जनोत्तरयोः पूर्वः ॥१॥

5. In place, however, of second and fourth mutes, when followed by consonants, is put the preceding mute.

That is to say, when an aspirate occurs between a preceding vowel (as the commentator specifies in his paraphrase of the rule) and a following consonant, or in such circumstances that by rule 1 it would be doubled, it receives instead an increment (*āgama*) of the mute next preceding it in its own series, or of its corresponding non-aspirate. Examples are *vikhyāya* (i. e. *vikkhyāya*) *cakshushā tvam* (iv.1.2³: only G. M. have the last two words) and *meghyā* (i. e. *megghyā*) *vidyuto vācah* (v.2.11¹: only G. M. have *vācah*); to which W. B. add *tat savituh* (i.5.6⁴ et al.; the *t* is converted to *th* by xiv.12, and to the *th* is then prefixed *t*, making *tatth savituh*) and *sādhyā* (i. e. *sāddhyā*) *vāi devāh* (vi.3.4⁵ et al.). To show that only the aspirates are thus treated, is quoted *ādyam* (i. e. *ād-dyam*) *asyā 'nnam* (ii.2.5⁶: O. omits *annam*); to show that a vowel must precede, *vashat svāhā* (vii.3.12; by v.33, *t* is inserted between *t* and *s*, and the inserted letter is made *th* by xiv.12; then, by this rule, no farther change of the *th* occurs, and we read *vashattth*, not *vashatttth*; W. goes so far on this road as to read *vashath svāhā*) and *pādbhyām* (i. e. *pāddbhyām*, not *pāddbbhyām*) *dve savane* (vi.1.6⁴)—but G. M. O. substitute for the former another similar case, *vat svayamabhiḡvartāya* (iii.2.8¹ seven times: i. e. *vattth sv-*; O. writes *vattth sv-*)—; to show that a consonant must follow, *ukhāyāi sadane sve* (iv.1.9² et al.: W. B. omit *sve*) and *meghāyate svāhā* (vii.5.11¹). The word *tu*, 'however,' in the rule, the commentator (with more than his usual success in dealing with this particle) explains as intimating the denial of duplication, enjoined by rule 1. He adds that some give the particle a different interpretation, as

5. *dvitīyacaturthayorḥ svarapūrvayor vyañjanottarayor pūrvā-gamo bhavati: yathākramena dvitīyasya prathamāḥ caturthasya tritīyah. yathā: vi-.....: me-.....: 'tat-.....: sā-.....' dvitī-yacaturthayor iti kim: ādyam-.....: evampūrvā' iti kim: va-shat-.....: pad-.....: evamparayor' iti kim: ukh-.....: megh-.....: prathamāsūtreṇa prasaktān deivam nivartayati tuṣabdhā. anye to anyathā manyante: pūrvāgamasya deivam nivartayati 'ti. nāi 'tat sāmam: savarnasavargīyapara (xiv.23) ity uttaranishedhā' eva tasya tannivṛttiḥ.*

atra kecid āhuḥ: vyañjanaparayor iti vācye vāco yuktyanta-ram arthāntaram sūcayati: sāmhitāsāmhitāsādhāraṇam¹⁰ para-nimittam¹¹ uktam¹²: tata¹³ ihā 'nyatarastha¹⁴ āgamanimittatve prāpte 'sāmhitapadānām nityatvāt tadgrahaṇam¹⁵ eva¹⁶ nyāyyam iti kṛtvā vāikṛtavyañjanaparatve sati nāi 'tad vidhānam bhavati¹⁷: yathā: abhy asthād ity ādī. nā 'yam pakshaḥ: adhyayona-

signifying that the increment-consonant is not itself to be doubled; but justly pronounces this to be inappropriate, as such duplication is forbidden by rule 23 of this chapter.

In this and the three following rules is contained, for all the cases which come within the purview of the *Prāticākhya*, the explicit prohibition of a double aspirate. Such double aspirates are, however, sometimes written by the Hindu scribes, both in situations where the authority of the phonetic treatises directly forbids them, and elsewhere. Thus, my manuscript of the *Tāittirīya-Saṁhitā* has, three times, *dh dh* instead of *d dh* as the result of combination of *t* and *h* (at ii.6.12^b: iii.4.1^a: v.3.12²), and the Calcutta edition, so far as printed, gives, unadvisedly, the same. Both authorities agree in reading *dididhāhi* at iii.1.11⁴. The edition, absurdly enough, gives *adhaththāh* at i.1.13², where my manuscript has *adhaththāh*. And I find a few cases of *khkh* and *chch*, which will be noted under rule 8, below.

As under the preceding rule, the commentator here also enters into a tedious and useless discussion of a verbal question; namely, why 'followed by consonants' is represented by *vyañjanottarayoh* instead of *vyañjanaparayoh*. Some, he says, have maintained that a difference of meaning is intended by the difference of phraseology; that it is desired, namely, to except cases like *abhy asthāt* (iv.2.8¹), where the following consonant is the product of euphonic alteration. The ground alleged for this claim is not entirely clear to me: it seems to be that a specified following cause (one that produces an effect in something that precedes it) is common to the *saṁhitā*-text and that which is not *saṁhitā*; hence, a cause of increment occurring in either kind of text being in question, a citation of words from outside the *saṁhitā* is alone suitable, on account of their constancy—that is, *abhi*: *asthāt* not being citable as an example under the rule in its *pada*-form, it must not be so treated in its *saṁhitā*-form, as well. But the claim is disallowed, as being opposed to the actual reading, and also to the fundamental

*virodhān mālasūtravirodhāc*¹⁴ *ca*: *tathā hi*: *mālasūtre svarapārvatve vyañjanaparavatve*¹⁵ *ca* *sati vihitam*¹⁶ *deitvam atra nishpādyate*¹⁷: *na tu*¹⁸ *tatra vyañjanam viśeṣitam*: *tadapavādakavād atrā*¹⁹ *'pi tadviśeṣo vaktum ayuktah*²⁰. *śikṣhādiparikṣhānād*²¹ *adhyayanānurodhāc ca vāco yūktyantarābhiprāyo 'smābhir abhidhiyate*²². *apavādyāpavādakayor*²³ *anayor*²⁴ *'niyamo nā 'sti*: *kim iti*²⁵ *svrapārvatve sati vyañjanaparam eva vyañjanam*²⁶ *deitvam*²⁷ *bhajate*: ²⁸ *dvitīyacaturthāu ca*²⁹ *vyañjanaparāv*³⁰ *eva pūr-vāgamam*³¹ *bhajata iti*: *kim tu prācūryābhiprāyeṇe 'dam sūtra-dvayam pravṛttam*. *katham niyamābhāvah*: *anyathā*³² *kuṭracit kāryadevayadarṇāt*. ³³ *attā*....: *annapata ityādāu deitvam*: *pra*....: *addhi*.... *ityādāu pūr-vāgamah*³⁴: *tān hasta ity atra tu*³⁵ *prāptāu satyām api ne 'dam kāryam dr̥ṣyata iti cu*³⁶ *niyamābhāvah*. *śikṣhā cāi 'vaṁ vakṣhyati*:

rule. For, the intent is to cast out or deny a duplication established by the fundamental rule (xiv.1), where the being preceded by a vowel and followed by a consonant was implied; and there no limitation was laid down for the following consonant; hence, it is improper to lay one down here, where an exception is prescribed.

The commentator then goes on to say that he will set forth the real intent of the difference of phraseology, with due regard to the *Cikshā*, and in accordance with the accepted reading of the text. But I am compelled to confess myself incapable of extracting a satisfactory meaning from his exposition and argument. The point of it is an asserted absence of *niyama* in the two rules (1 and 5), as of one suffering and the other prescribing exception. *Niyama*, 'obligatory force,' appears to signify here joint application, and so a mutual or reciprocal influence. When a vowel precedes, he continues, a consonant is doubled only when followed by a consonant; and second and fourth mutes take increment of the mute that stands before them in the alphabet only when followed by a consonant. But the pair of rules in question is constructed with the intent of multiplicity ('diversity' or 'independence?' *prācurya* is not found elsewhere). How does an absence of *niyama* appear? Why, from the fact that otherwise a twofold effect would in some cases come to light. In *attā haviṇshi* (ii.6.12²) and in *annapate* (iv.2.3¹ et al.), and so on, there is duplication; in *prachac chandah* (iv.3.12³: G. M. have instead *acchāvākah*, the reference for which I have failed to note) and *addhi team deva prayatā* (ii.6.12³: G. M. O. omit *prayatā*), and so on, there is increment of a preceding mute; but in *tāñ haste* (vi.1.3⁷: W. has *tāñs te* [iv.1.10³], but doubtless by accidental omission of *ha*), even though it falls under the rule, the same effect is not seen: hence, there is

*svarāt⁴⁰ pūrcasya⁴¹ varṇasya keacid deivam ca kathyate⁴²:
na ca varṇadevityasya na caturthe kadā⁴³ cana.
vyākhyātām ca vacanam etadvidvadbhiḥ:
kutracit svarayor madhye deivam lakṣhyānusārataḥ:
pūrvāgamas tathā tatra jñeyo varṇavicakṣaṇāḥ.
“evamrūpam aniyamaṁ sūcayitum vyañjanottarayor⁴⁴ ity anta-
rasvikārah⁴⁵.
vyañjanam uttaram yābhyām tāu⁴⁶ vyañjanottarāu⁴⁷: tayoh.*

¹ G. M. O. put next before *pūrv*, O. adding *tu*. ² in O. only. ³ G. M. O. om.
⁴ G. M. O. *svarapūrcayor*. ⁵ G. M. *vyañjanottarayor*. ⁶ B. *utaratranī*; G. M. *uttarasatranī*. ⁷ G. M. O. *-tēh*; O. om. *tan*. ⁸ B. om. ⁹ G. M. O. *-ti 'ti*; G. M. add *tatra*. ¹⁰ G. M. *sañhitāsamāh*. ¹¹ G. M. *paramani*; O. *uktani*. ¹² O. om. ¹³ O. *tatra*. ¹⁴ G. M. *-rasya*. ¹⁵ W. O. om. *tad*; B. *gunam*. ¹⁶ W. O. *evam*; M. exchanges the places of *eva* and *iti*. ¹⁷ O. *-ti 'ti*. ¹⁸ O. om. *sūtra*. ¹⁹ O. *-namā-trapar-*. ²⁰ G. M. *-ta*; O. puts after *deivam*, and adds *ity*. ²¹ G. M. *nishidhyate*; O. *viśishyate*. ²² W. B. O. *na*. ²³ W. B. *latr*. ²⁴ G. M. *yuktah*. ²⁵ W. *-dipavāca-kah*; G. M. *-pa*. ²⁶ O. *abhiśahi*. ²⁷ W. B. *apavādop*. ²⁸ G. M. *na 'sti vīrodha itī*. ²⁹ O. *paramani*. ³⁰ W. om. ³¹ O. ins. *svarapūrv*. ³² B. *ta*; O. om. ³³ O. *parāv*. ³⁴ W. *-me*; G. M. *-māu*. ³⁵ B. G. M. ins. *pi*. ³⁶ G. M. ins. *katham*. ³⁷ W. B. *-māñ*. ³⁸ O. om. ³⁹ W. om. ⁴⁰ O. *-ra*. ⁴¹ W. *sarvasya*. ⁴² G. M. *vakshyate*. ⁴³ G. M. *katham*. ⁴⁴ O. ins. *ity*. ⁴⁵ O. *-janayor*. ⁴⁶ G. M. O. *uttarase*. ⁴⁷ G. M. *tad*. ⁴⁸ G. M. *-rañ*.

absence of *niyama*. The examples here furnished, which ought to give us the clue to the commentator's meaning, seem to leave us wholly in the dark, since not one of them falls under either of the rules in question: the first, second, and fourth are by rule 23, below, exempt from duplication; the third is a case under rule 8; and the combination *ñh* is (see under rule 15) treated as a simple *h*. Next, the *Çikshā* is quoted, to the effect that "in some cases, also, duplication of the first consonant of a group after a vowel is prescribed; not, however, of a second mute, nor of a fourth, under any circumstances;" and, by those versed in the subject, the statement is explained [in conformity with what follows]: "in some cases, there is duplication of a consonant between two vowels, in accordance with rule; so there also is to be understood prefixion of the preceding mute, by those skilled in alphabetic sounds" (in the known *Çikshā*, it may be remarked, no such verses as these are to be found). And the final conclusion is, that the different term in *vyañjanottarayoh* is intended to signify an absence of *niyama* of this sort. That is to say, perhaps, the real independence of the two rules is intimated by the choice of a different term in expressing the common factor which they contain.

रेफपूर्वयोश्च नित्यम् ॥ ६ ॥

6. As also, in all cases, when they follow *r*.

This, it is pointed out, has the value of an exception under rule 4. The dual number of *rephapūrcayoh* shows that the pair, "second and fourth mutes," spoken of just above, is intended. "Also" (*ca*) implies the increment by prefixion of the next preceding mute. And the meaning is, that second and fourth mutes, with the limitations prescribed, as preceded by *r*, take always their respective predecessors as increment. Thus, *ārdhvo* (i. e. *ārdhvo*) *bhava* (i. 2. 14²), and *ardhyavān* (i. e. *arddhy-*) *prāṇaḥ* (vi. 5. 2²: only G. M. have *prāṇaḥ*). *Nityam*, 'in all cases,' implies that the increment is made after *r* when the mute to be increased is followed by a vowel also (not alone when it is *vyañjanottara*, as specified in rule 5). Thus, in *artheta* (i. e. *arth-*) *sthā'pām* (i. 8. 11: only B. has *apām*), *mārkhām* (i. e. *mārkkhām*) *tajjahanyām* (vii. 1. 6⁴), and *goargham* (i. e. *goarggham*) *eva* (vi. 1. 10¹).

लकारपूर्वे च ॥ ७ ॥

6. *rephāt param ca* (xiv. 4) *ity asyā'pavādakam etat': divi-
vacanena dvitīyacaturthāu gṛhyete: saviçeshanayo' rephapūr-
vayor anayor' nityam pūrvāgamo bhavati': āgamānvādeçakaç
cakārah. yathā': ārdh-----: ardhy----- nityam iti kim:
svaraaparatve'pi bhavato' etad iti: arthe-----: mārkhām-----
go-----*

¹ W. *avadat*. ² W. B. *navi*; G. M. O. *-shādu*. ³ O. *tayor*. ⁴ O. *nyāt*. ⁵ in G. M. only. ⁶ G. M. *-dy*.

7. And when *l* precedes.

The *ca*, 'and,' here brings down from rule 5 only the fourth mute [the last of the two there mentioned] and the increment. The second mute is not also included, because (see note to rule 2) no second mute occurs after *l* in the Sanhitā. The examples are *pragalbho* (i. e. *-galbbho*) '*śya jāyate* (ii.5.5³; only G. M. have *jāyate*) and *namo madhyamāya cā 'pagalbhāya* (i. e. *-galbbh-*) *ca* (iv.5.6¹)—but, in place of the latter, G. M. give *apagalbho jāyate* (ii.5.5³; O. reads *agagalya* simply, which doubtless means the first word of this).

As was remarked above (under rule 3), the laying down of the present precept without any limitation appears to confirm the commentator's interpretation of rules 2 and 3, as teaching the accepted doctrine of the *śākhā*. It would, to be sure, be not impossible to understand *lbh* for *lbh* as required here, without any reference to the other groups—*lk*, *ly* etc.—in which the duplication after *l* depends upon the earlier rules; but that seems quite unlikely.

उपसर्गपाथद्वयोऽन्यातिथामपरमभूतेपूर्वेषु हविर्भुजेषु

च ॥ ८ ॥

8. Also the preceding mute is inserted before *ch*, *khi*, and *bhuja*, when these follow either a preposition, *pātha eshaḥ*, *ati*, *āti*, *dhāma*, *parama*, or *bhāte*.

The examples after a preposition (in which situation alone the increment of *khi* and *bhuja* is made) are first given by the commentator: they are *ā cchṛṇatti* (v.1.7⁴; the preceding word, *andcchṛṇam*, might well have been included, as an additional instance; my MS. has simple *ch* in both cases); *nama ākkhidate ca prakkhidate ca* (iv.5.9²; G. M. omit the first word, G. M. O. the last two); *ayakshmayā paribbhujā* (iv.5.1⁴), with *vibhu ca me prabhu ca me* (iv.7.4¹⁻²; O. stops at the first *me*) as counter-example, to show the necessity of saying *bhuja*, instead of *bhu* simply, in the rule; and *yā ca vicchandāḥ* (v.2.11¹). Then follow counter-examples: first, to show that *kh* is increased only when followed by *i*, *nikhātam manushyānām* (vi.3.4⁶) and *datse adhi khādati* (vi.2.11⁴; only G. M. have *datse*); next, to show that the increment takes place only after a preposition, *sachandā yā* (v.2.11¹). The examples after the remaining words, as particularly specified in the rule, are *priyam opy etu pāthah*: *esha cchāgah* (iv.6.8¹; only O. has *priyam*), with *ṛtubhir cā esha chandobhiḥ* (vii.5.15²), to prove the need of quoting *pāthah* along with *esha* in the rule; *aticchan-*

7. *cakāraḥ caturthāgamayor¹ ākarshakah*: *caturthasparṣe² lakārapūrve sati pūrvāgamo bhavati*. *prag-----*: *namo-----* *lakārah pūrvo yasmād asāu³ lakārapūrvah*: *tasmin*.

¹ G. M. *-gam*. ² G. M. *-the sp-*. ³ G. M. O. *sa*.

dasam upa dadhāti (v.3.8²), *savitra āticchandasāya* (vii.5.14), *dhāmacchad iva khalu vāi* (ii.4.10²: B. O. omit *vāi*), *paramacchado vare* (iv.6.2¹), and *yad bhāteccchadān sāmāni* (vii.5.9⁴).

Further examples of the increment of *ch*, falling under this rule, are *ācchad* and *pracchad* (at iv.3.12^{2,3}) and *ācchettā* (i.1.2¹): if there are others, I have omitted to note them. The usage in the manuscripts, of our commentary and of the *Sanhitā*, is quite irregular, varying between *ch* simply, *ech*, and *chch*, without much regard to whether the case is one to which this rule applies or not. I have collected the cases in which my manuscript of the *Sanhitā* has *chch*: they are *dhāmachchad* (ii.4.10²; but *dhāmachad* in the same division), *prachchach chandah* (iv.3.12²), and *āyachchad-bhyah* (iv.5.3²); and, in the combination of separate words (besides the case just quoted), *ācchach chandah* (iv.3.12²), *kakuch chandah* (iii.1.6³), and *yach chresstah* (iii.4.8¹). In every one of these instances, the Calcutta edition, so far as it yet reaches, reads correctly *ech*.

I have found no other cases of the increment of *khi* under the rule; but my manuscript has (without authority) *udakhkhidat* (ii.1.1^{4,5}), *sam akhkhidat* (vi.6.11¹), and *akhkhidrāh* (iii.5.8), while (along with the MSS. of the comment) it reads *khkh* instead of *khh* in the example (iv.5.9²) cited above. The edition reads *khh* at ii.1.1^{4,5}, remarking at the latter place that its manuscript authorities have *khkh*. Of course, the doubled aspirate is to be rejected, here as elsewhere, in obedience to sound phonetic theory as well as to the concordant authority of the *Prātiśākyas*.

अधोपाद्रूपणः परः प्रथमो ऽभिनिधान स्पर्शपरा-
त्तस्य सस्यानः ॥ १ ॥

9. After a surd spirant followed by a mute is inserted a first mute of the same position with the latter, as *abhinidhāna*.

The surd spirants are (see i.9, 12, 13) five, namely *z* (*jihvāmālīya*), *ç*, *sh*, *s*, and *φ* (*upadhmanīya*). The rule is to be paralleled with those in the *Vāj. Pr.* (iv.99, 100), which direct that a mute be doubled after a spirant, and after *jihvāmālīya* and *upadhmanīya* (which in that treatise are not reckoned as spirants); also with

8. *upasargapūrvēshu pātha..... evampūrvēshu ca' satsu cha khi bhuje 'ty eteshu pūrvāgamo bhavati². cakāra āgamānvādeçakāh. yathā³: ā.....: nama.....: ayak.....: je 'ti kim: vibhu.....: yā.....: 'khi 'ti kim: nikh.....: datsv.....: upasarga⁴ iti kim: sa.....⁵ etāny upasargapūrvāni. anyāny⁶ ucyante: priyam.....: pātha iti kim: rtubhir.....: atī.....: savitra.....: dhāma.....: parama.....: yad.....*

¹ G. M. om. ² O. *syāt*. ³ G. M. O. om. ⁴ O. om. ⁵ G. M. -*rgapūrvā*. ⁶ G. M. O. ins. *apy*.

that in the Rik Pr. (vi.2) which allows, but does not require, duplication of a mute after the spirants (namely *ç*, *sh*, *s*, *h*, *ç*, *q*, *ñ*). The Ath. Pr. (unless such a precept is lost by the *lacuna* occurring in the treatment of this subject: see note to Ath. Pr. iii. 28) and Pāṇini have nothing similar. Our rule, however, is quite alone so far as the treatment of a nasal after a spirant is concerned, making an insertion of a surd non-aspirate, instead of a nasal: and, as will be seen, the next rule quotes an opinion which would bring the Tāittiriya usage more nearly into accordance with that of the Rik and Vājasaneyi Sanhitās; but the commentator pronounces that opinion unapproved.

The examples quoted are as follows: *yah kāmayeta* (i. e. *yax kkām-*: ii.1.2³ et al.); *açmann* (i. e. *açpman*, or, after all rules are applied, *aççpman*) *ārijam* (iv.6.1¹: O. omits the example and puts here, instead of below, that for *q*); *grishme* (i. e. *grishpme* or *grishshpme*) *madhyandine* (ii.1.2⁵); *ayasmayam* (i. e. *ayaspmayam* or *ayaspmpmayam*) *vi cṛtā bandham* (iv.2.5²: only W. has *bandham*); *yah pāpmanā* (i. e. *yax ppā-*: ii.3.13²): O. adds to this last *tasmin* (vii.1.5¹ et al.: to be treated like *ayasmayam*, above), and, after *madhyandine*, *prā'çnāti* (*prāççtnāti*): I have overlooked this citation in searching out the references). As counter-examples, we have first *çarady aparāhne* (ii.1.2⁵: but O. substitutes *brahmavādino vadanti*, i.7.1⁴ et al.), to show that the sonant spirant, *h*, does not require a like insertion (the case is one of *nāsikya*, xxi. 14); then *ruknam upa dadhāti* (v.2.7^{1,2}: the case is one for *yama*, xxi.12), to show that a mute receives the increment only after a spirant; and lastly *ishvā ca vajrena ca* (v.7.3¹), to show that a mute only is increased after a spirant. For the second of these counter-examples, O. substitutes two of the same character, namely *yam apnavānah* (i.5.5¹) and *sa pratnavat* (ii.2.12¹ et al.); for the last, it gives (in a passage which has strayed out of place, and got inserted near the end of the comment to rule 10) *agnaye svāhā* (i.2.2¹ et al.).

In all these combinations, *ç* and *q* are exempt from duplication by xiv.15, but the sibilants are doubled, except as some authorities (xiv.17,18) would leave them unchanged.

9. *sparçaparād aghoshād ūshmaṇaḥ parāh¹ prathamā² āgama³ tasya sparçasya sasthanā⁴ samānasthāno 'bhinidhāno bhavati. abhinidhīyata⁵ ity abhinidhānaḥ: āropaṇīya ity arthaḥ: 'vedāntare tasyā⁶ 'bhāvād atrā 'ropanīyate. yathā: yah..... 'açm..... grish..... ayasm..... yah..... aghoshād iti kim: çarady..... ūshmaṇa iti kim: 'ruknam.....' sparçaparād iti kim: ishvā.....*

sūtram idam eve 'shtam: na tatparadevayam¹⁰.

¹ G. M. om. ² B. O. *pratham*. ³ G. M. *-mo bhavati*. ⁴ B. om. ⁵ W. O. *-dhāyata*; B. *-niyata*. ⁶ G. M. *vedāntarasyā*; O. *-reṇa tad a*. ⁷ G. M. O. om. ⁸ O. om. ⁹ O. *yam apnavānah: sa pratnavat*, and om. all that follows (but see various readings to next rule). ¹⁰ G. M. *tu par*.

The commentator illustrates with groups of two consonants only (of which the Sanhitā presents twenty-three that would come under the action of the rule); the question arises, then, whether in groups of three or more consonants (of which there are over fifty)—where the mute is followed by another consonant (as *zkh, gny, shky, atm, stry, qpr*), or where the spirant stands second (as *rcm, kshn, rshny, tsē, tsphy*), or where each is the case (as *tstr, tstry, ntstr*), or where there are two spirants followed by mutes in the same group (as *zkshtu*)—the rule is to be relentlessly applied. It can admit of little doubt that the sequence of another consonant would not affect the case; whether a preceding consonant would do so is more doubtful. Such resultant groups as *nthattr, thsphy, kkhshṭṭny*, and *zkkh-shṭṭn*, have a tolerably frightful appearance; but whether they would stagger the heroic soul of a Hindu *śākhin*, is another matter.

To the inserted mute is applied the name *abhinidhāna*, which the commentator explains by *abhinidhāyate*, 'it is set down against,' giving as its synonym *āropaniya*, (I presume, simply) 'to be inserted;' and adding the remark, "owing to the absence of this in any other Veda, there is here insertibility" (?). He takes no notice of the doctrine of *abhinidhāna* as a peculiar and imperfect utterance of certain letters in certain situations, which plays so formidable a part in the phonetic systems of the Rik and Ath. Prātiśākhya (see especially the note to Ath. Pr. i.43): we, however, bearing that doctrine in mind, may conjecture with plausibility that the word here not merely signifies an insertion, but designates also a peculiar quality of the inserted letter.

अथोपे प्रान्तेः ॥ १० ॥

10. According to Plākshi, when the following mute is surd.

That is to say, not when it is a nasal: Plākshi would ratify *zkk, zkkh, shṭṭ, shṭṭh*, and so on, but would make no insertion in *cm, shn*, and their like. This, as was remarked under the last rule, would correspond more nearly with the teachings of the Rik and Vāj. Prātiśākhya. The commentator illustrates with *nishkevalyam* (iv.4.2²), *yah kāmāyeta* (ii.1.2³ et al.), *paçcāt prācim* (v.3.7⁴): B. reads *prāci*, which is found in the same division; W. has *prāncam*, which does not occur in the Sanhitā after *paçcāt*, *nish tapāmi* (i.1.10¹), *doshāvastah* (i.2.14⁴ et al.), *yah pāpmanā* (ii.3.

10. ' *aghosha eva sparçē pare 'saty aghoshād ūshmanah ' prathamāgama' bhavati: 'plākshē pakshah'. yathā: nish-----: 'yah-----: paçc-----: nish-----: 'aksh-----: dosh-----: yah-----: āsp-----: ' aghosha eve 'ti kim: kāçmāñ-----.*

¹ O. ins. *plākshē çākhino male*. ² W. B. G. M. -ja; O. -çē 'pi. ³ O. *prathamā 'bhinidhāno*. ⁴ G. M. ins. *parah*. ⁵ O. om. ⁶ G. M. O. om.; W. puts out of place, before *aksh*. ⁷ G. M. om. ⁸ O. substitutes *suçcandra-----: sparçaparād itī kim: agh-----: sūtram itam eve 'stam na te paradeçayati*. 95. *aghosha eva sparçapare prathamā yaç çandasaṁ: naç cid atī: syūtram: bṛhaspatisūrapate*. ⁹ O. adds *abhinidhānaniyamo nā 'sti*.

13²), and *āspātram juhār devānām* (ii.5.9³: G. M. have only the first word). All these are examples quite needless to be given, as they are read by Plākshi precisely as prescribed by the preceding rule. Counter-examples, exhibiting his discordant view, are *kūgmān chakabhih* (v.7.23: W. G. M. have *kūgmān* only, and B. reads *kūshmāndān*, which I have not found in the *Sanhitā*, although *kūgmānda* occurs in the *Tāitt. Āraṇyaka*, at ii.7.8) and *akshnayā vyāghārayati* (v.2.7⁵ et al.: given only by W. B., and introduced out of place, between *nish topāmi* and *doshāvastah*, above).

O. follows an independent course in the interpretation and illustration of this rule. It calls the insertion an *abhinidhāna* (though adding at the end "there is no obligation of *abhinidhāna*" and, for the examples *yah kāmayeta* to *āspātram*, it substitutes *suçcandra dasma viçpate haviyavāt* (iv.4.4⁶: the MS. omits *dasma*), *yaç chandasām* (the thing nearest to this that I have found in the text is *prajāpatiç chandasām*, iii.3.7¹), *naç cid ati* (this I have overlooked in searching out the references), *syātram* (doubtless meant for *āspātram*), and *brhaspatisūrapate* (probably *brhaspatisutasya te*, i.4.27).

The present precept was pronounced unapproved in the comment to rule 9.

उत्तमपरात्तु प्लानायणस्य ॥११॥

11. But according to Plākshāyana, on the contrary, when the following mute is a nasal.

This can only mean to teach the precise opposite of the preceding rule; or, that there is no insertion when a surd mute follows the spirant, but only when a nasal follows. And it is first so explained by the commentator, who gives as examples *akshnayā vyāghārayati* (v.2.7⁵ et al.), *açnāti* (i.6.7³ et al.), and *tirthē snāti*

11. 'plākshāyanasya tu paksha uttamaparād aghoshād āshmanah parah' prathamāgamo bhavati. yathā²: akshn-----: açnāti: tirthē----- uttamaparād iti kim: nish-----: 'yah k-----' 'yah p-----' paçcāt. tuçabdaḥ plākshēḥ paksham prakshipati³.

kecid evam ūcuḥ: aghoshatvam āshmanas tuçabdo nivartayati 'tī⁴. tatrā 'yam sūtrārthaḥ: uttamaparāt tu' ghoshavata' āshmanah parah prathamāgamo bhavati. aḥnām-----: çarady-----: brahm----- ghoshavata' iti kim: açmā-----: grīsh-----: ayas-----

(¹) G. M. om. (²) G. M. om. (³) B. om. (⁴) G. M. om. ⁵ W. apakshiyati; B. kshiyati. ⁶ G. M. om. ū. ⁷ in W. only. ⁸ G. M. ghoshād. ⁹ G. M. agh.

O. substitutes for the whole comment *aghoshaprakṛtān tuçabde niroayati: plākshāyanasya çākhino mate aghoshād āshmanah uttamaparāparāt: sasthanoprathamāgamo bhavati: aksh-----: grī-----: çnāti: ayas-----*

(vi.1.1²); and, as counter-examples, *nishkevalyam* (iv.4.2²), *yah kāmāyeta* (ii.1.2³ et al.: B. omits), *yah pāpmanā* (ii.3.13²: G. M. omit), and *paṣcāt* (v.2.9⁴ et al.). Plākshāyana would read the first class as rule 9 requires, but would leave the mute without increment in the second class.

Then a second and wholly different interpretation is set forth as taught by certain authorities: namely, that *tu*, 'but,' in the rule, instead of negating Plākshi's opinion, reverses the quality of the spirant as prescribed in rule 9, changing it from surd to sonant—that is to say, admitting the increment only after *h*. The examples given are *ahnām ketuh* (ii.4.14¹), *ṣarady aparāhne* (ii.1.2⁵: only W. has *ṣarady*), and *brahmavādino vadanti* (i.7.1⁴ et al.: W. B. omit *vadanti*); the counter-examples, illustrating omission of the increment after a surd spirant, are *aṣmā ca me* (iv.7.5¹), *grishmo hemantah* (v.7.2⁴), and *ayasmayan vi cṛta* (iv.2.5²: W. B. omit *cṛta*). This, which is in itself forced and inadmissible, would also be equivalent to limiting the insertion to the little class of cases in which a later rule (xxi.14) requires the interposition of a *nāsikya*.

In the exposition of this rule, O. goes its own peculiar way, and takes no notice of the second interpretation which the other manuscripts report. It furnishes no counter-examples, and its examples agree only in part with those already given: they are (corrected) *akṣhṇayā vyāghārayati*, *grishme madhyandine* (ii.1.2⁵), *aṣṇāti* (or *snāti*), and *ayasmayan vi cṛta*.

The rule was pronounced unapproved by the commentator under rule 9.

प्रथम उष्मपरो द्वितीयम् ॥ १२ ॥

12. A first mute followed by a spirant is changed into its corresponding aspirate.

Literally, becomes a second mute—of course, of its own series. The examples given are as follows: *visṛpo virapṣinn* (i. e. *viraph-ṣin*; or, by xiv.1, *virapṣṣin*) *udādāya* (i.1.9²: only O. has the first word, and it omits the last; W. reads *vāratricadāya*, which is evidently merely a corruption); *tat shodaṣy* (i. e. *-tth sh-*) *abhavat* (vi.6.11¹: only G. M. have *abhavat*); *pratyāñ somah* (i.8.21: i. e. *pratyāñk s-* by v.32; then *pratyāñkh s-*); and *tat* (i. e. *tatth*)

12. *ūshmaparah prathama sparṣah¹ savargīyam dvītiyam āpadyate. vis-.....: tat-.....: praty-.....: tat-.....² prathama iti kim: ³tāh-.....² ūshmapara iti kim²: vāk-.....⁴ arvāg-..... ity atra prathamapūrvō hakāraṣ caturtham tuṣya sa-sthānam (v.38) iti hakārasya caturthāpattir viṣeshavihitatvāt: tatas tṛtīyañ svaraghoshavatparas (viii.3) tṛtīyatvam.*

idam eva sūtram iṣṭam⁵.

ūshmā paro yasmād asāv⁵ ūshmaparah.

¹ O. *ātmasa*. ² O. om. ³ W. B. om. ⁴ in O. only. ⁵ G. M. *su*.

savituh (i.5.6⁴ et al.). As counter-examples, we have *tāh* (i. e. *tās*, ix.2) *sañrohah* (v.3.6⁵: omitted by O.; dropped out in W. B.) and *vāk ta ā pyāyatām* (i.3.9¹: only O. has the last two words), in which no aspiration takes place.

A possible difficulty in the application of this rule is noticed and removed by O. alone. Such a case as *arvāk : hi : enam : parāh* (vi.3.3¹) might seem to fall under its action, the spirant *h* following a surd mute. But it is pointed out that, in virtue of v.38, *h* becomes a fourth mute by special prescription; and hence that rule viii.3 alone applies to the preceding surd, changing it to a sonant.

The place of introduction of this precept and the following—coming in, as they do, right in the midst of the rules respecting duplication, with which they stand in no relation—is quite surprising and objectionable. The commentator, however, passes the matter without notice.

I have not noted any case in which my manuscript of the Sanhitā attempts the aspiration of a mute before a sibilant, as here required. The manuscripts of the commentary, however, which almost never heed the rules for duplication, even in illustrating those rules themselves, often (as we have repeatedly had occasion to notice) observe this one in their citations, although they yet more often neglect it (thus, in the examples here given, G. M. O. aspirate the mutes, and W. B. leave them unchanged). Being taught in company with the duplication, as part of the *varna-krama*, it has no claim to be taken account of in the construction of an ordinary Tāittiriya text. Respecting the teachings of the other Prāticākhyas upon the subject, see the note to Ath. Pr. ii.6.

बाडभीकारस्यासस्थानपरः ॥ १३ ॥

13. According to Bādabhikāra, when the following spirant is not of the same position with it.

Rule ii.44 teaches the accordance of the several (surd) spirants, in their order, with the series of mutes, in point of position—more literally, of place of production.

T. calls the individual here referred to Bāḍavikāra, and W. O. have in the rule *vāḍabhikāra*, but in the comment *bāḍabh*; the rest have uniformly *b* as initial letter, which I have therefore adopted, as being decidedly better supported than *v*. Weber gives the two forms *vāḍabh* (V. Pr. p. 250) and *vātabh* (ib., p. 78).

13. *bāḍabhikārasya* ¹ *mata ātmano* ² *'sasthānoshmaparāḥ prathamah savargīyam* ³ *dvitīyam āpadyate. 'samānam sthānam yasyā 'sau sasthānah: na sasthāno 'sasthānah: sa paro yasmāt sa tatho 'ktah. yathā: viś-....: tat-....'* *asasthāna iti kim: tat-....* ⁴

ne 'dam sūtram ishtam.

¹ O. *ina. cākhino.* ² G. M. O. om. (and begin the next word as-). ³ O. om. ⁴ O. om. ⁵ B. om. ⁶ O. *ina. idarā(?)sthāno yam sakirah.*

The commentary (except in O.) is at the pains to repeat a couple of the examples of aspiration already given, namely *visrpo visrpo-gin* (i.1.9²; W. omits *visrpo*) and *tat shodagi* (vi.6.11¹): and it adds, in illustration of the peculiar view of the quoted authority, *tat savituh* (i.5.6⁴ et al.), where the dental mute, being followed by the dental sibilant, remains unchanged.

This rule is pronounced unapproved.

अथ न ॥ १४ ॥

14. Now for exceptions.

A heading, introducing the detail of exceptions to the rules as already given, and continuing in force through rule 28.

अवसाने रविमर्तनीयजिह्वामूलोयोपध्मानीयाः ॥ १५ ॥

15. A consonant before a pause is not doubled; nor *r*, *visarjanīya*, *jihvāmūliya*, or *upadhmanīya*.

As example of a consonant before a pause, is given *ark* (iv.7.4¹ et al.: W. has instead *so 'rkah* [v.4.3²], but it is not an illustration of the rule, and is evidently here only a corrupted reading of *ark*), of which the *k* would otherwise be doubled by xiv.4. Of course, it is only a final after *r* that would fall under the rules of duplication before a pause. The text affords, I believe, no instance of a consonant occurring in this position in *samhitā*, but such words as *ark* and *amārt* (vii.1.1² et al.) need to have their reading in the other forms of text determined by a rule like this. The commentator quotes *ark ca* (i. e. *ārkk ca*) *me sūnṛtā ca me* (iv.7.4¹; B. omits the last two words, G. M. O. the last three), as showing that the *k* is doubled when in *sandhi* with a following letter. To illustrate the exemption from duplication of the other letters specified, are given *nā 'rtim ā rchatī* (ii.2.4⁷), *manah ksheme* (v.2.1⁷), *yah* (i. e. *yay*) *kāmayeta* (ii.1.2³ et al.), and *yah* (i. e. *yay*) *pāpmanā* (ii.3.13²). According to the approved usage of this *śākhā* (see ix. 2,3), *visarjanīya* comes within the ken of this rule only when it

14. *athe 'ty ayam adhikārah*: ¹ *uktasya dvitvavidher*² *yathā-sambhavam nishedho 'dhikriyata*³ *ity 'etad adhikṛtan*⁴ *veditavyam ita 'uttaram yad vakshyāmah*⁵.

¹ G. M. ins. *atha*. ² W. G. M. *-dhe*; O. *vidh*. ³ W. *-kṛta*. ⁴ B. G. M. om. ⁵ B. no *varṇah*.

15. *padāvasāne*¹ *vartamāno varṇo 'repho visarjanīyo jihvāmūliya upadhmanīya*² *ce*³ *'ty ete varṇā dvitvam nā 'padyante*⁴. *ark*: *rephāt param ca* (xiv.4) *iti prāptih*. *avasānavacanān*⁵ *virāmābhīprāyam*: *tasmān na saṁdhāne nishedho*: *yathā*: *ark ca*..... *nā*.....: *man*.....: *yah*.....: *yah*.....: *svara-pūrvam* (xiv.1) *ity anenāi 'shām prāptih*.

precedes *ksh*, since elsewhere it can stand only in *pausā*. *Jihvāmūliya* occurs (by the conversion of final *h* according to ix.2) in the groups *zk*, *zkl*, *zkr*, *zksh*, *zkshn*, *zkshr*, and *zkh*; *upadhmanīya*, in like manner, in *qp*, *qpy*, *qpr*, *qpl*, and *qph*: the combinations of *r* have been enumerated above (under rule 4).

The other Prātiśākhya has rules equivalent with this, into the variety of expression of which we do not need to enter.

It is to be accounted as a reprehensible omission on the part of our treatise, that it gives no direction as to the treatment of a group beginning with *anusvāra*. The Vāj. Prāt. (iv.107) expressly exempts *anusvāra* from duplication; and, in the Rik Prāt., in the fundamental rule (vi.1), *anusvāra* is ruled out of account in the estimation of consonant groups, it being taught that a consonant is doubled after it in the same manner as after a vowel. There is no good reason to doubt that the same is to be understood as the doctrine of the present work, and that it would have *anusvāra*; so far as duplication is concerned, deemed and taken as merely an affection of the vowel to which it is attached. That this is not explicitly stated, stands in connection with the equivocal position of the Tāitt. Prāt. in reference to the nature of *anusvāra* (see p. 68): according to the view taken at the beginning of the next chapter (xv.1), rules respecting it are no more required than in the Ath. Prāt., where they are equally wanting.

The commentator notices that some would read the rule now under discussion as two, cutting off *avasāne* from the rest; and for the reason that otherwise, as the rule stands, it seems natural to understand that "*r*, *h*, *z*, and *q*, when standing before a pause," are not doubled; as a similar construction was made in rule 10 of the fifth chapter. But he denies the validity of the objection, since duplication of *r* and the rest before a pause is not in the remotest

'avasāna iti: 'caturṇām varṇānām' prthag eva sūtram 'kecid ācuh: ekikaraṇe' doṣhadarṣanāt: asū' doṣhaḥ: avasāne var-tamānā rephavisarjanīyādaya' ity anvayasampādanam¹²: ava-graḥa āgīr dhāḥ suvar (x.10) itivād iti cet¹³: nāi 'sha do-shah: ravisarjanīyādinām¹⁴ padāvasāne¹⁵ dūtecaprāptir¹⁶ dūrot-sārite¹⁷ 'ti ne 'yam atra gankā 'sti¹⁸: avasāneprthakkarane¹⁹ saty²⁰ avasāne²¹ kim vā bhavati 'ti sākāṅkshatayā²² vacanam anartha-kaṁ²³ syāt: ekikaraṇe tu ravisarjanīyativarṇasāhacaryād²⁴ ava-sāne vartumāno varṇa iti²⁵ labhyate: tasmād ekikaraṇam eva ramanīyam.

¹ W. B. yad-. ² W. B. combine, as in rule. ³ O. om. ca. ⁴ G. M. -dyeran. ⁵ G. M. -śva iti v-. ⁶ O. om. ⁷ G. M. kecid idam sūtram prthag eva "cuh: avasāna iti ca: ravisarjanīyajihvāmūliyopadhmanīyā iti ca: katham prthakkaranam. ⁸ W. caturcārṇāḥ; B. om. varṇānām. ⁹ W. corrupt. ¹⁰ G. M. O. ko 'śu. ¹¹ G. M. O. rari; B. -niyā. ¹² G. M. avayavasāmbhāvanam; O. aya daitvaṁ saiv-. ¹³ O. om. ¹⁴ O. avasānevyatirikāsthalā vi-. ¹⁵ B. om. ¹⁶ W. rephaprāptir. ¹⁷ W. tūśā; O. dūratot-. ¹⁸ G. M. kim cit; O. kim ca. ¹⁹ G. M. O. prth-. ²⁰ W. stī; G. M. nāsti. ²¹ G. M. -śhā tathā; O. -śhaya. ²² B. arth-. ²³ W. saiv-. B. vi-; O. om. varṇa. ²⁴ O. om.

manner suggested by the rules (literally, 'is expelled to a distance'), and consequently cannot be suspected of being taught here. If, on the other hand, *avasāne*, 'before a pause,' were set by itself, the inquiry would be "what under the sun is it that happens before a pause?" and the expression would appear meaningless. When, however, it is combined with the names of letters that follow, we naturally infer from the association that 'a letter in *pausa*' is intended. Hence, the inclusion of the two precepts in one rule is alone to be approved.

This defense of the unity of the rule is evidently of the most trifling and futile character, and the objectors are in the right—not, indeed, as the separation into two rules is absolutely necessary, but as it is decidedly preferable, and more in accordance with the general usage of the treatise elsewhere.

उष्मा स्वरपरः ॥ १६ ॥

16. Nor a spirant, when followed by a vowel.

It is only, of course, after *r* (xiv.4) that a spirant can be liable to duplication before a vowel, so that the combinations to which the rule applies are *rg*, *rsh*, *rs*, and *rh*. All the other treatises excepting the Vāj. Prāt. have the same rule (R. Pr. vi.2; A. Pr. iii.32; Pān. viii.4.49).

The commentator's examples are *darṣapūrnāmāśau* (ii.2.5⁴ et al.), *varshābhyah* (vii.4.13: I presume; my MS. of the Sanhitā has *varshyābhyah* twice instead of *varshyābhyah* and *varshābhyah*: O. gives instead *suvarshām*, iv.4.4¹), *barsam nahyati* (ii.5.7^{1,2}), and *barhishā* (i.7.4¹ et al.: G. M. have instead *barhisho* 'ham, also i.7.4¹). To illustrate the limitation to a spirant, he gives *ebhir no arkāih* (i. e. *arkkāih*; iv.4.4⁷: O. omits); to show that a vowel must follow, *pārṣve* (i. e. *pārṣve*; vii.3.10³), *varshyābhyah svāhā* (i. e. *varshshy*; vii.4.13: G. M. omit *svāhā*), *barsvebhih* (i. e. *barsve*; v.7.11), and *agnir hy asya* (i. e. *hhy*; v.1.5⁵)—but O. has a different series, namely *dārcyam yajnam* (iii.2.2²), *varshye-bhih* (the MS. has *varshebhih*; I have not succeeded in finding either word in the Sanhitā), and *agner hy etat purīsham* (vi.2.8⁶).

The combinations in which the spirant after *r* is doubled, being followed by another consonant, are *rgm*, *rgy*, *rgv*, *rsh*, *rshn*, *rshm*, *rshy*, *rsv*, and *rhy*. To complete the *sandhi*, either with or without duplication, the rules for insertion of *svarabhakti* (xxi.15,16) have to be further applied.

16. *svarapara āshmā dvitvam nā* "padyate. *svarah paro yas-mād asdu svaraparāh. yathā: darṣ-----: varsh-----: bar-sam-----: barh-----* "rephāt param ca (xiv.4) iti prāptiḥ. *āshme 'ti kim: ebhir-----* " *svarapara iti kim: 'pārṣve: varsh-----: barsvebhih: agnir-----* "

¹ G. M. O. om. ² O. om. ³ O. *dā-----: varshebhih: agner-----*.

प्रथमपरश्च प्रान्तिप्रान्तायणयोः ॥ १७ ॥

17. Or, according to Plākshi and Plākshāyana, when followed by a first mute.

That is to say, these two *çākhiṇāu* would leave a spirant free from duplication before an unaspirated surd mute, contrary to the first rule of the chapter. The groups which would be thus affected are *çc* and *çcy*, *çp*, *shk* and *shky* and *shkr*, *sh* and its further combinations (*shty*, *shtr*, *shve*), *shp*, *sk*, *st* and its further combinations (*stm*, *sty*, *str* and *stry*, *ste*), and *sp*. One hardly sees why combinations with a second mute (namely *çch* and *çchy*, *shkh*, *shth* and *shthy*, *sth* and *sthn*, *sph* and *sphy*) should not be subject to the same rule—but then, one must not expect to see the reason of anything whatever, general rule or particular exception, in this doctrine of duplications. It may be made a question whether the single case, *rsht*, falling under rule 4 is not also here aimed at; if the pair of kinsmen did not overlook it, it is doubtless included with the rest.

The examples (which are lost in W.) are *suçandra dasma* (iv. 4.4⁶: O. omits *dasma*) and *ashtāu kṛtvah* (vi.4.5¹); a counter-example, with a last mute after the spirant, is *tasmād evām vidu-shā* (vi.4.9²: O. omits *vidushā*); but O. has, with B., omitted to point out that this is a counter-example, and gives further, as such, *ishvā ca vajrena* (v.7.3¹).

The commentator then goes on to say that although the word *ca*, 'or,' in the rule brings down by implication a spirant pure and simple (without exclusion of any sound belonging to that class), yet the real application is only to *ç*, *sh*, *s*, and *h*, since otherwise the mention of *ç* and *ç* in rule 15 would be without meaning, their exception being assured by the present precept. The interpretation is doubtless true, but the reason given for it is only acceptable on the supposition that what is here put forward as the view of two individual authorities is in fact the accepted doctrine of the Prāticākhya; in any other case, there is no inconsistency or interference between rules 15 and 17, and the commentator should rather have said that, as the pair of dissidents doubtless accepted

17. *plākshiplākshāyanayor pakshe* 'prathamapara āshmā dvitvān nā "padyate. cakāra āshmānam anvādiçati. suçc-----: ashtāu-----' prathamapara iti kim.³ tasmād-----² prathamah paro yasmād asāu prathamaparah.⁴

cakāro 'tra' yady apy' āshmamātrākārshakas' tathā 'pi' ça-shasaheshv eva sampratyayah: anyathā 'vasāne ravisarjanīya (xiv.15) iti¹⁰ sūtre jīhvāmāliyopadhmānīyayor grahaṇām vyartham: anendī¹¹ 'va nishedhasiddheh¹².

¹ O. male. ² W. om. ³ B. O. om. ⁴ O. ina. prathamapara iti kim: ishvā....

⁵ G. M. O. om. ⁶ W. om. ⁷ G. M. āshmāk-. ⁸ W. O. hī. ⁹ G. M. om. ¹⁰ W. O. om. ¹¹ O. ina. shāf. ¹² W. O. -shedhe s-

rule 15, it was not necessary to regard the present statement of their views as having any reference to *z* and *q*. That the rule is accepted in the *śākhā* represented by the commentator may be inferred also from the fact that (under rule 22) he pronounces the five that follow unapproved, but says nothing of this.

उष्माघोषो हारीतस्य ॥ १८ ॥

18. According to Hārīta, a surd spirant is not doubled.

There is unusual variety and inaccuracy of reading among the different manuscripts of the commentary of this rule, and O. goes off upon a course of its own: yet the aim of all is the same, and not difficult to discover. The word *ūshmā* (which was present or implied in the two preceding rules, and therefore might naturally enough come down into this by continued implication) is here expressly repeated, for the purpose of breaking connection with what goes before. If *aghosha*, 'surd,' only were specified, and *ūshmā*, 'spirant,' implied, the latter would have to be implied along with the attributes attached to it above, namely "followed by a vowel," or "followed by a first mute," and to such a spirant the further qualification of "surd" would be given; while the meaning intended is that Hārīta would forbid the duplication of a surd spirant altogether, in any situation.

O. alone gives as first example *dārçyam yajñam* (iii.2.2³); all have *vāçyo manushyānām* (vii.1.1⁵); to which W. B. add *pushyati prajayā paçubhiḥ* (ii.4.8²) and *vāçvānarasya rūpam* (v.2.3² et al.), which O. omits, while G. M. substitute the single passage *asyā 'parāpam* (iii.5.7³). As counter-example, showing the limitation to a surd spirant, W. B. give *tiroahniyā mā* (vii.3.13: B. omits *mā*); but G. M. give instead *mahyam imān* (iii.1.9⁶), and O. *sapta jihvāḥ sapta* (i.5.3²).

18. ¹ *hārītasya* ² *mate* ³ *'ghosha ūshmā deivam nā* ⁴ *'padyate. 'dārç-.....* ⁵ *vāçyo-.....* ⁶ *'pushy-.....* ⁷ *vāçv-.....* ⁸ *aghosha iti kin: 'tiro-..... ūshmagrahaṇam* ⁹ *pūrvasūtrānapekshārtham: atra yady apy ūshmagrahaṇam na kriyate ūshme 'ty etat svaraparātvena* ¹⁰ *' sambaddham* ¹¹ *tasmād ihā 'pi tatsambandhasyāi 'vā* ¹² *'ghoshavattaviṣeṣaḥ* ¹³ *syāt: atas tannirṭtyartham ūshmagrahaṇam* ¹⁴ *atra kṛtam: atah sarvāvastha ūshmā 'tra dvitevanishedhabhāk* ¹⁵.

¹ O. begins *ūshmagrahaṇam pūrvasūtrānapekshātham: pūrvasūtre svaraparātvena prathamaparātvena ca sambandha iti aghoshagrahaṇam tasyāi 'ca viṣeṣaṇam syāt: atas tannirṭtyayeshu punar ūshmagrahaṇam hāri-etc.* ² O. ins. *śākhino.* ³ O. *sarvācāthā eva ūshmā 'ghosha nyo na dvivarnam ā.* ⁴ in O. only. ⁵ O. om.; G. M. *asyā-.....* ⁶ O. simply *sapta-.....* ⁷ W. *ūshmāyāg-;* G. M. *-āyāg-.* ⁸ W. B. *pūrvatran-.* ⁹ G. M. ins. *ca.* ¹⁰ W. *-bandham;* B. *-bandhak.* ¹¹ W. B. *ca.* ¹² W. *-vāte vī-;* B. *-vāte 'tī vī-;* G. M. *'ghoshavattaviṣeṣaṇam.* ¹³ W. B. ins. *na.* ¹⁴ G. M. *ūshme 'tī gr-.* ¹⁵ W. *n 'shedhāt;* B. *nī-hedhāya,* and adds, out of place, the first part of the comment to the next rule (to *rephaparo*, excl.).

Rules 18-22 are pronounced unapproved under rule 22.

रेफपरश्च हकारः ॥ ११ ॥

19. Nor *h*, when followed by *r*.

The word *ca* in the rule is declared to continue the implication of "according to Hārīta." This individual having in the former rule limited his denial of duplication to a surd spirant, and so left the sonant spirant *h* (? the MSS. say "a surd spirant") liable to be always doubled, it is now taught that *h* with the distinctive mark of a following *r* remains single. The example given, alike in all MSS., is *duduhre ahrayah* (i.5.5¹); counter-examples are *juhve* (i. e. *juhve*) *hy agnis tvā hvayati* (i.1.12; G. M. end with *agnih*; W. B. omit altogether, along with the introductory explanation to the next citation), to show that *h* would be doubled by Hārīta before any other letter than *r*; and *çukraṁ* (i. e. *çukkraṁ*) *te anyat* (iv.1.11²; O. omits), to show that any other letter than *h* would be doubled before *r*.

O., though using two of the citations given by the other MSS., has a wholly independent exposition of this rule.

टवर्गश्च तवर्गपरः ॥ २० ॥

20. Nor a lingual mute, when followed by a dental.

That is to say, in the opinion of Hārīta. Thus, in *vashat te vishno* (ii.2.12⁴; O. has *vishat te vikshane*, but it is doubtless only a corrupt reading) and *vid dravinam* (i.8.13¹ et al.), Hārīta would leave the groups *tt* and *ddr* untouched, while the rules of the treatise would require *ttt* and *ddd*. The other groups in which he would teach the simpler combination are *ttr*, *dd*, *ddhr*, and *rtt*; and *ts*, *tse* and *rts* would fall indirectly under the same exception, since, by v.33, *t* (converted to *th* by xiv.12) must be inserted between *t* and *s*: *ts*, then, would in Hārīta's hands become *tths*; in those of the regular adherents of this school, *ttts*. Counter-examples, of obvious application, are *vāk te* (i. e. *vākk te*; i.3.9¹; wanting in B. O.), *tat te* (i.3.9¹ et al.: found in W. only, and of no

19. 'pārvam āshma' 'ghosha ity ukte' 'ghoshoshmano nityam dvitve prāpte' 'vīṣiṣṭa idānīm' rephaparo hakāraḥ' cakārākṣṣṭa-hārītamate dvitvam nā' 'padyate. yathā': *dud*..... *rephapara iti kim*: 'juhve..... *hakāra iti kim*': *çukraṁ*..... *rephaparo yasmād asau rephaparah*.

⁽¹⁾ G. M. a. ⁽²⁾ W. vīṣiṣṭādinām; B. vīṣiṣṭācīdanam; G. M. vīṣinashtī id. ⁽³⁾ W. -re. ⁽⁴⁾ G. M. om. ⁽⁵⁾ W. B. om.
O. substitutes caṣabdo hārītasya 'vādeçakah: hārītasya çākhino mate rephaparo hakāro dvitvam āpadyate. *dud*..... *rephapara iti kim*: *juhve*.....

20. cakāro' hārītānvādeçakah²: 'tavargas tavargaparo na dvitvam āpadyate. yathā': 'vashat.....' 'vid.....' 'tavargah paro

account, since exempt from duplication by xiv.23), *shatkapālaṁ nih* (i. e. *shatṭk*; i.8.5¹: wanting in O.), and *vid vāi marutaḥ* (i. e. *vidd vāi*; vi.6.5²).

लतवर्गो यवकारपरौ ॥ २१ ॥

21. Nor *l* nor a dental mute, when followed by *y* or *v*.

Hārīta is this time implied "by vicinage" merely, there being no word in the rule to which his memory can be directly fastened. Examples of *l* before *y* and *v* are *kalyāṇi* (vii.1.6³) and *bāilvo yūpo bhavati* (ii.1.8⁴: G. M. omit *bhavati*); of a dental mute in like situation, *kanye 'va tunnā* (iii.1.11⁵) and *ishe tvā* (i.1.1 et al.). The accepted usage of the school requires *lly*, *llv*, *nnv*, *ttv*, while Hārīta would leave the groups as in the ordinary text.

Combinations of a dental mute with a following *y* or *v* are quite numerous (I have noted about twenty in the Sanhitā).

परश्च ॥ २२ ॥

22. Nor the following.

This rule completely puzzles the native comment, which has nothing of any value to say about it. Two explanations are suggested, evidently on the barest conjecture only, and it would be hard to say which of them is the more senseless. In the first place, it is said that *parah*, being singular, implies the sound *v* (as being the one last mentioned in the preceding rule); it, namely, of the two affecting causes (*y* and *v*) specified in rule 21, does not suffer duplication: examples are *vibhūdāvne* (iii.5.8 et al.) and *ā grā- enah* (vi.3.2²: W. B. omit *ā*); and a counter-example, showing the limitation to *v*, is *kalpān juhōti* (v.4.8⁶). And the intent of the rule is to remove a restriction imposed in rule 3 of this chapter—that is to say, to allow the duplication of *l* before a mute, which is there forbidden. In the second place, *parah* is said to be equivalent to *dvitīya*, 'second,' and to signify that, when the

*yasmād asāu tavargaparah. tavarga⁷ iti kim: 'vāk.....: 'tat
.....: evampara⁸ iti kim: 'shat.....: 'vid.....*

¹ O. *caṣabdo*. ² O. *-tasyā 'ne*.

³ O. Ins. *hāritasya cākhino mate*.

⁴ G. M. O. om.

⁵ G. M. om. ⁶ O. *tavargapara*.

⁷ W. *-gapara*.

⁸ B. om.

⁹ G. M. om.

¹⁰ O. om.

21. *hārītaḥ sāmniḍhyāl lobhyate: tanmate latavargāu na khalu yavakāraparāu dvitvām āpnuṭaḥ. 'yathā: lakāraḥ: 'kalyāṇi: bāilvo.....: 'tavarge 'pi: 'kanye.....: ishe..... yavakāraū¹ parāu yābhyām tāu tathoktāu².*

¹ G. M. om. ² G. M. om. ³ W. B. *-ra*. ⁴ G. M. *yavakāraparāu*.

My collation of O. gives nothing whatever upon rules 21 and 22 and their comment, and I do not know whether there is a *lacuna* in the MS., or whether the collator has overlooked the passage.

duplication has been once performed, it is not done over again, as otherwise the process would go on *ad infinitum*. And if it be objected that rule 23 sufficiently forbids this repeated duplication, and that this one would therefore be an unnecessary repetition, the answer is made that that is no fault, since the matter in hand is a division of opinions—that is to say, doubtless, that here Hārīta's view only is concerned, and so there is no necessary connection between the two rules.

Fortunately, the commentator is able to add that the present precept, along with its four predecessors, is to be ruled out of account as unapproved, so that what it means is of very little consequence.

सवर्णसवर्गियपरः ॥ २३ ॥

23. A letter followed by one homogeneous with itself, or one of the same mute-series, is not duplicated.

By *savarṇa*, 'of like color or sound,' we are told, is signified identity of form, not merely correspondence as regards place and organ of production. The difference is, that the latter description would apply to the spirants, in their relation to the series of mutes (ii.44,45), and it is not the usage of this school to exempt the spirants (except *χ* and *φ*, rule 15) from duplication, even before a mute with which they are akin. The Ath. Pr. (iii.30) does so exempt them. The epithet *savarṇa*, then, applies only to an identical letter and to the nasal semivowels into which (by v.26,28) *n* and *m* are converted before *y*, *l*, and *v*.

The cited examples of the application of the rule to homogeneous sounds are *atvakkāya* (vii.5.12²), *attā haviṣhi* (ii.6.12²), *pippakā te śaravyāyāi* (v.5.19: only O. has the last word), *sanīyattāh*

22. *cakāro hārītākaraṣhakāḥ*¹: *para ity ekavacanena*² *vakāro*³ *grhyate*: *pūrvasūtrasthanimittayoḥ*⁴ 'so 'pi' na *deitvam* āpad-yate. *yathā*: *vī*..... *ā*..... *vakāra* itī kim: *kalpān*..... *sparga*⁵ *evāi* 'keshām ācāryānām (xiv.3) *ity* 'atrā' *vadhā-rananirākaraṇāyā* 'yam' ārambhah. *athavā*⁶: *taddeitve*⁷ *krte pa-ro deitiyaparyāyo*⁸ ¹⁰ *deitvavidhir nā* 'sti'¹¹: *anavasthāprasāṅgāt*. *nanu savarṇasavargīyapara* (xiv.23) *itī parasūtrenā*¹² 'pi *punardeitvanishedhaḥ*: ¹³ *pāunaruktyam mā bhūd itī*¹⁴: *mata-bhedān nāi* 'sha'¹⁵ *dosha itī brūmah*.

*hārītamātā*¹⁶ *āśhmā* 'ghoṣha (xiv.18) *ityādīsūtrapañca-kam*¹⁷ *anīṣṭam*.

¹ G. M. -*tamatik*. ² W. *eva* v-. ³ W. *see*, and puts after *grhyate*. ⁴ G. M. ins. *paraḥ*. ⁵ G. M. ins. *hārītamate*. ⁶ G. M. -*ṣapara*. ⁷ G. M. *evandhā*... -*ṇdyāyā* 'yam'. ⁸ W. B. *yathā*. ⁹ G. M. om. *tad*. ¹⁰ G. M. -*āyena*. ¹¹ G. M. -*dhīn* na *prāp-noti*. ¹² W. om. *para*. ¹³ G. M. ins. *tasmāt*. ¹⁴ W. -*kyo mā bhavati*; G. M. -*kyam āvahati*. ¹⁵ W. *va*. ¹⁶ G. M. -*mate*. ¹⁷ G. M. *ityādī paraḥ ce* 'tyantam sū-. O. wanting (see above).

(i.5.1¹ et al.: wanting in W. B.), *yal lohitaṁ* (ii.1.7²), and *tvam vā-tār arundāh* (i.3.14¹: only O. has *arundāh*). Those which illustrate absence of duplication of a mute before another of the same series are *aṅkāu nyanākaṁ* (i.7.7²), *prāñcam upa* (v.2.7³: O. omits *upa*), *kāṇḍāt-kāṇḍāt* (iv.2.9² et al.), *taṁ te dṛṣṭakṣhāh* (iii.2.10²), and *ambha stha* (i.5.6¹ et al.). Then the commentator quotes from some unnamed authority a verse prescribing that "when a nasal precedes, a *k* or *g* is inserted before *t* or *dh* respectively," and claims that, in virtue of it, there fall under the rule also such cases as *pāṅkto yajñah pāṅktāh* (i.5.2¹ et al.: G. M. O. omit the last word) and *tān brūyād yajñgdhvam iti* (iii.4.8²: O. omits the first two words). From this we should draw the inference that, in forms like those here quoted, the omission of the non-nasal mute (specially prescribed by the Ath. Pr., at ii.20) is the regular and proper reading of the *śākhā*, its presence, when found, being regarded as an irregular insertion, or a process forming part of the *varṇakrama*—which is just the opposite of the etymologically correct view. I have not collected all the passages illustrating the point, but the omission is certainly the prevailing, though not exclusive, reading in my manuscript of the Sanhitā, as also in the Calcutta edition. That the verse quoted is from some treatise dealing specifically with the Tāittiriya text may be inferred (not too confidently) from its making no mention of *th* as requiring the insertion of *k*; it being the fact that no example of *th* in such a situation is to be found in the Sanhitā.

Finally, as counter-examples, where the two mutes are of different classes, we receive (except in O.) *vān ma āsan* (v.5.9²: G. M. end with *me*), *śan māsaḥ* (vi.5.3⁴), *vidathāni manmahe* (iv.7.15³), and *dāmnā pāu mbhan* (ii.4.13: W. B. have *dāmnā* only): here the combinations are to be made *śām*, *nam*, *nm*, and *mm*. The illustrations are quite one-sided, both for and against the rule, being only groups containing a nasal.

This rule furnishes the most important of all the prescribed

23. *savarṇaparaḥ savargīyaparaḥ ca dvitvaṁ nā "padyate: savarnatevaṁ nāma śārāpyam" ucyate: na tulyasthānakaraṇatā-mātram: savargīyaḥ samānavargasambandhā. yathā: atvak-kāya: attā..... pipp..... saṁyattāḥ: yal..... tvam..... savarnaparāny evamādini: savargīyaparāny⁵ api vadā-mah: aṅkāu..... prāñcam..... kāṇḍāt..... taṁ..... ambha.....*

anunāsikapārvas⁶ tu kakāro madhya⁷ āgamah:

gakāraḥ ca takāre⁸ ca dhakāra ca⁹ yathākramam.

itivacanād idam apy udāharanam: pāṅkto..... tān.....

evampara iti kim: vān..... śan..... vīda..... dāmnā.....

¹ B. *pyateam*. ² W. B. om. ³ W. *savarṇap*. ⁴ W. *eva*. ⁵ W. *anuvārap*. ⁶ W. *dhya*. ⁷ O. *-raḥ*. ⁸ W. om.; G. M. *yak*. ⁹ O. om.

restrictions to the sphere of duplication, as there are somewhat over a hundred consonant groups to which it applies.

नानुत्तम उत्तमपरः ॥ २४ ॥

24. Unless, indeed, it be a non-nasal followed by a nasal.

This is a precept of counter-exception, contravening in part the exceptions established by the foregoing rule. Examples are *yācñā* (i.5.7⁴: the only example of this combination which the text affords), *yajñe-yajñe* (iii.1.11²: but O. has *yajñena*, vi.5.3¹ et al.), *ātnārah* (v.6.5³: also the sole instance), *sa pratnavat* (ii.2.12¹ et al.: in O. only), and *pāpmānam* (i.4.41 et al.): a counter-example is *tam mā devāh* (iii.3.2²: wanting in O.).

The cases here denied exemption from duplication are those in which, according to xxi.12, *yama* is introduced between the two mutes. According to the Vāj. Prāt. (iv.111), *yama* suspends duplication.

अथैकेषामाचार्याणाम् ॥ २५ ॥

25. Now for the views of certain teachers.

A simple heading for the rules that follow, in force as far as rule 28 inclusive—or, according to the commentator's interpretation of rule 28, through 27 only.

लकारो कृशवकारपरः ॥ २६ ॥

26. A *l* is not doubled when followed by *h*, *ç*, or *v*.

The commentator's examples are *malhā ā 'labhanta* (ii.1.2⁴: but B. O. have *-bhata*, which is found in the same division, and G. M. read *-bhate*, which is doubtless a corruption of the same), *çatavalço vi roha* (i.3.5 and vi.3.3²: O. omits *vi roha*), and *tato bīlvah* (ii.1.8²: O. substitutes *bāilvo yūpah*, ii.1.8¹); his counter-examples (omitted in O.) are *kalmāshī* (v.1.1⁴) and *kalyānī* (vii.1.6⁶).

This rule, we are told, determines the usage of the school so far as the combinations *lh* and *lç* are concerned, but not in the case of

24. *nakdro 'yam pratiprasavārthah*¹: *'uttamaparo 'nuttamo dvitvam āpadyate. yathā*²: *yācñā*: *yaj-----*: *ātnārah*: *'sa-----*³ *pāpmānam*. *'anuttama uttamapara iti kim*: *tam-----*⁴ *uttamah paro yasmād asāv*⁵ *uttamaparah. savarnasavargīyapara*⁶ (xiv.23) *iti pratishedhaprāptāv ayam ārambhah*.

¹ O. *pravārtha*. ² G. M. om. ³ O. om. ⁴ in O. only. ⁵ O. om.; B. om. *anuttama*; W. om. *uttama*. ⁶ G. M. om. *para*.

25. *athe 'ty ayam ādhikārah*: *ekeshām*¹ *mate*² *kriyata*³ *ity etad ādhikṛtaṁ veditavyam ita uttaram yad vakshyāmah*.

¹ G. M. ins. *doṣyāpām*. ² G. M. *matem*; O. *maçcitam*. ³ G. M. O. *adhikri*.

lv. But *O*. has an inserted passage, so corrupted as to be hardly intelligible, which quotes a verse (easily made such by a little emendation) from some authority unspecified, making a distinction between *lv* as occurring in a circumflexed syllable or otherwise—that is to say, between *bīlēh* and *bāileāh*.

All the groups here treated of are quite rare, *lv* occurring, I believe, only in *calga* (vii.3.19) and its compounds, and *lh* only in *malha*; *lv* is sometimes found also as the result of *sandhi* (as at i.5.9⁶: ii.5.1⁴).

The commentator adds, finally, that the next rule also is not approved.

स्पर्श स्पर्शपरः ॥ २७ ॥

27. Nor a mute that is followed by a mute.

This is a view of certain authorities merely, and unapproved. The examples are *vāg devī* (i.7.10²), *apām ojmānam* (iv.6.6⁶), *ātñārah* (v.6.5²), *sa pratnavat* (ii.2.12¹ et al.), and *yam apnavā-nah* (i.5.5¹): *O*. has only the first two of them.

पदान्तश्च व्यञ्जनपरः प्राकृतः ॥ २८ ॥

28. Nor an original final that is followed by a consonant.

The natural meaning of this rule would appear to be simply that, in the opinion of some authorities, a final mute which is not the product of euphonic alteration is exempted from duplication before any initial consonant whatever (not before a mute only, as in the preceding rule). The commentator, however, manages to extract from it a very different value: namely, that *n* final is not liable to duplication before a semivowel or spirant (i. e. *h*); and he regards

26. ¹ *ekeshām* ² *mate haçavakāraparo lakāro* ³ *dvitvaṁ nā* "padyate. *malhā*.....: *çata*.....: *tato*.....: "evampara iti *kim*: *kalmāshī*: "kalyāṇī". *hakāraç ca çakāraç ca vakāraç ca haçavakārāḥ*: *te* ⁴ *pare yasmāt sa tathoktaḥ*.

atra ⁵ *haçapare kāryam iṣṭam* ⁶ *na tu vakārapare*: " *nā* ⁷ *pi pa-rasūtram* ⁸ *iṣṭam*.

¹ G. M. ins. sa. ² G. M. O. ins. *ācāryāṇām*. ³ G. M. *lavakāro*. ⁴ O. om. ⁵ W. om. ⁶ O. etc. ⁷ G. M. O. om. ⁸ O. ins. *lakāraṣya haçavakārapara iti sūtre sthitaḥ kiñ kāraṇam nanu vakāra iti prayojanam asti*: *lakāravakāraṣya saṁyoga svarito yañi*: *tadā saṁyukta eva syād asaṁyuktas tadanyathā*: *iti vacandm asti tasmāt kā-raṇāt*: *yadā lakāravakārapara iti*: *tato bīlēh*. ⁹ O. *sūtram*.

27. *ekeshām* ¹ *mate sparçapara sparço* ² *dvitvaṁ nā* "padyate". *vāg*.....: *apām*.....: " *ātñārah*: *sa*.....: *yam*.....: " *sparçah* *paro yasmād asāu sparçaparah*.

¹ O. ins. *ācāryāṇām*. ² O. puts next after *mate*. ³ O. *na dvitvaṁ āpnoti*. ⁴ O. om.

this as the accepted doctrine of the school, and as determining the reading in this *śākhā*. How this strange result is arrived at, we have to follow through his lengthy exposition closely enough to discover.

In the first place, *vyāñjanapara*, 'followed by a consonant,' is declared to mean 'followed by any other consonant than a mute,' because otherwise, as we have read 'followed by a mute' in the preceding rule, the treatise would be guilty of a needless repetition so far as sequence by a mute is concerned. To this the natural answer would be that the two rules do not come into collision, since they do not occupy the same ground: the former relates to any mute in any situation, the latter only to an unaltered mute at the end of a word; and if the one is declared to have a single pronunciation before a mute only, the other before any consonant whatever, what objection can possibly be taken? Moreover, we are stating here the views of certain authorities, of whom one set might hold rule 27, and the other rule 28: and even if they partly covered one another, there would be nothing wrong about it. Once more, *sparṣapara* is claimed to be implied here merely for the purpose of denying it, the commentator's conclusion being that there is duplication of *n* before a mute, though not before a semi-vowel; and that is certainly a very remarkable kind of *anuvṛtti* which should work thus by contraries. Of the last two considerations, the commentator takes no notice (although he has once appealed to the former of them in a somewhat similar case above, under rule 22): the first he states and replies to. It may be objected, he says, that there is a difference of affecting cause laid down in consequence of the difference of the affected letter; the latter is here qualified as final and as original; and the former as being any consonant whatever. Nevertheless, he claims, there would be meaninglessness of the qualification of the affecting cause,

28. *vyāñjanapara iti sparṣavyatiriktavyāñjanapara ity arthaḥ: anyathā sparṣānām api grahane pūrvasūtre 'pi sparṣa' ity ukta-
tvāt pūrnaruktyaiḥ syāt. nanu nimittaviśeshān² nimittaviśesho³
'sti: padāntatvam prakṛtatvau ca nimittino⁴ viśeshā⁵ nimittasya
tu sarvavyāñjanātmakatvam⁶: iti cet: tathā 'pi sparṣabhāge⁷ ni-
mittaviśeshasya⁸ vāiyarthyam⁹: sparṣapara ity¹⁰ atra sāmānyenā¹¹
'pi¹² nimittaviśeshasya¹³ vigatatrāt¹⁴: tasmād¹⁵ antasthādāya evā¹⁶
'tra vyāñjanaçabdeno¹⁷ cyante. 'cakāro yady api sparṣamātrā-
karshakas tathā 'pi pāriṣeshyān¹⁸ 'nakārasyā¹⁹ 'nukarṣaṇam²⁰:
tathā hi: antasthādīvyāñjanaparatve 'nyasparṣānām²¹ avikṛtā-
nām padānte sthitir nā²² 'sti: samrād ity atra²³ 'sti 'ti cet: māi²⁴
'vam: na sañ sām iti²⁵ rāpara (xiii.4) ity atra vāiyarthyāt²⁶:
itiçabdo makārasya dvitvasadbhāvam bodhayati²⁷ 'ty²⁸ adhyayanā-
nurodhād upapāditaḥ: tasmān nāi²⁹ 'sha nishedhaviśayaḥ. 'nā³⁰
'i brahmaṇvantah: nyañ.... ityādiviśayaḥ³¹ kutaḥ: iha*

so far as mutes were concerned: the reason he gives is of course a mere quibble, and the point of it is so fine that I am not confident of seeing it rightly: it seems to be, that there is an absence of such qualification in the implied term *spargapara*. At any rate, the comfortable conclusion is, that only the semivowels etc. are intended by the term "consonant" as employed in the rule. The next step is, to declare that *ca*, 'nor,' although it strictly brings forward 'a mute,' without qualification, yet really amounts, on the principle of exclusion, to an implication of *n* only. Namely, thus: no other consonant remains unchanged at the end of a word before a semivowel or spirant. It may be objected that *m* also does so before *r* (by xiii.4) in such words as *samrāj*: but this is of no account; for, if admitted as a reproach to the interpretation now under treatment, it would convict of superfluity a part of rule xiii.4: namely, the *iti*, which was shown, in accordance with the received reading of the *śākhā*, to teach the duplication of the *m*. We see now why that atrociously forced and groundless construction of the meaning of rule xiii.4 was made; it was needed to bolster up in advance the forced and groundless construction to be put upon the present precept. As the *m*, then, constitutes no ground of exception, so neither do the nasals *n* and *ṇ* in such cases as *brahmaṇvantaḥ* (vi.4.10¹) and *nyān ragmibhiḥ* (ii.4.10²). For why? the qualification *prākṛta*, 'original,' in the rule involves [as belonging to the letter to which it is applied] the quality of being alterable, since it would otherwise be meaningless; and there is no case to be found where either *n* or *ṇ* is altered before a semivowel or spirant. If, then, the term *prākṛta* is to be allowed its proper force, the implication of any other mute than *n* must be excluded. Here is another most arbitrary act of construction—as if *prākṛta* meant necessarily '(an alterable mute) when it retains its original form,' instead of simply '(a mute) that retains its original form.'

prākṛta iti viśeṣaṇam vikṛtasadbhāvam²¹ kalpayati: "anyathā svasya²² vāiyarthyaḥ: tac ca vikṛtatvam nakārasya²³ ākārasya²⁴ vā 'ntasthādiparatve²⁵ sati kvacid api padānte na dṛṣyate: tasmāt prākṛta iti²⁶ prayogasāphalyāya²⁷ nakārasyaḥ²⁸ vā 'nukarṣaṇam yuktam iti pāriṣeṣyam.

kim ca: māhisheya 'pi nakārasyaḥ²⁹ vā 'nukarṣaṇam siddhavatkrtyo³⁰ 'ktam: "tatre 'yam sūtrayojanā³¹: ekeshām³² mate padāntaḥ prākṛto nakāro 'ntasthādīyañjanaparo³³ na dvitvam āpadyate. yathā: mitro-----: om-----: etān----- padānta iti kim: anyā-----: anv----- antasthādipara iti kim: tān-----: imān----- prākṛta iti kim: tān-----: "vāish-----³⁴ nanu katham atra³⁵ vikṛtatvam:

rephād ṛvarṇāt³⁶ pūrvaḥ ca ṭavargāc³⁷ ca paraḥ ca naḥ³⁸: ṭavargasthāna³⁹ ity āhur atasthāno⁴⁰ 'nya⁴¹ ucyate. iti vacanād asti sthānabhede⁴² kṛtam⁴³ vikṛtatvam⁴⁴ iti brāmaḥ.

The authority of Māhisheya (see note to the introductory verses, p. 7) is further appealed to as making the same restriction of implication. His explanation is that, in the view of some teachers, a final unaltered *n* followed by a semivowel or spirant is not doubled. Examples are *mitro janān yātayati* (iii.4.11⁵: only G. M. have *mitro*), *omanvati te* (ii.6.9⁵: p. *oman-vati*), and *etān homān* (i.5.4⁴); in all which we are to understand that the *n* remains single. On the other hand, there is duplication in *anyā* (i. e. *annyā*) *yanti* (ii.5.12²) and *anv* (i. e. *annv*) *aha māsāh* (i.7.13¹), where the *n* is not final; in *tān* (i. e. *tānn*) *kalpayati* (v.3.1²) and *imān* (i. e. *imānn*) *bhadrān* (i.6.3¹), where the *n* is followed by a mute; and also in *tān rakshadhvam* (i.2.7) and *vāishnavān rakshohanah* (i.3.2²), where, it is asserted, the *n* does not maintain its original form. Since, however, there is no rule in the Prāticākhya for altering a *n* in this last pair of cases, the commentator quotes (from the same authority, we may conjecture, which has been recently twice appealed to, under rules 23 and 26) a prescription to the effect that *n* when preceding a *r* or an *r*-vowel, or when following a lingual (the MSS. say, a dental) mute, is uttered in the lingual position: thus, he says, in virtue of its change of position, the *n* is phonetically altered. Finally, he makes an alleged citation from the Çikshā (not found in the version known to us), which teaches that a final *n* preceding *r* exhibits a peculiarity, and is liable to duplication. Such a modification of the utterance of *n* forms no part of the phonetic system of any of the Prāticākhyas.

Thus is brought to an end the tedious subject of duplication, the physical foundation of which is of the obscurest, although the pains with which the Hindu *gākḥināh* have elaborated it, and the earnestness with which they assert their discordant views respecting it, prove that it had for them a real, or what seemed like a real, value.

gikshā cāi 'eām vakshyati:

"rephāt pūrvo" nakāro yah padānte" yatra" dr̥cyate:

viśeṣam tatra jānīyād deitvam ity" abhidhīyate.

"vyañjanam asmāt "param iti" vyañjanaparāḥ: prakṛtiḥ" svabhāvaḥ: tatsambandhi prakṛtaḥ.

¹ O. -*capara*. ² G. M. -*ttavaçin*; O. -*ttanimittav*. ³ G. M. -*viçishṭa* 'py artho; O. *nānimittikaviçeṣo* 'py a. ⁴ G. M. -*ito*. ⁵ G. M. O. -*shah*. ⁶ G. M. -*kam*. ⁷ G. M. -*çavibh*. ⁸ G. M. -*çishṭe* 'sya. ⁹ O. -*rthye*. ¹⁰ O. *avyañjanasāmānye*; G. M. om. *apī*. ¹¹ G. M. -*syā*; O. -*sha*. ¹² G. M. 'pi g-; O. *pag*. ¹³ O. om. ¹⁴ W. B. *cakāra* *aparçakṣharapāri*; G. M. *cakāra* *sthānispārçakarshakah* *pariçeṣyan*. ¹⁵ B. *takāra* *karshayan*. ¹⁶ G. M. O. *saty any*. ¹⁷ G. M. ins. *tu*. ¹⁸ G. M. om. ¹⁹ W. om. *iti*. ²⁰ W. om. ²¹ W. -*āve*. ²² G. M. om. ²³ B. *svarasya*. ²⁴ W. B. *nak*. ²⁵ W. *dak*; B. om. ²⁶ O. *divyañjanop*. ²⁷ W. -*silkal*. ²⁸ O. -*dāhev*. ²⁹ O. om.; B. G. M. *tatrāi* 'eām s-; G. M. -*tre yo*. ³⁰ O. ins. *ācāryaṇām*. ³¹ W. -*sthāv*. ³² O. om. ³³ W. a. ³⁴ W. O. *av*; B. v-; G. M. *rav*. ³⁵ all the MSS. *ta*. ³⁶ G. M. *na*. ³⁷ W. B. O. *ta*. ³⁸ W. O. *ata sth*; G. M. *asthāne*. ³⁹ G. M. om. ⁴⁰ O. -*da*; G. M. -*dāt*. ⁴¹ G. M. om. ⁴² O. ins. *astī*. ⁴³ all but O. *rephap*. ⁴⁴ W. G. -*to*. ⁴⁵ G. M. *yadī*. ⁴⁶ B. om. ⁴⁷ O. ins. *cakāro* *kanasyarçakarshakah*. ⁴⁸ W. *paro*. ⁴⁹ G. M. O. -*tir iti*.

उदात्तात्परोऽनुदात्तः स्वरितम् ॥ २१ ॥

29. A grave following an acute becomes circumflex.

The following rule shows that the substantive here to be understood is *svarah*, 'vowel.' All the other Prātiśākhya's, in their corresponding rules (R. Pr. iii.9, V. Pr. iv.134, A. Pr. iii.67), state the principle as applying to an *aksharam*, 'syllable.' In his explanation and illustration, however, the commentator is not careful to bear this in mind. He states the sphere of the rule to be all the three kinds of enclitic circumflex, the *prātihata* (xx.3), *pādaṛṣṭa* (xx.6), and *tāirovyañjana* (xx.7), although these in part include cases to which only the next rule attributes the circumflexed quality. And his examples are *sā idhānāḥ* (iv.4.4²), *āthā 'bravīt* (iii.2.11²), *vāsavy asi* (i.2.5¹ et al.), *prāugam* (iv.4.2¹), and *tāyā devātayā* (iv.2.9² et al.); of which only the first and fourth show the circumflex vowel following the acute without an intervening consonant (rule 30). Nor are all the examples unexceptionable in other respects: for though the *i* of *idhānāḥ* and the *a* of *asi* are really *anudatta*, 'grave,' in the *pada*-text, and so show an actual conversion into circumflex, the other exhibited cases of enclitic circumflex are circumflexed in the *pada*-text as well, and undergo no alteration in consequence of their change to *samhitā*. It is at this that the commentator aims, when he adds that, "there being grave quality in the condition of separation of letters, then, when these are combined together, circumflex quality appears in accordance with the present precept." That is to say, it is the natural unaccented quality of the syllable that is here implied in *anudatta*, not its being technically grave, and marked as such. This understanding is also needed in order to make good rule 31, where we are not taught that the enclitically circumflexed final of *ātha*, for example, becomes grave before an acute or circumflex (as in *ātha tvām*, *ātha kvā*), but that the unaccented final *a*, which was made circumflex by rules 29 and 30 after *ā*, is exempted from the change when so followed, and remains unaccented.

The enclitic circumflex is written in the recorded Tāittiriya text in the same manner as in the Rik and Atharvan; namely, by the perpendicular stroke above the syllable, the same that is used for the independent circumflex. The method is so familiar to all students of the Veda that it does not need to be illustrated here. Certain specialties of Tāittiriya usage will come up for notice under later rules (xix.3, xxi.10,11).

29. *prātiḥatapādaṛṣṭatāirovyañjanavishayam*¹ *etat: udāttāt paro 'nudāttah svaritam āpadyate. yathā: sa.....: athā.....: vāsavy.....: pra.....: tayā.....: varṇavibhāgāvasthāyām anudāttatve saty² eva punas tatsamhitāyām³ eva⁴ tallakṣhaṇasavaritātvam⁵ prāugam ityādāu vijñeyam.*

¹ O. om. *pādaṛṣṭa*, and ins. *prāṛṣṭa* before *-vish*. ⁽²⁾ W. *evā* 'dhaṣṭāt samhi-'.
³ G. M. O. om. ⁴ G. M. O. *etallakṣhaṇāt sv*.

For an exposition of the place and value of the enclitic circumflex in the Hindu accentual system, see the note to Ath. Pr. iii.65. It may doubtless admit of question whether the Hindu phonetists, in noting the syllable naturally grave as being otherwise than grave when immediately preceded by an acute, would not have apprehended it better, and described it more truly, as a middle tone between acute and grave, rather than a combination (i.40) of acute and grave. Arguments drawn from the analogies of the Greek and Latin accentual systems (see F. Misteli, in Kuhn's *Zeitschrift*, vol. xvii., 1868; also Prof. J. Hadley, in the *Proceedings of the Am. Oriental Society* for Oct. 1869 [*Journal*, vol. ix., pp. lxii.-lxiii.]) may press upon us this latter view as the more plausible. But that any one having access to the sources of knowledge upon the subject should dispute the substantial identity in physical character of the Greek circumflex and the Sanskrit independent *svarita*, and should set down the latter as a "middle tone," in the face of all authority and of all sound phonetic theory, savors of inexcusable carelessness or prejudice.

व्यञ्जनान्तरहितो ऽपि ॥ ३० ॥

30. Even when consonants intervene.

For the necessity of this explicit statement, see the note on the preceding rule. The commentator, having already given under the latter several cases in which the affected and the affecting vowel were separated by one or more consonants, has nothing that is new to offer; but he quotes, nevertheless, *tād agne anró bhavāmi* (iii. 3.8²: B. O. omit *bhavāmi*) and *yás tvá hrdá* (i.4.46¹): in the first case, *ag-* and *bha-* are circumflexed; in the second, *tvá*.

नोदात्तस्वरितपरः ॥ ३१ ॥

31. Not, however, when an acute or circumflex follows.

That is to say, the syllable naturally unaccented or grave—but which, coming next after an acute, would usually take, by rule 29, the tone of transition from higher to lower pitch—retains its low or grave tone if immediately followed by an acute, or by a (*nitya* or independent, of course) circumflex, of which the first element is acute: the pitch of voice is governed by the following tone in preference to the preceding, and sinks at once, without perceptible movement of transfer, to the level of *anudatta*, as a vantage-ground from which to rise to the immediately succeeding high point.

In this rule, as well as that to which it constitutes an exception,

30. *vyañjanāntarhito* 'py *udāttāt paro 'nudāttah svaritam* 'āpadyate. *yathā*: *tād*.....: *yas*..... 'ity ādi'. *antarhito vya-vahita ity arthah*.

¹ O. ant-. ² B. -tatam. ³ G. M. om. ⁽⁴⁾ O. om.

all authorities are agreed (see note to Ath. Pr. iii.70); although we should not less naturally expect the double attraction, of a high tone on either hand, to exercise at least as much assimilating effect upon the pitch of an intermediate syllable as a preceding high tone alone exerts.

The commentator's examples are *sá imám lokám* (i.5.9⁴: but G. M. add *ajayan*, which doubtless means *tá imám lokám ajayan*, vii.1.5³), *tásmát tá ádyā annadhānāt* (vii.1.1⁵: only O. has the first word and the last), *kīrinā mānyamānah* (i.4.46¹), and *tāsyāi vyṛddham āndām ajāyata* (vi.5.6¹: only G. M. have the last two words): the vowels between acute and acute, or between acute and circumflex, in these examples, are *anudatto*, and written, as such, with the horizontal stroke beneath.

The three rules here given only apply, in strictness, to a single unaccented syllable following an acute; where there is more than one such, the rules for *pracaya* (xxi.10,11) come into force.

नाग्निवेश्यायनस्य ॥ ३२ ॥

32. Not so, according to Āgniveṣyāyana.

The significance of this rule (which is declared unapproved, in the comment to its successor) is more clearly stated by O., in an independent exposition, than by the other four versions of the comment. It is meant to exhibit an opinion contravening the doctrine laid down by its predecessor, and allowing the circumflex accent to stand, even when the following syllable has, or begins with, the high tone. No examples are given, except by O., which has *vódhavyē* (i.6.2¹ et al.) and *tāsyā kvā suvargāh* (ii.6.5⁵).

G. M. read, in rule and comment, Āgnivāṣyāyana.

सर्वी नेत्येके सर्वी नेत्येके ॥ ३३ ॥

33. Some say not, in all cases.

31. *udāttasvaritapara¹ udāttāt paro 'nudatto na² svaritam apadyate³. yathā⁴: sa.....: tas.....: kīr.....: tasyāi..... udāttas ca svaritas co 'dāttasvaritāu: tāu parāu yasmāt sa tatho 'ktah.*

¹ W. -*paro nān*; B. *svaritaparo vā*; G. M. *udāttapara svaritaparo vā*; O. do., except *vā*. ² G. M. O. put after *svaritam*. ³ B. *apnoti*; O. *prāpnoti*. ⁴ G. M. om.

32. *pūrvasūtrapratiprasavārtho¹ 'yam nakārah: udāttāt paro 'nudattaḥ svaritam² āgniveṣyāyanasya³ mata udāttaparo⁴ vā⁵ svaritaparo vā⁶ nā⁷ 'padyata iti na⁷. pūrvoktāny evo 'dāhara-nāni.*

¹ B. -*trasya prati*-. ² G. M. om. ³ G. M. -*yana*. ⁴ W. B. G. M. -*ttāt pa*-. ⁵ B. -*udatta*; G. M. om. ⁶ B. G. M. ins. *svaritam*. ⁷ B. om.

O. substitutes *āgniveṣyāyanasya cākhino mata udāttapara svaritaparo vā udāttāt paro 'nudatta svaritam apadyate na pratishedhaḥ. yathā: vo.....: tas.....*

According to the majority of MSS. of the comment, the denial of these skeptical people is not limited to the enclitic *svarita*, but extends to the whole accent, in all its seven forms (xx.1-8). Thus, namely; in the *brāhmaṇa* of the Vājasaneyins (that is to say, the *Çatapatha-Brāhmaṇa*) there are only two accents, the acute and the grave. But O. has once more a version of its own, stating that the authorities here referred to would not, like Āgñivegyāyana, annul rule 31 simply, but would also deny the rules in general for the enclitic circumflex, as in *sā idhānāh* (iv.4.4¹) and *prapā* (? MS. *prathā*) *asi* (ii.5.12⁴). We cannot well hesitate to prefer the latter interpretation; there has been no question here of the independent circumflex, and a denial of its existence would be altogether out of place and impertinent. Nor is the reference to the *Çatapatha-Brāhmaṇa* one at all likely to have been intended by the *Prāticākhya*. And it is not true, except so far as the mode of designating the accents is concerned, that that treatise has no circumflex accent: it writes, to be sure, only the *anudātta* sign, so that, if the value of this were the same as in the other usual systems of designation, all its syllables would be either grave or acute: and on this foundation, later Hindu systematists have declared them such, and painfully elaborated an exposition of them (see Weber's Ind. Studien, x. 397 ff.).

Rules 32 and 33 are, naturally enough, declared unapproved; but to us it is both interesting and important to find that there were Hindu phonetists in the ancient time who did not admit such an element of utterance as the enclitic circumflex.

CHAPTER XV.

CONTENTS: 1-3, nasalization of vowels, or insertion of *anusvāra*, in cases of the loss or alteration of *s* or *m*; 4-5, the same, in the cases detailed in the next chapter; 6-8, the same, in the case of certain finals; 9, utterance in monotone.

33. *na kevalam udāttāt paraḥ: kiṃ tu sarva eva saptavidha-svarito nā'sti 'ty eke gākhino manyante. tathā hi: vājasaneyi-brāhmaṇe' dvāv eva svarāu: udāttaḥ cā 'nudāttaḥ ca. ne 'daṃ sūtradvayam' iṣṭam.*

O. substitutes *eke gākhino manyante na kevalānudāttaḥ udāttaḥ svaritaparāḥ: prati-shidhyati kiṃ tathā udāttakopāvekaḥ ca: sa..... prathā..... ne 'daṃ* etc.

*iti tribhāshyaratne prāticākhyavivarane
caturdaśo' dhyāyah.*

¹ W. *vājanepibrah-*; B. *-nehibr-*; G. M. *-neyabr-*. ² W. *-tram*. ³ G. M. O. *dvitiye praṇe dvitiyo*.

नकारस्य रेफोष्मयकारभावाद्युक्ते च मलोपाच्च पूर्वस्वरो ञ्नुनासिकः ॥ १ ॥

1. In case of the conversion of *n* into *r*, a spirant, or *y*—also when the *y* is omitted—or in case of the omission of *m*, the preceding vowel becomes nasal.

That this Prāticākhya takes no distinct and consistent ground upon the question whether the so-called *anusvāra* consists in a nasalization of the vowel or in a nasal consonantal element following the vowel, has been already pointed out (note to ii.30); as also, that the present rule is the one where the former view is most unequivocally taken. As the school to which the commentator belongs has adopted the other view, he declares (under rule 2) that the doctrine here laid down is unapproved.

The "conversion of *n* into *r* or a spirant" is, of course, the retention of a historical final *s* after *n* unchanged before *t* (vi.14), or changed to *ç* before *c* (v.20), or to *r* before a vowel (ix.20 etc.); its "conversion into *y*," with the (invariably) consequent "loss of the *y*" (ix.20 etc., x.19), goes back to the same cause. The commentator's illustrative examples are *aymīr apsushadaḥ* (v.6.1²), *sa trīr ekādaçāñ iha* (iii.2.11³: found in O. only), *karnāñ çā 'karnāñ çā* (i.8.9³), *trīñ treāñ* (ii.5.10¹), and *mahāñ indrah* (i.4.20 et al.); of which the last is by part of the MSS., rather needlessly, quoted twice, once for the conversion of the *n* into *y* (for which it should be written *mahāñy indrah*), and again for the loss of the *y*. For the loss of *m* (by xiii.2), the examples are *pratyushtañ rakshaḥ* (i.1.2¹ et al.) and *sañçitam me* (iv.1.10³ et al.).

The commentator explains *anunāsika* by *sānunāsika*, as if the word were properly a noun, and needed reduction to adjective form: in this treatise, however, it is always and only an adjective, meaning 'nasal' (see note to ii.30).

निकेषाम् ॥ २ ॥

2. Some deny this.

1. 'nakārasya rephabhāvād āshmabhāvād yakārabhāvād cakārākṣṭayakāre lupṭe ca' sati 'makāralopāc ca' pūrvasvaro 'nunāsiko' bhavati: sānunāsiko bhavati 'ty arthaḥ. 'yathā: rephabhāvāt: agn-----: 'sa-----' 'atho "shmabhāvāt: karn-----: trīñs-----: 'yakārabhāvād yathā: mahāñ-----: 'yakāre lupṭe yathā: mahāñ-----' 'atha makāralopāt: praty-----: sañ-----: 'ity ādī¹¹. makārasya lopo makāralopāḥ¹²: tasmāt.

(¹) wanting in B. (²) O. om. (³) W. om. (⁴) O. om. (⁵) in O. only. (⁶) O. om.; G. M. om. *atha*. (⁷) O. om.; G. M. om. *yathā*. (⁸) W. O. om. (⁹) G. M. om. (¹⁰) O. om.; G. M. om. *atha*. (¹¹) O. om. (¹²) B. *mal-*.

This is a mere introduction to the next rule, which informs us what the doctrine is which these dissidents hold instead. The commentator pronounces it the approved doctrine for this *śākhā*.

ततस्वनुस्वारः ॥३॥

3. And claim that, on the contrary, *anusvāra* is inserted after the vowel.

The *anusvāra* here prescribed is called by the commentator an *āgama*, 'increment.' Its insertion is the alternative view to the nasalization of the vowel, and, as is pointed out, is held where that nasalization is denied—of which denial, the *tu*, 'on the contrary,' is the sign in the rule. There is one example given: *sa trīṇr ekādaśāṇi iha* (iii.2.11²: W. B. omit *sa*).

The approval of this rule is, of course, involved in that of its predecessor; and the usage of the recorded Tāittirīya text corresponds.

स्नादिषु चैकपद ऊष्मपरः ॥४॥

4. *Anusvāra* is also inserted in the case of *sra* etc., in a single word, before a spirant.

"Also" (*ca*) in the rule, we are told, brings down the implication of the above specified increment. The *śrādayas*, '*sra* etc.,' are the whole detail, given in the next chapter, of the occurrence of *anusvāra* in the Tāittirīya-Saṁhitā otherwise than as the result of the rules of combination, implied in rules 1-3 of this chapter. The precept, then, is introductory to the detail referred to, and also lays down some general limitations affecting it. The commentator quotes a single case, *ṣoṣā moda ive 'ti* (iii.2.9²: it falls under xvi.2); and then gives counter-examples, establishing the restrictions made: *tāsām trīṇi ca* (ii.5.8²) shows that the insertion is made only under the circumstances defined in chapter xvi.; *tam mā sañ srja varcasā* (i.4.45³ et al.: only G. M. have *varcasā*) and *prastaram ā hi sīda* (ii.6.12⁵: found in O. only) show that it is to

2. *ekeshām mate pārcasātrokteshu* ¹ *śānunāsikyam* ² *na* ³ *bhavati. uktāny evo* ⁴ *dāharāṇāni.*

idam 'eve' *'shtam* ¹ *na tu pārcam.*

¹ O. ins. *sthāneshu.* ² G. M. *na* 'nu-. ³ W. G. M. O. om. ⁴ O. *eva sūtram* *lek.*

3. *tata iti sarvanāmnā parāmṛṣhāt* ¹ *svarāt* ² *paro* ³ *'nusvāra* ⁴ *āgamo bhavati. yathā:* *sa*..... *parāmṛṣhāsvarasyā* ⁵ *'nunāsi-* ⁶ *kam* ⁷ *guṇam tuṣabdo nivartayati* ⁸ *'ti: tasmād anunāsikapra-* ⁹ *ti-* ¹⁰ *shedhapaksha* ¹¹ *evā* ¹² *'yam anusvārāgamah syāt.*

¹ G. M. *-shta.* ² G. M. *-ra.* ³ B. G. M. *-svār.* ⁴ G. M. om. ⁵ O. *-shtāt svarā.* ⁶ G. M. *-ka.* ⁷ O. *-vāray.* ⁸ G. M. O. om. *iti.* ⁹ W. B. *-dhāt p-;* G. M. *-dhah* *vak-* ¹⁰ *shyamāṇa.*

be made only in a single word—that is to say, if I understand the meaning, that if *mā sām* and *hi sīdo* were single words, they would fall respectively under rules 8 and 13 of the next chapter, and have the increment—; and *māyā māyindm* (iii.1.11⁷) shows that a spirant must follow (*māyindm* otherwise falling under xvi.8). To the specification *ekapade*, ‘in a single word,’ the commentator adds in his paraphrase the explanation *akhaṇḍapade*, ‘in an undivided word;’ and then, in his illustration, he treats this as a restriction or limitation, and establishes it by an example, *trishāhasro vai* (v.6.8³; p. *tri-sāhasrah*); rule xvi.25 would otherwise require the increment after *tri*.

नात्त्विकारात्पूर्वः ॥ ५ ॥

5. Not before an altered final.

The illustrative example is *bahis te astu bāl iti* (iii.3.10²; G. M. omit the last two words): we have in it a *s* following *hi* in a single undivided word; and hence, by xvi.13, should have to read *bahiṣ*, but for this restriction. The alteration is from *h* to *s*, according to ix.2. As counter-example is given *mā hiṣir dvipādam* (iv.2.10¹; G. M. O. omit the last word), a case falling under the rule already referred to.

अप्रग्रहाः समानान्तराण्यनुनासिकान्येकेषाम् ॥ ६ ॥

6. According to some authorities, the simple vowels, except the *pragrahas*, are nasalized.

This and the remaining rules of the chapter have the aspect of an intrusion, as they interrupt the natural connection of what precedes and what follows, and merely give the view of certain authorities on points which the *Prātiśākhya*s in general leave untouched. They are brought in here as having to do with nasalized vowels, which are the subject of this chapter and its successor.

With the nasalization thus taught is to be compared that noticed in the *Rik Prāt.* (at i.16, r. 63, lxiv), which teaches that the first

4. ‘*āgamānvādeṣakaṣ cakārah*: *srādishv ekapade* ‘*khaṇḍapada*’ *āshmaparo*’ *nusvārāgamo bhavati. yathā*: *ḡoṇsā*..... *srādishv iti kim*: *tāsām*..... *ekapada iti kim*: *tam*..... ‘*prast*.....’ *akhaṇḍaviṣhanena*’ *kim*: *trish*..... *āshmapara iti kim*: *māyā*.....

(¹) wanting in B. (²) O. *pada*. (³) G. M. O. om. (⁴) in O. only. (⁵) O. *-sheṣa*.

5. *na khalu padāntavikārāt* *pūrvāsminn anusvārāgamo bhavati. yathā*: *bahis*.....: *hipujigā* (xvi.13) *iti prāptih. antavikārāt iti kim*: *mā*..... *antasya vikāro* ‘*ntavikārah*: *tasmād antavikārāt*.’

(¹) W. *vīk*. (²) G. M. O. om. (³) G. M. om.

eight vowels (namely *a, ā, i, ī, u, ū, r, ṛ*) are by [some?] teachers declared nasal when they are not *pragṛhya*, and stand as finals before a pause. This is different, first, in including *r* and *ṛ* (which are not *samānāksharāṇi* according to our treatise: compare i.2; but the difference amounts to nothing, as the vowels in question never occur *avasāne*, but only *avagrahe*); and secondly, in limiting the nasalization to finals, before a pause. But it is perfectly evident that our rule also applies to finals only, and, as we shall see, the commentator resorts to great violence to bring in the implication of "final" in rule 8, below. Again, the specification "in *samhitā* also," in rule 8, and the interpretation of *padam* in rule 7 as signifying *padakāle*, 'in *pada*-text,' sufficiently prove that the present precept does not apply in *samhitā*—that is, that *avasāne*, 'in pause,' is implied here. And the absence of statement or *anuṛtti* of these two essential implications is strong additional evidence that the rules are interpolated.

By most of the MSS., only one example is given, namely *kulāyini vāsumati* (iv.3.4¹), which, if our understanding, as above explained, is correct, is to be read, in *pada*-text, *kulāyiniñ : vāsumatiñ*. O. adds *aminanta evāih* (iii.1.11²), one of the cases of suspended combination falling under x.13, and (by R. Pr. ii.31,32) in the Rig-Veda requiring nasalization of the uncombined final: its citation seems to indicate that O. would not limit the operation of the rule to the *pada*-text. To show that the nasalization does not take place in uncombinable vowels, or *pragrahas*, are quoted, in *pada*-form, *amī iti* (iii.3.7¹ et al.) and *tanā iti* (ii.2.7²; omitted in O.). To illustrate the limitation to simple vowels, we find in most MSS. *so evāi 'shāi 'tasya* (ii.2.9²); but O. gives instead *agnaye 'nikavate* (i.8.4¹ et al.), *vishnav e 'hī 'dam* (ii.4.12³), and *vāyav ishtaye* (ii.2.12⁴).

The commentator, as he has done repeatedly before (under i.49, ii.7, v.2), notices the apposition in the rule of *apragrahāḥ* and *samānāksharāṇi*, two words of different gender. He signifies, further, under the next rule, that both that and this are unapproved.

पदं च सुतः शाङ्खायनकाण्डमायनयोः ॥ ७ ॥

7. As is also, according to Śāṅkhāyana and Kāṇḍamāyana, a protracted *pada*.

By *pada* is here signified, according to the commentator, a word

6. ¹ *yāni samānāksharāṇy āpragrahasamjñāni tāny ekeshām mate bhavanti² anuśikāni³*. ⁴ *kul----- apragrahā iti kim : amī iti : 'tanā iti⁵ samānāksharāṇi 'ti kim : 'so----- pragrahāksharabdayor niyatalingatayā⁶ parasparānvayo ghatate. na pragrahā apragrahāḥ⁷*.

¹ O. ins. *ekeshām acāryāṇām mate*. ² O. om. ³ O. *-kagunāni potashante*. ⁴ O. ins. *a m-----* ⁵ O. om. ⁶ O. *agn-----* ⁷ *vish-----* ⁸ *vāy-----* ⁹ W. *niyamal-*

in the *pada*-text; and the interpretation, as was remarked above, is fully supported by the specification of *saṁhitā* in the next rule.

As examples of nasalized protracted vowels, are given *tvīs ity abravīt* (ii.4.12⁶) and *astu hīs ity abratām* (vii.1.6¹), both in *saṁhitā*-form, although it is again expressly pointed out that the nasalization is not made in *saṁhitā*: the two worthies referred to would read *tvīṣ*: and *hīṣ*. It is added that *ca*, 'also,' in this rule effects its connection with what is prescribed in the preceding one—or, as O., in more customary phrase, expresses it, brings forward by implication the preceding rule.

Some, we are further informed, restrict the application of the precept to words which contain a single vowel protracted, and would not regard it as authorizing nasalization in *na chinattis iti* (i.7.2¹⁴) or *na vicityās iti* (vi.1.9¹: G. M. omit *iti*).

The rule is declared to be of no binding force.

अकारस्तु संक्षिप्तायामपि ॥ ८ ॥

8. An *a*, however, is nasalized in *saṁhitā* also.

The commentator's explanation is that nasality and protraction are here implied (from the preceding rule) by vicinage; and that *tu*, 'however,' is intended to annul the implication that only the opinion of the two authorities specified in rule 7 is reported. And though the comprehensive statement "an *a*" is made in the rule, nevertheless, in virtue of rule i.58, "continued implication is of that which is last (or final)," the "also" (*apī*) really brings down only a final *a* as suffering a prescribed effect by the attribution of nasal quality. The sense, then, is that a protracted final *a* is nasalized, both in *saṁhitā* and elsewhere. Examples are *suṣṭhokāṁś sumāṅgalāṁś* (i.8.16²), *upakātāṁś* (ii.6.7³), *yaṣo mamāṁś* (vii.4.20); these are, in fact, all the cases of protraction of simple final *a* which the text contains; and the edition (so far as it goes) and my MS. nasalize the *ā*, as required by the interpretation of the rule here given. The cases are much more numerous in which a final *ah* exhibits *ās* as the ultimate result of protraction, the *h* being lost before a following vowel or sonant consonant: namely, at i.5.9⁶: v.5.1³, 3² twice: vi.1.9¹ twice: 3.8¹; 4.3⁴; 6.2³; and in one place, vi.5.8⁴, the same final *ās* comes from a protracted *e*: the question might possibly arise whether these do not also fall under

7. *yat*¹ *plutavat padam*² *²tac ca*³ *padakāle* *³ṣāṅkhāyanakāṇḍa-māyanayor mate*⁴ *⁴nunāsikam bhavati. yathā*⁵: *tvīs*.....: *astu*.....: *padam iti kim*: *saṁhitāyām mā bhūt. cakārah*⁶ *pārcasā-troktavidheyasamuccayam*⁷ *karoti*⁸. *apara āhuḥ*⁹: *³plutdikasva-ram padam iti*: *anyam mā bhūt*¹⁰: *na*.....: *na*.....
*ne*¹¹ *⁵dam sūtradvayam*¹² *isṭam*.

¹ W. *yatra*. ² O. om. ³ W. *ṣatra*. ⁴ O. puts after *bhavati*. ⁵ G. M. om. ⁶ G. M. O. *caṣāḍah*. ⁷ O. *-vidhim*. ⁸ O. *anvādicat*. ⁹ O. *plutavarṇapadam iti* *⁵ha mā bhūt*. ¹⁰ W. *sūtram*.

the rule, but it would have to be answered in the negative (see the counter-examples below); and the text reads accordingly. The manuscripts of the commentary give as found "in another *śākhā*," one example, read *brahmān* in W. B. (O. is wanting), and *yadghrā* in G. M.: I do not quite know what to make of this, as there seems to be no call for quoting from another text examples of what is capable of being fully illustrated from the received Veda of the school; *brahmān* is found at i.8.16¹ twice, ² twice, but would be a counter-example to this rule, its *a* not being final; it is, in fact, of the same character with the first of the counter-examples given. These are *satyarājān* (i.8.16²), *agnās ity āha* (vi.5.8⁴: W. has dropped out *agnās*), and *vicityah somās na vicityās iti* (vi.1.9¹: O. has only this).

Finally, the commentator remarks that Cāṅkhāyana and Kāṇḍamāyana also accept this principle. He may well say this, for the natural interpretation of the rule is to make it represent simply the view of those authorities; and the action of the comment, in cutting it loose from its predecessors, and declaring it alone to express the approved doctrine of the treatise, is in a high degree forced and arbitrary. It was noticed under i.58 what an unjustifiable act of violent interpretation was there committed, by way of preparation for this one. The implication of "final" is not needed in rule 8 any more than in rules 6 and 7, and is clearly enough made in them all; whence it comes, it would be the business of those who put the passage in to tell, if they could.

The Ath. Prāt. gives (at i.105) an enumeration of the protracted vowels occurring in the text to which it relates. This our treatise omits to do, and it may be well to repair the omission in this place. A final *a* is protracted to *ā* at i.8.16² twice; ii.6.7³; vii.4.20: —*ah* to *āsh* at i.4.27: v.5.1²; and to *ās* (the *h* being lost) at i.5.9⁶: v.5.1³, 3² twice; vi.1.9¹ twice; 3.8¹; 4.3⁴; 6.2³: —*an* to *ān* at i.8.16¹ twice, 16² thrice; ii.6.5⁶: —*am* to *ām* at vi.1.4⁵; 5.9¹: vii.1.7⁴: 1.7⁴; 5.7¹ twice: —*i* to *īs* at i.7.2^{1,4}; ii.4.12⁶: vi.5.9¹: vii.1.6¹, 7⁴: —*iḥ* to *īḥ* or *īr* at i.5.9⁶: vi.3.10¹: —*in* to *īn* at vii.4.20 twice: —*uh* to *ūr* at vi.3.8¹: —*e* to *ē* at i.4.27: vi.1.4⁵; and

8. *sāmnidhyād anuśāsikaplutāu' gṛhyete: tuṣabdah prakṛtācāryamatanivartakah²: ata' eva' saṁhitāyām asaṁhitāyām³ cā'kārah padāntah pluto 'nuśāsiko bhavati: yady apy akāra iti⁴ sāmānyeno 'ktaḥ: tathā 'py anvādeṣo 'ntyasya (i.58) iti vacanād apiṣabdo 'nuśāsikadharmatayā nimittinam padāntam eva' kāram anvādicati. yathā: suḥ-----: upa-----: 'yaṣo-----: brahmān⁵ ity anyasyām⁶ śākhāyām⁷. apiṣabdah kimarthah: "saty-----: agn-----: vicityah-----: cāṅkhāyanakāṇḍamāyanayor apy ayaṁ vidhir⁸ akāre plute sammataḥ⁹."*

¹ G. M. *plute*. ² O. *pūrvacārya*. ³ W. *eta*; M. *tata*. ⁴ O. om. ⁵ W. O. om. ⁶ O. om. ⁷ B. O. om. ⁸ O. om. ⁹ G. M. *yadghrā*. ¹⁰ G. M. *asya*. ⁽¹¹⁾ O. om. ⁽¹²⁾ G. M. *-raplute sammataḥ*.

to *ā* (see I.4) at vi.5.8⁴;—*āu* to *āṣv* at vi.6.2³. The protracted syllable has always the acute accent.

सर्वमेकयनं पूर्वेषां सर्वमेकयनं पूर्वेषाम् ॥ १ ॥

9. According to the former ones, all is of one pitch.

The comment is completely at a loss as to how this rule is to be understood, and gives three more or less discordant interpretations of it, the first of which we are probably to regard as the preferred one, if there be a preference. "All" means "every kind of articulate sound;" "of one pitch" is equivalent to *ekagruti*, *yama* denoting the tone of an acute syllable; "the former ones" are 'the sacrificers;' the meaning is, then, that in the sacrificial usage of the sacrificers everything is uttered in acute monotone. O. has an exposition of its own, which is in great part too corrupt to be read without considerable emendation, and which conducts to the same conclusion: it quotes, *apropos* of *pūrve*, a *pada* of a *tristubh* verse from some sacred text, "the former ones spoke those words to the former ones."

The second interpretation differs from the first only in declaring *pūrve*, 'the former ones,' to designate certain *chākhinaḥ*, or 'holders of a Vedic text.'

The third is of quite another character; it makes *yama* to be equivalent to *svara* in the sense of 'vowel,' and explains 'every monosyllable is nasalized'—the intent being to annul the restriction to simple vowels only (as made in rule 6). Who the *pūrve* are, is not told us this time.

The commentator consoles himself at the end by declaring the rule not approved. We may fairly extend the same condemnation

9. 'sarvam² varṇajātam³ ekayamam ekagruti⁴ 'ti pūrveśhām⁵ matam. yamo nāma svara⁶ udātta ity arthah: pūrve nāma yājñikāḥ⁷; teshām yajñakarmaṇi sarvam⁸ ekagruti⁹ bhavati.¹

anye manyante¹⁰: pūrve nāma keci chākhinaḥ: teshām sarvam¹¹ "ekagruti¹² 'ti¹³.

athā¹⁴ 'pare kathayanti¹⁵: sarvam ekasvaram amunāsikam bhavati¹⁶ 'ti¹⁷: "samānākṣarāmātrāpekṣhām adhikṣheptum¹⁸.

ne 'daṁ sūtram iṣhtam.

iti tribhāṣhyaratne prātiśākyavivarane
pañcadaśo¹⁹ 'dhyāyāḥ.

(1) O. substitutes *sarvam* *iti lakṣhyaṇi lakṣhaṇavishayaṇi grhṇāti*: *ekayam ekagrutiḥ*: *yamo* *grutisvāra* *ity athāntarā pūrveśhā pūrvā nāma yājñikā pūrve pūrvebhyo vaca etad ucyr iti darṣanāt*: *yājñikānām yajñakarmaṇi sarvam ekagrutiḥ bhavati*.
(2) W. B. *sarva*. (3) B. *varṇam ajātam*; G. M. *-ayamam*. (4) W. *sarv*. (5) G. M. *put* after *udātta*. (6) W. *-āyāḥ*. (7) W. *puts* after *bhavati*. (8) B. *-tir*. (9) O. *dhuk*. (10) O. *om*. (11) W. *-grutāni*; O. *-grutiḥ bhavati*. (12) G. M. *om*. *atha*. (13) O. *vyācakṣate*. (14) O. *om*. *iti*. (15) O. *sarvam* *iti samānākṣarāṇām apekṣhā grahavyudṣā sarvaṇi tatāḥ vidhīyate*; W. *-ramatrāpekṣhām apikṣhiptam*; B. *-kṣham adh*; G. M. *-mātrāpakṣham ākṣheptum*. (16) G. M. O. *dvitīyapraṇe tṛtiyo*.

to his treatment of it, and conjecture that, if he could only have told us what it meant, we might have found in it something to approve. We are tempted to seek in it some statement as to the accent of the protracted syllable, or *pada*; and, if it were allowed to amend *pūrveshām* to *ekeshām*, we might translate, 'some hold that the whole word in which protraction occurs is to be uttered in the same tone'—only then, to be sure, we should look for a statement of the usage actually followed in the text.

CHAPTER XVI.

CONTENTS: 1-31, detail of the cases of occurrence, in the *Sanhitā*, of *ā* in the interior of a word, before a spirant.

अथ सकारपराः ॥ १ ॥

1. Now for cases in which *s* follows.

A simple heading, of force through a considerable part of the chapter (i. e. through rule 13). The essential item of the precept laid down was given above, in xv.4, which directed that in all the cases to be specified in this chapter is to be assumed the presence of *anusvāra* following a vowel and followed by a spirant. Words in which that spirant is *s* form by far the most numerous class, and until rule 14 they alone are treated.

The *Rik Pr.* is the only one of the other treatises which offers anything at all analogous with this enumeration; it (at xiii.7-10) gives rules for the occurrence of *anusvāra* after long vowels only.

सशोऽप्यश पदादयः स्वरपरे ॥ २ ॥

2. *Sra*, *ṣo*, *ha*, *pā*, and *ṣa*, at the beginning of a *pada*, take *anusvāra* before a *s* that is followed by a vowel.

The commentator cites examples, as follows. For *sra*, *visraṇṣayē amehenā dhvāryuḥ* (vi.2.9⁴, 10⁷; G. M. O. have only the first word); we have other cases at ii.5.7²; v.1.6¹; vii.3.10³, all from the same root, *sras*. For *ṣo*, *ṣoṇṣā moda ive 'ti* (iii.2.9⁵; G. M. omit the last word, O. the last two); I have noted no other case: as counter-example, to show that only *o* after *ṣ* takes the increment, is given *ācāsānā sāumanasam* (i.1.10¹; O. alone has the latter

1. *athe 'ty ayam adhikārah: ita uttare grahanaviṣeshāḥ sakāraparā ity etad adhikṛtaṁ veditavyam. sakārah paro 'yebhyas te sakāraparāḥ*².

¹ B. -shoh. ² B. -para. ³ G. M. *yasmāt sa tathoktaḥ* (and -paraḥ in the rule).

word). For *ha*, *haṅsaḥ* *çucishad* (i.8.15²: iv.2.1⁵); various other cases of *haṅsa* are found in the text, and *haṅsi*: that *hā* is not treated in the same way is shown by *prajā mā mā hāsīt* (v.6.8¹: O. omits). For *pā*, *pāṅsura irāvati* (i.2.13²); other cases are *pāṅsūn* and *pāṅsavyāya*, at ii.6.10² and iv.5.9¹ respectively: that *pa* would not have been correct is shown by *āhatam gabhe pasah* (vii.4.19²: O. omits *āhatam*); *pāsi*, which would seem to fall under the rule, is excepted by rule 17, below. For *ça*, *yad āsinaḥ çāṅsati tasmāt* (iii.2.9⁷: W. B. G. M. omit *tasmāt*, thus allowing the citation to be found also at iii.2.9⁶); cases of this combination, all of them coming from the root *çāṅs*, are not infrequent in the *Sanhitā*. As general counter-examples, we have, to establish the necessity of the restriction "at the beginning of a *pada*," *agnir ukthēna vāhasā* (i.5.11¹), *somam pipāset* (ii.1.10¹), and *dahā* "çasah" (i.2.14⁶: O. omits); while *tasmāt sa viśasyah* (vi.2.9⁴, 10⁷: only O. has the first two words), *hastayoh* (iv.1.5² et al.: G. M. O. omit), and *kaviçastāh* (ii.6.12⁶: all the MSS. have *-çastah*, which I have not found in the text, but probably by my own fault) do the same service for the specification "when a vowel follows."

The commentator goes on to say that some authorities accept *hi* as a part of this rule: which is not to be approved, since "at the beginning of a word" is here implied, and so *ahiṅsāyāi* (v.2.8⁷) would be left without the increment. And if it be pleaded that *hiṅsiḥ paramē* (iv.2.10¹⁻² et al.) should be an example here, the reply is made, that the *anuvāra* is assured to it by rule 13, below, where there is no restriction to the beginning of a word; and that to repeat here the specification of *hi* would be useless. The only criticism to be offered upon this is that the objection has too little reason to be really worthy of notice.

2. *sra*: *ço*: *ha*: *pā*: *ça*: *ity ete grahaṇaviçeshāḥ*¹ *padādayaḥ sakāraparās tasmint sakāre svarapare saty anuvārāgamam*² *bhājante*³. *yathā*⁴: *vi*..... *çoṅsā*..... *okārena kim*: *āçā*..... *haṅsah*..... *'hrasva iti kim*: *prajā*..... *pāṅsura*..... *dirghena*⁵ *kim*: *āh*..... *yad*..... *padādaya iti kim*: *agnir*..... *somam*..... *'dahā*..... *svarapara iti kim*: *tasmāt*..... *'has*..... *kav*.....

*kecid atra sūtre 'higrahaṇam*¹⁰ *aṅgikurvate*¹¹: *tad anupapanam*: *padādaya iti niyamāt*: *ahiṅsāyā ity atrā 'nucvārābhā-vaprasaṅgāt*¹². *namu hiṅsiḥ*..... *ity etad atro 'dāharaṇam iti cet*: *māi 'vam*: *'hipuḥigā* (xvi.13) *ity atra niyamābhāvāt padādāv apadādāu ca* *higrahaṇasya kāryasiddheḥ punar atra grahaṇam vyartham*.¹³

svaraḥ paro yasmād asāu svaraparaḥ: *tasmīn*.

¹ G. M. -*aparāḥ* viç-. ² O. -*ma*. ³ O. *syāt*. ⁴ G. M. O. om. ⁵ O. om.; G. M. *hrasvena kim* etc. ⁶ O. -*ghe*. ⁷ O. om. ⁸ G. M. O. om. ⁹ W. om. ¹⁰ G. M. *him*. ¹¹ G. M. *aṅgīnik*. ¹² G. M. -*rabhā*; O. -*rābodhapra*. ¹³ B. om.

विकृते ऽपि ॥३॥

3. Even when the vowel is altered.

That is to say, even when the vowel that is by the last rule required to follow the *s* has undergone euphonic alteration, so as to become a consonant. A single example is cited, *apahaṁsy agne* (iv.7.13¹; p. *apa-haṁsi*); if the text contains any others, they have escaped my notice.

रापूर्वञ्च ॥४॥

4. As also, when they are preceded by *rā*.

This rule is made for the purpose of establishing a single additional case under the general rule given above (xvi.2), namely, the word *nārāṇasibhyaḥ* (vii.5.11²); the case being one, as the comment points out, where the *ṇa* is not at the beginning of a *pada*. The *ca*, 'also,' brings down only *ṇa*; and we are assured that this is the reason why *ṇa* was mentioned last in rule 2, even at the cost of a violation of the natural order of the vowels. Of this point we need not make much, since the rule contains other and unexplained violations of alphabetic order.

शस्तान्तोदत्ते ॥५॥

5. Also in *ṣaṁstā*, except when it is accented on the final syllable.

Here is another single case, falling under rule 2 by the suspension of one of the restrictions laid down in that rule—namely, that the *s* be followed by a vowel. The passage is *utā ṣaṁstā sūviprah* (iv.6.8²; O. omits *sūviprah*). The restriction as to accent

3. *opiṣabdaḥ svarānvādeṣakah*¹: *sakārāt pare tasmint svare vikṛtam āpanne 'pi vyañjanatām upagate 'pi syād' anuvāravidhiḥ*². *yathā*: *apa*.....

¹ B. *sakārān*-. ² W. and O.(?) *svārad*. ³ *lacuna* in O., from (*anuvāra*-) *vidhiḥ* to *svara* under the next rule.

4. '*caṣabdaḥ srādiṣhu*' *ṣakāram anvādiṣati*¹: *etadartham eva svaracyatyaye*² '*pi ṣakāragrahanam tatrā 'nte kṛtam. rā*: *ity evampūrvāḥ ṣakārah sakāraparo 'nusrāragamam bhajate. yathā*³: *nār*..... *apadādyaṛtho*⁴ '*yam ārambhaḥ*.

¹ W. *ṣabdasrādiṣhu*; B. *sacaṣabdādiṣhu*. ² W. B. ins. *caṣakārah*. ³ G. M. *vyak-taye*; O. begins again with *vyatyaye*. ⁴ G. M. O. om. ⁵ W. O. *apadārtho*.

5. *ṣaṁstā*: *ity etasmin*¹ *grahane 'nantodātte*² *sakārapare bhavaty*³ *anuvārāgamah. uta*..... *anantodātta*⁴ *iti kim: aṣv*..... *sraṣoḥa* (xvi.2) *iti prāptāu satyām*⁵ *sakārasya*⁶ *svāraparated-*

is intended to exclude *āpasyā viçastā* (iv.6.9³: O. adds *dvā yam*-).

अशंसन् ॥ ६ ॥

6. Also in *açañsan*.

Yet another case belonging with those disposed of by rule 2, but requiring special treatment because the *ça* in it does not stand "at the beginning of a *pada*." The passage is *abhi vy açañsan* (vi.6.11⁵).

O., in an added paragraph, brings forward the objection that, in virtue of rule i.52 (which makes the citation of any word include also the same word with *a* prefixed), *açañsan* has its *ñ* already assured by rule 2; but refutes it by pointing out that the principle appealed to has to do only with a *pada* or word, not with a mere fragment of one, like *ça* (compare rule 10, below). It adds that "another reading is *çañsān*."

न शसनं विशसनेन ॥ ७ ॥

7. But not in *çasanam* and *viçasanena*.

These are exceptions, the only ones the Sanhitā affords, under rule 2. The passages are *çasanam vāṇy arvā* (iv.6.7⁵: O. ends with *vāṇi*) and *çuno viçasanena* (v.7.23).

T. and O. have the simple *pada çasanena*, instead of *viçasanena* (p. *vi-çasanena*) in the rule, and O. reads the same in its comment. This is doubtless an emendation, and makes a reading more strictly in accordance with the approved usage of the treatise. The comment has (especially in the fourth chapter) explained away many a like inaccuracy by the allegation of a phrase "in another *çākhā*:" and we might expect to find added here *vi 'ti kim: āçañsanene 'ti çākhāntare*.

*bhāve 'pi nā 'yam vidhir nishidhyatām 'iti grahaṇam'. anta' udātto yasya tad antodāttam: 'nā 'ntodāttam' anantodāttam: tasmin.*¹¹

¹ O. *asmin*. ² W. B. O. *antod*-. ³ O. *syād*. ⁴ W. *antod*-. ⁵ G. M. om. ⁶ W. B. *çak*-. ⁷ G. M. ins. *eva*. ⁸ B. *padogr*-. ⁹ W. O. *ante*. ¹⁰ O. om. ¹¹ O. adds *opa-ddāyartho . . . ity anetanāi* (which belongs at the end of the comment on rule 6).

6. *açañsanu ity asmin grahaṇe syād anusvārāgamaḥ. abhi '-----' apadādāyartho 'yam ārambhah'.*

¹ O. puts at end of comment on rule 5, and adds, partly there and partly here (a little amended), *kimartham idam. sraçohapāçā* (xvi.2) *ity anenāi 'va tatsiddhau: apy akārādi* (i.52) *'ti vacanāt: māt' eam: apy akārādi 'ti vacanam padasya padārayavah çarabdhah: çañsān ity pāthāntaram.*

7. *çasanam: viçasanena: ity etayor grahaṇayor² anusvārā-gamo na syāt. ças-----: çuno----- sraçoha* (xvi.2) *iti prāptih.*

¹ O. *ças*-, as also (with T.) in the rule itself. ² O. om.

मा पदादिरनुदात्तः ॥ ८ ॥

8. *Mā* takes *anuvāra* when beginning a *pada* and unaccented.

All the implications of rule 2 are here cut off (as is distinctly enough intimated by the express repetition of one of them, *padādi*), and hence it is to be understood that the increment takes place before a *s* whether this be or be not followed by a vowel. The examples are *āhar māṇsena* (v.7.20) and *māṇspācanyāh* (iv.6.9¹). The restriction to the beginning of a *pada* is established by quoting *sīlikamādhyaṁsah* (iv.6.7⁴); that as to the accent, by *māsam dikṣhitāh syāt* (v.6.7³: only *O.* has *syāt*).

So far as I have discovered, this rule applies only to forms and combinations of *māṇsa*, which are not infrequent in the *Sanhitā*. The four following rules give it certain extensions and limitations.

पुमीपूर्वश्च नित्यम् ॥ ९ ॥

9. As also when preceded by *pu* or *mī*, under all circumstances.

The closing specification of the rule amounts to a removal of the restriction as to accent, imposed in rule 8—that as to initial position being virtually removed by the prescribed prefixion of *pu* or *mī*. The examples quoted are *ut pumāṇsāḥ haranti* (vi.5.10³: *O.* omits *haranti*, and *B.* runs the two citations together, having dropped out a part of each) and *mīmāṇsante kārye* (vi.2.6⁴). We have *pumāṇsam* again at iv.6.6³, and other forms of *mīmāṇs* at vi.2.6⁴ and vii.5.7¹: I have noted no other words as falling under the rule.

सकायपरश्च ॥ १० ॥

10. And when followed by *sakāya*.

The *ca*, 'and,' we are told, here brings down *mā*; and G. M. add that the intent of the rule is to establish an exception under

8. *mā*: *ity evam*¹ *vārṇaḥ padādir anudāttāḥ sakāraparo 'nusrādrāgamam bhajate. atra niyamābhāvāt sakārasya svaraparatābhāve 'pi nimittatvam bhavaty eva. yathā': ahar..... māṇs..... padādir iti kim: sīli..... anudātta iti kim: māsam*

¹ G. M. *O. ayan*. ² *O. om.*

9. *caṣabdo me 'ti jñāpayati: pu: mī: ity evampūrvo me 'ti 'vārṇaḥ sakāraparo nityam anusrādrāgamam bhajate. ut..... mīm..... anudāttatvanivartako² nityaṣabdoḥ.*

¹ G. M. *O. ina. ayan*. ² *O. -niyamavyavar.*

rule 8—that is to say, to bring under that rule a word which would otherwise be excluded in virtue of the requisition “when beginning a *pada*.” The case is similar to that about which O. raises a question under rule 6. The passage is *amāṇsakāya svāhā* (vii.5.12²).

नावग्रहपूर्वः ॥ ११ ॥

11. But not when preceded by a former member of a compound.

Or, ‘by a pause of division (between the two members of a compound),’ taking *avagraha* in its more original sense. W. B. O. define the rule as establishing exceptions under rule 8; G. M., which have taken in this notification (less correctly) as part of the preceding comment, say simply that *mā* is to be understood as implied here by vicinage. The examples given are *pūrṇāmāse vāi* (ii.5.5⁴: O. omits *vāi*) and *ardhamāse devāḥ* (ii.5.6⁶ twice). The words would satisfy all the conditions of rule 8, the separated element *-māse* or *-māse* being itself (by i.48) a *pada*. Since *māṇsa* nowhere appears as the latter member of a compound, this rule exempts from the increment of *anusvāra* all the cases in which forms of *mās* or *māsa* are found in such a situation; others are the subject of the next following precept.

नासिमासुमासोमासामिति च ॥ १२ ॥

12. Nor in *māsi*, *māsu*, *māsaḥ*, or *māsām*.

These are words which, without special exception, would fall under rule 8. The examples for the last three are *daśāsu māsaḥ* *‘tishthan* (vii.5.2²), *śān māsaḥ dākshinena* (vi.5.3⁴: only O. has the last word), and *māsām prātishthityāi* (vii.5.1⁶): we have *māsaḥ* also at vii.5.7¹, and *māsām* at v.7.18. The first, *māsi*, raises a difficulty. Some, the commentator says, cite in illustration of it *prathamē māsi prsthāni* (vii.5.3¹: O. omits the last word); but this is wrong; for the exemption of *māsi* in that passage is assured by rule 17, below: we are to assume, then, the occurrence in another text of some word of more than two syllables beginning

10. *caṣabdo me ’ti jñāpayati: me ’ty evaṁ’ varṇaḥ sakāyaparo’ nuscārāgamam’ bhajate. am-.....*⁴

¹ B. G. M. O. *ayan*. ² W. B. *sakdrop*. ³ G. M. *nityam anu*. ⁴ G. M. add *mā padādīr anudātta* (xvi.8) *ity asyā ’yam apavādaḥ*.

11. *’mā padādīr anudātta* (xvi.8) *ity asyā ’yam apavādaḥ:’ avagrahapūrvo me ’ty evaṁ’ varṇo nā’ nuscārāgamam bhajate. yathā: pūrṇ-.....: ardha-..... avagrahaḥ pūrvo yasmād’ asāv avagrahapūrvaḥ.*³

¹ G. M. have this as part of the comment on the preceding rule, and substitute here *sannidhyān mā itī labhyate*. ² B. G. M. O. *ayan*. ³ B. om. *nā*. ⁴ G. M. O. om. ⁵ G. M. *sa tathoktaḥ*; W. om. *asāv*.

with *māsi*. This interpretation is, of course, forced and false: *māsi* is included with the rest here because it is an example of the same class with them; and the makers of the treatise, when they put it in, either overlooked or neglected the fact that it falls technically under rule 14, and so also under rule 17, establishing exceptions to 14. We have also *masi-māsi*, more than once, at vii.5.1⁶.

हि पुतिगाजिधाहसिनेज्जस्यदातास्मिन्कनीयाज्याया-
द्राघीयार्घीयाश्रेयाद्भूसीयावसीयाभूयास्सोज्जिवाज्जिवा-
जिगिवाज्जिगिवातस्थिवादाश्चादीदिवापपिवापीपिवावि-
द्वाविविशिवाशुश्रुवाससृवा ॥ १३ ॥

13. The following words have *anusvāra* before *s*: *hi*, *pu*, *jigā*, *jighā*, *chaṅsine*, *ataṅsayat*, *ātāṅsit*, *kaṇiyā*, *jyāyā*, *drāghīyā*, *ra-ghīyā*, *ṛeyā*, *hrasiyā*, *vasiyā*, *bhūyāṅsah*, *jakshivā*, *jaghnivā*, *jigivā*, *jigivā*, *tasthivā*, *dāṇvā*, *didivā*, *papivā*, *pipivā*, *vidvā*, *vivi-ṇvā*, *cuṇruvā*, *sasrūvā*.

The commentator's examples are as follows: *hiṅsīḥ paramē vyoman* (iv.2.10^{2,3}: O. omits *vyoman*, and G. M. substitute *mā hiṅsīs tanuvā*, iv.2.3¹ et al.) and *cinute 'hiṅsāyāi* (v.2.8⁷: O. omits *cinute*); respecting this first specification, see further below;—*tena puṅsvatīḥ* (ii.5.8⁵) and *puṅsoḥ putrān* (iv.6.9⁴): I have only noted further two cases of *puṅsoḥ*, at ii.6.5⁵ and vi.5.8²;—*lokaṃ ajigāṅsan* (v.5.5⁴: vi.5.8²: O. omits *lokaṃ*): elsewhere only at iii.2.2³;—*vasatāram ajighāṅsan* (vi.5.8⁴): the text presents fourteen other cases of *jighāṅs*;—*brāhmaṇāchaṅsine* (i.8.18): the only case: a counter-example (but O. omits all the counter-examples), *pra yuchasy ubhe nī pāsi* (i.4.22), shows the necessity of including in the citation the *ne* of *chaṅsine*;—*gabhe mushtim ataṅsayat* (vii.4.19⁴), with a counter-example, *ataṅsaṃ na ṇushtim* (i.2.14²), to explain the citation of the whole word *ataṅsayat*;—*anvātāṅsit trayi* (iv.7.13⁵: O. omits *trayi*), with *anu vrātāsaḥ tava* (iv.6.7³), to prove the need of the final *it*;—*kaṇiyāṅso devāḥ* (v.3.11¹): the text offers half-a-dozen cases of this comparative, and about the same number of the next;—*jyāyāṅso bhrātaraḥ*

12. 'cakāro nishedhākarashakāḥ': *māsi*..... *ity eteshu graha-
neshu na syād anusvārāgamah. eshām api mā padādīr* (xvi.8)
*iti prāptiḥ. kecid atra prath..... ity udāharanti: tad asādhu:
na pade dvisvare nityam*³ (xvi.17) *ity anenāi 'va nishedha-
siddheḥ: tasmād anyacākhāyām*⁵ *bahuvaram aparam*⁶ *udāhara-
ṇam avadhāraṇyam. daṇasu..... shaṇ..... māsām.....*

(1) O. om. (2) W. *reṇam*. (3) W. O. π; G. M. om. (4) W. *-dham siddhaḥ*; B. *-dhaḥ siddhaḥ*. (5) G. M. *anyasyām* ṛ. (6) B. G. M. *param*; O. om.

(ii.6.6¹ et al.);—*drāghīyāṅsāu bhavataḥ* (v.2.5¹): the only case;—*atho raghiyāṅsah* (vii.4.9): also the only case;—*pra grēyāṅsam* (ii.4.1⁴): but Ō. substitutes the only other case, *grēyāṅsam pāpiyān*, v.1.2³);—*atha hrasīyāṅsam ākramanam* (vi.6.4²): but G. M. O. omit the last word, thus allowing the citation to include also the only other case, found in the same division);—*vasīyāṅsam bhāgadheyena* (v.4.10⁵): there are two or three further cases;—*bhūyāṅso 'nyebhyah* (vii.1.1⁵), with *annādo bhūyāsam* (i.6.2² et al.) as counter-example, proving that the final *h* had to be cited with the rest of the word: there are seven other cases of *bhūyāṅs* in the text;—*jakshivāṅsah papivāṅsah* (i.4.44²: Ō. omits the last word): the only case;—*vrtram jaghnivāṅsam mrdho bhā* (ii.5.3¹: W. B. omit the first word, Ō. the first and last; G. M. have only the first two, which are read also at ii.5.4⁵): I have noted the word besides only at ii.1.10² three times, with the negative prefix;—*vājam jigivāṅsah* (i.7.8⁴): the only case;—for *jigivā* is found only a case "in another *gākhā*," namely *jigivāṅsasya* (so W. G. M., though the word is not grammatically admissible; Ō. has *jigivāṅsamyāma* [i. e. *-ṅsah syāma?*]; B. is corrupt, running the previous citation and this together into *vājam jigivāṅsam iti gākhāntare*);—*dyumā tasthivāṅso janānam* (i.2.14⁴: Ō. alone has the last word): there is one other case, at iv.2.2²;—*dācāvāṅso dācushah sutam* (i.4.16: Ō. alone has *sutam*): another case at ii.2.12⁵;—*gucayo dūdivāṅsam* (ii.5.12²): another case at i.2.14⁴;—*pāpivāṅsah ca ricce* (i.4.44²): the only case;—*pāpivāṅsah sarakantah* (iii.1.11²: Ō. has *-tas trayah*, probably corrupt for *-ta stanam*, as the text reads): the only case;—*vidvāṅso vāi purā hotārah* (ii.5.11¹⁻²: only Ō. has the last two words) and *avidvāṅsah cakrma* (iv.7.15⁶: Ō. begins *vishtāvid*, by mutilation of the preceding word in the passage): the Sanhitā has over thirty cases of *vidvāṅs*;—*pravivivivāṅsam imahe* (iv.7.15¹);—*yac chuṣruvāṅsah* (ii.5.9² twice): there is another case at v.3.4¹;—and, finally, *vājaṅ sarvāṅsah* (i.7.8⁴).

After the second example (*ahīṅsāyāi*), G. M. insert the remark that it is brought under the present rule by the principle of "prefixion of *a*" (i.52). This is wrong, being inconsistent with the

13. 'hi.....¹ ity evampūreah sakāraparo 'nusrāragamo² bhavati³. yathā: hiṅsāḥ.....: cin.....⁴ tena.....: puṅsah.....: lokam.....: vrasht.....: brāhm.....: 'na iti kim: pra.....⁵ gabhe.....: 'yad iti kim: atasam.....⁶ anv.....: 'id iti kim: anu.....⁷ kan.....: jyāy.....: drāgh.....: atho.....: pra.....: atha.....: vasī.....: bhūy.....: 'visargena kim: ann.....⁸ jaksh.....: vrtram.....: vājam.....: jigivāṅsasye 'ti gākhāntare: dyum.....: 'dācāv.....: gucayo.....: papiv.....: pāpiv.....⁹ vidv.....: avid.....: pravī.....: yac.....: vājaṅ.....¹⁰ dācāvivivivivācūcūruve¹¹ 'ty atra srādīshu cāi 'kapada (xv.4) iti prāptyā cakāraparo 'nusrāragamāḥ kim

exposition given under rule 2 (see note on that rule) of the reason why *hi* was not there included: *hi* here is meant not as initial only, but wherever found in a word. Since, however, it is only in this one word that *hi* occurs otherwise than as initial, it would seem better to have disposed of the single case as of those which form the subject of rules 6 and 10, and to put *hi* into 2, where it would look much more at home than here at the head of a troop of perfect participles and comparatives. And why *pu* was not put into rule 2 without any ceremony, I cannot see at all; unless I have overlooked some case or cases of its occurrence, *pu* is invariably initial.

The commentator raises the question why rule xv.4 does not require us to insert an *anusvāra* before the *ç* of *dāçvā*, *vivigivā*, and *çugruvā*, since these too are *srādayah*; and he makes answer that it is because the restriction conveyed in xvi.1 is still in force. But in that case, he goes on to say, is there not a nasal increment before the *s* of *hrasiyā*, *vasiyā*, *tasthivā*, and *saçvā*? The answer to this objection is twofold. First, the competency of the citation is pleaded—that is to say, the words being read in the rule itself without nasal, that is to be understood as their authoritative form (compare under rule 19, where this plea leads to a further discussion). Secondly, the words in question being found associated with *ātāṣṣit*, *kanīyā*, *jyāyā*, and so on, all of which show the *anusvāra* to follow a long vowel, we are to infer that in the others also it does not follow a short vowel. The first of these answers is not such as is wont to be pleaded in this treatise, and the second is evidently very weak: I should almost prefer to assume that the difficulty was not remarked by the authors of the treatise, and that the commentators who have discovered it have been forced to make the best excuse they could for it.

A more serious objection to the rule, it seems to me, is that it mixes together cases of two different classes—those in which (*chaṣṣine* etc.) the nasal appears in the word itself as cited, and those in which it is to be added before a following *s*. Of this, however, the comment takes no notice.

*na syāt. atha sakāraparā*¹² (xvi.1) *ity āshmañiçeshasya*¹⁴ *sakārasya*¹⁵ *'nuvrttiḥ*¹⁶ *iti vadāmaḥ. tarhi hrasiyāvasiyātasthivāsaçve*¹⁷ *'ty atra*¹⁸ *'sakārapara evā*¹⁹ *'gamah*²⁰ *kiṁ na syāt. uccāraṇa-sāmarthyād eve*²¹ *'ty prathamah*²² *parihārah. atha vā: ātāṣṣitka-nīyājyāye*²³ *'tyādishu sarvatra dīrghānantaram evā*²⁴ *'nuscārasthānam*²⁵ *iti sāhacaryād*²⁶ *atrā*²⁷ *'pi na syād anusvārasya hravānantaram*²⁸ *sthānam ity*²⁹ *aparah parihārah.*

⁽¹⁾ B. om. ⁽²⁾ O. -man. ⁽³⁾ G. M. syāt; O. bhajate. ⁽⁴⁾ O. om. ⁽⁵⁾ G. M. ins. *apy akārādī* (1.52) *prāptih*. ⁽⁶⁾ O. om. ⁽⁷⁾ O. om. ⁽⁸⁾ O. om. ⁽⁹⁾ O. om. ⁽¹⁰⁾ G. M. om. ⁽¹¹⁾ G. M. ins. *nann*. ⁽¹²⁾ O. *vidēdvivigivāçugruvāçasve*. ⁽¹³⁾ W. om. *parā*; G. M. -para. ⁽¹⁴⁾ G. M. -shasasya. ⁽¹⁵⁾ G. M. O. -iter. ⁽¹⁶⁾ W. *makārasya* *'gamah*; O. ... *evā* *'nuscārāçg*. ⁽¹⁷⁾ G. M. -ma. ⁽¹⁸⁾ W. -svārāç. ⁽¹⁹⁾ G. M. O. *tatāçh*. ⁽²⁰⁾ W. G. M. *hravānt*. ⁽²¹⁾ W. *iti* *'ty*.

आकारिकारोकाराः सिषिपराः पदान्तयोः ॥ १४ ॥

14. The vowels *ā*, *i*, and *ū* have *anusvāra*, when they are followed by *si* or *shi* final.

This rule, of course, applies to the nominative, accusative, and vocative plural of neuters in *as*, *is*, and *us*. The illustrative examples are *vayāṅsi pakvagandhena* (v.7.23), *tamāṅsi gūhatām ajushā* (i.8.22^o: only O. has *ajushā*), *daṣa haviṅshi* (vii.5.14²), *jyotiṅshi kurute* (v.4.1⁴: O. omits), *agna āyāṅshi* (i.3.14⁷ et al.), and *avabhrthayajāṅshi juhōti* (vi.6.3¹: G. M. omit *juhōti*). To show that the *si* or *shi* must be final, are quoted *tasmād vāsishtho brahmā* (iii.5.2¹: only G. M. have *brahmā*), and *manāshino manasā* (iv.6.2^o: O. omits *manasā*). To show that the preceding vowel must be long, we have *yathā 'nasi yukta ādhīyate* (v.4.10²: only G. M. have the last word), *jyotis tē jāyotishī* (i.1.10³), and *āyushī durone* (i.2.14³); and, finally, to show that no other vowel than *i* after the *s* or *sh* calls out the increment, *prajāsv eva prajātāsv* (vi.4.1³), *oshadhishu* (iii.5.5² et al.), and *tanūshu buddham* (i.8.22^o).

The last six counter-examples are omitted in O., which adds at the end the obvious remark that, as *si* and *shi* are here indicated as occasions of the preceding *anusvāra*, that value no longer belongs to *s* merely—that is to say, the force of the heading given in rule 1 is henceforth at an end.

विकृते ऽपि ॥ १५ ॥

15. Even when the *i* is altered

That the *i* of the ending *si* or *shi* is here aimed at is in the nature of the case obvious enough, but not at all distinctly intimated by the terms of the rule. The commentator quotes in illustration *chandāṅsy upa dadhāti* (v.3.8^{1,2}), *haviṅshy ā sādāyet* (i.6.10³), and *tapūṅshy agne juhvā* (i.2.14¹: G. M. omit *juhvā*).

14. *sishiparā ākārekārokārās tayoh sishyoh padāntayoh sator anusvārāgamam bhajante¹. yathā²: vay-----: tam-----: daṣa-----: 'jyot-----³ agna-----: avabh----- padāntayor⁴ iti kim: tasmād-----: manā-----: 'ākārekārokārā iti dīrghena⁵ kim: yathā-----: jyotis-----: āyushī----- sishī 'ty⁶ atre 'kāreṇa kim: prajā-----: osh-----: tan-----⁷*

¹ MSS. *jate*. ² O. om. ³ O. om. ⁴ O. -ta. ⁵ G. M. *dīrghāh*; O. om., with all that follows. ⁶ W. B. *ity*. ⁷ O. adds *sishiparanimittayor nideṣāt sakārasya paranimittateva bhāti*.

15. *opīcabdānvādishte¹ sishyor ikāre vikṛte 'pi yakāram āpanne 'pi bhavaty anusvārāgamah. yathā²: chand-----: hav-----: tap-----*

¹ W. B. O. -bdone-; G. M. -bdenā 'ne-. ² G. M. O. om.

अनाकारो ह्रस्वः सांक्रृत्यस्य ॥ १६ ॥

16. According to Sāmkrtya, the vowel, except *ā*, is short.

That is to say, the two vowels *i* and *u*, to which alone reference has been made above, become short in the cases here referred to: for example, in *haviṇshi bhavanti* (v.5.1⁷ et al.: O. omits *bhavanti*) and *samishṭayajāṇshi juhoti* (vi.6.2¹: G. M. O. omit *juhoti*), where Sāmkrtya would read *haviṇshi* and *yajuṇshi*, while in *vayāṇsi* (v. 7.23 et al.: O. omits) he would admit the long vowel.

A curious case of dissent upon a point in grammar which we have not been accustomed to regard as open to any difference of opinion. The rule is, naturally enough, pronounced unapproved.

G. M. add *ca* to the rule, after *sāmkrtyasya*.

न पदे द्विस्वरे नित्यम् ॥ १७ ॥

17. Not, under any circumstances, in a dissyllabic word.

This is a rule prescribing exceptions under rule 14; the addition *nityam*, 'under any circumstances,' confirms its application to words ending in *si* or *shi* after *ā*, *i*, or *u* which would otherwise fall under any other rule prescribing the increment.

Examples under rule 14 alone are first quoted, namely *stuto yāsi vaçāṇ anu* (i.8.5¹: G. M. O. end with *yāsi*) and *yāsi dātah* (iii.5. 5²: G. M. have dropped out *yāsi*). Then, as a case also under rule 2, we have *vidhatah pāsi nu tmanā* (i.3.14³); and, as one under rule 8, *prathame māsi prsthāni* (vii.5.3⁴: G. M. omit the last word), which has been already made the subject of discussion under rule 12, above. The force of the *nityam* does not go so far as to prohibit an *anuscāra* in every dissyllabic word before *si*, what-

16. *ākārād anyo 'nākārah: ikāra ūkāraç ce 'ty arthaḥ: tayor eva prakṛtatvāt. sāmkrtyasya mātā ikāra ūkāraç ca hrascam āpadyate. yathā: hav-----: sam----- 'anākāra iti kim: vayāṇsi.*⁵

ne 'dam sūtram iṣṭam.

¹ O. om. ⁽²⁾ O. om.

17. *deisvare⁶ pade vartamānā⁷ ākārekārokārāḥ⁸ padāntasishiparā⁹ nā¹⁰ 'nuscārāgamam¹¹ bhajante. yathā: stuto-----: 'yāsi----- nityaçaabdaḥ prāptyantarapratishedhārthaḥ: vidhatah-----: 'sraçoha¹² (xvi.2) iti prāptiḥ: prathame-----: mā padādīr¹³ (xvi.8) iti prāptiḥ. dvāu svarāu yasmin¹⁴ vidyete tad deisvaram: tasmin.¹⁵*

¹ O. *deisvare*. ² G. M. *-na*. ³ G. M. *ākārah ikārah*; O. *ākāraūkārah*. ⁴ G. M. *-ntas sishiparo*; O. *-ntā si*. ⁵ B. om.; G. M. *nityam nā*. ⁶ B. *ins na*; O. *ins nityam*. ⁷ G. M. O. om. ⁽⁸⁾ W. om. ⁽⁹⁾ B. om. ¹⁰ O. *-hapāça padādaya*. ¹¹ O. *-dīr ijās*. ¹² G. M. *ins pade*.

ever vowel precedes, or it would include *hañsi* also, and possibly other cases.

स्त्रीषिजिगासिजिघास्यजासियजासिददासिदधासिवर्तया-
सि च ॥ १८ ॥

18. Nor in *rjishi*, *jigāsi*, *jighāsi*, *ajāsi*, *yajāsi*, *dadāsi*, *dadhāsi*, and *vartayāsi*.

These are verbal forms which need to be excepted under rule 14, and which, as containing more than two syllables, are not reached by rule 17. The passages in which they occur are quoted by the commentary, as follows: *tena rjishi sarvāni* (iii.2.2¹: only O. has *sarvāni*), *achā jigāsi* (iv.2.4²), *ā tvam ajāsi garbhadham* (vii.4.19¹), *havishā yajāsy agne brhat* (iii.5.11² et al.: O. omits the last two words), *yābhir dadāsi dāgushe* (iii.3.11³: G. M. omit *dāgushe*), *dadhāsi dāgushe kave* (iv.2.7²), and *agvam ā vartayāsi nah* (vii.4.20). *Yajāsi* I have noted in two or three other passages; if the rest occur elsewhere, I have overlooked them. This leaves unaccounted for *jighāsi*, which is declared to occur "in another text," in the passage *prathame jighāsi*.

दस्नानाम्योदस्सोभिर्दस्संवृषदस्शोदस्शुकादस्द्राम्यां परः

॥ १९ ॥

19. In *dañsanābhyah*, *dañsobhih*, *dañsam*, *vrshadañcah*, *dañcukā*, and *dañshtrābhyām*, *anusvāra* is taken in the latter place.

The commentator's citations are *vāiṣvānarasya dañsanābhyah* (i.5.11¹); *sajoshāv aṣvinaḥ dañsobhih* (v.6.4¹), to which is added as counter-example, proving the need of the *-bhih*, *yushmāko* "ti *ri-gādasah* (iv.3.13²: O. has only the last word, and G. M. begin

18. ¹ *cakāro nishedhākarshakah: rjishiprabhrtishu² grahaṇe-shu³ nā 'nuscārāgamah syāt: ākārekārokārā* (xvi.14) *iti prāp-tih. bahusvaratvād⁴ eshu⁵ pūrvasūtranishedo⁶ na sidhyati⁷ 'ty atrā⁸ 'yam ārambhaḥ. yathā: tena..... achā..... jighāsi⁹ 'ti śākhāntare: ¹⁰prathame jighāsi¹¹ 'ti¹²: ā..... havishā..... yābhir..... dadhāsi..... agvam.....*

¹ O. ins. an enumeration of the words in the rule. ² G. M. -rti. ³ O. om. ⁴ G. M. -rādī. ⁵ B. *esha*; G. M. om. ⁶ G. M. -tre ni-; W. B. -dhān. ⁷ O. om. *atra*. ⁸ G. M. O. om. ⁹ G. M. -āsi. ¹⁰ O. om.; W. *prathame* — — — (as being illegible in the MS. from which the copy was made); B. -ghāsati.

19. ¹ *dañsanābhyah ityādishu² grahaṇeshu para evā 'nuscārā-gamo bhavati³. yathā: vāiṣv..... saj..... bhir iti kim: yushm.....⁴ puruḥ..... vrsh..... paśūn..... dañsh..... dañse 'ty etāvatai⁵ 'vā 'lam: kim akhilapadapāthena⁶. kur-*

with *ūti*); *purudaṅsaṁ sanim* (iv.2.4³); *vṛshadaṅgaḥ te dhātuh* (v.5.12): there is another case at v.5.21; *paṅān daṅgukāḥ syer yad viśhācinam* (v.2.9⁶: O. omits the first word, and it alone has the last two); and *daṁṣhtrābhyām malimlān* (iv.1.10²): there is another case at v.7.11. To the objection that the citation in the rule of *daṁṣa* simply might have saved the rehearsal of whole words [in a part of the cases given], the commentator replies by quoting *kurvato me mo 'pa dasat* (i.6.3² et al.) as an example of cases which need to be excluded. The addition of *paraḥ*, 'in the latter place,' is because *vṛshadaṅgaḥ* contains two places at which, by xv.4, the *anuvāra* would otherwise require to be inserted.

This last point, however, does not pass (except in O.) without farther question and discussion. The objection is raised that the mere citation of *vṛshadaṅga* without *anuvāra* before the former sibilant is enough to settle its reading, according to the same principle that was appealed to under rule 13, for *hrasīyā*, *vasīyā*, and so on. This is undeniable; and the only real answer to be made is that there was no harm in adding *para* here, to make the matter sure, while it could not have been employed in rule 13 without occasioning a great deal of additional trouble. The commentator, however, prefers to have recourse to a plea of exceptionally puerile character. In xv.4 (the rule here in force), he says, the spirants in general are implied, but in xvi.1 (in force at rule 13) a special spirant, *s*; and it is an acknowledged principle that, as between a generality and a specification, the specification is the more powerful. That being the case, the putting down of that

vato.... ityādāu mā bhūd iti. 'para iti kim: vṛshadaṅga ity atra' sthānadvaye 'pi srādishu cāi 'kapada (xv.4) iti prāptāu satyām pūrcatra' mā bhūd iti. nanu grahaṇasāmāthyād evā 'nuscārah' pūrcatra na bhavati: yathā hrasīyāvasīyā (xvi. 13) ityādāu grahaṇasāmāthyād' upapādītum. nāi 'sha doshaḥ: srādishu cāi 'kapada (xv.4) ity atra "shmasāmānyam uktam: atha sakāraparā (xvi.1) ity atra tu tadviṣeṣa uktāḥ: sāmānyaviṣeṣayor viṣeṣo balacān iti nyāyah: tathā sati ¹²balacadbādhanam¹³ eva bhūṣaṇam ¹⁴na tu¹⁵ durbalabādhanam¹⁶ iti¹⁷ tatratī 'va grahaṇasāmāthyam¹⁸ samarthaniyam: na tv atra¹⁹ durbalasthāne; tathā 'pi²⁰: ²¹adhikāḥ²² puruṣo virodhinam²³ adhiḥkam eva bādhatē bhūṣaṇatvāt: na tu kadācid alpabalam²⁴: iti²⁵ paraḥabdoprayoga²⁶ upapadyate.

¹ O. prefixes a separate rehearsal of the words in the rule. ² G. M. -di. ³ G. M. syāt. ⁴ in W. only. ⁵ O. ins. *ity atra 'py akārādī* (i.52) *iti vacanād anuvāragamah syāt: tan mā bhūd iti.* ⁶ G. M. -thanena. ⁷ O. om. ⁸ W. aca. ⁹ W. -ra. ¹⁰ B. -rīgamaḥ. ¹¹ W. *sāmāthyōgrahaṇam.* ¹² W. *balavatīyam eva bhūṣaṇam: vādhanam eva bhūṣaṇam na tu durbalam iti bādhanam.* ¹³ G. M. -vatsīdh-; B. -dham. ¹⁴ G. M. om. ¹⁵ G. M. -lavādhanam na sādhe. ¹⁶ W. -nam eva sāmāthyam; B. -rīthya. ¹⁷ B. *artha.* ¹⁸ G. M. *hi.* ¹⁹ G. M. ins. *loke.* ²⁰ W. *adh-; G. M. -ka.* ²¹ W. -dhanam. ²² W. B. *apy alpam.* ²³ B. *iti 'ti.* ²⁴ W. B. *atra 'abd-*

which is powerful, not of that which is weak, is honorific; hence, the competency of the citation was to be insisted on in the former rule, but not here, in a weak position. Moreover, a superior man puts down, for honor's sake, a mighty opponent, but never a weak one. Therefore, the use of the word *para* here is right and proper!

All the MSS. except B. (and G. M., which have a slight *lacuna*, involving the word) read *dañsan* instead of *dañsam* in the rule.

मन्स्येमन्सतैयन्सद्यन्सन्वन्सतेवन्सगः ॥ २० ॥

20. Also in *mañsye*, *mañsatāi*, *yañsad*, *yañsan*, *vañsate*, and *vañsagah*.

The commentator quotes as follows: *paçûn nâ 'bhi mañsya iti* (iii.1.9⁶), *anu nâu çûru mañsatāi bhadrā indrasya rātayaḥ* (vii.4.15: O. alone has the first two words, B. alone the last one), *çocishā yañsad viçvam ny atrinam* (iv.6.1²: G. M. O. omit *çocishā*), *ishavaḥ çarma yañsan* (iv.6.6⁴), *agnir no vañsate rayim* (iv.6.1⁵), and *tigmacçrūgo na vañsagah* (ii.6.11⁴). The words here dealt with occur only in the passages quoted, except *yañsat*, which is found also at iv.1.11²; 7.14³. To the objection that it would have been enough to give *mañs*, *yañs*, and *vañs* (the MSS. leave it doubtful whether these are the precise forms suggested) in the rule, instead of citing whole words, the commentator replies by giving the counter-examples *uttamasyā 'va dyati* (vi.3.10⁴), *yasya bhūyañso yajñakratavaḥ* (iii.1.7²), and *adya vasu vasati* (ii.5.3⁷).

उन्न वन्शन् ॥ २१ ॥

21. Also in *vañçam*, after *ut* or *na*.

The passages are *ud vañçam iva yemire* (i.6.12²: W. has dropped out *yemire*, along with all the rest of the comment) and *prācinavañçam karoti* (vi.1.1¹ twice). A counter-example, with a different preceding word, is *brahmararcasy eva bhavati vaçam vā esha carati* (ii.1.7⁷: only O. has the first two words, and it omits the last two).

20. ¹ *mañsya ityādīshu² syād anusvārāgamah. yathā³: paçûn*
.....: *anu*.....: *çoc*.....: *ishavaḥ*.....: *agnir*.....: *tigm*
.....: *'mañs: yañs: vañs:* *ity etāvatāi 'vā 'lam: kim akhila-*
padapāṭhena: utt.....: *yasya*.....: *adya*..... *ityādāu mā bhād*
iti.

¹ O. prefixes a separate rehearsal of the words in the rule. ² B. -di. ³ G. M. O. om. ⁴ W. *bhadrayañ*; B. *sañsūr yañs vañs*; G. M. *mañsa: yañsa: vañsa*; O. *mañse: yañse: vañse*.

21. *ut: na: ity evampūrve² vañçam ity asmin grahaṇe syād*
anusvārāgamah. ud.....: *'prā*..... *'evampūrva iti³ kim:*
brahm.....⁴

¹ O. *uñsayatebhrat*. ² W. -reo; B. -rea. ³ W. om. ⁴ O. *unne 'ti*.

अक्रंस्तक्रंस्यतेरंस्यतेब्रंशते ॥ २२ ॥

22. Also in *akraṇsta*, *kraṇsyate*, *raṇsyate*, and *bhraṇṣate*.

The passages are *dyām vājy ā 'kraṇsta* (vii.5.19¹), *utkraṇsyate svāhā* (vii.1.19²), *uparaṇsyate svāhā* (vii.1.19¹: B. O. omit), and *nā 'smād rāshtram bhraṇṣate* (v.7.4⁴: O. omits the first two words); *bhraṇṣate* occurs also at i.6.11¹ twice.

G. M. read *utkraṇsyate* for *kraṇsyate* in the rule.

रंश्यै च ॥ २३ ॥

23. And also in *raṇhyāi*.

The only passage is *pūshno raṇhyāi* (i.3.10²). The significance of the *ca*, 'and,' which is here out of its proper place, will be given, we are told, under the next rule.

ऐकार उव्यस्य नितातः ॥ २४ ॥

24. The *āi*, according to Ukhya, is excessive.

That is to say, according to the commentator, the *āi* of the word *raṇhyāi*, here brought forward by the *ca*, 'and,' which is read in the preceding rule. *Nitānta*, 'excessive,' is explained as signifying 'uttered with more violent effort.' The whole business is a very queer one—Ukhyā's opinion itself, its introduction here at a place where it is entirely impertinent, and the bit of interpretation whereby it is worked into the connection.

विरित्रि संख्यासु ॥ २५ ॥

25. Also in *vi*, *ri*, and *tri*, in numerals, except in *su*.

22. 'akraṇste 'tyādishu syād anusvārāgamah'. *dyām*.....: *utkr*.....: 'upa'.....: 'nā'.....

(¹) O. substitutes a separate rehearsal of the words in the rule (except the last), and *eteshu grahaṇeshu anusvārāgamo bhavati*. (²) B. O. om.

23. *raṇhyā ity asmin grahaṇe syād anusvārāgamah*. *pūshno*..... *cakārasya 'vyatihāreṇā 'nvaya' uttarasātre prayojanam ucyate*.

(¹) G. M. *vyavahārād anvyād*.

24. *raṇhyā ity asmin' grahaṇe pūrvasūtrasthacakārasamar-pita' āikāro nitānto bhavati 'ty' ukhyasya' matē*. *nitāntas tīra-taraprayatna ity arthah*.

ndi 'tan matam iṣṭam.

¹ G. M. om. ² B. -*trasya cak*.; O. -*treprayasthacak*.; G. M. -*pīte*. ³ G. M. om. *iti*. ⁴ W. *ukhya*; O. *ukhyasyā 'cāryasya*. ⁵ O. -*tan*.

The syllable *su* is here, the commentator tells us, the ending of the locative case, just as *ah* (at i.23) is used as representing the nominative case. This remark is called for, because (see the example below) the actual form in which the syllable appears in the cases aimed at is *shu*. We have a right to be surprised at finding it given as *su* in the rule; and perhaps, also, to conjecture that *samkhyāsu* was originally simply the locative plural of *samkhyā*, and that the other value was interpreted into it when the cases calling for exception were noticed.

The quoted examples are *viñgatyāi svāhā* (vii.2.13 et al.: O. omits), *yad viñgatir dee tena virājāu* (v.3.3²: G. M. omit the last two words, O. the last three), *catvāriṅgate svāhā* (vii.2.17: G. M. O. omit *svāhā*; B. has dropped out *-te svāhā*, the next example, and the first word of the next but one), *triṅgate svāhā* (vii.2.17: O. omits *svāhā*), and *triṅcat trayaḥ ca* (i.4.11¹); there are other cases, which I have not taken the trouble to collect. The inclusion of *tri* in the rule, the commentator says, is for the sake of greater plainness, since *ri*, of course, involves *tri* also; it is to be compared with the inclusion of the *v* of *vāghā* in rule vii.13. Begging the commentator's pardon, however, the two cases are not at all analogous; and the citation of *tri* and *ri* together must be esteemed an oversight, and an offense against the law of economy of expression, obligatory in the *sūtra*-style. The need of restriction to numerals is illustrated by *viḥ janāya* (ii.5.12³), *sa rishah pātu naktam* (i.2.14⁷ et al.: G. M. O. omit *naktam*), and *trishtubhāi 'vā 'smāi* (ii.5.10¹ et al.). Finally, the specification "not before *su*" is established by *trishv ā rocane divaḥ* (iv.2.4⁴ et al.: O. omits *divaḥ*); if there is another case of this kind, I have failed to note it.

There is yet another word, *trishāhasrah* (v.6.8³; p. *tri-sāhasrah*), which would properly fall under this rule, but is exempted by a pregnant interpretation of the word *ekapade* in xv.4 (see the note to that rule).

शिंशुमारःशिंषत्संश्वासंश्वासंमृष्टसंस्कृत्यसंस्कृतसंशितसंशिताकिंशिलकिंशिला ॥ २६ ॥

25. *vi: ri: tri:* ¹ *evampūrva ūshmaparo* ² *'nusrāgamaḥ* ³ *syāt: ebhir yadī* ⁴ *samkhyo 'cyate:* *asu* ⁵ *sugabdam varjayiteā. su* ⁶ *saptamī vibhaktir uktā: yathā 'hkarāḥ* ⁷ *prathamāvibhaktiypalakṣaṇam:* *viñ-----: yad-----: catv-----: triñ-----: triñ-* ⁸ *gat-----: trigrāhaṇam vispashtārtham: yato* ⁹ *virī samkhyā 'sv* ¹⁰ *ity¹¹ etācatāi 'vā 'lam: yathā vāghāshapurva* (vii.13) *ity atra* ¹² *vakāro vispashtārthaḥ. samkhye 'ti kim: viḥ-----: sa-----: trishv-----: ase iti kim: trishv-----*

¹ G. M. O. *ins. ity.* ² B. *ūkarap.* ³ G. M. *-ro āp.* ⁴ G. M. *yadā.* ⁵ O. *'cyetā.*

⁶ W. a. ⁷ G. M. *sv itī;* O. *su itī.* ⁸ B. *ak-;* G. M. *āk-* ⁹ O. *-kter up.* ¹⁰ B. *om.*

¹¹ G. M. *om.* ¹² O. *om.*

26. Also in *giñcumārah*, *cīṃshat*, *sañcā*, *sañsrā*, *sañsrshā*, *sañskṛtya*, *sañskṛta*, *sañcita*, *sañcitā*, *kīñcila*, and *kīñcīlā*.

The passages, as quoted, are *sindhoh giñcumāro himavatoḥ* (v. 5.11: only O. has the last word); *kiñ tata uc cīṃshatī 'ti yad dhiranyeshtakāḥ* (v.5.5²: only O. has the last two words, and it omits the first two); *ubhayataḥsañcāyī kuryād avadāyā 'bhi* (ii. 6.8⁴: only O. has the last two words, and it leaves off *ubhayataḥ*); *sañsrācābhāyā stha* (i.1.13²); *sañsrshajit somapāḥ* (iv.6.4¹: W. B. put this after the next following example; see farther on); *garīram eva sañskṛtyā 'bhyārohati* (v.6.6³⁻⁴: O. omits the first two words; and all but O. omit the last one, thus making a citation which is also found again in v.6.8⁴); *tan nah sañskṛtam* (i.4.43²); *brahmasañcito hy eṣā gṛtāhavanah* (ii.5.9²: only O. has the last word); *gararye brahmasañcitā* (iv.6.4⁴); *kīñcila vanya yā ta ishuh* (v.5.9¹: all but G. M. end with *te*); and *kīñcilaḥ caturtho vanyah* (v.5.9²: G. M. alone have *vanyah*) and *kīñcīlāya ca kṣayāndya ca* (iv.5.9¹: O. ends with the first *ca*). The commentary prefaces the last two passages with the remark that the second citation of *kīñcila* is that of a part of a word, including a variety of cases. But this, in the first place, would imply that the reading of the rule at the end was *kīñcilakīñcila*, which is the case only in T.; and, in the second place, even were that the reading, the explanation would be a bad one, and the repeated *kīñcila* should be defined as a theme ending in *a*, and so including the declensional forms of that theme, by i.22: in fact, it was expressly cited under that rule, as an example of its application. If *kīñcīlā* is the true reading (as I presume to be the case), then we must suppose that the makers of the rule intended both words as *padāikadeṣa*'s, the one involving the first two examples quoted, the other the third, and the case being quite parallel with that of *sañcita* and *sañcitā*, just preceding: but the comment has discovered a difficulty, namely, that *kīñcila* is actually a *pada* in the text (v.5.9¹), and therefore cannot be quoted without ceremony as a *padāikadeṣa* (see under rule 29, where this is more distinctly brought out); and hence its efforts to amend the reading and interpretation—efforts in which it is too intent upon the end to be gained to be mindful of consistency in the means employed. In short, here as in many other places, the *Prāṭiśākhya* is less minutely accurate in its modes of statement than the commentator would fain have it, and he undertakes to make it what it should be by forced interpretation.

26. ¹ *giñcumāra ityādigrahaneshu² syād anuvārāgamah. ya-
thā: sindhoh.....: kiñ.....: ubhay.....: sañsr.....: sañsr-
.....: garī.....: tan.....: brahm.....: ⁴ gar.....: kiñ-
.....: parakiñcīlagrahanam³ padāikadeṣatayā bahūpādānār-
tham: kiñcīlaḥ.....: kiñcīlāya.....: nom⁵ sañsrshite 'ty atra
shakāroparo 'nuvārāgamah kiñ na syāt. māi⁶ 'vam: atra sūtre
sareotra⁷ padādicarṇānantaram⁸ evā 'nuvārādarṣanāt: tatsāha-*

Cases of various character are here intermingled. The first two and the last are indivisible words, of which the *anuvāra* forms an essential part, as of those cited in rules 19 and 20, or 29 and 30. The others come from combinations with the preposition *saṃ*, and are of two classes: *saṃskṛtya* and *saṃskṛta* the *pada*-text does not attempt to analyze, although (see v.6,7) it divides *saṃskurute* and *saṃskurvata*, ejecting the intrusive sibilant: those remaining are compounds with *saṃ* which enter into further composition, so that their compound character does not appear in the *pada*-text. And one or two cases of this last class seem to have been overlooked by the makers of the treatise: they are *svādushaṇṣadaḥ* (iv.6.6³; p. *svādu-saṇṣadaḥ*) and *striṣaṇṣādam* (ii.5.1⁵; p. *stri-saṇṣādam*). The former of them, indeed, is noticed in G. M., which introduce *saṇṣadaḥ* into the rule, after *saṃskṛta*, and quote the compound in the comment—seeming to betray their consciousness that the word is not a part of the ordinary reading of the rule by saying “when *saṇṣadaḥ* is read, the instance is *svādushaṇṣadaḥ*.”

There are further varieties of reading in the rule: G. M. have *gīṇshati*; W. B. put *saṃskṛta* between *saṃskṛtya* and *saṃskṛta*, and give its example a corresponding place among the examples; T. B. G. M. read *saṃskṛtaṇ*, which is perhaps to be preferred; other differences are mere copyists' errors, and not worth reporting.

So far as I have discovered, *saṃskṛtam* (i.2.9) and *saṃgita* (iv.6.4⁴ a second time) are the only words included in this rule which occur further in the *Sanhitā*.

The commentator raises the question whether we must not suppose that an *anuvāra* is also to be inserted before the spirant *śh* in *saṃskṛta*; but, without this time appealing to the “competency of the citation” to settle the reading, replies that, the word being associated here with others all of which have *anuvāra* only after the first vowel, we must assume the same to be the case with it also; all but O. adding that “there is no reason for inconsistency” in this respect.

सिन्धु हकारपरः ॥ २७ ॥

27. Also after *si*, *tr*, or *dr*, when *h* follows.

The quoted examples are *siṇho vayah* (iv.3.5), *ṣatatarhāṇs trīhanti* (i.5.7⁶ et al.), and *dr̥ṇhasva mā hvāh* (i.1.3 et al.). Of the

caryād atrā 'pi tathāi 'va" vijñeyam: "na vāiparītye kāraṇam asti"¹.

¹ O. prefixes a separate rehearsal of the words cited in the rule. ² G. M. -*dishu* gr.; O. -*dishu*. ³ G. M. O. om. ⁴ G. M. ins. *saṇṣada itī pāthe svādushaṇṣadaḥ*. ⁵ W. *param ki*. ⁶ G. M. om. ⁷ W. G. M. *sarva*. ⁸ W. *vayā*; G. M. -*paścaram*. ⁹ O. *sāh*. ¹⁰ B. 'vā 'pi. ¹¹ O. om.; W. om. *na*.

27. *si*: *tr*: *dr*: *ity evampūro hakāraparah*¹ *syād anuvāra-gamah*². *yathā*³: *siṇho*.....: *ṣatat*.....: *dr̥ṇh*..... *'evam*

noun *siñha*, and of forms from the roots *trñh* and *drñh*, which alone come under the action of the rule, there are other cases in the Sanhitā. Counter-examples are given (excepting in O.): to show that no other syllables take the increment before *h*, *sapatnasāhī svāhā* (i.2.12²; but G. M. substitute *sapatnasāhīñ sam mārjmi*, i.1.10¹) and *anati-dāhāyo 'vāca* (v.2.10³); that *r* takes the increment only when preceded by *t* or *d*, *grhānām asamartyāi* (iii.3.8²); that the increment is taken only before *h*, *sishāsantih* (vii.5.2¹; G. M. read *sishāsah*, but doubtless by a blunder only), *trshvīm anu* (i.2.14¹), and *naktam dr̥ce dīpyate* (v.6.4⁴).

मन्दिष्ठस्य च ॥ २८ ॥

28. As also, in *mañhishthasya*.

That is to say, before the *h*, which is brought down from the preceding rule by *ca*, expressly in order to exclude the assumption of *anusvāra* before the *sh* and *s* in the same word. The passage is *mañhishthasya prabhrtasya* (iv.2.3⁴), and there is no other.

आदिर्ऋतिरंहोऽहोरहोमुगन्यंहाग्रहसोऽह-
माश्मशुभिरश्मभुवाश्चश्मश्मश्वोऽशुरश्मुमश्म-
नश्मुनाशोरशायोपाश्चशौ ॥ २९ ॥

29. Also, after the first vowel, in *añhatih*, *añhah*, *añhoh*, *añhomuc*, *atyañhāh*, *añhasah*, *añhasā*, *añcam*, *añcubhih*, *añcabhuvā*, *añcu*, *añcū*, *añcavaḥ*, *añcuḥ*, *añcum*, *añcūn*, *añcunā*, *añcoḥ*, *añcāya*, *upañcu*, and *añcāu*.

We have here a detailed list of complete *padas* (or, in one or two instances, more than a whole *pada*), in which *anusvāra* is found. The illustrative examples are as follows. For *añhatih*, *pari dveshaso añhatih* (ii.6.11²): the only case. For *añhah*, *añhomucam vṛshabham yajñīyānām* (i.6.12⁴; p. *añhah-mucam*: G. M. O. omit the last word); *añhah* is found four or five times in the Sanhitā as an independent word, and about fifteen times in the

*pūrva iti kim: sap----- anati----- rkārenāi 'vā 'lam: kim takāradakārābhyām: grh----- evampara iti kim: sish----- trshvīm----- naktam----- hakārah paro yasmād 'asāu hakāraparah.*⁵

¹ G. M. -raç ca. ² O. asāu hekāraparah. ³ B. G. M. O. om. ⁽⁴⁾ O. om. ⁵ G. M. om. eva. ⁶ G. M. sa tathoktah.

28. *mañhishthasye 'ty asmin grahane cakārākṛṣṭāhakāraparo 'nuscārāgamo bhavati. yathā: māñh----- 'cakārah kimarthaḥ: atrāi 'va grahane sushakāraparo mā bhād iti.*²

¹ G. M. O. syāt. ² G. M. O. om. ⁽³⁾ O. om.

compound *añhomuc*—one of the forms of which, as we shall see farther on, has to be made separate account of. For *añhoh*, *añhog cid yā* (i.4.22 and ii.1.11⁴): there is no other case. For *añhomuk*, *añhomugbhyām dvikapālah* (vii.5.22: O. omits *dvikapālah*, and W. B. put it in out of place); of all the forms of *añhomuc*, this is the only one in which *añhah* does not form a *pada* (it is divided, of course, *añhomuk-bhyām*), and which therefore is not disposed of by the citation of *añhah*. For *atyañhāh*, *ṛtapāc cā 'tyañhāh* (i.8.13²⁻³): the word is found again at iv.6.5⁵; it is more than a simple *pada* (p. *ati-añhāh*), and the *ati* is included in the citation, we are told, to prevent confusion of *añhāh* with *ahāh* in such phrases as *shaduhā bhavanti* (vii.5.1⁴; *shat-ahāh*). For *añhasah*, *te no muñcatam añhasah* (iv.7.15⁶: all except B. read *muñcante*, which does not occur before *añhasah*): of this case of *añhas* I have noted about twenty instances. For *añhasā*, the only example is the one quoted, *añhasā vā esha grhītaḥ* (ii.4.2³: O. ends with *vāi*). The commentator next raises the question why whole *padas* should have been cited, when *añha* (as part of a word) would have been sufficient to assure the reading, and replies by quoting *sa rasam aha vasantāya* (vii.2.10¹: O. begins with *aha*), as an example of cases that required to be excluded. For *añcum*, *pari payāmo 'ñcum ā* (vii.1.6²: O. omits *ā*): the form is found again in the same division. For *añgubhiḥ*, *shadbhir añgubhiḥ pavayati* (vi.4.5⁷: O. omits *yavayati*; W. B. put this example off until after that for *añcu*, which would be, to be sure, a more suitable place for it, if the same order were followed in the rule; but there all authorities agree: see further on). For *añgabhuṃvā*, *tvayā 'ñgabhuṃvā somam* (vi.4.8²: G. M. O. omit *somam*): the word is found again at vi.4.8³. For *añcu*, *tenā 'ñcumat* (iii.2.2¹): and it is pointed out that, by rule i.53 (the comment blunderingly quotes i.52 instead), *anañcu kurrantaḥ* (iii.2.2¹) is involved with *añcu* (O. has lost, of this, all but the example *anañcu ku*). For *añcū*, *vṛkṣṇo hy etān añcū* (vi.4.5³). For *añcavaḥ*, *prānā vā añcavaḥ* (vi.4.4⁴). For *añcuḥ*, *añcur añcus te* (i.2.11¹ et al.): the word is found in eight other passages. For *añcum*, *yam ādityā añcum āpyāyayanti* (ii.3.5³ et al.: only W. has the last word): there are five other instances. For *añcūn*, *añcūn apa grhṇāti* (vi.4.4⁴: lost in W.): it occurs further in the

29. ¹ *añhatih*..... *eteshv ādir² anusvārāgamo³ bhavati⁴. ya-
thā⁵: pari*..... *añho*.....: *'sūtre saṃhitāyām oṭvavidhānād
ahar*.... *ityādāu na syād ayaṃ vidhiḥ: kimtu yasmin visar-
janīyo rephaṃ nā 'padyate tasyāi 'co 'pādānam⁶. añhog*.....: ⁷
*'nanv ayaṃ⁸ cāi⁹ 'kabandhaḥ: rephaprāptasyā¹⁰ 'yam vidhiḥ:
vihitānusvārasyāi 'va¹¹ rephanishedhate¹² 'ti: nā 'yam doshaḥ:
siddhasyāi 'vā¹³ nusvārasya bodhanam¹⁴ na tu vidhir iti¹⁵: añ-
hom*.....: ¹⁶ *ṛtap*.....: *ati 'ti kim: shad*.....: *te*.....: *añ-
hasā*.....: ¹⁷ *añhe 'ty¹⁸ etāvatā¹⁹ siddhe²⁰ sakalepadapāthah kim-
arthah²¹: sa rasam*.... *iti²² nishedhārthah: pari*.....: ²³ *shad*

same division, and in no other. For *añṣunā*, *añṣunā te añṣuḥ* (i.2. 6: G. M. O. end with *te*). For *añṣoḥ*, *yo vā añṣor āyatanam veda* (vi.6.10²: O. omits the last two words, and B. has lost the whole example, with most of the preceding one). For *añṣāya*, *añṣāya svāhā bhagāya* (i.8.13²: G. M. omit *bhagāya*). For *upāñṣu*, *upāñṣusavano yad upāñṣusavanam* (vi.4.4¹: O. omits the first two words). The word *upāñṣu*, when not further compounded, is separated in *pada*-text into *upa-añṣu*, and so most of its forms come under the various citations of the cases of *añṣu* already illustrated (thus, it furnishes additional instances, not counted above, to *añṣu*, *añṣuḥ*, *añṣum*, and *añṣoḥ*, twenty in all); but in its compounds it makes, of course, a single *pada* of itself (thus, *upāñṣu-savanam*), and so has to be cited in the rule as such (we have other combinations, namely, with *pātra*, *yāja*, and *antaryāma*); and, moreover, we have one case, *upāñṣāu*, showing a form of *añṣu* which does not appear independently, and so furnishing the final citation, for which the example is *tam upāñṣāu sam asthāpayan* (vi.4.6¹): there is another in the same division.

The restriction *ādih*, 'after the first vowel,' is intended to guard against any one's imagining that the *s* of *añhasaḥ* and so on is to be preceded by *anusvāra*.

What has thus been given represents the whole comment as found in O.; the other MSS. make two or three troublesome additions, to which it is necessary to return. The last of them regards the citation of *añṣu* and its inflectional forms (namely, those that contain *añṣu* as a part, or *añṣubhiḥ*, *añṣuḥ*, *añṣum*, *añṣunā*); and, if I understand it aright, it asserts that, if *añṣu* alone were cited, the other forms would not be included, because *añṣu* itself occurs as a *pada* (and would therefore have to be taken as such, and not as a part of a word, *padāikadeṣa*); and if it be proposed to cite it with each value, as was done with *kiñčila* (in rule 26: see note to that rule), there remains the difficulty that, as a phonetic complex only, it would involve such cases as *paṣum paṣupate te adya* (iii. 1.4¹: W. omits *paṣum*)—where, namely, we have the same elements in combination, only without the *anusvāra*. With regard to *añṣa*, a somewhat similar statement appears to be made: namely, that if *añṣa* simply were quoted, it would be understood as a *pada* (being such in *añṣa-bhuvā*), and hence *añṣam* would

.....²² *tvayā*.....: ²⁴*bhuvē 'ti kim: añṣe 'ty etāvātā*²³ *grahane tathāvidhapadasadbhāvād añṣam*²⁵ *ity atra na*²¹ *syāt*:²⁴ *tenā*.....: ²⁶*apy akārādi* (i.52) *iti vacanād anañṣu*..... *ity apy*²⁷ *uddharaṇam*:²⁸ *vr̥ṣṇo*.....: *prāṇā*.....: ²⁹*añṣur*.....³⁰ *yam*.....: ³¹*añṣān*.....³¹ *añṣunā*.....: *yo*.....: *añṣāya*.....: *upāñṣu*.....: *tam*.....: ³²*añṣo*³³ *ity*³⁴ *etāvati*³⁵ *gr̥hāta itareshām aparigrahaḥ*³⁶ *syāt*³⁷ *tathāvidhapadasadbhāvāt: atho 'bhayaṁ gr̥hyate padam ekadeṣaḥ*³⁸ *ca kiñčilavat: tathā sati padāikadeṣe shu paṣum*..... *ityādishu pāpnyād anusvārah*³⁹: *tac cā 'nishi-*

not be included. The comment, however, puts this forward as a reason for including the *bhuvā* of *añgabhuwā*, which, according to the interpretation here offered, it would not be; and perhaps my comprehension of the argument is insufficient. I do not see any reason why, if the *pada*-text divides *añga-bhuvā*, the *bhuvā* should be given in the rule. Equally unexplainable to me is the special citation of *añgubhih*, which, being divided in *pada* into *añgu-bhih*, falls under *añgu*: we have also in the *Sanhitā* *añgubhyām* (i.4.2 and vi.4.5²), which is a case analogous with the other, and ought to be treated like it. Possibly we may infer from the unsuitable position of *añgubhih* in the rule, and from the place of its example as given in W. B., next after that containing *añgu-mat* (as if it were, like the latter, a case of *añgu*), that it has been interpolated, by an awkward and blundering hand; but the conjecture is a more daring one than I venture seriously to make.

The first *excursus* of the comment is in connection with the second citation, *añhah*. Since the *sanhitā*-form of this word, we are told, appears by the rule itself to be *añho*, the rule does not apply to *ahah*, which shows a different result of combination in *ahar devānām* (i.5.9²: G. M. read *aharahar*, which is not found in the *Sanhitā* before *devānām*), but only to a word the *visarjanīya* of which does not become *r*. This seems plausible enough; but what shall we say of the *ahah* which appears in *sanhitā* as *aho* in *ahobhyām*, *ahobhih*, and *ahorātre* (p. *ahah-rātre*)? Either the makers of the treatise overlooked these words, or they did not attribute to the form *añho* in the rule the significance which is here claimed for it.

The remaining passage is more obscure to me than any of the others. In G. M., it is both preceded and followed by the examples for *añhoḥ* and *añhomuk*; in W. B., these examples precede it, excepting the last word of the second, which comes after it. I imagine that its true place is between the two, and that its intent is to turn against the rule the argument just pleaded respecting *añhah*, pointing out that, as *añhoḥ* becomes *añhor* in the rule, it ought not to exhibit *anusvāra* except when occurring in that phonetic form: the objection being then evaded by the plea that the form is given merely as it happens to occur, and not with any

*tam*²². *ādir iti kim: sarveshu sthāneshu mā bhūd iti: yathā*²³
ñhasa ityādi.

¹ O. ins. *ādih*. ² G. M. *svarād-*. ³ G. M. *-gamañ*. ⁴ G. M. *bhujate*. ⁵ O. om.
⁶ O. om. ⁷ G. M. *atv-īya*. ⁸ MSS. ins. *añhomugbhyām*. ⁹ O. om. ¹⁰ W. *aya*.
¹¹ G. M. *ca*. ¹² W. B. *ekapre-*. ¹³ G. M. om. *eva*. ¹⁴ W. B. *-phaññā*. ¹⁵ W.
'anusvārah syāt: nodhyanyana syāt: tu vidhīr iti deikapālāḥ; B. *'anusvāra syāt: bodh-*
yatāḥ nanu vidhīr iti: deikapālāḥ. ¹⁶ G. M. *udbodhnam*. ¹⁷ G. M. *ity añhoḥ cād*
yā. ¹⁸ W. *añh*; B. *aty*. ¹⁹ G. M. *-at-ī* 'ca. ²⁰ O. *-dheh*; B. *dheh kutah*. ²¹ W.
kih; B. om. ²² B. *ity atrā 'pi*; G. M. *ityādi*; O. *ityādāu*. ²³ W. B. put next
before *apy akārādī*. ²⁴ O. om. ²⁵ G. M. *-vad*. ²⁶ W. B. *açam*. ²⁷ W. B. om.
²⁸ O. *anañgu ku simply*. ²⁹ W. om. ³⁰ G. M. put before *erśhao*..... ³¹ W. om.
³² O. om. ³³ W. *añca 'ty*; G. M. *añce 'ty*. ³⁴ B. *-valā*. ³⁵ B. *upaviṅgha*; G. M.
apī grahaṇām. ³⁶ G. M. ins. *kuthām*. ³⁷ G. M. *-deçam*. ³⁸ G. M. *-rāgamañ*.
³⁹ W. O. a.

intent of prescription. But I have too little confidence in the correctness of this conjecture to be led to attempt amending the text into giving it consistent expression.

अबग्रह उदात्तो ऽसेऽसायाऽसाभ्यामऽसाविति ॥३०॥

30. Also in *añse*, *añśāya*, *añśābhyām*, and *añśāu*, when accented on the first syllable.

The term *avagraha* is declared by the commentator to be equivalent here to *ādi* or *padādi*, 'beginning of the word.' This is, of course, wholly and entirely inadmissible, except as we are driven by the irresistible force of circumstances to give it that meaning or none. There has evidently been some blunder committed, but we can hardly venture to attempt its rectification. Not one of the words here cited occurs, or could occur, as *avagraha*, 'former member of a compound.' The restriction is made with reference to *añśāu* alone, in order to distinguish it from *asāv*. The examples are *dakṣhiṇe 'ñsa upa dadhāti* (v.3.1⁵: O omits *dadhāti*; W. has lost the whole), *ṣṭyañśāya* (vii.3.17: W. has lost *ṣṭy*), *añśābhyāñ svāhā* (vii.3.16²), and *uttare 'ñśāv eva prati dadhāti* (v.3.1⁵: O. reads *tishthati* for *dadhāti*, but doubtless by a copyist's error only); the counter-example is *asāv abravie citra-vihitā* (ii.5.2⁵: O. omits the last word); *añśābhyām* alone is found more than once in the text (namely, again at v.7.13).

नासावा नासावा ॥३१॥

31. But not in *asāv ā*.

There is a single passage where the pronoun *asāv*, in the vocative case, stands at the beginning of a clause, and is, accordingly, accented on the first syllable; hence the necessity of the present rule, establishing an exception under its predecessor. The passage is *brūyād āsāv ē 'hī 'ty evām evā* (ii.4.9³: O. alone has *eva*; G. M. omit also *evam*, and B. blunderingly reads instead of it *atra*).

The Prāṭiśākhya's rehearsal of the cases of interior *anuvāra* is,

30. *avagraha ādir ity arthah: yadi padādir udāttoḥ syāt tarhy añse¹ ity eteshu² syād anuvārāgamah. itīcabdah svarā-pavāci. dakṣhiṇe.....³ ṣṭy.....: añśā.....: uttare..... ādir udātta iti kim: asāv.....*

¹ B. *pari*. ⁽²⁾ W. *om*. ³ G. M. *-śāñ*.

31. *ādyudātte¹ saty apy² 'asāv ē 'ty³ asmin 'grahane na khalu⁴ syād anuvārāgamah. brūyād.....*

*iti tribhāṣhyaratne⁵ prāṭiśākhyavivarane
'shodāṣo⁶ 'dhyāyah.*

¹ W. *yady ud-*; B. *yady udāttaṭce*. ² B. O. *om*. ⁽³⁾ W. *asāv āi ty*; B. *asāv*; G. M. O. *asāv ity*. ⁽⁴⁾ O. *om*. ⁵ B. *priti-*. ⁶ G. M. O. *dvītiyopraṇe caturtho*.

so far as I have been able to discover, complete for the present *Tāttiriya-Saṃhitā*, with the exception of the two compounds (*śrī-śaṅśāda* and *svādushaṅśad*) noticed under rule 26. Whether its rules are so drawn as to involve no cases that require to be excluded, is a much more difficult question, and one which my examination of the text has not been close enough to enable me to determine; but I have noted no instances of inaccuracy, unless the possible confusion of *aṅḥaḥ* and *ahāḥ*, pointed out under rule 29, is to be so considered.

CHAPTER XVII.

CONTENTS: 1-4, opinions of various authorities, as to the degree of nasality in different nasal letters; 5, as to increase of quantity in connection with *anuvāra*; 6, as to increased effort required by certain accents; 7-8, as to other more general matters of utterance.

तीव्रतरमानुनासिक्यमनुस्वारोत्तमेधिति शैत्यावनः ॥ १ ॥

1. *Çaityāyana* says that the nasal quality is stronger in *anuvāra* and the nasal mutes.

We have here a chapter entirely composed of the cited opinions of certain specified authorities, and none of them of any definite value or importance in themselves, though interesting as affording us a glimpse of subjects to which the attention of the old Hindu phonetists was drawn, and to their hair-splitting and discordant speculations respecting them.

The commentator's exposition adds nothing to our comprehension of the rule. It quotes the rule at the end of the second chapter (ii.52) as to the cause of nasal quality, and tries (without good reason) to connect with it the present one. Examples of the stronger nasal utterance are given, as follows: *agnīr apushadāḥ*

1. 'anuvāraḥ co 'ttamāḥ² cā 'nusrōttamāḥ: tesu tīvrataram bhavaty ānunāsikyam iti çaityāyano nāma munir manyate³. tīvrād adhikam tīvrataram: anunāsikāt⁴ "nunāsikyam: nāsi-kāvivarapād ānunāsikyam (ii.52) ity asya vidheḥ prayatnadārdhyam⁵ upadiṣyate. ⁶ yathā: agnīr.....: 'tāns.....: martyāñ.....: yañ.....: 'vañcate.....: mañinā.....: cleśh⁷ iti kim: rukmam.....: tigmam.....: 'suḥl.....⁸

(1) O. om. (2) W. -maḥ. (3) W. -sika; B. -sikanān bhāvah. (4) W. O. -dirgham; B. -dōrbyam; G. M. prayadārtham. (5) O. ina. anuvārottamā anunāsikā ity etāny anunāsikasthānāni. anuvārottameshu tīvrataram ānunāsikyam bhavati çaityāyano nāma manyate. (6) G. M. O. om. (7) in O. only. (8) O. prāñ..... (9) O. anuvārottameshu. (10) O. sa.....: cleśhu cāi 'va tīvrataram.

(v.6.1²), *yam kāmam kāmāyate* (vii.1.1²; G. M. O. substitute *yam kāmāyeta*, i.6.10⁴ et al.), *vañcate parivañcate* (iv.5.3¹), and *maminā rūpāni 'ndrena* (vii.3.14); but O. introduces after the first *tāñs te dadhāmi* (iv.1.10³) and *martyāñ āvivega* (v.7.9¹), and substitutes for the last two *prāñ prā 'dravat* (v.7.10¹). Counter-examples, of the weaker utterance, are *rukman upa dadhāti* (v.2.7²; but W. substitutes, by an evident blunder, *kārmam upa dadhāti*, v.2.8⁵), *tigman āyudham* (iv.7.15⁴), and *suçlokāñs sumāñ-galāñs* (i.8.16²); O. giving instead of the last *sa imāñ lokam* (i.5.9⁴), and spoiling the whole illustration by adding, "in these likewise it is stronger." The first two counter-examples are evidently given for the *yama* which, by xxi.12, is to be inserted between the mute and nasal in each: the last is a case falling under xv.8, which prescribes nasalization of a protracted final *a*. The other nasal sounds are the *nāsikya* (xxi.14), and the nasal semivowels into which *m* and *n* are to be converted (v.26, 28) before *l*, *y*, and *v*: these last are instanced by the phrase quoted in O. alone.

The manuscript O. follows an independent course in the exposition of this rule, as of the rest composing the chapter.

समः सर्वत्रेति कौहलीपुत्रः ॥ २ ॥

2. Kāuhaliṣputra says that it is the same everywhere.

The comment interprets *samam*, 'same,' as signifying here *tivrataram*, which it had explained above as an absolute rather than a relative comparative—"very excessive," rather than 'more excessive.' That does not seem likely to be the real meaning. As examples, are cited, rather needlessly, *sañrarāñdh* (iv.6.1¹ et al.), *sañyattāñ* (i.5.1¹ et al.), *nyāññ agniç cetavyah* (v.5.3²; only O. has *cetavyah*), and *upahūtāñs ho* (ii.6.7²). O. gives an entirely different, though equivalent, exposition, and only the last two of these examples, with two others, namely *sarvāñ agniññr apsushadah* (v.6.1²) and *imāñ lokāñ* (ii.1.3¹).

The name of the authority quoted is given by G. M. as Kāuhaliyaputra, and by O. as Kohaliṣputra, in both the text and commentary.

अनुस्वारे ञिविति भारद्वाजः ॥ ३ ॥

3. Bhāradvāja says it is faint in *anusvāra*.

2. *sarvatrā 'nunāsikavarṇeshu' tivrataratvañ 'samam iti' kauhaliṣputro manyate. sañr-.....: sañy-.....: nyāññ-.....: upa-.....: ityādi.*

¹ W. B. -*sikyav*; G. M. -*sikyav* v. (7) W. *sarvatve 'ti*. ² G. M. (as also in the rule) -*ñyap*.

O. substitutes for the whole *anusvārottamādishu sarveshu samavācesheñ 'nunāsikyāñ nyād iti kohaliṣputr: ścāryo manyate sma: tivrataram ity arthah: nyāññ-.....: sarvāñ-.....: imāñ-.....: upa-.....*

The term *anu*, 'faint,' is explained by *sūkshmatamam* (or, in G. M. O., *sūkshmataram*), 'exceedingly gentle.' In other nasals than *anuscāra*, we are told, Bhāradvāja accepts Čaittyāyana's rule, that the nasal quality is extra-strong in the nasal mutes, and simply strong in the *yamas* etc. Most of the MSS. quote only *tanuvā jaya tvañ satā* (iv.6.6¹: B. has dropped out all but the beginning, *nanu*, and O. has lost *tanuvā ja* from the beginning); but O. adds counter-examples, *brahmanvanto devā āsan* (vi.4.10²), *rukman upa dadhāti* (v.2.7²), and *tat saṁyatatā saṁyatatam* (v.2.10⁶).

नकारस्य रेफोष्मयकारभावाद्युते च मलोपाद्योत्तर-
मुत्तरं तीव्रतरमिति स्थविरः कौण्डिन्यः ॥४॥

4. Old Kāuṇḍinya says that when *n* is converted into *r*, or into a spirant, or into *y* (with loss of the *y*), or when *m* is lost, it is stronger in each case successively.

The alterations of an original nasal mute are here rehearsed in the same order, and in the same terms, as in a previous rule (xv.1). The comment gives an example for each case: namely *triñr ekāda-gāñ iha* (iii.2.11³: G. M. have lost *iha*, along with all that follows, to the last example; O. substitutes *triñr uta dyān*, ii.1.11⁵), *ṣuk-lāñ ca kṛṣṇdāñ ca* (ii.3.1³: O. substitutes *ṛtāñ tanvate*, iv.3.11²), *mahāñ indrah* (i.4.20 et al.: O. substitutes *svavāñ indro asme*, i.7.13⁵), and *sañcitam* (iv.1.10² et al.: O. substitutes *cihav-yañ ṣasyam*, vii.5.5²). The first combination is styled *saṁyo-*

3. 'anu sūkshmatamam' ānunāsikyam anuvāre syād iti bhāradvājo manyate. yathā: tanuvā..... anuvārād anyatra čaittyāyanavidhiḥ: uttameshu tivrataratvam yamādishu tivrāmātram iti.

¹ G. M. *anusūkshmataram*. ² G. M. om.

O. substitutes for the whole *bhāradvājasya* "cāryasya mate 'anuvāre' 'nur bhavaty ānunāsikyam: sūkshmataram ity arthah: ya tvañ..... anuvāra itī kin: alo 'nyatra čaittyāyanavidhiḥ: brahm.....: ruk.....: tat.....

4. *nakārasya rephoshmayakārabhāvāc* ¹ *cakārākrṣṭayakāre* ² *lupte* ³ *sati malopāc co* ⁴ *utaram uttaram* ⁵ *ānunāsikyam* ⁶ *ānupūr-vyena tivrataram syād* ⁷ *iti sthavirah kāuṇḍinyo manyate. yathā:* ⁸ *'triñr.....* ⁹ *ity atra* ¹⁰ *'nunāsikyam saṁyogamātravat: ṣukl.....* ¹¹ *ity* ¹² *'atra saṁcīṣṭam* ¹³ *: mahāñ.....: ity atra tivrataram:* ¹⁴ *sañ.....: ity atra tivrataram:* ¹⁵ *ity ānupūrvyam vijñeyam:* ¹⁶ *'atō 'ny- atra* ¹⁷ *čaittyāyanavidhiḥ.*

¹ O. *rephadhāvāc śmabhāvāc yak*. ² O. *-ṣṭe ya*. ³ G. M. ins. *ca*. ⁴ G. M. om. (and read *utaram* for *utaram* in rule). ⁵ O. om. ⁶ O. *ānunāsikyam bhavati*. ⁷ G. M. om.; O. *smā*. ⁸ O. substitutes *triñr.....: ṛt.....: svā.....: ā viveṣa: viḥ.....: triñr.....: ity atra tivrata saṁyogamātram:* ⁹ *ṛt.....: ity atra saṁcīṣṭam:* ¹⁰ *svā.....: ityatra tivrataram:* ¹¹ *viḥ.....: ityatra tivrataram.* ¹² G. M. om. ¹³ W. *atra tu ṣṭ*; B. *atrānuṣṭ saṁcīṣṭ*. ¹⁴ W. B. G. M. *atra*.

gamātravat, 'simple conjunction;' the second, *saṃgṛhīṣṭa*, 'fused together;' the third and fourth, only *tieratara*, 'more excessive.' And it is added at the end (only O. making the statement intelligibly) that in other cases Čaityāyana's rule (xvii.1) applies.

व्यञ्जनकालश्च स्वरस्यात्राधिकः ॥ ५ ॥

5. And to the vowel is added, in this case, the time of a consonant.

The "and" (*ca*) in the rule is declared to continue the implication of Old Kāuṇḍinya's opinion: according to this authority, here, in the prescription of *anuvāra*, the time of a consonant, half a *mora* (i.37), is to be added to the vowel that is accompanied by *anuvāra*; an example is *yujāthān rāsabham yuam* (iv.1.2¹ et al.). And "in this case" (*atra*, literally 'here') is added in the rule because the prescription of increased quantity is not of force in the cases detailed in the sixteenth chapter, in nasal mutes, nor where *n* or *m* is converted into *l* (v.25,26,28).

O. states the same thing in other language, giving two additional examples, *çatrān anapavyayantaḥ* (iv.6.6³) and *añhomuce* (i.6.12³ et al.)—of which the latter, being one of those established in the sixteenth chapter (xvi.29), ought to be a counter-example—and remarking further that in the opinion of other teachers the *anuvāra* merely was added to the vowel. *Anuvāra*, namely, was declared by i.34 to have the quantity of a short vowel; and we should be grateful if the commentator had pointed out in what relation this rule really stands to that; if, indeed, there is any connection between them, and if this does not belong properly to a doctrine that regards the *anuvāra* as an affection of the vowel merely; causing the latter's prolongation, to be sure, but not adding an element with independent quantity to it. O. appends the further restriction that the vowel undergoing prolongation is to be a simple one (not a diphthong). And it mentions another interpretation, as put forward by some authorities: that *atra* signifies wherever *anuvāra* is prescribed: and that where there is *anuvāra*, there the quantity of the vowel is to be short in every case.

5. *ca kāra sthāvira kāuṇḍīyam* 'anvādicati: *atrā 'nūsvāravīdhāne sāmūṇṣikāsvarasya vyañjanakālo hrasvārdhakālo 'dhikoh syāt iti sthāviraḥ kāuṇḍīnyo manyate: yuñj-.... ityādi. atrāi 'va svarasye 'ti kim: śrādishā 'ttameshā 'ttamalabhāve' cāi' tad adhiakakālavidhānam' mā bhūḍ iti.*

¹ W. B. -rah kau-; G. M. -nyamatam. ² W. B. -mābhā. ³ B. nūi; G. M. vāi. ⁴ W. adhiakāl-; G. M. adhiakāl-.

O. substitutes for the whole *atrā 'nūsvāre vyañjanakālo hrasvārdhakālamātrah svarasyā 'dhiko bhavati svarakālot: çatr-....: añh-....: yuñj-....: caçabde sthāvira kāuṇḍīnyamatāsvādicati: itarācāryamate 'nūsvāra eva svarasyā 'dhika syāt: atrā 'ti kim: śrādishā 'ttameshā uttamalabhāve sāmūṇṣikāsvarasya cāi' tad adhiakālavidhāna mā bhūḍ tesu svarakālādhiko 'nūsvāra syāt: apara dhuh utre 'tyanūṇṣikāvidhāna ity arthah: anuvārabhāve 'pi vyañjanakālo hrasvakālo bhavati yadā 'nūsvāras tadā sarvatra hrasvakālo eva syāt.*

The Rík (xiii.13) and Vājasaneyi (iv.147-8) Prāṭiśākhya also concern themselves with the respective length of a vowel and of *anusvāra* as constituents of a syllable, but their rules stand in no definable relation to the one here given.

स्वारविक्रमयोर्दृढप्रयत्नतरः पौष्करसादेः ॥ ६ ॥

6. Pāuśkarasādi says the utterance of *svāra* and *vikrama* is attended with firmer effort.

Most of the manuscripts supply in the comment *prayoga*, 'use, application,' as the subject involved in this rule; O. supplies simply *varṇa*, 'alphabetic sound.' *Svāra*, we are told, means *svārīta*, 'circumflex;' O. signifying the same thing by pointing out that the *svāras* are enumerated in the twentieth chapter (xx.1-8). *Vikrama* is a particular kind of *anulāta*, 'grave;' or, O. says, is explained in the nineteenth chapter (xix.1.2). As examples are given *yò'sya svò 'gnís tám ápi* (v.7.9¹: G. M. O. omit the last two words) and *ásyè havéñ priyám* (iii.3.11¹), for the latter of which O. substitutes *çikyám abhy úpa dadhāti* (v.2.4²): we have here two kinds of *svāra* or *svārīta*, namely *abhinihata* (xx.4) and *nitya* (xx.2), and one or more cases of *vikrama* (the grave syllable standing directly between two that are either acute or circumflex) in each example. A counter-example is *gām vā vá tū tát pāry avadatām* (i.7.2²: only O. has the last two words), which contains (except in O.'s addition) neither *svāra* nor *vikrama*.

प्रयत्नविशेषात्सर्ववर्णानामिति शैत्यायनः ॥ ७ ॥

7. Çāityāyana says, of all the letters, according to their difference of effort.

The comment (except in O.) supplies the same subject as in the preceding rule, namely *prayoga*; and also continues the predicate of that rule, *dr̥ḍhaprayatnatarah*. The latter we can hardly approve, since to assert a specially firm effort of all alphabetic sounds without exception is little better than nonsense. Çāityāyana may rather be credited with meaning that each constituent of the alphabet has its own proper (*svacita*) degree of articulative effort—which is more true than edifying.

6. *svāre vikrame ca prayogaḥ pāuśkarasāder mate' dr̥ḍhaprayatnataro bhavati. svārah svarita ity arthah: vikramo nāmā 'nudāttaviṣeṣah. yathā: yo..... āsyè..... svāravikramayor iti kim: gām..... dr̥ḍhaḥ prayatno 'yasyā'sau' dr̥ḍhaprayatnah: atīçayena dr̥ḍhaprayatno dr̥ḍhaprayatnatarah.*

¹ B. -*tah*. ² G. M. om. ³ W. B. -*dha*; G. M. -*dha eva*. ⁴ G. M. om.

O. substitutes for the whole *svāra viṣadannudke gānyante: ekāttaviṣadannudke vikramāḥ svāreṣu vikrameṣu ca dr̥ḍhaprayatnataro vaṇo bhavati pāuśkarasādar mate çikyām ... yo..... svāravikramayor iti kim: gām.....*

As example, is cited the first phrase of the Sanhitā, *ishe tvo 'rje tvā* (i.1.1: only O. has the last two words).

The manuscripts of the commentary leave us quite in a quandary as to the value of these seven rules, W. B. calling them approved, but G. M. O. unapproved.

नातिव्यक्तं न चाव्यक्तमेवं वर्णानुद्भिद्येत् ।

पयःपूर्णमिवामत्रं कुरन्धीरो यथामति ॥

इत्यात्रेय आत्रेयः ॥ ८ ॥

8. Ātreya says, one must utter the sounds not over-distinctly and not indistinctly; taking, as it were, a vessel filled with drink, steady, according to the sense.

The commentator gives only a simple paraphrase of this verse, and casts no real light upon its meaning, even as regards the naïve and not very instructive comparison in the second line.

CHAPTER XVIII.

CONTENTS: 1-1, opinions of various authorities as to the mode of utterance of the auspicious syllable *om*.

7. *sarvavarṇānām prayogaḥ¹ svocitaprayatnaviçeshād² dr̥dha-prayatnatara³ bhavati⁴ 'ti çāityāyano manyate. yathā⁵: ishe.... ityādi.*

¹ *nāi 'tāni² sapta sūtrāni³ 'shtāni.*

¹ B. -ga. ² B. *svoc*; W. B. -*shā*; G. M. -*shāt*. ³ W. -*taḥ prayatnatamo*; B. -*taḥ prayatnatara*. ⁴ G. M. *om*. ⁽⁵⁾ W. B. *etāni*.

O. substitutes for the whole *çāityāyanasya⁶ 'cāryasya mate svaprayatnaviçeshātth sarvavarṇānām viçeshyād⁷ dr̥dhoprayatnataraḥ evaṁ varṇeṣu bhavati⁸: na svavavakramayor eve 'ti: yathā: ishe..... nāi 'tāni etc.*

8. *ativyaktam¹ atispashtam² avyaktam³ aspashtam⁴ ca⁵ yathā na bhavaty evaṁ varṇān udiṅgayed uccārayed⁶ 'ity arthaḥ⁷: payaḥ-pārṇam⁸ ivā⁹ 'matraṁ¹⁰ kshirapūritam¹¹ bhājanam¹² 'harann¹³ ivā¹⁴ yathāmati¹⁵ matim¹⁶ anatikramya¹⁷ 'dhīro¹⁸ 'dhyetā¹⁹ bhaved²⁰ ity ātreya manyate.*

*iti tribhāshyaratne prātiçākhyavicarane
saptadaśo¹¹ 'dhyāyah.*

¹ W. *nā 'tāni*. ² O. *om*. ⁽³⁾ G. M. *om*. ⁴ O. *om*. *iva*. ⁵ W. *kshiram apū*; B. -*iraparipū*; O. -*irapū*. ⁶ G. M. *amatram*. ⁽⁷⁾ O. *pāratniva*. ⁸ W. O. *in*. ⁽⁹⁾ W. O. *om*. *dhīro*; G. M. *adhyatā yothā dhīro*. ⁽¹⁰⁾ G. M. -*vet tathe*. ⁽¹¹⁾ G. M. O. *dvītiyapraçne pañcamo*.

ओकारं तु प्रणव एके ऽर्धतृतीयमात्रं ब्रुवते ॥१॥

1. As *pranava*, some utter *o* with two and a half *moras*.

In the text of this rule, T. reads *oṅkāram*, and B. *oṃkāram*; in the comment, at the beginning, W. B. have *oṃkāram*. Doubtless the unnasalized form is the true reading; that *oṅ* or *oṃ* should be uttered with more than the quantity of a long syllable would not be worth the trouble of specifying, in view of rules i.34 and xvii.5, which would require either three or two and a half *moras* for the combination. Whether we are to infer that this holy exclamation was not yet uttered with a nasal ending at the time when the *Prātiśākhya* was made, is a more doubtful question; the whole matter lies, at any rate, outside the proper province of a *Prātiśākhya*. By way of examples, the comment appears to intend to quote the first and last words of the *Sanhitā* and of the *Brāhmaṇa*: namely *oṃ ishe tvā* (i.1.1), *samudro bandhuh oṃ* (vii.5.25²? see below: B. omits the *oṃ*), *oṃ brahma saṃdhattam* (Tāitt. Brāh. i.1.1), and *yebhyaḥ cāi 'nat prāhuḥ oṃ* (B. omits the *oṃ*: the Calcutta edition of the *Tāittiriya-Brāhmaṇa* being incomplete, I can only presume that these are the concluding words of that treatise). The manuscripts G. M. O. put these extracts in a different order, giving the two conclusions first, and then the two beginnings; G. M. add *oṃ* at the end of each, while O. gives no *oṃ* at all. G. M. further append two more citations, *bhadraṃ karnebhiḥ : oṃ*, and *āi 'va tapati : oṃ*, of which the former is the beginning, and the latter, I presume, the end, of the *Tāittiriya-Āraṇyaka*. With regard to the phrase *samudro bandhuh*, it is to be observed that the *Sanhitā* as found in my manuscript (or rather, manuscripts, for mine contains the last leaf of another and entirely independent one, which has the same reading), and in those to which Prof. Weber has access, ends with *samudrah* simply; but another word like this is evidently wanting to complete the sense (the concluding sentence is *samudro cā aḥvāsyā yonih samudrah*), and is not less needed to make up the tale of words as enumerated in the ending, which counts "twelve" after *avahat*, while without *bandhuh* there are

1. *pranava*¹ *oṅkāram*² *'ardhatṛtīyamātram eke bṛuvate*³: *'ēka ācāryā ardhatṛtīyamātram āhur ity arthaḥ*. *'ardham*⁴ *tṛtīyam yayos te ardhatṛtīye: ardhatṛtīyamātre yasyā 'sāo ardhatṛtīyamātrah*. *yathā*⁵: *"oṃ ishe tvā: samudro bandhuh: oṃ: oṃ brahma saṃdhattam: yebhyaḥ cāi 'nat prāhuḥ: oṃ"*. *kālanirnaye 'py evaṃ*¹² *varṇitam*:

*svādhyāyārambhāḥśeṣasya*¹³ *pranavasya svarasya cā*¹⁴:

*adhyāyasyā*¹⁴ *"nirvākasyā 'nte syād ardhatṛtīyatā"*.

*tuṣabdaya*¹⁵ *prayojanam ucyate: saṃdhyaksharāṇām veda-pranavam*¹¹ *cā 'ntarā tathe 'ti kālanirnaye: saṃdhyaksharāṇām*

*"hrasvā na santi"*¹⁶ *"ti"*¹⁷ *pāṇinīye 'py oṅkāramātrasya*¹⁸ *dirghakālo*¹⁹

only eleven. This is a very strange fact, and calls for a wider examination of Tāittīriya manuscripts, to see if any of them have saved the lost final word.

Then is quoted a verse "from the Kālanirnaya," to the effect that "the quantity of two and a half *moras* belongs to the *pranava* and to a vowel forming the beginning or end (?) of a passage that one reads in the Veda, also at the end of a chapter or section." The Kālanirnaya quoted here and below must, of course, be a very different work from that of Mādhava bearing the same title (Weber's Catalogue of the Berlin Sanskrit MSS., No. 1166).

In explanation of the word *tu* in the rule, another half-verse, from which I extract no suitable meaning, is quoted from the Kālanirnaya, and the authority of Pāṇini is further appealed to to prove that among the diphthongs there is no short quantity: hence for simple *o* long quantity is determined: here, "however" (*tu*), when the diphthong stands in *pranava*, that quantity is negatived; and (quoting, apparently, another half-verse) for the *pranava*, as occurring in the Veda, is prescribed long quantity along with [the quantity of?] a *m*. That is to say, the *tu* intimates a denial of the ordinary quantity of the diphthong *o*. And the remark is finally added that a difference of quantity is to be recognized in the different *pranavas*.

उदात्तानुदात्तस्वरितानां कस्मिंश्चिदिति शैत्यायनः ॥२॥

2. Çaityāyana says it is to be uttered with either one of acute, grave, or circumflex.

The comment simply paraphrases the rule, adding nothing in its explanation—not even telling us in what relation it stands to rule 7, and whether Çaityāyana would let us give the word, in any given case of its use, whatever accent we chose, or would have us governed by reasons in our choice between the three accents.

*nirūpitah²²: iha tu²³ pranavasthatvaviṣeṣeṇā²⁴ 'sāu kālo nishidh-
yate: vedasthapranave²⁵ tu syāt²⁶ samakāradvaimātrate²⁷ 'ti. 27pranavaviṣeṣe kāvaviṣeṣaḥ²⁸ pratyetaṇyāḥ.*

¹ W. B. -re; G. M. -vena. ² W. B. oṃkā-. ⁽³⁾ O. -tiyamāva'e. ⁽⁴⁾ G. M. O. om. ⁵ B. ins. iti. ⁽⁶⁾ W. ardhahṛtiyamātraṃ bruvate: pranave okāram. ⁷ B. O. ardhā. ⁸ G. M. O. mātre. ⁹ G. M. -tiyas tam; O. tiyamās tam; sāvadhavimāt-nity arthah. ¹⁰ W. B. O. om. ⁽¹¹⁾ G. M. sam-...: oṃ: ye-...: oṃ: ish-...: oṃ: brah-...: oṃ: bhāḍ-...: oṃ: dī-...: oṃ: O. sam-...: ye-...: ish-...: brah-... ¹² B. ins. ca. ⁽¹³⁾ B. pranavasthātavya ¹⁴ B. adhyāyāc ca. ⁽¹⁵⁾ G. M. -kasya tv ante 'to 'rdhatr-; O. -tiye tā. ¹⁶ B. auc-; G. M. antaḥ. ¹⁷ G. M. -dān ca pr-; O. -dān c: prānavām. ⁽¹⁸⁾ O. -svo nā 'stī. ¹⁹ W. om. iti. ²⁰ O. okārasya. ²¹ W. G. M. -te. ²² G. M. -te. ²³ B. om. ²⁴ O. -shād; G. M. -shānād. ²⁵ W. B. O. -sya pr-. ⁽²⁶⁾ B. -kālo de-; G. M. -kāle de-; O. -kāre dvaimātrete. ⁽²⁷⁾ G. M. pranavasya viṣeṣaḥ.

2. udāttānūdaṭṭasvaritānām madhye kasmīṃś cīt svare prana-
vaḥ prayoktavya iti çaityāyano brūte. yathā: oṃ.

O. substitutes utte anudatte svarite vā eṣhā madhyatamena svareṇa prayoktavya syād i çaityāyanamah dārya manyate: os ca.

धृतप्रचयः कौण्डिन्यस्य ॥ ३ ॥

3. According to Kāuṇḍinya, it is a sustained *pracaya*.

I have ventured to translate the word *dhṛta* in *dhṛtapracaya* by 'sustained,' but without feeling sure that it might not have been better to follow the lead of the commentator, who treats *dhṛtapracaya* as equivalent to simple *pracaya*. He brings up, it is true, the objection that in xix.2 the use of the term *pracaya* itself is attributed to this same Kāuṇḍinya, and that hence it should have been used here; but replies "not so; by this pair of words, even, an appellation is given: thus, namely: on the principle that even where there is no difference of meaning there may be a difference of application, the teacher exhibits a nicety of application: other examples of the principle are the names [of the second Pāṇḍava] Bhīmasena and Bhīma, [of one of Īśa's wives] Bhāmā [G. M. say Satyā] and Satyabhāmā, *pidhāna* and *apidhāna*, *dīpa* and *pradīpa*." The *pracaya* is defined as the fourth accent; and O. adds that it is to be explained in the twenty-first chapter (namely, at xxi.10,11): it is there said to be of the same tone as *udātta*, 'acute;' so that, unless *dhṛta* is to be regarded as signifying a modification, one does not see in what respect Kāuṇḍinya's opinion differs from that of Vālmīki, given in rule 6 of this chapter.

मध्यमेन स वाक्प्रयोगः ॥ ३ ॥

4. That application of the voice is with middle tone.

The meaning of this precept is very obscure, and the commentator's exposition does not give the impression that he comprehended it. According to him, the *sa*, 'that,' points us back to the utterance as prescribed by Kāuṇḍinya in the preceding rule: in whatever pitch of voice the application is made, the *pranava* is to be used with medial effort, or with one that takes into account the

3. *kāuṇḍinyasya¹ mate pranavo dhṛtapracayo bhavati: caturthaḥ² svaro dhṛtapracaya iti kathyate. nanu pracayapārvaś ca kāuṇḍinyasya (xix.2) itivat pracaya ity etāvatai³ vā⁴ lam: kin⁵ dhṛtaḥ abdena. māi⁶ 'vam.'⁷ padadvayenā⁸ 'py anena nāmadheyam abhidhīyate': tathā hi: arthabhedābhāve⁹ 'pi prayogabhedo¹⁰ 'sti 'ti prayogacāturyam¹¹ ācāryaḥ prakatayati: yathā: bhīmaseno¹² bhīmaḥ: bhāmā¹³ satyabhāmā¹⁴: pidhānam apidhānam: dīpaḥ pradīpa ityādi.*

¹ W. -nya. ² B. G. M. -tha. ³ G. M. dhṛtaḥ abdena nāma: evam. ⁴ G. M. evā 'bh-
⁵ B. arthabhed-; G. M. ittham bhe-. ⁶ B. -gaprabh-. ⁷ W. -gānturacā-. ⁸ W. -ne; B.
-na. ⁹ G. M. om. ¹⁰ G. M. ins. satyā.

O. substitutes *dhṛtapracayo nāma turīyasvaraḥ sa evāi¹⁵ 'kavīdāse 'nuvāke vakshyate dhṛtapracaya iti nāmadheyam prayānam api vyapadiṣyate iti kāuṇḍinya deś-
ārya manyate dhṛtapracayaḥ pranavo bhavati yathā om iti: uddṛtapracayo (rutiya-
bhedaḥ tat svaravijñānuḥkṛtāḥ phalam anutīyate.*

combination of high and low tone. The relation of *vāk* in the compound is described as that of a locative case, and the word is paraphrased by *vācaḥ sthāne*, 'in position (i. e., I presume, 'quality' or 'temperament:': compare xxii.11, xxiii.4,5) of voice.'

स्वरितः प्रानिप्रान्नायणयोः ॥ ५ ॥

5. According to Plākshi and Plākshāyaṇa, it is circumflexed.

This rule is, along with its three predecessors, pronounced by the commentator unapproved.

उदात्तो वाल्मीकिः ॥ ६ ॥

6. According to Vālmīki, it is acute.

This is the only rule in the chapter, except the first, which the commentator allows to stand as approved. In his school, then, the vowel part of the sacred exclamation is to be two and a half *moras* long, and of acute tone. This agrees with the teaching of the Vāj. (ii.51) and Rik (xv.3) Prātiśākhya, save that these give (what is really equivalent to the same thing) three *moras* to the whole word *om*; and the Rik Pr. mentions other opinions both as to its quantity and its accent.

यथाप्रयोगं वा सर्वेषां यथाप्रयोगं वा सर्वेषाम् ॥ ७ ॥

7. All allow that it may also be according to the application.

The commentator first quotes an absurd opinion of Mābhisheya's, to the effect that *yathāprayogaḥ*, 'according to the application,' here means *udātta*, 'acute;' but then goes on to set forth, as given by Vararuci, what appears to be the real meaning of the rule: namely, that with whatever tone the passage to be read [i. e. its beginning] is used, that tone is to be given also to the introductory exclamation. Thus, before *ishē tvā* (i.1.1 et al.), which begins with

4. *prayujyata iti prayogaḥ: madhyameno 'ccanīcasamāhāravicakṣaṇena prayatnena pranavaḥ: yatra² kvacana vāca sthāne³ prayogo bhavati sa⁴ iti kaudīnyābhīmataḥ pūrvokto gṛhyate. vāci prayogo vākprayogaḥ.*

¹ W. -ed; G. M. -vaḥ prayoktavyaḥ. ² W. anya-. ³ W. B. -na. ⁴ B. om.
O. substitutes *ko 'yam pravaḥ nāma dvāprayogaḥ* [i. e. vākpr.] *kaudīnyamatam ādīya yatra kvacana sthāne diyate: tena madhyamena svareṇa prayoktavyaḥ.*

5. *plākshiplākshāyaṇayoḥ¹ pakshe² svarito bhavati. nāi 'tat sūtracatusṭayam iṣṭam.*

¹ O. ins. *ācāryayor.* ² O. mate; G. M. O. add *pranava.*

6. *vālmiker mate pranava udātto bhavati.¹*

¹ O. adds *yathā.*

grave, the *om* is to be grave; before *āpa undantu* (i.2.1¹: wanting in W. B.), acute; before *vyṛddham* (v.1.2¹: W. B. have instead, evidently as a corrupt reading only, *vyādhaḥ*, with which word no *anuvāka* in the *Sanhitā* begins), circumflex.

The rule is declared unapproved—rather hard treatment for one which professes to lay down a principle accepted by all authorities.

CHAPTER XIX.

CONTENTS: 1-2, occurrence of *vikrama*, between syllables of high tone; 3-5, of *kampa*, in a circumflex followed by a circumflex.

स्वरितयोर्मध्ये यत्र नीचः स्यादुदात्तयोर्वान्यतरतो
बोदात्तस्वरितयोः स विक्रमः ॥१॥

1. Where a syllable of low tone occurs between two circumflex syllables, or two acute, or two of which either one is acute and the other circumflex, that is *vikrama*.

The commentator paraphrases the rule as if *anyatarataḥ* meant 'between a preceding circumflex and a following acute,' and the following *udāttasvaritayoh* 'between a preceding acute and a fol-

7. *yathāprayogaçobdeno*¹ 'dātto 'bhidhīyate iti māhisheyapa-
kṣaḥ: *pranave*² *yathāprayogaṁ vā kuryād iti sarveśhām ṛshi-
nām matam. vararucipakṣas tu vakshyate: adhyeshyamānam*³
yathāprayogaṁ yathāvidhasvaram 'tathāvidhena vā' *svarena*
pranavaḥ prayoktavya iti sarveśhām matam iti. yathā: 'ishe
tve 'ty *anenā* 'dhyeshyamānenā' 'nudātena *pranavo* 'py *anudāt-
taḥ:* 'āpa undante ity *udāteno* 'dāttaḥ': *vyṛddham* itī' *sva-
ritena svaritaḥ.*

ne 'dasi *sūtram ishtaṁ.*

O. (corrected a little) substitutes *yathāvidhena svarena* 'dhyeshyamāno bhavati: *tathāvidhena svareṇā* 'va *pranavaḥ prayoktavyaḥ: esho vā sarveśhām ācāryānām
nādhāraṇapranavavidhīr bhavet: ishe tve* 'ty *etad adhyeshyamāneṇa udāttaḥ pra-
nava vaktavyaḥ: āpa.... ity udātaḥ: vyṛddham itī svaritaḥ: ācāryagraha-
ṇam teshām kīrtiyartham: pakṣaparigrahaṇajñānasadrṣṭaḥ parikalpanā: ne* 'dasi
sūtram ishtaṁ.

iti tribhāshyaratne prāticākhyavivarane
ashtādaço⁴ 'dhyāyah.

¹ W. -*gasaç*. ² G. M. -*cani*. ³ W. *adhyeprathamānam*. ⁴ G. M. -*vidha*. ⁵ W. B. om. ⁶ W. 'dhyayamānā; B. -*mānā*. ⁷ W. B. om. ⁸ W. B. om. ⁹ G. M. O. *dvitīyapraçne shashtho*.

lowing circumflex.' He adds examples of a *vikrama* syllable in each of the four defined positions: namely *yò 'sya svò 'gnis tám ápi* (v.7.9¹: G. M. O. omit the last two words), *vòḍhavé* (i.6.2¹ et al.), *dhāveanā gā'h* (iv.6.6¹), and *tāsya kvā svārgó lokāh* (ii.6.5³: O. omits the last word, G. M. the last two). In the third example, the circumflex by which the *vikrama* syllable is preceded is the enclitic; this shows us (what we should have inferred without it) that, as regards the application of the present precept, no distinction is made between the independent and the enclitic circumflex. As an example of the use of the term, and showing the necessity of its definition here, is quoted rule xvii.6, where we are told that Pāṇshkarasādi asserts the utterance of *svāra* ('circumflex') and *vikrama* with a firmer effort. The word occurs elsewhere only at xxiii.20 and xxiv.5, where we have no assurance that it signifies the same thing as here. It is found, among the other Prāticākhyas, in that to the Rig-Veda only, and has there no such meaning.

The *vikrama* is marked by the usual sign of low tone, the horizontal stroke beneath. The following rule, as we shall see, extends its definition so as to include nearly all the syllables so marked.

The construction of *sa* in the rule, as agreeing in gender with *vikramah*, though referring to *nicam* (*akshoram*), was alluded to above, under v.2.

प्रचयपूर्वश्च कौण्डिन्यस्य ॥ २ ॥

2. As also, according to Kāuṇḍinya, when a *pracaya* precedes.

The *pracaya* (see xxi.10,11) is the series of unaccented syllables following a circumflex (enclitic or independent) in connected discourse, and uttered, save the one next preceding another following circumflex or an acute, in the tone of acute. This last one of the

1. *'yatra ' svaritayor' madhya ' udāttayor vā ' nyatarato ve 'ti svaritodāttayor vā 'ty arthah: ' udāttasvaritayor vā madhye nicam yad aksharam sa vikramo' bhavati. svaritayor' madhye yathā: yo 'udāttayor yathā': vòḍhave. svaritodāttayor yathā: dhāve..... udāttasvaritayor yathā: tāsya..... vikramasamjñāyāḥ prayojanam: svāravikramayor dṛḍha-prayatnatara (xvii.6) iti.*

(¹) O. *yad dvayor.* (²) B. G. M. ins. *sthale.* (³) G. M. ins. *vā.* (⁴) G. M. om. (⁵) G. M. om. *vā.* (⁶) G. M. ins. *iti vā.* (⁷) O. om.; G. M. put after *madhye.* (⁸) G. M. *-masam-jāo.* (⁹) O. *tayor.* (¹⁰) O. om.

2. *cakāro' vikrama iti jñāpayati: 'kāuṇḍinyasya mata udātta-parah scaritaparo vā pracayapūrvāḥ ca vikramo vijñeyah. udāt-taparo yathā: pary.....' scaritaparo yathā: upar..... pra-cayah pūrvo yasmād 'asau pracayapūrvah.'*

(¹) G. M. O. *caçabdo.* (²) W. om. (³) G. M. *sa tathoktaḥ.*

series, which retains its grave tone, is here declared to be, on Kāuṇḍinya's authority, likewise entitled to the appellation *vikrama*. This makes the term apply to all syllables in the *samhitā* that are marked by the horizontal stroke below, excepting those which, after a pause, precede the first accented syllable. The commentator cites two examples: *pāry avadatām yā yajñe dīyāte* (i.7.2²: lost in W.; only O. has the last two words) and *upāriṣṭhālakṣhmā yājyā* (ii.6.2³⁻⁴ et al.), in the first of which the *pracaya* is followed by an acute, in the second by a circumflex.

It is to be observed that the *vikrama* appears, so far as this treatise is concerned, to be a mere name; no peculiarity of tone is claimed to belong to it: the other treatises offer nothing analogous.

As nothing is said of the non-approval of the rule, we may regard it as accepted in the school represented by the commentator.

द्वियम एके द्वियमपरे ता अणुमात्राः ॥३॥

3. According to some, in a circumflex syllable that is followed by a circumflex, quarter-moras are so.

I have rendered this rule according to my own persuasion of its true meaning, and not at all in conformity with the interpretation of the commentator, who says "*yama* [W. alone says *deviyama*] is a synonym of *svarita*; where there are two such *yamas*, without intervention of anything, that is a *deviyama*; what is followed by such a *deviyama*, that is *deviyamapara*: in the former, and also in the latter, where there is a third *yama* [so in G. M., which is the best reading: the others perhaps mean *triyama*], whatever circumflexed materials there are, all those are depressed at the end to the extent of a quarter-mora: so some think. An example of a *deviyama* is *tē 'nyō 'nyāsmāi* (ii.2.11⁵: but B. G. M. have instead *tē 'nyō 'nyām*, vi.1.5¹); of a *deviyamapara*, *sō 'pō 'bhy āmriyata* (vi.1.1⁷; 4.2³). Whence do we derive the implication 'at the end?' from the precept 'and likewise, at the end of a word are *kampas*, quarter-moras depressed at the end.' And the implication of

3. *yamaçabdaḥ¹ svaritaparyāyāḥ: dvāu yamāu yatra deḥ nāirantaryeṇa² vartete sa deviyamaḥ: tasmin: deviyamaḥ paro yasmād asāu deviyamaparaḥ: tasmiñ ca deviyame³ sati yāḥ⁴ svaritaprakṛtayas tāḥ sarvā antato 'munātrā⁵ nihatā⁶ bhavanti⁷ 'ty eke manyante. deviyamo yathā: te.....: 'deviyamaparo yathā: so..... antata⁸ iti katham pratīyate: padānte ca⁹ tathā¹⁰ kampō antata nihatānukā¹¹ iti vacanād iti brēmāḥ: nihataṁ¹² tu svaritayor madhye yatra nīcam (xix.1) ity¹³ etatsāmnidhyāḥ la-bhyate. śikṣhā cāi¹⁴ 'vañ vakshyati¹⁵:*

nityo 'bhinihataç¹⁶ cāi¹⁷ 'va kṣhāiprah praçliṣṭa eva ca: ete svārāḥ¹⁸ prakampante yatro 'ccasvaritodayā¹⁹ iti²⁰: çeshasyo 'dāttatā vā syāt svārātā²¹ vā vyavasthaye²² 'ti:

depression comes by vicinage from rule 1, above, where a syllable of low tone between two that are circumflexed is spoken of. This seems to me entirely inadmissible. In *yama* as a synonym of *svārīta*, and meaning 'circumflex,' I cannot in the least believe; and the designation of a case of three successive circumflexes as *dviyamapara* would be excessively awkward, even without the omission of the *ca*, 'and,' which would be needed to connect it, in that signification, with *dviyama*. On the other hand, *dviyama*, 'of double pitch,' is an entirely natural and acceptable synonym for *svārīta*, 'circumflex,' the essential characteristic of which is that it combines the high and the low tone within the limits of the same syllable; and "a circumflex followed by a circumflex" includes every possible case. The limitation "at the end" is properly enough left to be understood from the nature of the case; but that the predicate "depressed," the most important part of the precept, should remain to be inferred by vicinage only, and from the subject, not the predicate, of the two preceding rules, is not to be tolerated. And I have no doubt that the *tāh* in the rule is the predicate, and represents *vikrama*, its gender and number being adapted to those of *anumātrāh* by the grammatical figure *anyonyānvaya*, to which the commentator (see under ii.7, v.2) has several times appealed in other like cases. There remains, as the only difficulty, the plural number of both words: we should certainly expect rather *sā 'numātrā*; but even if we have to let this pass unexplained, it is vastly more easy to get along with than the difficulties which beset the other interpretation. One hardly dares presume to suggest that the present reading is the result of an alteration, made after the meaning given in the comment was ascribed to the rule.

The commentator goes on to quote a verse from the *Çikshā*, to the effect that the four kinds of independent circumflex (see xx.1, 2,4,5) suffer *kampa* when they precede either an acute or a circumflex. This verse is (save that it gives the *Tāittirīya* instead of the *Rik* names to the accents) the same with that which is interpolated in the *Rik Pr.*, at the end of the third chapter (iii.19). He adds further, in another half-verse, doubtless from the same authority, that "of the remainder, there may either be the quality of acute or of circumflex, respectively;" and explains this "respectively" as

vyavasthāpabdenā 'nena²⁸ dvividhaḥ kampa uktaḥ: saṁhitāyām svaritakampa²¹ itaravedabhāga²² udāttakampa²³ iti ye²⁴ kampāḥ prasiddhā²⁵ teshe²⁶ etal lakṣaṇaṁ na tu kampavidhāyakam: anyathā yo.... ityādāu kampāḥ prasajyeta.

ne 'daṁ sūtram iṣṭam.

¹ W. *dviy-*. ² W. *norah-*; O. *norantatory-*. ³ G. M. *trītiyayame*. ⁴ W. *yani*; M. *ed.* ⁵ O. *-tra*. ⁶ W. *niyatā*; B. *abhiḥatā*; G. M. *bhīhīti*. ⁷ O. *om.* ⁸ O. *anta*. ⁹ O. *ka*. ¹⁰ W. B. *yathā*. ¹¹ O. *hi hat-*. ¹² G. *nīhīt-*. ¹³ O. *-tatvam*. ¹⁴ B. *om.* ¹⁵ O. *-te*. ¹⁶ B. *-hitaḥ*. ¹⁷ G. M. *svār-*. ¹⁸ W. *trav-*; M. *cedcaav-*; O. *caa-yav-*; G. M. *-ydd*; O. *-ye*. ¹⁹ O. *om.* ²⁰ B. *-tor*; G. M. *svārīta*. ²¹ W. *āte*; O. *om.* *anena*. ²² W. *-taḥ k-*; B. *-ta uktaḥ k-*. ²³ G. M. *-re ve-*. ²⁴ W. *-ttaḥ k-*. ²⁵ W. B. O. *om.* ²⁶ G. M. *om.* ²⁷ B. O. *ins.* *eva*.

implying that there are two kinds of *kampa*: in the Sanhitā, that before a circumflex; in other parts of the Veda, that before an acute; and concludes the exposition with pointing out (if I understand him) that this is a definition applying to those cases of *kampa* which are otherwise established; but that it is not a precept requiring *kampa*, since this would otherwise have to appear in such passages as *yô 'pā'm pūshpañ vēda* (only G. M. have *veda*: the passage is not to be found in the Sanhitā, and possibly is intended to be quoted from one of those "other parts of the Veda," referred to above). Finally, he remarks that the rule is unapproved.

The term *kampa* is not found anywhere in the text of our Prātiçākhyā, or of that of the Rīg-Veda, although the commentary to the latter (under iii.3.4), like our own, employs it to signify the peculiar modification undergone by the circumflex, when immediately followed by a high tone. The Atharva-Prātiçākhyā (iii.65) gives to the same modification the kindred name of *vikampita*. It is signified, in the Rik and Atharvan texts (as is fully explained and illustrated in the note to Ath. Pr. iii.65), by appending to the vowel of the circumflex syllable a figure, either 1 or 3, and applying to the figure the signs of both circumflex and grave accentuation. The theory of this mode of designation is obscure, and no account of it is given in any Prātiçākhyā, nor, so far as I am aware, in any other Hindu authority that has yet come to light. We should imagine the figure to be a mere *point d'appui* for an added sign of grave tone, but that there appears in a part of the Vedic texts an accompanying prolongation of the *vikampita* vowel (if the vowel be short), of which the figure, therefore, appears to be the sign: of this prolongation the Prātiçākhyās give no hint.

This accent wears a quite peculiar aspect in the Tāittiriya text, as compared with those to which reference has been made. In the first place, being limited to the case of a circumflex before a circumflex, it is relatively of rare occurrence, there being fewer examples of it in the whole Tāittiriya-Sanhitā than in the first book alone of the Atharvan (it occurs in the former, if I have overlooked nothing, only at ii.1.6^b; 2.11^b; v.4.3^c; vi.1.1⁷, 5¹, 11^{2,3}; 2.2^{1,2}; 3.2⁵, 4²; 4.2³, 9², 10¹; 6.8¹; and in the ending to v.2.1). Secondly, it is always intimated by an appended figure 1, with simply the mark of *anudatta* tone, or of *vikrama*, written beneath, while the circumflex vowel retains the mark of circumflex accent*—and this is clearly the method most easily defensible on theoretic grounds:

* That is to say, this is uniformly the case in my manuscript, which, for example, writes the commentator's quoted instances as follows:

ते॒ न्या॒न्यस्मि॑

सा॒ पा॒ भ्य॒म्रिय॑त

and the MSS. of the comment all add the figure 1, although, as everywhere else, they omit the accent signs. In the two cases that occur in the part of the Calcutta edition thus far printed, it seems to be by mere unintelligent blundering that the above method is departed from, a 3 being added in the one (ii.1.6^a), without any sign of *vikrama* beneath it, and no designation being attempted in the other (ii.2.11^a).

the figure represents the quantity that is added to the syllable to make room for the *vikrama* tone at the end, and it gets, therefore, the *vikrama* sign. Thirdly, in the only two passages (vi.3.4²; 6.8⁴) in which the vowel of the circumflexed syllable is short, it is made long.

What the commentator means by declaring the rule of no force, it is not easy to say. It can hardly be that his school acknowledged no *kampa* at all; and we should have expected him rather to interpret into his text the usage which he and his fellow-*gākhināḥ* accepted as proper—as he has done in so many other cases. There appears to be no discordance between the teachings of the *Prāṭicākhya* in this chapter and the practice in the known *Tāittirīya* text (but see the note on the next rule); the former, to be sure, do not fully explain the latter; but this is the case also with the other *Vedas*.

The denial of *kampa* in a circumflex syllable before an acute constitutes the most important and conspicuous peculiarity in the *Tāittirīya* system of accentuation as compared with that of the *Rik* and *Atharvan*, and also puts the former at a disadvantage in respect to clearness. Its effect is to deprive us of any constant means of distinguishing whether the syllable following a circumflex is an acute, or a grave with *pracaya* tone (xxi.10); and whether that distinction shall be shown at all depends upon mere accident. For example, *sò 'smā't* and *sò 'smāt* would be accented before a pause precisely alike; and so with any number of acutes or graves following a circumflex before a pause: e. g. *sò 'smād abhavat* and *sò 'smā'd yó vā'i tát.** And even if, instead of a pause, other syllables follow, there must be at least two grave syllables in succession to bring out the true condition of things: we see that the syllable after the circumflex is acute in *hy ēśhā prthi-vyā'h*, but not in *hy étād devā'h*, and the *saṁhitā* does not tell us whether in *sò 'smād etarhi* the *asmāt* is accented or toneless.† And so often does this ambiguity arise, that in the first chapter of the third book there are not less than twenty cases of *pracayas*, all whose syllables except the last admit of being understood as true acutes.‡ Other possible cases of ambiguity, of less frequency and importance, I pass without notice.

This same peculiarity belongs also to the existing *Tāittirīya-Brāhmaṇa* and *Āraṇyaka*, so that the commentator's allusion to "other parts of the *Veda*" as differing from the *Sanhitā* in respect to *kampa* is of doubtful meaning.

* Thus, सौ ऽस्मादभवत् । and सौ ऽस्मान्यो वै तत् ।

† Thus, क्षेत्रं पृथिव्याः and क्षेत्रदेवाः and सौ ऽस्मादेतर्हि.

‡ Thus, सौ ऽकामयत प्रजाः may be either *sò 'kāmayata prajā'h* or

sò 'kā'māyātā prajā'h.

तस्यामेव प्रकृतौ ॥३॥

4. In that very material.

The commentator's interpretation of this rule is just as violent and unsatisfactory as is that which he gave of its predecessor, and with which he forces it into strange connection. He says, "in a *dviyama* passage there is depression to the extent of a quarter-mora only in that—namely, the former—circumflex material; but, in a passage where a *dviyama* follows, there is depression to the extent of a quarter-mora of the two former materials; but they do not all share in the quarter-mora effect: that is what the *eva* means. And Kāuhaleya says thus: 'of two, the former is *anumātrika*; of three, the two former are *anumātrika*; beyond that, the natural condition holds.'"

I think we can have no hesitation whatever as to rejecting this: if the treatise had been intending to say what is here claimed, it would have said it in a very different manner. What is really meant, may be much more doubtful; but I imagine that we are directed to find our quarter-mora of *vikrama* in the very substance of the circumflex syllable itself; that is to say, not in any protraction of it; and so, that that treatment of the case which is signified by the insertion of a figure after the circumflex vowel is rejected. This, if established, would make the doctrine of the authorities (*eke*, rule 3) here reported in fact discordant with the practice followed in the recorded text.

न पूर्वशास्त्रे न पूर्वशास्त्रे ॥५॥

5. Not in the former teaching.

A rule of very obscure import, and respecting which the commentator has only his guesses to give us. He ventures two: first, that *pūrvacāstra* signifies the rule respecting *vikrama*, and that in it this affection of the quarter-mora finds no place; second, that *pūrvacāstra* means the first rule of the chapter (which amounts, so far, to the same thing with the other), and that the name of

4. *dviyamasthale pūrvasyām 'eva tasyām' svaritaprakṛtāu anumātrayā' pi' nihatatvam' bhavati: dviyamapare tu' sthale pūrvayor eva prakṛtyor' anumātrayā' nihatatvam' bhavati: na tu' tāh sarsā anukāryabhāja¹⁰ ity evakāro bodhayati. evam eva kāuhaleya¹¹ āha: deayoh pārvo¹² 'numātrikas¹³ trishu¹⁴ pūrvāu¹⁵ anumātrikāu¹⁶ uttarah¹⁷ prakṛtye 'ti.*

(1) W. *aparasyām*. (2) B. *-trayo*; G. M. *anumātram a*. (3) O. *om*. (4) B. *-hit*. (5) G. M. *tal*. (6) B. *-tyāyo*. (7) B. *anumātrayor*; G. M. *anumātrayā*. (8) B. *-hit*. (9) W. O. *nu*. (10) G. M. *anuk*; O. *anumātram bhajate*. (11) W. *-liya*. (12) W. *-rea*; B. O. *-raah*. (13) W. B. O. *anu*; M. O. *-trakas*. (14) W. *ins. ca*. (15) O. *pārvo vā*; G. M. *pārvo yathā upariśit*; etc. (end of comment to rule 2, above). (16) W. *-kā*; M. *-trakā*; O. *-trako py*. (17) W. *-ratah*.

vikrama, there given, does not apply here in the rule for *kampa*, since, by xvii.6, *vikrama* is uttered with a firmer effort of the organs, while that is not the case with *kampa*. There is nothing in either of these proposals to commend it to our acceptance. If we were ourselves to guess, we should perhaps say that the reference was to rule 4 only, which teaches *kampa* without any protraction, and that this was confessed to be a doctrine not before authoritatively taught. But we should not presume to put the conjecture forward with any confidence.

CHAPTER XX.

CONTENTS: 1-8, names of the different kinds of circumflex, independent and enclitic; 9-12, different degrees of force of their utterance.

स्वर्णोकारयोर्वकारभावे नैप्र उदात्तयोः ॥ १ ॥

1. When *i*, *ī*, and *u* are converted into *y* or *v*, the accent is *kshāipra*, if they were acute.

The conversion of *i*, *ī*, and *u* into *y* or *v* is by rule x.15; *ā* does not fall under such a rule on account of its being always *pragraha* (iv.5). Rule x.16 prescribes the conditions under which a circumflex accent is the result of such a conversion; and the addition of *udāttayoh* to the present rule is wholly unnecessary—a case to exercise the ingenuity of the commentator in defending the treatise from the charge of *pāunaruktya*: but either it escapes his notice, or he declines to touch it, as beyond his powers. Of course, if it be necessary to explain here that the altered vowel is acute, it needs to be added that the following vowel is grave.

5. 'pūrvaçāstram nāma vikramavidhīḥ': *tasminn etad anukāryam na bhavati. evam vā sūtrārthaḥ: pūrvaçāstre*¹ 'dhyāya-prathamāsūtre yā vikramasamjñō 'ktā 'sā kampavidhāv atra' na bhavati: *vikramasya dr̥ḍhaprayatnatvāt*² *kampasya tadabhāvāt* iti.³

iti tribhāshyaratne prātiśākhyavivarane
*ekonaviṃśo*⁴ 'dhyāyah.

(1) W. -*strāṇām api kram-*; B. -*stre 'pi yo vikr-*; O. -*dhiva*. (2) O. -*roasūtre*. (3) W. -*dhāu yatra*; G. M. *sā 'tra pracayavidhāu*; O. *sā kampavidhāyakatvaḥ*. (4) G. M. -*tuatara syāt*. (5) G. M. add *deḍe arthāu*. (6) G. M. O. *deṣṭiyapraçne saptaṃ*.

1. *udāttayor ivarnokārayor yathopadeçam*¹ *yavakārabhāve sati yah svarito vihitaḥ sa kshāipra iti samjñāyate*². *yathā*³: *vy-----: kṛdhī----- udāttayor*⁴ *iti kim: vas-----: an v-----*.

¹ W. -*çāir*; O. -*çe*. ² G. M. -*jñā jāyate*. ³ G. M. om. ⁴ W. -*ita*.

The examples are *vy évā'i 'nena* (v.3.11³) and *krāhī' sv āsmān* (iv.7.15⁷); counter-examples, where the altered vowel was not acute, are *vāsvy asi* (i.2.5¹ et al.) and *ānv enam mātā'*, which is not, I believe, to be found in the *Sanhitā*; the nearest thing to it is *ānv enām viprāh* (iv.6.8³); *ānu tvā mātā'* occurs several times (i.3.10¹ et al.).

All the *Prātiçākhyas* agree in calling this particular kind of circumflex by the name *kshāipra* (see note to Ath. Pr. iii.58).

सयकारवकारं वृद्धं यत्र स्वर्यते स्थिते पदे अनु-
दात्तपूर्वे ऽपूर्वे वा नित्य इत्येव ज्ञानीयात् ॥२॥

2. But where a syllable containing a *y* or *v* is circumflexed in a fixed word, being preceded by a grave syllable, or not preceded by anything, that is to be known as *nitya*.

This definition of the original circumflex accent, which belongs to the word in which it occurs, and does not merely arise as a consequence of the combination of words into phrases (although ultimately of the same nature with the *kshāipra*, just described), is a long and awkward one, but fairly attains its purpose: only we do not see why the reading is not *anudāttapūrvam apūrvam vā*, qualifying *aksharam* formally, as it does logically. A syllable that has the circumflex in *pada*-text (to which *sthite pade* is explained as equivalent), otherwise than enclitically after an acute, is an original (*nitya*, 'constant, invariable') circumflex. The other *Prātiçākhyas* (see note to Ath. Pr. iii.57) call it *jātya*, 'natural.'

The commentator defines *aksharam*, 'syllable,' in the rule as meaning *svarah*, 'vowel;' and, in fact, the use of *aksharam* here is somewhat at variance with the general custom of the treatise, which elsewhere talks of the vowel, not the syllable, as having tone (compare i.43, xiv.29). He inserts *sarvatra*, 'everywhere,' in his paraphrase, and then explains it, as if it were a part of the rule, to signify that the accent holds in *samhitā*, *pada*, and *ajāta* text. His examples are *vāyavyām* (i.8.7¹ et al.), *kanyē 'va tunnā'* (iii.1.11³: O. omits *tunnā*), *tāto bīvēh* (ii.1.8²), *nyāñcam cinuyāt* (v.5.3²: W. B. add, after a pause, as if a new example, *anyañcam* [B.

2. *sayakāram vā savakāram vā 'ksharam' svāra ity arthaḥ: sthite pade padakāla ity arthaḥ: yatra sthale svaryate: anudāttapūrvē 'pūrvē' vā pūrvābhāce 'satī': nitya eve 'ti sarvatra jānīyāt: sarvatre 'ti' samhitāpadojātāve ity arthaḥ. yathā: vāy-----: kanyē-----: tāto-----: nyāñ-----: 'kvā-----: kvā-----: itī jātyāyām. tuḡabdo nityādāv uccodayaviśaye' no 'dāttasvaritapara (xiv.31) itī nishedham nicārayati. nam' nityaḥ ka-tham etannishedhaviśayaḥ': udāttāt paro 'nudātta' (xiv.29) itilakṣaṇāsambhavāt'. atro 'cyate: varṇavibhāgavelāyām' udāttapūrvatvam' asti: samāhāraḥ svarita (i.40) ity ucca-*

reads -cām], but no such word is to be found in the Sanhitā, and it is probably only a blundering repetition of *nyañcam*), and *kvā jāgati ca* (vii.1.4³); and, from the *jatā*-text, *kvā 'syā 'sya kvā 1 kvā 'sya* (v.7.4²: B. has lost a part; it involves a case of *kampa*, with resulting prolongation, and use of the sign 1: see xix.3). Counter-examples are given in O. only: namely, of a circumflex not found in *pada*-text, *vy ēvā'i 'nena* (v.3.11²: the MS. has *vevyāi*), *drvānnah sarpīh* (iv.1.9²; p. *drū-annah*); of one which has an acute before it, *mātyāñ devēga* (v.7.9¹) and *sārvāñ agnīn* (v.6.1²). We have also one of the common attempts to give a profound significance to the word *tu*, 'but,' in the rule; and, as usual, it is abortive, involving difficulties which the commentator only pretends to get rid of. He says the *tu* signifies that, so far as the *nitya* circumflex etc. (i. e. and the other varieties of the independent circumflex) are concerned, the exception laid down in rule xiv.31—namely, that the circumflex character is not retained before a following acute or circumflex—has no force. But it is objected, with entire reason, that rule xiv.31 has nothing to do with the *nitya* at all, but only with the enclitic accent prescribed in rule xiv.29. His reply is, that in the condition of complete separation of sounds, there is, after all, a grave element preceded by an acute, as required in rule xiv.29, the combination of the two, by i.40, giving the circumflex character. Whether this implies his recognition of the fact that the semivowel in every *nitya* syllable really represents an acute vowel, pronounced as such in an earlier stage of the language—*kvā* being equivalent to *kūa*, and *kanyā* to *kanā*—admits of question. He expounds *anudāttapūrve* as a descriptive instead of a possessive compound, and *apūrve* as a substantive of the same character, as if the construction were 'there being a preceding grave, or there being no preceding accent'; it is doubtless better to supply in idea *tasmim akshare*, and to render 'when that syllable is' etc. The remaining bit of exposition is much corrupted in its readings, and the drift of it is not clear to me. O. brings it in very differently from the rest, and makes it involve an additional example, *yājyā'i 'cā'i 'nam* (ii.3.5²; p. *yājyā : ā : evā : enam*).

pūrvatvāt¹⁸ svaritasye 'ti nishedhaviśayātcam. anudāttag cā 'sau pūrvaç cā 'nudāttapūrvoh¹⁹ : tasmin²⁰ : 'pūrvābhāco 'pūrvah²¹ : tasmin²². 'cūnye tu sarvatrapūrvateāt²³ pūrvataviṣeṣaṇadevayasyā²⁴ 'nyathā²⁵ vāiyarthiyāt²⁶ : tasmāt tatra²⁷ nityasvaritatvam²⁸ eva na²⁹ saññāntaram iti vijñeyam.

¹ W. B. om.; G. M. add *yatra svaryate*. ² O. ins. *vā*. ³ B. om. ⁴ G. M. ins. *vā*. ⁵ G. om. ⁶ O. pī. ⁷ W. B. ins. *anyañcam*. ⁸ G. M. O. -darkav; O. -shayo. ⁹ G. M. na tu. ¹⁰ O. nish-. ¹¹ G. M. ins. *svaritam*. ¹² O. laksh-. ¹³ all MSS. have the lingual l. ¹⁴ W. -ream. ¹⁵ W. B. *ucyate pū-*. ¹⁶ W. ins. *tasmāt*. ¹⁷ G. M. om. ¹⁸ O. na *cūnye* ity arthah; *sthile pada iti kim*: *vy..... drv.....*: *anudāttapūrvā iti kim*: *mar-t..... sar.....* *kicid evam ūcuh*: *yājy..... ity ddi*: *prāthamanīka-karoty evakīroh*: *pūrvāsamucaye anudāttapūrvatvāt*; G. M. *cūnyapūrvasapūrvatvāt*; W. *sarvatrā*; B. *bhūnye* etc. ¹⁹ W. *pūrvaviṣeṣadev*; B. *pūrvataviṣeṣanad*; O. *pūrvaviṣe*. ²⁰ O. *stathā*. ²¹ W. -thyam; G. M. -thyam *syāt*. ²² W. *am*; B. *tat*; O. *tra*. ²³ W. O. *nityatvam*; B. *svaritatvam nityatvam*. ²⁴ B. *ca*.

अपि चेन्नानापदस्यमुदात्तमथ चेत्साङ्हितेन स्वर्यते स प्रातिहृतः ॥ ३ ॥

3. If, moreover, there is an acute standing in another word, then, if there be a circumflex resulting from a rule of combination, it is *prātihata*.

The phraseology of this rule is very peculiar indeed, and its peculiarity hard to account for. The Rik and Atharva Prātiçākhyas distinguish only two kinds of enclitic circumflex: the *pādvṛtta*, in which a hiatus intervenes between the acute and its successor, and the *tāirovyañjana*, in which the two are separated by consonants. According to the explanation, now, of our commentator, the present treatise sets off from the latter, as a separate class, a circumflexed syllable at the beginning of a word, following an acute at the end of the preceding word. He gives us four examples (of which, however, W. B. omit the first two, and O. the last two): *mā te asyām* (i.6.12⁵), *yās tvā hṛdā kīrinā* (i.4.46¹: only O. has *kīrinā*), *ishē tvā* (i.1.1 et al.), and *tām te duççākshāḥ* (iii.2.10²): the second word in each has the *prātihata* circumflex. As counter-examples, we have *yān nṛdācam* (v.5.3²: W. gives instead *yān nācam* [ii.3.10¹ et al.], but it does not illustrate the point arrived at, and so is doubtless a corruption of the other), to show that the following circumflex must be a result of a rule of combination, and *tāyā devātayā* (iv.2.9² et al.: O. substitutes *tasmād varupam*, which is corrupt; I have overlooked it in searching out the references, and do not know how, if it in fact represents a real citation, it ought to be amended), to show that the acute must stand in another word.

In working out this meaning for the rule, the commentator declares *api*, 'moreover,' to have the office merely of bringing down from the preceding rule the quality of going before (*pārvatva*); *atha*, 'then,' according to him, either cuts off the continued implication of *nitya* (that is to say, means nothing at all), or else gives the value of a heading to "the being preceded by an acute standing in another word"—which is wholly to be rejected; in the first place because unnecessary (*tasmāt* in the next rule having just that purpose), and in the second place because the word could at any rate make a heading only of what followed it in the rule, not of what went before.

3. *apīçabdaḥ 'pārvatvamātrākarshakaḥ': athaçabdo nityasam-
jñāvyaçchedakaḥ: nānāpadaçthodāttapārvatvādhikārako³ vā:
nānāpadaçtham aksharam udāttapārvatam⁴ cet parato nīcam sām-
hitena vidhinā svaryate cet sa prātihato⁵ 'tra' veditavyaḥ. 'yathā:
mā-----: yas-----⁶ 'ishe-----: tam-----⁷ sāmhitene 'ti kim:
'yan----- nānāpadaçtham iti kim: tayā-----'*

⁽¹⁾ W. *pāreç* simply. ⁽²⁾ G. M. om. -*tra*-; O. om. -*atr*-. ⁽³⁾ O. -*kāro*. ⁽⁴⁾ G. M. om.
⁽⁵⁾ W. B. om.; G. M. om. *yathā*. ⁽⁶⁾ O. om. ⁽⁷⁾ O. *tasmādevarupam*.

If this be indeed the original intent of the rule, it would seem that, to the apprehension of the Hindu phonetists, there was difference enough between the enclitic circumflex which *te* in *tām te* assumes in *samhitā*, having been grave in *pada*-text, and that which the *shāh* of *duççākshāh* has in *samhitā* as well as in *pada*, to furnish ground for a difference of classification and nomenclature.* But there are various obstacles in the way of our accepting the interpretation as satisfactory. In the first place, why ought not the same distinction to apply where the acute and circumflex are separated by a hiatus, as well as by consonants? or why, when a circumflex after an acute in the same word is called *tāirovyañjana*, alike whether a hiatus or consonants intervene, should a circumflex after an acute in another word have a different name according as it is preceded by a consonant or not? In the second place, why should the rule be thrust in here, wholly out of connection with the others respecting the enclitic circumflex, and with such a frightful sacrifice of that economy of expression which the *sātrakāra* proverbially rates so highly? for, following rule 7, a simple *nānāpadasthāt tu prātihatah* would have done the whole business, and much more unequivocally. Not one of the other treatises mixes together thus the enclitic and independent *svarita*s, when they come to be defined and named. Nor, again, does any other authority found a separate species of accent upon the basis here laid down. I have been inclined, therefore, to conjecture that the rule ought to be rendered 'when there is besides (*api*) a [preceding] acute in another word, then, provided a circumflex arises as the result of a rule of combination, it is *prātihata*:' understanding an independent *svarita* (except a *nitya*) to be intended, whenever that *svarita* was preceded by an acute, and so held a position which would make it an enclitic *svarita* as well; and the reason for thus calling attention to it being that, as written, it is not distinguished from a mere enclitic accent.† But there are too many difficulties connected with this interpretation also to allow of its being accepted as at all satisfactory.

The Vājasaneyi-Prātiśākhya (i.118) gives a special name, *tāirovirāma*, to the enclitic circumflex which falls in the *pada*-text upon the first syllable of the second member of a compound, under

* And this difference, it should be noted, applies in the same manner where division is made between the two parts of a compound word; for the extant Tāittirīya *pada*-text, in marked contrast with those of the other Vedās, regards the *avagraha* pause as suspending, like the *avaseśa*, all accentual influence, and writes *çukrā-vati*, for example, in the same fashion as it writes *çukrām* : *astī*—that is to say,

शुक्रञ्वती । instead of शुक्रञ्वती, as the rest would read.

† For example, *ghṛtā'ir vy udyate* (iii.1.11*) and *anaçānā'h svistīm* (iii.1.92*) are written precisely as if they were *ghṛtā'ir vy udyate* and *anaçānā'h svistīm*; namely,

घृतैर्व्युद्यते and आनशानाः स्विष्टिम् : this is an ambiguity which

is common to all the Vedic texts.

the influence of an acute on the final of the first member, and which is therefore 'separated by an intervening pause' from the tone which calls it forth. Thus, the *va* of *çukrá-vati* (as written the second time in the first marginal note on p. 369) has a *tāirovirāma svarita*, being marked by the ordinary *svārīta*-sign. Now the *vati*, as well as the *çukra*, in this word, is to the apprehension of the present treatise (i.48) a *pada*; and hence its syllable *va* appears to fulfil all the conditions laid down in rule 2, just above, as determining a *jātya*: it is circumflexed in the *pada*-text; it is *apūrva*, or preceded by no other accent in the same *pada*; and it is *savakāra*, or contains a *v*. Here, now, as it appears to me, we have the best explanation of the value, and at the same time of the position, and also, at least in part, of the phraseology, of the rule under discussion. This accent needs definition, though enclitic, immediately after the *nitya*, lest it be confounded with the latter: "even if all the conditions of the previous rule are fulfilled, if there is likewise an acute [preceding the syllable] in another word, and the accent is one which is produced by a rule of combination, this accent is not *nitya*, but *prātihata*."

The most conspicuous difficulty in the way of accepting this interpretation is the fact, already referred to, that in the extant *pada*-text of the Tāittiriya-Saṁhitā there is no such circumflex as is here assumed; the *va* of *çukrá-vati*, and all other syllables in like position, being grave, and marked as such. But the difficulty is more apparent than real, since we have no right to assume that this *pada*-text is precisely the same with that held by the school from which the Prātiçākhyā, or this particular rule, emanated: they may have accented their *īgyas*, or separable words, after the same fashion which prevails in the *pada*-texts of the other Vedas. Of more account is the awkwardness of the whole expression, and especially the use of *nānāpadaṣṭham* instead of *avagrahaṣṭham*, which would be the proper term to use in this treatise (compare i.49) in the sense here indicated. But, if not completely acceptable, the interpretation has more for it and less against it, in my opinion, than either of those given above.

Professor Roth, in his early digest of the teachings of the Prātiçākhyas respecting accent (introduction to the Nirukta, p. lvii. etc.), identified the *prātihata* accent with the *tāirovirāma*, but only in consequence of a misunderstanding of the character of the latter, which he supposed (ibid., p. lxx.) to designate an enclitic circumflex separated by consonants from its occasioning acute in a preceding word, thus giving it the same meaning which is attributed by our commentator to the *prātihata* in the present rule. And Weber (under Vāj. Pr. i.118), while defining the *tāirovirāma* correctly, repeats the same identification; I do not know whether as taking it incautiously from Roth, or as having arrived by conjecture at an independent interpretation of our present rule. He does not allude to any difficulties as connected with the latter, nor state his identification to rest upon a different basis from that of Roth.

तस्मादकारलोपे अभिनिहृतः ॥ ३ ॥

4. After such a one, in case of the loss of an *a*, it is *abhinīhata*.

The word *tasmāt* the comment explains as bringing down *nānāpadastham udāttam* from the preceding rule: 'after an acute occurring in another word.' But the specification (like that of *udāttayoh* in rule 1) is wholly unnecessary: rule xii.9 prescribes the circumflex and defines its conditions: here we need only to have given us the name by which it is to be called.

O. has an independent exposition, but of equivalent meaning.

The examples are *sō 'bravīt* (ii.1.2¹ et al.) and *tē 'bruvan* (ii.5.1² et al.); and a counter-example, where, as the eliding diphthong is not acute, no circumflex results, is *bhrā'jo 'si devānām* (ii.4.3²).

All the other treatises (see note to Ath. Pr. iii.55) give to this circumflex the name *abhinīhita*, of which our own term has the aspect of being an artificial variation.

उभावे प्रक्षिप्तः ॥ ५ ॥

5. Where an *ū* results, it is *praṅṣhita*.

Rule x.17 prescribes the circumflex to which the name of *praṅṣhita* is here assigned; and the examples given are to be found there also, being all the instances save one which the Sanhitā affords. They read in this place *sūnnīyam iva* (vi.2.4¹), *sūdgātā* (vii.1.8¹), *māsū 'tishthan* (vii.5.2²: G. M. omit *mā*), and *dikshā 'podādhātī* (v.5.5⁴: G. M. O. omit).

The same name (or, in the Ath. Pr., *praṅṣhita*) is given by the other treatises to the circumflex which results from the fusion of two short *i*'s, the first acute and the other circumflex (see note to Ath. Pr. iii.56).

पदविवृत्यां पादवृत्तः ॥ ६ ॥

6. Where there is a hiatus between two words, it is *pādavṛtta*.

Here there is abrupt change, without notice, from the independent to the enclitic circumflex. The examples given are *tā' asmāt sr̥ṣṭā'h* (ii.1.2¹: B. omits *sr̥ṣṭā'h*), *sā idhānā'h* (iv.4.4⁵), and *yā*

4. '*tasmān nānāpadasthodāttāt parabhūtānūdāttākārasya*' *lope sati ya'h svaritah so 'bhinihato veditavyah*'. *yathā: so.....: te tasmād iti kim: bhrā'jo.....*

(1) O. substitutes *tasmāt sūhīlena na svaryamānārādhe te: sadakāle nsvarita ity arthah: akāraloṣṭe ya svara ādicyat so 'bhinihato nāma svarito bhavati*. (2) W. B. -dāttasya; G. M. *parabhūtād anudāttasya 'kārasya*.

5. *ūbhāve yatra svaryate sa praṅṣhito veditavyah. sūn.....: sūd.....: māsū.....: 'dikshū.....'*

(1) G. M. O. om.

upasādaḥ (vi.2.4¹); while, as counter-example, to show that the hiatus must be between two *padas*, not two parts of the same *pada*, we have *prāṅgam ukthām* (iv.4.2¹: this implies, of course, that the *pada*-text does not treat the word as a separable one).

The Rik Pr. (iii.9,10) calls this accent *vāivṛtta*, and there is nothing in its definition or in that of the Vāj. Prāt. (i.119) which should limit the accent to the case of a hiatus between two *padas*, or deprive the *u* of such a word as *prāṅga* of its right to rank as a *pādaivṛtta*. See the note to the next rule.

उदात्तपूर्वस्तीरोव्यञ्जनः ॥ ७ ॥

7. Where an acute precedes, it is *tāirovyañjana*.

The form of this rule, again, is almost unaccountably peculiar. The term *tāirovyañjana* means 'with consonant-intervention,' and all the other treatises (see note to Ath. Pr. iii.62) define the accent in accordance with this, as being one in which the circumflex is separated by intervening consonants from the occasioning acute. Here, to be sure, such a definition would hardly answer, as there is a single word in the *Sanhitā*, *prāṅgam*, in which a vowel is regarded as having *tāirovyañjana*, although there is no consonant between it and the acute. But why specify *udāttapūrva*, 'preceded by an acute,' in this rule, when it was just as necessary in rule 6? The commentator says that, as the implication has been made all along, its repetition here is for the purpose of signifying that the acute is now to be understood to be in the same word with the circumflex. That may satisfy him, but is not calculated to content us. If *nānāpadastham udāttam* was implied in rule 6 from above, then *padavivṛtṭyām* should have been simply *vivṛtṭyām*. Things would be made much better by putting rule 6 after rule 7: then we should be able to give *udāttapūrva* in rule 7 a meaning, as recalling to mind the actual cause of these two accents; and rule 6 would stand as an exception to the other and more general statement, pointing out a class of cases in which, though depending on a preceding acute, another name was applied to the accent.

The commentator's examples are *yuñjānty asya* (vii.4.20), *vāsavy*

6. *padayor vivṛtṭih padavivṛtṭih¹: tasyām yaḥ svaryate sa pādavṛtto veditavyaḥ.² yathā³: tā-----: sa-----: ya----- vivṛtṭir vyaktir⁴ ity arthaḥ. padayor iti kim: pra-----.*

¹ W. B. O. om. ² B. *bhaviṭi*. ³ in O. only. ⁴ B. *vyāptatirīkṭa*.

7. *udāttapūrvādhikāre sati punar atra tatkathanād¹ ekopadaśhodāttaviśeṣo² 'vagamyate': tasmād ekopadaśhodāttapūrvo yaḥ svaritaḥ sa³ tāirovyañjano veditavyaḥ. yathā⁴: yuñj-----: vas-----: sa-----: tad-----: pra-----: tam-----.*

¹ G. M. *kath-*; O. *tu k-*. ² G. M. *-sthityavi-*; O. *-sthatavi-*. ³ O. *gam-*. ⁴ O. *asdu*. ⁵ in O. only.

asi (i.2.5² et al.), *sá indro manyata* (vii.1.5³: G. M. omit *sa*), *tád āgvo bhavat* (v.3.12¹), *prāugam* (iv.4.2¹), and *tām tvāśtā* "dhat-ta (i.5.1²: G. M. omit the last word). It is very odd—but, I presume, merely accidental—that in every one of these cases (except *prāugam*) the vowel which finally shows the circumflex is not of the same word with the acute, but belongs to another word which has been combined with its predecessor, and, after the combination, gets the circumflex by the general rules xiv.29,30 (for the commentator has expressly denied under rule x.12 that the initial grave *a* of *asya*, for example, receives the circumflex in virtue of its combination with the enclitic circumflex *ti* of *yuñjānti*). I do not see why, in the first two cases, at any rate, the circumflex is not *prātihata*, according to the commentator's explanation of the meaning of that term; and should even incline to conjecture that these are the examples selected and current for the present rule before the erroneous interpretation of rule 3 was established.

No one of the other Prāṭicākhyas limits *tāirovyañjana* to an enclitic circumflex following its acute in the same word (see note to Ath. Pr. iii.62); it is quite an oversight, therefore, that the St. Petersburg lexicon gives the term only this restricted meaning (perpetuating Roth's original error, referred to above, in the note to rule 3).

इति स्वारनामधेयानि ॥ ८ ॥

8. These are the names of the circumflex accents.

The commentator simply gives examples for each accent, in part new, in part the same with those furnished under the rules defining each: namely, for the *kshāipra* (omitted in G. M.), *abhy āsthāt* (iv.2.8¹) and *ādhvaryó 'veh* (vi.4.3⁴: this is a blunder, there being no *kshāipra* in the phrase; B. O. read instead *adhvaryāh* [vi.2.9⁴ et al.], which does not mend the matter); for the *nitya*, *vāyavyām* (i.8.7¹ et al.) and *kvā 'sya* (v.7.4²: G. M. have *kva* simply); for the *prātihata*, *sá te lokāh* (v.7.26: G. M. omit *lokāh*) and *yāt tvā kruddhāh* (i.5.4²: G. M. omit *kruddhoh*); for the *abhinihata*, *sò 'bravit* (ii.1.2¹ et al.); for the *praçlishta*, *sūdyātā* (vii.1.8¹); for the *pādavṛtta*, *tā enam* (ii.3.11⁴: W. reads, blunderingly, *tām nemim* [ii.6.11¹], and B. substitutes *sá idhānāh*, iv.4.4⁵); and for the *tāirovyañjana*, *māma nāma* (i.5.10¹).

नैप्रनित्ययोर्द्वितरः ॥ ९ ॥

8. *ity etāni sapta svaritanāmadheyāny' ākhyātāni*². *yathā*:
'abhy..... *adhv*..... *iti kshāiprah*³. *vāy*..... *kvā*..... *iti*
nityah. *sa*..... *yāt*..... *iti prātihatah*. *so*..... *ity abhinihatah*.
sūd..... *iti praçlishtah*. *ta*..... *iti pādavṛttah*. *mama*..... *iti*
tāirovyañjanah.

¹ W. -māny; B. -yāni svaritanām. ² O. vydkh. ³ G. M. om.

9. In the *kshâipra* and *nitya*, the effort is firmer.

The commentator makes very short work of the remaining rules of the chapter, and we can afford to do the same, as they teach us nothing of value.

अभिनिहते च ॥ १० ॥

10. As also in the *abhinihata*.

The commentator says that *ca* in this rule is used in the sense of secondary adjunction (*anvācaya*), and so signifies that the effort of utterance in the *abhinihata* is *dr̥dha*, 'firm,' merely—a less degree than the *dr̥dhatarā*, 'firmer,' or 'quite firm,' of the preceding rule. The same may be also inferred, he adds, from the fact that the *abhinihata* is made the subject of a separate rule, instead of being included in rule 9, with the other two.

प्रश्लिष्टप्रातिहृतयोर्मृदुतरः ॥ ११ ॥

11. In the *praśliṣṭa* and *prātihata*, it is gentler.

Nothing is to be inferred from its association here as to the real character of the *prātihata*. This rule and its successor were referred to under I.46, but for no intelligibly useful purpose.

तैरोव्यञ्जनपादवृत्तयोरल्पतरौ ऽल्पतरः ॥ १२ ॥

12. In the *tairovyañjana* and *pādavṛtta*, it is feebler.

9. *kshâipre nitye ca prayatno¹ dr̥dhatarāḥ kāryaḥ².*

¹ W. -*tna*; B. -*tni*; O. *yatno*. ² W. B. om.

10. *anvācaye vartamānaḥ cakāro dr̥dhamātram bodhayati: abhinihate¹ ca² prayatno³ dr̥dhaḥ⁴ syāt: na tu dr̥dhatarāḥ: iti prthaksūtrārāmbhād apī⁵ pratiyate.*

¹ B. -*hite* (as also in the rule). ² O. om. ³ G. M. insert *mṛdutarāḥ*, and rule 12.

⁴ O. -*dhatarāḥ*. ⁵ W. *abhā*; B. om.

11. *praśliṣṭe prātihate ca prayatno mṛdutarāḥ kāryaḥ.*

12. *tairovyañjane pādavṛtte 'ca prayatno 'lpatarāḥ syāt', 'yady apy' alpamṛdudr̥dhabhāvas 'tatro 'ktas tathā 'pi¹ dipavad venupatravad iti śikshānurodhāt² komalaḥṣiraskatvaṁ³ sarvatra vijñeyam⁴.*

iti tribhāshyaratne prātiśākyavivarāṇe
cin̄ṣo⁵ 'dhyāyaḥ.

(¹) O. *ca 'lpatarāḥ karāṇam bhovati*. (²) W. om. ³ G. M. O. om. ⁴ G. M. ins. *tatra*. ⁵ M. 'pi¹ti. ⁶ B. *kshikshānurodhoktān*. ⁷ B. *alpaśik-*; G. M. *kāicalyaḥṣirasto-*. ⁸ O. *jñeyam: yathā: yuvā kavī*. ⁹ G. M. O. *dvitīyapragne aṣṭamo*.

Alpatara, 'feeble,' is doubtless meant to signify a still less degree of force of utterance than *mṛdutarā*, 'gentler.'

To the commentator, his *Çikshā* appears to be a higher authority than the *Prāticākhya*, at least in this part; and he adds that, although the qualifications 'feeble, gentle, firm' are here attributed to the accents in question, yet, in accordance with what the *Çikshā* says, "like a candle, like a rush-leaf" (? unintelligible without the context), it is to be understood that there is softheadedness (?) in them all alike. And O. adds an example, *yūvā kavīḥ* (i.3.14¹).

CHAPTER XXI.

CONTENTS: 1-9, division of consonants in syllabication; 10-11, *pracaya* accent; 12-13, *y-mas* or nasal counterparts; 14, *nāsika*; 15-16, *svarabhakti*.

व्यञ्जनं स्वराङ्गम् ॥ १ ॥

1. The consonant is adjunct of a vowel.

This brief principle calls forth a long discussion. Reference is first made (except in G. M.) to rule xxiv.5, as, by its requirement of a comprehension of *aṅga*, 'adjunct' (literally 'limb, member'), creating a necessity for the present precept (and for those that are to follow). Objection is then at once taken to the principle: if, in such cases as *kāpa* and *yāpa* (and G. M. add yet other words as illustrations), it is the consonant that indicates the difference of meaning, ought not the vowel, rather, to be considered as adjunct

1. ' *vyañjanam svarāṅgam bhavati: śvāso nādo 'ṅgam eva ca* (xxiv.5) *iti vijñeyatvena² vidhānād ayam ārambhaḥ. nanu³ kāpo yāpa⁴ ityādāu vyañjanam eva 'rthaviśeshabodhakam⁵ iti svarō vyañjanāṅgam kiṁ na⁶ syāt. ucyate: vyañjanam kevalam avasthātum na śaknoti: kiṁ tu sāpeksham⁷: svaras tu nirapekshah⁸: sāpekshanirapekshayor nirapeksham eva viśiṣṭam ācakshate prekshācantah⁹: viśiṣṭapratyaṅgatvam¹⁰ aviśiṣṭasyāi¹¹ 'va. kiṁ ca: svaravāṇiṣṭyabodhakam anyad api vidyate¹²: durbalasya yathā rāshṭram harate¹³ balavān nṛpaḥ: durbalam vyañjanam tadvad dharate¹⁴ balavān svarah¹⁵.
¹²kiṁ ca: çikshāvyaḍkhyāne
 yaḥ svayam rājate tam tu svaram āha patañjaliḥ
 uparisthāyinā tena vyaṅgam vyañjanam ucyate.¹⁶
 svaras tu¹⁷ brāhmaṇa jñeyā ityādi.*

udāttaḥ cā 'nudāttaḥ ca¹⁸ svaritaḥ ca svaras trayah¹⁹:

¹⁹hrasvo dīrghah pluta itī²⁰ kālato²¹ niyamā²² aci²³

'ti²⁴

of the consonant? The answer given is, that a consonant is incapable of standing alone, and so is dependent, while a vowel is independent; and that, as between a dependent and an independent, the enlightened regard the independent as superior; and it belongs to the inferior to be adjunct to the superior. Moreover, there is found also another proof of the superiority of the vowel, in the verse "as a mighty monarch takes possession of the realm of a weak one, so the mighty vowel takes possession of the weak consonant." The beginning of another verse is added: "the vowels are to be known as belonging to *brahman*." But between this part of a verse and the whole verse that precedes, G. M. insert another, which is asserted to come from "the exposition of the *Çikshâ*," and which gives a highly imaginative derivation for *svara*, 'vowel,' and *vyañjana*, 'consonant': "Patanjali styled that a vowel which *shines by itself* [*sva-ra* from *sva-yam râ-jate*]: the consonant is so called as being imperfect [*vyañjana* from *vyañga*, literally 'limbless'] without [? the expression needs mending, to bring out a desirable sense] the other following it." Then all start together upon a new argument for the superiority of the vowel with yet another verse, which is actually found in the known *pāṇiniya Çikshâ* (verse 23; see Weber's *Indische Studien*, iv.353): "acute, grave, and circumflex, the three accents, and short, long, and protracted, these, in regard to quantity, are the necessary characteristics of the vowels;" which shows that acute tone and so on are attributes of vowels only, and of consonants in virtue of their being adjuncts of vowels.

svarāṇām eva 'dattādāyo dharmāḥ:²⁴ *vyāñjanānām tu²⁵ tadā-gatāyā²⁷*. *vyāñjanam ardhamaṭram²⁸*: *svaraḥ ca mātrākālah*: *tayoḥ saṁdhir²⁹ adhyardhamātraḥ³⁰*: *ity evaṁ dīrghakālah pra-saktah*: *tatpratishedhārtham vyañjanam svarāṅgam ity uktam*: *svarasamśṛṣṭasya³¹ vyañjanasya svarakāla eva kālo drutavṛttāu³²* *na tu³³ svarasyāi 'va³⁴ saratre³⁵ 'ty arthah*. *drutavṛttāv iti kim³⁶*: *hrasvārdhakālam vyañjanam (i.37) iti³⁷ vyartham syād iti brūmah*. *yathā³⁸ kshirodakasamparke³⁹ kshirasyaī 'vo 'palabdhir no 'dakasya tothā svaravyāñjanasamparke⁴⁰ svarasyāi⁴¹* *'vo 'palabdhir⁴² vācīṣṭyam⁴³*.

¹ O. ins. *svarasyā 'ngam svarāṅgam*. ² G. M. *svara*. ³ G. M. *na*. ⁴ G. M. *-pas* *sūpak* *kālah* *sūlak* *būlak*: *phāla*. ⁵ O. *-sha* *iti bo*. ⁶ O. om. ⁷ W. B. *-kshā*: O. *sākaheyaṁ*. ⁸ O. *-kshahāh*. ⁹ G. M. *-shṭam* *svaram* *prat*: O. *-shṭam* *prat*. ¹⁰ G. M. *-ya* *vyāñjanasyāi*. ¹¹ G. M. *astī*. ^{12,13} G. M. *hareta*. ¹⁴ G. M. *-ra* *iti*. ¹⁵ in G. M. only. ¹⁶ G. M. *ca*. ¹⁷ B. om. ¹⁸ G. M. put before *svards*. ¹⁹ G. M. O. *hrasvārdhāplāṭāḥ* *cāi 'va*. ²⁰ G. M. *-lakō*. ²¹ G. M. *-yatā*: O. *-yatōs*. ²² W. *-grāy*: G. M. *api*: O. *tate*. ²³ G. M. ins. *vacand*. ²⁴ G. M. ins. *na tu*. ²⁵ O. *jānam*. ²⁶ W. *tu dān*: G. M. om. ²⁷ O. *tadharmatāyā*. ²⁸ G. M. *-trokaṁ*. ²⁹ O. *saṁ*. ³⁰ B. G. M. O. *ardham*: G. *-trika*: M. *-traka*. ³¹ W. *-rasamashtī*. ³² W. *dūt*: B. *dūt*: O. *drutavṛttāu*. ³³ W. *svārah* *sparsasyāi 'va*: O. om. ³⁴ B. *-vasye*. ³⁵ B. om.: W. *dūt*: O. *drut*. ³⁶ G. M. om. ³⁷ G. M. *-rkūh*: O. *kshirāṇḍake-sampā*. ³⁸ G. M. *-rkūh*. ³⁹ W. *sparsasyāi*. ⁴⁰ W. O. *-bhir*: B. *-bdhāir*. ⁴¹ B. *vācīṣṭyam*: G. M. *-shyam*.

Next we pass to the consideration of another reason why the principle stated in the rule needed to be laid down. The consonant (by i.37) has half a *mora* of quantity; and a vowel has [for example] a *mora*: their combination, then, would seem to have a *mora* and a half, and so would be liable to be understood as of long quantity: this untoward conclusion is avoided by the present rule, which implies that in fluent utterance the quantity of the vowel belongs in all cases to the combination of consonant and vowel, and not to the vowel alone. The specification "in fluent utterance" (literally, 'in running action') is made in order to save the significance of rule i.37.

Finally, the superiority of the vowel is once more inferred from the fact that, when it is combined with a consonant, it alone is perceptible; just as, when milk and water are mingled, the milk alone is perceived, and not the water.

तत्परस्वरम् ॥ २ ॥

2. And it belongs to the following vowel.

The commentator explains *parasvaram* as a descriptive compound (*karmadhāraya*), governed by *bhajate* understood; such an ellipsis, however, is so violent as to be hardly admissible, and the word is perhaps better taken as a possessive (*bahuvrīhi*), somewhat anomalously used. The occasion of the rule, we are told, is the doubt which is liable to arise as to when the consonant—which, owing to its having the vowel as a superior, is unable to stand by itself—is an adjunct of the preceding, and when of the following vowel. A single phrase is quoted as example, namely *imān eva lokān upadhāya* (v.5.5²: O. omits the last word).

This is the leading and introductory principle in all the Prāticākhyas (see note to Ath. Pr. i.55); it is greatly restricted in its application by the following rules.

अवसितं पूर्वस्य ॥ ३ ॥

3. A consonant in *pausā* belongs to the preceding vowel.

The commentator explains *avasitam* as meaning 'standing at the end of a *pada*,' and gives as examples *ūr̥k* (i.2.2² et al.: W. has instead *r̥k* [iv.7.9¹ et al.], and O. has *vāk* [i.3.9¹ et al.]), *vashat*

2. *svarapradhānatayā kevalam avasthātum asahamānam*¹ 'vyaiñjanam kadā pūrcasyā 'ṅgam' kadā parasyā 'ṅgam' iti saṁdehe' vyavasthāpayati: tad aṅgabhūtam² vyaiñjanam parasvaram bhajate. yathā: imān..... paraḥ cā 'sau svaraḥ ca parusvarah: ' taiṁ³ svaraparam⁴.

¹ O. om. ² G. M. om. ³ W. O. om.; G. M. *kadācid apar-*. ⁴ G. M. *-janā*. ⁵ W. *aṅgab-*; O. *vyasūtrataṁ*. ⁶ B. om. ⁷ W. ins. *param svārī*. ⁸ O. om. ⁹ G. M. O. om.

(ii.2.12⁴ et al.), *tat* (*passim*: given by G. M. only), and *havih* (i.2.4¹ et al.)

This principle, of course, is without exception in its application. It is either stated or implied in the rules of the other treatises (see note to Ath. Pr. i.57).

संयोगादि ॥ ३ ॥

4. Also the first consonant of a group.

That is to say, as the commentator points out, of a group consisting of either two consonants or more than two. The "also" (*ca*) expressed in the next rule is declared to be implied here also, and to prescribe adjunction to the preceding vowel. The examples given are *yajñān vyādīcat* (vi.8.11¹) and *apsv antah* (i.4.45² et al.: but G. M. substitute *apsv agne* [iv.2.11³], and W. has the corrupt reading *agratāh*). If, now, we had only to take the groups of consonants as they stand in the ordinary text, and divide them, the application of this and of the remaining rules for syllabication would be simple enough; but we are required to apply also the rules for duplication etc. as found in chapter xiv., and to make the insertions required by the rules of the fifth (v.32,33) and the present chapter (12-16), which puts quite a different face upon the matter. In fact, in the examples furnished, *nt* is the only group which is divided *n-t* without farther ceremony; *gr* becomes and is divided *g-gr*; *ney*, in like manner, *n-ney*; *psv* is expanded into *p-phsv*; and *jñ* into *ṣ-jñ* (writing the *yama*, as I have done elsewhere, with a straight line above the letter), where, by the action of the next rule, two consonants go to the preceding vowel. The class of groups consisting of two consonants only, and such consonants as (by xiv.23) are not liable to duplication, is the only one of which the division is settled by the present rule alone: it contains (in the Tāittiriya-Saṁhitā) thirty-nine groups, such as *nt*, *tth*, *pp*, *yy*, *ney*, *ṣṣ*.

The other treatises hold this same principle, and teach it in an equivalent manner (see Ath. Pr. i.56 and note)—save that the Rik Pr. (i.5, xviii.18) allows the letter to be adjoined to either the preceding or the following syllable.

3. *avasitam padāntavartī¹ vyañjanam² pūrcasya³ scarasyā⁴ ūgam⁵ syāt. yathā: ārk: vashat: tat: havih.*

¹ G. M. *antare*. ² G. M. *pūrcasvarāṅgam*. ³ B. om. ⁴ O. om. ⁵ W. O. om.

4. *'dāyor¹ bahānām² vā saṁyogo bhavati³: tasya saṁyogasyā⁴ di⁵ vyañjanam⁶ pūrcasvarasyā⁷ ūgam⁸ bhavati. yathā: yajñān-----: apsv----- parasātre cakārah⁹ pūrcasvarāṅga-
tvabodhaka¹⁰ ity atrā¹¹ pi tat¹² labhyate¹³.*

¹ B. om. ² G. M. om. ³ W. *varāṇām*; G. M. *saṁyogamān*. ⁴ G. M. ins. *yadi*. ⁵ G. M. ins. *yad*. ⁶ G. M. ins. *tal*. ⁷ W. *pūrcasyā*; O. *svarā*. ⁸ O. om. ⁹ G. M. om. ¹⁰ W. O. om. ¹¹ G. M. *svarasyā ūg*; B. *ūgam* bo-. ¹² G. M. om.

The manuscripts of the commentary are more than usually defective in this neighborhood: B. has lost the present rule, with something of what precedes and follows it; O. omits the next rule, with passages before and after; W. has done the same, to a somewhat less extent; but rule 5 and the lacking part of its comment were apparently restored on the margin of W.'s original, and its copyist has put them in in the wrong place, next before rule 6.

परेण चासंहितम् ॥५॥

5. And one that is not combined with the following vowel.

The comment supplies the word *svareṇa*, 'vowel,' as that with which *pareṇa* here agrees, and the whole interpretation is constructed accordingly. The meaning is, then, that (with the exceptions to be further specified in the following rules) only the final member of a group of consonants is to be adjoined to the following vowel, the rest belonging to that which precedes. By way of illustration is given merely *tat savituh* (i.5.6⁴ et al.); a most insufficient and ill-chosen example; since, in the final form of the group *ts*, only one consonant goes with the preceding syllable: thus, *t-ths*. But the commentator is obliged to spend his strength, and vainly, in endeavoring to refute an obvious objection to the rule itself, which he thus states: "well, but then the foregoing rule is meaningless, since by this one also the quality of adjunction to the preceding vowel is assured to the consonant that begins a group." And he replies, "you must not think that: for, in such cases as *māyagrīh* (iv.1.2⁵ et al.) and *arvā 'si* (i.7.8¹ et al.), in which the *y* and *v* are doubled after *r* by rule xiv.4, the former *y* or *v* is by the present rule made an adjunct of the preceding vowel, but the *r*, by rule 7 below, would become an adjunct of the following vowel: and that is impossible, since no such pronunciation ever takes place. So, as one or the other must needs be annulled, the question arises which is to be annulled; and here rule 4 comes in to settle the question."

This is not a very acceptable exposition, although it in a manner involves the true relations. Rule 4 is not meant as a safeguard against the misapplication of following precepts, but as a fundamental principle, with reference to which the present rule stands in a subordinate position; and the two must be understood as if they read "the first member of a group belongs to the preceding vowel; and, along with it, such other members as are not immediately combined with the following vowel." The former principle obtains everywhere, without exception; to the latter, rules 7-9

5. 'pareṇa' svareṇā 'sāṃhitam' asaṃyuktam 'vyañjanam' pūrvavarāṅgam bhavati'. yathā: tat..... nanu tarhi pūrvavātram anarthakam: saṃyogādibhāṭasyā 'pi vyañjanasyā 'nenāi 'va pūrvavarāṅgatvasiddheh. māi 'vam maṃsthāh': māyagrīh: arvā 'si: ity atra yavakārayo rephāt param ca (xiv.

establish very important and extensive classes of exceptions. If the mode of statement adopted in the treatise is open to some objection, we cannot help it; the slight inaccuracy is perhaps a consequence of the general prevalence of the doctrine of rule 4, to which its successor is added as an extension peculiar to this school.

No one of the other *Pratīcākhyas* recognizes any such principle as this; those of the *Rik* (i.5, xviii.18) and *Atharvan* (i.58) add to the initial consonant of a group only the first of a following pair which is the result of duplication, that of the *White Yajus* including further (i.104, 105) the other one of the pair, provided a mate follows. Its sway is, as already remarked, much more limited than would be thought at first sight, because rule 7 establishes a different usage for the immense class of groups of which a semi-vowel stands as final member, and rule 9 for the much smaller but yet important class in which a spirant stands last, or followed by a semivowel. Its general effect is to attach to the following vowel only such consonants or groups as could begin a word, leaving the rest to belong to the foregoing syllable. There seems to be need of illustrating more fully than the commentator has deigned to do, the sphere of its application.

This is, in consonant-groups originally of two members, to

1. Groups in which a mute is doubled (or its corresponding non-aspirate prefixed to it, as will be understood hereafter without special remark) after a surd spirant (*ç* or *q*, xiv.9, 15), *l* (xiv.2, 3), or *r* (xiv.4, 15), the first member of the group remaining unchanged: thus, *çk-k*, *lk-k*, *rk-k*. These are twenty-seven in number; and to them may be added *xy-y*, *rl-l*, *rv-v*, which, by the final specification of rule 7, follow the same mode of division. In regard to these, the usage as fixed by our treatise is the same with that sanctioned by the rest, as already mentioned.

2. Groups in which a mute, or *v*, is doubled before a mute of another series: thus, *kk-c*, *vv-p*. Of these there are fifty-one in the *Sanhitā*.

3. The same, but with the addition (by xxi.12) of *yama* before the final member: thus, *gg-gh*. Twenty-three groups.

4. Groups in which the initial spirant (sibilant) is doubled, and also the following mute (by xiv.9), only the last of all going to the following syllable: thus, *çç-c*. Thirteen groups.

5. The same, but with *yama*: thus, *ççp-pm* (*çm*). Six groups.

6. Groups in which *h* is doubled before a nasal, with *nāsikya* (by xxi.14: but see the note to that rule, for a different interpretation): thus, *hh-n*. Three groups only.

Against these one hundred and twenty-six groups, growing out

4) *iti deivte* * *kr̥te prathamayavakārayoh parena cā 'sañhi-*
*tam*¹⁰ *ity anena pūrvāscarāṅgatvam*¹¹ *prāptam*¹²: *rephasya tu*¹³ *nā*
'ntasthāparam asavarnam (xxi.7) *ity anena parāscarāṅga-*
*tvam*¹⁴ *prāptam*¹⁵: *tac cā 'çakyam: tathoccaranāṁ sambhāvāt:*
*anyatarabādhe*¹⁶ *kartavye sati kim vā bādhyam*¹⁷ *iti sanidehoh*¹⁸:

of original simple pairs, there are eighty like *k-ky* (from *ky*) and *k-khsh* (from *ksh*), in which, by rules 7 and 9, only the initial consonant of the finally resulting group goes with the preceding vowel.

When, now, the pairs here rehearsed come to be extended to triplets by the addition of a third member, if that member be a semivowel, or a spirant (sibilant) following a mute, the point of division remains just where it was before. And so also, of course, in the like extension of the groups mentioned under rule 4, above, as undergoing no change in the *varnakrama*. Thus, *ggr* (*g-gr*) is divided like *gg* (*g-g*); *ḡcy* (*ḡc-cy*) like *ḡc* (*ḡc-c*); *ṅksh* (*ṅ-khsh*) like *ṅk* (*ṅ-k*); and *rks* (*rk-khs*) like *rk* (*rk-k*). And the very great majority (one hundred and fifty-four) of the groups of three consonants occurring in the *Sanhitā* have a semivowel as their final member; with final sibilant there are only seven.

If, on the other hand, double groups are extended to triplets by appending a mute, either non-nasal or nasal (which happens in thirty-one cases), the point of division is, by the operation of the present rule, shifted toward the end of the group. Thus, we have

1. *ṅ-k*, but *ṅk-t*, two groups; and *ṅ-ḥ*, but *ṅj-ṅ*, two groups;
2. *rk-k*, but *rk-kc*, five groups; and *rj-j*, but *rj-jm*, five groups;
3. *dd-gh*, but *ddgh-ṅ*, two groups;
4. *sst-t*, but *sst-tṅ*, two groups;

which are extensions of the groups of two members already treated of, and advance the division only one point. But further, groups ending in a sibilant, and falling under rule 9, below, and those which by rule 15 have *svarabhakti*, exhibit, when a mute is added, a still greater transference forward of the point of division, and we have

5. *k-khs* (*ks*), but *kkhs-t* (*kst*), four groups; and *k-khsh* (*ksh*), but *kkhsṣ-ṣm* (*kshṣm*), five groups; and, finally,
6. *r-sh* (*rsh*), but *rshst-t* (*rshṣt*); and *r-ṣ*, but *rṣṣ-ṣm* (*rṣṣm*), three groups.

In the yet further extension to groups of four members, the same principles prevail. There are found nineteen such groups in which the additional letter, being a semivowel, has no effect upon the division; and only three in which the division is altered by an added mute. These last are: *ṅkhsht-ṅ* (*ṅkshṅ*), from *ṅksh*; *ḥkhsht-ṅ* (*ḥkshṅ*), from *ḥksh*; and *ntst-t* (*ntst*), from *n-tha* (*nts*).

Finally, the only two groups of five consonants occurring in the

*tatra niṣcāyakatvena¹⁹ saṃyogādī²⁰ (xxi.4) sūtram upatish-
thate.²¹*

¹ O. om., with the rule; W. puts, with the rule, at the end of the comment, having here also *pūrvavarāṅgam bhavati*. ² B. *sva*; W. adds *svareṇa*. ³ G. M. *śāṅh* (as also in the rule). ⁴ W. ins. *ca*; G. M. ins. *yad*. ⁵ G. M. ins. *tat*. ⁶ B. G. M. om. ⁷ W. *ḍibh*. ⁸ G. M. om. ⁹ G. M. ins. *ca*. ¹⁰ G. M. *śāṅh*. ¹¹ O. *ṭva*. ¹² O. *ṭik*. ¹³ W. B. om. ¹⁴ O. *ṭva*. ¹⁵ O. *ṭik*. ¹⁶ W. B. *anyadbb*. ¹⁷ O. *cāryam*. ¹⁸ G. M. *ḥa syāt*. ¹⁹ W. *niyātate*; B. *niṣcāyate*. ²⁰ G. M. *ḍi 'ti*. ²¹ O. *iva ti*.

Sanhitā (*utstr* and *tstry*) are formed by added semivowels, and so do not come under the further action of the present rule.

G. M. read *asāṇhitam* instead of *asaṇhitam* in the rule.

अनुस्वारः स्वरभक्तिश्च ॥ ६ ॥

6. Also *anuvāra* and *svarabhakti*.

By G. M., this rule is divided into two, *anuvārah* and *svarabhakti* *ca* (while, on the other hand, T. reads *anuvārasvarabhakti* *ca*); and such a division is noted, if not accepted, in the comment, by all the manuscripts, which say "of this rule (*svarabhakti* *ca*) is made a setting-apart, although the prescription is identical (with that made in the other rule, *anuvārah*)." And the object of thus separating what is confessed properly to belong together is stated to be "to bring about the adjunction of *svarabhakti*, in some cases, to the following vowel," on the authority of a verse which is quoted, to the effect that "the knowing man should connect with its predecessor (?) the *bhakti* that follows a short vowel; and in *rtasya dhūrshadam* the *bhakti* is said to do as it pleases;" but G. M. substitute for the latter half of the verse "to it should be assigned one *mora*, also before a pause and in cases of hiatus." The whole matter is exceedingly obscure, or quite unintelligible, without aid from the context of the quoted verse. The words cited as examples are not found in the Sanhitā; but they occur in the Rig-Veda (at i.143.7), and also in the Taittiriya-Brahmana (i.2.1¹²), where the *svarabhakti* has assumed the form of a full vowel, and the word reads *dhūrushadam*. It looks as if the commentators had set out to divide into two rules what they nevertheless have to acknowledge to be really only one, for the purpose of interpreting into the latter half of it, when set by itself, a license to the element in question to be treated either way; but, as they have not fully carried out their intention, I have preferred to retain the unity of the rule. It is quoted, we may further remark, under rule i.34, in all the manuscripts of the comment, apparently without any thought of a division.

6. *cakārah samuccayakathanadevārā pūrvasvarāṅgatvākarshakah. 'anuvārah' pūrvasvaram bhajate. yathā: aṅc.....¹ svarabhakti ca pūrvasvaram bhajate. yathā: gāh..... vidhān samāne¹¹ sūtrasya¹² 'sya prthakkarāṇam¹³: kracit svarabhakte¹⁴ parāṅgatvam¹⁵ āpādayitum¹⁶. tathā hi:*

¹³ *svarād dhrasvāt¹⁷ parām bhaktim pracayatvam nayed¹⁸ budhah:*

¹⁴ *rtasya dhūrshadam ce 'ti svatantrā bhaktir ucyate¹⁹.*

¹ B. -ra; G. M. -thanād vā; O. -devāt. ² G. M. put after *anuvārah*, as its comment, giving all the rest as comment to *svarabhakti* *ca* as a separate rule. ³ O. om. ⁴ W. G. M. O. -svarāṅgān. ⁵ G. M. syāt. ⁶ G. M. O. om. ⁷ O. svar-. ⁸ G. M. O. om. ⁹ O. samān-. ¹⁰ O. -na; G. M. add *anuvāra svarabhakti* *ce* 'ti. ¹¹ B. -kkār-. ¹² O. prthagnaktāh. ¹³ W. B. G. M. padā-. ¹⁴ W. B. -ditum. ¹⁵ B. svarāṅga hr-. ¹⁶ G. M. na ced. ¹⁷ G. M. substitute *tasya mātṛa bhaved ekā cīrāme ca rīcīpīshu*; O. adds ¹⁸ from comment to next rule.

Anuseāra appears here once more with the distinct value of a consonantal element following the vowel—and yet not as a full consonant, else it would fall under rule 4 above, and would require no separate treatment. The treatise is not so explicit as were to be desired in defining what is to be done with it in syllabication; but I presume we may infer that it does not count as *saṃyogādi* at all, but only as if an affection of the preceding vowel; and hence, that all the groups which it introduces are to be divided as if it were not there; that *ñce*, for example, is to be made into *ñce-c*, *ṣsu* into *ṣsp-pm*, and *ṣṭr* into *ṣṣṭ-tr*. The example given by the commentator is *aṅgūnā te* (i.2.6); but it is an ill-chosen one, and quite worthless, as, in any view of the nature and treatment of *anuseāra*, no question could arise as to the division *aṅ-gūnā*.

For *scarabhakti*, see the concluding rules of this chapter (xxi. 15, 16). The example given is *gārhapatyah* (i.6.7¹ et al.), which we are to read and divide *gār-ha-pat-tyah*.

नातस्यापरमवर्णम् ॥ ७ ॥

7. But not a consonant that is followed by a semivowel, if dissimilar with it.

The negative here signifies a direct reversal of the implication, as it denotes a denial of adjunction to the preceding vowel, and hence necessarily involves adjunction to the one that follows, since the consonant cannot stand by itself. "Dissimilar" is simply explained by *vilakṣhaṇa*, 'of diverse characteristics, different'; it excludes from the operation of the rule the doubled semivowel itself, and would also exclude the nasal semivowel into which *n* and *m* are converted before *l*, and *m* before *y* and *r* (v.26, 28), if these occurred where the rule could apply, which is not the case.

The examples quoted by the commentator are *adhyavasāya diṣah* (vi.1.5¹; i. e. *ad-dhya-*), *madhumigrenā* (v.2.8² et al.; i. e. *miḡ-gre-*), *aḡlonayā* (vi.1.6³; i. e. *aḡ-glo-*), and *iṣhe tvā* (i.1.1 et al.; i. e. *i-shet-tvā*): they are not to be commended as at all fully illustrating the wide range of application of the rule. This has been sufficiently set forth above, under rule 5. It helps to determine the division of one-third of the groups of two consonants, of four-fifths of those of three, of six-sevenths of those of four, and of all those of five—or of four-sevenths of the whole number of consonant

7. *nakārah pūrvasvarāṅgatevāyāvartakah: antasthāparam vyañjanam tasyā antasthāyā asavarṇam vilakṣhaṇam pūrvasvarāṅgam na bhavati: arthāt paravarāṅgam 'tad iti veditaryam': 'scata sthātum aḡkyatvāt. yathā: adhy-....: madh-....: aḡl-....: iṣhe-.... antasthā parā yasmāt tad antasthāparam, asavarṇam iti kim: pari-....*

¹ G. M. *iti vijnēyam*; O. om. ² O. puts at end of comment on preceding rule; B. *svaram vinda sthā-*. ³ O. om.

groups. By way of further examples, we may cite the two groups of five; they are *vi-yu-yātthst-tryas-sya* (ii.6.5^{4,5}) and *ab-bru-ranthat-tri-kā-mā* (vi.1.6⁵).

But if the commentator's direct illustration of the rule is scanty, his counter-illustration is yet less satisfactory. To establish the necessity of the specification *asavarnam*, 'dissimilar,' he cites only *paricdyam civita* (v.4.11²). Such cases as this, however, are rather covered by the fundamental rule *saṁyogādi* (xxi.4), and the application of the present one is to the groups in which a semi-vowel is doubled after *r*, and which we are to read *ry-y*, *rl-l*, *re-e*; while, on the other hand, in the half-dozen groups in which two different semi-vowels follow a mute, both of them, along with the preceding mute, go to the succeeding vowel: thus, *viśh-shvañ-ñyāre-chat* (ii.3.2⁶), *a-vit-trya-va-tu* (i.8.22¹), and *gr-hād-deri-hin* (ii.3.1⁵).

नासिक्याः ॥ ८ ॥

8. Nor the nose-sounds.

The "nose-sounds" are here again (as under ii.49) defined as the *yamas* (xxi.12,13) only; but there is no reason why we should not regard the *nāsikya* (xxi.14) as likewise included (see the note on rule 14). The examples given are also of *yamas* only: *rukman upa dadhāti* (v.2.7¹ et al.: O. has *rukman* only) and *rājñe śakarah* (v.5.11: O. substitutes *svarājñe*, v.6.21). The groups, in their full form, are read and divided *kk-km* and *jj-jñ*. An example of the *nāsikya* would be *rahh-ñi-ta-mam* (i.1.4¹).

The Vāj. Pr. (i.103) reckons the *yama* to the preceding vowel; neither of the other treatises says anything about it.

स्पर्शश्चोष्मपर उष्मा चेत्परश्च ॥ ९ ॥

9. Nor a mute that is followed by a spirant—provided the following spirant is likewise in the same case.

The first *ca* (translated 'nor' here), the commentator says, effects the connection of the rule with its predecessor; the second (rendered 'likewise') implies adjunction to the following vowel. This is not very lucid, for the two things are really equivalent to one another. And in the further exposition, the *parañ* appears (the readings are not consistent or clear) to be taken as signifying *parascarāṅgam*; but this cannot well be correct. The phraseology of the rule, indeed, is very peculiar, and I do not see how it is to be accounted for unless we may conjecture that the proviso *uśmā cet parañ ca* is a later addition, made after it had been noticed that the more general statement *sparçaṣ co. "śhmaparañ*

8. *nāsikyā yamāḥ² parascaram³ bhajante. yathā: rukman
..... rājñe.....*

¹ B. om. ² G. M. *yah*. ³ W. *svaraparam*. ⁴ G. M. O. om.

included too much. The meaning is clear: that a spirant which itself belongs to the following syllable, as being either directly combined with the vowel of the latter (xxi.5) or followed only by a semivowel before that vowel (xxi.7), carries with it a preceding mute; but if, on the other hand, it be cut off from the succeeding vowel by a mute, so as itself to belong to the antecedent syllable, a mute before it goes, of course, to the same syllable. The examples given in the comment are this time well selected, and illustrate the three cases involved: they are *shatt sam padyante* (v.4. 3⁴ et al.) and *vashatt svāhā* (vii.3.12); in both of them a *t* is inserted, by rule v.33, between the *t* and *s*, and the final reading and division is *tt-ths* and *tt-thsv*. As counter-example we have *akṣmayā vyāghārayati* (v.2.7⁵ et al.); where, after all rules are satisfied, we have *kkhsh-tn*.

As compared with those to which rule 7 applies, the consonant groups falling under this rule are few, only forty-six in all; in thirty of which the spirant carries the mute before it to the following vowel, while in the remaining sixteen both go together to the one that precedes. The detail is as follows.

Of double groups, composed of a single mute and spirant, there are seven: for example, *k-khsh* (*ksh*).

Of groups containing three consonants, the largest class is that formed by the addition of a semivowel to the preceding: for example, *k-khshy* (*kshy*): it contains ten groups. Then there are two like *ñ-khsh* (*ñksh*), three like *tt-khsh* (*tksh*), and the isolated *rk-khs* (*rks*).

Of groups of four consonants there are seven on this side, all but one (*rtt-ths=rtts*) like those of three, but with an added semivowel, which does not (xxi.7) change the division.

On the other side, where the spirant goes back to the vowel of the antecedent syllable, there are, of course, no groups of two consonants. Of groups of three we have nine, four with following non-nasal mute (as *kkhst-t=kst*), and five with following nasal (as *kkhsh-tn=kshn*). Of groups of four, there are two (as *ttst-tr=tstr*) formed from the foregoing with added semivowel, and three from triplets ending in a sibilant increased by a mute, either non-nasal (namely *nthst-t=ntst*) or nasal (as *ñkhsh-tn=ñkshn*). The two groups of five consonants, which also belong here, have been given above, under rule 7.

This finishes the subject of the division of consonant-groups in syllabication, the special elaborateness and intricacy of whose treat-

9. *pūraṣ cakāro nāsikyā* (xxi.8) *ity anena samuccayavācakah: uttaras tu' parascarāṅgatvākarśhakah: āśmapara sparṣaṣ ca parascarāṅgam bhavati: asāo' āśmad' paraṣ cet' parascarāṅgam' ced ity arthaḥ. shat.... vashat.... āśmaparaṣ ced iti kim: aksh..... āśmad' paro yasmād asāo āśmaparaḥ.*

¹ G. M. cakāro 'pi. ² B. asī. ³ MSS. -ma. ⁴ W. cet na; O. cet: sha. ⁵ W. B. -gaṣ; O. -ga.

ment in this *Prātiśākhya* has rendered necessary a fuller illustration than was thought worth while in connection with the others, in order to render apprehensible the views held regarding it by the authors of the treatise.

स्वरितात्संहितायामनुदात्तानां प्रचय उदात्तश्रुतिः ॥ १० ॥

10. Of grave syllables following a circumflex in *saṁhitā* there is *pracaya*, having the tone of acute.

The theory of the *pracaya* accent has been so fully set forth in the note to *Ath. Pr.* iii.65 that I do not need to spend many words upon it here. Its effect is, as there pointed out, to give to all the syllables which are left in the written text without any accent-mark the same high tone, whether they be *udātta*, 'acute,' or *anudātta*, 'grave.' Thus, in the example given by the commentator, *agne dudhra gahya kiṅṅila canya yā te* (v.5.9¹; G. M. omit *yā te*), which is written in *pada*-text

अग्ने । दुध्र । गह्य । किंशिल् । वन्य । या । ते ।

the *saṁhitā*-reading is

अग्ने दुध्र गह्य किंशिल् वन्य या ते;

the grave syllables *dudhra gahya kiṅṅila can-* being without written designation of accent, like the two acute syllables *ag-* and *yā*, and being by this rule uttered upon the same pitch with them. It makes no difference whether the circumflex which precedes the *pracaya* is enclitic (as in the illustration given) or independent; and I have pointed out above (under xix.3) that, owing to the absence of *kampa* in the *Tāittiriya-Saṁhitā* where a circumflex precedes an acute, there are very numerous cases in the text where the *saṁhitā* alone does not show us whether the unmarked syllables following a circumflex are *udātta* or *pracaya*—whether, for example,

क्षैतदेवाः, सो ऽस्मादेतर्हि, and सो ऽकामयत प्रजाः,

are to be read *hy ētād devāḥ* or *hy ētād devāḥ*, *sō 'smā'd etārhi* or *sō 'smād etārhi*, *sō 'kā'māyātā prajāḥ* or *sō 'kāmayatu prajāḥ*.

In the note referred to, I ventured the conjecture that the mode

10. *svarītāt parēśhām anudāttānām anudāttayor anudāttasya vā saṁhitāyām* ' *pracayo nāma dharmo*² *bhavati. yathā: agne..... anudāttānām iti kim: agnaye..... saṁhitāyām iti kim: agne..... udāttasya grutir iva grutir yasyā 'sāv*³ *udātta-grutir iti*⁴ *pracayasavarūpanirūpanam*⁵: *ato na punaruktiṣānkā*⁶.

¹ B. *ins. ca.* ² G. M. *dheyo.* ³ G. M. *sa* for *asān.* ⁴ W. *om.* ⁵ B. *-savarūpanam.*

⁶ W. *-ktikānvā.*

of writing the accent might not have been without influence on the theory as to its character—that is to say, that the Vedic phonetists may have come by an afterthought to declare the *pracaya* syllables of acute tone, and to pronounce them so, *because* they agreed with the acute in being without a sign of accent, while originally no such correspondence in character was perceived or intended to be signified. The conjecture will doubtless have appeared to many somewhat wild, but I think that in studying the development of the Hindu theory respecting accent it at any rate deserves to be taken fully into account and carefully considered. I am far from regarding it at present as anything more than a conjecture; yet one or two matters have come to light since it was put forth which at least add to its plausibility. Haug, namely, in a valuable and interesting communication from India to the Journal of the German Oriental Society (vol. xvii., 1863, p. 799 ff.), shows that the modern Hindu reciters of the Veda give tonic distinction only to the syllables that have the accent-signs, the *svarita* and *anudatta*, so that the *udatta* appears to be no accent at all, and is entirely confounded with the toneless *pracaya*—thus, under the influence of the mode of written designation, turning topsy-turvy, as it were, the whole system of spoken accent. And again, the peculiar system of writing the accent practised in the *Çatapatha-Brahmana* (which uses only one sign, the horizontal stroke beneath the syllable, applied in all the other known systems to mark the *anudatta* tone), has been turned in later times into a peculiar system of accenting, and treatises have been written to explain and teach it as such (see Kielhorn and Weber, in Weber's *Indische Studien*, x. 397 ff.*).

The commentator points out that two grave syllables, or even one, following the circumflex, receive the character of *pracaya* (of course, with the restriction made in the next rule), and not more than two only, as is literally signified by the plural *anudattānām* in the rule. To show that the conversion into *pracaya* is limited to grave syllables, he quotes *agnāye prāpate* (ii.4.1² et al.); to show that the conversion is made only in *samhitā*, he gives part of the other passage in *pada*-form, namely *agne : dudhra : gahya : kīṅçila : vanya* (Q. adds *yā*). We might naturally infer from this that the *pracaya* accent does not occur at all in *pada*-text; but the inference is not a necessary one (since the rule only says that syllables which are *anudatta* in their *pada*-form become *pracaya* in *samhitā*, without implying that there may not be *pracayas* in *pada*-text which remain such in *samhitā*), and would doubtless be erroneous; for at least the extant *pada*-text of the *Tāttiriya-Samhitā* agrees in this respect with those of the other Vedas, and writes *gīrvanase*, *antārikṣham*, and *samāgachanta*, for example,

* It ought to be added, that Haug and Kielhorn do not look at the matter in the same light in which I have placed it, but incline to believe in the reality and antiquity of what I have called the modern and artificially substituted systems: this is no place to discuss the subject; but I feel confident that the view I have taken will prove the only one tenable.

गिर्वणसे । अंतरिन् । and सुमगहंतेति संग्रहंते ।
not गिर्वणसे । अंतरिन् । संग्रहंते ।

The peculiarity of this *padu*-text in treating the *avagraha* as a full *avasāna* in regard to the designation of accent (as shown in the third of the examples), has been already spoken of above (under rule xx.3).

The terms of the rule would justify us in understanding *pracaya* to have its etymological meaning of 'accumulation, continued series,' and translating 'a series of grave syllables following a circumflex in *samhitā* is of acute tone;' and perhaps this was actually the intent of the rule-makers; but I have preferred, as the safer course, to follow the authority of the commentator in translating. To him, indeed, the term is so distinctly a technical one, implying utterance with acute tone, that he thinks it necessary to explain that *udāttagrutiḥ* is added by way of definition of the peculiar character of the *pracaya*, and therefore is not open to the reproach of *pinarukti*, or superfluous repetition.

नोदत्तस्वरितपरः ॥ ११ ॥

11. But not when an acute or circumflex follows.

That is to say, when such a series or *pracaya* of grave syllables is followed by an acute or a circumflex syllable, the one next preceding the latter is not made to be of acute tone, but retains its proper grave character, and is marked with the *anudatta* sign. The commentator offers as examples *tāyā devāḥ sutām* (iv.1.2¹: W. B. omit *sutam*, without which the passage is found elsewhere; G. M. substitute *tāyā devātayā*, iv.2.9² et al.) and *tād āhuḥ kvā jāgati* (vii.1.4³: G. M. omit *jagati*). These illustrations are wanting in variety, inasmuch as they show between the two independent accents only two original grave syllables, whereof one becomes an enclitic circumflex and the other remains grave; we may take the first example under the preceding rule as showing how an actual *pracaya* ends with a grave before the following original accent.

The subject to be supplied with the predicate in this rule is *svarah*, of course. There is an objectionable ambiguity in the form of the rule, inasmuch as there might most naturally seem to be *anuvṛtti* of *pracayaḥ*, and so a denial of that accent anywhere excepting before a pause.

We have seen at xix.2 that the name *vikrama* is given to the

11. *udātta*paraḥ¹ svaritaparo vā 'nudattoḥ *pracayo* na bhavati. *yathā*: *tāyā*.....: *tād*..... *udatta* ca² *svarita* co³ *dāttasvari*-*tāu*: *tāu* parāu *yasmāt* sa tatho 'ktaḥ.

¹ O. -ro vā. ² G. M. O. om. ³ B. om.

grave following a *pracaṇa*, as well as to one that comes immediately after a circumflex.

स्पर्शादनुत्तमादुत्तमपरादानुपूर्व्यान्नासिकाः ॥ १२ ॥

12. After a non-nasal mute, when it is followed by a nasal, are inserted, in their order, nose-sounds.

Which nose-sounds, as we are told in the next rule, some call *yamas*; and by this familiar name, which the other *Prāticākhyas* apply to them directly, we shall here, as we have done elsewhere, know them. The treatise teaches us nothing more about them, except (ii.49-51) that their place of production is either the nose or the mouth and nose, and that the producing organ is as in the series of mutes; and farther (xxi.8), that in syllabication they are to be reckoned with the following vowel.

The theory of these curious and equivocal constituents of the ancient Hindu alphabet I have discussed pretty fully in the note to Ath. Pr. i.99, and I have no new light to throw upon the subject here. They are transition-sounds, assumed to intervene between non-nasal and following nasal, as a kind of nasal counterpart to the non-nasal, and therefore called its *yama* or 'twin.'

The meaning of *ānupūrvyāt*, 'in their order,' is ambiguous, as it might be understood to refer to the order either of the twenty non-nasal mutes or of the five nasals; or, of the four kinds of non-nasal mutes in each series—in which last sense the comment understands it, declaring that the first *yama* follows a first mute, the second a second, and so on; and he has before (under i.1) reckoned the *yamas* as four in the catalogue of alphabetic sounds. I have pointed out under ii.51 how difficult it is to reconcile this view with that of a variation of their organ of production as in the five series of mutes.

The commentator's examples are *tam prathathā* (i.4.9), *vimath-nānāh* (iii.5.4²), *vidmā te agne* (iv.2.2¹: O. omits *agne*), and *dārāni dadhmāsi* (iv.1.10¹)—one, namely, for each of the four classes of mutes. As rule xiv.24 expressly enjoins duplication of the non-nasal mute in these combinations, we are to read and divide *prathathā*, *vidd-ama*, and so on. The counter-examples (of which all but the last are lost in W.) are as follows: to show that the insertion is made only after a mute, *kalmāśā bhavati* (v.1.1⁴: O. substitutes *brahmuvādinah*, i.7.1⁴ et al.); that this mute must be a

12. *uttamaparād anuttamāt sparṇād* ¹ *ānupūrvyād yathākramam nāsikyā āgamā bhavanti: prathamāsparṇāt prathamānāsikyā²: dvitīyād³ dvitīyā⁴: evam 'anyatrā 'pi' yathā⁵: tam..... vim..... vidmā..... dār..... ityādi. sparṇād iti kim: 'kalm..... anuttamād iti kim: sumn..... uttamaparād iti kim:' sabdah.....*

¹ G. M. ins. *parata*; O. ins. *parah*. ² G. M. O. *-kyāh*. ³ O. *-yasparṇād*. ⁴ G. M. *-yāh*. ⁵ G. M. *anye*. ⁶ O. om. ⁷ W. om.

non-nasal, *sumnāya sumnini* (i.1.13³ et al.; O. substitutes *sushumnah*, iii.4.7¹); and that it must be followed by a nasal, *sabdah saḡarah sumekah* (iv.4.7²; G. M. omit *sumekah*; O. substitutes *vashat svāhā*, vii.3.12).

These examples are one-sided, in that they only exhibit the simplest form of group in which the *yama* is taken as increment. Of such simplest groups there are twenty-three met with in the *Sanhitā*: namely, after first mutes, *kn, kn, km, cn, cm, tn, tm, pn, pm, pn*; after second mutes, *chn, thn*; after third mutes, *gn, gm, jn, jm, dn, dm*; after fourth mutes, *ghn, dhn, dhm, bhn*. Then, of groups of three consonants involving such combinations: *jny* (*jñny*), *tny*; *ñhm, nñn* (*nññn*); *dghn* (*ādggh-ñn*), *nghn*; *rjm* (*rñjm*), *rtm, rtm, rdhn, rdhm*; *stm* (*sst-tn*), *sthm*. And of groups of four consonants, *rjny* (*rñjny*).

According to the phonetic systems of the other *Pratīcākhyas*, this would finish the tale of *yamas*. But, by the peculiar rule (xiv.9) which here requires a surd mute to be everywhere inserted between a sibilant and a following nasal, is brought forth a new and numerous brood of these curious twins. Thus, in double groups, *cn* (*cct-tn*), *gm, shn, shm, sn, sm*. Of groups of three containing these: *cny, shuv*; *kshn* (*kkhshp-ñm*), *kshn, tsn, tmn, psn*; *rjm* (*rñjm-ñm*), *rshn, rshn*; *smn*. Of groups of four, *ñkshn, ġcny*. In all, of both classes, fifty-seven groups.

तान्यमानिके ॥ १३ ॥

13. Some call these *yamas*.

The commentator adds nothing of value.

हकारान्नणमपरान्नासिक्यम् ॥ १४ ॥

14. After *h*, when followed by *n*, *ñ*, or *m*, is inserted *nāsikyā*.

I have translated this rule according to its obvious and incontrovertible meaning, which, if it needed any external support, would find it in the almost precisely accordant rule of the *Ath. Pr.* (i.100: the teachings of the other treatises upon the subject are much less distinct: see the note on the *Atharvan* rule). But the commentator gives it an entirely different interpretation. The ablative *hakārān*, he says, is here used in the sense of an accusative (his addition, "in the absence of *lyap* [the suffix *ya*]," I do

13. *tān nāsikyān eke śākhino yamān bruvate*¹. *uktāny evo 'dāharanāni*.

¹ G. M. *iti vadanti*.

14. *hakārād iti karmanī*² *lyablope*³ *pañcamī*. *tasmān naṇama-param hakāram āruhya nāsikyam bhavati*⁴: *sāmnāsikyō hakārāḥ syād ity arthah*. *ahnām*.....: *apar*.....: *brahm*.....

¹ W. -*ma*. ² W. *lyapūlope*; B. *lyaplope*; O. *lyaplope*. ³ B. -*ced* *iti*.

not understand); and the sense is, that a nose-sound is imposed upon the *h* itself, or that the latter becomes nasal. It is not difficult to see on what this theory of the quality of a *h* preceding a nasal is founded—namely, a recognition of the fact that such a *h* is really an expiration of breath through the nose: it being not less true of *h* before a semivowel or nasal than before a vowel, that it is (borrowing the phraseology of an earlier rule, ii.47) *udāya-carnādisasthāna*, ‘produced in the position of the succeeding letter.’ The commentator’s exposition might have come from the “some authorities” to whom the doctrine of that rule is attributed.

The examples given are *ahnām ketuh* (ii.4.14¹), *aparāhne* (ii.1.2⁵), and *brahmācādinah* (i.7.1⁴ et al.). Giving to the rule its real meaning, and applying the principle laid down at xxi.8 for the syllabic division, we should read *ahh-nām*: and so with the rest. As was suggested under Ath. Pr. i.100, it is probably this separation of the *h* from the nasal in syllabication that has led to the division of the two in point of utterance, and then to the thrusting in between them of a transition-sound.

G. M. have adapted the reading of the rule to the new interpretation, and give *hakāran nanamaparan nāsikyam* (the writing of *n* instead of *m* before *n* is frequent with these MSS.).

रेफोष्मसंयोगे रेफस्वरभक्तिः ॥ १५ ॥

15. In the combination of *r* and a spirant, there is a *svara-bhakti* of *r*.

The doctrine of our Prātisākhya respecting the *svara-bhakti* is less detailed, and less distinctly expressed, than that of the other treatises (for which, see the note to Ath. Prāt. i.101-2); from the statement here made, we should not even understand that this “vowel-fragment” is to be an insertion between the *r* and the spirant, although that is doubtless intended to be signified. The commentator enters into a long exposition of the subject; by no means, however, limiting himself to explaining and illustrating his text. The two South-Indian manuscripts (G. M.) are in some parts of this exposition fuller than the rest, and will be followed

15. ‘*rephasya co*’ *shmanas ca saṁyoge sati*’ *rephasvarabhaktir*. *iti jānīyāt*: ‘*svarasya bhaktiḥ svarabhaktiḥ*’: *yo* ‘*sya rephasya samānascaras*’ *tadbhaktiḥ syāt*: *ṛkāraḥ cā* ‘*sya jiheāgrakarana-teena*’ *rogrutyā cā* *samānadharmah*: ‘*bhaktir acayava ekadeṣa iti yavat*’: *etad uktam bhavati*: *ṛkāravayavo*’ *bhucati* ‘*ty arthah*. *sūtrenā*’ *’nena svarabhaktir eva*’ *cihitā*: *svarabhaktisvarūpam tu*’ *vispashtam*¹¹ *vyācashte vararucih*: ‘*ṛkāradīr anamātrā*’ *repho* ‘*rdhamātrā madhye ṣeṣhā*’ *svarabhaktir iti*¹². *asyā* ‘*yam arthah*¹³’.

*indriyavishayo*¹⁴ *yo*¹⁵ ‘*sāc amur ity ucyate budhāih*:

*caturbhir*¹⁶ *anubhir mātrāparimānam*¹⁷ *iti smṛtam*.¹⁸

in the abstract of it here given: the version of W. B. O., indeed, has rather the aspect of being an abbreviation of the other, and one not everywhere skilfully made.

At the outset, G. M. alone specify that the *svarabhakti* is combined with the spirant (and yet, by xxi.8, it is to be separated from the spirant in syllabication, going with the *r* to the preceding vowel). The term *svarabhakti* means 'a fragment, piece, or part of a vowel;' and a *repha-svarabhakti*, '*r*-vowel-fragment,' means a bit of the vowel that is akin, or has the same mode of utterance with, the *r*. Now the *ṛ* is of like quality with *r*, in being produced with the tip of the tongue and in having the sound of *r*: and it is a part of *r* that is intended. The rule merely prescribes the insertion; the nature of the latter is clearly set forth by Vararuci (one of the three principal sources of the present comment: see note to the introductory verses, pp. 6,7). The vowels are defined at i.5, and since among them only *r* agrees in place and organ with *r*, the "fragment" is of *r*. The *ṛ* is by i.31 declared to be short, or of one *mora*; and Vararuci defines the short *ṛ* as composed of a quarter-*mora* of vowel at the beginning, a half-*mora* of *r* in the middle, and a quarter-*mora* of vowel (W. B. O. say, of vowel-fragment) at the end. Then a verse is quoted describing the word *anu* as signifying a quarter-*mora*. This half-*mora* of *r*, now, found in the middle of *ṛ*, being divided, its two parts, each combined with the quarter-*mora* of vowel, severally receive the name of *svarabhakti*. Hence there are two *svarabhakti*'s. And in answer to the question where this *svarabhakti* of half a *mora* occurs, the makers of the *Çikshâ* have declared that the one ending with the vowel element occurs before *ç*, *śh*, and *s*, and the one ending with the consonant element before *h*; the former, moreover, being open, and the latter close. And it is added that in *yo cāi graddhām* (i.6.8¹) there is no *svarabhakti*, on account of absence of the order prescribed in the rule.

mātrikasya rkārasyā "dir *anumātrā*²¹ *svarabhāgo madhye rephe*
*'rdhamātrā*²² *çesho*²³ 'py *anumātrā*²⁴ *svarabhāgaḥ: etad rkārasva-*
rāpam. atra ²⁵ *rephe 'rdhamātre bhajyamāne*²⁶ *sati*²⁷ *tāu bhāgāu*
*pāreottarāc*²⁸ *anusahitāu*²⁹ *pratyekam svarabhaktināmadheyam*
*bhujete*³⁰: "sā cā svarabhaktir ardhamātrā. kutra³¹ vā³² *svara-*
*bhaktir*³³ ity āçaukya çikshākārāir ³⁴ *uktam:*

*çashaseshu svarodayām*³⁵ *hakāre vyañjanodayām*³⁶:

*çashaseshu tu*³⁷ *civṛtām*³⁸ *hakāre samvṛtām*³⁹ *vidur* ⁴⁰ *iti*⁴¹.

yo ---- *ityādāu* "sūtroktakramābhāvan na svarabhaktiḥ."⁴²

*svarabhaktyantaram*⁴³ *çikshāyām uktam:*

"*kareṇuḥ karviṇi cāi 'va hariṇi hārite*⁴⁴ 'ti *ca:*

*haṇṣapade*⁴⁵ 'ti *cijñeyāḥ pañcāi 'tāḥ svarabhaktayah.*⁴⁶

"*kareṇā*⁴⁷ *rahayor*⁴⁸ *yoge*⁴⁹ *karviṇi lahakārayoh:*

*harini*⁵⁰ *raçasānām cā*⁵¹ *hāritā*⁵² *laçakārayoh.*

So much by way of (would-be) explanation of the rule. But the commentator goes on to say that the *Çikshā* teaches other *svarabhakti*'s, to the number of five: namely, the *kareṇu*, between *r* and *h*, as in *barhiḥ* (i.1.2¹ et al.); the *karvini*, between *l* and *h*, as in *malhāḥ* (ii.1.2⁴); the *harini*, between *r* and *ç* or *s*, as in *darçapūrnāmāsū* (ii.2.5⁴ et al.) and *barsam* (ii.5.7¹); the *hāritā* (or *haritā*), between *l* and *ç*, as in *sahasravalçāḥ* (vi.3.3²); and the *haṇsapodā* (or *haṇsapādā*), between *r* and *sh*, as in *varshāhvām* (ii.4.10³)—and he who wants to go to heaven (on the score, no doubt, of patience, faith, and punctiliousness) must utter the five kinds of *bhakti*, as thus laid down. It appears, then, that the commentator's *Çikshā*, like the *Vāj. Pr.* (iv.16), regards *l*, not less than *r*, as followed by *svarabhakti* before a spirant.

न क्रमे प्रथमपरे प्रथमपरे ॥ १६ ॥

16. But not in case of *krama*, when a first mute follows the spirant.

The commentator defines *krama* as the equivalent of *deitva*, 'duplication,' and refers as authority to rule xxiv.5, where the word occurs again without, according to him, admitting any other meaning; whence, he infers, it must signify the same thing here also. We should rather turn the argument the other way, and say that, as *krama* can have no other meaning here, it may be conjectured to signify the same thing at xxiv.5. He further coolly

¹² *yā tu haṇsapādā nāma sū tu*²² *rephashakāroḥ;*

¹³ *evam pañcavidhām bhaktim uccaret svargakāmukah.*²³

(¹) G. M. *reph-shmanes sayyoge solī tatn ūshmasayyukto.* (²) G. M. *svarabhaktir iti kīnī : idreṣṣ svarasya bhakt s svarabhaktiḥ bhaktir chagah ; avayava iti ekadeṣa iti yāvat ;* B. O. om. *svarabhaktiḥ.* (³) G. M. O. *nakaravasi.* (⁴) O. *pena.* (⁵) G. M. *gruyā.* (⁶) W. *yana.* (⁷) G. M. om.; O. *-a ity arthak.* (⁸) W. O. *rkāru eva y-*; G. M. *rkārasya* *vay.* (⁹) G. M. *evam.* (¹⁰) B. om. (¹¹) O. *spa.* (¹²) G. M. *svara* *līvat kīnī* *viciḥṭa* *iti cet shodhaç* *"dītaḥ svarāḥ (i.5) iti svarasānīḥkṛtān tathu rkā-rarephayos samānasthānakaravātād rkāru-varasyai* *"va bhaktiḥ rkāros līvat kīnī* *viciḥṭa* *iti cet rkāvalkārāu hrasyāu (i.31) iti hrasyatvād ekamātro bhaved dhraṣea* *iti ekamātraka rkārak vararucinai* *"vam uktam mātrikasya rkārasya* *"dau svarasya* *"umātrah rephasya* *"dhamātro madhye* *"nta svarasya* *"umūtrai* *iti : anu-mātra* *iti kīnī.* (¹³) B. *-tralām api.* (¹⁴) O. *çsha.* (¹⁵) B. om.; O. *anumātrā.* (¹⁶) W. *nish;* G. M. *-driyā.* (¹⁷) B. O. om. (¹⁸) W. O. *-ter.* (¹⁹) W. *mātrāprayāgam;* B. *-trāpramānam;* G. M. *-ga.* (²⁰) G. M. *ins.* *asya* *"yam arthak.* (²¹) B. G. M. *-tra.* (²²) G. M. *-trah.* (²³) G. M. *ante.* (²⁴) W. *-trah;* G. M. *-tra.* (²⁵) G. M. *ins.* *rkārama-dhyava* *tinī.* (²⁶) G. M. *vidh.* (²⁷) O. om. (²⁸) G. M. *-rē.* (²⁹) W. B. O. *-sānīh.* (³⁰) W. B. *bhajyate;* G. M. O. *bhajate.* (³¹) G. M. *tato deṣ svarabhakti vidyete ardhama-dri-* *kosvarabhaktiḥ kutra vā tishthati.* (³²) W. *atra.* (³³) W. om.; B. *kā.* (³⁴) G. M. *ins.* *evam.* (³⁵) W. B. *-yā.* (³⁶) W. B. *-yā.* (³⁷) B. O. *ca.* (³⁸) W. *-tā.* (³⁹) W. *-tā.* (⁴⁰) O. om. (⁴¹) G. M. *sūtreṇa* *"kōkrameṇa syāt svarabh-* *kt-k.* (⁴²) G. M. O. *ins.* *api.* (⁴³) O. om. (⁴⁴) G. M. *har.* (⁴⁵) G. M. *-pāde.* (⁴⁶) G. M. *ins.* *kīr* *rya* *eti iti cet.* (⁴⁷) W. B. *-gu;* G. M. *-gūnī.* (⁴⁸) B. *hayor;* G. M. *hōrayor.* (⁴⁹) W. B. G. M. *vidyāt.* (⁵⁰) W. B. *ra-* *çayor yoge;* G. *çaravām jāyē;* M. *çasām jāyē.* (⁵¹) G. M. *har.* (⁵²) G. M. *sva-* *rbhaktiḥ haṇsapādām vidyāt.* (⁵³) O. om.; G. M. *-muka* *iti : yathā : karēpuḥ : bar-* *hiḥ : yathā karvini : mālḥḥ : harini : darçapūrnāmāsū : barsam : hā-* *ritā : sahasravalçāḥ : haṇsapādā : varshāhvām ityādi.*

inserts an "or" in the rule, and declares it to mean 'either when the spirant is doubled or when it is followed by a first mute.' This must evidently be condemned: for, in the first place, the text contains no "or;" and, in the second place, if that were the meaning, the specification would be superfluous, since the spirant is always doubled before a first mute, and so *krame* would include all the cases—except, indeed, according to the doctrine of Plākshi and Plākshāyana, who (xiv.17) deny the duplication of the spirant in such a situation; and we are perhaps to connect his interpretation of the present rule with his apparent acceptance of the doctrine referred to, and suppose that he would read *rsh-t*, and *rcp-pm* etc. (namely, for *rcm*, *rshn*, and *rshn*), while the reading actually approved by the treatise is *rshsh-t*, *rcpp-pm* etc. There are five groups—namely *rcy*, *rcv*, *rshy*, *rcv*, and *rhy*—in which the difference of interpretation would make a difference as regards the presence or absence of *svarabhakti*; if the "or" is implied, they will be read and divided *rc-cy* etc.; if not, they will be *r-c-cy* etc.

The commentator's examples are *dārçyañ yajñam* (iii.2.2^b: only O. has *yajñam*; G. M. read *dārçyañ hi*, which, if it be an actual passage, I have overlooked in searching out the references), *varshyābhyah* (vii.4.13: W. B. O. read *varshābhyah*), *barsvebhih* (v.7.11), and *etarhy ārūdhah* (v.1.5^b: found in O. only), illustrating four of the five cases in which his interpretation would exclude the *svarabhakti*; and further, for cases in which a first mute follows, *adarçma jyotih* (iii.2.5^a: omitted in O.), *kārshnī upānahāu* (v.4.4^a et al.), and *varshā parjanya* (vii.5.20: found in G. M. only).

CHAPTER XXII.

CONTENTS: 1-2, formation of articulate sounds in general; 3-8, definition of terms used in the treatise; 9-10, mode of production of high and low tone; 11-12, established tone and pitch; 13, length of pauses in the text; 14-15, heavy and light syllables.

16. *'kramaçabdo deitvaparyāyoh: katham etat: prakṛtir vi-kramah krama* (xxiv.5) *ity atra deitvasyāi¹ 'va' kramaçabdenā² 'bhidhānād atrā³ 'pi sa evā⁴ 'rtha iti niçcinumah.⁵ āshma-ṇah krame sati⁶ tasminn āshmaṇi prathamapare vā⁷ sati na svarabhaktir bhavati.⁸ 'krame yathā: dārç-.....: varsh-.....: bars-.....⁹ "prathamapare yathā: ad-.....¹⁰ kār-.....¹¹ prathamah paro yasmād asū prathamaparah.*

*iti tribhāshyaratne prātiçākhyavivarṇe
ekaviñço¹² dhyāyah.*

(¹) O. om. (²) G. M. -*team asty e*. (³) W. -*bdo nāmā*. (⁴) W. *red*. (⁵) G. M. *'rtho niçcitah*. (⁶) O. om.; G. M. add *vā*. (⁷) G. M. put after *sati*. (⁸) W. -*vet*. (⁹) O. om.

(¹⁰) O. *etar-.....*; G. M. *etasya prathamaparo y-*. (¹¹) G. M. add *varshā-.....*

(¹²) G. M. O. *deitvyapraṇe navamo*.

शब्दः प्रकृतिः सर्ववर्णानाम् ॥ १ ॥

1. Tone is the material of all articulate sounds.

The putting-together, as well as the material, of this and the following chapter is rather peculiar, and makes the impression of a supplement to the *Prāticākhya* proper. This present rule and its successor are akin with the first two of the next chapter, and all these with the rules of the second chapter. As under ii.1, the commentator explains *ṣabda* by *dhvani*; for *prakṛti* he gives as synonym *mūlakāraṇam*, 'radical cause'; and *varṇa* he declares to designate the whole congeries of vowels and consonants.

तस्य रूपान्यत्रे वर्णान्यत्रम् ॥ २ ॥

2. In the difference of form of the former consists the difference of the latter.

That is to say, in the difference resulting from the variety of positions giving audible quality: compare ii.3.

तत्र शब्दद्रव्याण्युदाहरिष्यामः ॥ ३ ॥

3. Here we will instance the offices of terms.

A complete and violent change of subject is introduced by this rule, continuing to rule 9; which last, again, attaches itself closely enough to the beginning of the chapter to have been its natural continuation. The intervening batch of rules looks like an interpolation, thrust in at this point *apropos* of *ṣabda* in rule 1; the word being taken here, however, in an entirely different sense. The commentator tries to smooth over the transition by pronouncing *ṣabda* a synonym of *śāstra*, 'text-book, body of doctrine'; which latter is formed by the putting to use of combinations of the alphabetic sounds just above spoken of. He distinctly ascribes to *dravya* the sense of 'office, aim,' as the connection also requires,

1. *sarvavarṇānām*¹ *ṣabdo*² *dhvaniḥ prakṛtir mūlakāraṇam bhavati: varṇaṣabdena svaravyaṅjanātmako rāṣir ucyate. sarve ca te varṇāḥ ca sarvavarṇāḥ³: teshām*⁴.

¹ G. M. om. ² G. M. ins. *nāma*. ³ O. om. ⁴ G. M. add *sarvavarṇānām*.

2. *prāticrutkathānabhedāt tasya*¹ *prakṛtibhūtasya*² *rūpānyatve sati varṇānyatvam syāt*³. *yathā: a: i: u: ityādi*.

¹ B. *prat*.; G. M. *-nād bhe*-. ² G. M. ins. *ṣabdasya*. ³ W. *pratibh*-. ⁴ O. om.

3. *teshām varṇānām sarvatra*¹ *saṅghātāprayoge*² *śāstram*³ *ity ucyate: tasya ṣabda*⁴ *iti paryāyanāma: tatra tasmiṇ chāstre yāni dravyāni bhavanti tāny udāharishyāmaḥ. yat karma yena kriyate tat tasya dravyam*⁵ *sādhanaṁ iti yāvat*⁶: *yathā gha-*

giving *sādhana*, 'efficiency,' as its equivalent. As clay to a vessel, we are told, so are alphabetic sounds to a text-book.

वर्णकारौ निर्देशकौ ॥ ३ ॥

4. *Varṇa* and *kāra* are indicatory.

These two terms have already formed the subject of rules i.16-20. Rules vi.1,7 are cited as examples of their use.

चापीत्यन्वदेशकौ ॥ ५ ॥

5. *Ca* and *api* are implicative.

Rules vi.3 and iv.4 are cited as containing examples of the use of these signs of continued implication from something that has gone before.

तथैवेति विनिवर्तकाधिकारकावधारकाः ॥ ६ ॥

6. *Tu*, *atha*, and *eva* are exceptional, introductory, and restrictive, respectively.

The use of these connectives is instanced by quoting rules i.19, v.1, and xiv.3 (G. M. substitute vii.1 for the second).

These rules are too trivial and superficial to make it worth while to enter, in connection with them, into any discussion of the use of the particles in the text of the *Prātiśākhya*. The index, and the notes on each rule, will give the means of investigating the matter. We have often had occasion to animadvert upon the commentator's

*tasya mṛd ity evaṃ śāstrasya varṇāḥ*¹; *yāni dravyāṇi saṁvyavahārārthāni kartavyāni tāni vyākhyāsyāmaḥ*. *śabdasya dravyāṇi śabdadravyāṇi: tāni*.

¹ O. -ta. ² O. ins. vā. ³ W. -tre. ⁴ W. B. *katham*; O. om. ⁵ W. B. ins. *tasya rūpāṇi*. ⁶ W. O. -bā. ⁷ O. *pradarśayishy-*. ⁸ O. *karmayate*. ⁹ W. *tatra*; B. *na*. ¹⁰ B. -ya; M. om. ¹¹ O. om. ¹² W. -ga; G. M. -gānāḥ; O. *savarṇāḥ*.

4. *varṇaśabdaḥ kāraśabdaḥ ca nirdeśakāu*¹ *nirdeśavācakāu*² *syātām*. *yathā: avarṇavyaṅjanaśakuni* (vi.7) *iti: atha śakāraṇ śakāravisaṛjanīyāv* (vi.1) *iti*. *varṇaḥ ca kāraḥ ca varṇakārau*.

¹ G. M. om. ² W. B. -deśakāu vāc; O. om.

5. *ca: api: ity etāv*¹ *anvādeśakāu syātām*. *pūrvāpekshoyā*² *'nvādeṣa ity ucyate*. *yathā: asadāmāsiṅcaṅś ca* (vi.3): *iti paro 'pi* (iv.4).

¹ G. M. ins. *śabdau*. ² W. B. *pūrvapakṣo*; O. *pūrvopakṣo*.

6. *tu: atha: eva: ity ete śabdā yathākramena*¹ *vinivartakādhikāraśādhārakā bhavanti: yatra tuśabdaḥ grūyate tatra*

tendency to put into them (especially into *tu*) a meaning which they were never intended to bear.

वेति वैमाषिकः ॥ ७ ॥

7. *Vā* is alternative.

Rule ii.50 is quoted as example.

नेति प्रतिषेधकः ॥ ८ ॥

8. *Na* is prohibitive.

The example this time is xiii.15 (G. M. substituting xiv.14); and in it appear again some of the differences of reading which were noted in the rule itself where it occurred.

आयामो दारुणमणुता खस्येत्युच्चैःकराणि शब्दस्य ॥ ९ ॥

9. Tension, hardness, smallness of aperture, are producers of high tone.

Reference is made to rule i.38, in which the acute accent is defined as consisting in high tone; and the present precept is declared to be given for the sake of that, and in order to prohibit that slack or indifferent utterance which prevails in common life. *Āyāma*, 'tension,' is explained as meaning rather 'extension (literally 'longness') of the members;' *dārunya*, as 'severity of the vowel;' and *anutā khasya*, as 'closure of the orifice of the throat:' this is what one who would utter a sound in high tone must do.

There is evidently much more guess-work than true observation in this rule and the one next following: if they had been given as definitions of sonant and surd utterance, instead of high and low

nivṛtīḥ: yatrā 'thaṣabdas tatrā 'dhikārah: yatrāi 'vaṣabdas tatrā 'vadhāraṇam' veditavyam. yathā: ephas tu rasya (i.19): 'atha sañhitāyām ekaprāṇabhāve' (v.1):² sparṣa' evāi 'keshām ācāryāṇām (xiv.3). viśeṣeṇa nivartayati 'ti vinivartakah: adhikaroti 'ty adhikarakah': avadhārayati 'ty avadhāarakah.

¹ G. M. -man. ² G. M. O. ins. ce 'ti. ³ G. M. atha nakāro ṇakāram (vii. 1). ⁴ O. om. ⁵ G. M. -ṣapara. ⁶ W. O. G. M. -rah.

7. *ve 'ty esha ṣabdo vāibhāshiko' vāikalpiko bhavati. yathā: mukhanāsikyā vā (ii.50).*

¹ G. M. -shabo (as also in the rule).

8. *ne 'ty esha ṣabdoḥ pratishedhako bhavati: yathā: 'na shumnognir (xiii.15) iti.²*

¹ G. M. O. syāt. ² G. M. atha na (xiv.14); B. na sushu-; O. -na sum-; W. B. -gni 'ti.

tone, they might more easily have been regarded as describing real processes of articulation.

अन्ववसर्गो मर्दवमुरुता खस्येति नीचैःकराणि ॥१०॥

10. Relaxation, softness, wideness of aperture, are producers of low tone.

The exposition of this rule runs quite parallel with that of the preceding (only O., however, referring to the definition of *anudatta*, 'grave,' as of low tone, at i.39). To *anvavasarga* is given *vinatātā*, 'drooping condition,' as synonym; to *mārdava*, *snigdhatā*, 'smoothness'; and to *urutā*, *sthūlatā*, 'bigness.' There is nothing at all to commend in such a description of the way in which low tone is produced.

मन्द्रमध्यमताराणि स्थानानि भवन्ति ॥११॥

11. Soft, middle, and loud are the three qualities.

Their use, we are told, will be explained farther on—namely, in rules 4–10 of the next chapter. I have ventured to render *sthāna*, literally 'place' or 'position,' by 'quality,' as better expressing the nature of the distinctions implied. The name apparently comes from such theories as that laid down in rule xxiii.10 as to the "place" of production of the different qualities of tone.

In answer, we are told, to the suggested inquiry, "of what are

9. *uccāir udatta* (i.38) *ity uktam: tadartham idam ārabh-yate: lokavad yādṛchikoccāraṇapratishedhārtham: āyāmo gā-trāṇām dāirghyam: dārunyam svarasya kathanatā: anutā kha-sya galavivarasya samvrtatā: etāni sādhanāni śabdasyo ccāih-karāni śabdam uccāir udattam kurvanti ty arthah. uccaśabdam uccārayatāi tat kartavyam iti vidhiḥ. uccāih kurvanti ty uc-cāihkarāni.*

¹ W. *yāvach-*; B. *hādach-*; W. B. O. *-rthah*. ² W. om. ³ B. *-virarāṇasya*; G. M. *-virarāṇasya*, and put after *samvrtatā* (B. O. *-vrtā*). ⁴ G. M. *nāmādheyāni*. ⁵ W. *ccāih-*. ⁶ G. M. om. ⁷ W. G. M. om.; B. adds *kaṇṇini*, and om. the following rule.

10. ¹ *anvavasarga gātrāṇām vinatātā: mārdavam svarasya snigdhatā: khasyo rutā kathanasya sthūlate ty etāni sādhanāni śabdasya nīcāihkarāni śabdam nīcam anudattam kurvanti ty arthah: nīcaśabdam uccārayatāi tat kartavyam iti vidhiḥ: nī-cāih kurvanti ti nīcāihkarāni.*

¹ O. ins. *nīcāir anudatta* (i.39) *ity uktam*. ² G. M. O. *vīrtatā*. ³ G. M. om. *iti*. ⁴ G. M. *ud-*. ⁵ W. *uddhārayanā*; B. *-yan*; G. M. *-rayiyatā*; O. *-rayatā*.

11. *mandram madhyamam tāram ce ti sthānāni bhavanti: mandram iti prathamam: madhyamam iti dvitīyam: tāram iti*

these positions or qualities?" the subject is continued in the next rule.

तत्रैकविंशतिर्यमाः ॥ १२ ॥

12. In them are twenty-one tones.

For the application of these tones or keys, also, we are referred to a later passage (xxiii.11 etc.). As synonym of *yama* is given *svara*, 'tone.'

The commentator chooses to connect these rules with those that follow in the next chapter, and to overlook the obvious fact that in the two chapters we have separate and independent statements upon the same subject, which cannot have come from the same hand, and of which the second renders the first wholly superfluous.

ऋग्विरामः पदविरामो विवृत्तिविरामः समानपदवि-
वृत्तिविरामस्त्रिमात्रो द्विमात्र एकमात्रो ऽर्धमात्र इत्या-
नुपूर्व्येण ॥ १३ ॥

13. The verse-pause, *pada*-pause, pause for hiatus, and pause for hiatus in the interior of a word, are respectively of three *moras*, two *moras*, one *mora*, and a half-*mora*.

As example of the pause of three *moras* at the end of a verse is quoted *ubhā vājasya sātaye huve vām* : (i.5.5² : O. omits the first two words); of the pause of two *moras*, in *pada*-text, between the *padas*, *ishe* : *tvā* : *ūrje* : *tvā* (i.1.1 et al.) : and, for all that the *Prāticākhya* tells us, we are to regard the *avagraha* pause, dividing the two parts of a compound word, as of the same length (the *Rik* [i.6, r. 29] and *Vājasaneyi* [v.1] *Prāticākhyas* give it only one *mora*); of the hiatus-pause, *sa idhānah* (iv.4.4³), *ta enam* (ii.3.11⁴), and *tā asmāt* (ii.4.4¹) : W. prefixes *ā*, but doubtless only by

trītiyam : *eteshām*² *sthānānām prayojanam uttaratra*⁴ *vakshyate*.
²*etāni sthānāni keshām ityapekshāyām āha parasūtram*⁵.

¹ G. M. om. ² O. 'ty etāni. ³ G. M. O. *esh*. ⁴ B. *īkṛatra*. ⁵ O. om.

12. *teshu*¹ *sthāneshu ekaviṃśatir yamāḥ svarā bhavanti* : *teshām yamānām uttaratra prayojanam vakshyate*.

¹ O. *tatra trishu* ; B. adds *trishu*.

13. *ṛgvirāmādayas trimātrādikālā*¹ *yathākramam*² *bhavanti*.
*yathā*³ : *ubhā*..... : *ity ṛgvirāmāḥ* : *ishe*..... : *iti padavirāmāḥ* :
sa..... : *ta*..... : *tā*..... : *iti vivṛttivirāmāḥ* : *prauḡgam iti samā-*
napadavivṛttivirāmāḥ. *'rci'*⁴ *virāma ṛgvirāmāḥ* : *padasya virā-*
maḥ padavirāmāḥ : *padadevavivṛttāu*⁵ *virāmo vivṛttivirāmāḥ*⁶.
śikshāyām ⁷ *asya viśeṣa uktaḥ* :

a copyist's blunder); of the pause of interior hiatus, *pratiṅgam* (iv. 4.2¹), which is, I believe, the only case. The commentator also quotes a couple of verses from his *Çikshā*, laying down four subdivisions of the pause of hiatus, and assigning them different quantities: that between a short and long vowel is *vatsānusṛti*, and is one *mora* long; that between a long and following short is *vatsānusārinī*, of the same length; between two short vowels, *pākavati*, three quarters of a *mora*; between two long vowels, *pīṇikā*, a quarter-*mora* only (Uvata's comment on the *Rik Prāt.* [ii.1] states the intervals quite differently). In W. there are two verses which are not found in the rest; as they stand, their meaning is in great part obscure to me, and I prefer to leave them unamended and untranslated.

यद्यज्ञानान्तं यदु चापि दीर्घः
 संयोगपूर्वं च तथानुनासिकम् ॥
 एतानि सर्वाणि गुणानि विद्याच्च
 हेषाण्यतो ज्यानि ततो लघूनि ॥ १४ ॥

14. A syllable that ends with a consonant, one that has a long vowel, one that precedes a conjunction of consonants, one that is nasal—all these are to be accounted heavy; the rest, other than these, are light.

**pipīlikā dirghasame ca madhye
 savarnatā pākavati paddākye:
 dr̥shṭvā ca vatsānusṛjas to asāmye
 te atho 'ci mukhyas tu virāmakālah.1.*

*svarodaye to anusvāro bhaved adhyānumātrikah:
 virāmaḥ ca taylor madhye vāiṣṇeshikāc ca dirghayoḥ.2.
 hrasvādir vatsānusṛtir¹⁸ ante vatsānusārinī:
 pākavaty ubhayahrasvā¹¹ dirghobhaya¹² pipīlikā.
¹³mātrā¹⁴ ca¹⁵ vatsānusṛtis¹⁶ tathā vatsānusārinī:
 pādona syāt pākavati pādāmātrā pipīlikā.¹⁷*

*¹⁷samānam ca tat padam ca samānapadam: ekopadam ity
 arthah¹⁷: ¹⁸samānapade vivṛttiḥ samānapadavivṛttiḥ: tasyām¹⁹
 virāmaḥ²⁰ samānapadavivṛttivirāmaḥ. ²¹tisro mātrā yasyā 'sāu
 trimātrah: ²²dve mātre yasyā 'sāu dvimātrah: ekā mātrā yasyā
 'sāv ekamātrah: ardhā mātrā yasyā 'sāv ardhāmātrah²³.*

¹ W. -trak-. ² O. -mena. ³ G. M. om. ⁴ O. puts below, at ¹⁸. ⁵ W. rg; G. M. rco. ⁶ B. padavi-; O. -yamadhye vivṛtti. ⁷ W. B. om.; O. padavie-. ⁸ G. M. ins. apy. ⁹ in W. only. ¹⁰ W. -tsānusārtimadhyer; G. M. -nusāter. ¹¹ B. -yoh-; G. M. -yeh-. ¹² G. M. -ghayos tu. ¹³ O. om. ¹⁴ G. M. -trikā. ¹⁵ G. M. om. ¹⁶ W. -nusṛjanti; G. M. -nukṛtis. ¹⁷ O. puts below, at ²¹. ¹⁸ O. puts ¹⁶ here. ¹⁹ W. om.; B. -sma; O. -sya. ²⁰ W. om. ²¹ O. puts ¹⁷ here. ²² in G. M. only.

The commentator instances the different kinds of "heavy" syllable, as follows: one ending with a consonant, *māte 'va putram* (iv.2.3² et al.: G. M. omit); one long by its vowel, *te te 'dhipatayah* (iv.4.11³: G. M. omit the last word); one followed by a consonant-group, *aṣmā ca me* (iv.7.5¹: W. has *ānmāyina*, which appears to be merely a corrupt reading; I have found nothing at all like it in the *Sanhitā*); one that is nasal, *viñcatyāi* (vii.2.13 et al.).

The distinction of the syllable as "heavy" or "light" has value only in a metrical point of view, and does not make its appearance elsewhere in our treatise (except as it is referred to in rule xxiv.5—which rule we might have expected the commentator to quote here, as the occasion of this one). The quality of "long" or "short" belongs to the vowel alone, and (see xxi.1 and its comment) the consonants accompanying the latter are regarded as absorbed into it, and forming part of its natural quantity. This separation of "heavy" and "long," or of weight and quantity, is practically convenient, perhaps, but theoretically indefensible; and we have reason to be surprised that phonetic observers so acute as the Hindus had not worked the theory of syllabic quantity into a more consistent shape. The other treatises agree with this: see *Ath. Pr.* i.51-54, and notes.

The use of the word *anunāsika* in describing a syllable containing *anusvāra* is (as already noted, under ii.30) one more sign of a theory which regards the *anusvāra* as a quality and not an element. The *Ath. Prāt.*, which holds this theory, uses the same term in its definition (i.53). It deserves to be noted, however, that to read *anusvāram* instead of *anunāsikam* in the verse would help the metre, making the four *pādas* similar.

This rule is enough by itself to determine the weight of any syllable whatever: but, as the commentator points out, the one following is added to resolve any doubts which might after all arise as to what syllables were light.

14. *vyāñjanāntam yad aksharam: 'vyāñjanam ante' yasya tad vyāñjanāntam: 'yad u cā 'pi dīrgham' aksharam: 'saṁyogapūrvam ca yad aksharam: 'saṁyogāt pūrvam' saṁyogapūrvam: tathā 'nunāsikam: sānunāsikam' yad aksharam: uktāny etāni sarvāny akṣharāṇi gurūṇi vidyāt: jānīyāt. yathā 'vyāñjanāntam: māte.....' yathā dīrgham: te..... yathā saṁyogapūrvam: aṣmā..... yathā 'nunāsikam': viñcatyāi. 'ṣeshāny ato 'nyāni': ata¹² ebhya gurubhyaḥ ṣeshāny anyāny akṣharāṇi tato 'nanturam'¹⁴ laghāni vijānīyāt¹⁵. ṣeshāni¹⁴ kāni¹⁷ ty āṣaṅkyo 'ttaraḥlokena¹⁷ vīṇṇoti.*

⁽¹⁾ G. M. put at beginning. ⁽²⁾ G. M. -*tan*. ⁽³⁾ G. M. ins. *yad*. ⁽⁴⁾ G. M. ins. *yogāt pūrvam*. ⁽⁵⁾ G. M. om. ⁽⁶⁾ B. G. M. om.; O. -*gam*. ⁽⁷⁾ O. om.; G. M. *anu*. ⁽⁸⁾ G. M. *vyāñjanāntam ity ātra*. ⁽⁹⁾ G. M. om. ⁽¹⁰⁾ O. puts before *yathā*. ⁽¹¹⁾ B. omits from here to the middle of rule 15 (beginning again with *saṁyogapūrvam*). ⁽¹²⁾ G. M. O. ins. *tato laghāni*. ⁽¹³⁾ W. *eta*. ⁽¹⁴⁾ G. M. om. ⁽¹⁵⁾ G. M. *jān*. ⁽¹⁶⁾ W. -*pi* 'ti. ⁽¹⁷⁾ W. -*ke*.

अव्यञ्जनान्तं यद्वस्वमसंयोगपरं च यत् ।

अननुस्वारसंयुक्तमेतल्लघु निबोधतै

तल्लघु निबोधत ॥ १५ ॥

15. A syllable that does not end with a consonant, that has a short vowel, and that is not followed by a conjunction of consonants, and one that is not combined with *anusvāra*—know that to be light.

This is a mere negative to the preceding rule, and a wholly superfluous addition to it—and an addition made, we may conjecture, by a different and later hand: the use of the term *anusvāra* distinctly suggests this.

The commentator quotes, by way of example of light syllables, simply *madudayanā asan* (vi.1.5¹: B. O. omit the last word).

CHAPTER XXIII.

CONTENTS: 1–3, causes of the differences of articulated sounds; 4–10, qualities or temperaments of voice; 11–19, tone or pitch of utterance; 20, general mode of correct utterance.

अथ वर्णविशेषोत्पत्तिः ॥ १ ॥

1. Now for the origin of the differences of articulate sounds.

15. 'avyañjanāntam yad aksharam yac ca hrasvam yac 'cā 'saṁyogaparam' yac cā 'nanusvārasaṁyuktam etat sarsam aksharam laghu' nibodhata' jānīdheam. yathā: mad-.... ityādi. vyañjanam ante' yasya tad vyañjanāntam: 'na vyañjanāntam avyañjanāntam: saṁyogah paro yasmāt tat saṁyogaparam: 'na saṁyogaparam' asaṁyogaparam: 'anusvāreṇa saṁyuktam' anusvārasaṁyuktam: 'nā 'nusvārasaṁyuktam' ananusvārasaṁyuktam.

iti tribhāṣhyaratne prātiçākhyavivarane
dvāviṁṣo¹⁶ 'dhyāyah.

⁽¹⁾ G. M. om. ⁽²⁾ W. ca saṁyogapārvaram. ⁽³⁾ W. B. laghū. ⁽⁴⁾ W. om. ⁽⁵⁾ G. M. antam. ⁽⁶⁾ W. om. ⁽⁷⁾ G. M. tadbhinnam. ⁽⁸⁾ O. om.; W. yuktam only. ⁽⁹⁾ B. om.; G. M. anusvārayogavirahitam. ⁽¹⁰⁾ G. M. O. dvitīyapraçne daçamo.

1. athe 'ty ayam adhikārah: varṇānām viçeshotpattir ucyata ity etad adhikṛtam veditavyam ita uttaram yad vakshyāmah. varṇānām viçesho varṇaviçeshah: tasyo 'tpattih sā tatho 'ktā.

It was hardly worth while to give a rule introductory to so very brief a treatment of the subject as is here to follow.

अनुप्रदानात्संस्पर्शस्थानात्करणविन्ययात् ।

जायते वर्णविशेषं परिमाणाच्च पञ्चमाद् इति ॥२॥

2. The differentiation of articulate sounds arises from emission, closure, position, disposition of producing organ, and, fifthly, from quantity.

That is to say, according as any sound is different from another in respect to one or more of these five constituent or determining elements, so its nature or quality is different. The *anuprādāna* is the emitted material, whether tone, breath, or the intermediate *h*-sound (ii.8-10); by *saṁsarga* (a term not elsewhere used) is doubtless intended the degree of approximation of the articulating organs, as contact (*spargana*, ii.33), approach (*upasaṁhāra*, ii.31), and the like (ii.14, 16, 45 etc.); *sthāna*, 'place, position,' and *karana*, 'producing organ,' are the familiar names given respectively to the more passive and the more active of the two parts of the mouth by whose contact or approach the sound receives its articulate character (*vinnyaya*, which the commentator explains by *vinnyāsa* [B. reads this in the rule itself], seems to be added more to make up the verse than for the sake of its meaning); *parimāṇa*, 'measure' (used only here), is synonymous with *kāla*, 'time, quantity' (see i.31-37). The commentator takes *a* as an example, and says of it that its "emitted material" is tone; its "closure," in the throat; its "position," the two jaws; and its "disposition of producing organ," the two lips. Excepting in the first item, this is blundering work: *a* is, of all the alphabetic sounds, the one least easy to try by the tests laid down in this rule; and the commentator would have done well to choose some more manageable illustration.

वर्णप्रकृतः शब्दो वाच उत्पत्तिः ॥३॥

3. Sound combined with articulation is the origin of voice.

The commentator defines *prkta* by *miçra*, 'mixed,' and *utpatti*

2. *anupradānādibhiḥ pañcabhiḥ¹ karaṇāḥ varṇavāḍeṣhyam² jāyate. akārasya tāvad anupradānam nādaḥ: saṁsargah kaṇthe: sthānam hanū: karaṇavinnyaya³ oṣṭhāu: vinnyayo nāma vinnyāsaḥ: parimānam⁴ mātṛakālah; evam sarvavarṇānam boddhavyam. viçeshabhāvo⁵ vāḍeṣhyam: varṇānam vāḍeṣhyam varṇavāḍeṣhyam⁶.*

¹ G. M. om. ² G. M. O. -nānam v. ³ O. -nyāsa. ⁴ W. O. parim-, as also (with T.) in the rule. ⁵ G. M. O. -shasya bh. ⁶ W. O. om.; G. M. tāthā.

3. *prkto miçra ity arthaḥ: varṇamiçraḥ¹ çabdo vāco vākyasyo*

by *upādāna* and *kāraṇa*, 'cause.' This combination denies the quality of voice to the mere "sound" of drums and the like.

सप्त वाच स्थानानि भवन्ति ॥ ३ ॥

4. Of voice, there are seven qualities.

Here is a different and expanded version of the doctrine of three qualities, as laid down above, in rule xxii.11. The following rules give the details. The commentator gives of *sthāna* the lucid definition "those whereby the voice is put to use, and that wherein it stands—that is *sthāna*."

उपाशुधाननिमदोषब्दिमन्मन्दमध्यमताराणि ॥ ५ ॥

5. Namely, inaudible, murmur, whisper, mumbling, soft, middle, and loud.

The rules that follow define the senses in which we are to understand the terms here given. They indicate plainly enough a continual progression, from inaudible and merely mental utterance up to loud and distinct speaking; but it is not easy to find words which shall represent them closely.

करणवदशब्दमनःप्रयोगमुपाशु ॥ ६ ॥

6. "Inaudible" is without sound, without application of mind, but with articulating action.

The commentator explains *karaṇavat* by *prayatnavat*, 'with effort,' and states its object to be to deny absolute silence to the *upāṅgu*. "Without sound" signifies the exceeding littleness of

'tpattir upādānaṁ¹ kāraṇam bhavati. varṇaprākṛta iti kim: duḥ-dubhyādiçabdānāṁ vākyatā² mā bhūd iti.

¹ MSS. -*pa*. ² B. G. M. O. -*na*. ³ B. -*tuam*.

4. '*vacāḥ sapta sthānāni bhavanti:*¹ *tāny uttarasūtre vakshyante. yāir vāk² prayujyate³ yasminç ca tishṭhati tat⁴ sthānam: tāni yathākramam udāharishyāmaḥ.*

¹ G. M. om. ² B. -*kyam*. ³ B. *yuj*-. W. O. add *ze*. ⁴ O. om.

5. *upāṅge iti prathamam vāca sthānam: dhvāna¹ iti dvitīyam: nimada² iti tṛtīyam: evam itarāṇy api nāmataḥ sapṭāi 'tāni sthānāni jānīyāt. uparītanam³ sūtram ārabhya pratyekam eṣhām lakṣaṇam⁴ vakshyate⁵.*

¹ O. -*nam*; G. M. -*naḥ*. ² O. -*dam*. ³ B. O. -*na*. ⁴ G. M. *sthānānām*. ⁵ G. M. *lak*-.

6. *karaṇavat prayatnavat ity arthaḥ: nā 'sti çabdo dhvanir asminn ity¹ açabdam²: manasā prayogo manaprayogaḥ³: nā 'sti*

sound in this mode of utterance. "Without application of mind" excludes any intentional use of *udatta* etc. This last is not very satisfactory; and, indeed, we should as soon expect the contrary term, *manahprayoga*, 'with application of mind,' to be read, as indicating an utterance in which the mind does its full part, though not the voice also (G. M., in fact, read it in the rule).

अन्तरव्यञ्जनानामनुपलब्धिर्धानः ॥ ७ ॥

7. "Murmur" is inaudibleness of syllables and consonants.

The commentator explains *akshara*, 'syllables,' as meaning here 'vowels,' but there seems no need of refusing the word its ordinary signification. Inaudibleness, we are further told, being a characteristic of *upāṅgu* also, it is here again specified in order to teach that there is no actual sound heard. Of what follows, a great part has dropped out in B. G. M., and is much corrupted in the other two manuscripts, so as to be very obscure. The separate mention of syllables and consonants is for the sake of clearness (?), and indicates exceeding inaudibleness: and there is added a comparison with tame and wild cattle, of which I fail to make any sense. Others say that the inaudibleness is of *s*, *h*, and so 'on. All of which is very trivial and unedifying.

उपलब्धिर्निमदः ॥ ८ ॥

8. "Whisper" is their audibleness.

*manahprayogo yasminn' ity amanahprayogam*¹. 'vāca sthānam idr̥cam' *upāṅgu ity upadiṣyate. tatra karanavad iti tūshnimbhāvanirvṛtyartham*²: *aṣadnam iti ṣabdasyā 'tyantālpatārtham*³: *amanahprayogam ity udattādīnām sāmkalpikaprayogapratisiddhārtam*⁴.

¹ W. B. put before *asmin*. ² G. M. -*dah*. ³ W. *manah*; B. -*gah* *stream*; O. *manasah gr-*. ⁴ G. M. O. 'smīn. ⁵ G. M. -*gah*. ⁶ W. *sthānam* *vāca ichvān*. ⁷ G. M. -*thah*. ⁸ G. M. -*thah*. ⁹ G. M. *sāmkalpikapratī-*; B. G. M. -*thah*.

7. *aksharāṇi svarāḥ*: *aksharāṇām vyañjanānām*¹ *cā 'nupalabdhir dhwāno nāma dvitīyam vāca sthānam. upāṅgulakṣaṇe 'py anupalabdhāu satyām punarvacanam*² *aṣadopalabdhividhānārtham*³: *'aksharavyaṅjanānām bhedagrahaṇam*⁴ *abhikhyārtham*⁵: *atyantānupalabdhir*⁶ *ity arthaḥ. ' anye tv' āhuḥ*⁷: *'aksharavyaṅjanānām savisarjanīyādīnām*⁸ *anupalabdhir iti.*

¹ G. M. *svārāṇām*. ² W. B. -*cana*; O. -*canam*. ³ W. B. O. *ṣad-*; G. M. -*rthah*. ⁴ B. G. M. om. ⁵ O. *bhedena gr-*. ⁶ W. *ābhāṣayyayārtham*; O. *ādh-*. ⁷ O. -*ntā-pal-*. ⁸ W. ins. *yāmanyasya paṇor araranyasya pī tūcyam iti*; O. ins. *yathā na grāmyasya paṇor aūte nāranyasādhyetacyam iti*. ⁹ O. om. *tu*. ¹⁰ G. M. *vis-*.

8. *aksharavyaṅjanānām upalabdhir nimado nāma tritīyam vāca sthānam bhavati.*

I have rendered *nimada* by 'whisper' rather at a venture: whether the word accurately represents it or not is at any rate of very small consequence.

• मशब्दमुपब्दिमत् ॥ १ ॥

9. "Mumbling" is the same, with sound.

Ābda would seem to be used here in the sense of *nāda*, 'tone,' if the definition is to be made anything of; the term *upabdimat* is found in the *Tāittiriya-Saṁhitā* (at iii.1.9¹), used in antithesis to *upāṅgu*.

उरसि मन्द्रं कण्ठे मध्यमः शिरसि तारम् ॥ १० ॥

10. "Soft" is in the chest, "middle" in the throat, "loud" in the head.

The South-Indian manuscripts (G. M.) divide this rule into three, and break up the comment into three corresponding parts, without other change. I presume that the treatment of the whole as one rule is more original; the subject joins on, as it were, to rule xxii. 11, and gives the received doctrine as to the mode of production of the three qualities of voice there laid down. And the distinction of the four other qualities by which "soft" shades off into utter inaudibility is a later addition to the doctrine—one of those pieces of useless over-refinement which are thoroughly characteristic of the Hindu mode of working.

The commentator points out that the first four of the seven *sthānas* described in this chapter are used "in sacrifices etc.," and the last three, at the morning, noon, and evening *savanas*, or somalibrations, respectively. And he quotes "from the *Çikshā*" a pair of verses which are found in the *Rik*-version of the *pāṇiniya Çikshā* (verses 36,37; see Weber's *Indische Studien*, iv.363-4), to the effect that "in early morning, one must always read with chest-tone, resembling the growl of the tiger; at noon, with throat-tone,

9. ¹ *akṣharavyañjanānām saçabdam upalabdhir² upabdiman³ nāma caturtham vāca sthānam bhavati⁴.*

¹ G. M. ins. *çabdena saha vartata iti saçabdam*. ² W. O. om.; B. *bdhiman*. ³ B. om. ⁴ W. B. O. om.

10. *yatro 'rasi sthāne prayoga upalabhyate tan mandram nāma¹ vācaḥ pañcamam² sthānam³. yatra kañthe sthāne prayoga upalabhyate tan madhyamam nāma shashṭham vāca sthānam⁴. yatra śirasi sthāne prayoga upalabhyate tat tārām nāma sapṭamam vāca sthānam⁵. eteshv āditaḥ caturtham⁶ yajñādishu prayogaḥ⁷: mandram⁸ prāṭhasavana upayujyate⁹: madhyamam mādhyaṇdine savane¹⁰: tārām tṛtīyasavane. çikshā cāi vañ vakshyati:*

like the warble of the *cakravāka*; the third soma-libation is known as accompanied with loud tone, and this is always to be employed as head-tone, with sound proceeding from the head, and resembling the cries of the peacock, *harisa* and *kokila*."

The Rik Pr. (xiii.17) teaches the same three *sthānas*, but calls the third *uttama* instead of *tāra*. The Vāj. Pr. (i.10,30) lays down their number and their place of production (assigning to the third the *bhrāmadhya*, 'middle of the brows,' instead of *śiras*, 'head'), but gives them no specific names. We cannot well avoid regarding them as involving a difference of pitch, as well as of force or loudness of utterance; the first is low, the third high and shrill, the other intermediate between them, or at the ordinary natural pitch of the voice. They answer to the lower, middle, and upper "registers" of a voice; and our modern musical theory recognizes an analogous distinction of chest-tone and head-tone. Each register, as the following rules go on to explain, is divided into seven tones or pitches.

मन्द्रादिषु त्रिषु स्थानेषु सप्तसप्त यमाः ॥११॥

11. In the three qualities beginning with "soft," there are seven tones each.

As synonym of *yama*, the commentator gives *svara*, doubtless here to be understood as 'musical note, tone of the gamut;' he adds 'acute, and so on,' which might be said blunderingly, as if the word he had just given meant 'accent' instead of 'musical tone,' or also intelligently, as implying the identity of accent with

*prātaḥ pathen*¹⁰ *nityam urasthītena*¹¹
*svareṇa śārdūlarutopamena*¹²;
madhyandine kaṇthagutena cā 'va
cakrāhvasaṅkūjitasannibhena.
*tāraṁ tu vidyāt savanaṁ*¹³ *trītiyaṁ*¹⁴
*śirogataṁ*¹⁵ *tac ca sadā*¹⁶ *prayojyam*;
mayārahāṁsānyabhṛtasvanānām
*tulyena nādena śirasthītena*¹⁷.

¹ B. om. ² G. M. O. put before *vācaḥ*. ³ G. M. ins. *bhavati*. *kaṇthe madhyamam*. ⁴ G. M. ins. *bhavati*. *śirasi tāram*. ⁵ G. M. ins. *bhavati*. ⁶ B. *caturvarṇānām*. ⁷ G. M. *-śū* *pay-*. ⁸ W. *-nam up-*; G. M. *-ne urasi prayo-*. ⁹ B. G. M. om. ¹⁰ W. *ka-*; G. M. *-than*. ¹¹ G. M. *-sthālena*. ¹² G. M. *-rato-*. ¹³ G. M. *-ne*. ¹⁴ G. M. *-ye*. ¹⁵ G. M. *-otthītan*. ¹⁶ G. M. *tathā*. ¹⁷ G. M. *śirogatena*.

11. *trishu mandrādishu sthāneshv ekāikasmint saptasapta yamā bhavanti*: *yamāḥ 'svarāḥ*: *udāttādāya*¹ *iti yāvat*. *saptasapte*² *ti vīpśāyā*³ *ekāikasminn iti labhyate*. *ke te*⁴ *yamā ity āṇākyo*⁵ *'ttarasātreno*⁶ *'ttaram āha*.

¹ G. M. *svarādāya*. ² W. B. *-yāḥ*; O. *-yām*. ³ W. O. *ne*; G. M. O. put before *ke*. ⁴ W. *-tro*.

musical pitch—an identity which is the ground of their common appellation.

The same statement, as to the seven *yamas* or 'tones' in each *sthāna*, 'register' or 'scale,' and the same identification with the *svaras*, are made in the Rik Prāt. (xiii.17). We are to assume, without much question, that the scales pass into one another by a constant ascending series, like the bass and soprano scales in our own system of musical notation.

कृष्टप्रथमद्वितीयतृतीयचतुर्थमन्द्रातिस्वार्याः ॥ १२ ॥

12. Namely *kr̥ṣṭa*, first, second, third, fourth, *mandra*, and *atīsvārya*.

These are not the ordinary names of the seven notes of the Hindu scale, or *svaras* (for which, see Jones "on the Musical Modes of the Hindus," As. Res., vol. iii.; Weber's Indische Studien, viii.259 ff.); but they are, apparently, alternative appellations for the same thing; they are given by Uvaṭa, in his comment on Rik Prāt. xiii.17, as used *sāmasu*, 'in the *sāmans*,' or 'in the *Sāma-Veda*' (Müller's Rik Pr., p. cclxxii.). Uvaṭa calls the first *krushta*, instead of *kr̥ṣṭa*, and the same is the reading of G. M. in our rules and their commentary, as also of T. in rule 14 only (Müller, l. c., p. cclxxiii., marginal note, states *krushta* or *kushta* to be the reading of O. also, but the maker of my collation does not note the fact, except once, under rule 14, in putting in on the margin a passage inserted out of place).

तेषां दीप्तिज्ञोपलब्धिः ॥ १३ ॥

13. Of these, the perception is born of brightness.

I have simply translated the problematical word *diptijā* literally, without claiming to understand what it signifies. The comment throws no light upon it, nor do I get any from any other quarter. The former says merely that the perception of each preceding one is "born from the brightness" of its successor; namely, the per-

12. *kr̥ṣṭaṣ ca¹ prathamāṣ ca² dvitīyaṣ ca tṛtīyaṣ ca caturthaṣ ca mandraṣ ca³ atīsvāryaṣ ca kr̥ṣṭapṛathamadvitīyatṛtīyacaturthamandrātīsvāryāḥ⁴: te tatho 'ktāḥ: 'ete khalu⁵ yamā nāma.*

¹ G. M. *krushtaṣ* (as also in the rule). ² O. om. *ca*. ³ O. om. *ca*. ⁴ B. O. om. ⁵ G. M. O. om. ⁶ B. *kr̥ṣṭādāya*.

13. *teshām¹ khalu saptayamānām² uttarottaradiptijā³ pūrvapāropalabdhiḥ⁴ syāt. tat⁵ katham: atīsvāryadiptijā mandropalabdhiḥ⁶: mandrāc caturthopalabdhiḥ: caturthāt tṛtīyah: tṛtīyād dvitīyah: dvitīyāt prathamah: prathamāt kr̥ṣṭa⁷ upalabhyate.*

¹ W. *diptijopalabdhiḥ*. ² G. M. O. *saptayamānām*. ³ B. *-rād-*; G. M. *-ran d-*. ⁴ O. *pūrvop-*. ⁵ G. M. om. ⁶ W. B. *mantr-*; G. M. *nimadop-*. ⁷ G. M. *krushtaḥ*; O. *kr̥ṣṭah ity*.

ception of *mandra* from that of *atīsvārya*; that of the fourth, from *mandra*; and so on through the series. Perhaps the expression is nothing more than one violently figurative, signifying that each tone receives light from, or is set in its true light by, the rest, or the ones or one nearest it: only, in that case, we should look for some word combined with *dipti* to indicate the source of the light.

Müller (under Rik Prāt. xiii.17, r. deeli.) surmises that the present rule may mean the same thing with the rule of the Rik Prāt. *anantaraç cā 'tra yamo 'vīçeshah*, which he translates 'in these three places (*sthāna*) a *yama* without another *yama* is undistinguishable.' It is very doubtful, however, whether he is justified in rendering *anantara* by 'not having another,' and whether his rule is not rather intended to signify that the three scales pass directly into one another, the first note of the second being equivalent to an eighth of the first, and so on.

द्वितीयप्रथमकृष्टास्त्रय आह्वारकस्वराः ॥ १४ ॥

14. "Second," "first," and *kr̥ṣṭa* are the three tones of the *Āhvārakas*.

This rule makes a *çloka* with the one that follows: which is, of course, a marked indication that both are interpolated here. The same thing may be inferred from the fact that rule 15 teaches nothing which is not found also in 16.

The comment adds nothing whatever to our understanding of the rule.

The *Āhvārakas* are mentioned in the *Caranavyūha* (paragraph 12: see Weber's *Indische Studien*, iii.257) as holders of one *çākhā* of the *Yajur-Veda*.

मन्द्रादयो द्वितीयास्ताश्चत्वारस्तैत्तिरीयकाः ॥ १५ ॥

15. The four beginning with *mandra* and ending with "second" are those of the *Tāittirīyas*.

This second half-verse, as already pointed out, is superfluous in view of the next rule, which treats the same subject, and much more explicitly.

14. *dvitīyaç ca prathamāç ca kr̥ṣṭaç¹ ca te tatho 'ktāh²: ete traya āhvārakasvarāh³ syuh⁴: 'eshām⁵ tair eva prayogo veditavyah⁶. 'āhvārakāṇām svarā⁷ āhvārakasvarāh.*

O. inserts the whole comment out of place, after that to the next rule. ¹ G. M. *kr̥ṣṭa* (as also, with T., in the rule); O. *kush*. ² B. ins. *dvitīyādayah*. ³ W. *-kāsv*; O. *-kard*. ⁴ O. om. ⁵ G. M. *te*. ⁶ B. *-kashṭāsvarāṇām*; G. M. *-kasvarā*.

15. *mandrādayaç catvāro¹ dvitīyāntāh² svarā³ mandracaturthartīyadvitīyās tāittirīyakāh⁴ syuh⁵.*

¹ G. M. O. *-ra svarā*. ² G. M. O. om. ³ O. *teshām tittirīyake prayogo veditavyah*.

द्वितीयान्मन्द्रस्तैत्तिरीयाणां तृतीयचतुर्थीवनन्तरं त-
च्चतुर्थममित्याचक्षते ॥ १६ ॥

16. According to the Tāittirīyas, the *mandra* proceeds from the "second," and the "third" and "fourth" come next after: this they style the tone-quaternion.

The order of the four tones is not made entirely clear by this rule, nor by the commentator's explanation of it. The latter says that "the *mandra* of the Tāittirīyas is born or produced from the 'second';" and, if the expression be used in a manner akin with those under rule 13, this would imply that the *mandra* came first, and the "second" after—which would, of course, accord best with the value of the two names: *mandra* would thus be the lowest of the four *yamas*, as it is the lowest of the three *sthānas*. But the commentator then goes on to say that the series of *yamas* thus "beginning with 'second'" is styled tone-quaternion; and this would imply that the order is second, *mandra*, third, fourth. Yet further, he adds that "second" is *udātta*, *mandra* is *anudātta*, and "third" and "fourth" are *svārīta* and *pracaya*. This makes the impression of a purely formal and unintelligent identification, or a forcing through of a parallelism between the four tones and the four accepted accents (which, however, are in respect to tone only three, since the *pracaya* is "of *udātta* tone," xxi.10), without the slightest regard to the already defined tonic quality of the accents. The comment, in truth, through this whole subject, seems to be written with a very insufficient comprehension of the meaning of the text: see especially the rules that follow.

Our attention is called to the fact that the preceding rule laid down the number of the Tāittirīya *yamas*, the present one undertaking nothing more than to describe their order; and that the intention of the last words of the rule is therefore simply to give a name to the series. I have pointed out above, however, that rules 14 and 15 seem to have been put in by themselves, without any regard to 16.

16. 'tāittirīyānām dvitīyāt khalu mandro jāyate: tadananta-
ram' 'ṛtīyacaturthāu syātām:' etad eva dvitīyādi' svaramaṇḍa-
lam' caturyamam' ity ācakshate. yo 'dvitīyah sa udāttaḥ: 'yo'
mandraḥ so 'anudāttaḥ:' yāu ṛtīyacaturthāu tāu svaritapracayāv
'ity arthaḥ'. anena sūtreṇa pūrvashām¹⁰ eva caturṇām svarāṇām
kramaniyamam kriyate: catuḥsamkhyā tu pūrvasūtreṇādi 'vo'¹¹
'ktā: tasmād atra caturyamam ity etat saṁjñāvidhiparam¹² iti
pratīyate.

(1) B. om. (along with all the rule save the first three words). (2) G. om. (3) W. B. O. -ādih. (4) W. B. -ndanam. (5) G. M. -yam. (6) B. dvitīyo udāttaḥ. (7) G. M. O. om. (8) W. dvitī-. (9) G. M. om. (10) W. sarv.; G. M. O. pūrvoktānām. (11) O. om. eva. (12) W. O. -dhināparam; G. M. -dhānap.

The mention of the Tāittīriyas here, and in this manner, seems to indicate that the Prāṭicākhya does not belong to their school, or concern itself with their *śākhā*; although, perhaps, both stand in an especially near relation to it. See what is said upon this point in the concluding note.

तस्मिन्द्वयमात्रा वृत्तिः ॥ १७ ॥

17. In it, progression is by intervals of two tones.

I have rendered this rule according to what seems to me most likely to be its real meaning—although, at the same time, I do not feel by any means confident that I understand it correctly. If the Tāittīriyas acknowledge only four notes in the scale or octave, it seems natural that they should fix these at wider intervals from one another; and the phraseology of the rule is well enough calculated to express this. The verification or rejection of my version may be left till we shall better comprehend the Hindu musical system, and its modification or adaptation as here presented. I am, at any rate, persuaded that my guess is more likely to be right than either of the two which the commentator ventures. Of these, the first is nothing less than absurd: it makes *tasmin* refer to *anudatta*, although such an antecedent can only have tumbled in out of the clouds, there having been nothing whatever to suggest it in the preceding rules; and renders 'in this *anudatta* there is a being-within of two *yamas*; that is to say, in *anudatta* inheres the quality of *svarita* and also that of *prachaya*!' And, as examples of this wonderful *anudatta*, are quoted *sā nah parshat* (not found in the Tāittīriya-Saṁhitā, but occurs Rig-Veda i.99.1; x.187.1-5; and Atharva-Veda vii.63.1), and *pāry avadatām* (i.7.2²).

The commentator's second guess is so far better than his first that he gives the obviously correct interpretation of *tasmin*, as referring to *caturyama* in the preceding rule; but he makes out the meaning to be that, in this series of *svaras*, two are contained in the interior, or are included between the other two. And he

17. *dvāu ca tāu yamāu ca¹ dviyamāu²: dviyamayor³ antarāvṛttir madhyavṛttis⁴ tasminn⁵ anudatte bhavati: svaritatvam pracayatvam cā⁶ 'nudatte⁷ bhavati⁸ 'ty arthah. yathā: sa....: pary----*

kecid anyathā kathayanti: tasmin⁹ caturyame¹⁰ svaramandale dviyamāntarā¹¹ vṛttih: svaradevayasya¹² madhye cartamānam syāt¹³.

anudatto hṛdi jñeyo mūrdhny udatta udāhṛtaḥ:

svaritaḥ karnamāliyaḥ¹⁴ sarvāṅge¹⁵ pracayaḥ smṛtaḥ.

¹asyā 'yam arthah.² udattānudanūttayor³ ⁴madhye svaritapracayayor⁵ antarāvṛttir bhavati. ⁶tathā kāuhaleyahastavinyāsasamaye 'pi⁷ svaritapracayayor antarāvṛttir upadiṣyate:

cites a verse: "*anudātta* is to be known as in the heart; *udātta* is uttered in the head; *svarita* is at the root of the ears (or of the throat, as G. M. have it); *pracaya* is declared to be in the whole member (or to belong to the whole mouth, W. says);" the meaning of which he states to be that *svarita* and *pracaya* are found between *udātta* and *anudātta*—forgetting that under the previous rule he had assigned them a different position. Further, he says that the interior position of *svarita* and *pracaya* is shown in Kāu-haleya's system of motions of the hand, as appears from the verse "the chief of the digits (i. e. the thumb) points out *udātta* when its apex is applied to the root of the forefinger; when to the last but one (i. e. the ring-finger) and to the middle finger, it points out the *svarita* and the *dhṛta*; when to the little finger, the *anudātta*." This verse occurs in the Rik-version of the *pāṇinīya* Çikshā (as verse 43; see Weber's Indische Studien, iv.365): the commentator does not regard it as a Çikshā verse, but adds yet another which he claims to take from his Çikshā, although it is not found in either version of the known treatise of that name (but compare verse 44, l. c., p. 366): "the little finger, the ring-finger, the middle finger, and the forefinger—these, along with the tip of the thumb, severally point out the grave, circumflex, *dhṛta*, and acute accents." The *pracaya* is here twice called *dhṛta*, and it again, apparently, receives the same name in the last rule of the chapter (unfortunately, I overlooked these passages when commenting on the term *dhṛtapracaya* in rule xviii.3): "sustained" or "continued" is a sufficiently natural substitute for *pracaya*, as appellation of the accent in question.

I do not understand precisely what and how much credit the commentator intends to claim for these two explanations in calling them (in his final remark) *mukhya*: if he means that they are the best among a number which had been suggested and might have been reported, it is so much the worse for the rest.

¹ *udāttam ākhyāti vṛsho 'ṅgulinām*

² *pradeçinīmūlanivishṭamārdhā:*

*upāntamadhye*³ *svaritam dhṛtam ca*

kanishṭhikāyām anudāttam eve

⁴ *ti*.

⁵ *çikshāvacanam api*⁶ *cāi 'vañ vakshyati:*

*kanishṭhikā*⁷ *nāmikā ca*⁸ *madhyamā ca pradeçinī:*

*nicaśvāradhṛtodāttān āṅguṣṭhāgreṇa*⁹ *nirdiçet.*

*mukhyam eve*¹⁰ *vyākhyānadeçayam*¹¹ *etat.*

¹ MSS. om. ² W. O. om. ³ W. B. O. -mor. ⁴ G. M. om.; B. *medhyev*; O. *madhyev*. ⁵ O. om. ⁶ G. M. -iñç. ⁷ W. B. O. ma. ⁸ W. B. O. *dvitry*. ⁹ G. M. *deçyamasya*. ¹⁰ G. M. O. ins. *tathā hi*. ¹¹ G. M. *kantham*. ¹² W. *sarvāsyah*; O. *saydasye*. ¹³ W. om.; B. om. *asya*. ¹⁴ G. M. *udāttānūdāttasvarita*. ¹⁵ W. om. ¹⁶ O. om.; G. M. -*leçye hast*. ¹⁷ O. om.; G. M. *ākhyāti yathā*; *pradeçinīmūla* *udāttam upāntamadhyayor madhye svaritam ca kanishṭhikāyām anudāttam itī*. ¹⁸ W. *atecam*. ¹⁹ O. *çikshā*. ²⁰ O. -*shthā*. ²¹ G. M. *cā 'pi*; O. *cā 'tha*. ²² O. *āṅguṣṭhayena*. ²³ G. M. *evam*. ²⁴ W. O. -*nam dv*.

तामुपदेक्ष्यामः ॥ १८ ॥

18. That progression we will set forth.

The commentator declares *tām* here to bring forward solely the word *ṛttim* from the preceding rule (not that word with its qualifications), and the *ṛtti* aimed at to be the fourfold progression of the *caturyama* taught in rules 16 and 19. This is, of course, forced and unacceptable. I imagine that, on the contrary, in the oral tradition of the *Prāticākhya*, an uttered illustration of the four tones, separated by double intervals and so covering the whole octave, was given—which illustration, of course, could not be set down in the written text.

तच्चतुर्यममित्युक्तम् ॥ १९ ॥

19. That is what is called the quaternion of tones.

This is naturally enough explainable as a winding-up remark, after the exemplification of the four *Tāittirīya* tones notified in the preceding rule has been duly given. To the commentator, it is a mere repetition of what had been already stated above, in rules 15 and 16; and he excuses it as being intended, under the guise of a summing-up, to confirm the view laid down, and repel other opinions inconsistent with it. For, he adds, some people hold the doctrine that there are three *svaras* only, as appears from the half-verse "acute, grave, and circumflex are the three accents." This verse (from the *pāṇiniya* *Çikshā*) was quoted in full above, under rule xxi.1; and W. adds the second half of it here also.

The futility of this exposition, as well as of much that precedes it, will, I think, be obvious to any one. Instead of tracing and pointing out the relation which actually exists between the accents and the *yamas*, and letting us see what musical intervals are re-

18. *yad etad ācāryāḥ caturyamam ity uktam tasya caturbheda-
bhinnā¹ ṛttir² nāma: tām upadekshyāma ity ucyate. ³tām iti
tachabdena⁴ pūrvoktaṛttimātram anukṛshyate⁵.*

¹ G. M. -ām. ² G. M. -ām. ³ W. O. *tānimittāṣabd-*; B. *tām iti labdhena*. ⁴ W. -kathy-.

19. *ity anena prakāreṇa caturyamam ity¹ uktam. yady api
mandrādayo dvitīyāntā (xxiii. 15) ityādisūtradevayena yama-
catuṣṭayateva² siddham tathā³ 'py upasamhāramishena⁴ matān-
taranirṛtyartham⁵ dr̥ḍhayati. yataḥ kāraṇād evam anye man-
yante svaratrayamātram:*

udāttaḥ cā⁶ 'mudāttaḥ ca svaritaḥ ca⁷ svarās trayah⁸:

'hrasvo dirghaḥ pluta iti kālato niyamā aci.⁹

¹ O. om. ² W. *caturyayamacatuṣṭayam pra*; B. *-tayan na*; O. *cat-*. ³ W. -shena; G. M. -hāreṇa mi-. ⁴ G. M. ins. *imam artham*. ⁵ B. O. -ya iti; G. M. *trayasvād iti manyante*. ⁶ in W. only.

garded as separating the different accentual pitches from one another, the commentator simply confuses the two together, and regards as said of the one what has reference only to the other.

क्रमिवक्रमसंपन्नामद्रुतामविलम्बिताम् ।

नीचोच्चस्वारसंपन्नां वदेद्द्रुतवतीः समां

वदेद्द्रुतवतीः समामिति ॥ २० ॥

20. It must be uttered with *krama* and *vikrama*, not hurried, not delayed, with grave, acute, and circumflex accent, with *prācaya*, and even.

The commentator supplies *vṛttim* as the subject of all these attributes, accounting for it as derived from rule 17, above. This is hardly admissible; but what is to be understood instead is doubtful, depending upon the connection in which this verse may have stood in the text from which it was taken. The same connection would perhaps explain what *krama* and *vikrama* are to be regarded as meaning: the commentator defines *krama* by *deitva*, 'duplication' (taught in chapter xiv.), and *vikrama* as the accent of that name prescribed at xix.1.2; but it seems very unlikely that two things so dissimilar would be thus combined, or that a detail of accent would not be put in the second line, with the rest of its kind (compare rule xxiv.6, where *krama* and *vikrama* are found again in conjunction). *Dhṛta* is defined as synonymous with *prācaya*: compare the note to rule 17, above. *Samām* means, we are told, 'free from the faults of deficiency and excess in the matter of *udātta* and the other accents.'

There are slight variations of reading in the rule, T. giving *adhrutām* in *pāda* b; B. *svāra* for *svāra* in c; W. G. M. having *vade* for *vaded*, and W. *drutavatiṇ* and T. *drutav-* after it; but they are mere errors of scribes, as the comment plainly shows.

20. tāṭṭiriyāhvarakamatanirūpakō¹ 'yam ślokaḥ: kramavikramābhyāṁ² sampannām: kramo nāma³ dvitvam⁴: vikramas tu svaritayor madhye yatra nicam⁵ (xix.1) ityuktalakṣaṇaḥ: adrutām atvaritām: avilambitām amandām: nicoccasevārasampannām anudāttodāttasvaritasahitām⁶ dhṛtavatīm pracayavatīm: samām udāttādibhir nyūnādirekādidosharahitām⁷: vaded brūyāt: ⁸ vṛttim⁹ ity arthaḥ: vṛttim iti katham labhyate: tasmin dviyamāntarā vṛttir¹⁰ (xxiii.17) itiprakṛtatvād¹¹ iti brāmah.

iti tribhāṣhyaratne prātiśākhyaavivarāṇe
trayoviṃśo¹² 'dhyāyah.

¹ W. B. -rakam etan nir-; O. -rakamatan nir. ² W. -vikrama. ³ G. M. O. om. ⁴ G. M. dvitvaparyāyah. ⁵ O. -cañ syād. ⁶ B. -ritapracayasanih-. ⁷ B. nyūnādirū-tādī-; O. nyūnādirek-. ⁸ G. M. ins. imām. ⁹ B. om. ¹⁰ O. v. ¹¹ O. -kṛtīv-. ¹² G. M. O. dvitvyapraṇe ekādaśo.

CHAPTER XXIV.

CONTENTS: 1-4, the four *saṁhitās* or texts; 5-6, qualifications of a Veda-reader and teacher.

अथ चतस्रः संहिताः ॥ १ ॥

1. Now for the four texts.

A simple heading to the following rules.

पदसंहितान्नरसंहिता वर्णसंहिताङ्गसंहिता चे-
ति ॥ २ ॥

2. Word-text, syllable-text, letter-text, and member-text, namely.

Here is a very curious and problematical enumeration and designation of *saṁhitās*. The commentator divides up among them the teachings of the *Prāticākhya*. To the "word-text" he assigns chapters v.-ix., xi., xii., and xiii.1-4—that is to say, the great body of rules for the combination of *pada*-text into *saṁhitā*. To the "syllable-text" he assigns chapter x., which has to do chiefly with such euphonic combinations of vowels as make one syllable out of two. With the "letter-text" are concerned chapters xiii. (i. e. except rules 1-4), xiv., and xvi., mainly occupied with the subjects of duplication and of the occurrence in the *Sanhitā* of *n* and *ñ*, otherwise than as these are results of the rules of euphonic combination. And the "member-text" is said to be taught in chapter

1. *athé 'ty ayam adhikārah: catasrah saṁhitā ' ucyanta' ity etad adhikṛtaṁ vedītavayam ita uttarāṁ yad vakshyāmaḥ*.

¹ G. M. ins. *ity*. ² O. om. ³ O. *-yate*.

2. *padākṣharavarṇāṅgācchrayāc' catasrah saṁhitāḥ krameṇa boddhavyāḥ. pañcamādhyāyam 'ārabhyā' navamād ekādaṣa-
dvādaṣāṁ trayodaṣasyā' dāu sūtracatusṭhāyam ca padasaṁhitā.
daṣamo 'ksharasamhitā. trayodaṣacaturdaṣāṁ shodaṣaṣ ca var-
ṇasaṁhitā. 'vyañjanaṁ svarāṅgam (xxi.1) ity eṣhā' ṅga-
saṁhitā. etāc' catasrah saṁhitāḥ. eteṣh anyatra ' vihitāṁ ni-
śiddham' ca kāryam sarvasamhitāsu' kuryāt¹²: yatrā¹¹ 'rsha-
grahanādiko viṣeṣho nā 'sti¹³.*

¹ W. *-gā ayāc*; O. *-gōyāc*. ² W. B. O. *ārabhya ā nav-*; G. M. *ārabhya ānapa-
dāikāda-*; W. O. *-dvādaṣa*. ³ O. *-ā*. ⁴ W. *-daṣa*. ⁵ B. G. M. *ekaviṃśo*. ⁶ G. M. om. ⁷ O. ins. ca. ⁸ G. M. *nishidhyakāṁ*. ⁹ B. *-ā*; G. M. *sarvatra saṁhit-*; O. *saṁhit-*. ¹⁰ G. M. *syāt*. ¹¹ W. B. O. *atrā*. ¹² G. M. *add tatra kuryāt*.

xxi. (rules 1-9), which prescribes of what vowel each consonant shall be regarded as "member" or adjunct, or lays down the rules of syllabication. And it is added that whatever is prescribed or forbidden elsewhere than in [the rules belonging to each of] these is of force in all the different texts, unless there be some special restriction, as by the use of the word *ārsha* (ix.21; x.13) or the like.

It is unnecessary to point out that the *Prāticākhyā* contemplates no such division of its rules and restriction of their application as is here made, and that, unless the distinction of texts laid down in the rule means something different from what the commentator explains it to be, it is trivial and worthless.

नानापदसंधानसंयोगः पदसंक्षितेत्यभिधीयते ॥ ३ ॥

3. Conjunction of independent words by euphonic combination is called word-text.

The commentator first explains *samdhāna* as modifying *saṁyoga* in quality of a locative, and then declares the use of the two equivalent terms to be for the purpose of signifying the exceeding closeness of the combination (if, as I presume to be the case, the reading of B. is here the correct one). And he quotes the rule of Pāṇini (i.4.109) as what "the grammarians" say upon the subject, giving the definition of *samhitā* or combined text. As example of word-text, he gives *agne dudhra gahya kiṅṇila vanya yā ta ishuh* (v.5.9¹: only G. M. have *ishuh*).

This interpretation makes *padasamhitā* signify what we are wont to call *samhitā* simply, in distinction from *padapāṭha*, or *padasamhitā* as usually employed, 'pada-text.'

यथास्वमन्त्रसंक्षितादीनामप्येवम् ॥ ४ ॥

4. And in like manner with the syllable-text and the rest, in accordance with their several names.

The commentator explains *yathāsvam* as signifying 'it goes on without exceeding that which is its own,' and pronounces it a 'distinction of office or use;' thus, namely, the peculiar form of all the other specified texts is to be determined; the combination of inde-

3. *nānābhūtayoh padayoh samdhāne yah saṁyogah sa padasamhite 'ty abhidhīyata ucyata ity arthah. yathā: agne.... ekārthayoh samdhānasamīyogacabdayoh' prayogah samdhānādhi-kyārthah¹. tathā ca vāīyākaraṇāḥ² paṭhanti³: paraḥ saṁnikar-śah samhite 'ti.*

¹ G. M. -yogayoh; O. samīyogesambadhānaḥ. ² W. -nādīkyādītyarthah; G. M. sambandhikārthah; O. sambandhīkthādhārthah. ³ G. M. O. -nā. ⁴ G. M. bhayanti; O. api.

4. *svamsvam¹ anatikramya vartata iti yathāsvam: kriyāviṣe-śhanam² evāi³ 'tat': evam aksharasamhitādinām api yathāsvam⁴*

pendent syllables is syllable-text—and so on. And he quotes three passages from the text, by way of illustration: *athā 'bravīt* (iii.2.11²), *adhishavanam asi* (i.1.5²), and *akṣhṇayā vyāghārayati* (v.2.7³ et al.). Of these, the first is an example of the combination of two separate syllables (vowels) into one syllable, by a rule (2) of the tenth chapter; the second, of the occurrence of *n* after *sh*, by rule xiii.6,7; the third offers (like almost any other pair of words in the *Sanhitā*) cases of the division of consonant-groups, *akṣhṣt-tna-yāc-vyā-* etc. Or, by a different treatment of the successive distinctions, it is said that the combination of two vowels alone is "syllable-text;" that of a vowel and consonant in one word is "letter-text;" that of consonants alone in one word (consonants being "members" or adjuncts of vowels, xxi.1) is "member-text;" anything else than these is "word-text."

It appears from all this that *saṁhitā* is here used nearly in the sense of *saṁdhi*, 'euphonic combination,' and that these four rules have no significance whatever, being a mere bit of outside classification, in which some one has amused himself by indulging.

गुरुत्वं लघुता साम्यः रुस्वदीर्घप्लुतानि च ।
लोपागमविकाराश्च प्रकृतिर्विक्रमः क्रमः ॥
स्वरितोदात्तनीचवः श्वासो नादो ङ्गमेव च ।
एतत्सर्वं तु विज्ञेयं हन्द्वाभाषामधीयता ॥ ५ ॥

5. Heaviness, lightness, evenness; short, long, and protracted quantity; elision, increment, and euphonic alteration; natural state, *vikrama*, *krama*; circumflex, acute, and grave quality; breath, tone, and adjunction—all this must be understood by him who reads the Veda language.

svarāpam nirāpanīyam. nānāksharasamīyogo 'ksharasamhitā: 'nānāvārnasamīyogo varṇasamhitā: nānāṅgasamīyogo 'ṅgasamhitā. 'krameno 'dāharanāni bhaṇāmaḥ: yathā: athā..... adhi..... akṣhṇ..... kevalasvarayorṇ samīyogo 'ksharasamhitā: 'ekapade svaravyañjanasamīyogo varṇasamhitā: ekapade kevalavyañjanasamīyogo 'ṅgasamhitā: anyatra padasamhitā: ity avāntarabhedo vijñeyah.

¹ W. B. svam. ⁽²⁾ G. M. om.; O. om. eva. ³ O. -sva. ⁽⁴⁾ G. M. put also after rule 4 in the text of the *Prāticākhyā*, as if rules 5 and 6. ⁽⁵⁾ O. om. ⁶ W. om.; G. M. *vyāgharāmaḥ.* ⁷ G. M. om. ⁸ B. om.

5. *yad gurutvādyuṣtādaṣavidham etat sarvaṁ chandobhāshām vedarāpām' vācam adhiyatā pathatā vijñeyam. ātha vā chandobhāshām' vedalakṣhaṇam' ity arthaḥ. tuṣabdo 'dhyetṛevya-tiriktanishedhārthaḥ: anena' tu sarvathā vijñeyam ity arthaḥ.*

The commentator explains *vedabhāshām* as meaning either 'voice having the form of Veda,' i. e. the uttered material of the Veda, or (according to another sense of *bhāshā*) 'explanation of the Veda.' The particle *tu* in the last half-verse (which I have omitted in translating, as being a mere expletive or *pādapūrāṇa*), he states to mean that the reader referred to must by all means understand all this, but not any one besides. And he adds at the end that *vijñeya* indicates the peremptoriness of the rule, there being risk of harm in the absence of the required knowledge, as is shown by the verse "a *mantra* deficient in respect to accent or to letters" etc. This is the familiar verse, found in the *pāṇiniya* *Çikshā* (verse 52: see Weber's *Indische Studien*, iv. 367-8), and quoted times innumerable in Hindu works, where the present subject is under consideration: O. alone adds the second *pāda*, "being falsely applied, does not express the intended sense;" the rest is, "it, an uttered thunderbolt, harms the sacrificer, like the word *indragatru* [when used by *Tvashtar*] with false accent."

The rest of the comment is occupied with illustration of the points referred to in the rule, along with now and then a few words of explanation. For "heavy" quality (see xxii. 14) is cited *vashat svāhā* (vii. 3. 12); for "light" (see xxii. 15), *akuruta* (v. 5. 8¹ et al.: W. B. give instead *akurvata* [i. 7. 3² et al.], which is less acceptable, as containing also a heavy syllable). *Sāmya*, 'evenness, sameness,' is defined as implying that, of two elements compared, there is—in respect to place and organ of articulation, quantity, etc.—sameness (so G. M., but B. O. read 'bigness' instead, and W. has 'steadiness'): what is really meant, is obscure; we may compare the use of the adjective *sama* in xxiii. 20. The examples for short, long, and protracted, respectively, are *gamayati* (i. 7. 3⁴ et al.), *vāyāv evā 'sya* (vi. 3. 7⁴), and *astu hīz iti* (vii. 1. 6¹: G. M. omit *iti*). Elision is instanced by *in 'andrāsu* (iv. 1. 8²: see above, v. 12); increment, by *trapuṣ ca me* (iv. 7. 5¹: see above, v. 4); euphonic conversion, by *sam indra no manasa* (i. 4. 44¹: only O. has *manāsa*: a case under vii. 2). To illustrate *prakṛti*, 'original condition,' are given three phrases, *agne dudhra gahya kiñcīla vanya yā te* (v. 5. 9¹: W. B. end with *kiñcīla*, and G. M. with *vanya*; and G. M. O. omit *agne*), *prapā asi* (ii. 5. 12⁴), and *na mi-*

*guruteam yathā: vashat..... laghutā yathā: akuruta. sām-
yam yathā: sthānakaranakālādibhir⁸ anayor asti sthāuryam⁷ iti.
hrasvadirghaputāni ca⁹ yathā: gamayati: vāyāv..... astu
..... lopo yathā: ¹⁰im..... āgamo yathā: trapuṣ..... ¹¹vi-
kāro yathā: sam..... prakṛtir yathā: agne..... prapā.....
na..... ¹²vikramo yathā: voḍhave. kramo nāma dvitvam ¹³
yathā: yad..... ¹⁴yad..... ¹⁵svaritodāttanīcānām bhāvaḥ svari-
todāttanīcatvam: ¹⁶tad yathākramam¹⁷ nirdiṣyate¹⁸: nyañcam:
gām..... avadatām. vivṛte ṣvāsa (ii. 5) ity uktah¹⁹ ṣvāso
yathā: pā..... samvṛte²⁰ kaṇṭhe nādaḥ kriyata (ii. 4) ity*

thamā abhavan (v.3.6²; G. M. omit *na*). Of these, the second is a case under x.13; the third, under x.18; both exhibiting a vowel which irregularly remains *prakṛtyā*, or exempt from alteration. But the particular bearing of the first example on the point of *prakṛti* is more obscure: the phrase is one in which the *samhitā*-reading is (except in respect to accent) the same with the *pada*; and this, probably, is the reason why it is taken. Compare the comment and note to v.2, where this part of the rule now in hand is quoted. For *vikrama* is given the word *vōdhavē* (i.6.2¹ et al.), of which the second syllable has the accent called *vikrama*, by xix. 1. *Krama* is again (as under xxiii.20) defined as 'duplication,' and a phrase is quoted containing a case that calls for duplicated utterance, *yad vāi hotā* (iii.2.9¹; i. e. *yad dvāi*, by xiv.1): O. adds another of like character, *yad venoh* (v.1.1⁴). We are permitted to doubt, however, here as at xxiii.20, whether these terms were intended by the maker of the rule in the sense which the commentator assigns to them. The three accents are instanced, in their order as mentioned, by *nyāncam* (v.5.3²); *gām vā vā tā u tā* (i.7. 2²), and *avadatām* (i.7.2²). Reference is made to rule ii.5 as defining "breath," and as example of breath-sounds, or surd consonants, is cited *pūshā te* (i.1.2²: B. has instead *pāte*, and W. *pārte*, which occurs at iv.7.13⁵). Rule ii.4, again, is referred to as defining "tone" or sonant utterance, and the example is *bhāgadhe bhāgadhāh* (ii.5.6⁶). Finally, *aṅgam*, which I have rendered 'adjunction,' is interpreted as alluding to the subject of syllabication (xix.1 etc.), and a phrase is quoted, *tam matsyah prā bravit* (ii.6. 6¹), which we are to divide *tam-mat-syah-prāb-bra-vit*.

The verses composing this rule are found in a passage prefixed to the proper text of the Rik Prāt. (see Müller's edition, p. viii.).

पदक्रमविशेषज्ञो वर्णक्रमविचक्षणः ।

स्वर्नात्राविभागज्ञो गृहेदाचार्यसंस्तदं

गृहेदाचार्यसंस्तदमिति ॥ ६ ॥

6. He who understands the distinctions of the *pada-krama*, who is versed in the *varṇa-krama*, and knows the divisions of accent and quantity, may go and sit with the teachers.

ukto nādo yathā: bhāg-..... vyañjanañ svarāṅgam (xxi. 1) *ity uktam aṅgam yathā: tam-..... vijñeyatvam*¹¹ *iti*¹² *nitya-vidhiḥ: vipakṣhe bādhat: mantrō hīnaḥ svarato varṇato ve*¹³ *tyādī*¹⁴.

¹ G. M. -*dasvar*. ² O. -*śā*. ³ W. O. -*pāt*; G. M. -*ṇām*. ⁴ W. -*ktā itī nish*. ⁵ G. M. *anend 'dhiyatā*. ⁶ G. M. *sthānakāt*. ⁷ B. O. *sthānulyam*; G. M. *tī sāmyam*. ⁸ G. M. O. om. ⁹ W. ins. *etāt sarvaṁ tu vijñeyam chandobhāvādhiyatā*. ¹⁰ B. om. ¹¹ G. M. ins. *tad*. ¹² in O. only. ¹³ W. *padakr*; O. *tad yathā*. ¹⁴ O. om. ¹⁵ MSS. -*tan*. ¹⁶ W. om. ¹⁷ G. M. O. -*yam*. ¹⁸ G. M. *ita*. ¹⁹ O. *vā*. ²⁰ W. -*dīnā*; B. -*dīnā* *nāma*; O. *mīthyā prayukto nā tam artham āha tyādinām*.

This verse also is prefixed to the Rik Prāt. (Müller, p. viii.).

The commentator gives a merely mechanical explanation of the two terms composing the first half-verse, without telling us what he understands them really to mean. Doubtless the *pada-krama* is that which is commonly known as the "*krama-text*," and for the construction of which the other Prātiçākhyas (Rik Pr. x., xi.; Vāj. Pr. iv. 179-194; Ath. Pr. iv. 101-126) give full directions; and the *varṇa-krama* is the text with duplicated consonants, according to the rules of our fourteenth chapter. The compound *svaramātrāvibhāga* we are taught to treat as a dependent one; we might also be tempted to regard it as copulative, and to understand *vibhāga* in the sense of 'separation' (as in *pada-text* etc.), as in the only other place where it occurs in the treatise (iii. 1). "Going to the assembly of teachers" is interpreted to signify not merely the sitting with them on earth, but the enjoyment with them of the abode of felicity, the *brahmaloka*—it being explained (except in G. M.) that "the teachers" are Vyāsa and his like. Then, *apropos* of this promise of heaven to those versed in the class of subjects of which the Prātiçākhyas treat, the commentator proceeds to quote from various *purāṇas* and kindred works the praises and promises there given to those who teach the Veda.

Thus, from the Garuḍa-purāṇa: "Of all kinds of knowledge, that of the Veda is called highest; hence, he who communicates that wins heaven and final beatitude. As chief of all sciences has been produced the *brahma-science*; hence, he who is devoted to giving it will receive the whole recompense of giving." From the Devī-purāṇa: "To those twice born, the Veda is the chief means

6. 'padānām kramah padakramah': *tasya viçeshah: tam jānāti 'ti padakramaviçeshajñah. varṇānām kramo varṇakramah': tasmin vicakshano nipuṇo varṇakramavicakshanaḥ'. svarāḥ ca 'mātrāḥ ca' svaramātrāḥ: tāsām vibhāgaḥ: tam jānāti 'ti svaramātrāvibhāgajñah'. mātrāḥ abdena kālaviçeshah kaçcid ucyate: so 'pi caturāṇur' ityādishu'. evamvidhaḥ puruṣa ācāryasaṁsādanāḥ gachet: "ācāryā" vyāsādayaḥ¹²: teshām "brahmaloke"¹³ sthānam: "yaḥ ce 'dām"¹⁴ çāstram jānīte so¹⁵ 'py ācāryatvāt teshām sadṛçam¹⁶ brahmalokaṁ gachati¹⁷.*

tathā ca¹⁸ paurāṇikā bhaṇanti¹⁹. gāruḍapurāṇe²⁰:

āhuḥ samastavidyānām vedavidyām anuttamām²¹:

atas taddātūr asty eva lābhah svargāpavargayoḥ.

vidyānām paramā²² vidyā brahmavidyā²³ samīritā:

atas "taddānaçīlaḥ ca"²⁴ sarvaṁ²⁵ dānaphalam labhet²⁶.

devīpurāṇe²⁷:

veda eva dvijātīnām sādhanam "yaçasaḥ phalam"²⁸:

ato²⁹ svādhyayanābhyāsāt³⁰ param brahmā 'dhigachati.

"tam eva çīlayet prājñah çishyebhyas tam pradāpayet:

tadabhyāsopradānābhyām "etat kim nā"³¹ 'dhigachati³¹.

of obtaining good things; hence, by application to the reading of the Veda one attains the highest *brahma*. To that let him who is wise especially devote himself; that let him deliver over to pupils; by application to that and communication of it what is there that one does not attain?" From Yājñavalkya: "Above all sacrifices, and ascetic practices, and pure works, the Veda is the highest means of felicity to the twice-born ones. The Brahman who, not reading the Vedas, expends his labor in other directions—he quickly falls, while living, into the condition of a *Qūdra*, and his posterity with him" (the latter of these two verses, which is not given by W. B., is found in Manu, at ii.168). From the Mahābhārata: "Whoever shall repeat to pupils the religious, sacred Sarasvati, he shall gain a reward equal to that from the giving of land and kine." From the Vishṇudharmottara-purāṇa: "By imparting the Veda, a man attains all the fruits of sacrifices; by imparting an *upaveda*, he shares in the bliss of the Gandharvas." From the Brahma-purāṇa: "That reward cannot be told in a thousand aeons, which, oh sage! one obtains by even a very little teaching of the Veda." And from the Bhaviṣyat-purāṇa: "The sonless obtains sons; the poor becomes rich; but he who is ever devoted to the study of the Veda is dissolved in the highest *brahma*."

Next we are told the characteristic form of the Veda: "The Yajur-Veda is brown-eyed, slim-waisted, big-throated, big-checked, black-footed, dusky, born of the family of Kaśyapa." If there is (as may be the case) real meaning hidden under these apparently senseless epithets, it escapes my discovery.

tathā ca yājñavalkyaḥ :

yajñānām tapasām cāi 'va gubhānām' cāi 'va karmaṇām :
veda eva dvijātīnām nihigreyaśakarah paraḥ.

"yo 'nadhītya" dvijo vedān anyatra kurute gramam :
sa jivann eva gūdrateam āgu gachati sāncayah".

mahābhārata" :

yo brūyāt cā 'pi śishyebhyo" dharmyām brāhmīm sarasvatīm :
prthivigopradānābhyām sa tulyaphalam āpnute.

vishṇudharmottare 'pi" :

vedadānād avāpnōti sarvām yajñaphalam narah :
upavedapradānena gandharvāḥ saha modate.

brahmapurāṇe 'pi" :

na tat" kalpasahasreṇa gaditum" śakyate phalam :
yad vedadānād āpnōti" svalpād" api mahāmate.

bhaviṣyatpurāṇe 'pi" :

aputro labhate putrān adhanō dhanavān bhavet :
sadādhyanayuktas tu "pare brahmaṇi" liyate.

vedasvarūpam ucyate :

yajurvedaḥ piṅgalākṣaḥ kṛṣṇamadhyo bṛhadgalaḥ :
bṛhatkapolāḥ kṛṣṇānūghris" tāmrāḥ kaśyapagotrājaḥ".

Once more, the *vedāṅgas* and *upāṅgas* are rehearsed: the former, in the usual number and with the usual names: the latter, as *anupada*, *anupada* (?), *chandobhāshā*, *mīmāṃsā*, *nyāya*, and *tarka*—the first two of these last are elsewhere called *pratipada* and *anupada* (see Weber's *Indische Studien*, iii.260-261, and the *St. Petersburg Lexicon*).

With this, in W. B., the *Tribhāshyaratna* ends; but G. M. O. have an added passage, the bearing of which is not in all points quite clear to me. It begins with stating that he who reads the Veda thus accompanied by the *āṅgas* and *upāṅgas*, and with knowledge of the characteristic form and family, becomes purified. A verse then follows, in which it appears to be laid down how far the rules of the *Prātiçākhyā* have force: namely, as regards other texts, and passages which are not the subject of *sūtras* and are of human authorship (?). By way of illustration, nine passages are quoted, not one of which is to be found in the *Saṁhitā* proper, although five are from its endings of sections, or the summaries of words with which the divisions of sections (half-centuries, *kandikās*) conclude: they are *pra nakshatrāya devyāya* (G. M. omit *devyāya*, and O. begins *anaksh-*), *sa im mamāda mahi karma kartave* (O. omits *karma*: *Tāittiriya-Brāhmaṇa* ii.5.8⁹; *Rig-Veda* ii.22.1), *mahi-saptadagenā-vasyuvātōh* (from the ending of iv.4.12), *api-sida-mithunṣ ashtāu ca* (from the ending of vi.5.8), and *asminś-tanuvastuhi-pinākam* (from the ending to iv.5.10): in these the rules are said not to hold good; and *sinhe vyāghra uta yā prdākāu* (*Tāittiriya-Brāhmaṇa* ii.7.7¹; *Atharva-Veda* vi.38.1; *Kāthaka* xxxvi.15), *dvādaçā gnishtomasya stotrāni* (O. *stotroni*), *ātmanāparā-nish-pra-çukraçocishā* (from the ending of vi.4.10: G. M. stops at *pra*), and *upmāṣi-posham ekānnaviṇçatiç ca* (ending of i.3.6: G. M. stop at *posham*), in which the rules are said to hold good. So much as this, now, seems clear: that the first two quotations in each class are given as coming from some other Vedic text than the *Tāittiriya-*

vedāṅgāny ucyante:

çikshā kalpo vyākaraṇam niruktam jyotisham tathā:
chandasaṁ¹⁰ lakshanaṁ ce¹¹ ti shod āṅgāni vidur budhāh¹².
anupadam¹³ cā¹⁴ nupadam chandobhāshāsamanvitam:
mīmāṃsānyāyatarkaṁ¹⁵ cā upāṅgāni vidur budhāh¹⁶.
¹⁷*evam sāṅgopāṅgavedasya lakshanaṁ sampūrṇam.¹⁸*

iti tribhāshyaratne prātiçākhyavivarane
çaturviṅço¹⁹ dhyāyah.
iti dvitīyapraçṇaḥ samāptah.

⁽¹⁾ G. M. om. ⁽²⁾ W. B. om. ⁽³⁾ W. B. om. ⁽⁴⁾ O. om. ⁽⁵⁾ O. om. ⁽⁶⁾ O. sd. ⁽⁷⁾ W. caran-. ⁽⁸⁾ O. -nuka. ⁽⁹⁾ G. M. ity ovaḍishma; O. ity āvāḍishma. ⁽¹⁰⁾ O. ins. sthānaḥ. ⁽¹¹⁾ G. M. saṁsadam sthānaḥ ācāryasya saṁsadam. ⁽¹²⁾ W. B. O. -ryah. ⁽¹³⁾ O. ins. ca. ⁽¹⁴⁾ W. -kan; G. M. -ko hi. ⁽¹⁵⁾ B. pada. ⁽¹⁶⁾ B. om. ⁽¹⁷⁾ G. M. sadanaḥ; O. saṁsadam sthāna. ⁽¹⁸⁾ O. gachet. ⁽¹⁹⁾ W. om. ⁽²⁰⁾ W. B. bhavanti; O. vadaṁti. ⁽²¹⁾ B. gar-. ⁽²²⁾ G. M. -de p-. ⁽²³⁾ W. B. -man. ⁽²⁴⁾ G. M. ca parā. ⁽²⁵⁾ W. om. ⁽²⁶⁾ G. M. O. -nato rājan. ⁽²⁷⁾ B. G. M. -rea. ⁽²⁸⁾ W. B. bhavet; O. bhet. ⁽²⁹⁾ O. tathā ca dev-

Sanhitā (I should guess that they would all prove to occur in the Brāhmaṇa or Āraṇyaka), and that the first class are offered as containing cases of combination at variance with the rules of the Prāticākhya, while in the second class these rules are observed throughout. Thus, in the first example, vii.4 would require *naksh-* after *pra*; in the second, v.12 would require *im* 'amāda; in the third, the *s* of *sapta* should be *sh* by vi.2; in the fourth, the *i* of *mithunī* should remain unchanged by x.18; in the fifth, *asmin* is not included among the words which by vi.14 have an increment of *s* before *t*. In the other class, on the contrary, *agnishtomasya* follows vi.2, *nish pra* is by viii.24 and 35 (see the comment to viii.35, where the passage is quoted as illustration), and *ugmasi* by iii.13; the first example has nothing but cases under the general laws of euphony. I conjecture, then, that the *na* in the second line of the introductory verse is to be amended to *ca*; and that we are instructed that the rules of the treatise are followed, outside the Sanhitā proper, only according to the nature of each particular case, or even by arbitrary choice. If there is any definite system according to which the phonetic peculiarities of the Sanhitā are observed or neglected in putting together the endings of sections and other divisions, I, at any rate, have not been at the pains to study it out, and the work belongs rather to an editor of the Sanhitā than to an editor of the Prāticākhya: it seems somewhat strange to find the prolonged *i* of *ugmasi* retained in the ending, while the uncombinable character of the final of *mithunī* is neglected.

There can be little question that the passage here treated is an appendage to the proper text of the Tribhāshyaratna, which, with the Prāticākhya, takes in general (the only exception is at viii.35) no account of the subdivisions of *anuvākas*.

By way of conclusion, the remark is added that the repetition of the final words of the rule indicates the end of the treatise. This is not to be approved, for the repetition is simply that which is made at the end of every chapter, and so shows nothing more than the conclusion of the chapter.

(29) W. yasasā ph.; G. M. *creyasām param*; O. *creyasah param*. (30) G. M. O. *tato*. (31) G. M. *-dhyāyanirātāt*. (32) W. B. om. (33) O. *tat ki yajñā*. (34) O. *cucinām*. (35) W. B. om. (36) O. *nadhiteva*. (37) G. M. O. *-te 'pi*. (38) G. M. *rishyāya*. (39) G. M. O. om. (40) G. M. O. om. (41) W. O. *tulya*. (42) O. *gani*. (43) W. B. *avop*. (44) W. O. *svatmād*. (45) G. M. O. om. (46) O. *parabrahmaṇi*. (47) W. *-pādhrīh*; O. *-shtanāndhī*. (48) G. M. *kāc*. (49) W. *-dānsi*. (50) W. *-dhāh*. (51) O. *-prad*. (52) G. M. *nā*. (53) W. B. O. *-rkaç*. (54) W. *-dhāh*. (55) B. *sāṅgopāṅgavedasavalakṣaṇam*, and put below, after *-varape*; G. M. O. substitute *evam sāṅgopāṅgaṇi vedāṇi gotrasavarūpādijñānena* (G. M. *-di vijñānann*) *aathiyānah pūto bhavati*.

[*yadrchaya*: *granthāntare yathālatvam* (O. *yathā tadev*) *idam śāstram* (G. M. *ina*, *yathāvidhi*) *asūtrīteshu* (O. *sūcakeshu*) *sthāneshu pūrvusheshu na* (O. om.) *varlate*. *tathā hi*: *pra*.....: *sa*.....: *mahi*.....: *āpi*.....: *asmins*.....: *ityādau na* (O. om. *na*) *varlate* (G. *prav*-): *sīṅhe*.....: *dvād*.....: *ātman*.....: *ugmasi*.....: *ityādau tu varlate*. *gachhed doṣṭyasaṁsadanā itī vipśā śāstrasmūptim* (O. *-trapari-sam*-) *dyotayati*. (56) B. *-hcatim*; G. M. O. *deityapragne dvādaç*.

CONCLUDING NOTE.

It seems desirable to present here, at the end of the work, a discussion and exposition of certain points which could not be connectedly or fully treated in the notes upon the rules.

A first important question is that of the relation of the *Prātiçākhyā* to the known text of the Black Yajur-Veda, or to the *Tāittiriya-Saṁhitā*.

In considering this question, it is impossible to separate entirely the *Prātiçākhyā* itself from its commentary. The former does not quote passages in its rules, but defines situations or specifies words, singly or in combination. Sometimes, indeed, either of these virtually amounts to the citation of a passage; but, in the great majority of cases, only the commentator can inform us what are the passages had in view. For example, we may regard *eshtah* (viii.18) as in effect a reference to i.2.11¹ and vi.2.2²; but the words cited in viii.8 (as *abibhar*, *akar*, *punar*, *pitar*) are indefinite in their indications, and it would be impossible to say that any given passage in the *Saṁhitā* in which one of these words occurs either was or was not contemplated by the makers of the rule. I shall therefore present in connection with one another the evidence derivable from the text itself and that from the comment.

There are four words or parts of words specified in the *Prātiçākhyā*-text which are not to be found in the *Tāittiriya-Saṁhitā*: they are *stanutar* (viii.8), *carshan* (xiii.13), *jigivā* (xvi.13), and *jighāsi* (xvi.18). It is very remarkable, however, that each of these is a kind of reflex or varied repetition of another word preceding it in the same rule: thus, we have *sanuta stanutah*, *carman carshan*, *jigivā jigivā*, and *jigāsi jighāsi*. And this, taken in connection with the fact that all of them appear to be in themselves ungenune, never having been found, so far as I am aware, in any Vedic text, and being, at least in part, impossible or highly implausible forms, is sufficient to stamp them as probable corruptions, blundering intrusions into the *Prātiçākhyā*, and of no force to prove that the latter was made for a text that contained them.

The cases are much more numerous in which the commentator declares the *Prātiçākhyā* to have in contemplation phrases not to be found in the *Saṁhitā*. They are nearly all of this kind: in iv. 11, *viçākhe* is declared *pragraha*; now the word is divided in *pada*-text, *vi-çākhe*, and *çākhe* is by itself a *pada* (according to i. 48); and therefore, unless there were some other *çākhe* not a *pragraha* in the *Saṁhitā*, it would be enough to cite *çākhe* alone in the rule; hence, as the citation of *bhāgadhe* (p. *bhāga-dhe*) just before implies that the maker of the rule had in view such a word as *uda-dhe*, whose *dhe* was not *pragraha*, so the citation of *viçākhe* is declared to have in view such a word as *sahasra-çākhe*, not a *pragraha*, "in another text." The phrases thus quoted from outside the *Saṁhitā* by the commentator are as follows: under iv.11, *tas-*

mint sahasraçākhe, ārdhve çastre pratishthite, brahmasāme pratishthite, agnidhrte, and prathamaje; under iv.12, *paçucrapanī* (or *bhūsmacrapanī*); under iv.15, *tam* (or *tām*) *āhuti hwayante* (or *vā-cayati*), *hūti punar* (or *manar*) *jūhoti*, and *huti tasmād vivāh* (or *evāh*); under iv.37, *indrāgnī havāmahe*; under vi.5, *pramatis te devānām*; under xi.3, as beginning of an *anuvāka*, *dhātā devebhyo 'surān*; under xi.16, *gayasphāno 'gnīshu*. All this, in my view, is false and arbitrary interpretation; the Prāticākhya is less careful to limit itself to the *minimum citabile* than the commentator would fain have it, and it quotes, for example, the whole word *çākhe* instead of *-çākhe* alone, simply because *çākhe* occurs as *pragraha* only in that word.* The same implication is appealed to by the commentator under xi.9,15, xii.3, xvi.12 (though without actual citation of phrases), to explain away what would otherwise be inaccuracies in the Prāticākhya; *naḥam pṛavam* is given under xiii.16, in the course of the unjustifiable exposition of that rule; and *brahmāṣṇ*, though found in the Sanhitā, is credited under xv.8 to another *çākha*. I do not regard anything in this whole class of cases as authorizing us to suppose that the Prāticākhya had in view a text including anything not found in the Tāittirīya-Sanhitā.

Next, as to citations made in the commentary as if from the text to which the Prāticākhya relates, but not found in the Sanhitā. And here I have first to report a few phrases which are among those occurring only in the manuscripts that came last to my hands, and which escaped my notice when preparing for my last search through the Sanhitā, so that I have not looked for them (not having had the courage to undertake the long and tedious quest through the Sanhitā a fourth time for so little). They are *achāvakah* (xiv.5), *uccā ratnam ayajanta* (ii.49), *tasmād varāpam* (xx.3), *dārçyañ hi* (xxi.16), *naç cid ati* (xiv.10), *prāçnāti* (xiv.9), and *brhaspati sārāpate* (xiv.10). Respecting several of these, it is doubtful whether they are not mere corruptions of phrases actually found and referred. Then there is *kaviçastah* (xvi.2), instead of which, by an error, I sought and found *kaviçastāh*. There remain, of quotations hunted for but not discovered, the following: *adya vasu vasati 'ti 'ndram eva* (x.10: O. only), *anv enam mātā* (xx.1: Weber refers me for this to Çāṅkh. vi.17.2 [?], Âcval. iii.3; also Âit. Brāh. ii.6), *ahorātre pārçve* (viii.7: only W. and [?]) O.: found in Tāitt. Âr. iii.13.2), *uta çravasā pṛthivīm mītrasya* (v.12: only G. M.), *upārçuty askandāya* (x.9: only G. M.), *caturhotā* (ii.25: Tāitt. Br. ii.2.3²), *brahmāudanam pacati* (x.7: Tāitt. Br. i.1.9³), *yaç chandasām* (xiv.10: O. only), *yā prāci dik* (iv.33: W. B. O.), *varshābhyah* (xiv.16: but I am not certain that I did not satisfy myself with *varshyābhyah* and omit to search for this), *varshyebhīh* (xiv.16: O. only, and it reads *varshebhīh*),

* The quotation of *dhātā rātīh* (xi.3), to be sure, is more out of the way, and only to be explained as irregularly pleonastic, like that of *īyam eva sād yā* (xi.3), into which the commentator, with equal arbitrariness, tries to interpret a very different meaning.

çitikanthâya svâhâ (xiii.11: only G. M.), and *sa nah parshat* (xxiii.17: Rig-V. i.99.1 et al.).

Along with these may properly be reported the few phrases which are quoted by the comment, confessedly or impliedly from outside the text contemplated by the *Prâtigākhyā*. Thus, we have under xviii.1 the beginning and concluding words of the *Tāittiriya-Brāhmaṇa* and the *Tāittiriya-Āraṇyaka* (that is to say, of the latter, the concluding words, *āi 'va tapati*, of the fifth *prapāthaka*, with which, accordingly, to the apprehension of our commentator, the whole treatise appears to have ended); under xxiv.6 are given (by G. M. O.) *deādaçā 'gnishtomasya stotrāni, pra nakshatrāya devyāya, su im mamāda mahi karma kartave* (*Tāitt. Br. ii.5.8⁹* etc.), and *siñhe vyāghra uta yā prākāu* (*Tāitt. Br. ii.7.7¹* etc.); in a quoted verse under xxi.6 is read *ṛtasya dhārshadam* (*Tāitt. Br. i.2.1¹²* etc.); and the comment to xix.3 has *yo 'pām pushpan veda*.

Finally, we note that the comment gives, under xviii.1, a word, *bandhub*, which ought to form the conclusion of the *Sanhitā*, by its own count, but which is lost in the known manuscripts.

In all this, again, there is no satisfactory evidence that the *Sanhitā* of the *Prâtigākhyā* or its commentators was other than the one we know. The missing citations are in part found in a minority of the MSS.; in part, they are perhaps corruptions; in part, they are likely to have been taken by an error of the quoter's recollection from some other *Tāittiriya*-text—and the remainder, if there be a remainder, is too scanty to prove anything.

When we come farther to inquire whether any part of the *Tāittiriya-Sanhitā* as it exists was not before the authors of the *Prâtigākhyā*, we seem to be brought to the same negative result. There are, to be sure, here and there points in the text which the rules do not cover, but we have reason only to wonder that in executing so immense and intricate a task as that undertaken by the *Prâtigākhyā* there should have been so few oversights. These, so far as they have been discovered, have been pointed out in the notes; I recapitulate them here. The word *rakshā* (p. *rakshāh*), at i.4.24, should have been exempted in some way from the operation of rule iii.8, which requires its *ā* to be shortened when separated from the following word. *Devī*, at vi.1.77, is made *pragraha* by the strict letter of rule i.61 (see under i.59), though the passage in which it occurs is not one to which that rule was meant to apply. In the rehearsal of cases of elision or non-elision of initial *a* (chapters xi. and xii.), there are a couple of cases which the commentator is driven into attempting to provide for by forced and false interpretations of the rules (see under i.61 for *ye 'ntarikshe* at iv.5.11², and under xi.3 for *ye oparishu* at i.4.33); and I have noted beside (under xii.8, at the end) only *so agnih* at v.2.3³ as unaccounted for thus far (its companion case, *ārdhvo asthāt*, is read first in an *ukhya*-passage, at iv.2.1⁴, as Prof. Weber has pointed out to me; and *so agnih* may yet find a like solution). And in the enumeration of cases of interior *ñ* (see under xvi.26), two compound words appear to have been overlooked, *svādushaṇṣadam* (iv.6.6²) and *strī-ṣhaṇṣadam* (ii.5.1⁵).

I would repeat here, what I have already said, that my testing of the precise adaptation of the Prāṭicākhya to the Sanhitā is not absolute, since I possess neither an *index verborum* to the latter nor a *pada*-manuscript, and my results will probably admit of rectification in some points—but I trust not to any such extent as should invalidate the general conclusion.

This conclusion is, that the Prāṭicākhya probably contemplates the same text, neither more nor less, as that which constitutes the Tāittiriya-Sanhitā, the only *śākhā* left us (unless the Kāthaka be regarded as another) of the many which formerly represented the Black Yajur-Veda. The name Tāittiriya-Prāṭicākhya, then, is both a convenient and a suitable one to be applied to the treatise.

If, however, this name be understood as implying that the text-book emanates directly from the Tāittiriya school, its propriety is much more questionable. Besides the numerous teachers and "holders of *śākhās*" referred to in the rules, whose names in some cases are related with those of traditional schools of the Black Yajus (see Weber's notes to the Caranavyūha, in his Indische Studien, iii.256 ff.), three schools are mentioned by name, those of the Mīmāṃsakas (v.41), Āhvārakas (xxiii.14), and Tāittiriya (xxiii.15, 16). Now we do not expect the text-book of a school to name that school; its rules are those which apply "here," "with us," and only outsiders need specification; besides, the Tāittiriya are represented as holding a doctrine which is not that of the treatise itself, although it is deemed of consequence enough to be set forth with a detail elsewhere unknown. We are far from fully comprehending as yet the origin, nature, and relations of the "schools" of Vedic study and their accepted texts or *śākhās*, or the causes which have preserved to us so few of the latter, and of the school-treatises or *prāṭicākhyas*; but we must of course assume that there were various degrees of difference among the *śākhās*, and that some were only infinitesimally unlike some others. And it is perhaps possible to point out certain minor points, in which the orthoepical form of the Tāittiriya-text as recorded differs from that to be inferred from the Prāṭicākhya.

Among these points we are not allowed to reckon the retention of *h* before surd gutturals and labials and before sibilants (against ix.2), nor of *n* before palatals (against v.24) and *l* (against v.25), nor the omission of *t* (required by v.33) between *t* and *s*, nor of the various duplications and insertions and aspirations taught in chapter xiv., since these are matters on which we are to expect discordance between theory and practice. Nor would it be safe to make anything of the consistent and emphatic acceptance in the Sanhitā of *anuvāra* as an alphabetic element, while the Prāṭicākhya wavers (see under ii.30) between regarding it as such and as a mere affection of the preceding vowel. Of more consequence is the division of the sections or *anuvākas* in the recorded text into fifties of words, or *kandikās*, which causes the disappearance of more than one specialty of reading expressly prescribed in the treatise (e. g., of the *i* of *uḡmasi*, at the end of i.3.6¹: see under iii.

13). The retention of the final *v* of *av* and *āv* (from *o* and *āu*) before a vowel is also against the letter of rule x.19, and in accordance with a dissident opinion quoted in x.21. The *kampa* of a circumflex accent followed by a circumflex, consistently made in the *Sanhitā*, is only mentioned in the *Prātiśākhya* (at xix.3) as taught by some authorities, nor is the form of the doctrine taught in full and clear accordance with the practice followed. And it is very questionable whether the prescription of nasalization of a final protracted *a* (xv.8) is not merely reported by the treatise as made by certain specified teachers. These are small matters, and few, and a degree of doubt, perhaps, hangs over them all; but they are worthy of notice, as being all that we have on which to found any discordance between the *Sanhitā* of the manuscripts and that of the *Prātiśākhya*. While, on the other hand, the points of accordance, even in matters which are most specially characteristic of the *Tāittiriya*-text, are very numerous and important.*

Of course, the existence of other forms of the text besides the ordinary *saṁhitā* is assumed by the *Prātiśākhya*. Such a work without a *pada*-text at least as its foundation would be a thing inconceivable. Our treatise does not give, as the others do (see add. note 1 to the *Ath. Prāt.*), formal rules for the construction of any of the other texts; its nearest approach to doing so is in the third chapter, where (see note to iii.1) it teaches us what final or initial vowels, long in *saṁhitā*, are to be shortened whenever the word in which they occur is thrown out of *sandhi* with its next neighbor—a form of statement which applies to *krama* and *jaṭā* text as well as *pada*. The occurrence of such terms as *pada*, *nā-nāpada*, *īṅgya*, *avagraha*, implies also the familiar usages of the *pada*-text; and the employment of *iti* is directly alluded to in iv.4 and ix.20, and indirectly assumed in the use of *āraha* in ix.21 and x.13. What were the limits to the use of *iti* in the *pada*-text held by the school from which the *Prātiśākhya* proceeded does not appear: its combination in the extant *pada* with the prepositions (thus *pré 'ti* for *pra*, *vé 'ti* for *vi*, and so on—and without restriction to the ten words which alone are allowed by the *Prātiśākhya*, at i.15, to count as prepositions) does not come to light anywhere either in the text or commentary. Nor does the treatise chance to show whether its *pada* treated the *īṅgyas* or separable compounds after the same manner as the extant *Rik* and *Atharvan* texts—writing simply *upa-āyavaḥ*, for example—or as the extant *padas* of the *Yajur-Veda* (including that to the *Tāittiriya-Saṁhitā*) and the one assumed by the *Atharva-Prātiśākhya* (see note to *Ath. Prāt.* iv.74)—writing *upāyava ity upa-āyavaḥ*. The commentator, however, accepts and follows the latter method. Reason has been

* I have pointed out under rule ii.25 that the peculiar *Tāittiriya* orthography of such words as *suvar*, *tannud*, *aghniyā* finds no occasion for mention in the *Prātiśākhya*; nor is the very strange change of a final labial in certain words to a guttural (as in *trishtug indriye*, ii.4.112; *trishtug yāyā*, ii.6.20; *trishtugbhāh*, v.1.42) noticed anywhere; I presume (I have omitted to obtain distinct information upon the point) that in every such case the *pada*-text also has the guttural—which would take the whole matter out of the sphere of the *Prātiśākhya*.

found (under xx.3) for questioning whether in the *pada*-text belonging to the makers of the Prāṭicākhya the peculiar rule followed by the known Tāittiriya *pada*-text as to the accentuation of its separable words was of force. The latter text is of a very peculiar, not to say an anomalous, character in many respects; in these it is supported by the Prāṭicākhya, so far as the latter goes (I will instance as examples only the treatment of *yojā* and *evā*, and other cases noticed under iii.15, of *nīcāḍ*, v.8, and of *ekāikayā*, v.19): whether it does not contain other peculiarities which are ignored by the Prāṭicākhya, and which consequently prove it not to be the one which this presupposes, I cannot say; but, from an item or two of information received from Prof. Weber, I imagine that it does so. The question will, at any rate, be cleared up by the discussion of the Tāittiriya *pada*-text which Weber, as I rejoice to learn, intends to add to his transliterated edition of the *Sanhitā*, now going through the press.

I attribute it only to a (very unusual) awkwardness of statement on the part of the Prāṭicākhya, that it appears to leave a part of the words ending in an original *o* out of the category of *pragrahas* (see under iv.7), and so to deny them the right to be followed by *iti*, as they are in fact followed in the known *pada*-text.

The *krama*-text ("word-*krama*") appears to be mentioned in rules xxiii.20 and xxiv.5, and more unequivocally in xxiv.6 (all of them, however, of suspicious authenticity as original parts of the Prāṭicākhya: see below); but it is only three times quoted in the comment (under vii.2, ix.17,20), and so makes but a small figure there as compared with the *ajā*. Examples from the latter are given under iii.1, v.33, viii.8,12,16,35, ix.22, x.9,10,13, xi.9,16,17, xii.7, xx.2, and sometimes in considerable number and at great length; and once (under xx.2), where the commentator has occasion to mention the various kinds of text, he specifies *saṁhitā*, *pada*, and *ajā*, ignoring the *krama* altogether. This seems strange, inasmuch as the *ajā* is regarded* as a secondary form of *krama*, and founded upon it; but the simple explanation appears to be that the *krama* brings up no questions of *sandhi* which do not arise also in *saṁhitā* and *pada*, and so needs no special attention where only methods of *sandhi* are taught; while the inversions of the *ajā* bring new elements into contact, and so create new cases of combination which require to be settled. If we may trust the commentator's interpretation, rules viii.12,35 are given expressly for cases that arise only in *ajā*-text; under viii.16, he commits an obviously false explanation in order to reach a *ajā*-case; under v.33, he makes a *sandhi* which the Prāṭicākhya certainly never intended, because it is required by the letter of the rule, in a case which the makers of the treatise had apparently overlooked; under xi.16,17, the *ajā* is resorted to, apparently with reason, for counter-examples to justify the form of statement adopted in the rule. The weight of evidence, upon the whole, is decidedly in favor of

* See Dr. Thibaut's "Jatāpātala," Leipzig, 1870.

the assumption that the peculiar *jaṭā* combinations were had in view by those who constructed the *Prātiśākhya*—or, at least, by those who brought it into its present form. I would add, that it seems to me not unlikely that the term *vikrama* (in the sense of *kramavikṛti*) signifies the *jaṭā*-text in rules xxiii.20 and xxiv.5.

The names of the divisions of the *Sanhitā*, *kāṇḍa*, *pragṇa* (not *prapāthaka*), and *anuvāka*, are found only in the commentary (see Index); respecting the absence of the subdivision of *anuvākas* into *kāṇḍikās* see above, p. 427 (also under viii.35 and xxiv.6, where this division is acknowledged by the commentator). But the *Prātiśākhya* itself gives names to certain parts of the *Sanhitā*; which names, for the sake of convenience, I will put together here, with a reference to the rule under which the part designated by each is stated (for further details of their occurrence, see the Index): they are *agni* (iii.9), *ishti* (iv.52), *ukhya* (ix.20), *graha* (ix.20), *prśthya* (ix.20), *mahāprśthya* (xi.3), *yājyā* (iii.9), *rudra* (xi.3), *vājapeya* (xi.3), *vikarsha* (xi.3), *viharya* (xi.3), and *hiranyavarṇya* (ix.20).

A marked feature of the *Prātiśākhya* is its frequent citation of authorities by name. The list of names has been repeatedly put together by students of the *Prātiśākhya*s (in Weber's *Indische Studien*, iv.77-8, may be found notices respecting the historical and geographical indications derivable from them), but ought not to be omitted here also. It is as follows (including the cases of mention in the commentary, distinguished by an added *c*):

- Āgniveṣya, ix.4.
- Āgniveṣyāyana, xiv.32.
- Atreya, v.31, xvii.8.
- Ukhya, viii.22, x.20, xvi.24.
- Uttamottariya, viii.20.
- Kāṇḍamāyana, ix.1, xv.7.8c.
- Kāṇḍīya, v.38, xviii.3.4c, xix.2; (*sthavira*), v.40c, xvii.4.5c.
- Kāuhaliṣṭha, v.40c, xvii.2; (Kāuhaleya, xix.4c, xxiii.17c).
- Gāutama, v.38.
- Pāuṣkarasādi, v.37, 38, 40c, xiii.16, xiv.2.3c, xvii.6.
- Plākshāyana, ix.6, xiv.11.17, xviii.5.
- Plākṣī, v.38, ix.6, xiv.10, 11c, 17, xviii.5.
- Bādabdhikāra, xiv.13.
- Bhāradvāja, xvii.3; (Bharadvāja, v.40c).
- Mācākīya (or Māyikāya), x.22.
- Vātsapra, x.23.
- Vālmīki, v.36, ix.4, xviii.6.
- Cāṅkhāyana, xv.7.8c.
- Āityāyana, v.40, xvii.1.3c, 4c, 7, xviii.2.
- Sāmkrīya, viii.21, x.21, xvi.16.
- Hārta, xiv.18, 19c, 20c, 21c, 22c.

Of the three schools cited, the names have been already given (above, p. 427). And we have besides *ācāryāḥ* quoted in i.46; *eke ācāryāḥ* in v.30, ix.5, xiii.3, xiv.3.25; *eke* simply in i.47, ii.19, 27.47, v.39, viii.19, xi.19, xiv.33, xv.2.6, xviii.1, xix.3, xxi.13; *pāree* in xv.9; and *sarve* in xviii.7.

The questions which all this array of authorities is called in to help settle may be classified as follows:

- I. Matters of phonetic theory, with others of a general nature.

The nature of the tone of a circumflexed syllable, i.46-7; with this is combined an uncertainty of view of the Prāticākhya itself, expressed in rules 44-5; there is nothing else like it in the treatise; perhaps we may best assume that rules 44-7 are a later intrusion. The mode of production of *anusvāra* and *svarabhakti*, ii.19. The quality of the *a*-element in *āi* and *āu*, ii.27. The phonetic character of *h* and *ḥ*, ii.47-8. The nature of the combination of *e* or *o* with (elided) *a*, xi.19. The occurrence of lingual *l*, xiii.16: this the comment vainly endeavors to make out an accepted doctrine of the Prāticākhya. A denial of the enclitic circumflex, xiv.32-3. Nasalization of final vowels, xv.6-8: the comment treats rule 8 as the direct teaching of the text-book. Accent of protracted vowels (?), xv.9. Correction of the final theme-vowel of neuters in *as*, *iś*, *us* in the nom. pl. before *ñ*, xvi.16. Utterance of *āi* final in a single case, xvi.24. Degrees of nasalization, xvii.1-5. Utterance of accents and alphabetic sounds generally, xvii.6-8. *Kampa* between two circumflex syllables, xix.3-5. Use of the term *yama* for the nasal counterparts, xxi.13. Utterance of the syllable *om*, xviii.1-7. *Yama*-tones held by certain schools, xxiii.14-19.

II. Matters of *sandhi* or euphonic combination.

1. The most important cases in this division are two or three in which the views of different authorities are reported without any clear expression by the treatise of the opinion held, or the rule to be followed, by its school. Thus, with regard to the combination of a final mute with an initial *h*, v.38-41; where, indeed, the view first stated, as that of certain specified teachers, is doubtless to be regarded as that of the Prāticākhya, notwithstanding the equivocal way in which it is put forward. Again, at ix.1, the dropping of final *h* before a sibilant followed by a surd mute must probably in like manner, though referred to the authority of a single teacher, be taken as a binding rule. And it is hard to believe that rule x.19, prescribing the invariable omission of final *v*, was not meant to be modified by x.21. That the treatment of *anusvāra* as a distinct consonantal element is put by xv.2-3 upon certain dissidents, must not be looked at by itself alone; it stands connected with the general equivocal attitude assumed by the Prāticākhya with reference to this vexed question in phonetics (see note to ii.30). Once more, the mode of duplication in groups beginning with *l* as reported in xiv.2-3, with reference to the authorities who teach it, seems to be acknowledged by a later rule (xiv.7) as binding: this interpretation, however, is not free from doubt.

2. In all other cases, the Prāticākhya is liberal enough to record the opinions of respected authorities upon points as to which its own teachings are distinctly opposed to theirs. Thus, as to the treatment of *m* before *y* and *v*, v.30 and xiii.3 (the repeated mention of this shows it to be regarded as a view entitled to the most respectful consideration); the combination of *p* with *ç* and of *n* with *ç* before a consonant, v.36-7; the *sandhi* of *eshtar* with *rāyah*, viii.19-22; the treatment of *h* before an initial consonant, ix.4-6; the utterance or omission of final *y* and *v*, x.20-23; the insertion

of a surd mute between spirant and mute, xiv.10-11; aspiration of a mute before a sibilant, xiv.13; duplication in certain specified cases, xiv.17-22, 25-8 (but the comment treats 28 as the direct prescription of the authors of the treatise); and *vikrama* accent after *pracaya*, xix.2.

Thus it is evident that, while this arraying of discordant opinions is a quite distinctive and a very interesting feature of our *Prāṭiśākhya*, it does not, except to a very limited extent, detract from the character of the latter as a consistent and positive record of the views of a school of Vedic study. Nor is it fairly to be brought into any relation to the peculiar character of the Black Yajur-Veda, as a text of which the constituent parts had been gathered together more miscellaneous, and less fully fused into conformity, than the other Vedic texts. No text could be so definitely constructed, and be made the object of so thorough and systematic study as the setting up of a text-book like the *Prāṭiśākhya* evinces, without assuming an established character, and being as authoritatively handed down and as accurately learned as any Vedic text.

It is by no means improbable that a part of these citations of authorities have been interpolated in the *Prāṭiśākhya* after the latter ceased to be a mere body of practical rules for the guidance of a school, and, in virtue of its thoroughness and comprehensiveness, gained more the character of a phonetic "treatise" on the Black Yajur-Veda, and was used in other schools than that which originated it. The commentator (as will be pointed out below) uses the citations as a cover under which to put upon the treatise certain doctrines which do not properly belong to it; and in other hands it may have undergone a like distortion in other directions.

Accretions of other kinds to the original text of the *Prāṭiśākhya* are plausibly to be presumed in various places. All the metrical rules (namely xvii.8, xxii.14, 15, xxiii.2, 14-15, 20, xxiv.5, 6) are to be set down without much question as unauthentic; they are proved such by their character not less than by their form; and several of them are found in other parts of the *Prāṭiśākhya* literature. We may include in the same category, indeed, with considerable show of reason, the seventeenth and eighteenth chapters, and all that follows the twenty-first, on the score of content alone: a part of their matter is inferior repetition of what had been given before; a part deals with subjects, and in a style, unsuited to a *Prāṭiśākhya*. That there is room at least to suspect the intrusion of rules in other parts of the work has been pointed out here and there in the notes: at this place, I will merely refer to certain rules which are put in strangely out of place, interrupting the natural connection of passages: such are i.25-7, 60, vii.13, 14, xiv.12-3, xv.6-9, xvi.24, xxii.3-8; of these, only vii.13, 14 are indispensable parts of a treatise like the present.

Another notable characteristic of our *Prāṭiśākhya* is its sparing use of technical terms belonging to general grammar, consequent upon its refusal to deal with words or classes of words according to their grammatical character, its laborious definition of its subject-

matter in the Sanhitā by position and surroundings merely. There are but two cases of its departure from this method: namely, its use of *alopa* at xiii.15, and of *saṃkhyāsu* at xvi.25; and in neither one is its success precisely of a character to make us wish it had gone farther in the same direction. This peculiarity renders impossible any profitable comparison of its phraseology with that of other grammatical works.

The general character of the Prāṭicākhya is that of an earnest, sensible, consistent treatise, thoroughly worked out and dealing with its proper task with completeness and accuracy, and confining itself quite strictly to that task. There is no labored feebleness and artificial obscurity, as in parts of the Vājasaneyi-Prāṭicākhya, nor any inclusion of matters pertaining to general grammar, as in the Atharva-Prāṭicākhya. It has its minor inaccuracies and inconsistencies, its obscurities of *anuvṛtti* inseparable from the *sūtra*-style, and its rules that seem to defy interpretation: but these are inconspicuous blemishes; no one of the other works of its class is more thoroughly respectable throughout.

Turning, now, to the more special consideration of the commentary, we have to note, as the most important point, a break of continuity between it and the Prāṭicākhya. The commentator is not the recipient of a certain tradition, that gives him surely and precisely the import of the rules which he has to expound; the text-book has come down to him as something authoritative and sacred, indeed, yet in some points obscure, so that he is in doubt as to what it means; in others imperfect, so that it needs emendation; in others not in accordance with the views held by him and his school respecting the text, so that these have to be interpreted into it.

Thus, in the first place, the instances are frequent in which, to his own interpretation of a rule, he adds a different view held by other interpreters: either without naming them (as under i.19,21, xiii.16, xiv.5,11, xvii.5, xxiii.7), or referring to one of his special sources and predecessors (as under ii.19,33), or setting off against one another the views of two of these, Vararuci and Māhishēya (as under ii.14, iv.40, viii.19,20,22, xviii.7). In a large proportion of the instances, it is true, the difference of opinion is upon some utterly trivial point, turning on the interpretation of a *tu* or the like, and only illustrating the hair-splitting tendencies of the native exegetes; but in some cases it is of more consequence, and once goes so far as to question (under viii.20) whether an authority referred to is Uttamottariya or Dvāvuttamottariya. Again, where a rule is really obscure, the commentator has sometimes, palpably, nothing more than guesses to give at its meaning, and ventures two or three of them (as under ii.2, xiv.22, xv.9, xix.5, xxiii.17), among which it would be hard to choose the least acceptable; or, if he gives but one (as under xi.19, xviii.4, xxiii.18,19), it is no less unsatisfactory. There are yet other cases in which what seems to be the evident meaning of a rule is misapprehended and distorted,

without reason (as under ii.52, iv.4, v.29, vii.11, xix.3). Occasionally, false interpretations, of every degree of violence, are committed, for the purpose either of correcting an oversight or inaccuracy of the *Prāṭiśākhya* (as under i.61, iii.1, viii.16, xi.3, xvi.26), or else of imposing upon the latter a doctrine which it was not intended to teach, but which is held by the commentator and his school (as under i.58, xiii.4, xxi.14, 16). For this last purpose, too, advantage is sometimes taken of the citations of varying opinions so liberally made in the rules; the *dictum* of the quoted authority is declared to be approved in usage, or is even imposed upon the *Prāṭiśākhya*, to the setting aside of what the latter really prescribes. Thus, Pāuṣkaraśādi's doctrine of the conversion of *l* to *d* (xiii.16), which belongs neither to the *Prāṭiśākhya* nor to the *Sanhitā*, is accepted; and the duplication of consonant-groups beginning with *l* which is ascribed (xiv.3) to certain unspecified teachers; and Plākṣhi's mode of treatment of a spirant before a first mute (xiv.17), which has as further result a misinterpretation of xxi.16; and a part of rule xiv.26, respecting the duplication of *l*; and rule xiv.28, to which a strange interpretation is given, prepared for by a yet stranger one of xiii.4; and rules xv.2, 3, which require *anusvāra* instead of nasalization of a vowel; and the nasalization of a final protracted *a* (xv.8); and two rules (xviii.1, 6) from among those which concern the utterance of *om*; and rule x.21, as to the retention of final *e*, is given the preference over 19, which requires its omission; and the first rule (v.38) as to the combination of initial *h* with a preceding mute is ratified; and, in the variety of opinions respecting the circumflex tone, one (i.46) is selected for approval. In the few cases where the commentator does not express himself as to whether a rule is *ishṭa* or *anishṭa* (they are ii.19, 27, 47-8, xi.19, xix.2, xxi.13, xxiii.14-9), there may be question whether he means to have it regarded as approved, or thinks the matter of no consequence either way. There remain the majority of cases, in which he stands by the *Prāṭiśākhya*, rejecting the intruded doctrine (for further details, refer to the words *ishṭa* and *anishṭa* in the Sanskrit index).

Besides these more serious cases of misapprehension or intended modification of the teachings of his text-book, the commentator is not free from the ordinary and characteristic weaknesses of his craft in India: from feeble and puerile expositions, from attempts to find a wonderful pregnancy of meaning in some innocent particle or unintended difference of expression, from groundless etymologies, and the like; to these attention has been directed in the notes, and they are not of consequence enough to be recapitulated here.

For determining the personality of the commentator we have no data whatever, and for his place and period we have only the references to other authorities, which, though too few and indefinite to yield any statable result, need to be put together in this note. The three earlier commentators on whom the work is avowedly founded—namely, Vararuci, Māhishēya, and Ātreya—are repeatedly appealed to, especially (as has been pointed out above)

in the settlement of difficult or controverted points (for the details, see index). Vararuci is a name very common in grammatical literature; to identify our commentator with any other of the various individuals who have worn it would doubtless be daring in the extreme. Nor does Ātreya, probably, stand in any definable relation to the grammarian of that name who is (see p. 430) twice quoted in the Prāticākhya itself. From Pāṇini, rules are directly quoted under ii.12, iii.9, v.1, xiii.16, xiv.4, xxiv.3; and the *pāṇinīyāh* or the *vyākaraṇa* are farther referred to under i.15, 53, 57, ii.47, xviii.1. Pāṇinean terms are, further, *nañ*, i.60, x.22, *nic*, ii.17, *hal*, ix.24, *yar*, xiv.4, and *lyap*, xxi.14. The Mahābhāṣhyā is professedly quoted under ii.7, v.2; but the passage given is actually from Kāiyyata's gloss. A definition is taken from the Amarakoṣa under i.1. Kāuhaleya is quoted under xix.4, xxiii.17; and the Kālanirnaya under xviii.1. The Brāhmaṇa of the Vājasaneyins is referred to under xiv.33, and extracts from the Mahābhārata and various Purāṇas are set forth under xxiv.6.

But the authority most often appealed to is the "Çikshā," by which the commentator intends a very different work from the *pāṇinīya* Çikshā, and one much more comprehensive. He takes extracts from it, of a verse, or part of a verse, or more than one verse, under i.1 (three times), ii.2, xiv.5, 28, xix.3, xx.12, xxi.1, 15, xxii.13, xxiii.10, 17. Among these extracts are (under i.1, ii.2, xxi.1, xxiii.10) several passages which are found also in the *pāṇinīya* Çikshā; and among the metrical extracts which are now and then given without specifying their source (under xiv.23, 26, 28, xix.3, xxi.1, 6, 15, xxiii.17, 19, xxiv.6) are likewise one or two (under xxiii.17, 19) which occur in the same treatise. That the commentator is inclined to regard his Çikshā as of higher authority than the Prāticākhya itself was pointed out under xx.12; that it was a work specially appertaining to the Tāittirīya-Saṃhitā may be inferred with probability from the words which it cites (under xxi.15) in illustration of the varieties of *svarabhakti*.

ANALYSIS.

I. EXPLANATORY: TERMS AND THEIR USE, INTERPRETATION OF RULES, ETC.

1. *Terms and their use:*

kāra forms names of letters, xxii.4; of vowels, i.16; of consonants, i.17; exceptions, i.18.—*varga* forms names of letters, xxii.4; includes short, long, and protracted vowels, i.20.—*epha* forms name of *r*, i.19.—*varga*, with first mute, forms name of series, i.27.—*a* forms name of consonant, i.21; of a cited word, i.22.—*aprkta*, a *pada* of a single letter, i.54.—*avagraha*, first member of a separable word, i.49.—*lopa*, loss, i.57.—*upasarga*, 'preposition,' includes what words, i.15.—offices of *ca*, *api*, *tu*, *atha*, *eva*, *vā*, *na*, xxii.5-8.

2. *Interpretation of rules and forms, etc.:*

an increment, or word having euphonic change or elision, put in nominative, i.23; or in its text-form, i.24.—product of euphonic change put in accusative, i.28.—next element, or more, taken in case of doubt, i.25, 26.—a cited *pada* means that *pada* only, i.50; but applies to it even when euphonicly altered, or preceded by *a* or *aa*, i.51-3.—rules for a specified passage apply only there, and peremptorily, i.59; but a series of three or more words, if repeated, reads as the first time, i.61.—*pūrva*, 'preceding,' and *uttara*, 'following,' designate a word only under the specified circumstances, i.29, 30.—continued implication is of what stood last, i.58.—words to be combined, and rules to be applied, in their order, v.3.—a separable word treated as two words, except in enumeration, i.48.—an *aprkta* treated as initial and as final, i.55.—elision and euphonic alteration affect single letters only, i.56; after elision of *y* or *v*, no farther combination made, x.25.—in *pragrahas*, and in enumeration of words containing *auśvedra* a cause in another word maintains its force, i.60.

II. PHONETIC: ENUMERATION, CLASSIFICATION, DESCRIPTION OF ALPHABETIC SOUNDS, QUANTITY, ACCENT, ETC.

1. *Enumeration and classification of alphabetic sounds:*

nine simple vowels [a, ā, ă, ī, î, ȳ, ū, ūs], i.2; sixteen vowels [the above, with *ṛ*, *ṝ*, *ṛ̆*, *ṛ̈*, *ṛ̌*, *ṛ̍*, *ṛ̎*, *ṛ̏*], i.5; the rest consonants, i.6.—mutes, i.7; in five series, i.10; called "first" etc., i.11.—semivowels [*y*, *r*, *l*, *v*], i.8.—spirants [*ç*, *ś*, *h*, *s*, *ṣ*, *h*], i.9.—surd consonants, i.12; *h*, i.13; sonants, i.14.

2. *Mode of formation of alphabetic sounds:*

general mode of production of articulate sounds, ii.2, 3, 7, xvii.7, 8, xxii.1, 2, xxiii.2, 3.—difference of surds, sonants, and *h*, ii.4-6.—mode of utterance of vowels, in general ii.4, 8, 31, 32; in particular, of *a*, ii.12; of *ī*, *î*, ii.20-22; of *u*, *ū*, ii.20, 24, 25; of *ṛ*, *ṝ*, *ṛ̆*, *ṛ̈*, ii.18; of *e*, ii.15-17, 23; of *ai*, ii.26-8; of *o*, ii.13, 14; of *au*, ii.26, 27, 29.—similar vowels, i.3, 4.—mode of utterance of consonants, in general, ii.33, 34; of sonants, ii.8; of surds, ii.10, 11; of *h* and sonant aspirates, ii.6, 9; of nasality, ii.52; difference of nasal quality in different nasal sounds, xvii.1-4; of nasal mutes, ii.30.—mode of utterance of consonants in particular: of *k*-series, ii.35; of *c*-series, ii.36; of *t*-series, ii.37; of *ṭ*-series, ii.38; of *p*-series, ii.39; of *y*, ii.40; of *r*, ii.41; of *l*, ii.42; of *v*, ii.43; of *ś*, *j*,

rants, ii.44,45; of *h*, ii.6,9,46,47; of *visarjaniya*, ii.46,48; of *anusvāra*, ii.19, 30; of *nāsikyas* (*yamas* etc.), ii.49-51; of *svarabhakti*, ii.19.

3. Quantity:

quantity of short and long vowels, i.31-3,35; of protracted vowels, i.36; of consonants, i.37; of *anusvāra* (or nasalized vowel), i.34, xvii.5; of syllables ("heavy" and "light"), xxii.14,15; of pauses and hiatus, xxii.13; of *om*, xviii.1.

4. Accent:

general character of accents: acute, i.38, xxii.9; grave, i.39, xxii.10; circumflex, i.40-47, xvii.6.—varieties of independent circumflex: *nīṭya* or original, xx.2; its quality, xx.9: *kṣhāḍipra*, xx.1; its occurrence, x.16; its quality, xx.9: *abhinihata*, xx.4; its occurrence, xii.9; its quality, xx.10: *prāṇishṭa*, xx.5; its occurrence, x.17; its quality, xx.11.—enclitic circumflex: its occurrence, xiv.29-33; its varieties: *prātihata*, xx.3; its quality, xx.11: *pādavṛtta*, xx.6; its quality, xx.12: *tārocyāñjana*, xx.7; its quality, xx.12.—*pracaya* accent, xxi.10,11.—*vikrama*, xix.1,2; its quality, xvii.6.—*kampa*, between two circumflexes, xix.3-5.—accent resulting from combination of two syllables into one, x.10,12,16,17, xii.9-11.—accent of *om*, xviii.2,3,5-7.—accent of protracted vowel (?), xv.9.

5. Syllabication:

division of syllables, xxi.1-9.

6. Mode and tones of utterance:

general mode of utterance, xxiii.20; the three *sthānas* or qualities, xxii.11; the seven do., xxiii.4-10; the twenty-one *yamas* or tones, xxii.12, xxiii.11-19.—tone of *om*, xviii.4.

III. SANDHI OR EUPHONIC COMBINATION:

introductory, v.1-3; four kinds of combination, xxiv.1-4.

1. Final vowels:

final vowels not liable to combination, *pragrahas*, iv.1-54, x.24; special cases of uncombinable finals, x.13,18; protracted finals, x.24; their nasalization, xv.7,8.—nasalization of final vowels, xv.6.—the particle *u*, ix.16,17.—lengthening of final *a*, iii.2-6,8-12; of final *i* and *u*, iii.7,13,14.

combination of simple final vowels: with similar initial, x.2; of final *a* with initial vowels, x.4-9; exceptions, x.13; lost in certain cases before *e* or *o*, x.14; *i*, *i*, *u*, final, x.15, ix.17; exceptions, ix.16, x.18.—combination of final diphthongs, ix.11,12,14,15; *e* and *o* with initial *a* (see also Initial vowels), ix.13; treatment of the resulting *y* and *v*, x.19-23; after their loss, no further combination, x.25.

accent resulting from combinations of final vowels, x.10,12,16,17, xx.1,5,9,11; resulting nasalization, x.11.

2. Initial vowels:

initial vowel lengthened, iii.15.—loss of *a* after final *e* or *o*, ix.13, xi.1; detail of cases of loss, and exceptions, xi.2-19, xii.1-8; resulting accent, xii.9-11, xx.4,10—*r* to *ar* in special case, v.9.

3. *Final consonants:*

surd to nasal before nasal, viii.2; to sonant before all other sonant letters, viii.3; and, in a special case, before *m*, viii.4; to aspirate before spirant, xiv.12,13.

visarjaniya to spirant before surda, ix.2-6; except before *ksh*, ix.3; to *sh* before *t*, in certain cases, vi.5.—omitted before spirant and surd mute, ix.1; also in *sa* etc., v.15-17; also before *r*, viii.7,16,17; special case before *r*, viii.18-22.—changed to *r*, viii.6; do. after *a* and *d*, viii.8-15; exceptional cases, v.10.—changed to *s* or *sh* before *k*, *kh*, *p*, in compound words, viii.23; do. in independent words, viii.24-35; exceptions, viii.32,33.—*ah* final to *o*, before *a* and sonants, ix.7,8; special exception, viii.18-22; before other vowels, ix.10; *ah* final, ix.9,10.

final mutes: *ś* doubled before vowel, ix.18; *ś* before *s*, *sh*, v.32.—*t* before *s*, *sh*, v.33.—*t* before palatals, v.22,23; before *l*, v.25; before *ç*, v.22.—*n* before palatals, v.20,21,24,37, xv.1-3; before *t*, vi.14, xv.1-3; before *l*, v.25,26, 31, xv.1-3; before *ç*, v.24; before *s*, *sh*, v.33; changed to *r* or *y* [i. e. to *anusvāra*, xv.1-3] ix.20-24; doubled before vowel, ix.19.—*m* before mutes and semivowels, v.27-31, xiii.3; before spirants and *r*, xiii.1,2, xv.1-3; unchanged before *rā*, xiii.4; special case of loss, v.18.

4. *Initial consonants:*

ç to *ch*, v.34-7.—*s* to *sh*, in words independent or compound, v.10, vi.1,2,4,6-13.—*t* to *ç*, vii.13.—*h* after a mute, v.38-41.—*n* to *ṇ*, vii.2,4.
elision of initial *m*, v.12; of *v*, v.13; of *s*, v.14.

5. *Interior consonants:*

t, *th* to *ç*, *th*, vii.13,14.—*n* to *ṇ*, in same word with its cause, xiii.6-9,11,13-15; in other word, vii.3,5,6-12,15,16.—*s* to *sh*, vi.3.—*t* to *ç*, xiii.16.

6. *Abnormal insertions and elisions. duplication, etc.:*

insertion of *s*, v.4-7; of *d*, v.8; of surd mute between sibilant and mute, xiv.9-11; of nasal counterparts (*yamas* and *nāsikya*), xxi.12-14; of *svarabhakti*, xxi.15-16.

elision of initial *m*, *v*, *s*, see Initial consonants.—in composition of forms of *eka*, v.18,19.

duplication in consonant-groups, xiv.1-7,14-28; of initial *ch*, *kh*, *bh* in certain cases, xiv.8.

IV. SUNDRIES:

enumeration and specification of cases of *ṇ*, otherwise than euphonic, in interior of words, xiii.9,10,12; of *anusvāra*, do. do., xv.4,5, xxvi.2-31.
requirements in a scholar or teacher, xxiv.5,6.

INDEX OF CITATIONS

MADE IN THE COMMENTARY, FROM THE TĀITTIRĪYA-SAMHITĀ.

THIS INDEX contains the references reported above in the body of the work, as made by the commentator to the fundamental text. If, however, a cited word or passage is reported as occurring more than once in the text, reference is given only to the first occurrence. It has been found impracticable to carry out any scheme of distinction of the value of the citations; and any one using the Index will have to turn back to the notes in order to determine whether a given passage is quoted merely as an example of some general class, or as one that was more or less probably had directly in view, as example or counter-example, by the makers of the treatise; whether it is a unique phrase, or one more than once repeated, or even a word of frequent occurrence—and so on.

TS. I.	TS. I.	TS. I.
1.1 1.21.33, 11.22, 111.1.3, ix.1, x.5, 10.19, xiv.21, xvii.7, xviii.1.7, xx.3, xxi.7, xxii.13.	2.12 1 xi.11.17; 2 xvi.27.	4.14 11.44, ix.4.
2 1 xiii.2, xv.1, xxi.15; 2 x.2, xxiv.5.	13 1 iii.2, iv.34; 2 iii.7, iv.15.22.33, xvi.2; 3 iv.46, xi.17.	16 xvi.13.
3 1 iv.6, viii.8, xvi.27.	14 1 iii.8, ix.20.23, xii.7, xvi.15.27; 2 1.48, 11.47, iv.28, v.8, vi.5, viii.24, x.16, xiii.15, xiv.6, xvi.13; 3 1.56, v.15; 4 v.17, vii.10, xvi.14; 5 xiv.10, xvi.13; 6 viii.8; 7 iii.8; 8 vii.11, xi.4, xvi.2; 9 vi.2, viii.24, xvi.25.	18 1 iv.41, xi.16.
4 1 viii.8.	3.1 1.61.	19 1 vi.7, ix.20.
5 1 iv.44, ix.22, x.25, xi.16; 2 vi.11, xiii.7, xxiv.4.	2 1 vii.11; 2 iv.12, vii.11, xiv.28.	20 1 xv.1, xvii.4.
7 1 x.10.	3 1.51.60, 111.1, vii.6 <i>ter</i> .	22 1 iii.12, iv.4.12, xvi.13.29.
8 1 vi.5, x.2.6, xi.8.16, xiv.1.	4 1 viii.26; xi.13.16.	24 1 vi.5, xi.13.
9 1 vi.10, vii.14; 2 iii.15, v.2.21, x.12 <i>bis</i> , xi.16, xiv.12.13.	5 1 xiv.26.	25 1 xiii.9.
10 1 vi.5, vii.14, xiv.10, xvi.2.27; 2 v.3, vi.4, xi.16; 3 ii.48, vii.13, ix.2, xvi.14.	6 1 iv.42; 2 iii.13; 3 i.33, x.10; end'g xxiv.6.	26 1 iv.42.
11 1 xiii.6.	7 1 iii.8, iv.11.47, viii.16; 2 viii.9, xi.16.	27 1 vi.7, viii.27.
12 1 iii.3, v.5, viii.8, xi.17, xiv.19.	8 1 iii.8; 2 iii.2, ix.22.	30 1 iv.11.
13 1 11.20, ix.22 <i>bis</i> ; 2 xiii.10 <i>bis</i> , xvi.26; 3 iv.12, ix.9, xii.8, xxi.12.	9 1 1.37, v.38 <i>bis</i> , viii.2, xiv.12.20 <i>bis</i> , xxi.3.	33 1.55, 111.14, vi.5, xi.3.
14 1.61, 111.8.9.10; 2 viii.23, xi.3, xii.7; 3 1.61, xi.3, 9, xiii.16; 4 iii.12, v.17, vi.5 <i>bis</i> , vii.5.10, ix.22, x.10.25, xiii.3.	10 1 xi.17; 2 xiii.14, xvi.23.	36 1 viii.32.
2.1 1 ix.10, x.19.22.25, xi.8, xviii.7; 2 xi.18.	11 1 xi.17.	41 11.49, xiv.24.
2 1 iv.47, xiv.9; 2 iv.42; 3 xxi.3; 4 vi.12, x.2, 17.	12 1 ix.21, xi.18.	42 1 vi.16, ix.20.
3 1 xi.13 <i>bis</i> ; 3 iii.5, xi.8.	13 1 2 v.13; 2 iv.20, viii.9.	43 1.61, xi.9; 2 xvi.26.
4 1 xi.3, xxi.3; 2 xi.3.	14 1.61, 111.12, ix.23, xiv.23, xvi.17, xx.12; 2 iii.10; 3 vii.12; 4 x.15, xii.7; 5 1.61; 6 vii.9, viii.28.34, xii.5; 7 iii.5; 8 iv.6, xvi.14; 9 viii.31, ix.22.	44 1 vi.2, xi.3, xii.5.7, xiii.4, xxiv.5; 2 viii.3, ix.22, xii.7, xvi.13 <i>bis</i> .
5 1 xiv.29; xx.1.7.	4.1 1 iii.5, ix.20, xiii.15; 2 iv.38, vi.13.	45 1 iii.2, vi.5; 2 viii.24, xiii.12, xxi.4; 3 ix.21, xi.7, xv.4.
6 1 xi.10.17, xiii.10, xvi.29, xxi.6.	2 1 viii.27.	46 1 xii.8, xiv.30.31, xx.3; 2 xiii.15.
7 1 iii.5, iv.9 <i>bis</i> , xiv.28.	3 1 viii.10.	5.1 1 v.28.30, xiv.23, xvii.2; 2 ix.19, x.10.13; 3 v.28.30, xx.7.
8 1 ix.21.22, x.10, xi.16.17; 2 1.56, v.10.	4 1 x.10.	2 1 ix.20, xiv.23; 3 iv.16; 4 iv.15; 5 x.10.
9 1 iii.2, viii.27.28.	9 1 v.27, xxi.12.	3 1 ii.48; 2 xiv.18; 3 iii.8, ix.22.
10 1 iii.8, ix.21; 2 iv.52.	10 1 iv.42, vi.4.	4 2 xx.8; 3 v.28.31, xiv.28.
11 1 viii.8.18-22.29, x.14, xvi.29; 2 xi.16.	11 1 xi.16, xvi.25.	5 1.33, xi.3 <i>bis</i> , xiv.9.19, 27; 2 xii.13; 3 iii.4.

TS. I.

- 5.10 ¹iv.17,38,42, ²xl.13,14,
xx.8; ³xl.16; ⁴xl.
16; ⁵ix.22, xl.12; ⁶ix.
22
11 ¹viii.33, xvi.2,19; ²iii.2,
xiii.14; ³iii.14; ⁴iii.
10.
6.1 ¹ii.25.
2 ¹xi.11,17, xiv.32, xix.1,
xxiv.5; ²xi.16; ³xvi.
13.
3 ¹ix.21, xi.3, xiv.28;
²xvi.19.
5 ¹vi.14, xi.16; ²iii.7.
6 ¹xi.11; ²ix.21 *quater*,
22, xi.16.
7 ¹iv.36, xxi.6; ²v.13, x.
16, xiv.11; ³xi.16.
8 ¹xxi.15; ²iv.49, v.18;
³vii.3,11.
10 ¹iii.7; ²xvi.15; ³v.27,
xiii.3, xviii.1; ⁴x.8.
11 ¹vii.6; ²vii.6; ³xiii.9.
12 ¹iii.8, v.13, viii.24,32;
²iii.12, xiii.12; ³xi.
7; ⁴iii.10, iv.7, v.29,
viii.15, x.22, xiii.4,
xiv.4, xvi.21, xvii.5;
⁵xii.5,11, xvi.29; ⁶iii.
10, ix.13, xii.8, xx.3;
⁷ix.20,23, xii.7, xiii.
12.
7.1 ¹ix.22; ²iv.44; ³xiv.9,
11, xxi.12,14.
2 ¹v.35, xv.7; ²i.39, xvii.
6, xix.2, xxiii.17,
xxiv.5 *bis*; ³x.13.
3 ¹iii.6, xxiv.5; ²ix.21,
xxiv.5.
4 ¹xiv.16 *bis*.
6 ¹vi.8.
7 ¹viii.27, xi.3; ²viii.4, xi.
3, xii.7 *bis*, xiv.23.
8 ¹xxi.5; ²iv.20, xi.3, xii.
4; ³v.15, xii.7, xiii.12;
⁴xvi.13 *bis*.
9 ¹i.30, viii.7,13,16; ²viii.
13,29, ix.22, xii.7.
10 ¹xiii.15; ²xiv.27; ³i.61,
vi.4.
11 ¹v.25,31, ix.10.
12 ¹vi.2.
13 ¹iv.18, xiv.28; ²iii.12;
³vi.2, viii.8, xvii.4.
8.3 ¹iii.14, vi.2, vii.2 *bis*.
4 ¹iii.12, vii.12, xv.6.
5 ¹iv.48, vii.16, ix.21, xiv.
20, xvi.17; ²ix.21,
xiii.13.
6 ¹xii.11; ²xiv.4.
7 ¹xiv.2, xx.2,8.
9 ¹xiii.15; ²v.30, xv.1.
10 ¹iii.11, v.10, viii.13, xi.
17.
11 ¹vi.3, xiv.6.
12 ¹iv.11,13, xi.15 *bis*;
²xiii.12.
13 ¹xiv.20; ²iv.11; ³xvi.
29; ⁴ix.1, x.10, xvi.29.

TS. I.

- 8.14 ¹iii.13, viii.24.
15 ¹vi.7, xvi.2.
16 ¹i.58, v.29, vi.4, xiii.4,
xv.8; ²i.58, ii.52, xv.
8 *bis*, xvii.1.
18 xvi.13.
21 v.32, xi.17, xiv.12.
22 ¹vii.4; ²iii.14; ³xvi.14
bis.

TS. II.

- 1.2 ¹iv.6, ix.7, xi.1, xii.9,
xx.4,6,8; ²iv.12; ³ix.
2,4,5,6, xiv.9,10,11,
15; ⁴xiv.36, xxi.15;
⁵viii.11, xiv.9 *bis*, 11
bis, xxi.14.
3 ¹xvii.2; ²vi.12; ³vi.12;
⁴ix.2,6.
4 ¹iv.12,52.
5 ¹xi.7; ²iv.14; ³iii.7.
7 ¹v.25, xiv.23; ²iii.4, viii.
16; ³xvi.21.
8 ¹xiv.21,26; ²xiv.26, xx.
2.
9 ¹xi.8; ²iv.3,4,11,51.
10 ¹xvi.2.
11 ¹v.12, xiii.13; ²iii.7;
³iii.10; ⁴iii.5, v.14, vi.
5; ⁵iv.40, ix.24, xiii.
12, xvii.4; ⁶iii.13, iv.
10, v.12, xiii.15.
2.2 ¹v.9; ²iii.7.
3 ¹ii.49.
4 ¹i.61; ²ix.21; ³xiv.15;
⁴i.61, vi.13, xi.16.
5 ¹xiv.16, xxi.15; ²iii.2;
³xiv.5; ⁴iv.40.
6 ¹iv.40; ²xiii.12 *bis*.
7 ¹iii.5; ²viii.15 *bis*, xi.4;
³iv.52, xv.6.
8 ¹ix.1 *bis*; ²v.32, ix.18.
9 ¹iv.2; ²v.21; ³iv.7, xv.
6.
10 ¹i.43, iv.52.
11 ¹xix.3.
12 ¹viii.24, xiv.9,34,27; ²v.
38, xiv.20, xxi.3; ³xii.
7; ⁴iii.7,12, vii.2,4;
⁵iv.12; ⁶iii.5, vii.2,
viii.16, x.19,21,22, xv.
6.
3.1 ¹ix.1, xvii.4.
2 ¹iv.53; ²ii.44; ³ix.4;
⁴x.16.
3 ¹iv.53, xiii.13.
4 ¹xiii.14; ²iv.52, vii.5.
5 ¹ix.10; ²x.10, xvi.29,
xx.2.
7 ¹ix.16.
8 ¹xiii.12; ²iv.11.
9 ¹viii.26, xi.3.
10 ¹xx.3; ²ii.48.
11 ¹iv.42, ix.11, x.22, xx.8,
xxii.13; ²viii.24.
12 ¹v.21.
13 ¹ii.44, xiv.9,10,11,15.
14 ¹iv.15; ²v.17, xiii.9;
³xii.7; ⁴iv.34, v.8.

TS. II.

- 4.1 ¹iii.7, v.24,33; ²ix.19,
xi.10, xxi.10; ³xvi.
13.
2 ¹ix.19; ²vi.12, xiii.14,
xvi.29.
3 ¹xx.4.
4 ¹xxii.13.
5 ¹v.2, vii.2, x.13,15.
6 ¹xiv.18.
7 ¹iii.5, viii.11; ²viii.12,
xi.16.
8 ¹iii.10 *bis*, 12.
9 ¹xvi.31.
10 ¹xiv.8,28; ²iii.5, iv.24,
ix.11, x.19, xxi.15.
11 ¹x.16; ²vi.3; ³vi.14;
⁴iii.2, xiii.15.
12 ¹iv.6, vii.6, viii.8, ix.12,
xv.6; ²iii.9; ³xv.7.
13 x.7, xiii.8, xiv.23.
14 ¹v.5, xii.8, xiv.11, xxi.
14; ²xii.7; ³iii.8; ⁴vi.
2, viii.12.
5.1 ¹viii.8 *bis*; ²ix.13, xi.1,
xii.9, xx.4; ³xiii.9.
2 ¹iv.2; ²iv.53; ³iv.28,29,
52, xvi.30.
3 ¹xvi.13; ²xi.13; ³vi.9,
x.10, xxi.20.
4 ¹vii.2.
5 ¹iv.52, xiii.12; ²x. xiv.
7 *bis*; ³xvi.11; ⁴iv.11.
6 ¹iv.44; ²ii.46, viii.8;
³iv.42,44, x.24; ⁴i.60,
iv.11,44, xvi.11, xxiv.
5.
7 ¹xxi.15; ²xiv.16; ³iv.
33.
8 ¹xv.4; ²xvi.13; ³ii.14.
9 ¹ix.21, x.10 *bis*; ²xvi.13,
20; ³vi.14, ix.21, xiv.
10; ⁴ix.22.
10 ¹vi.14, xvi.21, xvi.23.
11 ¹xvi.13.
12 ¹iv.52, vi.5, vii.13; ²iii.
3, xiv.28, xvi.13;
³xvi.25; ⁴v.2, x.13,
xiv.33, xxiv.5; ⁵vi.5,
xiii.8.
6.2 ¹iv.12,44, xiii.16; ²ii.49,
iv.30; ³xix.2; ⁴iv.
53; ⁵x.12.
3 ¹x.10; ²iv.49.
5 ¹iv.25, x.10; ²iv.25;
³xiv.32, xix.1.
6 ¹xvi.13, xxiv.5; ²viii.
33; ³iv.11, v.13, x.16.
7 ¹iv.39, vii.9; ²iv.7, xv.
8, xvii.2; ³x.10; ⁴iv.
23.
8 ¹xvi.26.
9 ¹iv.44; ²iii.7; ³iv.29, ix.
19, xiv.28; ⁴viii.30.
10 ¹v.22, vii.3; ²vi.7.
11 ¹iii.8,9, xiii.2, xx.8; ²vi.
2, xi.4, xiii.10, xvi.29;
³iii.8, vii.2, xii.25, x.
10, xiv.1; ⁴iii.9, viii.
24, xiii.2, xvi.20.

TS. II.

6.12 ¹H.49, xiii.15; ²H.12,
xiv.5,23; ³ix.21, xi.4;
⁴I.21, iii.9, xi.4; ⁵xiv.
5; ⁶xii.7, xv.4, xvi.2.

TS. III.

1.1 ¹v.15.
2 ¹v.15.
3 ¹159, iv.52.
4 ¹ix.21, xi.10, xvi.29;
²iv.28; ³ix.22 *bā*;
⁴x.14; ⁵vi.14.
6 ¹x.8,10.
7 ¹ix.3; ²iii.5; ³iv.36,
xvi.30.
8 ¹xiii.9; ²xi.10.
9 ¹vi.14; ²ix.21, xi.9,13;
³xiv.18, xvi.30.
10 ¹xi.3 *ter*; ²vii.15, viii.
28 *bā*, ix.20,21.
11 ¹iii.3, ix.20; ²viii.8,29,
xiv.24, xvi.13; ³iv.
11; ⁴xiii.9; ⁵v.2, x.
13, xv.6; ⁶iii.8, xii.8;
⁷xv.4; ⁸iii.8,10, x.12,
xiv.21, xx.2.
2.2 ¹i.53, xi.17, xvi.18, 29
bā; ²v.7, xi.5; ³i.40,
iv.24, v.33, vi.14 *bā*,
xiv.16,18, xxi.16.
3 ¹viii.29, xiii.4.
4 ¹ii.30, iv.42, xi.15,16;
²iv.47, viii.24; ³iv.38,
vii.10.
5 ¹v.3, viii.29, ix.16; ²i.
50, iv.11; ³viii.13, xi.
12, xxi.16; ⁴iv.46, vi.
14; ⁵xi.17.
6 ¹i.29, iv.13.
7 ¹viii.8.
8 ¹v.3, xi.3, xiii.15, xiv.5;
²vi.2; ³iii.8, viii.23,
ix.19, xi.3, xii.8 *bā*;
⁴iv.35, xi.3; ⁵viii.6,
ix.22 *bā*.
9 ¹iv.54, viii.3, xxiv.5;
²vi.14; ³xv.4, xvi.2;
⁴viii.34, ix.18, xvi.2.
10 ¹iv.35, v.27, viii.27,31,
xiv.23, xx.3.
11 ¹iii.11, iv.6,7, xii.6;
²viii.24; ³ix.24; ⁴iv.
12, x.12, xiv.29, xv.1,
3, xvii.4, xxiv.4.
3.1 ¹x.10.
2 ¹viii.8, xiv.24.
3 ¹xi.16.
4 ¹ii.25,30.
5 ¹iv.40.
6 ¹iv.12, xv.6.
7 ¹iv.40; ²v.9, xi.16,17,
xiv.30, xvi.27; ³iii.6.
8 ¹viii.8.
9 ¹iii.12, vii.2; ²iv.12,34,
xi.17, xv.5.
10 ¹i.43,46,47,52, iv.35, v.
13, xiii.2, xvii.6;
²xii.7; ³viii.26; ⁴vii.
9, xvi.18.

TS. III.

4.2 ¹ii.12.
3 ¹iv.42 *bā*, 52; ²iv.24;
³xiii.7; ⁴xiii.12.
4 v.23.
7 ¹xiii.15, xxi.12.
8 ¹xiv.23; ²v.34, viii.4,
³v.33.
9 ¹iv.7,11.
10 ¹viii.27, xi.17; ²vii.8.
11 ¹xii.7; ²iii.10; ³iii.7,
xiii.13, xiv.28; ⁴xii.
7.
5.1 ¹vi.9, xiii.15.
2 ¹xvi.14.
3 ¹ix.22, xiii.15; ²xi.10.
4 ¹xi.16; ²iii.12; ³vi.14,
xi.16, xxi.12.
5 ¹ii.25, xvi.14; ²i.49, iii.
2, xi.16, xvi.17.
6 ¹viii.27; ²iii.5.
7 ¹vi.2; ²v.24, xiv.18.
8 ¹iii.7,15, xiv.2,22.
10 ¹i.50, iv.10.
11 ¹i.51, iii.3,7,11, v.21, vi.
2; ²iii.12, xvi.18;
³iii.11, vii.11.

TS. IV.

1.1 ¹ix.4,5,6; ²vii.6, xi.3;
³iii.5.
2 ¹i.61, xvii.5, xxi.11;
²xii.6 *bā*, xiii.9,14;
³ix.23, xiv.5; ⁴viii.
8; ⁵i.61, viii.24, xxi.
5.
3 ¹iv.52, xii.6; ²iv.11 *bā*,
19 *bā*, viii.10, ix.18;
³iii.8, xii.4,6.
4 ¹i.61, iii.8; ²i.61, iii.12,
14, vi.2, vii.2 *bā*;
³iii.5.
5 ¹iii.1,8,10, vi.2,4; ²xvi.
2; ³ix.23.
6 ¹xii.7.
7 ¹xi.4; ²xii.8; ³viii.24,
xii.7.
8 ¹iv.2; ²i.57; ³iv.20, v.
12, xii.7 *bā*, xxiv.5;
⁴xii.4; ⁵iv.20,27.
9 ¹viii.28, xx.2; ²iii.8,
viii.10, xii.7 *bā*, xiv.5.
10 ¹xii.7, xxi.12; ²viii.29,
xii.7, xiii.12, xiv.1,
xvi.19; ³v.35, vi.14,
ix.24, xii.2, xiv.5,
xv.1, xvii.1,4; ⁴iv.11,
xii.4; ⁵viii.16,18,
xii.7; ⁶viii.27, xii.2.
11 ¹v.17, viii.32; ²iv.11,
xii.4, xiv.19; ³iv.12,
20; ⁴iv.11 *bā*, 19 *bā*,
23 *bā*.
2.1 ¹ix.3, xii.7; ²i.60, vi.2.
2 ¹iii.10, xxi.12; ²xii.7.
3 ¹xii.8,10, xiv.5, xvi.13;
²iii.10, vi.5, xxi.14;
³v.17, viii.8, x.10,25,
xii.3; ⁴iii.8, xi.5, xvi.
28.

TS. IV.

2.4 ¹xii.7; ²xvi.18; ³iii.5,
vii.7, xii.7, xvi.19;
⁴xvi.25.
5 ¹viii.8; ²iii.12, xiv.9,
11; ³iii.7; ⁴iii.5.
6 ¹viii.23, x.22; ²xii.8;
³iii.2, viii.32; ⁴x.22.
7 ¹xvi.18.
8 ¹iv.5, vi.2, viii.6, x.15,
19, xiv.5, xx.8; ²vi.
4, viii.8,9,32; ³i.61,
ix.20, xi.3, xii.7.
9 ¹iii.15, v.12, x.13, xii.2,
7; ²iv.45, viii.28, xiv.
23,29, xx.3, xxi.11;
³ix.20.
10 ¹xv.5; ²xvi.2,13; ³iii.
15, xii.8.
11 ¹iv.15,40, viii.24; ²iii.
5,10 *bā*; ³v.16, vi.3,
x.16,19, xxi.4.
3.1 ¹iv.11, vi.4, x.14 *bā*.
2 ¹i.32, iv.23; ²v.34,26.
3 ¹iv.33; ²i.54,55, ix.16.
4 ¹xi.3, xv.6; ²xi.3; ³viii.
25, xi.3.
5 ¹xvi.27.
9 ¹vii.2.
11 ¹iv.20, xi.3 *ter*, 5; ²vi.
13, vii.6; ³vi.14, xvii.
4.
12 ¹iii.8; ²vi.13, viii.4;
³vi.13, xiv.5.
13 ¹iii.9, vii.12, ix.22, xii.
3; ²iv.11, v.17, x.25;
³ix.23, xvi.19; ⁴iii.10,
ix.20, xii.7, xiii.6;
⁵vi.5, xi.4; ⁶iii.7, v.
2, x.13; ⁷xiii.9,15;
⁸iii.10.
4.2 ¹xiv.1,29, xx.6,7, xxii.
13; ²xiv.10,11; ³iv.
12,52.
3 ¹xiii.16; ²xi.17.
4 ¹v.10, xi.3, xiv.16; ²xi.
3 *bā*, xiii.13; ³i.38,41,
viii.31, xiv.29,33, xx.
6,8, xxi.13; ⁴v.5,
ix.10,17; ⁵iii.9,10,
vi.5, xii.8, xiv.16.
5 ¹xii.12,15.
6 ¹vi.12.
7 ¹xxi.12.
9 ¹vi.6, xi.3.
10 ¹iv.12; ²iii.7, iv.11.
11 ¹iv.5; ²v.2, x.13, xi.11,
xxii.14.
12 ¹ix.20, xi.3,4; ²xi.3;
*end*g xxiv.6.
5.1 ¹iv.43; ²v.20; ³xi.3,
xii.7; ⁴iv.43,54, ix.21,
xii.9, xiv.8.
2 ¹iii.7, xii.12.
3 ¹xvii.1; ²xi.14,17.
4 ¹xiii.12.
5 ¹viii.30, xiii.11; ²xi.
14.
6 ¹xiv.7.
8 ¹xi.14.

TS. iv.

- 5,9 ¹ix.22, ix.35,6, xvi.26;
²xiv.8.
 10 ¹iv.7, xi.3; ²iii.8, viii.
 26, xi.3; ³iii.9; ⁴iii.
 8, vi.5, vii.4; ⁵xii.8;
 end'g xxiv.6.
 11 ¹xi.17; ²i.61, xi.16.
 6.1 ¹vi.14, xi.3 *bis*, xii.8,
 xiv.9, xvii.2; ²iii.14,
 xii.5; ³xi.3, xii.7;
⁴xvi.20 *bis*.
 2 ¹xiv.8; ²v.17; ³iii.13,
 iv.38, vi.11; ⁴viii.37,
 xvi.14; ⁵iii.12.
 3 ¹iii.8; ²vii.9; ³ix.21,
 22; ⁴ix.22.
 4 ¹i.21, v.34, ix.3,4,5,6,
 xiii.15, xvi.26; ²iii.
 12; ³vi.12, ix.21, xii.
 8; ⁴iii.10 *bis*, xvi.
 26.
 5 ¹viii.24; ²xii.6; ³iii.
 10, ix.7; ⁴xiii.9.
 6 ¹ix.20, xi.3, xvii.3, xix.
 1; ²x.13; ³iv.20,21,
 v.2, vi.13 *bis*; ⁴iii.7,
 8, ix.20, xii.7, xiii.9,
 xvi.5; ⁵iv.11, xi.3,
 xii.7 *bis*, xvi.20; ⁶i.
 59, ix.20, xii.3,7; ⁷v.
 17, x.10, xiv.27; ⁸vi.
 4, xii.7.
 7 ¹vii.8, ix.20, xi.3, xii.3;
²iii.8, viii.8, xi.5 *ter*,
 xvi.13; ³iv.38, xii.4,
 xvi.8; ⁴iii.8, xvi.7.
 8 ¹ix.20, xi.3, xiv.8;
²xii.7, xvi.5; ³xii.7.
 9 ¹ix.20, xi.3, xvi.8; ²iii.
 7; ³iii.8,12, viii.32,
 xvi.5; ⁴i.25, iii.14,
 iv.15 *bis*, v.4 *bis*, 38,
 viii.28, xii.7, xvi.
 13.
 7.1 ¹xi.11.
 2 ¹ii.44.
 3 ¹v.20,27.
 4 ¹xiv.15; ²v.4, xiv.8;
³xiii.12.
 5 ¹iv.38, v.4, xiv.11, xxii.
 14, xxiv.5.
 6 ¹viii.6, ix.2,6.
 8 xii.7.
 9 ¹xxi.3.
 10 ¹v.21.
 12 ¹iii.10, xi.3 *bis*, xii.7
bis; ²ix.22.
 13 ¹iv.52, xvi.3; ²iv.11,
 viii.25; ³viii.26; ⁴iii.
 12; ⁵iii.6, iv.11, vi.
 14, xvi.13, xxiv.5.
 14 ¹iii.3; ²iii.12, xi.3, xii.
 7; ³viii.8, xii.7.
 15 ¹ix.20, xi.3, xiii.15, xvi.
 13; ²iv.40, v.4; ³iii.
 7, iv.52, xiv.23; ⁴ix.
 23, xvii.1; ⁵iii.10, iv.
 20 *bis*, 21, xvi.13,29;
⁶iii.12,13, vi.2, xx.1.

TS. v.

- 1.1 ¹ix.20, xi.16; ²v.18;
³viii.33, ix.3, xiii.9
bis, xiv.26, xxi.12,
 xxiv.5.
 2 ¹vii.8, x.9, xi.13, xviii.
 7; ²xvi.13; ³iii.6.
 3 ¹i.61, xi.18; ²i.61.
 4 ¹xi.13,15; ²iv.44.
 5 ¹i.61, iv.25; ²i.61;
³iv.17,25; ⁴xiv.16,
 xxi.16.
 6 ¹iv.44,45; ²vi.12,13,
 vii.16, ix.1.
 7 ¹vi.2, xiii.13; ²viii.8,
 xiv.8.
 10 ¹x.10, xiii.7, xiv.4;
²iv.52; ³ii.49.
 11 ¹vi.5, ix.7,13,20, xi.16;
²iii.10, iv.20, vi.9,
 13.
 2.1 ¹i.21, iv.12, ix.3, xiv.15.
 2 ¹xi.16,17.
 3 ¹i.29; ²xiv.18; ³iii.
 5; ⁴v.21,24; ⁵iv.31;
⁶iii.8.
 4 ¹xvii.6.
 5 ¹xvi.13; ²xiii.9; ³vi.
 12; ⁴viii.8.
 6 ¹vi.12; ²vii.5,6.
 7 ¹iv.25, xxi.8, xiv.9;
²xvii.1,3, xxi.8; ³ii.
 30, x.10, xiv.23; ⁴iv.
 25,26; ⁵iii.15, xiv.10,
 11, xxi.9, xxiv.4.
 8 ¹xiii.14; ²xvii.1; ³xxi.
 7; ⁴xvi.2,13.
 9 ¹xiv.11; ²xvi.19.
 10 ¹xvi.27; ²xvii.3; ³ix.
 21.
 11 ¹ix.20, xiv.5,8 *bis*.
 12 ¹ix.20; ²xi.3,17.
 3.1 ¹x.9; ²xiv.28; ³vi.12;
⁴iv.50; ⁵xvi.20 *bis*.
 3 ¹vi.13; ²xvi.25.
 5 ¹iv.44,45; ²vii.10; ³x.
 14.
 6 ¹vi.14; ²x.18, xxiv.5;
³vi.14, xiv.12.
 7 ¹iv.42; ²i.25, iv.11,
 33.
 8 ¹xvi.15; ²xiv.8.
 11 ¹xvi.13; ²iii.5, vi.14;
³x.16, xx.1,2.
 12 ¹xx.7; ²v.38, xi.17.
 4.1 ¹iv.42; ²xvi.14.
 2 ¹v.38.
 3 ¹vi.3, xiv.15; ²xxi.9.
 4 ¹vi.4; ²iv.12, xxi.16.
 6 ¹viii.29.
 7 ¹iv.29; ²xiii.9.
 8 ¹i.31, iv.52, xiv.2,22.
 9 ¹iv.11; ²xi.5,6.
 10 ¹xvi.14; ²xvi.13.
 11 ¹xxi.7.
 12 ¹vi.5,14; ²v.6.
 5.1 ¹v.21; ²xvi.16.
 2 ¹v.17; ²v.33, xiii.2.
 3 ¹ix.31; ²ix.18, xvii.9,
 xx.2,3, xxiv.5.

TS. v.

- 5.4 ¹ix.25 *bis*, ix.10; ²iv.
 31; ³iv.38, ix.16.
 5 ¹xi.8,9; ²vii.5,16, xvi.
 26; ³xxi.2; ⁴x.10,
 17 *bis*, xvi.13, xx.5.
 6 ¹iv.44; ²iv.37.
 7 ¹iv.33; ²viii.30, xi.5;
³viii.23.
 8 ¹x.18, xxiv.5.
 9 ¹iv.11, xvi.26, xxi.10,
 xxiv.3,5; ²i.22, ii.25
bis, 48, viii.2, xiv.23,
 xvi.26; ³viii.16, xi.
 16,17.
 10 ¹iv.32.
 11 ¹iv.39, xvi.26, xxi.8.
 12 ¹xvi.19.
 15 ¹iv.39, vii.13, xiii.12.
 16 ¹viii.17.
 18 ¹iv.28, ix.2.
 19 ¹viii.17, xiv.23.
 20 ¹ii.2.
 21 ¹x.4.
 24 ¹iv.12.
 6.1 ¹iv.11, ix.20; ²ii.47, iii.
 12, ix.15,20 *bis*, x.19,
 21, xv.1, xvii.1,2, xx.
 2; ³iii.15, vii.2, viii.
 8, xi.3,5; ⁴vi.10.
 2 ¹xi.18.
 4 ¹iv.25 *bis*, xii.8, xvi.19;
²xvi.27.
 5 ¹ii.49, ix.19,21, xiii.12,
 xiv.24,27.
 6 ¹v.22; ²xi.17; ³xvi.
 26; ⁴v.6.
 7 ¹xvi.8.
 8 ¹xvi.2; ²vi.12,13; ³vi.
 13, xv.4; ⁴iv.52; ⁵iv.
 11.
 9 ¹vii.3; ²xiii.3.
 12 ¹iv.15.
 14 ¹x.14.
 15 ¹x.6.
 21 ¹iv.39,48 *bis*, xxi.
 8.
 23 ¹vi.12.
 7.2 ¹vii.2; ²vii.8, xi.17;
³iii.10, xiv.11; ⁴iv.
 7.
 3 ¹vi.12, xi.13, xiv.9,17;
²ii.25, iv.44, vi.14.
 4 ¹x.12, xx.2,8; ²iii.3;
³xvi.22.
 5 ¹vii.2; ²iii.7.
 6 ¹viii.8, xiii.14; ²vi.7.
 7 ¹xi.16; ²iv.11; ³iii.15.
 8 ¹xi.17.
 9 ¹iv.7, ix.21,22,24, x.19,
 xi.9,16, xvii.1,6, xix.
 1, xx.2.
 10 ¹xvii.1.
 11 ¹v.14, xiv.16, xxi.16.
 12 ¹i.22, v.37, x.14.
 14 ¹vi.7.
 17 ¹iii.7.
 20 ¹viii.13, x.12, xvi.8.
 23 ¹xiv.2,10, xvi.7,14,16.
 26 ¹ix.4, xx.8.

TS. vi.

- 1.1 ¹xvi.21; ²iv.17, xiv.11;
³vii.13; ⁴viii.34;
⁵xix.3.
 3 ¹iv.11,24,38,42 *bā*, vi.7,
 vii.16, xiii.6; ²xiii.
 6; ³i.34, xiv.5; ⁴iv.
 38, xiii.11.
 4 ¹xiii.12; ²vi.4, vii.14.
 5 ¹iv.52, vii.6, xix.5, xxi.
 7, xxi.15; ²iii.7, vii.
 6; ³vii.6.
 6 ¹i.48, xiv.1.5; ²iv.42,
 vii.31; ³ix.22; ⁴iv.
 28, xiii.9,12, xxi.7.
 7 ¹viii.9; ²i.59.
 8 ¹iv.44,45.
 9 ¹i.58, vii.23, ix.9, x.19,
 xv.7.8; ²x.10, xiii.13;
³v.19.
 10 ¹iv.2, xi.16 *bā*, xiii.12,
 xiv.6; ²xi.17.
 11 ¹vii.16; ²ix.17.
 2.1 ¹iii.7, vii.4; ²iv.12,33;
³ix.22.
 2 ¹iii.8.
 3 ¹v.7; ²viii.8; ³v.18.
 4 ¹ii.25, x.10,17, xx.5,6;
²viii.17.
 6 ¹ix.21; ²vii.6, xvi.9.
 8 ¹iv.11; ²xiv.16.
 9 ¹iv.11 *bā*; ²iv.33; ³v.
 10, vi.8, xvi.2 *bā*, xx.
 8.
 11 ¹i.59, iv.11; ²iv.5,11 *bā*,
 v.9, xiii.14; ³ii.44, iv.
 11, vi.11, vii.16, xiv.
 8.
 3.1 ¹v.6, ix.22; ²ii.30, v.
 32,38.
 2 ¹xiii.14, xiv.22; ²vi.7.
 3 ¹v.38,39,40, xiv.12;
²xxi.15.
 4 ¹xiv.8; ²xiv.5.
 5 ¹iv.52.
 6 ¹iii.8, xiii.15.
 7 ¹xxiv.5.
 9 ¹viii.14; ²xi.16; ³iii.7;
⁴iv.12.
 10 ¹viii.8; ²xvi.20; ³xiii.
 6; ⁴vii.10.
 11 ¹iv.11,24; ²xiv.2.
 4.1 ¹iv.14, xvi.14.
 2 ¹xiii.2.
 3 ¹xi.6,14; ²viii.23; ³xii.
 8, xx.8.
 4 ¹xvi.29; ²iii.8, xvi.29
bā.
 5 ¹xi.16, xiv.17; ²xvi.29;
³xvi.29.
 6 ¹vii.10, ix.20, xvi.29;
²viii.10.
 7 ¹i.48, iv.40, v.23, xiv.1;
²vii.12 *bā*, vii.2.

TS. vi.

- 4.8 ¹xvi.29.
 9 ¹viii.23, xiv.17.
 10 ¹iv.40, xiii.13, xiv.28,
 xvii.3; ²viii.35; ³iv.
 11; ⁴end'g vii.35,
 xxiv.6.
 11 ¹iv.11, vi.10.
 5.1 ¹vii.32.
 2 ¹xiv.6.
 3 ¹xiv.24; ²xiv.23, xvi.12.
 5 ¹viii.2.
 6 ¹xiv.31.
 8 ¹ii.21, iv.7; ²i.4,58, vii.
 27, xv.8, xvi.13; ³i.
 59, iii.15, iv.53, vii.
 8, end'g xxiv.6.
 10 ¹xvi.9.
 11 ¹vii.16; ²vi.10, xi.17,
 xiii.7.
 6.1 ¹xi.9.
 2 ¹xvi.16; ²i.54.
 3 ¹viii.30, xvi.14; ²viii.
 33; ³v.33.
 4 ¹xiii.16; ²xvi.13; ³i.30,
 59, iv.35, x.10; ⁴v.14.
 5 ¹vi.10, x.10; ²xiv.30.
 7 ¹xi.12.
 8 ¹iv.28.
 10 ¹x.10, xvi.29.
 11 ¹v.32, xiv.12,13, xxi.4;
²iv.11, vii.11; ³xvi.6.

TS. vii.

- 1.1 ¹xvii.1; ²xiv.18,31, xvi.
 13.
 2 ¹vi.14; ²v.20.
 4 ¹iv.11, xx.2, xxi.11.
 5 ¹vi.14; ²v.22; ³x.10,
 xii.11, xiv.31; ⁴xx.7.
 6 ¹x.24, xv.7, xxi.5;
²xvi.29; ³xiv.6;
⁴xiii.12; ⁵iii.15, v.9,
 vii.5, xiii.12, xiv.2,21,
 26; ⁶xi.17.
 7 ¹xiii.9.
 8 ¹vi.12, x.17, xx.5,8.
 9 ¹ix.21.
 12 ¹x.10.
 19 ¹v.12, vi.12, vii.5, xiii.
 14, xvi.22; ²v.14,
 xvi.22.
 2.1 ¹iv.52; ²ii.34; ³x.10.
 2 ¹ii.25.
 4 ¹xiii.9.
 5 ¹viii.4.
 6 ¹i.31; ²iv.54.
 7 ¹viii.10, xi.16.
 8 ¹vii.6, vii.13.
 9 ¹iv.11.
 10 ¹xi.13, xvi.29; ²vii.2,
 xiii.12; ³x.10.
 13 ¹xvi.25, xxi.14.
 15 ¹ii.44, v.3, vii.2, vii.2.

TS. vii.

- 2.17 ¹xvi.23 *bā*.
 3.1 ¹xiii.12; ²iii.15.
 2 ¹ix.30.
 4 ¹v.21.
 5 ¹viii.13.
 8 ¹xii.10.
 9 ¹viii.13.
 10 ¹iv.11, xiv.16.
 12 ¹v.33, xiv.5, xxi.9,12,
 xxiv.5.
 13 ¹xi.17, xiv.18.
 14 ¹ii.30, xiii.9, xvii.1.
 15 ¹xiii.14.
 16 ¹i.22, iii.7 *bā*, x.14; ²iii.
 7, xvi.30.
 17 ¹x.14, xvi.30.
 18 ¹vi.12, xiii.12.
 4.2 ¹v.32, vii.13, ix.18.
 3 ¹vi.14; ²iii.7; ³v.8.
 4 ¹iv.54; ²iv.52.
 5 ¹iv.51, vii.13; ²vii.2.
 7 ¹xiv.1.
 8 ¹iv.52; ²iii.4; ³x.10.
 9 ¹xvi.13.
 10 ¹vi.13; ²vii.8.
 11 ¹vi.12,13; ²iv.12; ³iv.
 53.
 13 ¹iii.7, xiv.16, xxi.16.
 15 ¹iii.10, xi.17, xvi.30.
 17 ¹xi.6.
 19 ¹x.10, xi.17, xvi.18;
²xiii.12, xvi.2; ³xvi.
 13.
 20 ¹viii.8, xi.6,7, xiii.12,15,
 xv.8, xvi.18, xx.7.
 21 ¹vi.12.
 5.1 ¹xiii.14; ²iv.11, vii.14,
 xvi.29; ³xvi.12.
 2 ¹ii.47, vi.3, ix.14, x.19,
 xvi.27; ²vi.12, x.17,
 xvi.12, xx.5.
 3 ¹iv.11, xvi.12,17; ²iv.
 11.
 5 ¹x.10; ²xvii.4.
 6 ¹iv.26; ²iv.42; ³vi.
 14.
 7 ¹iv.42,52, ix.17; ²iii.8,
 xi.13.
 8 ¹xiii.6; ²v.19.
 9 ¹xiii.16, xiv.4; ²xiii.12;
³vii.16; ⁴viii.10, xiv.
 8.
 10 ¹vii.16.
 11 ¹iii.2.5, xiv.5; ²xvi.4.
 12 ¹xiii.13; ²xiii.13, xiv.
 23, xvi.10.
 14 ¹xiv.8.
 15 ¹xiv.8, xvi.14.
 19 ¹xvi.22.
 20 ¹xxi.16.
 22 ¹xvi.29.
 24 ¹iv.20, xi.13.
 25 ¹xiii.13; ²xviii.1.

SANSKRIT INDEX.

THE following Index contains the whole matter of the *Prāticākhya* itself—both the proper vocabulary of the treatise, and the words and parts of words which it quotes from the *Saṁhitā*; the latter being distinguished by being printed with *spaced letters*. To this is added a very liberal selection from the vocabulary of the commentary; perhaps more liberal than may seem to some worth while, but I preferred to err in this direction rather than the contrary. The references to the commentary are designated by a prefixed *c*; and an added *v* indicates that the word is to be sought among the various readings given at the foot of the comment.

- a*, xiii.15.
ahkṛā, i.23:—*ci*.24, xvi.25.
ahsra, ix.7.
aṅga, ciii.8, iv.23, xxi.2v.
aṅgabhuva, xvi.29.
aṅgam, aṅgāya, xvi.29.
aṅgavaḥ, xvi.29.
aṅgu, xvi.29.
aṅguḥ, xi.10, xvi.29.
aṅgunā, aṅgubhīḥ, aṅgum, aṅgū, aṅgūn, aṅgoh, aṅgdu, xvi.29.
aṅsābhyām, aṅsāya, aṅse, aṅsāu, xvi.30.
aṅhah, viii.15, xvi.29.
aṅhatih, xi.4, xvi.29.
aṅhasah, viii.24, xi.4, xvi.29.
aṅhasā, xvi.29.
aṅhoh, xvi.29.
aṅhomuk, xvi.29.
akah, viii.8, ix.22.
akaram, xii.7.
akarot, iv.52.
akāra, i.17, 21, 32, 52, ii.21, 26, iv.6, viii.23, ix.7, 13, xi.1, 9, xv.8, xx.4.
akurva, v.7.
akurvata, ix.22.
akṛṇot, xi.17.
akte, iv.11.
akṛāṣṭa, xvi.22.
akṣaṇ, xiii.13.
akṣhara, xx.2, xxiii.7:—*ci*.13, x.1, 4–12, xix.1, xxii.14–5, xxiii.8–¹¹, and *saṁdhyakṣhara*, *saṁdā-kṣhara*.
akṣharasāṁhitā, xxiv.2, 4.
akṣhapada, civ.11, xv.4.
akṣipada, cvi.12, xvi.19, 20.
aganma, ix.22.
agamat, xi.7.
agnayah, xii.8; *agna-anumātrā*, xix.3:—*c* xix.4, xxi.15.
yah paprayah, xii.7.
agni, iii.9:—*ci*.2, ix.20 (*kāṇḍa*).
agni, xi.15.
agnih, vi.5, xi.13, xiii.15.
agnim gāyatram, iv.52.
agnir mārddhā, xi.3.
agne, xi.10.
agner jihvām, xii.7.
agriyāya, xi.14.
agre, ix.22, xi.14, 16.
agha, xi.13.
agha, iii.2.
aghosha, i.12, ii.10, ix.1, 2, xiv.9, 10, 18:—*ci*.14 etc.
aghoshaṭea, ci.13.
aghoshavant, cix.1, 3 (*-tea*).
aghniya, xi.17.
aṅga, xxi.1, xxiv.5:—*c* xxi.2 etc.: and *pratyā-*
aṅgasāṁhitā, xxiv.2:—*c* xxiv.4.
aṅgānām, vii.10.
aṅgiraḥ, xi.17.
aṅgirasvat, xii.7.
angikar, cxvi.2.
aṅgushthāgra, cxxiii.17.
aṅge, xi.17.
ac, cxiv.4.
acyutaḥ, xi.17.
achā, iii.8.
achidre, iv.11.
ajāst, xvi.18.
ajigah, viii.8.
ajitān, xi.17.
ajyanim, xi.17.
anj, + *abhi*, cv.7: and *vyajjana*, *ativyakta*, *avyakta*.
anava, ca, xiii.12.
anishthdā, xiii.12.
anu, xvii.3:—*c* xix.3, 4–5 (*-kārya*). xxi.15, xxiv.6.
anulā, xxii.9.
anumātrā, xix.3:—*c* xix.4, xxi.15.
anumātrika, cxix.4, xxii.13 (*adhy-*).
ataḥ, xxii.14.
ataśsayat, xvi.13.
atī, xiv.8.
atī divaḥ, viii.24.
atīdrutah, xi.17.
atiprasaṅga, ci.9.
atiprāpti, ci.11.
atī yanti, xi.17.
atireka, cintr., xxiii.20.
ativyakta, xvii.8.
ativyasta, ii.12:—*c* ii.13.
ativyōpti, ci.11.
atigaya, ci.16, 27, xvii.6.
atipashṭa, cxvii.8.
atīvārya, xxiii.12:—*c* xxiii.13.
-ate, iv.54.
attā, iii.12.
atyāṅhah, xvi.29.
atyanta, cxxiii.6, 7.
atyupasaṁhṛta, ii.12.
atra, xvii.5:—*ci*.1, 15 etc.
atra stha, xii.7.
atrā, iii.8.
atha, i.1, 2, ii.1, iii.1, iv.1, 8, v.1, 11, vi.1, 6, vii.1, viii.1, 5, ix.10, x.1, 3, xi.2, xii.1, xiii.1, 5, xiv.14, 25, xvi.1, xx.3, xxii.6, xxiii.1, xxiv.1.
atha, iii.10, ix.24.
atho, xii.7.
adāḥ, xii.7.
adabdhāṣah, xi.16.
aditih, ix.22; *aditih* *carma*, xii.7.
adugdhāḥ, xii.7.
aduḥat, ix.22.
adbhīḥ, xi.8.
adya, xi.10; *adya pa-thi*, xi.13.

- adyā*, II.5,8 (instead of *anukarṣhaṇa*, c. xiv.28.
aghā).
adyā'nu, xii.7.
adruta, xxiii.20.
adharānt sapatnān, ix. 22.
adharoshtha, c. ii.39,43.
adhastāt, c. ii.28.
adhā, iii.9.
adhāyī, xii.7.
adhī, i.15.
adhika, xvii.5:-c. ii.11,25,28, xvi.19, xvii.1: and *adhīkya*.
adhikarāṇa, c. i.59.
adhikāra, c. i.2, ii.1, iii.1, iv.1,8, etc.
adhikāraka, xxii.6:-c. xx.3.
adhigama, c. i.1.
adhishāvaṇa, iv.11.
adhī, iii.7.
adhiyayana, c. i.1, xiv.4,5,28.
adhyardha, ii.28:-c. ii.25,28, xi.19, xxi.1.
adhyāya, c. i.61, x.15, xii.1, xiii.3,15, xiv.4, xix.5, xxiv.2, and endings of chapters.
adhyetar, c. ii.34, xvii.8, xxiv. 5.
adhvara, xi.18.
adhvaraṇa vīcṛataḥ, viii.32.
adhvaryo, xii.8.
anadvān, v.21.
anadātā, iii.12.
anadhikrīta, c. vii.15.
anantak, viii.8.
anantara, i.41,44, xxiii.16:-c. i.1, ii.1, iii.1 etc., iv.53, x.12, xvi.13.
anantodātā, xvi.5.
anapekṣa, c. xiv.18.
anamivak, xi.17.
anartha, c. ix.23.
anarthako, c. iv.23, viii.13, ix.8,23e, xiv.15, xxi.5.
anavagraha, c. iii.8,10,12-4.
anavasthā, c. xiv.22.
anādeṣa, ii.20:-c. ii.21.
anādyudātā, viii.10.
anān, vi.14.
anānikā, c. xxi.17.
anārsha, c. ix.22.
anāgyānta, viii.13:-c. viii.8, anivā, c. vi.14.
anishṭa, c. i.4,21, ii.20, iv.23, v.3,31, ix.6, x.11, xii.3, xiv.22, xvi.29.
anishṭīrtaḥ, xi.4.
anī, vii.12.
anu, xi.5,7.
anuccraṇa, c. iv.23.
anuttama, xiv.24, xxi.12.
anudātā, i.39,45,46, iii.15, iv.43, vi.4, viii.9, x.12,16, xii.9,10, xiv.29, xvi.8, xviii.2, xx.2, xxi.10:-c. x.10, xii.6, xxii.10, xxiii.16,17.
anudattatara, c. i.44.
anunāsika, ii.30, v.26-8, 31, x.11, xv.1,6, xxii.14:-c. i.1, ii.19,30, v.29-31, xiv.23, xv.7-9, xvii.1 (-tā): and *sānu-*, *anunāsika*.
anupada, c. xxiv.6.
anupapatti, c. iv.23, xiv.4.
anupapanna, c. i.21,59, iv.23 (-tā), v.26,35, viii.18, xvi.2.
anupalabdhi, xxiii.7.
anupradāna, ii.8, xxiii.2:-c. ii.9,10.
anurodha, c. i.2, xiv.5,28, xx.12.
anuvartana, c. ix.9, x.14, xiii.16.
anuvāka, c. i.61, iii.9, iv.25, 26,48,52, ix.20, xi.3, xvii.6e, xviii.3e.
anuvṛtti, c. iv.40, viii.23, xvi.13.
anusāra, c. i.21,57,59, iv.52.
anusārīta, c. xiii.16.
anusārīn, c. xiii.16.
anusvāra, i.18,34, ii.19,30, xv.3, xvii.1,3, xxi.6, xxii.15:-c. i.1,60, ii.25,33, viii.15, xvi.2-15,17-23,25-31, xvii.5.
anū, iii.7.
anūkāra, iv.52.
anūśhmavant, iii.15.
anṛṇak, xi.17.
anṛte, iv.11.
aneka, i.26.
anekārtha, c. i.1 (-tea), vi.13, viii.28 (-tea).
anākāra, i.53.
anta, i.55 (-raf), ii.17,40,43, 48, iv.3, vii.16, xiii.15, xv.5, xxii.14,15, xxiii.15:-c. i.21 etc.: and *āgyānta*.
antak, viii.10,32.
antahpātīta, c. iv.23, viii.18, xii.3.
antatāḥ, c. xix.3.
antamāḥ, xi.13.
antama, v.40, ix.16, xxiii.17:-c. x.3 etc.: and *anant-*, *ekānt-*.
antar asyām, xii.7.
antarā, iv.20.
antarātman, c. ii.41.
antarhita, xiv.30.
antasthā, i.8, v.28, xxi.7:-c. i.1, xiv.28.
antodātā, xvi.5:-c. viii.10.
antya, i.58:-c. viii.4, x.13,18.
andhak, xi.10.
annāya, xii.7.
anneshu, xi.17.
anya, ii.11,33, xxii.14:-c. i.19, ii.2,19, ix.1, xiv.5, xv.9.
anyah, vii.16.
anyatarataḥ, xix.1.
anyat-rastha, c. xiv.5.
anyateva, xxii.2.
anyathā, c. i.42 etc.
anyāni, vii.16.
anyābhikṣ, vii.16.
anyāyānva, c. i.49, ii.7.
aneya, c. i.1, xiv.15, xvi.23: and *anyonyānu-*, *poras-parānu-*.
anvārtha, c. i.3.
anvavasarga, xxii.10.
anvākarṣhaka, c. i.34, x.17.
anvācāya, c. xii.14, xx.10.
anvādeṣa, i.58:-c. iv.3,16, vi.3, vii.3,6, viii.12, ix.22, xi.4,6,11, xii.6, xiv.4, xxii.5.
anvādeṣaka, xxii.5:-c. i.52, ii.13,18, v.30, vi.3, xi.4, xiv.5,8,20, xv.4, xvi.3.
apah, xi.6.
apara, c. i.21, xi.1, xv.7,9.
aparā, xi.12.
aparigraha, c. xvi.29.
apavāda, c. i.13, iv.2, vi.5, viii.4, xii.8, xvi.11.
apavādaka, c. xiv.5,6.
apaṇa, c. i.14.
apasaḥ, viii.24.
apā, iii.12.
apān napāt, xi.8.
apī, i.26,43,51,52, iv.4,51, vii.5, viii.12, xiii.7, xiv.30, xv.8, xvi.3,15, xx.3, xxii.5,14, xxiv.4.
apī dadhāmī, xii.7.
apīdhāna, c. xvi.3.
apāpam, x^{iv}.7.
apīrva, xx.2.
aprakṛta, i.54, ix.16:-c. ix.17.
apekṣā, c. ii.35, iv.2, ix.22 (-kṣhāva), xiv.18, xv.9, xxii.5,11: and *anap-*, *nir-ap-*, *sāp-*.
apy etu, ix.22.
apragraha, xv.6.

- aprayoga*, ci.18.
aprosakta, cxiv.4.
aprovaddha, cxiii.14,15.
apsu yāh, xi.17.
abibhah, vii.8.
abrātām, iv.52.
abdhāh, viii.8.
abhāva, ci.14,33,42, ii.20,25 etc., iv.52 etc.
abhi, i.15.
abhi, xi.13.
abhikhyā, cxxiii.7.
abhighata, ci.2.
abhidroham, xii.7.
abhidhāna, ci.11, xxi.16.
abhinidhāna, xiv.9:—c xiv.10v.
abhinidhata, xx.4,10:—c xx.8.
abhiprāya, cxiv.5,15.
abhimata, cxviii.4.
abhi vāṣu, xi.6.
abhidhā, civ.23,52.
abhi, iii.7.
abhedavivakṣā, ci.1,18.
abhyantara, ci.41.
abhydvartān, xii.7.
-am, i.28.
amatra, xvii.8.
amanahprayoga, xxiii.6.
amā, xii.7.
amitrān, ix.21.
aminanta, x.13.
ami, iv.12.
amukhya, cxiii.14.
amuṣcātā, iii.12.
amṛtān, ix.21.
ambakān, vi.14.
ambāli, xi.17.
ay, ix.11.
ayajuk, vii.8.
ayan, vii.6.
ayam, iv.23.
ayam u, vi.2.
ayān, ix.21.
ayukta, cxiii.9, xiv.5.
r. ar: *samarpita*, cxvi.24.
ar, v.9, x.8.
aratim, xi.17.
arathāh, xii.7.
arān, ix.21.
ariśatāh, xii.7.
arcanti, xii.7.
arcān, ix.23.
arcik, xi.17.
artha, cxviii.14,20, xxi.7:—*and ana*, *ekā*, *arthika*, *sāthaka*.
arthacōstra, cxiii.14.
arthantara, ci.7, iv.47, xiv.4.
ardha, i.37,41, ii.26, xi.19:—*and adhya*-.
ardhatrīya, xv.ii.1 (-*mōtra*).
ardhamātra, xxii.13:—c i.34 (-*tra*). ii.25, xi.19, xxi.15.
arpita, iv.11.
aryaman, xii.7.
arvantam, xi.17.
atam, ix.22.
alam, ci.59, iv.23, v.1, vi.3, x.25, xi.3, xvi.19,20,25, 27, xviii.3.
alopa, xi.2:—c xi.4,9, xii.8.
alpa, xx.12 (-*tara*):—c xvi.19, xiii.6 (-*tā*).
av, ix.12.
ava, i.15.
avakāṣa, cxiv.4.
avagraha, i.49, iii.7, iv.2, v.10,18, vi.2,9, viii.23, xiii.13, xvi.11,30:—c iii.2-5,7, vi.9, xiii.13 (-*stha*):—*and anav*-.
avatā, iii.10.
avadyāt, xi.4.
avadhāraka, xxii.6.
avadhārāya, cxiv.3,22, xxii.6.
avodhi, civ.23 (-*tea*), 23, viii.5.
avante asman, xi.4.
avayava, ci.20, iv.52, x.12, xxi.15.
avayavin, civ.52.
avarna, ii.12, vi.7, vii.5, viii.16, ix.9, x.3,19.
avasara, ci.1.
avasāna, xiv.15:—c v.1, xiv.15.
avasita, xxi.3.
avasthā, ci.22, ii.25, x.14, xiv.18,29.
avasthāna, cix.17.
avā, iii.8.
avāntara, cxxiv.4.
avāntaram, iv.52.
avikṛta, v.39:—c ix.16, xiv.28.
avicalita, cv.2.
avimān, ix.21.
avilambita, xxiii.20.
avīśhita, cxxi.1.
avīśhā, ci.18,19, ii.47, iv.3, x.9,12.
avīśhyān, xi.17.
-ave, iv.54.
avyakta, xvii.8.
avyaṅjana, ci.23.
avyathamānā, xii.7.
aśāṣan, xvi.6.
aśakya, cxxi.5,7 (-*tra*).
aśabda, xxiii.6.
aśīret, xi.17.
aśman, vi.14.
aśmanah, vii.24.
aśmā, xii.7.
aśyāma, xii.7.
aśloṇaya, xiii.12.
aśvasanā, xi.17.
aśvasya, iii.8.
aśvā, xii.7.
aśvinā, xi.12.
aśvedhyah, xi.14.
aśādāh, xi.16.
r. as: *syāt*, xix.1.
r. as: see *vyasta*, *pranyasta*.
asah, v.16.
asamhita, xxi.5.
asat, xi.13.
asadama, vi.3.
asam, v.9.
asambhava, ci.25, xi.18, xx.2, xxi.5.
asāhita, iv.6:—c iv.7, xiv.5.
asādhu, ci.19, xvi.12.
asāra, ci.21.
asāv d, xvi.31.
asi, x.13, xii.2.
asiṅcan, vi.3.
askabhāyat, xi.17.
astā, xii.7.
astu, xi.17.
asthabhik, xi.17.
asthūri, vii.2.
asparcana, civ.23, xiv.4.
aspashta, cxvii.8.
asmat, ci.19 (-*ukta*), xiii.14 (do.), xiv.5 *asmābhik*.
asmatpāṇān, xii.7.
asmākam, xii.7.
asmān, ix.21, xi.8.
asmin, v.21, xi.13.
asmin yajñe, xii.7.
asme, iv.9.
asme dhātta, xii.7.
asya, xi.12.
asya yajñasya, xi.17.
r. āh: *āha*, civ.3 etc.
ahāh, iv.42, viii.13.
ahani, xi.4.
ahani, iv.12.
aharahāh, viii.8.
ahāh, viii.13.
ahorātre, iv.11.
ahniyāh, xi.17.
ahne, iv.39, vii.11.
ā, i.15, iv.22,23,52.
ākārshaka, ci.43v, vii.14, 16, viii.18, ix.21,22, xiv.4,7,17,22, xvi.12,18, xx.3, xxi.6,9.
ākāṅkshā, ci.1.

ākāra, iv.40, ix.20, xvi.14
16 (anā-).
ākhyā, i.16, 27; -ci.16, 17, 19-
23, 27, 28.
āgama, i.23, xxiv.5; -ci.24,
53, 60, v.4-8, 32, 33, 40, 41,
ix.16, xiv.5-11, 23, xv.3-
5, xvi.2-31, xxi.12.
Āgñe, ya, see p. 430.
Āgñe, yāyana, see p. 430.
ān, ci.1, 15, iv.23.
ā ca, ix.22.
ācārya, xxiv.6; -ci.47, ix.4,
x.21, 22, xiv.4, xv.8, xviii.
13, xxi.18; and see p.
430.
ātadrah, xiii.12.
ātāṣit, xvi.13.
ātī, xiv.8.
-ātmaka, c. xiv.28, xxi.1.
Ātreya, c. intr., v.1; and see
p. 430.
ādī, i.41, 46, 52, 53, 55, ii.26,
47, iii.1, xvi.29, xxi.4,
xxiii.15; (=etc.), v.40,
xxiii.11, xxiv.4.
ādīṭha, i.2, 5; -ci.47, xxiii.
10.
ādeṣa, ci.52, iii.8, ix.7, x.19,
xiii.16; and anād-.
ādeṣaka, ci.33.
ādya, i.7.
ādyadatta, vi.14; -c vii.8;
and anā-.
ādhiḥya, c. xxiv.3.
ān-, iii.15.
-ān mahā, iv.34.
ānantarya, ci.1, ii.1.
ānukūlya, ci.46.
āmunāsikya, ii.52, xvii.1; -
c xvii.3, 4; and an-.
ānupada, c. xxiv.6.
ānupāreya, i.1, 10, ii.44, xxi.
12, xxii.13; -ci.1, xvii.4.
ānumānika, c. ix.9.
r. āp, c. viii.11-15, ix.17, x.
2, 4-8, 10, 11, xiii.7, 8, xiv.
3, 21; +pra, ii.32, 34, 35,
ix.13, x.13, xi.4, xiii.16,
xvi.29; and prāpāya,
prāpta, prāpti, ativyāpti.
āpāh, iv.25, xi.5, 8.
āpāthi, ci.37, 51, v.24, 31, 35,
viii.13, xiii.3, xiv.12.
āpādaka, c. v.35.
ā pūshā, x.13.
-ā prshatī, iv.15.
āpo hi, vi.2.
ābhāsata, ci.25.
ābhāḥ, vi.5.
āy, ix.14.
āyajiśhṭhah, ix.22.

āyana, v.21.
āyama, xxi.9.
āyukh, vi.5, 13.
āyo, xii.8.
ār, x.9.
ārambha, ci.60, ii.20, 23, v.
10, 41, vi.3, viii.8, 16, 24,
ix.13, 21, x.22, xii.1, 6,
xiii.10, xiv.22, 24, xvi.4, 6,
18, xx.10, xxi.1.
ārambhana, c. v.1, xiv.3.
ārīthā, iii.10.
āropanyu, c. xiv.9, 9 (-tea).
ārthika, ci.59.
ārdhnauvan, v.21.
ārsha, ix.21, x.13; -ci. ix.23,
xxiv.2.
āv, ix.15.
āvah, viii.9.
āvīh, viii.24.
āvīnash, xi.15.
āvrt, viii.11.
āvrtti, ci.31v.
ācīh, v.10.
ācraṇa, c. xxiv.2.
ācraṇa, c. ix.1.
ācraṇatva, ci.1, viii.18.
r. ās: + adhi, c. xiv.4.
āsate ye, xi.16.
āsanna, i.25.
āstām, iv.52.
āhuti, iii.7, iv.15.
Āhvāraḥ, xxi.14.
r. ī: + adhi, xxiv.5; -c xviii.
7, xxiv.6v; +prati, ci.30,
42, ii.41, iv.11, v.7, xviii.
1, xix.3, xx.10, xxi.16;
and adhyayana, adhyetar,
vyaveta, etc.
ākāra, ii.28.
r. īng: + u, xvii.8.
iāgya, i.48; -ci.49, iii.8, iv.
10.
iāgyanta, iv.10, viii.13 (an-);
-c viii.13, 13 (-tea).
īdāh, viii.24.
īdāvān, ix.21.
ītaratra, c. viii.14.
ītarathā, c. v.12.
īti, i.15, 29, 30, 46, 47, ii.3, iii.
7, iv.3, 10, v.10, 15, 31, xiii.
4, 14, xiv.33, xvi.12, 30,
xvii.1-4, 7, 8, xviii.2, xx.2,
8, xxii.5-10, 13, xxi.2,
16, 19, 20, xxiv.2, 3, 6.
ītipara, iv.4, viii.12, ix.20
(an-); -ci.15 (-tea), ix.2
(an-), 21 (-tea), 23 (do).
ītivat, ci.7 etc.
ītham, ci.2.
īty evam, v.18.

īd agne, v.17.
īdam etc., i.46, ii.51.
īd u, v.17.
īdanam, ci.43, ix.11.
īndra, vii.2.
īndrah, vi.8, xi.9.
īndrā, iii.3.
īndriya, c. xxi.15 (-vishaya).
īndriyā, iii.5.
īndro me, ix.22.
īndān nah, v.17.
īme, iv.24.
īyam eva sū yā, xi.3.
īrdvati, iv.22.
īva, xvii.8.
īvarṇa, ii.22, x.4, 15, xx.1.
r. īsh, īch, c. v.1, viii.15;
+ abhi, c. ix.9; and īshṭa,
īshṭi.
īshṭa, ci.46, v.37, 41, viii.
22, x.21, xiv.3, 5, 13, 26, 33,
xv.2, 7, 9, xvi.16, 24, xvii.
7, xviii.5, 7, xix.3; and
ani-.
īshṭak, iv.44.
īshṭā, iii.6.
īshṭi, iv.52.
īhā, ix.22.
īkāra, iv.8, ix.20, xvi.14.
r. īksh: + vi, c. intr.; + apa,
c. v.24 (anopekshya); and
apekshā.
īdenyān, ix.22.
īm, v.12.
īyukh, vi.5.
r. ir: + sam, ci.2.
īrayatā, iii.10.
īshat, ii.15.
u, xxii.14.
u, vi.2.
ukāra, ii.29, viii.21, ix.16,
x.15, 22, xx.1.
ukta, i.61, xxiii.19; -c iv.23
(-tea).
ukti, ci.61, ii.23, iii.7, viii.
13, x.9, 12.
ukthā, iii.2.
ukshatā, iii.10.
ukhya, ix.20, xi.3; -ci.61,
ix.23 (-tea).
Ukhyā, see p. 430.
ugapā, xiii.12.
r. uc: ucita, c. xvii.7.
ucca, i.38 (uccāh), xxiii.20; -
ci.18, xviii.4, xx.2.
uccā, v.8.
uccāraṇa, ci.11, iv.11, x.23,
xvi.13, xxi.5, xxii.9; and
anu-.
uccāhikāra, xxi.9.

- uccāstara, i.41.
 uchvāsa, c.v.1.
 ut, iii.15, v.14, ix.24, xvi.21.
 uttama, i.11, ii.30, v.31, viii.2, xiv.11,24, xvii.1, xxi.12: and anutt-
 uttame, iv.11.
 Uttamottariya, see p. 430.
 uttara, i.16,20,27,30, ii.17, 29, iii.1, xiv.5, xvii.4: c.ii.25, iii.1 etc.
 uttaratra, c.xxii.11,12.
 uttaradanta, c.ii.43.
 uttarapada, c.iii.1.
 uttare, iv.11.
 uttaroshtha, c.ii.39.
 utpatti, ii.1, xxiii.1,3: c.ix.22, x.12.
 utpala, c.v.28.
 udaka, c.ii.1, xxi.1.
 udaya, ii.47.
 udayān, ix.21.
 udātta, i.38,41,42 (-sama), 46 (-sama), v.13, x.10,16, xii.5,9,10, xiv.29,31, xvi.30, xviii.2,6, xix.1, xx.1, 3,7, xxi.11, xxiv.5: c.xxii.9, xxiii.16,17.
 udāttara, c.i.41.
 udāttavant, x.10.
 udāttaṣṭuti, xxi.10.
 udāharana, c.i.18,21,22,42, 44, ii.25,50, iii.2,7, iv.54, v.3,26,41 etc.: and pratyud-
 upa, i.15.
 upa, xi.3; iv.24,42.
 upadeṣa, c.i.1, ii.20, xx.1.
 upadhānīya, i.18, xiv.5: c.ii.44.
 upapatti, c.intr., ii.23,47, iv.52: and anup-
 upabandha, i.59: c.iv.23.
 upabdimant, xxiii.5,9.
 upari, c.ii.47, iv.45.
 uparītaṇa, c.i.46, x.6, xxiii.5.
 uparībhāga, c.ii.37,41.
 upariśtāt, c.i.40, ii.18,44.
 upariśthāyina, c.xxi.1.
 upalakṣhakatva, c.iv.23, viii.34.
 upalakṣhaṇa, c.i.23,28, viii.34, ix.24, xvi.25.
 upalabdhī, xxiii.8,13: c.ii.1, xxi.1, xxiii.8,9: and anup-
 upalambha, c.i.1,18.
 upaśeṣa, c.ii.31.
 upasamīdhra, ii.24,31: c.ii.19,24,25, xxiii.19.
 upasamīhṛtara, ii.14,16, 18: and atyupasamīhṛta.
 upasarga, i.15, vi.4, x.9, xiv.8: c.vi.9,12.
 upastha, iv.21.
 upāṣṭu, xxiii.5,6.
 upāṣṭu, xvi.29.
 upāṅga, c.xxiv.6.
 upādāna, c.i.25, ii.1, iv.40, viii.4, xvi.29, xxiii.3: and bahup-
 upottama, xi.3.
 upyamānam, vii.3.
 upha, iv.47, x.1.
 ubhayataḥ, c.x.10,11.
 ubhayatra, c.ix.21.
 ubhayathā, c.ii.12,23.
 ubhābhyaṁ, iv.52.
 ubhe, iv.11.
 uras, ii.2,3, xxiii.10.
 uru, vii.2.
 urutā, xxii.10.
 urvi, iv.20.
 ulbāṇam, xiii.12.
 uvarṇa, ii.24, x.5.
 uṇmāsi, iii.13.
 uḥyamānāḥ, vii.6.
 ū, iii.14, vi.2.
 ūkāra, iv.5,52 (an-), ix.20, xvi.14.
 ūdhvam, ix.22.
 ūpyoḥ, xiii.10.
 ūbhava, x.17, xx.5.
 ūrdhva, c.x.12.
 ūrdhvan, vi.14.
 ūrdhve, iv.11.
 ūshmatea, c.i.13.
 ūshman, i.9,12, ii.44, ix.1,2, 5, xiii.2, xiv.9,12,16,18, xv.1,4, xvii.4, xxi.9,15: c.i.1 etc.: and anūshma-
 vant.
 ūhaniya, c.i.59.
 ūkāra, i.31, ii.18, v.9, vi.8, x.8, xiii.6: c.i.33, xxi.15.
 ūkāśmā, iii.5.
 ūkāśme, iv.11.
 ūgvidma, xxii.12.
 ūc, c.iv.20,21, xi.3.
 ūjishī, xvi.18.
 ūṇa, xiii.14.
 ūtā, iii.2.
 ūtu, vi.7, ix.22.
 ūtūn, vi.14.
 ūdhyānā, iii.10.
 ūrṇa, c.xiv.28.
 ūśabhāḥ, xi.16.
 ūśhi, c.xi.19, xviii.7.
 ūśhṇān putrah, xi.16.
 ūkāra, i.31, ii.18: c.i.33.
 ūka, iv.51, x.1; (ēka) i.47, ii.19,27,47, v.30,39, viii.19, ix.5, xi.19, xiii.3, xiv.3, 25,33, xv.2,6, xviii.1, xix.3, xxi.13.
 ekatā, c.ii.7.
 ekadeṣa, c.ii.23, iv.52, xxi.15: and padāik-
 ekapada, xv.4: c.iv.11, v.9, xiii.6, xx.7, xxii.13, xxiv.4.
 ekaprānabhāva, v.1.
 ekabandha, c.xvi.29.
 ekam, v.18.
 ekamātra, xxi.13.
 ekayā, v.19.
 ekavacana, c.i.23, ii.35, iv.2, xiv.22.
 ekavarṇa, i.54.
 ekavīṇatī, xxii.12.
 ekagruti, c.xv.9.
 ekasvara, c.xv.7,9.
 ekādāśāsah, xi.16.
 ekādeṣa, c.i.4, x.10,12.
 ekāntara, ii.25.
 ekāra, ii.15,23, iv.8,40, ix.11, x.4,6, xi.1.
 ekikarapa, c.xiv.15.
 ekibhāva, -bhūta, c.i.1, x.10.
 ekāika, c.i.11, xiii.11.
 epī, xiii.12.
 eta (pron.), iv.20,25,48, v.24, viii.6, x.23, xxi.14, 15, xxiv.5: c.xiv.4.
 etana, x.14.
 etāvant, c.i.1,15, ii.47, iv.23, etc.
 eta, iv.44.
 enam, vii.8.
 enam abhī, iv.42.
 end, v.17.
 ene, iv.11.
 epha, i.19.
 eman, x.14.
 eva, ix.5, xiv.3, xix.4, xx.2, xxii.6, xxiv.5.
 eva, iii.6, iv.44; eva rase-
 na, iv.24; eva smān,
 v.21; eva ttare, iv.11.
 evah, x.14.
 evakāra, c.xix.4.
 evam, xviii.8, xxiv.4.
 eśah, v.15, xi.16, xiv.8.
 eśhah, viii.8,18, x.14.
 dikāra, ii.26, ix.14, x.6, xvi.24.
 dikshav, iv.12.

- āirayan*, v.21.
ākāra, ii.13, iv.6, ix.7, 12, x. 5, 7, 22, xi.1, xviii.1.
oñkāra, c.11.
otva, ci.51, viii.8, 16, 19, 21, ix.7, 8, xi.5, xvi.29.
odman, x.14.
one, vii.10.
oshadhī, iii.7.
oshadhik, v.17.
oshtha, ii.12 (-*hana*), 14, 21, 24, 39; -c ii.25, xxiii.2; and *adhāro*, *uttaro*.
oshtha, x.14.
oshthinta, ii.43.
oshthya, cii.25.
aukāra, ii.26, ix.15, x.7.
ka (k), viii.23, ix.4.
ka (pron.), xviii.2 (*cit*); *ke-cit*, ci.57, viii.15, xi.1, 3, 9, xii.3, xiii.13, xiv.4, 5, 11, 15, xv.9, xvi.2, 12, xxiii.17.
kak, viii.9.
kakāra, v.32, viii.31.
kakut, viii.4.
kakshivān, ix.21.
kathinātā, cxxii.9.
kantha, ii.2, 3, 4, 46, xxiii.10; -c ii.47, xxii.10, xxiii.2, 17 (-*mūliya*).
kanthokta, ci.59, 59 (-*tea*), iii.8, iv.41.
kanthokti, ci.14, 59, vi.3, 5, viii.15.
kanva, xiii.9.
r. kath, ci.11, 53, ii.33, 47, v. 28, xi.3, xv.9, xviii.3, xxiii.17.
kathana, civ.23, v.26, xx.7, xxiii.17.
kanishthikā, cxxiii.17.
kaninika, iv.11.
kaniya, xvi.13.
kapālān, vi.14.
kam u, vi.2.
r. kump: + *pra*, cix.3.
kampa, cxix.3, 5.
r. kar, ii.4; -ci.61, v.3, 35, etc.; *kārya*, cii.14 etc.; *karāṇiya*, cxxiii.12; + *a* *dhī*, ci.1, viii.5, xii.9, xiv. 14, xxi.6; *adhikṛta*, cii. 1, iv.1, etc.; and *adhī-kāra* etc., *kārya*, *anadhī-kutra*, civ.23. *kṛtata*, *prakṛta*, *vikṛta*, *kuṭrā*, iii.10, etc., *vāḍṛta*.
karāṇa, ii.27, 32, 34, 45, xxiii. 2, 6 (-*vaf*); -c ii.20 etc., xxiii.2, xxiv.5.
kareṇu, cxxi.15.
karo, viii.30.
karṇa, civ.52, xxiii.17 (-*mūliya*).
karṇakā, iii.5.
kartṛta, cii.2.
karmata, cii.2.
karmadhāraya, cx.6.
kurman, cxxi.14, xxii.3.
karvina, cxxi.15.
r. karsh: + *anu*, ci.51, viii. 34, xxiii.18; + *ā*, ci.22, 43, ii.17, vii.6, 7, viii.4, 15, ix. 4, 20, etc.; + *saṃni*, cii.15, 24, 27, iv.23, xi.3; and *kṛṣṭa*, *anukarṣhaṇa*, *an-vākarṣha*, *ākārṣha*, *saṃnikarṣha*.
r. kalp, xiv.28; + *vi*, ci.21.
kalpayanti, iv.15.
kalyāṇi, xiii.12.
kavarga, ii.35; -c ii.44.
Kaṇyapa, cxxiv.6 (-*gotra*).
kāṇikāṣhī, cix.21 (-*vaf*).
kāṇa, xiii.9.
kāṇḍa, ci.61, iii.9, ix.20.
Kāṇḍamāyana, see p. 430.
kāmacāra, cii.7.
kāra, i.16, xxii.4.
kāraṇa, cii.1, xvi.26, xxiii. 3, 19.
kārya, ci.55, 60 (-*sva*), ii.13, iv.3, 7, 11, v.1, viii.13, 15, ix.7, 24 (-*sva*), xiv.5, xvi. 2, xix.5 (-*anu*), xxiv.2.
kāryabhāj, ci.25, 55, 58, 61, iii.1, iv.23 (-*sva*), xix.4 (-*anu*).
kārshṇa, iv.12.
kālā, i.33 (-*śamāna*), 37, xvii. 5; -ci.1, 35, 36, vi.4, x.12, xi.12, xxi.1, xxii.13, xxiii. 2, xxiv.5, 6; and *padak*.
Kālanirṇaya, cxxviii.1.
kāṇḍila, *kāṇḍila*, xvi.26.
kāṇḍa, ci.21, ii.47, iv.23, v. 22, etc.
kāṇḍa, ci.21, 53, 61, ii.18, 23- 5, iv.23, vii.15, viii.13, ix. 7, etc.
ku (= *kavarga*), cii.47.
r. kuc: + *saṃ*, ci.15.
kuṇapam, xiii.12.
kuṇḍala, -*lin*, civ.52.
kuṭoh, ci.18, 21, ii.23, v.22, etc.
kurū, v.6.
kuryāt, iv.52.
kūṭastha, cv.2.
kṛṇutā, iii.10.
kṛṇudhvañ sadane, iv. 11.
kṛṇvan, vi.14.
kṛdhi, viii.26.
kṛdhi suvaḥ, vii.2.
kṛdhi, iii.13.
kṛṇamadhya, cxxiv.6.
kṛṣṭa, xxiii.12, 14.
kṛṣṇaḥ, iv.38.
kṛṣṇāṅghri, cxxiv.6.
kēna, viii.8.
kevala, ci.18, 43, 59, ii.47, xiv.33, xxi.1, 2, xxiv.4.
kāicālyā, cxx.12v.
komala, cxx.12.
kāṇḍeyak, xiii.12.
Kāṇḍiṇya, see p. 430.
Kāṇḍaleya, see p. 430.
kra, viii.26.
kraśsyate, xvi.22.
krato, xii.8.
r. kram: + *ati*, civ.23, xvii. 8, xxiv.4; + *pra*, cx.15.
krama, xxi.16, xxiii.20, xxiv.5, 6; -c ii.9, xxiii.16, xxiv.2.
kraṇi, iii.13.
kriyā, cxxiv.4.
r. kṛg, cvi.9.
kṛuṣṭa, cxxiii.12-4v.
krūram, iv.25.
kvacit, cxiv.28, xxi.6, etc.
kṣha (*kṣh*), ix.3.
kṣhāmā, iii.10.
r. kṣhip: + *adhi*, cxv.9; + *nī*, c ii.18; + *pra*, cxiv.11.
kṣhira, cxviii.8, xxi.1.
kṣhāipra, xx.1, 9; -c xx.8.
kha (*kṣh*), viii.23.
kha, xxii.9, 10.
khanana, cii.1.
khalu, ci.18, ii.23, iv.32, 37, etc.
khi, xiv.8.
r. khyā: + *ā*, cix.20, xx.8; + *vyā*, cxiii.16, xiv.5, xxi.3; and *akhyā*, *vyā-khyāna*, *saṃkhyā* etc.
gakāra, cxiv.23.
r. gaṇ, cxvii.6v.
gaṇa, xiii.9.
r. gud: + *nī*, ci.60.
r. gam, i.50, xxiv.6; -ci.33, xiv.3, 4v; + *ava*, ci.33v, 51, xx.7; + *upa*, cxvi.3; + *saṃ*, cv.1; and *adhī-gama*.
gamanikā, ci.18, viii.16.
gamayataḥ, iv.52.
r. gar: + *saṃ*, ci.21, xi.1.

- garbhah*, xii.3.
garbham, iv.24,42.
gala, cxxii.9 (-vivara).
gāṇa, cxiii.9.
gātra, cxxii.9,10.
gāṇām, *gāni*, vii.10.
Gāruḍapurāṇa, cxxiv.6.
gāhamānāḥ, xii.8.
gīr, cintr.
guda, cviii.16.
gūṇa, ci.35 (*dvī*), 36 (*trī*), xv.3.
guṇa, xiii.9.
gura, xxii.14: -cintr.
gurutva, xxiv.5.
grāhāmy agre, xi.16.
go, xi.16.
gotra, cxxiv.6.
gomān, ix.21.
gūṇa, c.v.23.
Gāntama, see p. 430.
gaurava, ci.33, iv.23, viii.13.
gna, xii.5.
gni, iv.36.
gyāni, vii.10.
grantha, cxxiv.64.
r. grah, cintr. i.22,25,50,51, 59, ii.15, v.25,40, vi.13, viii.18,34, ix.13, x.12, xi.17, xiv.6,22, xv.8, xvi.29, xviii.4: + *pari*, cviii.14, ix.9.
graha, ix.20.
grahana, i.22,24,50: -ci.18, 22,26,50-3,59,61, ii.23, iii.1 etc., iv.9 etc., v.7 etc., vi.5 etc., vii.2 etc., viii.4 etc., ix.1 etc., x.9 etc., xi.3 etc., xii.3 etc., xiii.4 etc., xiv.17 etc., xv.1 etc., xxi.7, xxiv.2.
grāma, vii.2.
grāmi, iv.53.
grdhaka, ci.21.
ghakāra, viii.26.
r. ghat, cxiii.15, xv.6.
ghata, cii.7, xxii.3.
gharmāsah, xi.5.
ghā, iii.8.
ghuṣhyā, iii.12.
ghṛṣṭavān, v.21.
ghoshavanā, i.14, ii.8, viii.3, ix.8: -ci.14 (-*vattva*), etc.
ghni, iv.28.
ghrāṇābala, cii.52.
ha, v.32.
hakāra, ix.18.
ca (c), v.4,20,22, xiii.15.
ca, i.22,32-4,53,55,60, ii.13, 17-9,23,42,51, iv.7,13,16, 18,25,26,46,47,50,54, v.5, 7,15,28,30,33,36,37,41,vi.3, vii.3,6,7,14,16, viii.4,15, 17,18, ix.4,8,19-22,24, x.16,17,25, xi.4,6,7,9,11,12, xii.6,10,11, xiii.3,14, xiv.2,4,6-8,17,19,20,22,28, xv.1,4,7, xvi.4,9,10,12,18, 23,28, xvii.4,5,8, xix.2, xx.10, xxi.5,6,9, xxii.5, 14,15, xxiii.2, xxiv.2,5.
caḥāra, v.22: - (=ca) c.v.28, 30,33, etc.
caḥrmd, iii.10.
caḥre, iv.28.
r. caḥsh: + *d*, xxiii.16: -c ii.44: + *vyā*, cxv.9v, xxi.15: + *samā*, ci.1.
caḥshushī, iv.12.
caḥkūṇa, xiii.12.
catuh, vi.13.
catur, i.8, xxi.15, xxiv.1.
caturtha, i.11, ii.9, v.38,40, xiv.5, xxiii.12,16.
caturyama, xxiii.16,19: -c xxi.17,18.
catuṣṭaya, cxxiii.19, xxiv.2.
candra, v.5.
r. car: + *ut*, ci.12,13,28,35, 44,50, iv.23, v.1, xvii.8, xxi.15, xxii.9,10: + *oya*, bhi, cii.25: and *uccāra*, na.
carā, iii.8.
carāvaḥ, iv.38.
carman, xiii.13.
carshaṇ, xiii.13.
carshaṇi, iii.7.
carvaga, ii.36: -c ii.44.
cāturya, cxviii.3.
r. ci: + *nih*, ci.1, xiv.4, xxi.16: and *niṣcāyaka*.
cikītvān, ix.21.
cit, xviii.2.
r. cit: *cintya*, cii.19, xii.3.
citi, iii.7.
citra, iii.4.
ci, iv.33.
r. cud: *codya*, ci.14,53, iv.11.
cupuṣṭikā, xiii.12.
cṛdā, iii.12.
ce, xx.3, xxi.9: -c ii.25, etc.
co 'ttame, iv.11.
cha, v.22, xiv.8.
chaṣṣine, xvi.13.
chakāra, v.34.
chateva, c.v.22,35,37.
chandāsvatī, iv.20.
chandobhāshā, xxiv.5: -c xxiv.6.
ja (j), v.23.
jakāra, v.23, xii.5.
jakshivā, xvi.13.
jagāmā, iii.10.
jaghanya, cviii.13.
jaghniṣā, xvi.13.
jajñe, xi.16.
jatā, ciii.1, xi.9,16,17, xx.2.
r. jan: *jāyate*, xxiii.2: *jan*-*yate*, cii.8, v.1.
janayathā, iii.10.
janayā, iii.12.
janishvā, iii.8.
janman, cii.1.
janmani, iv.12.
janya, ci.40.
janbhya, ii.17.
jayatā, iii.19.
jala, cii.1.
jāta, cxv.9 (*varṇa*), *jātaḥ*, viii.32.
jāti (-*tyapekshā*), cii.35, iv.2.
jāyamānāḥ, xii.8.
jāla, ci.46, viii.22.
jigā, xvi.13.
jigāsi, xvi.18.
jigivā, xvi.13.
jigdhā, xvi.13.
jigdhāsi, xvi.18.
jihvā, ii.20.
jihvāgra, ii.18,37,38,41 (-*madhya*): -c ii.19,20, xxi.15.
jihvāmadhya, ii.17 (-*anta*), 22,36,40 (-*anta*): -c ii.20.
jihvāmūla, ii.35.
jihvāmūliya, i.18, xiv.15: -c ii.44.
jihvikā, cviii.16.
jigivā, xvi.13.
jushāṇāḥ, xi.16.
jushṭa, xi.3.
jukutā, iii.12.
-jha, xxiv.6.
r. jhā, xx.2: -ci.29,50, x.17, etc.: *jñāpay*, c.v.40, xii.6,11, xvi.9,10, xix.2: + *vī*: *vijñeya*, xxiv.5: -c i.7,52, 53,61, ii.18, etc.: + *sam*, cxx.1: and *vijñeyatva*.
jñāpaka, c.v.47.
jñāpāna, cviii.18.
jñā, iv.39.
jyā, x.13.
jyāyā, xvi.13.
jyotih, vi.13.
ñakāra, v.24,37.

- ta (t), v.33, vii.13, xiii.15.
 tatva, ci.21.
 tavarga, ii.37, xiii.11, xiv.
 20: -c ii.44, xiv.28.
 tavaryiya, c xiii.14.
 tha (th), vii.14.
 da (d), xiii.16.
 dakāra, civ.38.
 na (n), xxi.14.
 nakīra, vii.1, xiii.6.
 natva, ci.51,60, v.3, vii.2
 etc., xiii.7 etc.
 nīc, ci.17.
 ta (t), vii.13.
 ta (pron.), i.33,41,49, ii.3,7,
 31-4, v.27,38, ix.2, xii.9,
 xiv.9, xix.3,4, xx.4, xxi.2,
 13, xxii.2, xxiii.13,16-9.
 takāra, v.22,33, vi.5,14, vii.
 15.
 tat, ix.17.
 tatabh, xv.3, xxii.14.
 tatra, v.3, xxii.3,12.
 tatrā, iii.8.
 tathā, xxii.14.
 tathāstva, ci.43, ii.20.
 tathābhāva, ci.61.
 tadānīm, ci.21.
 tadāstha, cxiii.9.
 tanuvāu, iv.44.
 tanū yat, iv.52.
 tantu, ci.7.
 tapatā, iii.12.
 tapasah, xii.8.
 tapasi, iv.17.
 tamasah, viii.24.
 r. tar: +ava, ci.9.
 taratā, iii.12.
 tarā, iii.8.
 tarhān, vi.14.
 tarhi, ci.15,21, ii.25, iii.8,
 etc.
 tavarga, ii.38, xiv.20,21:-
 c ii.44.
 tavaryiya, xiii.15.
 tasthivā, xvi.13.
 tasmat, ix.17.
 tasmān, vi.14.
 tātparya, ci.15,24,35,36.
 tān, vi.14.
 tābhyām eva, iv.52.
 tānra, cxiv.6.
 tāra, xxii.11, xxiii.5,10.
 tālu, ii.22,36,40.
 tāvant, i.35:-c i.1,41,56, ii.3,
 25, vii.16.
 tishthān, vi.14.
 tishthantya ekayā, v.19.
 tishthā, iii.12.
 turalara, xvii.1,4:-cxvi.24,
 xvii.2,3 (-tea).
 tu, i.19,59, ii.14,25,29,33,45,
 iv.40, viii.16, ix.9, x.19,
 21, xi.1, xiv.5,11, xv.3,8,
 xviii.1, xx.2, xxii.6, xxiv.
 5.
 tu, iv.42, v.13.
 tulya, ci.33, ii.19 (-tea), xiv.
 23.
 tū, iii.14.
 tūnave, xiii.12.
 tūshatm, ci.20 (-bhāva,
 -bhūta), xxiii.6 (-bhāva).
 tṛ, xvi.27.
 tṛṇṇe, iv.11.
 tṛtiya, i.11, viii.3, xxiii.12,
 16:-ci.61 (-tea), xxiii.10
 (-savana).
 tṛdyē, iv.11.
 te, iv.40,42, xi.10.
 te asya, iv.20.
 te ācaranti, iv.20.
 Tāittirīya, xxiii.16,15 (-ka).
 tāirovyaṅjana, xx.7,12:-
 cxiv.29, xx.8.
 trapu, v.4.
 tri, i.20, xxiii.11,14.
 trī, vii.2, xvi.25.
 trih, i.36.
 tripadaprabhṛti, i.61:-ci.
 59,61 (-tea), xi.9,18.
 Tribhāshyaratna, c intr. and
 endings of chapters.
 trimātra, xxii.13.
 triripa, ci.36.
 tri, vi.2.
 trin, vi.14.
 trāividyā, c ii.3.
 teah, xi.5.
 tvañ tard, iii.8.
 r. tva: atvaritam, cxiii.
 20.
 tvashṭah, viii.8.
 tvā, iii.5.
 tvishṭi, iii.7.
 tve, iv.10.
 tha (th), iv.7, vii.14.
 -the, iv.40.
 da (d), iv.7.
 dañṣukā, dañṣhtrā-
 bhyām, dañsam, dañ-
 sanābhyah, dañso-
 bhik, xvi.19.
 dakāra, v.8.
 dakshinena, iii.10.
 datte, xi.5.
 dadāsi, xvi.18.
 dadhānah, xii.6.
 dadhāsi, xvi.18.
 danta, ii.43:-c ii.18 (-pañkti).
 dantamūla, ii.38,41,42.
 r. dar: +ā, ci.21, xiii.16.
 darvi, iv.12.
 r. dars, ci.1, ii.2,5, iv.11,
 viii.16, ix.22, x.10, xiv.5,
 28.
 darṣana, ci.59, ii.1, iii.1
 (ad-), xi.19 (ad-), xii.3
 (ad-), xiv.5,15, xv.9v, xvi.
 26.
 r. dā: +anupra, ci.8; +u-
 pā, ci.7,8; and anupra-
 dāna, upādāna.
 dādāhāra, iv.22.
 dāruṅga, xxii.9.
 dārdhya, cxvii.1.
 dārdvā, xvi.13.
 divah, viii.24,28.
 divi, vi.2.
 r. diḥ: +ā, cxv.4v; +anvā,
 ci.26,32,51,55,60, ii.19,
 etc.; +ut, civ.2,52, x.11:
 +upa, xxiii.18:-c i.1,60,
 vii.1, xxiii.6,17; +uñh,
 ci.29, ii.7,23, x.23, xiii.
 9v, xxiii.17, xxiv.5; +pra-
 tinah, ci.7; and anvāde-
 ṣa, -ṣaka, ādeṣa, -ṣaka,
 nirdeṣa, -ṣaka.
 r. diḥ: +sam, cxiv.4.
 didivā, xvi.13.
 dipa, cxviii.3, xx.12 (-vat).
 dṛptiya, xxiii.13.
 diyā, iii.12.
 dirgha, i.3,35, viii.17, x.2,
 xxii.14, xxiv.5:-c ii.24,
 iii.1, v.12, etc.: and dāir-
 ghya.
 dirghā, iii.5.
 duhṣiṣṭha, cxiii.16.
 dundubhi, cxviii.3.
 durbala, cxvi.19, xxi.1.
 duryān, ix.21.
 dṛ, xvi.27.
 dṛdha, xvii.6, xx.9 (-tara):
 -c ix.5, xx.10.
 dṛdhay, cxviii.19.
 dṛdhe, iv.27.
 dṛṣṭanta, cxiii.15.
 deva rishah, viii.24.
 devatā phalgunt, iv.12.
 devate, iv.11.
 Devadatta, ci.14, iv.52.
 devā, iii.2.
 devān, vi.14.
 Devipurāṇa, cxxiv.6.
 deḥa, i.59:-c i.29, ii.17, viii.
 21, xix.3.
 deha, cvi.9.
 dāirghya, cxvii.9.

- dosha*, iv.23, xiv.15,22, xvi.19,29, xxiii.20.
dāurbalya, c.vi.5.
dyavi, vi.2.
dyāvapṛthivī, iv.12.
r. dyut, ci.61, iv.10, v.15, x.19, xiii.14, xxiv.6v.
dyotaka, civ.11.
draviṇḍ, iii.5.
dravya, xxii.3.
drāghīyā, xvi.13.
druta, cxxi.1 (-vṛtti): and *adr-*.
dva, i.3, iv.45, viii.20.
dvandva, ciii.9, x.6.
dvaya, civ.23,52 etc., xiv.4.
dvār, cxxi.6.
dvārdu, iv.38.
dvī, i.35.
dviguṇa, ci.35.
dvīya, i.11,12, xiv.5,12, xxiii.12,14,15,16: -ci.28 (-yā), xxi.12.
deiva, cv.3, xiii.4, xiv.2 etc., xxi.5,16, xxiii.20, xxiv.5 etc.
devīmatra, xxii.13: -c xviii.1 (-tā).
diviyama, xix.3, xxiii.17: -c xix.4.
divīrūta, cviii.16.
divīrūpa, ci.35.
divīroshṭhya, cii.25.
divīvacana, ci.23, ii.15, v.25, ix.13, xiv.6.
divīvarṇa, ix.18, xiv.1: -c xiv.2-4.
divīvara, xvi.17.
dve, iv.49.

dha (*dh*), viii.33.
dhakāra, cv.23.
dhātte, iv.53.
r. dhar: + *ava*, cxvi.12, xxii.6: and *acadhra*, -*ra*-*ṇa*.
dharma, ci.1, iv.52, v.28, viii.15, x.10,11, xv.8 (-tā), xxi.1,10,15.
-dharma, cx.10.
dharma, ci.1, v.28.
dhārshā, iii.8.
r. dhā: + *abhi*, xxiv.3: -c xiv.5,28, xviii.3,7; + *vyasa*, ci.17, iv.51e, xiii.7,14, xiv.30; + *abhyā*, ci.46; + *abhin*, cxiv.9; + *vī*: ci.34, iv.28,41, xiv.4; *vīhī*-*ta*, cii.47, xi.4, xiii.15, xvi.29, xxi.1, xxi.15, xxiv.2, yathāśchitām, cviii.24,26, 27,29-34, ix.24, x.18; + *sa*, cv.3: and *asāhī*-*ta*, *abhidhāna*, *vidha* etc., *vihī*-*tata*, *vyavadhāna* etc., *saṁdhāna* etc.
dhā, x.13.
dhāyikā, xiii.12.
dhātā rāṭhī, xi.3.
dhāma, xiv.8.
dhāmā, iii.8.
dhārāyā, iii.8.
-dhī, vi.11.
dhī, iv.12.
dhīra, xviii.8.
dhīrāsah, xi.16.
dhūh, v.10.
dhṛta, xviii.3 (-*pracaya*): -c xxi.17.
dhṛtavant, xxiii.20.
dhṛtavarate, iv.11.
dhruvakshīṭhī, xi.3.
dhvani, cii.1, xxii.1, xxiii.6.
dhvāna, xxiii.5,7.

na (*n*), iv.32, xii.4, xxi.14.
na, i.4,13,18, ii.12, iv.2,14, 21,30,32,37,39,41,43,53, v.16,21,29,35,37, vi.6,11, 13, vii.15, viii.7,14,19,26, 32,35, ix.3,6,13,17,23, x.13,18,20,24, xii.3, xiii.4, 15, xiv.14,24,31,32,33, xv.2,5, xvi.7,11,17,31, xviii.8, xix.5, xxi.7,11,16, xxii.8.
-na-, xvi.21.
na, xi.13.
na *pṛthivī*, iv.19.
nakāra, v.20,24,26,33, vii.1, ix.19, xiii.6, xv.1, xvii.4.
nakī, vi.5.
nañ, ci.60, viii.33, x.22.
namu, ci.1,2,15,18,21,53,59, ii.7,9,18,20,23,25,47, iii.1, iv.3 etc., v.1 etc., vi.3, viii.13 etc., ix.8 etc., x.10,25, xiii.9,15, xiv.4 etc., xvi.2 etc., xviii.3, xx.2, xxi.1,5.
r. nam: in *vinatā*.
nama, iv.42, viii.30, xi.14.
navan, i.2.
naḥyati, vii.16.
nā, iii.8.
nāda, ii.4,8, xxiv.5: -c ii.3, xxi.2.
nānāpada, i.48 (-*pat*), xx.3 (-*stha*), xxiv.3: -c xx.4 (-*stha*).
nānāpadīya, i.60.
nānābhūta, cxxiv.3.
nābhī, iv.12.
nāmata, cxxiii.5.

nāmadheya, xx.8: -c xviii.3, xxi.15.
nāman, ci.11.
nāsikā, ii.3,49,52: -c ii.30.
nāsikya, i.18, ii.49,50 (*mu*-*khan*), xxi.8,12,14: -c ii.50,51, viii.15, xxi.13.
nā, i.15.
nā, vi.4,5, vii.2, viii.24,35.
nītarām, ci.59, v.28.
nīlānta, xvi.24.
nīlga, i.59, iv.14,39,43,54, vi.5,14, xiv.6, xvi.9,17, xx.2,9: -c i.57 (-*tā*), iv.40, x.12, xii.11, xiv.5 (-*tea*), 19, xx.8, xxiv.5: and *an-*.
nīpāṇa, cxxiv.6.
nīmada, xxiii.5,8.
nīmitta, i.60: -c i.11,22,25, 58, iv.3,6,40,47,52, v.9, 22,35, ix.10 (-*tea*), 19,22, 24, xi.5, xiii.7,15, xiv.22, 28, xvi.8 (-*tea*): and *pa-*-*ran*, *pārva*-*n*.
nīmittin, ci.58, iv.3,45,47, x.16, xiii.15, xiv.28, xv.8.
nīyata, see *r. yam*.
nīyama, ci.21,49e, ii.23,25, 44, iii.1, iv.23,52, v.22, viii.8, xii.8, xiii.15, xiv.4, 5, xvi.2,8, xxi.1, xxiii.16.
nīrāpeksha, cxxi.1.
nīrāyaka, ci.15.
nīrākaraṇa, ci.57, x.22, xiii.13, xiv.22.
nīrūpaka, cxxiii.20.
nīrūpaṇa, cxxi.10.
nīrūpa, ci.1.
nīrdeṇa, ci.14, ii.43, iv.3, v.24, viii.6, xiii.9, xxi.4.
nīrdeṇaka, xxii.4: -c i.59.
nīrvāha, civ.3.
nīvartaka, ci.33, iv.40, x.21, xv.8, xvi.9.
nīvṛtti, cii.33,45, viii.32, xiv.5,18, xxii.6, xxiii.6,19.
nīccōdāya, cxxi.5 (-*tea*).
nīshedha, ci.21,59, iv.14,23, 40,41,54, v.16,30, vi.5 etc., vii.2 etc., viii.15 etc., ix.4 etc., x.15 etc., xi.1,5, xii.8, xiii.4 etc., xiv.4 etc., xvi.12,18,29 (-*tā*), xx.2, xxiv.5.
nīshedhaka, cxxiii.5.
nīshpādīyata, cii.20,23.
nīhata, cxix.3,4 (-*tea*).
nīca, i.39, xix.1, xxiii.20: -c xviii.4, xx.3, xxiii.17.
nīcata, xxiv.5.
nīcā, v.8.
nīcādhika, xxii.10.

- nidāstara*, i.44.
nu, v.13.
nudd, iii.8.
nū, iii.14.
nūnam, vii.16.
nr, vii.9.
nrtyanti, vii.16.
nemir devān, vi.14.
neṣṭaḥ, viii.8.
naimūtika, cix.22, xiv.28v.
nārantarya, cxix.3.
nyāya, ci.59, ii.17, 25, 51v, iv.23, 51, v.35, viii.16, xi.18, xiii.15, xiv.4, xvi.19.
nyāyga, cxiv.5.
nyāna cintr., i.42 (-tea), ii.23, 23 (-tea), xxiii.20.
-nati, iv.29.
pa (p), iv.28, 30.
paḥāra, v.36, viii.23.
paśha, cix.23, 49, v.30, viii.13, ix.6, x.20, xiv.10, 11, 17, xv.3, xviii.5, 7.
paḥka, cix.23, xiv.4.
paḥkti, ci.18.
pañcan, i.10.
pañcan, xxiii.2: -c xxi.14 (-mi).
pañcaviṣṭi, i.7.
paṭa, ci.7, v.28.
r. paṭh, ci.51, v.1, 2, ix.20, xxiv.3, 5.
paṇi, *paṇim*, xiii.10.
paṇeta, xiii.12.
paṭaṇḍān, ix.23.
Patañjali, cxxi.1.
pataye, *patih*, *patim*, viii.27.
patir nah, xi.16.
pati, iv.35, viii.27.
patē, viii.27, xii.8.
patni, vi.7.
patni ve, viii.27.
pathe, viii.25.
r. pad: +d, ci.1-15, v.9, 10, 20-25, 34-7, vi.1-14, etc.; *āpanna*, ci.51, v.35, x.10, xvi.3, 15; *āpād*, ci.7, xxi.6; +t, c vii.15; +upa, ci.1, ii.47, iv.3, 52, v.1, 35, viii.18, xiv.28, xvi.19; +nik, cxiv.5; +pra-
ti, c vi.13, viii.15; +sam, xxiii.20; and *anupapana*, *āpatti*, *āpādaka*, *ūpatti*, *upapatti*, *nishpādyā*, *pratiṭṭi*.
pad, iv.44.
pada, i.50, 54, vi.4, viii.9, xv.7, xvi.17, xx.2, 6, xxii.13 (-vīrāma): -c v.1, 2, 3, 10, 12, vi.8, viii.33, ix.1, xiv.5, xx.2, xxiv.6, etc.; and *ekap*, *nānāp*, *prakṛtip*, *saṃanap*.
padakala, ci.60, vi.4, viii.9, xv.7, xx.2, 4v.
padakrama, xxiv.5.
padagrahaya, i.50: -ci.51-3, iv.11, v.12, ix.22.
padapātha, cix.5, v.2.
padasaṃhitā, xxiv.2, 3: -c xiii.5, 14, xxiv.4.
padasamaya, c vi.14.
padādi, xvi.2, 8: -c iii.1, 15, etc.
padānta, xiv.28, xvi.14: -c iii.1, iv.3 (*ap*), 5, ix.11-15 etc. xiii.13 (-tea).
padārtha, c xiii.14.
padī, vi.2.
padādikadeśa, ci.23, 50, iv.35, 54, vi.10, 12, vii.6, 11, viii.28, 29, xi.15, 17, xii.6, xiii.14, xvi.26, 29.
padādhātī, cxiv.4.
pāpivā, xvi.13.
payoh, xvii.8.
payasvān, ix.21.
para, i.8, 9, 30, iv.18, 45, 47, 50, v.7, 10, x.16, 25, xiii.16, xiv.4, 9, 22, 29, xvi.19, xxi.5, 9; -*para*, iii.1, 3, 4, iv.4, 6, 24, 28, 30, 32, 33, 37, 38, 42, 44, 46, 52, v.4-6, 8, 14, 17, 20, 22, 23, 25, 27-30, 32, 37, vi.5, 14, vii.15, viii.2-4, 7, 11, 12, 14, 16, 23, 25-31, 34, ix.1-5, 7, 8, 10, 13, 20, 22, 24, x.2, 4-8, 13, 14, 22, xi.9, 15, 18, xii.4, 5, xiii.2-4, 11, 15, xiv.1, 9, 11-13, 16, 17, 19-21, 23, 24, 26-8, 31, xv.4, xvi.1, 2, 10, 14, 27, xix.3, xxi.7, 9, 11, 12, 14, 16, xxi.15; *para*, xxi.2.
parataḥ, c v.24, viii.6, x.10, 11, xx.3.
paratra, c viii.33.
parateva, ci.15, 30.
paranipāta, ci.2.
paranimitta, cix.7, 25, v.24, viii.6, 23, xiv.5, xvi.14v.
parabhūta, c viii.33, xx.4.
paramā, xiv.8.
paraspara, ci.3, v.2 (-rān-
voya), xv.6 (do).
parāmarjīn, ci.7.
pari, i.15.
pari, vii.4, viii.28.
pari ed, viii.34.
parikalpanā, c xvi.7v.
parigraha in *ap*.
paribhāṣā, cix.52.
parimāṇa, xxiii.2: -ci.37.
parisamāpti, ci.61.
parihāra, cintr., i.14, 21, 53, 59, ii.9, 20, iii.1, iv.54, v.28, viii.18, ix.8, xiii.14, xvi.13.
pari, iii.7, vii.4.
parikṣaya, cxiv.5.
parikṣā, ci.1.
paruh, viii.32.
paryanta, ci.5, 6, iii.9, etc.
paryavasāna, ci.1.
paryāya, ci.47, ii.47, xiv.22, xix.3, xxi.16, xxii.3.
pavarga, ii.39, ix.4: -c ii.44.
payu, ci.14 (-mant), xxiii.7v.
paśūn, vi.14.
pā, x.13, xvi.2.
pākavati, c xxi.13.
pātha, ci.15 (*viśeṣa*), iii.1, vi.12, vii.16, viii.27, ix.21, x.13, xiii.16, 16 (-antara), xvi.19, 20, 26v, 29.
pāthakrama, ci.1.
pāṇi, xiii.9.
pāṇinīya, ci.15, 53, xiv.4, xvi.1.
pāthak, xi.16.
pātha eṣak, xiv.8.
pāthā, ii.10.
pāda, c xxi.13.
pādavṛtta, xx.6, 12: -cxiv.29, xx.8.
pāyubhik, vi.5.
pārayā, iii.12.
pārīcchya, ci.4, 14, ii.23, xiv.28.
pār, iii.7, vii.4.
pārśve, iv.11.
pālay, c ii.17.
pāṅgalikāha, c xxiv.6.
pī, iv.7.
pītaḥ, viii.8.
pīṭrah, xi.16.
pīṭṭa, vi.14.
pīdhāno, c xvi.13.
pīva, viii.25.
pīṭikā, c xxi.13.
pībā, iii.8.
pīpivā, xvi.13.
pu, xvi.9, 13.
puṭhiga, ci.7.
pūnyo, xiii.9.
put, viii.28.
putrah, xi.16.
punah, viii.8, 32.
punarukta, i.61: -c i.33 (-tā), xi.9 (-tea): and *pāmaruktya*.
punarukti, c xxi.10.

- punarevacana*, c.viii.13, xxiii.7.
purastāt, c.i.43, iv.2, vi.5.
puvaka, xi.16.
pushpā, iii.5.
pūjā, cv.41, xiii.16.
pūti, iii.7.
pūrita, cxviii.8.
pūrṇa, xviii.8.
pūrṇa, iv.26.
pūrte, iv.11.
pūrva, i.29, ii.28, iv.13, 16, v.3, 31, 37, viii.17, xi.19, xii.9, xiii.9, xiv.5, xv.5, xxi.3; *pūrva*, i.4, iii.15, iv.7, 40, v.4-6, 8, 9, 12-14, 32-6, 38, vi.2, 4, 7, 11, 13, vii.2, 4, 7-9, 11-13, viii.16, 23, ix.9, 18, 20, 21, x.3, 9, 19, xi.1, 5, 8-11, 13-16, xii.3, 6, 8, xiii.6, xiv.1, 2, 6-8, xvi.4, 9, 11, xix.2, xx.2, 2 (ap-), 7, xxii.14; *pūrva*, ii.48, xv.1, xix.5; *pūrva*, xv.9; *pūrva*, c.i.1, ii.1.
pūrvaje, iv.11, 23.
pūrvatah, c.x.10, 11, xi.3.
pūrvatah, cxvi.19.
pūrvanimitta, cix.19, xi.5 (-*tea*).
pūrvapoda, i.49; c-iii.1, 15, v.3.
pūrvaparibhūta, c.x.2, 6.
pūrvokta, cii.19, etc.
pūshā, x.13.
pūta, xiii.16 (-*vara*), xxiii.3 (*varṇa*): and ap-.
prajavā, iii.8.
prthak, ii.23, 25, 25 (-*tea*), v.41, xiv.15, xx.10.
prthakkarana, c.iv.11, ix.8, 9, xiv.15, xxi.6.
prthivi, iv.19.
prthivi yajñe, xi.16.
prshati, iv.15.
prshāti, iii.7.
prshthe, xi.16.
prshthya, ix.20; c-ix.23 (-*tea*).
po, viii.29.
poshām, ix.21.
pāunaruktya, c.i.37, ii.47, iv.23, xiv.4, 22, 28.
pāurāṇika, cxviii.6.
pāurusha, cxviii.6e.
Pāṇishkurasādi, see p. 430.
pra, i.15.
pra, iv.33, vii.4, viii.34.
prakatay, cxviii.3.
prakarsha, cii.20, xiii.9.
prakāra, c.i.15, ii.6, iii.7, v.10, xxi.19.
prakāśaka, c.iii.9.
prakṛta, ii.25; c-i.35, ii.3, 7, 15, v.25, 30, vii.15, viii.6 (-*tea*), xv.8, xvi.16 (-*tea*), xxiii.20 (-*tea*).
prakṛti, ii.7, v.2, ix.16, xix.4, xxii.1, xxiv.5; c-iii.1, v.22 (-*tea*), x.24 (-*eat*), xiii.9-13, xiv.28, xix.3 (*svarita*), 4, xxii.2; and *prakṛta*.
prakṛtipada, c.iii.1.
prakṛshṭa, ii.15.
prakṛshṭana, c.iv.23, xiv.4.
pragraha, i.60, iv.1, x.24, xv.6 (ap-); c-iv.2 etc., x.15, xii.8, etc.
pracaya, xviii.3 (*dhṛtop*), xix.2, xxi.10; c-xxi.6 (-*tea*), 11, xxiii.16, 17, 17 (-*tea*), 20.
pranava, xviii.1; c-i.1, xviii.1-7.
pranyasta, ii.20.
prati, i.15.
pratidhvani, cii.3.
pratipatti, cxi.3.
pratipadapātha, cvii.16, vii.27.
pratiprasava, c.vi.13, xiii.8, 13, xiv.24, 32.
pratibandhaka, c.iv.39.
pratiṣṭeṣhāna, c.iv.11.
pratiṣrut, cii.3.
pratiśhedha, c.i.11, iv.43, v.36, 37, viii.13, xiii.8, 13, 15, xiv.4, 24, 32e, xv.3, xvi.17, xx.1, xxii.9, xxiii.6.
pratiśhedhaka, xxi.8.
pratiti, cii.23.
pratte, iv.11.
pratyak, ii.41; c-ii.42, 42 (-*tea*).
pratyaksha, c.viii.34, ix.9.
pratyagātman, cii.41.
pratyagāteea, c.i.34, xxi.1.
pratyaya, v.7; c-i.11.
pratyuddharana, c.xii.3.
pratyekam, cv.10, 15, xxi.15, xxiii.5.
prathama, i.11, 12, 27, ii.11, v.3, 38, viii.1, xi.3, xiv.9, 12, 17, xxi.16, xxiii.2, 14; c-i.23 (-*ma*), xxi.12.
pradipa, cxviii.3.
pradeṣa, c.i.59, ii.18, 42.
pradeṣini, cxviii.17.
pradhāna, c.i.58, xxi.2 (-*tā*).
pradhvaṁsin, cvii.15.
prapañcita, c.i.59.
prabandha, cxii.9, xiii.15.
prabala, cix.13.
prabhṛti, i.61, iv.22, 23; c-i.11, ii.3, iii.9, v.10, 38, xvi.18.
prayatna, xvii.6, 7; c-i.3, xvi.24, xviii.1, xviii.4, xix.5, xx.9-12, xxiii.6.
prayoga, xviii.4, 7 (*yathā*), xxiii.6; c-i.7, 18, 42, ii.7, xiv.28, xvi.19, xvii.6, 7, xviii.3, xxii.3, xxiii.10, 14, xxiv.3; and ap-.
prayojana, c.i.2 etc., ii.4-6, v.1, xiv.4, xvi.23, xviii.1, xix.1, xxii.11, 12.
pravaṇa, i.47.
pra varta, iv.52.
pravāda, xiii.9; c-xiii.9 (-*tea*), 10.
pragna, c.i.61, iii.9, iv.52, ix.20, xi.3, xiii.15, end'gs of chap. xii, xxiv., xiii.-xxiv.
pragṛhṣhta, xx.5, 11; c-xx.8.
prasakti, cxiv.4e.
prasaṅga, c.i.53, ii.9, iv.52, 54, v.22, xiv.22, xvi.2; and atip-.
prasaraṇa, cv.22.
prasiddhi, c.i.2, ix.7.
prasthā, iii.5.
prā, iii.5, vii.7.
prakṛta, vi.14, xiii.14, xiv.28; c-v.22, xiii.14.
prācūrya, cxiv.5.
prāna, v.1.
prātaḥ, viii.8.
prātahsavana, cxviii.10.
prātikūlya, c.i.46.
prātipadika, c.i.22.
prāṭīkākhyā, c.intr., and end'gs of chapters.
prāṭīkrutka, ii.3; c-xxii.2.
prātihata, xx.3, 11; c-xiv.29, xx.8.
prāthamika, c.iv.23.
prānta, cii.17.
prāpana, cxiii.14.
prāpta, c.i.13, 18, 19, 34, iv.43, v.3, 10, vi.14 (-*tea*), xii.8, xiv.19, xvi.29.
prāpti, c.i.59, iii.1, iv.14, 39, 43, 54, v.13 etc., vi.7 etc., vii.15-6, viii.7 etc., ix.3 etc., xiii.13-5, xiv.5 etc., xv.5, xvi.5 etc.; and atip-.
prābalya, c.i.59.
prekshāvanta, cxxi.1.
prevaṇa, cii.2.
pre, vi.2.
Plākshāyana, see p. 430.
Plākshi, see p. 430.

- pluta*, i.4,36, x.24, xv.7, xxiv.5; -ci.20, ii.12, iii.1, ix.9, x.15, xv.7 (-vut), 8. *pluti* in *maṇḍūkāp*-.
phaṇat, xiii.12.
phalguni, iv.12.
r. badh: + *upa*, ci.59; + *sam*, ci.21, xiv.18; + *abhisam*, cv.10: and *upabandha*, *prabandha*.
r. badh (*bādḥ*), ci.61, xvi.19: and *bādha* etc.
barsva, ii.18; -ci.ii.19.
bala, ci.53, ii.18.
balavant, cxvi.19, xxi.1.
bahule, iv.11.
bahuvacana, ci.23, v.24, viii.6.
bahusvara, iv.40: -c viii.10 (-*tsa*), xvi.12, 18 (-*tsa*).
bahūpādāna, cvi.10, 12, vii.6, 11, viii.10, 29, xi.15, 17, xiii.14, xvi.26.
Bāḍabhiḥkāra, see p. 430.
bāṇa, xiii.9.
bāṇavān, ix.21.
bāṇijāya, xiii.12.
bādha, -*dhana*, cxvi.19, xxi.5, xxiv.5.
bādhyā, cxxi.5.
bāhulya, civ.23.
bībhṛta *ta*, iv.52.
bībhṛtā, iii.10.
r. budh, ci.53, xiv.28, xix.4, xx.10, xxiii.2, xxiv.2; + *nī*, xxii.15.
budhniyā, x.13.
bṛhatkūpola, cxxiv.6.
bṛhadgala, cxxiv.6.
bṛhaspati, vi.7.
bodhaka, cxxi.1.4.
bodhana, cxvi.29.
bodhā, iii.8.
brahma ja-, iv.25.
brahma, xiii.13.
Brahmapurāṇa, cxxiv.6.
brahmaloka, cxxiv.6.
brāhmana, ci.61 (-*vākyā*), xiv.33, xxi.1.
r. brā, xviii.1: -ci.2, 36, 46, iii.1, iv.3 etc., v.22, 37, viii.16, ix.23, x.10, xi.9, xiv.4 etc., xviii.2, xix.3, xxi.1, 13, xxiii.20.
bhakti, cintr., xxi.6, 15.
bhaṅga, ci.53, ii.9, iv.52, v.10, 22.
bhaṅgura, iii.5.
r. bhaj, cv.26-30, 38, vii.5-16, viii.24-32, ix.2 etc., x.24, xi.19, xiv.5, xvi.2 etc., xxi.2 etc., 15 (*bha-jyamāṇa*): and -*bhāj* etc., *vidhājya* etc.
bhaja, iii.8.
r. bhāṭa, ci.15, 57, xxiv.3v.4, 6.
bhādrah, xii.3.
bhaya, cxiv.4.
bharatā, iii.11.
Bharadvāja, see p. 430.
bharā, iii.12.
bharishyanti, iv.19.
bharema, iii.10.
bhavataḥ, iv.52.
bhavatā, iii.12.
bhavant, ci.21, iv.23.
bhavā, iii.8.
Bhaviṣyatpurāṇa, cxxiv.6.
bhāga, cv.1 (*veda*-), xiv.28, xix.3 (*veda*-), xxi.15 (*sva-ra*).
bhāgadhe, iv.11.
-bhāj, cxiv.18 (*nīshedha*): and *kāryabhāj*.
bhājana, cxviii.8.
bhāma, cxviii.3.
bhāmītaḥ, xii.8.
Bhāradvāja, see p. 430.
bhāva, v.1, 31, x.17, xv.1, xvii.4, xx.1, 5: -ci.61, ii.12, viii.16, xxiv.5: and *abh*-.
-bhāvīta, ciii.1, x.12.
r. bhāṣh, ci.14, ii.14, 33, viii.19.
bhāṣhā in *chandobh*-.
bhāshya, cintr.
r. bhāṣ, cintr.
bhāḥ, viii.14.
bhinna, ci.3, 29, iv.11, xiii.15, xxiii.18.
bhīma, *bhīmasena*, cxviii.3.
bhūja, xiv.8.
r. bhū, ii.3, xxi.11, xxiii.4: -c v.1; + *sam*, ci.49, ii.7, iv.23, viii.13, xiii.15: and *sambhava*.
-bhūta, ci.2, iv.23, viii.5, etc. etc.
bhūte, xiv.8.
bhūyans, ii.11.
bhūyāṇaḥ, xvi.13.
bhūṣhaṇa, cintr., xvi.19.
bhūṣura, cintr.
bheda, civ.40, 47, viii.18, 21, xiii.9, xiv.22, 28, xviii.3, xxii.2, xxiii.7, 18, xxiv.4: and *abh*-.
-bhāṇam, viii.14.
-bhraṇate, xvi.22.
ma (*m*), iv.7, xv.1, xvii.4, xxi.14.
maḥ, xii.6.
maṇṣatāi, *maṇṣye*, xvi.20.
māhishṭhasya, xvi.28.
mākṛā, v.12, 27, 35, viii.4, xiii.1.
mākṣh, iii.14.
maṅgala, ci.1.
maṅca, cvi.9.
maṇi, xiii.9.
maṇḍala, cxxiii.16, 17.
maṇḍūkaphluti, ci.17, iv.51.
mata, ci.21, 59, ii.2, 19, 27, 47, v.1, 36-41, viii.18, 19, etc. etc.
matī, xvii.8 (*yathām*).
madhumān, ix.21.
madhya, ii.6, 41, 45, xix.1: -ci.10, ii.2 (-*deṣa*), viii.15 (-*stha*), xxi.15.
madhyama, xviii.4, xxii.11, xxiii.5, 10: -c xxiii.17.
r. man, ci.15, 18, 19, 21, ii.47, v.2, 31, viii.23, xiii.13, xiv.5, 33, xv.9, xviii.1-8, xix.3, xxiii.19; + *sam*, cv.41, xv.8: and *mata* etc.
manah, xxi.6.
manāḥ, vii.9.
mantra, ciii.9.
manda, cxxiii.20 (*am*-.).
mandadhi, cx.13.
mandra, xxi.11, xxiii.5, 10, 11, 12, 15, 16: -c xxiii.13.
manyamānaḥ, xii.8.
mayānī, vii.12.
marṭaḥ, xi.5.
martyān, ix.21.
maryādā, ci.1, iv.23.
r. marṣ: + *parā*, cxv.3: and *parāmarṣin*.
malimlu, vi.7.
mahān, ix.21.
mahāprsthya, xi.3.
Mahābhārata, cxxiv.6.
Mahābhāshya, ci.7, v.2.
mahī, vi.2.
mahī, iv.34.
mā, x.13, xvi.8; *md pā-tam*, iv.42.
mākiḥ, vi.5.
Mācākiya, see p. 430.
mātaḥ, viii.8.
-mātra, xviii.1, xxi.13: -ci.21, 56, 61, ii.13, 19, 25, 33, etc. etc.
mātrā, xxiv.6.
mātrika, cxxi.15.
mādhyaṇḍina, cxxiii.10.
Māyikāya, see p. 430.

- mārdava*, xxii.10.
māśah, *māśam*, *māsi*,
māsu, xvi.12.
māse, iv.53.
Māhishya, cintr., i.14, 59,
 ii.14, 35, iv.40, viii.19, 20,
 22, xiv.28, xviii.7.
mīthū, v.4.
mīthunā, iv.53, x.18.
mīthū, iii.14.
mīgra, cxxiii.3.
mīgrila, cii.23.
-misha, cxxiii.19.
mi, xvi.9.
-midhuk, vi.5.
Mīmāṃsaka, v.41.
mukha, ii.3, 59.
mukhya, ci.43, ii.23, 25, iv.
 23, 52, v.22, x.12, 12 (-*two*),
 xli.3, xliii.14, xliii.17: and
am-.
muñcā, iii.8.
muni, cv.31, xvii.1.
mushṭi, iv.12.
mūrdhā, ii.37: -c xlii.16,
 xliii.17.
mūla, cxliii.14, xiv.5 (-*sūtra*).
mūlakāraṇa, ci.8, xxii.1.
mṛdā, iii.8.
mṛtyu, vi.7.
mṛd, cii.7, xxi.3.
mṛdutarā, xx.11: and *mār-*
dava.
me, xi.11.
meghā, iii.5.
-m epā, xiii.12.
medhye, iv.11.
melana, ci.40.
mo, vi.2.
mṛṇa, xii.14.

ya (y), v.30, x.15, 19, xii.4,
 xiii.3, xiv.21, xx.1.
ya (pron.), ii.32, 34, xxii.14,
 15.
yañsat, *yañsan*, xvi.20.
yakāra, ii.40, ix.10, 20, xv.1,
 xvii.4, xx.2.
yajñsi, xvi.18.
yajyān, ix.23.
yajurveda, ci.15, xxiv.6:
 and *yajurvedika*.
yajña, iv.44.
yajñakarman, cxv.9.
Yajñadatta, ci.14.
yajñe, xi.16.
yaj, iv.33.
yatra, ii.31, 33, xix.1, xx.2.
yatrā, iii.8.
yatva, ci.4, viii.8, ix.7, 13,
 21, 22, x.18.
yathā, i.61 (-*ukta*), v.2 (-*yuk-*
raṅga, ci.1, ii.52,
 ta), xvii.8 (-*ma*), xviii.7
 (-*prayoga*), xxiv.4 (-*va*).
yathākrama, ci.11, ii.44, x.
 10, xiv.5, etc.
yadā, iv.38.
yadī, iii.13.
yadrchayā, cxxiv.6v.
yam *krāṇḍasi*, iv.20.
r. yam: + *nī*, ci.1: *niyata*,
 ci.49, xv.6.
yama, xv.9 (*ekay-*), xxi.13,
 xxii.12, xxiii.11: -ci.1, ii.
 49, xv.9 xvii.3, xix.3, xxi.
 8, xxiii.17: and *dvīy-*, *ca-*
tury-.
yamāh, xii.3.
yamān, ix.23.
yavena, vii.6.
yashṭah, viii.8.
yajurvedika, ci.1.
Yajñavalkya, cxxiv.6.
yājñiya, cxv.9.
yajyā, iii.9, 11, ix.20, xi.3:
 -ci.61, iii.1, ix.23 (-*two*).
yātā, iii.10.
yādrchika, cxxii.9.
yānam, vii.6.
yāmena, vii.10.
yavat, i.41 (-*ardha*): -ci.22,
 58, xxi.15, xxii.3, xliii.
 11.
yukta, v.2 (*yathā*): -ci.18,
 19, 61, x.12, xliii.14, xiv.
 28: and *ay-*.
yukti, civ.23, xliii.15 (-*anta-*
ra), xiv.4 (do.), 5 (uo.).
r. yuj, ci.23, iv.11: + *pra-*,
 cvi.5, xviii.2, 4, 7, xliii.4:
 + *upa*, cviii.13, xliii.10:
 + *am*, cxiv.26v: and
yukta etc., *prayoga* etc.,
yoga etc., *saṃyukta* etc.
yukshvā, iii.8.
yuvayor yaj, xi.16.
yushmān, vi.14.
yushmānitah, xliii.15.
ye, xi.16.
ye aprathetām, iv.20.
yenā, iii.12.
yogavibhāga, cii.12, 23.
yogyatva, cii.37.
yojanā (*sūtra*-), ci.35, xiv.
 28.
yo rudrah, xi.16.

ra (r), i.19, vii.11, xlii.6,
 xiv.15.
rañsyate, xvi.22.
rañhyāi, xvi.23.
raṅghā, iii.8.
raghiyā, xvi.13.

r. rac: + *vi*, cintr., i.18, viii.
 19.
rathah, xi.5.
rathamāture, iv.11.
rathi, iii.7.
r. rabh: + *d*, ci.2, 5, 14, 33, 47,
 iv.22, 23, v.1, x.10, 24,
 xlii.9, xliii.5, xxiv.2: and
ārambha etc.
ramaniya, civ.23, xliii.13,
 xiv.15.
raçmin, ix.23.
r. rah: *rahita*, ciii.15, xliii.
 20.
-rā-, xiv.4, xvi.4.
r. rāj, cxxi.1.
rajadantia, cii.2.
rātri, iii.7.
rāyāh, viii.29.
rāye, xi.9.
rāvṇ, xliii.14.
rāpi, ci.6, xlii.1.
-rasah, vi.5.
-ri-, xvi.25.
r. ric: *vyatirikta*, civ.52, ix.
 20, xiv.28, xxiv.5: and
atireka.
riśah, viii.24.
ru, vii.12.
ruçira, ci.18 (*ar-*), iv.40.
rudra, xi.3: -ci.61.
rudrah, xi.16.
r. rudi: + *vi*, cxiv.4: and
anurodha, *virodha* etc.
rundhe, iv.14.
r. ruh: + *d*, cxiv.9.
ruhemā, iii.10.
rōpa, xlii.2: -ci.14, 29, 30,
 59, xlii.14, etc. etc.
r. rūp: + *nī*, cii.1, xviii.1,
 xxiv.4.
rūpe, iv.11.
repha, ii.41, v.10, 29, vi.8
 (-*ront*), viii.6, 7, 16, 20, ix.
 20, xlii.2, xiv.4, 6, 19, xv.
 1, xvii.4, xxi.15.
roṣate, iv.11.
rodasi, iv.17.

la (l), v.25, 31, xlii.16, xiv.2,
 21.
lakāra, ii.42, v.25, xiv.7, 26:
 -ci.1.
r. laksh, ci.40, iii.9, vi.9,
 xlii.13: + *upa*, ci.29, 38,
 39.
lakshaya, cintr., i.1, 38, 46,
 ii.3, 18, 23, 25, iii.1, iv.43,
 v.26, ix.1, xi.18, xlii.15,
 xiv.29, xv.9v, xix.3, xx.2,
 xliii.5, 7, 20, xxiv.5, 6: and
upal-.

- lakṣhya, ci.22, iv.52, viii.5-
(-tea), xv.9v.
lagha, xxii.14, 15, xxiv.5
(-tā).
r. labh, ci.11, 14, 16, 21, 25,
27, 32, 34, iii.1, etc. etc.,
xiv.4; +upa, ci.15, xxiii.
10, 13; and upalabdhi etc.
r. lamb: +a, civ.11.
lāghava, civ.3.
lābha, ci.21.
liṅga, ci.49, ii.7, xiii.9, xv.6.
r. lup, viii.16, ix.1, 9, x.14,
19, 22, xi.1, xv.1, xvii.4: -
ci.4, 61, v.12-9, viii.17-9,
x.14, 20-2, 23 (luptavat),
xi.3-18, xii.2-10, xiii.2-4.
lega, x.23: -civ.23, xiv.4.
loka, civ.52, xxii.9 (-vat).
lokān, vi.14.
loke, iii.6, iv.53.
lopa, i.56, 57, v.11, xii.1, xiii.
1, 15, xv.1, xvii.4, xx.4,
xxiv.5: -ci.51, 61, viii.8,
17, 18, ix.9, x.19, 25, xii.
6, 8, xxi.14: and al-
lopīn, i.23: -ci.24.
lūkika, ci.1.
lyap, cxxi.14.
va (v), iii.4, xii.4.
vāh, xi.16.
vaṅga, xvi.21.
vaṅsagah, vaṅsate, xvi.
20.
vakāra, ii.43, v.13, 30, ix.16,
x.15, 19, 21, xiii.3, xiv.2,
21, 26, x.1, 2.
vaktra, ci.37.
r. vac, i.61, xiii.19: -ci.17, 50,
52, 53, 59, 60, ii.23, 24, iv.2,
3, 11, viii.10, 18, ix.24, xi.
2, xii.1, xiii.4, 5, 8, 13, xiv.
4, 5, etc. etc.; +vāksh,
ci.37, xiii.15; +pra,
civ.4: and ukta, ukta,
vāc etc., vīvakṣā.
vacak, xi.16, xii.6.
vacana, ci.1, ii.7, iii.2, 7, 8,
iv.23, 38, v.2, vi.5, 13, 14,
vii.2, viii.8, 13, ix.1, x.14,
xi.16, xii.11, xiv.5, 15, 23,
28, xv.8, xvi.29, xix.3.
-vat, i.48, 55, ii.21, 51.
-vat, iii.3.
vatsarasya rūpe, iv.11.
vatsānūsārīn, cxxii.13.
vatsānūsārī, cxxii.13.
r. vad, xiii.20: -ci.48, ii.9,
iv.52, v.3, xiv.4, 23, xvi.
13, etc.; +apa, civ.5: -
and opavāda, -daka.
-van, iii.3, vii.6.
vanaspatibhyah, xii.8.
vapācārapana, iv.12.
vayunā, iii.2.
r. var: +nī, ci.19, ii.14, iv.
40, xi.1, xiii.4, xiv.4, xx.
2; +vī, cxxii.14: and vi-
varta, xxi.17a.
Vararuci, ci.18, ii.14, 19, iv.
40, viii.19, xviii.7, xxi.15.
varga, i.10, 27, ii.51 (-vat).
vargasa, iv.53.
r. varj, civ.52, ix.20, xvi.25.
-varja, ci.20.
varpa, i.1, 16, 20, 56, ii.7, xiii.
5, xvii.7, 8, xxii.1, 2, 4,
xxiii.1-3: -civ.15, xvi.8-
10, xx.2, etc.
varṇakrama, xxiv.6.
varṇasamhitā, xxiv.2: -
ci.13, 14, xxiv.4.
varṇā, ci.1, xviii.1.
r. varṇ, ci.47, iii.1, 15, iv.5,
23, 45, 52, 54, v.10, 19, etc.
etc.; +ana, ci.36, ii.30,
vii.34, x.9; +nī, ci.18,
51, 59, 60, ii.25, ix.9, x.15,
19, xi.1, xiv.5, 11, xv.3,
xxii.6: +pra, cv.1, 3, 22,
xiv.5: and anuvartana,
anuvṛtti, dvṛtti, nivartaka,
nivṛtti.
vartamānava, ci.15.
vartayā, iii.12.
vartayāsi, xvi.18.
-vartā, ci.47, viii.23, ix.18,
xii.3.
vardhaya, vardhā, iii.8.
varshayathā, iii.10.
varshā, iii.5.
varshishthe, xi.16.
vaśān, ix.21.
vasiṣṭh, xvi.13.
vasuḥ, viii.31.
vasuḥ, iii.7.
vastak, viii.8.
vā, i.24, 44, 45, ii.50, xviii.7,
xix.1, xx.2, xxii.7.
vāh, vii.2, viii.8.
vān eshaḥ, xi.16.
vākya, ci.61, xxi.3, 3 (śa).
vāghā, vii.13.
vāc, xviii.4, xxiii.3, 4: -civ.
4, 5, xxiii.5-10, xxiv.5.
vācika, ci.18, v.28, xxi.9,
xxii.4.
vācayati, iv.52.
-vācin, ci.15, v.10, xvi.30.
vācya, ci.18, iv.47, xiv.5.
vājapeya, xi.3: -ci.61.
Vājāsaneyin, civ.33.
vāṇah gata, xiii.12.
vāṇijāya, xiii.12.
vāṇik, xiii.12.
vāṭah, xi.5.
vātā, iii.5.
Vātsapya, see p. 430.
vāda, cxxii.9.
-vān, iii.3.
vāya, ii.2.
vāyuh, iv.42.
vāraruca, cintr., ii.47, viii.
20, 22.
vārunda, v.21.
Vālmiki, see p. 430.
vāṣṭi, iii.7.
vāsasi, iv.17.
vāṣanah, vii.6.
vā, i.15.
vī, iii.15, xvi.25.
vikarsha, xi.3.
vikalpa, ci.19, 46, viii.22, ix.
1, xiii.16.
vikāra, i.28, 56, xv.5, xxiv.
5: -civ.3, v.9, ix.11, 12, 14,
15, x.8, 9.
vikārin, i.23: -ci.24.
vikṛta, i.51, xvi.3, 15: -civ.
8 (-tea), xiii.15 (do), xiv.
28 (do); and av-
vikrama, xvii.6, xix.1, xxiii.
20, xxiv.5: -civ.2, 5.
vikriyā, cxxii.8.
vigatava, cxiv.28.
vigraha, civ.4.
vicakṣhaya, xxiv.6: -civ.18.
4.
vijāyatan, cv.2, xxi.1, xxiv.
5.
r. vid, xxii.14: -ci.1 (vidya-
mānava), ii.47, ix.24,
xiii.14, etc.
vidatān, ix.21.
viduh, vi.5.
vidmā, iii.10.
vidvā, xvi.13.
vidvān, vi.14.
-vidha, cxiv.33, xvi.29,
xxiii.7, xix.3, xxiv.5, etc.
vidhāna, ci.11, 15, 19, 34, 53,
ii.9, 13, iv.7, 11, v.2, 3, 35,
x.10, 12, 15, xii.11, xiv.5,
xvi.29, xvii.5, xxi.1, xxiii.
7.
vidhāyaka, cix.3.
vidhi, v.2: -ci.14, 40, 43, 61,
ii.14, 19, 23, 25, 44, iii.8, v.
1, 41, vii.15, viii.7, 15, 25
(yathā) 28 (do), ix.3-6,
8, 13, 17, 22, 24, x.10, 11, 13,
24, xi.1, xiii.3, xiv.14, 22,
xv.8, xvi.3, 5, 29, xvii.1, 3,
4, xix.5, xx.3, xxi.6, xxii.
9, 10, xxiii.16, xxiv.5.

- vidhṛte*, iv.11.
vidheya, cxv.7.
vinatātā, cxvii.10.
vināga, l.57.
vinivartaka, xxii.6.
viṇaya, xxiii.2.
viṇayaśa, cxviii.2, 17.
vipakṣa, cxv.5.
vibhakti, ci.23, 28, xiii.9, xvi.25.
vibhajya, cv.13.
vibhāga, iii.1, xxiv.6:—cii.12, iii.1–15, iv.4, xiv.29, xx.2: and *yogac*.
vibhū, iii.7.
viyoga, cv.13.
virāma, xxii.13:—cxiv.15, xxi.6v.
viruddha, cxiv.4, 4 (*-vigrha*).
virūpe, iv.11.
virodha, ci.1, 15, ii.23, viii.15, 16, xiv.5.
virodhin, cxvi.19.
vilakṣhaṇa, cxxi.7.
viśaḥ, viii.8.
viśakṣa, ci.1, 18.
viśara, cii.37, xxii.9.
viśaraṇa, ii.52, and end'gs of chapters.
vivicitā, xvi.13.
vivicitā paruk, viii.32.
viśṭā, ii.5, 45:—cii.12 (*ati*), xxi.15.
viśṭā, xx.5, xxi.6v, xxii.13.
viśasanana, xvi.7.
viśāḥ, iv.11.
viśeṣa, xvii.7, xxiii.1, xxiv.6:—ci.1, 14, 15, ii.13, 31, 33, 47, iv.47, 52, v.10, viii.16, x.10, xi.19, xiv.5, 12, 18, 28, xvi.1, 2, 13, 19, xviii.6, xviii.1, xx.7, xxi.1, xxii.6, 13, xxiii.2, xxiv.2, 6: and *av*, *viśeṣya*.
viśeṣhaṇa, ci.61, ii.25, iv.11, viii.13, 23, 32, x.9, xiv.6, 28, xv.4, xx.2, xxiv.4: and *prati*.
viśeṣha, cii.31v, 33v.
viśvataḥ, viii.24, 32.
viśvadevyā, iii.5.
viśvā, iii.5.
viśama, cxiii.15.
viśaya, ci.1, 15, 48, 59, ii.20, iii.8, 9, 11, iv.23, v.15, ix.20, 21, x.19 (*-tva*), xi.4, xii.1, xiii.15, xiv.28, 29, xv.9v, xx.2.
viśayikar, cv.24, vii.15.
viśhurūpe, iv.11.
viśhū, iii.7.
Viśvadharmottara, cxvii.6.
visarga, ci.51, iv.38, 46, vii.2, viii.16, xi.5, xvi.13.
visarjanīya, i.12, 18, ii.46, 48, vi.1, viii.5, xiv.15:—ci.1, ii.47, xiii.7, etc. etc.
vispaṣṭa, ci.1, iv.11, xvi.25, xxi.15.
viṣaya, xi.3.
vihitatva, cxiv.12.
viḍ, iv.38.
viṇḍyam, xiii.12.
vipsā, ci.61, v.3, xxiii.11, xxiv.6v.
viyamāṇaḥ, xiii.10.
virya, ii.5.
viṭṭi, xxiii.17:—cxiv.4, xxiii.18, 20.
viśhadaṇṇaḥ, xvi.19.
viśhaṇ, xiii.13.
viśhaṇaḥ, xi.16.
viśhaṇīyā, iii.5.
veḥ, vi.5.
veṇu, xiii.9.
veṇupatra, cxv.12 (*-rat*).
veda, ci.1, v.1, xiv.9 (*-anta*), xviii.1, xix.3, xxiv.5: and *yajurv*, *vaidika*.
vedāṇya, cxv.6.
veda, cxv.2.
v. veshṭ: + *prati*, ii.37.
vāikālpika, cxvii.7.
vāikṛta, cv.22, vi.14, vii.2, xiii.13, xiv.4, 5.
vaidika, ci.1.
vāiparitya, cxvi.26.
vāibhāṣhika, xxii.7.
vāiyarthya, ci.61, ii.47, iv.11, 23, v.22, xiv.28, xx.2.
vāiyakarāṇa, cv.1, xxiv.3.
vāiśiṣṭhya, cxv.1.
vāiśeṣha, xiii.2.
vāiśhaṇīyā, iv.12.
vāi sam, iv.44.
vocatā, iii.12.
vayakti, cii.47, iv.40, v.15, xx.6.
vyaṅga, cxv.1.
vyaśasvatā, iv.19.
vyaśjana, i.6, 14, 17, 21, 37, iii.1, iv.6, v.14, 37, vi.7, xiv.1, 5, 28, 30, xvii.5, xxi.1, xxii.14, 15, xxiii.7:—cx.12, xvi.3 (*-tā*), xxi.1, etc.
vyatihāra, cxvi.23.
vyatyaya, cxvi.4.
vyabhicāra, ci.33.
vyartha, ci.21, iv.11, viii.34, xiv.17, xvi.2, xxi.1: and *vāiyarthya*.
vyavachedaka, cii.25 (*-tva*), xx.3.
vyavadhāna, cii.25.
vyavadhāyika, cxviii.15.
vyavasthā, cxix.3.
vyavāya, xiii.15:—c.ii.25.
vyaveta, i.17, iv.51, vii.5, xiii.7:—ci.19 (*-tva*), vi.3.
vyasta in *ativ*.
vyastataḥ, cii.14.
vydkaraṇa, ci.57, ii.47, xiii.16: and *vāiyak*.
vyakhyāna, c. intr., ix.8, xxi.1, xxiii.17.
vyācāraka, cxv.7.
Vyāsa, cxv.6.
vyāhṛti, iii.7.
vyudāsa, cxv.9v.
ṣa (*ṣ*), v.22, xiii.15, xiv.26.
ṣa, xvi.2.
ṣaṣṭā, xvi.5.
r. ṣak, cii.12, 23, xxi.1: and *ayakya*.
ṣakāra, v.4, 20, 34:—c.ii.44.
ṣakuni, vi.7.
ṣakti, cii.33.
ṣakti, iii.7.
r. ṣaṅk: + *d*, cxv.15, xxii.14, xxiii.11.
ṣaṅkā, ci.3, x.22, xiii.13, xiv.4, 15, xxi.10.
ṣaci, iii.7.
ṣatepañcāṇnyāya, cii.25.
ṣatrū, iii.7.
ṣatva, cv.24.
ṣabha, ii.1, xxi.1, 3, 9, xxiii.3:—c. intr., i.1, 7, 15–7, 19–22, 26–9, 37, 42, etc. etc.: and *aṣ*.
ṣamitāḥ, viii.8.
ṣarāva, cii.7.
ṣarira, ii.2.
ṣaṣvataḥ, viii.24.
ṣasanam, xvi.7.
ṣākhā, cxv.8, xvi.12 (*an*), *ya*); *ṣākhāntara*, ci.11, 12, 15, 37, vi.5, viii.8, xi.3, 9, 15, 16, xii.3, xiii.13, 16, xvi.13, 18.
ṣākhin, cviii.20, ix.4, 6, x.20, xiii.16, xiv.10v, 11v, 13v, 19v, 20v, 32v, 33, xv.9, xxi.13.
Ṣāṅkhāyana, see p. 430.
ṣāryāte, iv.41, xi.16.
ṣāstra, xix.5 (*pūre*):—ci.2, 14, 21, 53, ii.18, xxi.3, xxiv.6.
ṣāṣṭumāraḥ, xvi.26.
ṣāṣṭat, xvi.26.

- śikṣā*, c.1.2,21, ii.2, xiv.5, 28, xix.3,12, xxi.1,15, xxi.13, xxi.10,17.
śikṣā, iii.8.
śikṣakāra, c.1, xxi.15.
śipre, iv.11.
śiras, ii.3, xxi.10:—c xx.12 (komala-).
śive, iv.11.
r. śish: +vi, c.130, ii.44, iv.7,34, v.18,19,28, vi.5, x.10, xiv.5,19, xxi.1: and *aviśiṣṭa*, *viśeṣa* etc., *vācīśiṣṭya*.
śiṣṭa, c.1.
śikā, iii.2.
śirṣap, xiii.13.
śukla, c.v.28.
śuddhā, iii.2.
śuśruvā, xv.13.
śuśmanā, xi.16.
śūnya, cxx.2.
śūṅge, iv.11.
śrṇutā, iii.10.
śeṣa, i.6,14,42,46, ii.28, xxi.14:—c.144-5, ii.29,47, xiii.15, xxi.15.
śeṣabhūta, c.147, iv.3, xi.3. (*śiṣṭyāyana*, see p. 430).
śo, xvi.2.
śoṇā, xiii.12.
śyeta, x.18.
śyendāya, xi.3.
śrapayān, ix.23.
śravāṇa, c.iv.35.
śrī, vii.9.
r. śru, cxxii.6.
śruti, iv.35, xii.7, xiii.12:—cxi.15.
śrudhī, iii.13.
śreyā, xvi.13.
śroṇi, iii.7.
r. ślish: +*sam*, c.ii.12, xvii.4: and *upaśleṣa*, *duḥśliṣṭa*, *praśliṣṭa*, *saṁśleṣa*.
śloka, cxxii.14, xxi.10.
śvā, iii.2.
śvāsa, ii.5,10, xxiv.5:—c.ii.3.
śha (śh), vii.13, viii.23,33, xiii.6.
śhah, vii.11.
śhakāra, v.10,32, vi.1:—c.ii.44.
śhat, vii.2.
śhapp, xiii.14.
śhatra, c.151,60, v.3, vi.4,5,13, vii.2, viii.16,35.
śhāṣ, i.9.
śhāshṭha, iv.52.
śhi, xvi.14.
śhu, vii.2.
śhumnaḥ, xiii.15.
śhū, vii.2.
śhodaṣa, i.5.
śhapa, xiii.14.
śa (ś), iv.7, v.32, viii.23,26, xiii.15.
śa (pron.), v.2, xi.19, xviii.4, xix.1, xx.3.
śah, v.15,17, xi.9.
śamīyukta, xxi.15:—c. xxi.5 (as-).
śamīyuta, c.154 (as-).
śamīyoga, xxi.4 (-gādi), 15, xxi.14,15, xxiv.3:—c. xvii.4.
śamīrakṣhaṇa, c.vi.5.
śamīrta, ii.4,27:—c. xxi.15, xxi.9 (-tā).
śamīyavahāra, c.14, xxi.3.
śaṅṣita, *śaṅṣitā*, xvi.26.
śaṅṣeṣa, c.ii.33.
śaṅṣvā, xvi.26.
śamīnad, xxiv.6.
śaṅśadāḥ, xvi.26.
śamīarya, xxi.2.
śaṅśrṣṭa, xvi.26.
śaṅśkṛta, *śaṅśkṛtya*, xvi.26.
śaṅśphāṇaḥ, xi.16.
śaṅśvā, xvi.26.
śamīhā, v.1, xv.8, xxi.10, xxiv.1-4:—c.160,60 (as-), iii.1,8, v.3, vii.10, ix.22, 24, x.10,12, xi.9, xiii.5,14, xiv.29, xv.7, xvi.29, xix.3, xx.2: and *śamīhita*.
śak, vi.12.
śakala, c.iv.52, xvi.29 (-pa-da).
śakāya, xvi.10.
śakāra, v.6,10,14, vi.1,14, xvii.1:—c.ii.44.
śamīketa, c.121.
śamīkṣhepa, c.ii.6.
śamīkhyā, xvi.25:—c.1,11, ii.19, x.15,22, xxi.16.
śamīkhyāna, i.48 (as-):—c.159.
śamīghāta, cxxii.3.
śacasaṁvā, iii.8.
r. saj: +*pra*, c.ii.9,20, iii.1, xix.3; *prasakta*, c.14, ii.29, v.3,37, ix.13, xiv.5, xxi.1: and *op*-, *prasakti*, *prasanga*.
śajātiya, c.x.1.
śajūā, iv.25.
śamījāka, c.19,16.
śamījāda, c.12-15, 31-9,49, ii.4-6,9, iii.9, iv.3,11,12, 17, xi.3, xv.6, xix.1,5, xx.2, xxi.16.
śamījāka, c.13v, xiii.16.
śattvā, vi.12.
śatya, c.21,53, ii.18, viii.16, xiii.15.
śatyabhāma, c.xviii.3.
śatrā, iii.5.
r. sad: +*pratyā*, c.ii.42, v.24: and *dsanna*.
śadane, iv.11.
śadṛṣi, xi.19:—c. v.28, xxiv.6.
śadohavīrdhāne, iv.11.
śaddhā, c.xiii.14, xiv.28, xvi.29.
śadhik, vi.5.
śani, *śaniḥ*, *śaniā*, vi.12.
śanutaḥ, viii.8.
śamīdānebhyaḥ, vi.12.
śamīdeha, i.25:—c.14,26, iv.23, v.1, xxi.2,5.
śamīdhāna, ii.2, xxiv.3:—c. xv.15.
śamīdhi, c.ii.18, x.15,24,25, xxi.1.
śamīdhyaḥ, c.133, ii.47, 48, xviii.1.
śamīnaddhāḥ, xii.3.
śamīnikarṣa, c.xiv.3.
śamīnīpāta, x.12.
śapīra, v.19, viii.22.
śapta, xxi.4,11.
śaptami, c.v.10, xvi.25.
śaptābhik, vi.12.
śapte, vi.5.
śadhyaḥ, vi.12.
śam, v.6, xiii.4; *śamīn-dra*, vii.2.
śama, i.42,45,46, xvii.2, xxi.19.
śamābhivyaḥāra, c.xiii.14.
śamāya, c.iii.1, iv.5, vi.14, xiii.17.
śamarthana, c.xiii.14.
śamarthanīya, c.xvi.19.
śamarthay, c.v.3, xiii.4v, xiv.4.
śamāna, c.ii.23,47,48, iv.23, v.27, viii.19,21, ix.8, xxi.6,15.
śamānakāla, i.33.
śamānāpāda, iv.54, xiii.6, xxi.13:—c. xiii.15,16.
śamānākṣhara, i.2, x.2, xv.6:—c.1,34, x.10, xv.9.
śamānāna, ix.23.
śamānāya, i.1:—c.1,2,5, ii.1.
śamāsa, c.ii.2, iii.9, v.1, x.6, xiii.9.

- samdhāra*, i.40: -cīntr., i.61, ix.18, x.6, xiv.1, xviii.4.
samīddhāṣa, xi.16.
samīci, iv.31.
samīraṇa, ii.2.
samuccaya, ci.15,21, xv.7, xxi.6,9.
samuttha, cv.1.
samudāya, ciii.7, iv.3.
sampādana, ciii.1, xiv.15.
sampratyaya, cv.24, x.12, xiv.17.
sambandha, ciii.1, x.22, xi.1, xiv.18.
sambandhi, ci.60, ii.3,50, iv.40, xiv.23,28.
sambhava, ci.25, ii.18,25, iii.1, iv.23, x.12, xiv.14: and as-
sambhāvanā, civ.11.
samsatām, vi.12.
r. sar: + ut, c xiv.15; + pra, ci.59, iv.3, vi.11, vii.16, xi.18: and *prasarāṇa*.
sarapi, ci.18.
sarala, c viii.13, ix.1, xiv.4.
r. sarj: + ci, c ix.11; + sam, c xxi.1.
sarva, i.47, ix.7, xiv.33, xv.9, xvii.7, xxii.1,14, xxiv.5; *sarve*, viii.15, xviii.7.
sarvatra, ii.25, xii.11, xvii.2: -ci.18, iv.5,27,49, ix.22,24, xxii.3.
sarvathā, ci.59, v.3, xxiv.5.
sarvanāman, cii.7, viii.6, xv.3.
sareṇṅga, c xxi.17.
sareṇudatta, cvi.4.
sava, vi.10.
savana, c xxi.10.
savane paṇḍu, vi.14.
savargya, viii.2, xiv.23: -c viii.3,4, xiv.12,13.
savarga, i.3, v.28, x.2, xiv.23, xxi.7: -ci.4.
savita, viii.8.
savyāṇjana, i.43: -c ii.23.
saṣabda, xxiii.9.
saśaddā, iii.12.
saṣṭvā, xvi.13.
saṣṭhāna, ii.47,48, v.27,38, ix.2, xiv.9,13 (as-).
saṣyādyāi, vi.12.
sahacārita, ci.47, xiii.16.
sahasak, viii.28.
sahita, ci.43 (-tva), iv.47, v.19, xxi.15, xxiii.20.
sahurī, *sahātā*, iv.15.
r. sā: + *adhyaya*, c ii.7: and *avusita*.
sāhita, ix.17, xx.3: -c xiv.5, xx.4v: and as-
sāhāṅkshatā, c xiv.15.
sāhākalpika, c xxi.6.
Sāhākrtya, see p. 430.
sādāya, iii.12.
sādr̥gya, ci.13, xiii.16.
sādhana, c xxi.3,9,10.
sādharmya, ci.1.
sādhārāṇa, c xiv.5, xviii.7v.
sādhu, ci.53 (-tva), ii.7,18, xiii.13: and as-
sānūnāsika, cv.28, xv.1, xvii.5, xxii.14.
sānūnāsikya, c xv.2, xxi.14.
sāmūhidhya, ci.36, ii.11 etc., iv.30 etc., v.23, viii.14,33, ix.9,10, x.9,21,25, xii.3, xiv.21, xv.8, xix.3.
sāpeksha, ci.1 (-tva), iv.40 (-tā), xxi.1.
sāphalya, c xiv.28.
sām, xiii.4.
sāmanī, iv.12.
sāmarthya, ci.61, iv.11, v.25, viii.16, ix.13,21, xiii.14, xvi.13,19.
sāmānya, ci.29, ii.9,23, v.22, x.12, xiv.28, xv.8, xvi.19.
sāmya, xxiv.5: -c ii.20,39, 45, viii.16.
sāra, c xiv.5: and as-
sārathīh, vi.13.
sārōpya, c xiv.23.
sārthaka, c iii.1, iv.11, viii.16.
sahacarya, c xiii.14, xiv.15, xvi.13,26.
sahasra, vi.13.
-si, xvi.14,27.
siṅhavalokana, c ii.51, iv.4, xiii.3,15.
siṅcathā, iii.10.
siddharūpa, c viii.19.
siddhavarṅkṛti, c xiv.28.
siddhi, c ii.20,25,47, iv.11, 23,52, v.22, viii.13,18, xiii.4, xiv.17, xvi.2,12, xxi.5.
r. siddh, c ii.25, viii.8,16, ix.7, xiii.14, xvi.18; *siddha*, ci.11,14, iv.3, v.26, viii.21, etc.; + *mī*, ci.4,14,59,60, ii.25,29, v.24,29,35, viii.8, ix.13,21, x.24, xiii.16, xvi.5, xviii.1, xxiv.2; + *pra*, ci.4; *prasiddha*, ci.21, ii.47, xiii.14,15, xix.3; + *prati*, ci.4, viii.8, xiii.3, xiv.33v: and *aprasiddha*, *spār dhāh*, vi.13.
nishedha, -*dhaka*, *prati-*
shedha, -*dhaka*, *prasiddhi*.
sita, vi.12.
su, v.5, xvi.25 (as-).
sugopā, iii.5.
sutarām, ci.25.
sumati, vi.5.
sumnā, iii.2.
sumānī, iv.12.
suva, v.10, vii.2, viii.8,13, xii.7,14.
sūkshma, c xvi.3.
r. sūc, c xiv.5.
sūcaka, ci.7.
sūtra, ci.1,14,18,22,25,35, 39,46,50,53,57, ii.1 etc., iii.1, iv.3 etc., v.1, etc. etc.
sūtrakṛt, ci.15.
sūtrita, c xiv.6v (as-).
surjā, iii.12.
so asmān, ix.21.
sopādhiṅka, c ii.23.
soma, ix.21.
somah, xi.15.
somāya eva, iv.48.
standm, vi.12.
stanutak, viii.8.
stabhūnidm, iv.52.
starima, vi.13.
starimā, iii.10.
stutagastre, iv.11.
stubbh, vi.13.
sto, vi.13.
stotak, viii.8.
striliṅga, c ii.7.
-stha, xx.3: -c iii.1, xvi.24, etc. etc.
stha, iv.46.
sthalā, ci.61, iv.11,23, xi.4, xix.4, xx.2.
sthavira, xvii.4.
r. stha, xx.2: -c v.2, xxi.7; + *ava*, ci.16, xxi.1,2; + *vyava*, c xxi.2; + *upa*, c xxi.5.
sthā, iii.8.
sthāpam, xiii.12.
sthāna, ii.31,33,44,46,49, xxi.11, xxiii.2,4,11: -c i.3, 33, ii.3,23,39,43,47, etc. etc., xviii.4.
sthānam, vi.10.
sthita, xx.2.
sthi, c xiv.28.
sthāpau, xiii.12.
sthāla, c vi.9, xxi.10 (-tā).
sthe, xii.6.
sthaurya, c xiv.5.
sthāulya, c xiv.5v.
snigdhatā, c xxi.10.
r. spar, ii.17,34,35: -c ii.36
shetha, -*dhaka*, *prasiddhi*.
 -43.

<i>spareca</i> , i.7, 10, ii.44, v.27, 34, xiii.15, xiv.2, 3, 9, 27, xxi.9, 12.	11, xiv.29, 31, xviii.2, 5, xix.1, xxi.10, 11, xxiv.5: -c x.10, xvii.6, xix.3, xx.1, xxiii.16, 17, 17 (-tea).	+ <i>vyā. cxxiv.46</i> ; + <i>pari</i> , ci.59, iii.1; + <i>upasaṃ</i> , cii.18, 32; -c ii.22, 23; and <i>u-dāharaja</i> , <i>parihāra</i> , <i>upa-sāśhṛta</i> , <i>-hāra</i> , <i>saṃāha-ra</i> .
<i>sparcana</i> , ii.33; and <i>as-</i> .	<i>svarūpa</i> , ci.21, 40, v.2, xvi.30, xxi.10, 15, xxiv.4, 6.	<i>harā</i> , iii.12.
<i>spacah</i> , vi.12.	<i>svā</i> , iii.5.	<i>hariṣa</i> , cxxi.15.
<i>spashā</i> , c xvii.8 (<i>atis-</i> , <i>as-</i>): and <i>vis-</i> .	<i>svādhyāya</i> , c xviii.1.	<i>haritā</i> (or <i>hār-</i>), cxxi.15.
<i>spashtikar</i> , c xiii.15v.	<i>svānāso divi</i> , vi.2.	<i>hari</i> , iv.15.
<i>sphutikar</i> , c ix.8, xiii.15.	<i>svāyoga</i> , c ii.25.	<i>hal</i> , c ix.24.
<i>sphuranti</i> , vi.13.	<i>svāra</i> , xvii.6, xx.8, xxiii.20: -c xxiii.17.	<i>havana</i> , vii.11.
<i>sphuritateva</i> , c ii.25.	<i>svārtha</i> , c ii.17.	<i>haviśhmān</i> , ix.21.
<i>syah</i> , v.15.	<i>svādhākṛti</i> , iii.7.	<i>hastaviṃśasa</i> , c xxiii.17.
<i>sra</i> , xvi.2.	<i>svitar</i> , ci.19, 21, 25, iv.23, 52, xi.3, xiii.14.	<i>hāh</i> , viii.8.
<i>srādi</i> , i.60, xv.4: -c xvii.5.	<i>svikāra</i> , civ.23, x.12, xiv.5.	<i>hārītā</i> (or <i>har-</i>), cxxi.15.
<i>srīdhah</i> , xii.8.	<i>svend</i> , iii.10.	<i>Hārta</i> , see p. 430.
<i>sra</i> , xxiv.4 (<i>yathā</i>): -c xiv.28.	<i>ho</i> (<i>h</i>), ii.9, iv.7, xii.4, xiv.26.	<i>hi</i> , iv.37, 44, vi.2, xvi.13;
<i>svatah</i> , c ii.23, xxi.7.	<i>ho</i> , xvi.2.	<i>hi payasvān</i> , ix.21;
<i>svatantra</i> , c xxi.6.	<i>hansapada</i> (or <i>-pāda</i>), cxxi.15.	<i>hi shthā</i> , iii.8.
<i>svadeṣa</i> , ci.59.	<i>hakāra</i> , i.13, ii.6, 9, 46, 47, v.38, xiv.19, xvi.27, xxi.14: -c ii.3, 7, 44.	<i>hīṇyāt</i> , <i>hīnoti</i> , xiii.12.
<i>svadhāvaḥ</i> , xii.8.	<i>r. han</i> : in <i>nihata</i> .	<i>hīraṇmayam</i> , xiii.8.
<i>svabhāva</i> , c xiii.14 (-tea), xiv.28.	<i>hanu</i> , vii.11.	<i>hīraṇyacaraiya</i> , ix.20, xi.3.
<i>svayanipātha</i> , c ix.21.	<i>hanu</i> , ii.12 (<i>ośhtha-</i>), 16: -c xxi.2.	<i>hūtamān</i> , ix.21.
<i>r. svar</i> , xx.2, 3: -c i.41; and <i>atisvādrya</i> .	<i>hamā</i> , iii.7.	<i>hṛd</i> , cxxiii.17.
<i>svara</i> , i.5, 33, ii.8, 31, 47, viii.3, ix.10, xi.18, xii.4, xiii.16, xiv.1, 16, xv.1, xvi.2, xvii.5, xxi.1, 2, xxiii.14, xxiv.6: -c xvii.3, xxi.12, xxiii.7, 11, 15-7 etc. etc.	<i>hanūmāla</i> , ii.35: -c ii.17.	<i>hṛdayā</i> , iii.2.
<i>svara</i> , vi.13.	<i>hantand</i> , iii.10.	<i>hetayah</i> , xii.8.
<i>svarabhakti</i> , ii.19, xxi.6, 15: -c i.1, 6, ii.33, xxi.16.	<i>hanyat</i> , vii.3.	<i>hotah</i> , viii.8.
<i>svarasa</i> , c v.22.	<i>r. har</i> , xvii.8; + <i>udā</i> , xxi.3: -c xii.3.	<i>hrasiyā</i> , xvi.13.
<i>svarāṅga</i> , xxi.1.	<i>xxiii.4, 17</i> ; + <i>samā</i> , ci.40.	<i>hrasva</i> , i.3, 20, 31, 41, iii.1, ix.18, xvi.16, xxii.15, xxiv.5.
<i>svarita</i> , i.40, x.12, 16, xii.9.		<i>hrasvateva</i> , ci.52.
		<i>hrasvārtha</i> , i.37: -c i.42, 44, 46, xvii.5.
		<i>hrādanti</i> , iii.7.
		<i>hrādāḥ</i> , viii.8.

GENERAL INDEX.

THE references by Roman and Arabic figures together are, as in the other Indexes, to chapter and rule; those by Arabic figures alone (with *p.* prefixed), to page of the volume.

- a*, *ā*: how uttered, ii.12; how combined with a following vowel, x.3-9;—*a*, is short, i.32; *āh* to *a* before, ix.7; lost before initial *e* or *o* of certain words, x.14; when initial, lost after *e* or *o*, xi.1; detail of cases of its elision or non-elision, xi.2-xi.8; resulting accent, xii.9-11;—*a*, final, result of irregular prolongation, iii.2-6, 8-12; initial, *do*, iii.15;—*ā*, nasalized when final, xv.8.
- abhinidhāna*, xiv.9.
- abhinidhata* circumflex, xx.4; its occurrence, xii.9; its comparative tone, xx.10.
- Accent: see Analysis, p. 437; also Acute, Circumflex, Grave, and the names of the various accents.
- Acute accent (*udatta*), defined, i.38; mode of production, xxii.9; acute tone of grave syllables after circumflex, xxi.10-11.
- ā*, how uttered ii.26-8; peculiar utterance in a single word, xvi.24; combination with following vowel, ix.14, x.19-23; with preceding *a*, *ā*, x.6.
- Alphabetic sounds, enumeration of, p. 8-10; classification, mode of production, etc., see Analysis, p. 436; names for, i.16-9.
- anudatta*, see Grave.
- anusvāra* (*ṇ*): its equivocal treatment by the Prāticākhya, p. 67-70; is an independent element, p. 8; how uttered, ii.19,30; how designated, i.18; belongs to preceding vowel, xxi.6; its quantity, i.34; makes a heavy syllable, xxii.14; its occurrence, xv.1-3; *do*, otherwise than as result of euphonic combination, xv.4-5, xvi.1-31.
- Articulate sounds, see Alphabetic.
- Aspirate mutes: sonant, contain *h*-sound, ii.9; surd, contain more breath than non-aspirates, ii.11; substituted for non-aspirate before sibilants, xiv.12-3; how duplicated, xiv.5; double aspirates in the MSS., p. 290,294.
- ā*, how uttered, ii.26,27,29; combination with following vowel, ix.15, x.19-23; with preceding *a*, *ā*, x.7.
- Authorities quoted in the rules of the treatise, p. 430.
- avagraha*, name of first member of a compound, i.49; quantity of the pause following it in *pada*-text, p. 399.
- b*, labial mute, ii.39.
- bh*, labial mute, ii.39; doubled in certain words, xiv.8.
- Brāhmaṇa-passages in the Saṁhitā, p. 48.
- c*, palatal mute, ii.36; insertion of *c* before, v.4,5; *t* to *c* before, v.22; *n* to *c* before, v.20,21,24.
- ç*, palatal spirant, i.9, ii.44-5; initial, to *ch* after any mute save *m*, v.34-7; *t* to *c* before, v.22; *n* to *ç* before, v.24; irregular insertions of, v.4,5; inserted after *n*, v.20-1.
- ch*, palatal mute, ii.36; product of *c* after a mute, v.34-7; *t* to *c* before, v.22; *n* to *ç* before, v.24; doubled in certain words, xiv.8.
- Cerebral mutes, see Lingual.
- Çikshā, quoted in the comment, p. 435.
- Circumflex accent (*svarita*), mode of utterance, i.40-7; degree of effort in, xvii.6, xx.9-12; kinds of independent circumflex, xx.1,2,4,5; their occurrence, x.16,17, xii.9; kinds of enclitic circumflex, xx.3,6,7; its occurrence, xiv.29-33; *kampa* between two circumflexes, xix.3-5; nature of enclitic circumflex, p. 315.
- Citation, rules of, i.22,24,50-3.
- Citations in the comment not found in the Tāittiriya-Saṁhitā, p. 425-6.
- Commentary, see Trībhāṣhyaratna.
- Compound words, separable, count as two, i.48; first member called *avagraha*, i.49.
- Consonants, i.6; their classification and description, i.7-14, ii.8-11,30,33-52; names, i.17-8,21; quantity, i.34,37, p. 377; accent, i.43; belong to what vowel, xxi.1-9; relation of consonant and vowel, p. 72,375-7; see also the several letters and classes, and Groups.
- d*, dental mute, ii.38; irregular insertion of, v.8.
- ḍ*, lingual mute, ii.37; product of alteration of *t*, xiii.16.

- Dental mutes (*t, th, d, dh, n*), how formed, ii.38: see also the several letters.
- dh*, dental mute, ii.38.
- dh*, lingual mute, ii.37.
- Diphthongs (*e, ai, o, au*): see the several letters.
- Duplication, of *ā, a*, final, ix.18-9; of *ch, kh, bh*, xiv.8; of aspirate mutes in the MSS., p. 290, 294; duplication in consonant groups, xiv.1-7, 9-28.
- e*, how uttered, ii.15-7, 23; combination with preceding *a, ā*, x.6; with following vowel, ix.11, 13, x.19; initial *a* elided after, xi.1 etc.; resulting accent, xii.9-11; final *a* elided before, x.14; *pragraha* ending, iv.8-54.
- Elision, see Omission.
- Euphonic alteration, concerns single element only, i.56; of a cited word, does not suspend rules, i.51; mode of intimating in rules, i.23, 28.
- Final consonant, belongs to preceding vowel, xxi.3; makes heavy syllable, xxi.14.
- g*, guttural mute, ii.35.
- gh*, guttural mute, ii.35.
- Grammarians quoted by name in the rules and comment, p. 430.
- Grave accent (*anudatta*), defined, i.39; how produced, xxi.10; grave syllable, when converted to enclitic circumflex, xiv.29-31; when uttered at acute pitch, xxi.10-1.
- Groups of consonants, occurring in Tāttirīya-Saṁhitā, detail of their division in syllabification, p. 380-2, 385; make a heavy syllable, xxi.14.
- Guttural mutes (*k, kh, g, gh, ŋ*), how formed, ii.35: see also the several letters.
- h*, a spirant, i.9; not surd, i.13; intermediate between surd and sonant, ii.6; inheres in sonant aspirates, ii.9; uttered in the throat, ii.46; has same position as following vowel, ii.47; combination with preceding final mute, v.38-41; before a nasal, *nasika* inserted after, xxi.14.
- h*, see *visarjanīya*.
- Heavy syllable, xxi.14.
- i*, i: how formed, ii.22; combination with preceding *a, ā*, x.4; with following vowel, x.15; resulting circumflex, x.16;—i, final, result of irregular prolongation, iii.7, 13; *pragraha* ending, iv.8-54.
- Increment, how intimated, i.23.
- Insertions, of *ṣ, ś, ḍ*, anomalous, v.4-8; of *k, t*, v.32, 33; after spirant before mute, xiv.9.
- j*, palatal mute, ii.36; *t* before, to *j*, v.23; *a* before, to *ā*, v.24.
- śatā*-text, p. 429-30.
- jh*, palatal mute, ii.36; not found in the Saṁhitā, p. 72.
- jihvāmūliya* (*χ*), guttural spirant, i.9, ii.44-5; its designation, i.18; occurrence, ix.2-4.
- k*, guttural mute, ii.35; inserted after *ā* before *s, sh*, v.32; *ā* to *s* or *sh* before, viii.23 etc.
- kampa*, peculiar affection of a circumflex followed by another circumflex, xix.3-5; differences between the Tāttirīya and other texts as to its occurrence and treatment, p. 362-3.
- kaṇḍīka*, division of *anuvākas* into, not recognized by the Prācīkhyā, p. 5, 83, 427, 430.
- Kārttikeya, asserted author of the Prācīkhyā, p. 1.
- kh*, guttural mute, ii.35; *k* to *s* or *sh* before, viii.23 etc.; doubled in certain words, xiv.8.
- krama*-text, p. 429.
- kshaiṣṭra* circumflex, xx.1; its occurrence, x.16; its tone, xx.9.
- l*, semivowel, i.8; how produced, ii.42; assimilates preceding *t, m, n*, v.25, 26, 28; resulting nasal *l*, v.26, 28; changed to *d*, xiii.16; duplication after, xiv.2, 3, 7.
- l*, not a simple vowel, p. 11; of short quantity, i.31; how produced, ii.18.
- Labial mutes (*p, ph, b, bh, m*), how formed, ii.39: see also the several letters.
- Light syllable, xxi.15.
- Lingual mutes (*t, th, d, dh, n*), how formed, ii.37: see also the several letters.
- Long vowel, i.35: and see Prolongation.
- m*, labial mute, ii.39; assimilated to following mute, v.27; and semivowel (except *r*), v.28-31, xiii.3; irregularly dropped, v.12; to *ā* before *r* or spirant, v.29, xiii.2; unchanged before *ra*, xiii.4.
- Manuscripts of Prācīkhyā and commentary: see Tāttirīya-Prācīkhyā.
- Mutes, i.7; division and names, i.10, 11; what mutes are surd, i.12; mode of formation of the various series, ii.35-9; their designation, i.27: see also the several series and letters.

- n*, dental mute, ii.38; change of, to *ṣ*, before palatals, v.24,37; to nasal *ṇ*, v.25-6,31; to *ṣ*, v.20,21; to *ṣ*, vi.14; to *ṣr* or *ṣ* (through *y*), ix.20-4; to *ṣ*, vii.1-12,15,16, xiii.6-8,13-5; physical ground of this change, p.281; adds *t* before *ṣ*, *ṣh*, v.33; doubled, ix.19.
- ṇ*, guttural mute, ii.35; adds *k* before *ṣ*, *ṣh*, v.32; doubled, ix.18.
- ṇ*, palatal mute, ii.36; *ṇ* changed to, v.24, 37.
- ṇ*, lingual mute, ii.37; *ṇ* changed to, vii.1-12,15,16, xiii.6-8,13-5; detail of its occurrence when not result of euphonic causes, xiii.9-12.
- ṇ*, see *anuvāra*.
- Nasal, what sounds are, ii.30; nasal quality how given, ii.52; its differences of degree, xvii.1-4;—nasal mutes, surd mute to nasal before, viii.2; exception, viii.4; take a prefixed surd after a sibilant, xiv.9; take *yama* after preceding non-nasal, xxi.12; take *nasikya* after preceding *ḥ*, xxi.14; see also the several letters;—nasal semivowels, result of change of *m*, *n*, v.26,28;—nasalized vowel, alternative for *ṇ*, v.31, xv.1; result of combination, x.11; discussion of the doctrine of the treatise as to *ṇ* or nasal vowel, p.67-70; nasalization of a final vowel, xv.6-8; its prolongation, xvii.6.
- nasikya*, or *yama*, xxi.12; nose-sound, inserted between *ḥ* and nasal mute, xxi.14.
- nitya* circumflex, xx.2; its tone, xx.9.
- Nose-sounds (*yamas*, *nasikya*), how produced, ii.49-51; how designated, i.18; occurrence, xxi.12-4; how treated in syllabication, xxi.8.
- o*, diphthong, how produced, ii.13-4; when *pragraha*, iv.6,7; combination with preceding *o*, *ā*, x.7; with following vowel, ix.12-3, x.19-23; final *o* elided before, x.14; *oā* changed to, before *a* and sonant consonant, ix.7,8; initial *o* elided after, xii etc.
- om*, utterance of, xviii.1-7.
- Omission (*lopa*), defined, i.57; how intimated, i.23; affects single elements only, i.56; cases of, irregular, v.11-19; omission of *ḥ* before spirant followed by surd, ix.1; before a vowel, ix.9; of *o* after *e* or *o*, xi.1 etc.; nature of this omission, xi.19.
- Organs of articulation, ii.3; their mode of action, ii.31-4; and see the several letters and classes.
- p*, labial mute, ii.39; *p* to *sh* or *s* before, *s*, viii.23 etc.
- pada*-text, peculiarities of, in Taittiriya-Saṁhitā, p.85,98-9,369 note, 428-9.
- pādaṛṣṭa* enclitic circumflex, xx.6; its tone, xx.12.
- Palatal mutes (*c*, *ch*, *j*, *jh*, *ṣ*), ii.35; see also the several letters.
- Pāpini, cited in commentary, p.435.
- Pauses, quantity of, xxii.13.
- ph*, labial mute, ii.39.
- pluta*, see Protracted.
- pracaya* accent, xxi.10-1; of *om*, xviii.3; *vikrama* after, xix.2.
- prāḍishṭa* circumflex, xx.5; its occurrence, x.17; tone, xx.11.
- pragraha* finals, detail of, iv.1-54; are uncombinable, x.24; rarely elide *a*, p.264.
- Prācīkhyā, see Taittiriya.
- prāthāta* enclitic circumflex, xx.3; its tone, xx.11; discussion of its true character, p.369-70.
- Prepositions, list of, i.15; *a* of preposition combines with *r* to *ār*, x.9; usually take *iti* in *pada*-text, p.229,428.
- Prolongation, irregular, of vowels in *saṁhitā*, iii.1-15; of vowel after loss of final *r*, viii.17; of nasalized vowel, xvii.5; of circumflex vowel taking *kampa*, p.362-3.
- Protracted (*pluta*) vowel, quantity of, i.36; uncombinable, x.24; detail of cases occurring in Saṁhitā, p.323-4; a vowel following, is not styled "similar," i.4; nasalization of, when final, xv.7,8; tone of (*ṛ*), xv.9.
- Qualifications of a scholar and teacher, xxiv.5,6.
- Qualities (*sthāna*) of sound, xxii.11, xxiii.4-10.
- Quantity, see Analysis, p.437.
- r*, semivowel, i.8; how uttered, ii.41; its name, i.19; takes *svaraśakti* before a spirant, xxi.15; *ṛ* converted into, v.10, viii.6-15; but lost before *r*, and preceding vowel lengthened, viii.16-7; *ṛ* converted into, ix.20-4; causes duplication, xiv.4,6; changes following *s* to *ṣ*, xiii.6; *m* to *ṇ* before, xiii.2, xv.1-3.
- r*, *f*: not simple vowels, p.11; their composition, p.392; how uttered, ii.18; change following *a* to *ṇ*, xiii.6 etc.; quantity of *r*, i.31; combination with preceding *a*, *ā*, x.8,9; anomalous conversion to *ar*, v.9.
- Repeated passages, treatment of, i.61.
- Repetition of compound words, with *iti*, in *pada*-text, p.85.
- s*, dental spirant, i.9, ii.44; irregular intensions of, v.6,7; omission, v.14;

- conversion to *sh*, v.10, vi.1-13; inserted after *a* before *t*, vi.14; insertions of *k* and *t* before, v.3-32; *s* from *h* before *k*, *kh*, *p*, viii.23-35.
- Schools of Vedic study cited by name, p. 427.
- Semivowels (*y*, *r*, *l*, *v*), i.8; their effect on division of syllables, xxi.7; and see the several letters.
- sh*, lingual spirant, i.9, ii.44; conversion of *s* to, v.10, vi.1-13; insertions of *k* and *t* before, v.32-3; changes following *t*, *th*, to *t*, *th*, vii.13-4; *u* to *u*, xiii.6 etc.; *sh* from *h* before *k*, *kh*, *p*, viii.23-35.
- Short vowels, i.31-3.
- Sibilants (*ç*, *sh*, *s*), see the several letters and Spirants.
- Similar vowels, i.34.
- Sonant utterance, ii.4; sonant consonants, i.14.
- Spirants (*ç*, *r*, *sh*, *s*, *ç*, *h*), i.9; quality as regards sonancy, i.12-3; require more breath, ii.11; mode of articulation, ii.44-5; *h* converted into, ix.2-6; insertion after, before mute, xiv.9-11; aspiration of a surd mute before, xiv.12-3; effect of, on division of syllables, xxi.9; see also the several letters.
- Surd mute, converted to sonant before sonant, viii.3; to nasal before nasal, viii.2, 4.
- Surd utterance, ii.5, 10; surd consonants, i.12.
- svarabhakti*, how uttered, ii.19; occurrence, xxi.15-6; belongs to what syllable, xxi.6; various kinds of, p. 392-3.
- svarita*, see Circumflex.
- Syllabication, xxi.1-14.
- Syllables, heavy and light, xxii.14-5.
- t*, dental mute, ii.38; changed to *c* or *j* before palatals, v.22, 23; to *t* before *l*, v.25; *a* becomes *as* before, vi.14; inserted after *t*, *n*, before *s*, *sh*, v.33; changed to *t* after *sh*, vii.13.
- t*, lingual mute, ii.37; adds *t* before *s*, *sh*, v.33; *t* changed to, after *sh*, vii.13.
- tāirovyanjana* enclitic circumflex, xx.7; its tone, xx.12.
- Tāittīriya-Āraṇyaka, phrases quoted from, in commentary, p. 425-6.
- Tāittīriya-Brahmaṇa, phrases quoted from, in commentary, p. 425-6.
- Tāittīriya-Prāticākhya, manuscripts of, p. 1-3; various readings in its text, see Additions and Corrections, p. 467; its commentary, see Tribhāshyaratna; right to its name, p. 427; relation of the text it implies to the known Tāittīriya-Saṁhitā, p. 424-8; grammarians quoted by it, p. 430; classification of their quoted doctrines, p. 430-2; presumable alterations in it, p. 432; its character, p. 432-3.
- Tāittīriya-Saṁhitā, relation of, to the text assumed in the Prāticākhya, p. 424-7; its divisions, p. 430; names of different parts of, p. 430.
- Text, four kinds of, xxiv.1-4; various forms of, assumed by the Prāticākhya, p. 428-30.
- th*, dental mute, ii.38; changed to *th* after *sh*, vii.14.
- th*, lingual mute, ii.37; *th* changed to, after *sh*, vii.14.
- Tones (*yama*), the twenty-one, xxii.12, xxiii.11 etc.; tone of *om*, xviii.4.
- Tribhāshyaratna, manuscripts of, p. 1-3; different versions, p. 3; its sources, and meaning of its name, p. 6-7; works quoted in it, p. 435; its relation to and treatment of the Prāticākhya, 433-4; quotation of phrases not found in the Saṁhitā, 424-6.
- u*, *ū*: how formed, ii.24-5; combination with preceding *a*, *ā*, x.5;—combination of *u* with following vowel, x.15; resulting circumflex, x.16;—*ū*, *pragraha* as final, iv.5; result of irregular prolongation, iii.7, 14; occurrence of *prāṇīṣṭa* circumflex in, x.17.
- u*, particle, combination of, ix.16-7; finals combined with, p. 102-4.
- udatta*, see Acute.
- Uncombinable final vowels, x.13, 18, 24, 25.
- upadhmanīya* (*φ*), labial spirant, i.9, ii.44-5; its designation, i.18; occurrence, ix.2-4.
- Upāṅgas, enumerated, p. 422.
- v*, semivowel, i.8; how uttered, ii.43; irregular omission of, as initial, v.13; final, dropped, x.19-23; nasal *v* from *m*, v.28, 30; duplication after, xiv.2; resolution of usual *v* into *ur*, p. 64.
- Vājasaneyi-Brahmaṇa, referred to in commentary, p. 317.
- varṇakrama*, see Duplication.
- Veda, rewards promised for studying or teaching, p. 420-1; see also Yajurveda.
- Tāittīriya-Saṁhitā.
- Vedāṅgas, enumerated, p. 422.
- vikrama* accent, xix.1, 2; its tone, xvii.6.
- visarjanīya* (*h*), not a spirant, p. 14; how uttered, ii.46, 48; is surd, i.12; its designation, i.18; authorized in *saṁhitā* only before pause and *ksḥ*, ix.3; becomes spirant before surd, ix.2; dropped before spirant followed by surd, ix.1; to *s* or *sh*, before *k*, *kh*, *p*, viii.23-35; to *sh* before *t*, vi.5; omitted in *sak* etc., v.15-7; to *r* (except before *r*), viii.

- 6,7,16-7; do. in anomalous cases, v.10; do. after *a*, *ā*, viii.8-15; dropped after *ā*, *ā*, ix.9; to *y* (which is dropped) after *a*-vowel, before vowel, ix.10:—*ah* to *o*, ix.7,8; do. before *r*, p. 192-3, viii.18-22.
- Vocatives in *o*, treatment of, as *pragraha*, iv.6.
- Vowels (*a*, *ā*, *ā*, *i*, *i*, *ī*, *u*, *ū*, *ā*, *ī*, *ī*, *ī*, *e*, *ai*, *o*, *au*), i.5; the first nine simple, i.2; similar vowels, i.3,4; their common designation, i.20; quantity of, i.31-3,35-6; are sonant, ii.8; how produced, ii.17-29,31-2; combinations of vowels, and resulting accent, x.1-18; relation of consonant and vowel, p. 72, 375-7: see also the several letters, and Nasal vowels.
- Weight or quantity of syllables, xxii.14-5.
- y*, semivowel, i.8; how uttered, ii.40; dropped as final, x.19-23; *h* converted into, after *a*-vowel, ix.10; *n* converted into, ix.20; resolution of usual *y* into *iy*, p. 64-5.
- Yajur-Veda, depiction of, p. 421.
- yamas*, nasal counterparts, xxi.13; occurrence, xxi.12; how produced, ii.49-51; belong to what syllable, xxi.8.
- yamas*, tones, xxii.12, xxiii.11 etc.
- yā*, irregular omission of, v.19.

ADDITIONS AND CORRECTIONS.

PART of these emendations are due to Prof. Weber, who has called my attention to them in private communications. A few slight misprints, of obvious character, are not noted here.

p. 2, l. 25. The MS. used by Weber was another (No. 504) in the same collection, containing only the text (incomplete) of the Prāticākhya.

p. 3, l. 1. Dr. Ros's description of these MSS. has not yet appeared. It appears, however, that the rules of the Prāticākhya are read interspersed in the commentary also, as well as prefixed to it in a body (with separate paging).

p. 3, l. 4. The differences of reading in the Prāticākhya text itself are more numerous than is here stated. They have been pointed out in the course of the work (either in the notes on the rules, or in the various readings to the comment)—namely, as occurring (with here and there an addition, omitted in its proper place) in i.61, ii.17,51, iv.11,39 (T. W. *ahue*, for *'huc*), v.13,20 (G. M. *ṣakāras*, for *-ram*: a mere blunder), vii.8 (G. M. *yajush*, for *yajuk*), 12, viii.8 (T., it should be added, has dropped both *sanuta* and *stanuta*), 13,35, ix.21,22. x.11 (T. W. B. O. *anunāsikam*, for *'nun-*), 13 (G. M. *-pā asiparo budhniyā jyā ā pūshā aminanta drāhe*, which is perhaps the more acceptable reading, since it gives the uncombining finals their uncombining quality in the rule also), 22, xi.16 (G. M. *adabdhāsa* and *ashādhak*, with unelided *a*), 17 (G. M. *ahniyā mā 'mbolī*), 18,19 (G. M. repeat the whole rule, instead of its last two words only), xii.4,9 (T. O. *asmin*, for *tas-*), xiii.4,13,14 (see farther on), 15, xiv.3,8 (G. M. *upasargac ca pātha*: a blunder only), 13,32, xvi.1,5 (G. M. *ṣanśān anant-*: a blunder), 7,13 (G. M. omit *pīpivā* in the rule, as well as its example in the comment; but they give the word in the rehearsal at the beginning of the comment), 16,19,22,26, xvii.2,4, xviii.5 (T. *searitaṣ ca pl-*), xx.9 (G. M. substitute in the text-MSS. rule xvii.6, except the word *pūshkarasādeh*), xxi.5,6,14, xxii.7 (W. O. also have *shakak* in the rule, but not in the comment), xxiii.2,6,10,12,14,20, xxiv.4. The reading adopted for rule xiii.14 is that of T. G. M. (save that T. has *shtha* for *shya*, and *rāvnyā*, with *virāma* under the *v*; and G. M. have *rāvnyā* in the text-MSS., and *vīrānyā* in the MSS. with comment); W. gives *ṣṣṣṣ shay shtha mpa rāva* (with *virāma* under both *v* and *a*); for O. the collator has noted nothing; B. reads *ṣṣ shay shya mpa rāva grāva*. Other evident copyists' errors occur, of too little account to be worth notice.

A reading has been adopted contrary to the authority of all the MSS. at ix.1,20 (where the MSS.-reading is *ikāraūkrap-*), xi.1,17. The writing of *iṅgya* for *īṅgya* was noted under i.48.

p. 9, l. 16. The commentator, as will be seen under xxi.14, interprets out of existence the *ndīkyā* as an independent element.

p. 11, l. 7. The structure of *r* is defined by the commentator under xxi.15.

p. 18, l. 12. The commentator refers to some "different reading" (perhaps in his *Ākṣhā*? there is no trace of it in the Prāticākhya), beginning *pra pari 'pa sam*, but declares it to have to do only with the addition to all these words of *iti* (in the *pada*-text, namely, which writes *e 'ti* for *ā*, *ape 'ti* for *apa*, and so on) and not to their receiving the name *upasarga*. I still fail to see any reason for the limitation of the class to half its usual number.

p. 23, l. 13. Delete the hyphen at the end of the line.

p. 33, l. 16. One may conjecture that rule 43 formerly concluded the treatment of accent in this chapter, and applied to all the three kinds of accent; but, rules 44-7, on the circumflex, being later interpolated, the connection made it necessary to understand this also as applying to the circumflex alone.

p. 34, rule 46. The same example (from iii.3.111) is quoted by the comment under this rule as under rules 43 and 47.

p. 37, l. 19. Compare under rules xvi.26,29, where this claim is distinctly made. But it is not entirely well founded, for there are cases where combinations of sounds which are *padas* are quoted as *padāikadeṣas*: thus *han* in vii.11, *pā* in xvi.2, *hi* in xvi.13, etc.

- p. 42, ll. 28, 32, 43, read iv.23 (for iv.25).
- p. 46, l. 3. Read (in part of the edition) *alteration* for *nasalization*.
- p. 82, last line. Restore (in part of the edition) the lost figure 6 before *na*, at the beginning of the line.
- p. 83, l. 2. The passage is found at iv.1.51.
- p. 87, rule 5. For *aghd*, in rule and translation, read *adyā*; and the example, on the next page, is *adyācādd* (p. *adya-cāt*). The St. Petersburg lexicon (in the Appendix) has this word in its proper form, but I unfortunately overlooked it.
- p. 88, l. 28, and p. 99, l. 5. No division is made of *prāṭhga* in *pada*-text.
- p. 96, l. 28. Read *kāh* for *kāḥ* (in part of the edition).
- p. 101, l. 20. I have little or no doubt that the interpretation here suggested is the true one.
- p. 103, l. 7 from below. *To* is not an independent word: see the St. Petersburg lexicon, s. v. *totah*.
- p. 104, l. 24. So far as the vocatives in *o* are concerned, the existing *pada*-text appears to accord with the *Prāṭicākhya*: we have them with *iti*, as *pragrahas*, for example, at i.3.81, 147; 4.27, and without *iti* at i.2.132; 4.39. But *o*, *uto*, *upo*, and *pro* are followed by *iti* wherever they occur (for *to*, see the preceding correction), although this is not authorized by the *Prāṭicākhya*.
- p. 110, l. 32. The *pada*-text divides *dyāvā-prthivi*.
- p. 121, ll. 23, 24. Read (in part of the edition) *āindrāgni* and *indrāgni*.
- p. 123, l. 18. Insert the omitted example *tripī eratā vidathe antar eṣām* (ii.1.115).
- p. 124, l. 12. Read (in part of the edition) *pātam* for *palam*.
- p. 132, l. 15. But note the case reported under i.59 (p. 43).
- p. 138, l. 13. Read (in part of the edition) *nica* (for *nica*).
- p. 153, l. 27. I have omitted part of the passages in which *t* occurs before *śh*, namely vi.6.111.2; vii.2.87. It should have been added, too, that the *Sanhitā* furnishes no example of *n* before *śh*.
- p. 157, l. 23. The citation is from vi.3.31, as under the two preceding rules.
- p. 160, l. 24. This is not correct, so far as the existing *pada*-text is concerned. I was not aware at the time of writing the note that that text treated the *avagraha*-pause as suspending the continuance of accentual influence (see p. 369, first marginal note). The application of the rule, however, is as stated, compound words having been already provided for by rule 2.
- p. 167, l. 14. The peculiarity of accentuation referred to in the preceding correction would allow of these examples being brought under rule 4.
- p. 173, l. 20. Read *-parāṇuttayā*.
- p. 176, rule 11, translation. Read *havani*.
- p. 179, l. 12. The suggestion of *panaruktī* here is not well-founded, the sphere of action of the rules in this and in the thirteenth chapter being different.
- p. 183, l. 10. *Ahorātre pārye* is found in Tāitt. Ārayaka, at ii.13.2.
- p. 193, ll. 9, 10. References should have been given for the words *ahorātrābhyām* and *ahorātrayok*: the former is found at ii.1.73 et al., the latter at vi.1.31. *Adhishavane* occurs only at vi.2.114.
- p. 194, l. 14. The reference for *rukmo antar* is iv.1.104.5 et al.
- p. 199, l. 9 from below. The *pada*-text leaves *brhaspati* undivided, so that the combination does not come within the ken of the treatise at all.
- p. 199, l. 13 from below. Read (in part of the edition) ii.1.57 for ii.1.57.
- p. 205, l. 14. The omission of *h* before a spirant followed by a sonant consonant, here referred to as a doctrine held in schools of the Black Yajus, is practised in the manuscripts of our treatise and its commentary to a degree far beyond what can be regarded as merely accidental. G. M. observe it almost without exception, and it prevails also in the others.
- p. 209, rule 7. Doubtless *āśarvo* is to be understood here as an adjective, qualifying *visarjaniyāḥ* understood, 'h completed to *ah*,' as the comment clearly intends. This also removes the difficulty of *anvṛtti* spoken of on pp. 210-11, so far as the implication of *visarjaniyāḥ* is concerned.
- p. 216, l. 2. Read *is* for *does*.
- p. 218, l. 5. The example *paṇin* etc. occurs first at i.5.21.
- p. 222, l. 12. Read (in part of the edition) 'que' *vinān* (for *-mān*).
- p. 224, l. 4. Read *Also* for *Nor*.

p. 232, l. 26. I have noted here all the cases in which the *samhitā*-text shows *dha*, *mā*, or *pā* before *asi*; it appears, however, from Weber's edition of the *Samhitā*, that a part of them have *k* in *pada*-text after the *d*.

p. 233, l. 11 from below. Read (in part of the edition) *prope* 've (for *-pā*).

p. 239, l. 6. Read *o* for *a*.

p. 265, l. 5. The combination *śrīdhva asthāt* is in fact read first at iv.2.14, in an *ukhya*-passage.

p. 265, l. 10. There is, however, a case in which *a* is omitted according to the general rules, when by the letter, though not the spirit, of i.61 it ought to be retained; see under i.61 (p. 47).

p. 273, rule 12. I should doubtless have done better to adopt the reading *vāṇi-jāya* (for *dāy*-), in rule, version, and example.

p. 291, l. 24. *Achādevakāḥ* is found at vii.1.55.

p. 296, l. 9. Read *kṣhṣy* (by ix.3); and this would change the treatment of the group, since *k* (i.9) is not a spirant.

p. 301, l. 3. Read *kṣh*, *kṣhṣy*, *kṣhṣv* (by ix.3); so that *jīhvāmūlya* occurs only in the four remaining groups.

p. 302, l. 23. I can give no reference for *varshābhyah*, the reading at vii.4.13 being *varshyābhyah* *śvāḥ* 'varshyābhyah

p. 303, l. 9. I was heedless enough here to overlook the fact that a spirant never stands, according to the rules of this chapter, before either an aspirated surd or a nasal, since a first mute (by rule 9, above) is always inserted in such cases between the two. The groups *ch* etc., therefore, would be read according to this rule *chch*, instead of *chch*. The groups in which a nasal originally follows the spirant will be found catalogued under rule xxi.12 (p. 390). The example *tasmād* etc., below, is therefore no counter-example, and it is G. M. that are in the wrong in so calling it; it is to be read *taspmāt*, according to Plākshi etc., instead of *tasspmāt* (or, with *yama*, *tassppmāt*).

p. 304, l. 5. See also under xxi.16.

p. 308, l. 6 from below. Read *dhakore* for *-ra*.

p. 316, l. 10. Prof. Hadley's paper may be found printed in full in the Transactions of the American Philological Association (vol. I., 1871, p. 1 ff.).

p. 334, l. 7. Read vii.5.152 (for vii.5.142).

p. 336, l. 7. "Verbal forms"—that is, of course, all excepting *vijishī*.

p. 354, ll. 17, 25. See p. 426. Prof. Roth's MS. also ends with *samudrah*; he calls my attention, further, to the passage in the *Bṛhad-Āraṇyaka* (i.1.2), *samudra eva 'sya* [i. e. *acvāsyā*] *bandhuh samudro yonih*.

p. 356, l. 3. For *dhrta* as synonym of *pracaya*, see below, under xxiii.17 (p. 412).

p. 364, l. 24. And accordant, it may be added, with the practice followed in the *Vājasaneyi-Samhitā*, where there is no added figure, and no prolongation of the vowel.

p. 369, marg. notes, l. 6. The *anuddatta*-mark under *cu*- (the second time) has fallen out.

p. 373, l. 1. Read i.2.51 (for i.2.52).

p. 386, l. 18. The *e* sign has broken off in the *samhitā*-reading of *agne*.

p. 387, l. 7. I have considered this point more fully in a paper on the Sanskrit accent in the Transactions of the Am. Philological Association (vol. I., 1871, p. 20 ff.).

p. 414, l. 4. Read (in *Devanāgarī*) *kramarik*-, for *kramivak*-. (altered in the type, by some mishap, after the last correction).

p. 425, l. 29-30. *Achādevakāḥ* is found at vii.1.55.

p. 428, l. 37. But see, for the commentary, the additional note above to i.15 (or p. 18).

p. 429, l. 26. The *krama*-text is also quoted under ix.24 (p. 224) by O. alone.

p. 438, last line but one. Read xvi. for xxvi.

AMERICAN ORIENTAL SOCIETY.

Proceedings at Boston and Cambridge, May 16th, 1866.

THE Annual meeting was held at the usual place (the American Academy's room, in the Athenæum building, Boston), on Wednesday, May 16th, at 10 o'clock, A. M. In the absence of the President, the chair was taken by Dr. Jenks, the only Vice-President present, but was by him relinquished to Dr. Anderson, who conducted the deliberations of the meeting.

After the reading and acceptance of the minutes of the last meeting, the Committee of Arrangements announced their proposed programme for the present session, which was, on motion, ratified by the Society. After the noon recess, from 1 to 4 o'clock, the Society would re-assemble for hearing communications at Prof. Peabody's in Cambridge, and would adjourn at about 8 o'clock, in order to accept an invitation to a social gathering at Mr. L. R. Williston's.

1. *Treasurer's Report.*

RECEIPTS.

Balance on hand, May 17th, 1865,	-	-	-	-	\$632.39
Members' fees: ann. assessments for the current year,	\$265.00				
do. do. for other years,	125.00	390.00			
Sale of the Journal,	-	-	-	23.00	
Total receipts of the year,	-	-	-	-	413.00
					\$1,045.39

EXPENDITURES.

Printing of Journal (vol. viii, Part 2), Proceedings, etc.,	-	-	-	\$479.31
Binding and sundries,	-	-	-	16.00
Expenses of Library and Correspondence,	-	-	-	45.96
Total expenditures of the year,	-	-	-	\$541.27
Balance on hand, May 16th, 1866,	-	-	-	504.12
				\$1,045.39

2. *Librarian's Report.*

The accessions to the Library, though not so numerous and valuable as last year, had been important. Besides many continuations of series, 34 new printed works and 3 manuscripts had been received. The names of the donors were read, and the donations briefly described.

3. *Report of the Committee of Publication.*

The second half of Vol. viii of the Journal was reported as completed, and in process of distribution to the members. The Committee were unable to state when the printing of the next volume would be begun.

4. *Report of the Directors.*

The Directors appointed the next meeting of the Society to be held at New Haven, in October, and designated Professors Salisbury and Green and the Corresponding Secretary as a Committee of Arrangements for it.

They recommended for election as Members of the Society the following persons:

as Corporate Members,

- Rev. Nathaniel G. Clark, D.D., of Boston.
- Rev. Oliver Crane, of Carbondale, Pa.
- Mr. Richard J. Haldeman, of Pittsburgh, Pa.
- Mr. Charles W. Zaremba, of St. Joseph, Wisc.

as Corresponding Members,

- Rev. J. G. Auer, of West Philadelphia, Pa.
- Mr. Hyde Clarke, of Smyrna.
- Prof. Constantine Tischendorf, of Leipzig.

whereupon, ballot being taken, they were declared duly elected.

The Corresponding Secretary presented a list of the Members who had deceased since the last annual meeting:

CORPORATE MEMBERS.

- Prof. Charles Beck, of Cambridge.
- Rev. David Green, of Westboro, Mass.
- Rev. Edward C. Jones, of Philadelphia.
- Dr. Joseph E. Worcester, of Cambridge.

CORRESPONDING MEMBERS.

- Rev. Henry Ballantine, of Ahmednuggur, India.
- Rev. J. Edwards Ford, late of Sidon, Syria.
- Rev. C. C. Hoffman, of Cape Palmas, W. Africa.
- Rev. Homer B. Morgan, of Antioch, Syria.
- Rev. Samuel A. Rhea, of Orumiah, Persia.

HONORARY MEMBERS.

- Prof. Friedrich Rückert, of Coburg.
- H. M. Pawarendr Rames, Second King of Siam.

Of Dr. Beck—one of the oldest surviving members of the Society (he was elected in May, 1843, within a few months of its origination), for many years a Vice-President, and always one of its most active friends—an eloquent eulogy was pronounced by Prof. George M. Lane, of Cambridge, embracing a history of his life, an account of his literary labors, and an estimate of his character as a scholar and as a man.

Dr. S. H. Taylor, of Andover, and Mr. Charles Folsom, of Cambridge, also expressed in a feeling manner their sense of the loss which the Oriental Society, the community of American scholars, and the public at large, had sustained by the death of Dr. Beck.

Mr. Folsom farther set forth the services rendered to learning by the eminent lexicographer Dr. Worcester, and paid a merited tribute of respect to his memory.

Rev. E. Burgess and Dr. C. Pickering, of Boston, spoke in recognition of the labors and virtues of the veteran Indian missionary Rev. H. Ballantine.

Dr. R. Anderson, of the American Board, performed the same office toward his former colleague, Rev. Mr. Green, and the missionaries whose names are included in the list.

The Corresponding Secretary added a few words respecting some of them, and spoke more particularly of the renowned Orientalist and poet, Rückert, describing an interview which he had with him in 1852.

The election of officers being next in order, Mr. Folsom of Cambridge, Dr. Taylor of Andover, and Prof. Packard of New Haven were, in accordance with custom, appointed a Nominating Committee to make up and propose a ticket. To them was referred a communication from Prof. Salisbury, of New Haven, referring to the unwillingness with which he had accepted the office of President, to which he was elected three years before, and positively declining a re-election. The Committee presented the following candidates, who were then duly elected by ballot:

<i>President</i> —Pres. T. D. WOOLSEY, D.D., LL.D.,	of New Haven.
<i>Vice-Presidents</i> { Rev. WILLIAM JENKS, D.D.,	" Boston.
{ Hon. PETER PARKER, M.D.,	" Washington.
{ Prof. EDWARD E. SALISBURY,	" New Haven.
<i>Corresp. Secretary</i> —Prof. W. D. WHITNEY, Ph.D.,	" New Haven.
<i>Secr. of Classical Section</i> —Prof. JAMES HADLEY,	" New Haven.
<i>Recording Secretary</i> —Mr. EZRA ABBOT,	" Cambridge.
<i>Treasurer</i> —Prof. D. C. GILMAN,	" New Haven.
<i>Librarian</i> —Prof. W. D. WHITNEY,	" New Haven.
{ Rev. RUFUS ANDERSON, D.D.,	" Boston.
{ Mr. A. I. COTHEAL,	" New York.
{ Prof. W. H. GREEN, D.D.,	" Princeton.
<i>Directors</i> { Prof. J. J. OWEN, D.D.,	" New York.
{ Prof. A. P. PEABODY, D.D.,	" Cambridge.
{ Dr. CHARLES PICKERING,	" Boston.
{ Prof. JOHN PROUDFIT, D.D.,	" New York.

Mr. Folsom accompanied the report with remarks upon the withdrawal of Prof. Salisbury, which he was requested to commit to writing. This being done, those remarks were, on motion, formally adopted by the Society as an expression of its sentiments, and ordered to be entered upon the records of the meeting. They were as follows:

"When the Committee accepted their appointment, it was with the belief that they should find their duty limited to the indication of a successor to our late lamented Vice-President, Dr. Beck; and it is with deep regret that they have yielded to an understood necessity of naming for the office of President some other than the present incumbent. Not that they have hesitated for a moment whom to propose, if there must be a change.

"But the actual President of the Society so early began, and has so long continued, to contribute much of the best labor of his scholarly life to enriching the pages of the "Journal," and, in all its pecuniary exigencies, has taken such liberal care for its publication, that we have rejoiced in the hope of seeing him long at the head of an institution he has done so much to foster and adorn.

"As the Committee are happy to learn that the President's retirement from his present office is not owing to reasons of health, they propose that the Society do not relinquish him from the corps of its officers, feeling assured that in no condition will his personal efforts or other means of influence be withdrawn from that department of learning which he has hitherto so signally served."

The following communications were made:

1. Rev. M. A. Sherring, English missionary at Benares, being introduced to the meeting by Dr. Anderson, gave, by request, an account of Benares, as one of the chief religious and literary centres of India, and of its antiquities, which he had for many years been engaged in exploring.

2. Prof. Geo. E. Day, D.D., of New Haven, made a brief written communication, which was read by the Corresponding Secretary, respecting the Syriac version of the Revelation of St. Paul, of which the translation had been published in the last volume of the Journal. He explained the circumstances connected with the transmission to this country of the manuscript, which had been, at his own suggestion, searched out and transmitted to him by the late Rev. D. Stoddard. He then pointed out that the impression under which the Society had published the translation—namely, that the long-lost Revelation referred to by some of the Church Fathers had been now for the first time recovered—appeared to have been an erroneous one. On visiting Prof. Tischendorf in Leipsic, last summer, he had found him “just then engaged in preparing for the press a Greek text of the same apocryphal book, which he had discovered in Italy in 1843, and which he did not doubt was the original work referred to by Augustine and Sozomen. The volume in which it is contained, entitled “*Apocalypses Apocryphas Mosis, Esdræ, Pauli, Johannis, item Mariæ Dormitio*” (Lipsiæ, 1866, 8vo), has just been received in this country. Dr. Tischendorf, it seems, had given an account of the contents of this Revelation of Paul in the “*Theologische Studien u. Kritiken*” for 1851. He still holds the view he there expressed, that the book was probably composed in the year of the death of the emperor Theodosius (A.D. 395), but now hesitates to fix upon Palestine as the place in which the author lived. On comparing the Greek text, as given in two different manuscripts, with Dr. Perkins’s translation of the Syriac text, he pronounces the Greek form undoubtedly the purer and more ancient. Considerable additions, together with transpositions and other changes, have been made in the Syriac version. Occasionally, however, the Syriac text appears to supply some deficiency in the original Greek. The Syriac additions (as translated into English), together with other variations, Dr. Tischendorf has given in notes at the foot of the page. As the matter now stands, we may regard the recovery of this part of the apocryphal literature of the New Testament as more complete than if either the Greek or the Syriac text alone had been published.”

3. Specimens of the recently printed Turkish Commentary on the Koran, by Mr. John P. Brown, of Constantinople; read by the Corresponding Secretary.

Mr. Brown’s letter, accompanying this paper, is dated January 16th, 1866, and reads as follows:

“I send you a translation of the 1st and 112th chapters of the Koran, made from a very interesting work which has recently been printed here, under peculiar circumstances. You are aware that the Sunnee Moslems have always held that it is sinful to print the Koran, and even to attempt to translate it. Many commentaries, nevertheless, exist; some of them, probably, printed, though mostly to be found only in manuscript. It is said here that the Sultan, having become aware that the Christians possess the Bible in each of their own languages, while the

Koran remains in Arabic, and therefore unknown to the masses, ordered that a concise version should be printed in Turkish, under the title of a "Commentary." It is styled "A Translation (called *Mendhib*, 'Gifts') of the Commentary called the *Mendhib*, 'Escorts,' by the Member of the Divan of the Sublime Porte, Ismail Feraklı Effendi." The title *Mendhib*, 'Gifts,' may also denote that it is printed mostly for private distribution; though it is, at the same time, actually for sale. I have a copy for the Oriental Society.

Most of the versions of the Koran are open to criticism, and I have not found one which does justice to the ideas of its author. Translated literally, and restricted to the words of the original, without some necessary license, a version gives but little satisfaction; and to explain the definition by notes is tedious. In making my literal translation of the Turkish definition, I have not examined any existing translation, to see how far the two agree with each other. It would be of interest to translate the whole of this work, as I am sure that it would throw some more light upon the ideas of the able and talented man who, for the purpose of withdrawing his fellow-men from idolatry, imagined so many sublime verses. I have selected the two chapters mentioned, as they are the basis of his particular creed, or belief, respecting the Deity."

The translation of the two brief chapters, and of the commentary upon them, is expected to be given in full in the next volume of the Society's Journal.

4. On the Origin of the English Possessive Case, by Prof. James Hadley, of New Haven; read by the Recording Secretary.

The paper of Prof. Hadley was a review of an essay on "The English Possessive Augment," by Serjeant James Manning, of Oxford, Eng., published in the Transactions of the Philological Society (London, 1864). Mr. Manning holds that the Anglo-Saxon genitive was given up in the 13th century, and its place supplied by of with the accusative; but that, for the possessive relation, a special form was then introduced, such as "father *his* book," "mother *his* gown," "children *his* plaything," which gradually passed into "father's book," "mother's gown," "children's plaything." Against the common view, which identifies the *s* of our possessive with that of the A.-S. genitive, he urges that the latter was not applied to feminines and plurals, and that it was used for many relations which are not expressed by our possessive. But Prof. Hadley referred to examples of grammatical forms (as the *s* of plural nouns in French and Spanish) extended to classes of words that once excluded them, and of forms (as the Latin perfect indicative active in all Romance languages) restricted in the range of meanings that once belonged to them. He examined the constructions of our possessive which Mr. Manning regards as inconsistent with its genitive origin. In "Caesar's crossing the Rubicon," we have only the ordinary use of a genitive to denote the subject of an action. In "John and Walter's house," the possessive *s* is added to "John and Walter" taken as a complex whole; compare *eth* in "three-and-twentieth." The same explanation applies to "King of England's crown;" compare *ism* in "Church-of-England-ism." In "a servant of my brother's," Lowth regarded "brother's" as depending on "servants" understood—an explanation which fails for "that wife of my brother's;" it is better to regard the genitive here as dependent on a general idea of "belongings," "that which belongs," the same idea which is evidently understood in "all mine is my brother's." Positive arguments for his own view Mr. Manning draws from the popular dialects of modern Germany, and from the usage of Semi-Saxon and early English writers. But while the common German says "*des Vaters sein Buch*," he says "*der Mutter ihr Kleid*;" if our English possessive were of the same nature, we should have, not "mother *his* gown" (according to Mr. M.'s theory), but "mother *her* gown." That the Gothic reflexive *seins* and the Latin reflexive *sui* mean *her* and *their* as well as *his*, proves, at most, only a possibility that *his* might be so used in place of *her*: that it was actually and currently used in this way, there is no sufficient reason for believing. In almost every instance where it seems to be used, *his* refers to a word like *wife*, *maiden*, *child*, which in Anglo-Saxon were neuter, not feminine. Mr. Manning gives great prominence to a comparison between the two manuscripts of Layamon's Brut, in the first of which, written about 1200 A.D., the genitive expressed by *his* is rarely, if ever, met with; while in the second, written perhaps sixty years later, such forms are of common occurrence. Even here, in ex-

amining the first 9000 lines of the poem, Prof. Hadley had found, from common nouns, about eighty genitives with inflectional *s*, and only two expressed by *his*: from proper names of place, thirteen with inflectional *s*, and two expressed by *his*: even from proper names of persons, where the genitives expressed by *his* are numerous, there are nearly as many with inflectional *s*, and the two forms are freely and capriciously interchanged. In the *Ormulum*, written by a very careful scribe at a time not earlier than the second text of Layamon, the form with *his* is never once used. And although this form is often seen in old English writings, and down to the beginning of the last century, yet it appears, on the whole, as an occasional—and, seemingly, a merely orthographic—variation of the inflectional genitive—a variation suggested by a false, though plausible, etymology, and favored by the general confusion of early English orthography.

In connection with this paper, Prof. Whitney referred to another and wholly new account of our possessive suffix, given in the "Reader" for Sept. 24, 1864, in the form of a critique upon Mr. Manning's essay, under the signature of Th. G. [Prof. Goldstücker]. Its author accepts as satisfactory Mr. Manning's disproof of the relationship between the suffix in question and the ancient genitive-ending, but regards the former as a mere connecting-link between the name of the possessor and the thing possessed, binding them together into a kind of compound. Prof. Whitney combated this view, as in a high degree far-fetched and fanciful, and attempted to overthrow the arguments by which it was supported. There is no more difficulty, he claimed, in supposing the retention of a true synthetic form along with the elaboration of an analytic substitute for it in the case of *John's son* and *the son of John*, than in the case of *I loved* and *I did love*. The position of the possessive before the thing possessed is no more fixed in the case of a noun than in that of a pronoun, as *his* or *her*, which no one would think of denying to be ancient genitives. And the *s* in such German words as *Hilfsgruppen*, *Liebesgabe*, is really a genitive-ending, or introduced after the analogy of such; precisely as is the *s* of *nachts*, formed after the analogy of *abends*, *morgens*, etc.

5. On the Beginnings of Indo-European Speech, by Prof. W. D. Whitney, of New Haven.

This paper was intended to meet the objections of those who are unwilling to receive the prevalent belief respecting the character of the germs of the languages belonging to our family—namely, that these are radical syllables, indicative of action or quality—and who hold that the first words must have been, rather, signs for concrete things. The fundamental error with such persons is that they confound the *primum cognitum* and the *primum denominatum*, which are, in fact, entirely independent of one another. Without doubt, the synthetic apprehension of concrete objects as such preceded the analytic apprehension of their qualities; but no language-making was possible until analysis had begun. It is impracticable to make a sign directly designating a complex existence; we can get hold of it only by its distinctive qualities. All the processes of word-making, throughout the later history of language, are based upon this principle, and the earliest must have been of the same character. The writer argued at some length against the doctrine that thoughts are impossible without words, and that general ideas are not conceived by beings inferior to man; and he endeavored to set forth and illustrate the characteristic differences between the mental action of man and of the lower animals. It was because all language-making is a devising of intelligible signs, to be used in communication between man and man, for ideas which have been conceived and for which expression is desired, and because an intelligible sign, uttered or acted, can only body forth an act or quality, that the first utterances must have directly meant the latter, and have been applied by a secondary process to designating the beings to which these belonged.

6. On the Origin and Antiquity of the Hindu Astronomy, by Rev. E. Burgess, of South Franklin, Mass.

Mr. Burgess defended at considerable length the originality of the Hindu science. His arguments were briefly controverted by Prof. Whitney.

No farther communications being offered, the Society adjourned.

Proceedings at New Haven, October 24th and 25th, 1866.

PURSUANT to adjournment, the Society assembled on Wednesday, October 24th, at 3 o'clock, P. M., in the Library-room of the Sheffield Scientific School of Yale College, at New Haven.

The chair was taken by the President, Pres. Woolsey of Yale College.

The minutes of the preceding meeting were read by the Recording Secretary and approved.

The Committee of Arrangements reported the order proposed by them for the present meeting: that the literary session be adjourned at about 6 o'clock, till 9 o'clock on Thursday morning, and that the Society accept the invitation of the Corresponding Secretary to meet socially at his house on Wednesday evening. The report was accepted, and the order adopted.

The Directors announced that they had designated Wednesday the 15th of May, 1867, as the day on which the next Annual meeting should be held in Boston, and had appointed Prof. Peabody of Cambridge, with the Recording and Corresponding Secretaries, a Committee of Arrangements for that meeting.

They further recommended for election to membership, as Corporate Members:

Rev. William H. Fenn, of Portland, Me.
Mr. Henry M. Pierce, LL.D., of New York.
Rev. Thomas C. Pitkin, D.D., of Buffalo, N. Y.
Dr. Ernst Schmid, of White Plains, N. Y.
Rev. James R. W. Sloane, of New York.
Mr. E. Bailey Smith, of Middletown, Conn.
Gen. A. von Steinwehr, of Wallingford, Conn.
Mr. Albert B. Watkins, of Fairfield, N. Y.

and, as Corresponding Member:

Dr. Adolf Bastian, of Bremen.

The correspondence of the past half-year was next presented, and read in part. Among the extracts read were the following:

From Rev. E. B. Cross, dated Toungoo, May 17th, 1866:

"I enclose to you a paper which I have prepared on the Karens and their language. In 1853, I gave the Society, by request, an article on the traditions and religious beliefs of the Karens.* A great deal which was then unknown in regard to the different tribes of this remarkable people has since been discovered.

"I have dwelt on the peculiarities of Karen grammar, without entering into extended comparisons with the grammars of other languages. It will be seen that this is plainly a member of the general family of languages of Farther India; and the distinctness of its peculiar features might almost entitle it to claim the place of typical language of the family. The philosophy of its grammar is essentially different from that of the grammars of the West. It may be safely said that, if an intelligent and competent scholar should reduce the Karen grammar to its true system, without taking western grammars for his model, nearly the whole nomenclature of the science would be changed.

"I have by no means exhausted the subject, either of the general characteristics,

* Printed in the Society's Journal, vol. iv, p. 289 seq.

or of the number and peculiarities of the dialects of this language. The gospel is advancing among the Karen people, and revealing new tribes and new varieties of speech.

"But this people are interesting not solely by reason of the variety of dialect exhibited by them. Like the Jews of heathen Greece and Asia Minor in the times of the Apostles, the Karens are the lodging-place for the beginning of the gospel."

From Rev. H. H. Jessup, dated Beirut, Sept. 19th, 1866:

"I take pleasure in sending you, for the Society, the first volume of Mr. Butrus Bistany's new Arabic lexicon, the *Muhit el Muhit*. Mr. Bistany is going on with the publishing of the two remaining volumes as rapidly as possible. The price to non-subscribers will be four pounds sterling for the three volumes. I think you will be pleased with it."

From Hyde Clarke, Esq., dated Smyrna, July 7th, 1866:

"What is going on in these districts is chiefly in the way of illustration. For the Troad, Mr. Frank Calvert has communicated to me a new memoir, with his latest observations, which I publish in Murray's Handbook for Turkey, with other observations. The Baron Paul Des Granges, of Athens, a photographer of eminence, has just visited me on his return from the Troad, where he has taken numerous views for the new work of the learned Dr. von Halin, the Austrian consul at Syra, who has lately taken up that region. Mr. R. Poppleton Pullane, an archeologist of reputation, has just arrived here. He is charged with a mission from the Dilettanti Society to excavate on the site of the temple of Apollo Smynthus, near Assos, in the southern Troad.

"It may be mentioned, as a curious confirmation of ancient traditions, that during the spring the fields in the neighborhood of Pergamus have been ravaged by hosts of mice. The Smynthian Apollo was the foe of mice. These vermin have this year done much harm to Turkey.

"On the Lydo-Assyrian monuments of our district I have already communicated to you the latest news.

"In the Ephesus district Mr. Sroboda has continued to take numerous photographs, and has proposed to me the publication of a joint work. I hope he will next take Magnesia ad Mæandrum. He has also executed fourteen views for a work on Ephesus proposed by Mr. J. T. Wood, an architect employed on excavations by the British Museum.

"M. Ernest Renan, I understand from his communications, will in his next volume embody his observations made during his investigations at Ephesus. I examined at his request the church of St. John, and obtained further evidence. My opinion is that this church and the great mosque are identical.

"I have not found anything in my late explorations of the Ephesus district. I spent some time fruitlessly on the question of the Roman roads beyond Anziel, one the main road from Ephesus to Magnesia ad Mæandrum, and the other, perhaps, a road from the Panionium to Magnesia.

"Mr. Wood thinks he has discovered the shrine of St. Luke at Ephesus, but this opinion rests on no good evidence.

"Mr. Sroboda has photographed Aidin, the ancient Tralles."

From the same, under the same date:

"I send you the *Revue Archéologique* of Paris, with a memoir by Messrs. Georges Perrot and Edmond Guillaume on the Pseudo-Sesostris of Ninfi. It gives some of the most recent opinions of the learned world on the Lydo-Assyrian monuments of Asia Minor, with many notes of my own, and will put the Society in possession of the present state of this new and important subject, which involves a modification in the ancient history of Asia Minor.

"I differ from the learned authors as to the road from Sardis to Smyrna and that from Ephesus to Phocæa, as referred to by Herodotus, and I think I have informed the Society of my last year's explorations. It is quite true that the present monument is off the road from Sardis to Ephesus; but this is only an error of Herodotus, and I doubt if he ever saw the monument. The present is not the first attempt to represent the pass in which the monument is as the road from Ephesus to Pho-

case. But I doubt the identification, for the following reasons: The pass in question does not appear to represent a main road. If treated as the road from Ephesus to Phocæa, the traveller would, on reaching the plain of Cassaba or the Nini Chai, have a troublesome route to Phocæa, either all the way around by Magnesia ad Sipylum and the valley of the Hermus, or crossing the difficult pass of Kavakli Dereh (the present road from Kassaba to Smyrna), and so along the Boornabat plain.

"There is another well-defined pass leading off the Ephesus road at the foot of the Takhlatu mountain by the villages of Takhlatu to the village of Achiklar, right into the Boornabat plain. At Takhlatu are such large remains as are only to be explained by a well-frequented route. I now conceive that the second Sesostris is to be sought for at the back of the mountain on which is the first.

"I may observe that on the cliffs near Ephesus are some niches as well-defined as those of the Pseudo-Sesostris or Niobe."

From the same, under date of June 18th, 1866:

"The receipt of the Pseudo-Sesostris has been already acknowledged by the Society, and I have since sent the photograph of the Niobe. I now send the photograph of the newly discovered colossal head near Smyrna, found by Mr. Frederick Spiegelthal, and photographed by Mr. A. Svoboda. This monument is on a smaller scale than the others, and does not embrace the whole figure. I consider it, however, as belonging to the same general group, and class it as Lydo-Assyrian. It is about one mile from the Caravan Bridge, and the same distance from the Baths of Diana (Hulka Boonar), on a part of the Boojah range, in the valley of St. Ann or the Meles, opposite Mt. Pagus. It is on the cliff or wall of an amphitheatral opening, partly quarried, and, as I think, partly natural, and which has doubtless been used as some kind of theatre.

"The head is carved on a projecting knob of limestone, and Mr. Svoboda's photograph shows the best side of the figure, but the necklace is not so well defined on that side as on the other. The nose, left eyeball, and mouth are marked and injured by musket-balls, some of them fired by shepherds within the last few years. The large ears we consider to represent horns. The necklace is well cut, and consists of oblong discs strung together. What by others are considered as a human arm and hand I rather look upon as the paw and claws of a beast.

"On each side of the head, down below, are large rock-cut tombs, one of which, to the left, consists of two chambers, and is inhabited by a beggar. The neighboring amphitheatral formations also show signs of tombs.

"We continue our researches, in the hope of finding the other Pseudo-Sesostris described by Herodotus. In this month, Mr. Spiegelthal has made a most interesting discovery, namely of a reproduction or replica of the well-known Pseudo-Sesostris of Nymphaum, described in my former paper. It is close by on the same brook, but lower down on the margin of the brook, and obscured by brushwood.

"Mr. Spiegelthal affirms that it is colossal, like the other, and has the same details, lance, bow, etc., but that the face is more injured. He has arranged for me to examine it.

"Mr. Georges Perrot has called my attention to a rock-cut monument mentioned by Mr. Hamilton as near Isbarteek (Sparta tès Pisidias), in the interior, and I had despaired of getting any account of it; but fortunately an archaeologist has proceeded there, and I have applied to him."

After the reading of the correspondence, communications were declared in order.

1. On the Niobe of Magnesia ad Sipylum; and, On the newly discovered Lydo-Assyrian Monument of Smyrna; by Hyde Clarke, Esq., of Smyrna.

These two brief papers were read by the Corresponding Secretary, in connection with the letters of Mr. Clarke on the same and kindred subjects, given in full above. Each was accompanied by a photograph of the monument treated of. Mr. Clarke expresses his opinion that the Niobe is altogether an artificial work, against those who hold that it is a natural formation, or such a formation touched up and per-

fectured by artificial labor. Besides the tomb near the other monument now occupied by a beggar, spoken of in the letter, Mr. Clarke says that in the adjoining hollow are evidences of rock-cut tombs blocked up with masonry, which he is hoping to explore.

These papers bear date of May 3d, 1866.

2. On the Formation of the Chinese Language, by Rev. E. W. Syle, of Pelham, N. Y.

Mr. Syle gave a succinct account of the characteristic features of the Chinese, and of its mode of writing, illustrating his remarks by reference to written documents. He described the process of learning the written language practised in the native schools, and thought that the absorption of time and mental effort in the task of acquiring and handling an instrument so unmanageable and burdensome was one of the main causes of the comparative stagnation of the Chinese mind.

3. Rev. S. H. Calhoun, D.D., of the Syrian Mission (at Abeih), explained the present position of affairs in the neighborhood of his field of labor, and described various journeys which he had made in and about the chain of Lebanon, speaking more particularly of his visits to Baalbec, and of the aspect of the ruins there.

The Society met again at 9 o'clock on Thursday morning, in the same place.

Before the reading of communications was resumed, the Corresponding Secretary brought once more to the notice of the Society the subject of the Bopp Fund, first presented before them a year ago, and read from the last circular of the Committee (dated May 16th, 1866) their proposal as to the disposition to be made of the income of the fund (which now amounts to 8000 thalers): it is to be applied to "the support of a young scholar, of whatever country, who shall have already completed his university studies, in order to the continuance of the same, wherever it may be; as also, to the bestowal of prizes for completed scientific labors, or to the support of scientific undertakings—in all cases, of course, only within the departments cultivated by Prof. Bopp, of Sanskrit philology and comparative grammar, with special reference to the Indo-European family." The Secretary stated that the American subscriptions to the fund now amount to two hundred dollars, which sum he hoped would be yet farther increased.

The Secretary also read, from the last-received number of the *Monatsberichte* of the Berlin Academy, an account by Prof. Lepsius of his recent discovery of a bilingual (hieroglyphic and Greek) monument at Tanis in Egypt, longer than the celebrated inscription of the Rosetta stone, and in a perfect state of preservation. He pointed out the exceeding interest and importance of the discovery.

4. On the Chinese Musical Notation, by Rev. Mr. Syle.

Rev. Mr. Syle explained the method in which the Chinese managed to indicate musical tones, their length, and their accent, and in which the combination of the tones with the words intended to be sung to them was made. He further characterized the Chinese gamut and the style of the national music. His explanations were fully illustrated with charts and other documents.

5. On the Cedars of Lebanon, by Rev. Mr. Calhoun.

The speaker described his visits to the celebrated grove of these trees, so well known by the accounts of travellers, and gave a very interesting description of its

situation and aspect, with details respecting the age and mode of growth of the trees. He also spoke of other groves of the same tree upon other parts of the same range.

6. On the Classifications of Languages, by Prof. W. D. Whitney, of New Haven.

This paper was stated to be mainly an extract from a general treatise upon language and its study which the writer had now in press. The classification of languages into families, on the ground of proved or probable descent from a common ancestor, was first succinctly sketched, and the evidences on which it reposes were reviewed, being shown to be in part correspondences of material, in part morphological correspondences or analogies of structure. The less certain and satisfactory character of the latter kind of evidence was alluded to. The morphological classification, depending upon style of structure only, was then set forth—the division of human tongues into monosyllabic and polysyllabic, into isolating, agglutinative, and inflective, and so on. The defects of this mode of classification were pointed out: as its inequality, there being but one genetic family in the isolating class (the Chinese etc.), and two in the inflective (Indo-European and Semitic), while the great mass of languages was agglutinative; the heterogeneity of its classes, there being differences of structure between the two inflective families, as also between certain of the agglutinative families, hardly, if at all, less important than those which separate the great classes; and its indistinctness, certain languages constituting transitional forms between one class and another. Müller's distinction of "family," "nomadic," and "state" languages was criticised. Schleicher's scheme of formal notation for the characteristic features of linguistic structure was explained and illustrated. Classification by general value as means and instrument of expression was also spoken of, the various and diverse items of value which have to be taken into account in making out such a classification were pointed out, and the difficulty of the task indicated. Finally, the superior value and importance of the genetical method was shown; it is the first and directest object at which the comparative philologist aims, it furnishes the necessary foundation of all the others, and with its establishment are directly connected those more general ethnological conclusions which form so conspicuous a part of the interest of linguistic science.

7. Rev. Mr. Syle exhibited a number of Chinese pictures illustrating the national superstitions, especially those connected with the doctrine of transmigration, and accompanied the exhibition with oral explanations.

8. On the Karens and their Language, by Rev. E. B. Cross, Missionary in Farther India; read by the Corresponding Secretary.

Mr. Cross's letter accompanying this paper has been given above.

The paper begins with an account of the name "Karen," which Mr. Cross explains as signifying 'first, aboriginal,' and regards as indicating the belief by the Burmans that this was the race of original possessors of the soil. Their language was first reduced to writing, by the missionaries of the American Baptist board, about thirty years ago, in two principal dialects, the Sgau and P'gho (P'wo, Shu), of which the former is looked upon as the especially typical language of the race. The grammatical and lexical works in which they have been already treated are mentioned, and Mr. Cross then proceeds to draw out his own independent statement of the peculiarities of Karen speech, treating first of the spoken alphabet, including the five (or six) tones which, as in the other monosyllabic tongues, are used to help the variation of meaning of the words, then taking up the means of expression of grammatical relations, by the means of affirmatives or adjunctive words. Into the details of the statement it is impossible here to enter. The clannishness and segregation of the tribes of Karens, and their necessary consequence, the great variety of dialects, are spoken of, and an enumeration of many of these dialects is given, with indication of their relations and respective importance—it being stated, however, that there are not a few tribes of which the names only are known.

By way of appendix, Mr. Cross reports a Karen tradition respecting the origin

of their race, in two versions, as given by the Sgau Karens and by the eastern Bghais, two extreme members of the race. It represents them to have come from the west, along with their brothers, the Chinese, and to have been left behind by the latter. The Bghai tradition speaks of a metal plate as left by the departing Chinese for their ancestors, and of this plate Mr. Cross remarks: "The book, or brass and gold plate, spoken of in this tradition, is still in existence. It is said by a trustworthy and learned Karen, Rev. Quala, who has seen and examined it, to be a thin lamina of metal, of a very dark color, and smooth and shining; and one end seems to have been cut off, so as to destroy some of the letters. The letters are said by Quala to resemble those of the Hindustani, and to be entirely unlike the Burmese. The same authority states that the Red Karen King, Kaiphogyee, who holds this plate, has also in his possession five ivory plates, in shape and size like the ordinary Burmese palm-leaf strips, or about two feet in length by two and a half inches in width, and covered with the same kind of characters."

After the reading of this communication, the Society adjourned.

Proceedings at Boston and Cambridge, May 22d, 1867.

THE Society met at the usual time and place, and was called to order by the President soon after 10 o'clock.

After the reading of the minutes of the last meeting, it was voted, in accordance with the recommendation of the Committee of Arrangements, to adjourn the morning session about 1 o'clock, to re-assemble at 4 o'clock, at Dr. Peabody's, in Cambridge, and to adjourn at 8 o'clock, in order to accept an invitation kindly tendered by Dr. Peabody, to take tea socially with a few friends at his house.

The Treasurer's Report was presented, audited, and accepted. It showed the receipts and expenditures of the year to have been as follows:

RECEIPTS.

Balance on hand, May 16th, 1866,	-	-	-	-	-	-	\$504.12
Members' fees: ann. assessments for the current year,	\$410.00						
do, do, for other years,	185.00	595.00					
Sale of the Journal,	-	-	-	-	-	6.00	
Total receipts of the year,	-	-	-	-	-	-	601.00
							\$1,105.12

EXPENDITURES.

Binding books,	-	-	-	-	-	-	\$21.25
Expenses of Library and Correspondence,	-	-	-	-	-	-	34.11
Total expenditures of the year,	-	-	-	-	-	-	\$55.36
Balance on hand, May 22d, 1867,	-	-	-	-	-	-	1,049.76
							\$1,105.12

The Librarian made a brief statement respecting the additions to the library and cabinet during the past year, and said that the full acknowledgments would be printed along with the Proceedings at this meeting (see below).

The Committee of Publication reported that, owing to unfavorable circumstances, nothing had been issued from the press by the Society during the past year; it was hoped that the printing of Vol. ix of the Journal would soon be begun: the *Tāittiriya-Prāṭicakhyā*, text, commentary, translation, and notes, was expected to occupy a considerable part of it, as already some time since announced. In view of the intermission of any issue of the Journal since the last annual meeting, the Committee had recommended that no annual assessment be levied upon the members for the year 1867-8, and this recommendation had been considered and approved by the Directors, and was, by their authority, presented to the Society for acceptance.

Hereupon, on motion, the recommendation was accepted by the Society, and the assessment for the year suspended.

The Directors announced that they had appointed the autumn meeting to be held in New Haven, on Wednesday, Oct. 16th, 1867, unless

the Committee of Arrangements—Prof. Salisbury of New Haven, Mr. Cothrel of New York, and the Corresponding Secretary—should see reason to fix on some other day in the same month. Also, that they had designated Prof. Hadley of New Haven and Mr. J. H. Trumbull of Hartford, with the Corresponding Secretary, a committee to examine, at the request of Prof. Henry, Secretary of the Smithsonian Institution, an ethnological essay by Mr. L. H. Morgan of Rochester, on systems of consanguinity, and to report upon its worthiness to be accepted for publication by the Institution.

The following gentlemen, recommended by the Directors, were elected Corporate Members of the Society:

Rev. Edson L. Clark, of Guilford, Conn.

Mr. John Fiske, of Cambridge, Mass.

Prof. Charles M. Mead, of Andover, Mass.

Announcement was made to the meeting, by the Corresponding Secretary, of the Society's loss by death during the past year of three of its members, Rev. Dr. William Jenks of Boston, Rev. Dr. William Goodell, late of the Constantinople mission of the A.B.C.F.M., and Mr. Theodore Dwight of Brooklyn.

Rev. Dr. Anderson, of Boston, gave a sketch of the life and labors of Dr. Jenks. With him, as much as, or more than, with any other person, originated the idea of the American Oriental Society, one of whose Vice-Presidents he had been from its inception in 1842, although now long prevented by deafness from taking an active part in its deliberations. He was born in 1778. He held for some years the Professorship of Oriental and English literature in Bowdoin College. His chief literary work was the compilation of the Comprehensive Commentary. He was a man of profound learning and extensive reading, and his private library, thirty years ago, was reputed one of the best in New England.

Dr. Parker, of Washington, also spoke of the services rendered by Dr. Jenks to various departments of learning and philanthropic effort.

Rev. Dr. Clark, of Boston, paid the merited tribute to the worth of the venerable Dr. Goodell, who had finished his missionary labors in the East a year or two since, and returned to pass a brief remnant of life among his friends at home.

Rev. Mr. Syle, of Pelham, N. Y., spoke briefly and with much feeling of the character of Mr. Dwight, his devotion to every good work, and his services as for a long time Secretary of the American Ethnological Society.

Out of the remarks of Dr. Parker grew a discussion of the recent progress of western ideas and institutions in China and Japan, in which, besides himself, Rev. Mr. Syle, and Rev. Dr. Pitkin, of Buffalo, took a part.

Mr. J. S. Ropes, Dr. Clark, and Prof. Hoppin were appointed a committee to nominate officers for the next year. Pres. Woolsey desired to decline a nomination for re-election as President, but was prevailed upon by the general remonstrances of the members present to withdraw his objections. The following ticket was offered by the committee, and elected without dissent:

<i>President</i> —Pres. T. D. WOOLSEY, D.D., LL.D.,	of New Haven.
{ Rev. RUFUS ANDERSON, D.D.,	“ Boston.
<i>Vice-Presidents</i> { Hon. PETER PARKER, M.D.,	“ Washington.
{ Prof. EDWARD E. SALISBURY,	“ New Haven.
<i>Corresp. Secretary</i> —Prof. W. D. WHITNEY, Ph.D.,	“ New Haven.
<i>Secr. of Classical Section</i> —Prof. JAMES HADLEY,	“ New Haven.
<i>Recording Secretary</i> —Mr. EZRA ABBOT,	“ Cambridge.
<i>Treasurer</i> —Prof. D. C. GILMAN,	“ New Haven.
<i>Librarian</i> —Prof. W. D. WHITNEY,	“ New Haven.
{ Mr. A. I. COTHEAL,	“ New York.
{ Prof. W. W. GOODWIN, Ph.D.,	“ Cambridge.
{ Prof. W. H. GREEN, D.D.,	“ Princeton.
<i>Directors</i> { Prof. J. J. OWEN, D.D.,	“ New York.
{ Prof. A. P. PEABODY, D.D.,	“ Cambridge.
{ Dr. CHARLES PICKERING,	“ Boston.
{ Prof. JOHN PROUDFIT, D.D.,	“ New York.

Communications were next called for.

1. Rev. N. G. Clark, D.D., Secretary of the A. B. C. F. M., read extracts from a letter lately received from Rev. O. P. Allen, Missionary at Kharput, relative to certain ruins in Kurdistan, north of Diarbekir. The letter bears date of Nov. 5th, 1866. Mr. Allen says:

Our road to-day leads out of the valley in which Hazro is built, and we come out upon the highlands of the Diarbekir plain. We are now entering the Koordish speaking region. We stopped awhile at Hashtar, an Armenian village of fifty or sixty houses, where they know only Koordish. Passing by Bulbal and Atsha and other villages, we reached Farkin early in the afternoon. This was once a large city. It was surrounded by a wall which is still standing, being broken down in only a few places. The foundation is built of round stones, but the upper portion of huge hewn stones. The Armenians of the place all speak Koordish, and know scarcely anything of Christianity. This will be one of the first places to occupy as an outstation. We went over some of the ruins, having with us Consul Taylor's pamphlet giving an account of his explorations. We first went to the southeastern corner, where is a stately pile of ruins, said to have been built by St. Marutha over the graves of the christian martyrs slain by the Persian king Shapur. It was once a beautiful building, and seems intended rather as a monument than for a church. The outside walls and some of the pillars and arches are still standing. Other columns two and a half feet in diameter, of porphyry, beautifully polished, had fallen. The capitals of the columns are singular, looking exactly like a basket of wicker work set on the top of a column. These were finely carved from a softer kind of stone. There are many other buildings near this, but so broken down that we could not determine what they were. The ground about the monument church is thickly laid with grave stones. Passing on around the eastern end, the wall is double, and in a good state of preservation. There are many inscriptions, but none of very ancient date, it is said. An extensive ruin at the north-east corner looks like an old palace. Considerable space inside the walls is cultivated. At the western side is a beautiful mosque, which, from an inscription read by Mr. Taylor, seems to have been built in the year 624 of the Hejira or 1213 of our area, by Modhuffer ed Deen Ghazi, nephew of Selah ed Deen, or Saladin, as he is usually called. The most interesting ruin was an old christian church which seemed much older than the mosque. Its walls, 3 feet thick, are made of large blocks of hewn stone. Three sides are standing. The two gable ends show that it had a slanting roof, like the Grecian temples. A portion of the eastern wall is semi-circular, to form a space for the pulpit or altar. This space was frescoed, probably, as the stones are fitted to hold the plaster. Above this is a beautifully carved cornice. The capitals are the real Corinthian, carved in stone. Its interior width is 75 feet, its length 108 feet, its height

to the eaves about 30 feet. But we could not examine the ruins as we would gladly have done, as we had only a couple of hours where one would need to spend weeks to examine all there is to be seen. Another object of interest is a watch tower, about 100 feet high, some distance from the present walls, said to have been built by Saladin's nephew. It overlooks a valley in which an enemy might have approached the city unobserved but for this tower. The present ruins appear to have been built since the Christian era, but the mounds and scattered stones outside the city indicate a much earlier date. Some geographers suppose this to be the ancient Carthiocrta.

Out of the remarks upon this paper grew a discussion respecting the advisability and value of archaeological, literary, and scientific investigations made by missionaries in their various fields of labor. Part was taken in the discussion by Dr. Anderson, Dr. Pitkin, Rev. Mr. Syle, Mr. Ropes, and Prof. Whitney. The opinion was unanimously expressed that such investigations, undertaken and carried on as opportunity offered, in the intervals of missionary work, were of very high importance in their bearing on the culture and freshness and activity of mind of the missionary himself, on his relation to the people and conditions among which his lot was cast, and on the general public—both in the way of direct enlightenment, and by attracting attention, admiration, and sympathy to the missionary cause and its representatives. Reference was made to the immense amount of valuable contributions to knowledge which had been brought before the world by missionaries, to their abundant labors in connection with this Society, as recorded in its Journal, and to the honorable estimation in which American missionaries were held everywhere by reason of these and other similar labors. It was thought that only the narrowest and least enlightened apprehension of the missionary work, could find ground for aught but praise and satisfaction in the literary and scientific activity of the missionaries.

2. On the Niobe of Mt. Sipylus, by Rev. H. J. Van Lennep, D.D., Missionary in Syria of the A. B. C. F. M.; read by the Corresponding Secretary.

Dr. Van Lennep first rehearses the myth of Niobe, turned to stone upon Mt. Sipylus, as related by Homer and the other classic writers. He then gives a description of the mountain and its surroundings, and goes on to describe a journey which he made near it last autumn, in the course of which he observed and visited the remarkable and ancient work which he regards as Niobe's image. The situation is about five miles east of Magnesia, upon the highroad which skirts the mountain, and at the first *café*. There is a pond at the base of the mountain, and directly above it, about four hundred feet up, is an artificially smoothed wall of rock, in which is sunk a double niche, containing the colossal bust upon a pedestal, cut in very high relief—the whole much defaced, but still plainly recognizable. The rock is a hard white marble, with occasional blue veins, and one of these veins "begins at the region of the eyes, covers the lower part of the face, trickles down the neck and breast, and, falling upon the pedestal, there divides into two broad streams, which flow down to the platform beneath, perfectly representing the pouring of a dark-colored flood of tears."

Mr. Van Lennep quotes the passages of Pausanias, Strabo, etc., referring to the Niobe, and argues that their descriptions are applicable to this monument.

He also encloses a sketch of the monument and its immediate surroundings, taken from a little distance at its left.

3. On the old Egyptian Chronicle, by Dr. Charles Pickering, of Boston.

Dr. Pickering presented some of the main features of this document, with chronological conclusions of his own founded upon it.

Hon. J. D. Baldwin pointed out that the chronicle in question was by the best authorities, such as Lepsius, regarded as spurious, and that he fully concurred in their opinion.

4. On the rendering of the word God in Chinese, by Pres. Woolsey, of Yale College.

This was an essay on the Chinese equivalents for our word God which have been used by Christian missionaries. A historical account was first given of the terms adopted by the Catholics, from Ricci's time until the settlement of the disputes in relation to that matter at Rome near the beginning of the 18th century. Then the views of the Protestant missionaries in China were noticed, the decision of the American Bible Society in favor of *Shin* and against *Shang-ti* in 1850, the continuance of a part of the missionaries to use *Shang-ti* in their versions, and the rise in recent years of an opinion on the part of some very able translators in favor of *Tien-chu*. A comparison was then instituted between these three terms. It was claimed that *Tien-chu*—the term adopted by early catholic teachers and authorized at Rome—had no shade of heathenish or pantheistic thought attached to it, and was well understood through China, as the term in use to denote the supreme object of christian worship. At the same time it was admitted that *Tien-chu* was not properly a translation of the original words used for God in the Bible. The term *Shin* was next examined, and it was shown from printed statements of Messrs. Hartwell and Peet, as well as from the testimony of other missionaries, that it is far too vague to take the place of God in general, although, as most concede, it cannot be wholly dispensed with. Next, *Shang-ti* was discussed at considerable length, in connection with the disputes of the Jesuit and other Catholic preachers, and with the Chinese religious philosophy. The essay of the honest and able Jesuit, Langobardi, who condemned *Shang-ti* and strove to show that the Chinese were atheistic (or, as we should say, pantheistic) in their view of the universe, not only in modern times but from the very origin of Chinese speculation, was cited with approbation. The opinions also of modern writers on philosophy, of Schelling, and especially Wuttke in his *Geschichte des Heidenthums*, were made use of to corroborate the position taken by the author of the essay, that *Shang-ti*, as properly denoting heaven personified, a conception of naturalism and of pantheism, was an unsafe representative of the scriptural idea of God. On the whole then, *Shang-ti* being condemned, and *Shin* as a leading term pronounced too vague and general, *Tien-chu* had the preference given to it.

Extended remarks were made upon this paper and its subject by Dr. Parker and Rev. Mr. Syle, both of whom agreed with the writer in his definitive rejection of *Shang-ti*, but thought more favorably than he of *Shin*, and less favorably of *Tien-chu*.

5. On the views of Prof. Key and M. Oppert respecting Sanskrit and Indo-European Philology, by Prof. W. D. Whitney, of New Haven.

In this paper Prof. Whitney defended the current methods and commonly accepted results of comparative philology against the attacks of Prof. Key (in the *Transactions of the Philological Society of London*, 1862-3) and M. Oppert (in the *Annales de Philosophie Chrétienne* for 1866). He began with pointing out the nature and grounds of the dependence of general linguistic science upon Indo-European philology, and of the latter upon Sanskrit study, the limits to this dependence, and its liability to misapprehension and exaggeration by incautious or ill-informed students. The faults of detail which Mr. Key indicates in the work of particular scholars, as Müller and Bopp, do not affect their general philological method, and if his own basis of scholarship had been so extended as to embrace a good knowledge of Sanskrit, he might have been able to criticize their work from a higher point of view, separating its sound from its unsound portions, and duly estimating both. While many of his objections are well taken, others are insufficiently founded, and cannot be maintained. M. Oppert's assault is one of much more serious intent, but much weaker substance and result. He fully accepts the Boppian method, even going so far as to maintain that Bopp has exhausted the whole field of linguistic science, leaving nothing of consequence for others to do after him: but its conclusions he allows to be grammatical only, refusing them any value as historical or ethnological data; he strongly condemns also the introduction of any elements of the new historical philology into the methods of classical instruction. His conception of the scope, bearings, and condition of the science is as far as possible out of the way. He is not a general skeptic as to ethnological connections, as might be expected from his denial of the accepted sources of information respecting them: on the contrary, he puts forth the most detailed and definite state-

ments about the derivation and composition of the Indo-European races, in general and in particular; but they are mere *dicta*, resting upon no assignable basis, and in no small part explainable as the conversions of doubtful or half-understood hypotheses of linguists, drawn from linguistic data, into absolute facts. A main, if not the main, object of the essay is to deny that there is any race connection, any tie of common descent, between the various nations speaking the branches of Indo-European language: the author does not attempt to disprove the connection, but treats it as a palpably unsound and absurd dogma; but his allusions show that he regards the exceptional propagation of the Latin and Arabic as, by their analogy, sufficiently accounting for the extension of Indo-European language over half a world of heterogeneous tribes. The analogy, however, is a wholly insufficient and inapplicable one, as was attempted to be shown by an inquiry into the causes of the spread of Latin and Arabic, and an indication of their absence in the ancient history of Indo-European speech. M. Oppert's essay is, from its beginning to its end, a tissue of misrepresentations, unwarranted assumptions, and unsound inferences, and cannot but seriously damage his reputation as a linguistic and ethnological scholar.

6. On Chinese Chronology, by Rev. E. Burgess, of South Franklin, Mass.

Mr. Burgess, basing himself mainly upon the discussions of the subject in the introduction to the last volume of Dr. Legge's edition of the Chinese Classics, attempted to show the unauthentic character of the accepted Chinese chronology in its earlier period, previous to the time of Confucius.

After the reading of this paper, the Society adjourned, to meet again in New Haven in October next.

ADDITIONS TO THE LIBRARY AND CABINET.

MAY, 1865—MAY, 1867.

From Prof. G. J. Adler.

Wilhelm von Humboldt's Linguistical Studies. By G. J. Adler New York: 1866. 8vo.

From the American Academy of Arts and Sciences.

Proceedings of the American Academy of Arts and Sciences. Vol. vi, pp. 341-364; Vol. vii, pp. 1-184. Boston: 1864-7. 8vo.

From the American Antiquarian Society.

Proceedings of the American Antiquarian Society, Jan. 17, 1865; Apr. 26, 1865; Oct. 21, 1865; Mar. 16, 1866 and Apr. 25, 1866; Nov. 15, 1866. Boston: 1865-6. 8vo.

From the American Philosophical Society.

Proceedings of the American Philosophical Society. Nos. 72-5; vol. x, pp. 1-254. Philadelphia: 1865-6. 8vo.

Transactions of the American Philosophical Society. Vol. xiii, Part 2. Philadelphia: 1865. 4to.

Catalogue of the American Philosophical Society's Library. Part II, Class v. Historical Sciences. Philadelphia: 1866. roy. 8vo.

From Prof. G. I. Ascoli, of Milan.

Studj Ario-Semitici Articolo Secondo.—Studj Iràni, di Graziadio Isaia Ascoli. [Extracts from the Memoirs of the Royal Institute of Lombardy, Vol. x.] Milan: 1865. 4to.

From the Asiatic Society of Bengal.

Bibliotheca Indica, Nos. 181, 190-92, 196-7, 204-19; and New Series, Nos. 56-100, viz.:

The Taittiriya Sanhitā, etc. Fasc. xx, xxi.

The Taittiriya Brāhmaṇa, etc. Fasc. xiv-xxi.

The Taittiriya 'Aranyaka of the Black Yajur Veda, with the Commentary of Sāyanāchārya, edited by Rajendralala Mitra. Fasc. i-iv.

The Nyāya-Darśana of Gotama, with the Commentary of Vātsyāyana, edited by Pandita Jayanārayana Tarkapānchāna. Fasc. i-iii.

The Brihat-sanhitā of Varāha-Mihira. Fasc. iii-vii.

The 'Srauta-Sūtra of 'A'svalāyana. Fasc. ii-x.

The Kāmandakiya-Nītisāra. Fasc. iii.

The Sāhitya-Darpana, or Mirror of Composition, a Treatise on Literary Criticism; by Vis'vanātha Kavirāja. Translated into English by Bābu Pramādāśa Mitra and the late James R. Ballantyne, LL.D. Fasc. i-iii.

The Sāṅkhya Aphorisms of Kapila, translated. Fasc. ii.

The Da'sa-Rūpa of Dhananjaya. Fasc. iii.

Sāṅkhya-Sāra; a Treatise of Sāṅkhya Philosophy, by Vijnāna Bhikshu. Edited by Fitz-Edward Hall. 1 Fasc.

The Mīmāṃsā-Darśana. Fasc. ii, iii.

Ibn Hajar's Biographical Dictionary, Vol. IV, Fasc. i-vii.

The Muṣṭakhaḥ al-Tawārikh of Abd-al-Qādir bin i Malūk Shāh al-Badāoni. Edited by Capt. W. N. Lees, LL.D., and Mawlawi Kabir al-Din Ahmad, and Munshi Ahmad Ali. 6 Fasc.

The Nārada-Pancharātra. Fasc. iv.

Wis o Rāmīn. Fasc. v.

Iqbāl-nāmah-i Jehāngīrī of Motamad Khan. Edited by Mawlawi Abd al-Hāfi and Ahmad Ali. 3 Fasc.

- The 'Alamgir-Namah. By Muhammad Kazim Ibn-i Muhammad Amin Munshi. Edited by Mawlawis Khadim Hussain and Abd al-Hai, under the superintendence of Major W. N. Lees, LL.D. Fasc. i-vii.
 The Bādshāh Nāmāh, by 'Abd al-Hamid Lahawri. Edited by Mawlawis Kabir al-Din Ahmad and Abd al-Rahim, under the superintendence of Major W. N. Lees, LL.D. Fasc. i, ii.

From the Asiatic Society of Paris.

Journal Asiatique. 6^{me} Série. Tomes iii, iv, and Nos. 27-32. Paris: 1864-7. 8vo.

From Rev. J. G. Auer, of West Philadelphia.

Grebo Grammar. By the Rt. Rev. John Payne, D.D. New York: 1864. 12mo.

Grebo Primer. Under the direction of the same. Second edition. New York. 12mo.

From Hon. J. D. Baldwin, of Worcester.

Catalogue of Additions made to the Library of Congress, from Dec. 1, 1864, to Dec. 1, 1865. Washington: 1865. 8vo.

From Dr. A. Bastian, of Bremen.

Die Völker des Oestlichen Asien. Studien und Reisen von Dr. Adolf Bastian. Erster Band. Geschichte der Indochinesen. Zweiter Band. Reisen in Birma in den Jahren 1861-1862. Leipzig: 1866. 8vo.

From the Batavian Society of Arts and Sciences.

Verhandelingen van het Bataviaasch Genootschap van Kunsten en Wetenschappen. Deel xxix. Batavia: 1862. 4to.

Tijdschrift voor Indische Taal, Land-, en Volkenkunde. Deel xii. Batavia: 1862. 8vo.

From Rev. Cephas Bennett, of Rangoon.

A Dictionary, English and Burmese. By A. Judson. Second edition. Rangoon: 1866. roy. 8vo.

The Youth's Guide to Arithmetic. By L. Stilson. Rangoon: 1866. 8vo.
 Genesis and Exodus in Burmese, with Dr. Judson's last emendations. Rangoon: 1864. 8vo.

The Life of our Lord and Saviour Jesus Christ. 3d Burmese edition. Maulmain: 1857. 8vo.

A few Simple Rules for Land Measuring, by L. Stilson. Rangoon: 1865. 8vo.
 Five Burmese tracts: The Golden Balance.—The Tree of Life.—The Awakener.—The Resurrection.—Glad Tidings. Rangoon: 1864-6. 12mo.

The Catechism. By Mrs. Judson. Rangoon: 1865. 18mo.

The Books of Genesis and Exodus, in Sgau Karen. Translated by Francis Mason. Rangoon: 1864. roy. 8vo.

An (Abridged) Arithmetic, for the use of Karen Schools, by E. B. Cross. 3d edition. Maulmain: 1861. 8vo.

Primary Geography, in Sgau Karen. By Mrs. C. B. Thomas. Rangoon: 1865. 12mo.

The Psalms and Proverbs. Translated by Francis Mason. Rangoon: 1865. 12mo.
 Hymns. [Sgau Karen.] 4th edition. Maulmain: 1860. 18mo.

Revival Hymns. By Rev. B. C. Thomas. 2d edition. Rangoon: 1866. 24mo.

A Catechetical History of the Saviour in Pwo Karen. By Rev. D. L. Brayton. Rangoon: 1865. 24mo.

Pwo Catechism. By H. L. VanMeter. Rangoon: 1865. 24mo.

Acts of the Apostles. Rangoon: 1865. 8vo.

The Child's Book. By Mrs. C. H. Vinton. 3d edition. Rangoon: 1865. 24mo.

Hymns for Public and Social Worship. 8th edition. Rangoon: 1863. 24mo.

Catechism. By Rev. E. L. Abbott. 4th edition. Rangoon: 1865. 12mo.

The Child's Scripture Catechism. Prepared by Mrs. Whitaker. 2d edition. Rangoon: 1865. 12mo.

From the Royal Academy of Sciences at Berlin.

Monatsberichte der Königl. Akademie der Wissenschaften zu Berlin. 1864, 1865, 1866. Berlin: 1865-7. 8vo.

Philologische und Historische Abhandlungen der etc. 1864, 1865. Berlin: 1865-6. 4to.

From Prof. Otto Böhtlingk, of St. Petersburg.

Indische Sprüche. Sanskrit und Deutsch herausgegeben von Otto Böhtlingk. Dritter Theil. St. Petersburg: 1865. 8vo.

From Professors Böhtlingk and Roth.

Sanskrit-Wörterbuch Bearbeitet von Otto Böhtlingk und Rudolph Roth. Lieferungen 28-33. St. Petersburg: 1865-7. 4to.

From the Bombay Branch of the Royal Asiatic Society.

Journal of the Bombay Branch of the Royal Asiatic Society. No. xxii. Bombay: 1865. 8vo.

From the Royal University of Norway, at Christiania.

Nine scientific essays, published as University programmes, etc. Christiania: 1851-1865. 4to.

Quellen zur Geschichte des Taufsymbols und der Glaubensregel, herausgegeben und in Abhandlungen erläutert von Dr. C. P. Caspari. I. Christiania: 1866. 8vo.

From Mr. Hyde Clarke, of Smyrna.

Le Bas-Relief de Nymphi, d'après de nouveaux renseignements. Par MM. Georges Perrot et Edmond Guillaume. [Extrait de la Revue Archéologique.] Paris: 1866. 8vo.

A Help to Memory in learning Turkish. By Hyde Clarke. Constantinople: 1862. 12mo.

From Prof. Edward B. Cowell, of London.

The Kavya Prakasa, or a Treatise on Sanskrit Rhetoric, by Mammata Bhatta, with Explanatory and Illustrative Notes. By Mahesa Chandra Nyayaratna By order of E. B. Cowell Calcutta: 1866. 8vo.

From Rev. Oliver Crane, of Carbondale, Pa.

Episcopal prayer-book, in Arabo-Turkish. Leipzig: 1842. 8vo.

An imperial firman, given by the Sultan Abd-ul-Mejid, of Turkey. One sheet, 22 by 31 inches.

A collection of coins (not yet identified and described).

From Rev. C. H. A. Dall, of Calcutta.

Dictionarium Anamitico-Latinum, primitus inceptum ab P. J. Pigneaux, dein absolutum et editum a J. L. Taberd Serampore: 1838. 4to.

Dictionarium Latino-Anamiticum, auctore J. L. Taberd Serampore: 1838. 4to.

From Mr. Frank R. Forbes, of Shanghai.

Notes for Tourists in the North of China. By N. B. Denoya. Hongkong: 1866. 8vo.

From M. Garcin de Tassy, of Paris.

Cours d'Hindoustani. Discours d'Ouverture du 4 Dec., 1865; du 3 Dec., 1866. Paris: 1865-6. 8vo.

From the German Oriental Society.

Zeitschrift der Deutschen Morgenländischen Gesellschaft. xix, 3, 4; xx. Leipzig: 1865-6. 8vo.

Indische Studien herausgegeben von Albrecht Weber. ix, 1. Leipzig: 1866. 8vo.

Abhandlungen für die Kunde des Morgenlandes, herausgegeben von der Deutschen Morgenländischen Gesellschaft, iv. 1-5, viz.:

Ācāryana's Grhyasūtras, Part ii, translation.

Āntanava's Phitsūtra. Mit verschiedenen Indischen Commentaren, Einleitung, Uebersetzung, und Anmerkungen herausgegeben von Franz Kielhorn.

Ueber die Jüdische Angelologie und Daemonologie in ihrer Abhängigkeit vom Parsismus. Von Dr. Alexander Kohut.

Die Grabschrift des Sidonischen Königs Eschmun-ezer, übersetzt und erklärt von Dr. Ernst Meier.

Kathā Sarit Sāgara. Die Märchensammlung des Somadeva. Buch ix-xviii. Herausgegeben von Hermann Brockhaus.

From Prof. D. C. Gilman, of New Haven.

Seven pamphlets on Java, bound in one volume, viz: A Discourse delivered on the 11th Sept, 1815. By the Honorable Thomas Stamford Raffles—Essay on the Geography, Mineralogy and Botany of the western portion of Java. Addressed to the same, by Dr. Thos. Horsfield.—Short Account of the Medicinal Plants of Java.—An Inscription from the Kawi or Ancient Javanese Language. translated into the modern idiom by Nata Kusuma, rendered into English by Mr. Crawford, and submitted to the Society by the President, Thos. S. Raffles.—Eruption from the Tomboro Mountain in the Island of Sumbawa on the 11th and 12th of April, 1815.—Byna Woordelyk Traslaant van een Javansch Geslacht-Register van de Vorsten van Java.—Uittreksels uit eenige Aanteekeningen oopen den Javaan. Door F. van Boeckholtz. 1775.

From the Ducal Library at Gotha.

Die Orientalischen Handschriften der Herzöglichen Bibliothek zu Gotha. verzeichnet von Dr. Wilhelm Pertsch. Zweiter Theil. Die Türkischen Handschriften. Wien: 1864. 8vo.

From Prof. S. S. Haldeman, of Columbia, Pa.

Affixes in their Origin and Application, exhibiting the Etymologic Structure of English Words. By S. S. Haldeman. Philadelphia: 1865. 12mo.

From Prof. Fitz-Edward Hall, of London.

Office and Dewtie of Kyngis be William Lander. Edited by Fitzedward Hall. [No. 3 of Early English Text Society's Series.] London: 1864. 8vo.

The Monarchie and other Poems of Sir David Lyndesay. Edited by Fitzedward Hall. [Nos. 11 and 19 of the same.] London: 1865-6. 8vo.

Scriptorum Arabum de Rebus Indicis Loci et Opuscula inedita recensuit et illustravit Joannes Gildmeister. Fasc. primus. Bonnae: 1853. 8vo.

Supplement to the Glossary of Indian Terms. A-J. By H. M. Elliott Agra: 1845. 8vo.

The Life of Sheikh Mohammed Ali Hazin, written by himself: edited from two Persian manuscripts By F. C. Belfour. London: 1831. 8vo.

The same, translated. By the same. London: 1830. 8vo.

Ikhwan us-Safa. 1846. 8vo.

Fusul Imadi. 1827. lithographed. 8vo.

Malavika et Agnimitra. Drama Indicum Kalidasae adscriptum. edidit Otto Fridericus Tullberg. Bonnae: 1840. roy. 8vo.

From Prof. C. A. Holmboe, of Christiania, Norway.

Six archaeological essays, in Norwegian, extracts from the Vid-Selsk. Forh. for 1864-5, viz: Om Gull og Rød Jord i Gravhøie.—Om Vægtlodderne i Nummelandsfundet.—Om Eeds-Ringe. II.—Om Hestoffer, —Om Helleristninger. II.—Om en Nordisk og Indisk Vægteenhed.

Ezechiel's Syner og Chaldaernes Astrolab. Af C. A. Holmboe. Christiania: 1866. 4to.

From Mrs. Wooster Hotchkiss, of New Haven.

Lettre sur la Découverte des Hiéroglyphes Acrologiques par M. J. Klaproth. Paris: 1827. 8vo.

Essai sur les Hiéroglyphes d'Horapollon, et quelques Mots sur la Cabale. Par M. le Chevalier de Gouliano. Paris: 1827. 4to.

From Rev. H. H. Jessup, of Beirut.

The Muhit al-Muhit, an Arabic Dictionary, by Butrus Bistany. Vol. I, a—r. roy. 8vo.

From M. Nicolas de Khanikoff, of Paris.

Mémoire sur l'Ethnographie de la Perse, par Nicolas de Khanikoff. [Extract from the Mémoires de la Soc. de Géographie de Paris.] Paris: 1866. 4to.

Notice de M. N. de Khanikof, sur le livre de Marco Polo. [Extract from the Journal Asiatique.] Paris: 1866. 8vo.

From the University of Kiel.

Schriften der Universität zu Kiel. XI. Aus dem Jahre 1864.—XII. Aus dem Jahre 1865. 4to.

From Prof. Adalbert Kuhn, of Berlin.

Zeitschrift für Vergleichende Sprachforschung. xiv. 3-6; xv; xvi. 1-4. Berlin: 1865-7. 8vo.

Beiträge zur Vergleichenden Sprachforschung. iv. 3, 4; v. 1, 2. Berlin: 1865-7. 8vo.

From Prof. Christian Lassen, of Bonn.

Indische Alterthumskunde von Christian Lassen. Zweite verbesserte und sehr vermehrte Auflage. Ersten Bandes Erste Hälfte: Geographie und Ethnographie. Leipzig: 1866. 8vo.

From Rev. John Liggins, of Japan.

One Thousand Familiar Phrases in English and romanized Japanese. By the Rev. John Liggins. Second edition. New York: 1867. 8vo.

The Oriental Picture Gallery.—The Missionary Picture Gallery With explanatory remarks, and missionary information. Edited by the Rev. John Liggins. New York: 1866. 4to.

From M. L. Léon de Rosny, of Paris.

Revue Orientale et Asiatique. Vols. iv, ix, and Nos. 34, 38-41, 44-47. Paris: 1860-64. 8vo.

From the University of Lund, Sweden.

Acta Universitatis Lundensis. Lunds Universitets Ars-Skrift. 1864. Mathematik och Naturvetenskap.—Philosophi, Språkvetenskap och Histori. Lund: 1864-5. 4to.

From the Minister of Public Instruction of France.

Mission de Phénicie, dirigée par M. Ernest Renan. Texte, I; Planches, I-III. Paris. 4to and fol.

From Mr. John Muir, D.C.L., of Edinburgh.

Six essays on Hindu religion, by J. Muir (extracts from the Journal of the Roy. As. Soc'y), viz.: Progress of the Vedic Religion towards Abstract Conceptions of the Deity.—Yama and the Doctrine of a Future Life according to the Rig, Yajur, and Atharva Vedas.—Contributions to a knowledge of the Vedic Theogony and Mythology, No. II.—Miscellaneous Hymns from the Rig and Atharva Vedas.—On the Relations of the Priests to the other Classes of Indian Society in the Vedic Age.—On the Interpretation of the Veda.

From the Royal Bavarian Academy at Munich.

Abhandlungen der Churfürstlich-Bayerischen Akademie der Wissenschaften. Vols. ii-ix. München: 1764-75. 4to.

Neue Philosophische Abhandlungen der Bayerischen Akademie der Wissenschaften. Vols. i-vii. München: 1778-97. 4to.

Neue historische Abhandlungen der Bayerischen Akademie der Wissenschaften. Vols. i-v. München: 1779-98. 4to.

do. do. do. Vol. i. München: 1804. 8vo.

Historische Abhandlungen der Königlich-Bayerischen Akademie der Wissenschaften. Vols. i-v. München: 1807-23. 4to.

Abhandlungen der Historischen Classe der etc. Vols. i-viii, ix 1, 2: x 1, 2. München: 1833-66. 4to.

Abhandlungen der Philosophisch-philologischen Classe der etc. Vols. i-x; xi 1. München: 1835-66. 4to.

Monumenta Secularia. Herausgegeben von der etc. zur Feier ihres Hundertjährigen Bestehens am 25 März 1859. München. 4to.

Die Gottesurtheile der Inder Von Emil Schlagintweit. München: 1866. 4to.

From the Royal Library at Munich.

Catalogus Codicum Manuscriptorum Bibliothecae Regiae Monacensis. I. 2, Codices Arabicos complectens.—I. 3, Codices Persicos complectens. München: 1866. 8vo.

From Mr. John Murdoch, of India.

Classified Catalogue of Tamil Printed Books, with Introductory Notices. Compiled by John Murdoch. Madras: 1865. 12mo.

The Indian Missionary Manual: or, Hints to young Missionaries in India. With lists of books. Compiled by John Murdoch. Madras: 1864. 12mo.

Indian Year-Book for 1861. A Review of Social, Intellectual, and Religious Progress in India and Ceylon. Compiled by John Murdoch. Madras: 1862. 8vo.

The same, for 1862.

From the North China Branch of the Royal Asiatic Society.

Journal of the North-China Branch of the Royal Asiatic Society. New Series II. Shanghai: 1866. 8vo.

From Rev. A. T. Pratt, M.D., of Syria.

Grammaire de la Langue Arménienne par J.-Ch. Cirbied. Paris: 1823. 8vo.

A grammar of the Ottoman Turkish language, in Turkish, by Fuad Pasha. Constantinople. 8vo.

Catalogue and description of extant Turkish coins, in Turkish. Constantinople: A. H. 1280 (A. D. 1863). fol.

A manuscript of the New Testament, in Ancient Armenian; on parchment, 311 leaves, about $4\frac{1}{2}$ by $3\frac{1}{2}$ inches.

From Babu Rājendralāla Mitra, of Calcutta.

Vividhārtha-Sangraha. A Bengali monthly periodical. Vols. iv-vii. Calcutta: 1856-9. 4to.

Rahasya-Sandarbha. A Bengali monthly periodical. Vol. I. Calcutta: 1862. 4to.

Prākṛta-Bhūgola, etc. A physical geography, in Bengali; by Rājendralāla Mitra. Calcutta: 1861. 12mo.

Vyākaraṇa-praveśa, etc. An Introduction to Bengali grammar, in Bengali, by the same. Calcutta: 1862. 12mo.

Patra-Kaumudi; or, Book of Letters [in Bengali] Compiled by the Hon'ble W. S. Seton-Karr and the same. Calcutta: 1863. 12mo.

Īlipika-darśana, etc. A life of Īvaṇi, in Bengali. Second edition. Calcutta: 1862. 12mo.

From the Royal Asiatic Society of Great Britain and Ireland.

Journal of the Royal Asiatic Society of Great Britain and Ireland. New Series, I. 2; II. 1, 2. London: 1865-7. 8vo.

From the Royal Saxon Society of Sciences.

Berichte über die Verhandlungen der Königlich Sächsischen Gesellschaft der Wissenschaften zu Leipzig. Philologisch-historische Classe. xvi. 2, 3; xvii; xviii. 1-3. Leipzig: 1864-6. 8vo.

Abhandlungen der Philologisch-historischen Classe der etc. iv. 5-6; v. 1, 2. Leipzig: 1865-6. roy. 8vo.

From the Sanskrit Text Society, of London.

The Jaiminiya-Nyāya-Māhā-Vistara of Mādhavāchārya. Edited for the Sanskrit Text Society by Theodor Goldstücker. Parts i, ii. London: 1865. 4to.

From Her Majesty's Secretary of State for India.

The Aitareya Brahmanam of the Rig-Veda Edited, translated, and explained by Martin Haug Bombay: 1863. 2 vols. 12mo.

From the Imperial Academy of Sciences of St. Petersburg.

Bulletin de l'Académie Impériale des Sciences de St. Pétersbourg. iv. 1; vii. 3-6; viii, ix. St. Petersburg: 1864-6. 4to.

Mémoires de l'Ac. Imp. etc. v. 1; vi. 10; vii-ix; x. 1, 2. St. Petersburg: 1862-6. 4to.

Beiträge zur Kenntniss der Iranischen Sprachen. II. Theil, 1 u. 3 Lief. Masanderanische Sprache herausgegeben von B. Dorn. St. Petersburg: 1866. 8vo.

From Rev. M. A. Sherring, of Benares.

The Transactions of the Benares Institute, for the Session 1864-5. Benares: 1865. 8vo.

Four archaeological essays, by Rev. M. A. Sherring, viz.: Benares and its antiquities.—Description of the Buddhist Ruins at Bakariya Cund, Benares.—Some Account of Ancient Remains at Saidpur and Bhitari.—Benares, Past and Present. Vidyāsāra [‘Essence of knowledge’]. Mirzapore Educational Books. Hindi Series. No. I. 3d edition. Mirzapore: 1862. 8vo.

An illustrated work on natural history. do. Urdu Series. No. VI. Mirzapore 1864. 8vo.

From the Smithsonian Institution.

Smithsonian Miscellaneous Collections, vi, vii. Washington: 1867. 8vo.

Smithsonian Contributions to Knowledge, xiv. Washington: 1865. 4to.

From Rev. J. P. Thompson, D.D. of New York.

Grammar of the Hawaiian Language. By L. Andrews. Honolulu: 1851. 8vo.

A Dictionary of the Hawaiian Language, to which is appended an English-Hawaiian Vocabulary By Lorrie Andrews. Honolulu: 1865. 8vo.

A short Synopsis of the most essential points in the Hawaiian Grammar By W. D. Alexander. Honolulu: 1864. 12mo.

From Prof. C. J. Tornberg, of Lund.

Ibn-el-Athiri Chronicon Edidit Carolus Johannes Tornberg. Volumen Septimum.—Volumen primum. Lugduni: 1865-7. 8vo.

From the Tübingen University Library.

Systematisch-alphabetischer Hauptkatalog der Königlichen Universitätsbibliothek zu Tübingen. F. Geschichte und ihre Hilfswissenschaften. pp. 1-120.—M. Handschriften. a. Orientalische. I. Indische Handschriften. Tübingen: 1865. 4to.

From the U. S. Sanitary Commission.

Documents of the United States Sanitary Commission. Nos. 1-95, May, 1861—Dec. 1865, bound in two volumes. New York. 8vo.

United States Sanitary Commission Bulletin. Nos. 1-40, Nov. 1862—Aug. 1865. New York. 8vo.

From the Imperial Royal Geographical Society of Vienna.

Mittheilungen der Kaiserlich-königlichen Geographischen Gesellschaft. vii; viii 1, 2; ix. Vienna; 1863-5. roy. 8vo.

From M. F. Wallmass, of Cairo.

Paleologia Copta di Felice Wallmass del Cairo di Egitto. Pisa: 1865. 8vo.

From Prof. Albrecht Weber, of Berlin.

Indexes, Latin and German, of lectures delivered at the University of Berlin, during the years 1859-66. 4to.

Ueber ein Fragment der Bhagavati. Ein Beitrag zur Kenntniss der heiligen Sprache und Literatur der Jaina. Von A. Weber. [Aus den Abh. d. Kön. Ak. d. Wiss. zu Berlin.] Erster Theil. Berlin: 1866. 4to.

From Dr. M. C. White, of New Haven.

Essai sur l'Origine et la Formation Similaire des Ecritures Figuratives Chinoise et Egyptienne par G. Pauthier. Paris: 1842. 8vo.

From Prof. W. D. Whitney, of New Haven.

Phrasis: a treatise on the history and structure of the different languages of the world By J. Wilson. Albany: 1864. 8vo.

From Mr. C. W. Zaremba, of St. Joseph, Mich.

- A Calendar for 1836, in the Church Slavic, elegantly illuminated; one sheet, 8 $\frac{1}{2}$ by 22 inches, folded.
 Manuscript copy of a papyrus, inscribed with hieratic characters, in the Imperial library at St. Petersburg; one sheet, 10 by 30 inches.—Also, a description and translation of the same, by Dr. C. W. Zaremba.
 A Russo-Tartaric Primer. Kasan: 1839. 8vo.
 The gospels of Matthew and John, in Chinese. 8vo size.
 Die Atlantis nach Griechischen und Arabischen Quellen von A. S. von Noroff St. Petersburg: 1854. 8vo.
 Johann Christian Friedrich Meister's Anleitung zu Verständiger Ansicht jeder Hieroglyphen jeder Symbolischen Wortsprache. Breslau. 12mo.
 Bemerkungen über die Phönizischen und Punischen Münzen. Erstes Stück von Johann Joachim Bellermann. Berlin: 1812. 12mo. (The last two stitched together in one volume.)

From an unknown donor.

- A Hebrew Grammar. no title, place, or date. 8vo.

By exchange.

- Seven Tamil works, printed on native presses, for native use, viz.: Pansa Perakaramam. On Saiva philosophy.—Agastya's Science of Divination by Birds.—Nannul, a grammar by Pavananti, text and commentary; edited by Vesaka Perumal.—A work in praise of Krishna.—A comedy entitled Aressentera.—Tiruvāla ur Puranam: a local Purana.—Nana Vettiyan, by Tiruvalluvar.

Proceedings at New Haven, October 16th and 17th, 1867.

The Society was convened by notification, on the day appointed at the last meeting, and in the same place as last year—namely, the Library-room of the Sheffield Scientific School of Yale College. The President took the chair and called the meeting to order at 3 o'clock.

The minutes of the last meeting having been read by the Recording Secretary and accepted, the Committee of Arrangements gave notice that the Treasurer of the Society, Prof. D. C. Gilman, invited the members to come together at his house in the evening, for a social gathering, at which, however, it was arranged that a single paper, that of Rev. Dr. Thompson, should be read. The invitation was accepted, with thanks, and the meeting so ordered.

The Directors announced that the Annual meeting for 1868 would be holden in Boston, on Wednesday, May 20th, and that Mr. Joseph S. Ropes, of Boston, with the Recording and Corresponding Secretaries, had been designated as Committee of Arrangements for it.

The following gentlemen, proposed and recommended by the Directors, were chosen Corporate Members of the Society :

- Prof. Edward B. Coe, of New Haven.
- " D. Stuart Dodge, of New York.
- " E. P. Evans, of Ann Arbor, Mich.
- Mr. Michael Heilprinn, of New York.
- Prof. Ammi B. Hyde, of Meadville, Pa.

The Corresponding Secretary presented the correspondence of the past six months, extracts from which are given below.

Among the numerous letters of excuse from members unable to be present was one from Rev. J. G. Auer, dated from the Mission House of the Protestant Episcopal Church, at West Philadelphia, saying that his time of service in this country was now ended, and he was just leaving for his mission-field in West Africa, where he hoped to arrive about Christmas. He sent with the letter copies of the Grebo prayer-book and the Grebo-English dictionary of Bishop Payne, just published.

Another, of similar tenor, from Rev. G. W. Wood, of New York, was accompanied by an Armenian prayer-book, of which Mr. Wood writes—

"The book is in the Modern Armenian language, and is the revised prayer-book issued by that party in the Armenian church which desires a reform in that church. It is put forth by those who reject the Protestant name; yet, by its omissions and positive teachings, it is a decided approach toward the Protestant faith."

Dr. S. Wells Williams, under date of Pekin, March 12th, 1867, says—

"You will be interested to learn that the Nestorian monument at Si-ngan-fu in Shensi has been recently visited by two foreigners, English missionaries, who found it in a good state of preservation, on the whole; the building in which it formerly stood, or in whose wall it was embedded, was in utter ruin, and the tablet remained upright, exposed to the weather. Mr. Lees and Mr. Williamson were quickly directed to the place, for the people knew the character of the inscription, and had no trouble in getting impressions of the engraving. It is a great and thick slab of black marble, and shows signs of the effects of the weather.

"The region around Si-ngan is now almost destitute of population, its inhabitants having fled to escape the horrible cruelties and exactions of the insurgents and Mohammedans during the last three years, who are still ravaging the country south of the mountains toward Hankau. Another Bible agent, Mr. Wylie, has just reached Peking from a journey across from Hankau through Kaifung, and narrowly escaped the hands of these marauding bands.

"I have just received the Society's Proceedings for 1865, which are very interesting. The notice of Mr. C. W. Bradley contains a just tribute to a very energetic and liberal promoter of Oriental studies. It was, however, Mr. Reed, our minister, who induced him to come up to the Pei-ho; I do not remember that Mr. Bradley had much intercourse at that time with Lord Elgin. Mr. Reed, too, sent him with the Treaty to Washington in July 1858, and he returned soon to China. The expedition was not in the winter, at which time ice covers the stream. Mr. Reed was also the means of getting him placed on the Commission of Claims, which were all settled in six weeks; it was the refusal of the government at Washington to pay what all regarded as his just salary for this work as Commissioner that led him to resign.

"My spare time is all employed in the revision of my dictionary, or I would try to send something for the Society."

Dr. J. Muir, of Edinburgh, writes under date of July 10th, 1867—

"I sent you some time ago Prof. Goldstücker's summary in the Examiner of his reply read in the winter to my paper on the interpretation of the Veda. Lately I wrote to Dr. Rost to find out if the article in *extenso* was yet in type, as I was naturally desirous to read the author's propositions in detail. But I was informed that Prof. Goldstücker was reserving the paper till he should be able to complete it by the addition of his proofs. When, then, if ever, the article is to see the light, must be left for the future to clear up; but I really wish he would let us have it, and show how he is going to demolish all his adversaries.

"Prof. Aufrecht is working steadily at his vocabulary—or concordance, as he calls it—of the Rig-Veda, having already sent his vocabulary of the Atharva-Veda to the press. Max Müller, as you will have become aware, is about to bring out a new translation of the Rig-Veda. He has been in rather weak health, but, I am glad to learn, is better now.

"I have been working all winter at a new edition of the first volume of my Sanskrit Texts, on Caste: it is partly printed, but will not be ready for at least another six months. It is very much enlarged."

Dr. W. F. A. Behnauer, of Dresden, writes from Leipzig, June 12th, 1867—

"I send you my programme of the Oriental Photolithographic Album, destined to be printed in Leipzig, Paris, and Beyroot; with a proof. Have the kindness to print it in your Journal."

The Corresponding Secretary read the chief parts of the detailed (manuscript) prospectus, as follows:

"This great collection will contain in the first part fourteen Arabic works, in the second part six Persian works, in the third part four Turkish works, and in the fourth part the Assyrian cuneiform inscriptions of the Royal Museum of Antiquities of Dresden; namely,

Section I. No. 1. Al-Ghazrālī's ethical treatise entitled *Bedāyat ul-Hidāya*, 'The Beginning of the Right Way,' with an account of the philosophical systems of the Arab schools of the Middle Ages.—2. Plato's metaphysical treatise, known as the *Kitāb ar-Rawāfi*, 'Book of the Four Elements,' translated by Ahmed Ben al-Huṣain Ben Jihār Bokhtār; and Ahmed Ben 'Alī Esnabādī's treatise on the science of the divinity (*ʿilm ilāhī*) and the sciences relating to the substance of the matter of the world (*al-ʿulūm al-hakīkiyya*).—3. A zoological treatise extracted from the *Nasha* of the Sheikh Ustād Daud al-Baqir, collated with an extract from the *Kharidat al-Ajāib* of Ibn al-Wardī: with an introduction to the study of the Arab zoologists and botanists, given in the *Ajāib al-Makhlikāt* of Kazwini.—4. A specimen from the Arabic work of Abū 'Alī Yahya Ben 'Isa Ben Jazla, known as the *Minhāj ul-Beyān*, 'Methodical Exposition' of all that man wants for his life: with a special account of the author and his position among the Arab physicians.—5. The denominations of the medicaments (*al-adwiya al-mufrida*), ascribed to Ibn Sina (Avicenna), in the Arabic, Greek, Persian, and Turkish languages.—6. Two physiological extracts, one Arabic and one Turkish.—7. The little-known medical treatise, *al-Kāfiya al-Hariniya*, by Meslī Ben Hakem; and an important physiological essay, of unknown authorship.—8. The well-known work entitled *Tadhkirat ul-Kahhādīm*, 'Memorial of the Oculists,' by 'Alī Ben 'Isa, with additions and various readings; also, an extract from the celebrated pharmacopeia entitled *Minhāj ud-Dukkān*, of the Jewish apothecary Kuhen al-Attar.—9. An important extract, of twenty-six pages, from the noted work called *Beinissā*, a treatise on the diseases which can be treated in an hour, by the famous Abū Bakr Shamsaddin Ben Zakariya ar-Razi.—10. An extract of twenty pages from the *Kitāb ul-Idhāh fī 'Im in-Nikāh*, 'Exposition of the Science of Copulation,' of Abūlfaraj 'Abdarrahman Ben Nasr ash-Shirazi; with a biography of the author, and a short notice of the oneiromancy of the eastern peoples.

Section II. No. 1. A musical treatise of the poet Jāmi, with the latter's biography, being an account of the relation of the Persian musical system to the Arab, the names of instruments from the dictionary *Haft Kulzum*, etc.—2. The grand mystical work, *Rebab-Nāme*, 'Book of the Violin,' by Sultān Walad, son of the great poet Jelāleddin Rūmī, with biographical account and notes.—3. A Persian work on astronomy by the astronomer 'Alaeddin 'Alī Kushji (son of the first Turkish mathematician, Kādi Zade), named *Merkes-t-alem*, 'Middle of the World,' with commentary.—4. Molla 'Abdul-'Alī's astronomical treatise on the division of time; with biography of the author.—5. An arithmetical treatise by the epitomiser of the Persian work *Hall-i-takwīm*. 6. The remainder of Wasir Rashiddeddin's great work *Jāmi at-Tawārīkh*, of which the first volume was published by Quatremère, together with the forty pages on the Chinese kings, with their portraits.

Section III. The four Turkish works composing this section are of a historical and scientific character, with appendixes, translations, and biographies. Their special description, as well as that of the Nineveh slabs whose photolithographic representation constitutes the IVth Section, is omitted here.

From Rev. D. D. Green, Missionary of the Presbyterian Board at Hang-chau, China, comes a finely executed impression of a Chinese monument, with accompanying letter (dated May 7th, 1867), and translations:

"Enclosed please find a rubbing from a tablet in one of the monasteries near this city. It is a representation of the Goddess of Mercy, with her hundred hands, ready to do good to all. The inscription above the image is a Buddhist chant, and contains so many foreign words that but few Chinese scholars can read it. Of the inscriptions under the image I send you a version. It is very unsatisfactory, but the best I can do with my present knowledge of the Chinese, in connection with the manifest ignorance of Chinese teachers as to the doctrines of the Buddhists. I send you this as an acknowledgment of the receipt of a copy of the Proceedings of the American Oriental Society for 1865, read about Jan. 1st, 1867."

The commemorative part of the inscription reads as follows:

"In the reign of the emperor Gyin-long, in the fiftieth cycle, during the spring, in [the city of] Vu-ling [i.e. Hang-chau], one having a good and believing heart sculptured this image of the Goddess of Mercy, and the sacred chant over it, and erected the tablet in the Dzin-z monastery, which is situated in the plain south [of the lake to the west of Hang-chau], in the hall of the god of longevity, by the favor of the Goddess of Mercy, the god presiding over the great present, and Buddha, whose ages cannot be numbered—to whom belong blessedness of community, in hope of the original unity without the least diversity. For the purpose of celebrating the praises of the pure perfection, these three chants were most carefully prepared. On examination, it is found that these three chants were anciently handed down from their author Wang, of the district city of Kyi-ling. His honorary title was Dzao-an, and his name was Zwiin-yiao."

Mr. Green adds a note or two:

"The monastery was first built during the Tsin dynasty, a few years before the beginning of the Song. The buildings have been repeatedly burned down, and again built up, sometimes by imperial patronage, but more often from funds collected by the priests. The place is now in ruins, like most of the temples in this vicinity, destroyed by the Tai-ping rebels. The tablet, however, is still standing.

"The date given in the inscription as that of the erection of the tablet is about A.D. 1795. The author of the verses lived about eight centuries earlier: the exact date could be ascertained, if access were had to the *kyien-tu* of his native place. The chants show that during the Song dynasty (A.D. 960-1280) scholars of no mean pretension were Buddhists."

The following communications were presented at the different sessions of the Meeting:

1. On the Routes and the Chief Articles of Commerce from the East to Europe during the Middle Ages, by Pres't T. D. Woolsey, of New Haven.

President Woolsey spoke of the route which led from India, by the Persian Gulf and the Euphrates, to Babylon, and so to the Mediterranean, and by the Red Sea to Egypt, and especially to Alexandria. These were ancient routes, and the trade passing through them was principally in the hands of Constantinople, although Venice at an early day shared in it. Venice dealt even in Christian slaves with the Mohammedans. The Popes long tried in vain to prevent commercial intercourse with these enemies of the faith. From Constantinople the route of trade lay especially up the Danube, by Vienna and Ratisbon, and thus penetrated into the regions of northern Europe.

During the crusades, so long as the avenue by the Persian gulf and the Red Sea were controlled by hostile Mohammedan powers, it became necessary to adopt another more expensive and circuitous route, requiring much land-carriage and several transfers of freight. This route led up the Indus, across the mountains on beasts of burden, thence by the Oxus, and so to the Caspian Sea. This, which was an ancient route, was now adopted by Venice and Genoa. From the Caspian it took especially the direction of the Volga, to a place called Zarizyn, thence across the country to the Don, where, at the river's mouth, in the town of Tana, now Azov, both Venice and Genoa had commercial privileges, and the former had a consul from the end of the 12th century. Afterwards an important entrepôt for Genoa was Theodosia, now Kaffa, in the Crimea.

When, in 1258, the Mongols under Hulagu Khan overthrew the Caliphate of Bagdad, Egypt being still hostile, it became possible to take the path by the Persian gulf and the Tigris to Bagdad, and so through the Mongol dominions to the west. Two subordinate routes—one across the country to Tauris (Tabris) and the Black Sea, the other *via* Tabris to the north-eastern corner of the Levant—sent the productions of the Orient into Europe. The important marts of the Italians on the Black Sea and the coast of Cilicia were noticed. The trade also of the Christian kingdom of Jerusalem was illustrated by reference to a chapter of the "assises

of the Burgesses' court of the kingdom of Jerusalem," in which the tariff on eastern products is carried out into a multitude of particulars.

After the crusades were over, the Popes having now softened down their prohibitions of commercial intercourse with Mussulmans, the Venetians made arrangements with the rulers of Egypt, by which they were enabled to engross the trade with the east along its most convenient path through the Red Sea, and this continued until towards the end of the Middle Ages, when the Portuguese found out a cheaper and better way of communication.

The principal products of the east imported into Europe were then spoken of, especially silk, until its manufacture was introduced into the Byzantine empire under Justinian, and from thence into Sicily and Italy. Of sugar also, and of the sugar refineries on the Tigris, whence the knowledge spread, not only westward with the cultivation of the cane, but eastward to India and China, an account was given, which was based on Ritter's valuable illustration of that subject in his great geographical work.

2. Translation of the Siamese Work entitled *Bre-Temiya-Jatak*, a life of Buddha in one of his previous existences, by Dr. A. Bastian, of Bremen; presented by the Corresponding Secretary.

The Buddhists, Dr. Bastian says, distinguish five hundred and fifty lesser Jatakas, and ten principal ones, treating of the life of Buddha in his various existences anterior to the historical one. The whole, collected together, form the *Nibbat*, thirty books of which have been translated out of Pali into Siamese by Bana Dammapiyat. The Temi Jataka is the first of the ten principal ones; the last, which relates the saint's life next preceding his being re-born as Gautama Çakyamuni, in Kapilavastu, being entitled the Vésantara, or the Maha-Jat, 'great Jataka.'

This, like so many other Indian biographies, begins with telling of a king (sovereign of *Vārānasi*, 'Benares'), who lives long childless, until the merits and prayers of one of his numerous wives move Indra to come to the relief of the royal pair. The god's regard falls upon Bre-Borom-Bodhisatr, who, since his previous existence as a king of Benares, had spent 10,000 years in hell in expiation of his misdeeds committed in that capacity, and then had lived long in heaven in reward of his good deeds, and now, his debt and credit being both cancelled, was just ready to be born once more. Indra proposes that he choose for his next life the condition of son to the present king and queen of Benares, and promises that it shall tend to the further perfection of his merits. He assents; and five hundred other inhabitants of heaven, whose time is nearly up, are also despatched below to be born as his contemporaries and playmates. Sixteen wet-nurses are provided for him by the delighted king; the good points which led to their selection are fully detailed. The Brahmans prophesy all manner of good-fortune for him, and give him the name Temiya.

When a month old, he chances to be sitting in his father's lap when the latter pronounces sentence of torture and death on four malefactors. This offense against mercy, which the king will have to expiate hereafter by the torments of hell, startles and alarms him. He reflects on his own past history, and perceives that for such acts during his previous reign he had suffered almost endlessly in hell-fire, and that, if he allows himself to grow up a prince and become again a king, the same or a worse fate awaits him anew. He resolves, therefore, for the purpose of evading the royal dignity, to feign himself lame, deaf and dumb, and stupid; and he rigidly carries out his vows, emaciating his body by abstinence from his natural food. Now commences a series of severe tests, in which his unfortunate five hundred comrades have to share, intended to try whether he cannot be made to act like them, and to exhibit the desires and capacities suited to his age. But the prince, reflecting on the torments of hell, so much greater, bears all the tests unflinchingly, and shows an utter impassiveness. Deprivation of food, temptation by cakes, sweetmeats, fruits, playthings, and other sensual pleasures, alarms of fire, of wild elephants, of arms, of terrible noises, of darkness, distress by flies, by stench, by heat—all are fruitless. When he has thus reached the age of sixteen, his father again consults the Brahmans, who confess that their former prognostications were lies; and now advise that he be

sent away and buried in the cemetery of spectres. But the queen interferes, and, in fulfillment of an old promise made her at the time of the child's birth, extorts a cessation of the royal authority to him for the space of seven days, and, during their continuance, lavishes upon her son her entreaties that he will have pity on her, give up the part she is sure he is acting, and show the powers he possesses. This also failing, he is carried out, in accordance with the directions of the Brahmins, to be killed and hidden away. But while the king's charioteer, charged with putting him to death, is digging his grave, he tries and finds himself possessed of superhuman powers, receives consecrated garments from Indra, and preaches the law to his intending murderer till the latter is fully converted, and desires to join him in a hermit's life in the forest. He refuses the proposal, and sends the charioteer back to the palace with the apparel he had worn and the tidings of his condition. The king and queen, the court and army, come out to see him in his hermitage, are also converted by his preaching, and, forsaking the capital, take up a religious life. The same fate befalls five other kings with their armies, as they come in succession with the intent of warring upon Benares. "There was room enough for all these recluses, and for more to come. The elephants were turned loose in the jungle; the horses returned to their wild condition; the royal chariots decayed and fell in pieces, mouldering in the forest. Gold, silver, precious gems, and jewels were strewn about and covered the ground like sand. And all these Bre-Dabos and Bre-Dabosi, on the extinction of life, ascended to the upper terraces of the Brahma-world, abiding there together. Those beings which were brute animals, if they had shown themselves of a kind and benevolent disposition toward the hermits, were re-born, on their death, in one of the six heavens, where they enjoyed celestial riches, and all became sons and daughters of divinities, in god-like existence."

3. On the Egyptian Doctrine of the Future Life, by Rev. Joseph P. Thompson, D.D., of New York.

Of this long and elaborate paper, the following are the leading points:

The legend of Isis and Osiris, which was but a spiritualizing of the yearly phenomena of nature in the Nile valley, lay at the foundation of the Egyptian doctrine of the future life. The departed soul is called the son of Osiris, sometimes Osiris himself, and repeats in his own course through Hades the various experiences of that divinity. He is furnished also with statuettes which represent the mummified form of Osiris bursting into wrappings and coming forth to renewed activity. The sources of Egyptian eschatology are limited: Herodotus, Plutarch, Diodorus Siculus, Empedocles, and others, have given a fragmentary account of the Egyptian belief; but our principal source is the "Book of the Dead."

This Book, which Champollion had already designated the "Funereal Ritual," was published entire by Lepsius in 1842, from the text of a hieroglyphic papyrus at Turin, which dates from the twenty-sixth dynasty, or the seventh century before Christ. The most important chapters of the book are found in papyri of a much older date, and also upon tombs of the eighteenth dynasty and sarcophagi of the eleventh. Indeed, fragments of it can be traced back to the age of the third pyramid.

Fragmentary, repetitious, without logical order, it revolves about two central points—the judgment of the deceased after death, and his passage onward through various transformations, unto the highest felicity in the presence and likeness of "the Chief God."

Dr. Samuel Birch, of the British Museum, has published in volume fifth of Bunsen's "Egypt's Place in Universal History" the first translation of the entire book. This translation is so extremely literal as sometimes to be unintelligible, while the prevailing mysticism of the book throws a degree of obscurity over its doctrines. Translations of the most important chapters have been made by Vicomte de Rougé, Pleyte, Chabas, Reinisch, Brugsch, and others. Rougé is now issuing a superb edition of the text, illustrated with vignettes, which sometimes furnish a most effective commentary; and Lepsius has just published the fragments of the Book of the Dead written upon the inner sides of the sarcophagi of the Old Empire in the Berlin Museum, under the title *Aelteste Texte des Totenbuchs*.

The Book teaches that the souls of all men, good and bad alike, continue to exist after death; that they all pass immediately into Hades, a doleful region, full of enmities and terrors, from whose ordeal the righteous cannot escape; here the wicked may be arrested and delivered to some devouring monster, or remanded to earth, for the discipline of animal transmigration, such being the Egyptian idea of metempsychosis. The righteous pass through a form of justification, and then, emerging at the gates of the West, follow the sun-bark in its bright career; they pass through various transformations, each advancing to a higher plane of existence, by the elimination of the mortal and the evil; then follows a solemn judgment-scene, in the Hall of Two Truths, where the heart of the deceased is weighed in the balance against the image of righteousness, and he is compelled to clear himself of each of the forty-two deadly sins, against as many accusers, who dispute his passage. Being acquitted, he enters the Elysian fields, and partakes of the food of the gods; after which he rises by a succession of grand halls and stair-ways to the Empyrean, the luminous presence-chamber of Osiris.

The consummation of blessedness, however, is not absorption into the divinity, for the soul retains throughout its consciousness and personal identity: and moreover, the soul visits the body, which has been so carefully preserved, and this is revived. The book clearly recognizes moral distinctions as the basis of divine judgment in the Hereafter, and the personal accountability of man to a supreme tribunal beyond the grave. There is not only a purgatory for the wicked, but a hell for the finally incorrigible.

Such, in general, is the theology of this remarkable book. The researches of scholars will eventually bring out its minuter shades of meaning, and perhaps reduce its doctrines to a well-ordered system.

4. A Plan for a Universal History, by Prof. Joseph W. Jenks, of Boston; presented by the Corresponding Secretary.

Prof. Jenks states that he has been long engaged upon a work which he proposes to call "History re-read, or an attempt at a simple and instructive philosophy of history," of which he presents the fundamental outline. He claims that man is of necessity the universal type; that humanity in the complex resembles, in nature, progress, and destiny, humanity in the individual; and that, accordingly, the periods of human history correspond with the successive stages in the life of the individual. He hopes to be able to present, in a year or two, a true historic view of the "childhood" of the race, extending from the end of the period of mythology and fable to the time of Abraham, or about 2000 B. C.

5. Critical Notice of Dr. Friedrich Böttcher's Hebrew Grammar, by Prof. George E. Day, D.D., of New Haven.

This grammar was issued last year from the press of J. A. Barth, in Leipzig. It is as yet unfinished, there being a second volume still to appear, which will be furnished with complete indexes to the whole work. The present volume is of six hundred and fifty-four royal octavo pages. Prof. Day recognized and commended the fidelity and care exhibited by the editor, Dr. Ferdinand Mühlman, a pupil of the deceased author, and characterized the work itself as deserving the attention of Hebrew scholars on account of its scientific treatment of Hebrew grammar, and the large number of methodized facts brought together in it. Dr. Böttcher has aimed to produce an exhaustive work, in which all the phenomena of the language should be subjected to the modern rational treatment. His divisions and subdivisions, although sometimes excessive and tedious, exhibit great thoroughness, and an evident mastery of the subject. After speaking favorably of the historical introduction, Prof. Day criticised the plan of the grammar. This volume is divided into two books, the former of which treats of the phonology, the other of the etymology of the language. The syntax is to follow in the second volume. In developing the sound-relations of the Hebrew, the author makes a constant distinction between what he calls "sonitals" and "spiritals," the latter class embracing the semivowels, as *Vav* and *Fodh*, and the gutturals, the former the vowels and most of the consonants. On the ground of this distinction, he

treats all the inflected words, whether nouns, verbs, or even particles, as either sonantal, guttural, or semi-vocal. The treatment of the verb is quite general, while that of the substantive, which occupies two hundred and fifty pages, is unnecessarily long, in consequence of being burdened with an excessive citation of particulars. The paper dwelt upon a number of special points, in which the views of the author were either accepted or criticised, and closed with an appreciative estimate of the work, as in reality a thesaurus of materials for Hebrew grammar, and a valuable contribution to Semitic philology and to comparative philology in general.*

6. On the Translation of the Veda, by Prof. W. D. Whitney, of New Haven.

One of the leading philological problems of the present day, Prof. Whitney remarked, is to make a translation of the Veda, the Hindu Bible, both on account of its importance as exhibiting the ground-work of Hindu history, and because it is the most ancient existing Indo-European record, and the one that shows us the most primitive attainable phase of Indo-European life and institutions. By the Veda, we mean especially the Rig-Veda, the earliest and most extensive of the four hymn-collections which constitute the kernel of the sacred literature of India—together with such parts of the other collections as are akin with this in character. It has been handed down to us accompanied with a great body of accessory and explanatory works, of which the latest and fullest is the elaborate commentary of Śāyana, made in southern India, in the fourteenth century; in which is summed up the whole learning of the Hindu *pandits*, as gathered and transmitted by a long succession of generations. By the aid of this, especially, were made the first researches of European scholars into the Vedic language and antiquities. A question, now, has arisen as to the absolute value and authority of the commentary and its more ancient sources; the one side maintaining that it represents an immemorial tradition, and is to be, in the main, implicitly followed by us; the other, that it is the final product of a long-continued course of learned inquiry, and must be freely and searchingly criticized in every item, before acceptance. A number of important articles bearing on the controversy have been published within no long time, and of these Prof. Whitney's paper was mainly an abstract and review.

The first article is by Prof. Roth, of Tübingen, and is published in Vol. xxi. (for 1861) of the German Oriental Society's Journal. It sets forth the general principles bearing upon the point under discussion, the conditions under which a so-called "traditional" interpretation grows up, and the impossibility that it should ever have the authority claimed for it; and points out that the historical circumstances which should make the case otherwise in India are wholly wanting, and that an examination of the interpretation itself shows it to be of the ordinary character—namely, founded only on a grammatical and etymological basis.

Into such an examination of Śāyana's commentary and its chief predecessor, Yāska's Nirukta, the next article reviewed enters in detail. It is by Dr. Muir of Edinburgh, and published in Vol. ii., Part 2 (1861), of the Journal of the Royal Asiatic Society. With unimpeachable fairness, with great industry and learning, with clear statement and logical method, it goes over the whole ground, with great fulness of illustration; reaching the conclusion that "there is no unusual or difficult word or obscure text in the hymns in regard to which the authority of the Indian scholiast should be received as final, [for his interpretation accepted] unless it be supported by probability, by the context, or by parallel passages;" and that hence, "no translation of the Rig-Veda which is based exclusively on Śāyana's commentary can possibly be satisfactory."

* At the moment that this abstract of Prof. Day's notice is passing through the press, the first half of the second volume has come to hand. Its first ninety-five pages are occupied with the pronouns and pronominal suffixes, the remaining two hundred and twenty-four pages with the verb. The conclusion of the work is expected to be ready early in 1868.

Of the principles of Vedic interpretation thus established in the abstract by Prof. Roth, and in the concrete by Dr. Muir, a striking exemplification is furnished by Prof. Max Müller, in his article on the "Hymns of the Gaupāyana and the Legend of King Asamāti" (published in the same volume with the one last spoken of). He selects a set of four hymns from the concluding book of the Rig-Veda, to which the tradition has attached an explanatory legend: he shows how this legend has grown up by degrees, by misapprehension and distortion of epithets and phrases of the hymns themselves, and that neither it nor the version made in conformity with it (and which he gives in full) really belongs to them; ending by giving a true version, founded upon independent study, and a determination of the relations of the parts of the text to one another.

In these three papers, we have the case of the anti-comment party presented from every point of view and with all desirable fullness.

The first European scholar of note to set forth and defend the contrary view was Prof. H. H. Wilson. He, however, had long passed the acme of his scholarly activity when the Veda began to attract attention in Europe, and, though his influence and patronage were freely given to the new study, and were of great importance to its progress, he was never in sympathy with its votaries, nor ever won a right to be called a Vedic scholar. The arguments by which he defends the commentaries show the prejudice naturally engendered by an Indian education, and sometimes involve gross transfers to the old Vedic time of the conditions of modern Hindu literature.

Since Wilson's death, his mantle has fallen upon Prof. Goldstücker of London, author of the fourth and last paper reviewed. This is entitled "On the Veda of the Hindus and the Veda of the German School," and was read before the Royal Asiatic Society early this year, but is not yet published otherwise than in a full and careful abstract (evidently made by the author himself) in the London "Examiner" for February 2, 1867. The title of the paper is in two respects open to criticism. In the first place, it seems to involve a *petitio principii*—the "Veda of the Hindus" being the object of all parties, and the point in dispute being whether this is to be arrived at by the methods of the modern Hindu schools, or of the modern European. In the second place, the name "German school," upon which the author dwells, and which he claims to borrow from Dr. Muir, is not found in the latter's paper, and is to be avoided, as seeming to appeal to whatever of prejudice may exist in English minds against foreign scholars and methods. At the same time, Dr. Goldstücker endeavors to disprove the existence of any such school, alleging that those who are claimed to belong to it are discordant in their methods and results. He overlooks, however, the fact that it is only with reference to one common doctrine—the non-acceptance as paramount authority of the commentator's interpretation—that they are ranked together as a school at all; and that they all in the fullest manner acknowledge the true interpretation to be attainable only as the final result of more or less discordant individual effort. Indeed, it may with much more truth be claimed that there is but one school of Vedic study in Europe, with Prof. Goldstücker as its opponent; since it is not known that any other Vedic scholar of eminence shares his views. And whether even he is its opponent on principle has been made doubtful by Dr. Muir, who shows that in his Dictionary he not infrequently criticises unfavorably and rejects Śāyana's version. It becomes, then, merely a question of personal capacity between the one side and the other; whether the right to deviate from the native authorities is to be confined to any person or persons, or restricted within the limits which these shall prescribe. Of course, each scholar must exercise his independence under responsibility, and he who, on a foundation of insufficient learning and judgment, attempts to translate the Veda, will render himself liable to be condemned and laughed at; there is doubtless temptation to over-confidence on the one side, as to a comfortable and labor-saving submissiveness on the other; yet all hope of progress is bound up with the former method. Prof. Goldstücker, in justification of the alternative versions so often given by the commentary, proposes to recognize them as originating in and held by different native schools: but, in so doing, he distinctly assents to the fundamental doctrine of his opponents—that these versions are the products of learned study, not of authoritative tradition. He declares that the determination of the grammatical cognateness of Vedic passages (upon which he

assumes the independent interpretations of the other party to be founded) is a peculiarly difficult problem, which has not yet been broached, much less settled. This claim requires farther explanation to make it intelligible: but, meantime, we are justified in going on to interpret simply by aid of the comparison of parallel passages—about which, certainly, there is no mystery, as it is the method successfully employed in every other language and literature besides the Vedic; not only as between authors of the same age, but through all the periods of every literature.

The principles of the "German school" are the only ones which can ever guide us to a true understanding of the Veda. We have within our reach precisely the same means of research which the Hindu schools had—namely, a knowledge of the classical Sanskrit and of modern Hindu institutions, and if our command of such knowledge is in some respects inferior to theirs, the deficiency is much more than made up by the superiority of our methods of research, and by our possession of a critical and historical spirit which was denied to them.

7. On Recent Geographical Explorations in the Hindu-Kuh Range, and its Vicinity, by Prof. D. C. Gilman, of New Haven.

Prof. Gilman gave an abstract of the results of several works which have appeared within no long time past, treating of this interesting region, especially of the alleged wanderings and observations of an anonymous writer, brought to light by the Russian traveller, M. Veniukof, and recently printed in the London Geographical Society's Journal.—the authenticity of the original document having been called in serious question by English geographers. He exhibited maps of the region, and pointed out how it was being approached from more than one side by geographical exploration and discovery.

Rev. Cyrus Byington, for nearly fifty years a missionary among the Choctaw Indians, being present, gave, by request, some account of the progress of civilization and religion in that community during his presence with them, and described, partly in answer to questions, some of the striking peculiarities of their language.

The Society then adjourned, to meet again in Boston, on the 20th of May, 1868.

The account, having been audited by a committee of two, appointed for that purpose, were accepted. The Librarian presented a list of donors during the year to the Society's collection, and gave oral explanations of the character and value of the donations made. To the catalogue of the Librarian, have been added 11 new titles, besides one manuscript title. In behalf of the Committee of Publication, a report was made by the Corresponding Secretary. There has been no issue of the Journal during the past year, owing mainly to the lack of suitable material for publication of the *Tāntrik* literature, and its commentary, the *Prakāśhastava*, which work has been intended and expected to occupy a part of the next volume has been delayed by unforeseen and unavoidable circumstances. The delay, however, was to some extent greatly for the advantage of the work, since new and very important manuscript material has been

Proceedings at Boston, May 20th, 1868.

The Annual meeting of the American Oriental Society was held in Boston, on Wednesday, May 20th, at the usual hour and place. The President being absent, the chair was taken by Rev. Dr. R. Anderson, Vice-President. The day was very stormy, and the attendance of members unusually small.

The minutes of the preceding meeting (at New Haven, Oct. 1867) were read by the Recording Secretary and approved. Reports from the retiring officers were then called for.

The Treasurer's report was presented, in his absence, by the Recording Secretary. It showed the income and expenses of the year to have been as follows:

RECEIPTS.

Balance on hand, May 22d, 1867, - - - - -	\$1,049.76
Annual Assessments, - - - - -	\$ 75.00
Sale of the Journal, - - - - -	149.49
Interest on deposit in Savings Bank, - - - - -	107.88
Total receipts of the year, - - - - -	332.37
	<u>\$1,382.13</u>

EXPENDITURES.

Printing of Proceedings, etc., - - - - -	\$ 92.72
Expenses of Library and Correspondence, - - - - -	29.81
Total expenditures of the year, - - - - -	\$ 122.53
Balance on hand, May 20th, 1868, - - - - -	1,259.60
	<u>\$1,382.13</u>

The accounts, having been audited by a committee of two, appointed for that purpose, were accepted.

The Librarian presented a list of donors during the year to the Society's collections, and gave oral explanations of the character and value of the donations made. To the catalogue of the Library have been added 41 new titles, besides one manuscript title.

In behalf of the Committee of Publication, a report was made by the Corresponding Secretary. There has been no issue of the Journal during the past year, owing mainly to the lack of suitable material. Preparation of the edition of the *Tāittiriya-Prātiçākhyā* and its commentary, the *Tribhāshyaratna*, which work has been intended and expected to occupy a part of the next volume, has been delayed by unforeseen and unavoidable circumstances. The delay, however, was to turn out greatly for the advantage of the work, since new and very important manuscript material has been

recently secured. Besides a collation of the (imperfect) Oxford MS., obtained through the kind offices of Prof. Müller, a copy and collation of two other manuscripts, recently discovered in the library of the Royal Asiatic Society in London, has been secured. Information of these was sent to Prof. Whitney by Dr. R. Rost, Secretary of the Roy. As. Soc., last autumn; and the copy and collation has been made, with his kind coöperation and aid, by Dr. Julius Eggeling, a German scholar now residing in England, to whose generous and friendly devotion the work will be greatly indebted for its completeness. The manuscripts referred to have been for many years in the possession of the London Society, but, being written in the southern Indian characters (one in Malayalam, the other, on strips of palm leaf, in Grantha), they have until now escaped identification and notice. Their assistance will render it possible to furnish a satisfactory text of the commentary, which it is accordingly proposed to add in full to the treatise and notes. There is no reason to believe that a half-volume will not be ready for delivery to the members by the next annual meeting, and the other half-volume in the course of 1869.

The Board of Directors announced that the autumn meeting would be held in New Haven, October 14th, and that Mr. Cothéal of New York, with the Recording and Corresponding Secretaries, would act as a Committee of Arrangements for it.

They also gave notice that they had appointed Prof. Salisbury and Rev. Dr. Clark to aid the Corresponding Secretary in endeavoring to secure a more extended and active participation of American Missionaries in the work of the Society; and had committed the lists of members for revision to Professors Salisbury, Hadley, and Whitney, with directions to report at the next annual meeting.

Two gentlemen, recommended by the Board for election to membership, were balloted upon, and duly elected, namely:

as Corporate Member,

Prof. John B. Feuling, Madison, Wisc.

as Corresponding Member,

Rev. Charles H. H. Wright, of Dresden.

The Corresponding Secretary called the attention of the meeting to the unusual loss it had suffered during the past year in the death of four of its Honorary Members—namely, Prof. F. Bopp of Berlin, the Duc de Luynes and M. Reinaud of Paris, and Rāja Rādhākānta Deva of Calcutta. He gave a brief statement of the claims of each of these gentlemen to the respectful and grateful remembrance of Orientalists, entering into more detail respecting the brilliant achievements of Bopp in the department of comparative philology.

Notice was also taken of the death of Prof. C. C. Jewett of Boston, a Corporate Member, Prof. Peabody of Cambridge giving some account of his life and literary labors.

Messrs. Ropes of Boston, Sanborn of Springfield, and Brigham of Taunton, were appointed a Nominating Committee, to propose a board of officers for the next year. They presented the following ticket (the same with last year's), which was elected without dissent:

President—Pres. T. D. WOOLSEY, D.D., LL.D., of New Haven.
Vice-Presidents—{ Rev. RUFUS ANDERSON, D.D., " Boston.
 { Hon. PETER PARKER, M.D., " Washington.
 { Prof. EDWARD E. SALISBURY, " New Haven.
Corresp. Secretary—Prof. W. D. WHITNEY, Ph.D., " New Haven.
Secr. of Classical Section—Prof. JAMES HADLEY, " New Haven.
Recording Secretary—Mr. EZRA ARNOT, " Cambridge.
Treasurer—Prof. D. C. GILMAN, " New Haven.
Librarian—Prof. W. D. WHITNEY, " New Haven.
 { Mr. A. I. COITHEAL, " New York.
 { Prof. W. W. GOODWIN, Ph.D., " Cambridge.
 { Prof. W. H. GREEN, D.D., " Princeton.
Directors—{ Prof. J. J. OWEN, D.D., " New York.
 { Prof. A. P. PEABODY, D.D., " Cambridge.
 { Dr. CHARLES PICKERING, " Boston.
 { Prof. JOHN PROUDFIT, D.D., " New York.

A few extracts were read from letters received since the last meeting. Among them was the following, from Mr. John P. Brown of Constantinople, dated Jan. 24, 1868:

"I see in Trübner's catalogue that my little work on 'The Dervishes' is out and for sale, although I have not yet received a copy of it. I have just had printed, also, in London, a small work, called 'Ancient and Modern Constantinople,' which will soon be for sale. I shall try and send you a copy of each. During the spring and summer months I have been absent, and have done but little in the literary line. I am collecting materials for a 'Life and Times of Ali, the 4th Caliph,' which I hope sometime to publish. This will have a religious rather than a historical character—or rather, will partake of both.

"Dr. Paspatis is employed on a large work on 'the Gypsies and their Language, with their Tales and Ballads.' This will interest you, as the roots of their language are Sanskritic. The secret religion of the Gypsies would be of much interest, and may be found in their tales and ballads; but as yet, no one has taken it up. Dr. Moritmann of this city has promised to do so, but has not as yet accomplished anything, so far as I am aware.

Only one communication was presented at this meeting, namely On Bell's "Visible Speech," by Prof. W. D. Whitney, of New Haven.

The work in which this new system of phonetic writing is laid before the public is entitled "Visible Speech: the Science of Universal Alphabets; or, Self-interpreting Physiological Letters, for the writing of all Languages in one Alphabet. Illustrated by Tables, Diagrams, and Examples. By Alex. Melville Bell, etc. etc. Inaugural Edition, London, 1867." (4to. pp. 126.) It begins with an account of the circumstances attending the origination and development of the system, of the attempt made by its author to get it taken up and propagated through the community by the British Government, and the failure of this attempt, of the tests through which it had triumphantly passed, and of the testimony given in its favor by practiced phonetists like Mr. A. J. Ellis. The system is one, which cuts loose from all alphabets in present use, and sets up a new scheme of signs, of

which every element is intended to be directly symbolic of a physical act, so that each letter represents the whole method of production of the sound it stands for, and is, after the symbolism is learned, self-interpreting. Not only articulate sounds, but almost all andible utterances of which human organs are capable, are claimed to be representable by it: it aims at, and fairly accomplishes, more than any other system ever invented. Prof. Whitney gave an account of the contents of the work, and an analysis and criticism of its signs for sounds. He showed that, while these are exceedingly ingenious, and in the main sufficiently exact, they nevertheless are far from being entitled to all the credit claimed for them. Even in the consonantal part of the alphabet, Mr. Bell's analysis of not a few sounds is faulty, and his designation false; for example, in *x*, *z*, *th*, he either introduces symbols of unreal acts, or omits to symbolize other real acts of articulation, or both. With his treatment of the far more difficult matter of vowel utterance much more fault was found: his whole scheme of classification and description of the vowels was rejected, as being a step backward rather than forward, when compared with the labors of his predecessors. On the whole, it was asserted that Mr. Bell has not in a single point sensibly advanced the science of alphabetic notation, although he has shown superior skill in the art of alphabetic notation. He is disposed also to overrate the value and usefulness of his invention, imagining that it is going to do away with the difficulties of learning to read, of learning to pronounce a foreign language, of analysing and representing the sounds of unwritten tongues, and the like. Whereas, a scheme of alphabetic symbols is like a scheme of chemical symbols, or a nomenclature in any branch of science; a good nomenclature efficiently facilitates the mastery of a science, as a bad one throws obstacles in the way of it; but the nomenclature is of secondary consequence, and to acquire it is not to master the science. It is to phonetists that Mr. Bell's system must be chiefly valuable; and there seems no good reason why the task of spreading the knowledge and use of it should have been assumed by Government.

The construction of the volume presenting the system was criticized as being far too obscure and difficult. By first giving the physical descriptions of sounds complete, and putting off all illustration to another part of the work, the author has doubtless repelled many who might otherwise have learned to understand and favor the new alphabet.

After some discussion of the subject of this communication, the Society adjourned.

Ballot being had, those gentlemen were declared duly elected. Prof. Whitney, for the Committee of Publication, stated that still another manuscript of the *Taittiriya Pratisakhya* and its commentary had been furnished for the benefit of the publication to Prof. Weber. Dr. S. Goldschmidt, of a manuscript recently sent to Prof. Weber at Berlin, by Prof. Bahler of Bombay. The Directors had kindly acknowledged the kindness of Dr. Goldschmidt in making the transcription. The work it was further mentioned, was already in part prepared for the press, and its printing would be soon commenced.

The correspondence of the past six months was presented, and extracts from it were read by the Corresponding Secretary.

Habu Ramachandra Ghosh, under date of Calcutta, Jan. 4, 1888, writes:

"The collection of Sanskrit in Europe and America excites a general interest. It has formed a new era in philology. It has opened the dark vista of antiquity and contributed to the enlightenment of your ethnographical past. It is highly desirable to give a basis for the study of Sanskrit existing in Bengal. Several has

Proceedings at New Haven, October 14th and 15th, 1868.

The Society met, as adjourned, at New Haven, in the Library-room of the Sheffield Scientific School, the President in the chair. The minutes of the last meeting having been read, the Committee of Arrangements presented their plan for the conduct of the present session, which was, on motion, adopted. The Society would adjourn at about 6 o'clock, in order to accept an invitation from the President, Dr. Woolsey, to take tea at his house. After tea, it would receive a communication from Dr. Martin, and would assemble again at 9 o'clock on Thursday morning, to hear further communications.

The Directors gave notice that the next Annual meeting would be holden in Boston, on Wednesday, May 19th, 1869, and that they had appointed for it the same Committee of Arrangements as last year—namely, Mr. Joseph S. Ropes of Boston, and the Recording and Corresponding Secretaries.

They also recommended the election, as Corporate Members, of the following gentlemen:

- Mr. John W. Barrow, of New York.
- Prof. Albert S. Bickmore, of Hamilton, N. Y.
- Rev. Edward L. Clark, of New Haven.
- Mr. Albert F. Heard, of Boston.
- Rev. William W. Hicks, of Williamsburg, N. Y.
- Rev. William Patton, D.D., of New Haven.
- Hon. Elisha R. Potter, of South Kingston, R. I.

Ballot being had, these gentlemen were declared duly elected.

Prof. Whitney, for the Committee of Publication, stated that still another manuscript of the *Tāittiriya Prāṭicākhya* and its commentary had been furnished for the benefit of the publication to be made of those works in the Journal. It was a copy, made by Dr. S. Goldschmidt, of a manuscript recently sent to Prof. Weber, at Berlin, by Prof. Bühler of Bombay. The Directors had suitably acknowledged the kindness of Dr. Goldschmidt in making the transcription. The work, it was further mentioned, was already in part prepared for the press, and its printing would be soon commenced.

The correspondence of the past six months was presented, and extracts from it were read, by the Corresponding Secretary.

Babu Rāmachandra Ghosha, under date of Calcutta, Jan. 4, 1868, writes:

"The cultivation of Sanskrit in Europe and America excites a general interest; it has formed a new era in philology, it has opened the dark vistas of antiquity, and contributed to the establishment of great ethnographical facts. It is highly delightful to see a taste for the study of Sanskrit reviving in Bengal. Seven hun-

dred and ninety-five years ago, the Brahmins of Bengal were so ignorant in the higher branches of the Hindu Śāstras, that King Adisar had to request the Raja of Kānūj to send down five Brahmins well known for their erudition. Schools of an elementary character may have existed at this time, but no institutions of a higher order were then to be found in Bengal. Now, many schools are found in Haldisahar, Bhātpāra, and Nudda, where the higher branches of the Hindu Śāstras are carefully studied. Celebrated schools, especially of the Nyāya philosophy, however, had been established long before in Mithila. This prevalence of the Nyāya Philosophy in Mithila can be accounted for by the fact that Gotama established a school at a place not far distant from that renowned city, and the study was kept up by his pupils for a considerable time. The first regular school of philosophy established in Bengal was that of Bashudeva Sarvobhāṣa. Of the numerous students of that Pandit, the names of three have become known throughout the land. This constellation of bright names is composed of Raghunānanda, Chaitanya, and Raghunātha/Siromani. The first compiled the *Smṛiti*, whose dictum is now law; the second was the famous Vaishnava reformer; and the third, the genius whose philosophical acumen Bengal, nay India, may well be proud of. Raghunātha wrote a work exposing the fallacies of the several expositions of the Chintamani, a book written by Gaṅgēśopādhyāya, who had graduated at Mithila. This treatise is a full development of the abstruser parts of the science, as laid down in miniature by Gotama. Nudda is still regarded as the focus of philosophical learning. A number of geniuses appeared one after another, and the profound works of these mighty minds have shed a glory on India itself. The number of the Pandits in Calcutta who have written treatises on different branches of learning in Sanskrit is very small. Here we have a very small number of men who take any interest at all in the labors of an antiquarian. Babu Rājendralāla has already written several papers on different subjects appertaining to the primeval history of India, but has only reproduced the facts which have long since been brought to light by Lassen and others, in a different garb. Babu Rājendralāla is now engaged in compiling a *Prākṛita Dictionary*. Prof. Bühler of Puna College has finished his very learned essay on the *Aśvina*, and is now busy with an edition of Gobhila's *Grihya Sūtra*, with Nārāyaṇa's commentary.

Having lately had occasion to refer to the *Gaṇeśa Purāṇa*, I found that the author of this has artfully blended Buddhism with the other subjects of his work. The *Gaṇeśa Purāṇa* comprises two *Kāṇḍas*. Both the *Kāṇḍas* sanction the worship of *Gaṇeśa*. An account of *Gṛtsamada* forms a part of this *Purāṇa*. *Gṛtsamada* was the grandson of Rāja Bhīma of *Vidarbha*.

My work on the *Vedas* is now in the press. When it is published, I shall be very happy to send you a copy of it. My essay on the *Aryans* is out of print.

Rev. A. P. Happer, D.D., Pittsburgh, Pa., June 17, 1868:

I have been quite interested in looking at the Proceedings of the two meetings as published, which you have kindly sent me with your circular. I have been especially interested in reading the summary of the contents of the paper read by Pres. Woolsey, of Yale College, on the word for 'God' in Chinese. That is a subject which has engaged great attention in China. The discussion has all been conducted during the twenty-four years of my residence in China and connection with Chinese missions. The question is not, what word or compound term would be free from difficulties? That question could be easily settled. But the question is connected with the translation of the Sacred Scriptures, and it is very definite and precise. What Chinese word is the best to translate *Elohim* of the Hebrew and *Theos* of the Greek Testament? When answering the question, no philologist can say that *Tien-chu*, which is not a simple word, but a compound term, made by the Jesuit missionaries, and which means 'Heaven's Lord,' can in any way be regarded as a translation of *Elohim*, or *Theos*, or *God*.

As a title of the true God, it may and it is very properly used; but it is so used very sparingly by Protestants, for this reason. By general usage of the Chinese, Roman Catholicism is designated "The religion of the Lord of Heaven," i.e. *Tien-chu kiau*; while, by a like general usage of the Chinese themselves, Protestantism is called "The religion of Jesus," *Ye-su kiau*. This usage originated from the Romanists' using that term to designate the true God; while, of course,

Protestants in their preaching have principally spoken of Jesus as the Savior of sinners. Protestants here used *Ye-ve-veah* to represent the proper name "Jehovah" of the true God; as they use *Ye-su* to represent the name of Jesus. It appears very undesirable that Protestants should be confounded by the Chinese with Romanists. This would be the case if they used *Tien-chu*. This, however, is a subordinate reason. The chief reason is that that compound term is not a translation for the words in the original languages. Neither is the term *Shang-ti* a translation of the words in the original; this is also a compound term, originally meaning "Ruler above," or "Supreme Ruler" among gods, as *Huang-ti* is the highest ruler among men, and is the name of the Emperor in China. *Shang-ti* is now also used as the title of an idol—the proper and distinctive name of an idol, as much as *Jupiter* was.

While *shin* may be admitted to be "vague and general," yet were not *Elohim* and *Theos* vague and general words? Are they not applied in the Scriptures to false gods, to many gods, to male and female gods, to gods of the hills and of the valleys, gods of great dignity and of small dignity, to gods of many divine qualities and gods who had qualities which are not divine—in a word, to all that class of beings which by polytheists were worshipped? And yet, by usage, they are very properly applied, without any derogation to his character or dignity, to designate the only living and true God, "whose name is above every name." The use of these words, thus applied to the true and the false, to the one only God and to the multitude that are false gods, does not produce any confusion, either in Hebrew, Greek, or English.

Now *shin* is such a "general and vague" word. It is applied by the Chinese to all the objects of their idolatrous worship, which are represented by idols of wood and stone and paper, and for the worship of which they erect temples, and to worship which they have shrines in every family residence, store, and workshop. There are *shin* of the hills and valleys, a *shin* of fecundity, a *shin*, a goddess, "the hearer of prayer and the most compassionate one who saves from suffering and misery," *shin* in Heaven, *shin* on the Earth. The Chinese go to their temples to worship *shin*. They pray to *shin* to restore their health. They return thanks to *shin* for prosperity. There is a *shin* called the *shin* of wealth. Now what word in English would translate *shin* in all these cases? Why, manifestly, "god, gods, goddess"—and if that is the word that represents all the various objects of false or idolatrous worship, what should be done when we wish to teach that idolatrous people to worship the true God, but to tell them there is a true *shin*, whose name is Jehovah, and who is "the Maker of the Heavens and the Earth." Is there any vagueness in such a statement? Does it not avail of all the knowledge which they have of God in general from the light of nature and tradition, and tell them that the Bible teaches there is only one object of proper divine worship?—that Jehovah is therefore the only and the true *shin*, while all those *shin* which they have hitherto worshipped are false *shin*, and they must cease to worship them? Will any other word so definitely state to them the only true object of worship, and so distinctly cut them off from all worship of false gods? Can any person preach to a polytheistic people, without having a word which, like *Elohim* and *Theos* and "god," will admit of being applied to one only and to many, to the true and the false, to male and female, etc., etc.? I think not. Can *Tien-chu* be so used? No, there is only one "Heaven's Lord." It is a title, and cannot be used to translate *Elohim* or *Theos*. Try it in the passage "The great goddess Diana" (Acts xix. 35). It would read, "Great Heaven's Lord Diana," which is an absurdity; but "great *shin* Diana" is as illogical in Chinese as "great goddess Diana" is in English. When the teaching of the Bible has driven away idolatry, the now "vague" word *shin* will be as definite, meaning the one true God, as "God" is in English, or *Theos* is in Greek.

The arguments that *shin* is the true, the proper, and the only word to use in translating *Elohim* and *Theos*, are, in my opinion, unanswerable. At the same time, I think that such titles as *Tien-chu*, *Shang-ti*, Maker of Heaven, etc., etc., may be properly and wisely applied to Jehovah, to assist in conveying to the Chinese mind the character and power of Jehovah, the one true *shin*.

"Excuse me for writing so much; I had no such purpose when I commenced."

Upon the subject of this letter, Dr. Martin, of Peking, at the invitation of the President, remarked somewhat as follows:

"The common objection that *Tien-chu* was coined by Europeans, and therefore is no Chinese word, is founded on an error. That term is found in the works of *Sze Ma-t'ien*, the great historian of the Han dynasty, B. C. 122. It is there applied to one of eight divinities, who is called *Tien-chu*, the Lord of Heaven, in distinction from *Ti-chu*, the Lord of Earth, *Hai-chu*, the Lord of the Sea, etc. The composition of the term is therefore not original with the Roman Catholic missionaries. Nor was its application to the supreme and only God altogether so.

"On a mountain in the vicinity of Peking, a stone gateway, bearing the inscription *Tien-chu-kung*, 'Palace of the Lord of Heaven,' marks the site of a ruined temple. This might have been taken for the ruins of a Christian church, but for a more extended inscription on an adjacent pillar, which describes the temple as erected in honor of *Shang-ti*, the Jupiter of the Chinese Pantheon, who is there represented as the God of Nature. The term, in its later as well as its earlier sense, had become obsolete; and to the Roman Catholic missionaries belongs the credit of reviving it in its later and purer signification.

"In the recent movement towards the adoption of *Tien-chu*, those Protestant missionaries who favored it were influenced by four considerations: 1st, a desire to escape the difficulties besetting the use of the rival terms *Shin* and *Shang-ti*; 2d, to find a common ground on which all Christians, Catholic and Protestant, might unite; 3d, to profit by the experience of their Roman Catholic predecessors; 4th, to avail themselves of the advantage derived from the currency which has been given to *Tien-chu* by the Roman Catholics, and to *Chu* by the Mohammedans.

"Dr. Happer was wrong in supposing that *Tien-chu* was to be taken promiscuously for God, god, and gods. It was only used in a special signification, *shin* being retained for idol gods, and divinity in general. Nor does this use of *shin* preclude its use in the formula *Sheng-shin*, for 'Holy Ghost'; *shin* in the one case not departing more widely from its popular sense, than *ghost* does in the other."

Dr. John Muir, Edinburgh, July 17, 1868:

"... In preparing the new edition of the third volume of my 'Sanskrit Texts,' I have had my attention drawn again to the Vedānta Sūtras, and to 'Sankara's' account of the use made by the rival schools of Indian philosophy of the Vedic texts to support their own views—interpreting them as variously as Christian divines do the Bible. I have had the desire, experienced before, renewed in me of seeing a complete English version of 'Sankara' produced; as I think that these Indian speculations, even if they should be found to contribute little or nothing to the true theory of Being and the relation of the Finite and the Infinite (which I should be slow to affirm), are at least deserving of notice, more notice than they have yet received, in the history of human thought. I have recently written to K. M. Banerjee, to see if he can be induced to translate 'Sankara.' I also wrote not long ago to my brother (the author of the life of Mahomet), who has lately been appointed lieutenant-governor of the North-West Provinces of India, and has the Benares College under his control, to ask if he could get any one to complete the late Dr. Ballantyne's translations of the Sūtras, of which only the Sāṅkhya and most of the Nyāya were finished...."

Rev. William Tracy, Norwich, Conn., Sept. 3, 1868:

"Just before leaving India last year, I procured a number of small copper coins, most of them apparently of considerable antiquity. There were also among them two small ancient gold coins, and a few silver ones, the latter mostly recent.

"These coins, of which I send you specimens, are dug up from the ruins of ancient towns and villages in the South of India, and their devices indicate the different dynasties under which they were coined; and in some cases, also, the religion dominant at the time. Some appear to be Buddhistic, some Brahmanic, of the Vaishnava sect, and others of the Saiva sect. A few are Mohammedan. I

regret that I am unable to give a more definite description of these coins, but since obtaining them I have had neither time nor facilities for making a satisfactory examination of them. If you think they are of enough interest to warrant their being placed in the Cabinet of the Society, please make such a disposal of them.

I take the liberty, also, of sending a few specimens of pottery, from what I suppose to be ancient Buddhistic sepulchres, such as are found in various parts of India. Some of the best specimens I had procured were entirely destroyed by the carelessness of the native coolies in India. Those which I send have been restored as far as possible; in one instance only a few fragments remain to show the original form of the vessel.

The only metallic remains found in these sepulchres in Southern India, so far as I know, are in the form of daggers, or sacrificial knives. The oxidized fragments of an instrument of this kind, apparently a dagger, accompany the vessels sent. Similar remains are found in all parts of Southern India, and closely resemble those found in the Buddhist Topes of the Punjab.

These ancient burial places, as found in Southern India, are of two kinds. The first is simply a large funeral urn, of coarse pottery, from three to four feet in height, pointed at the bottom, and covered with a closely fitting top, within which are deposited various earthen utensils, such as those I send you. These contain small fragments of bones and ashes; and, in one instance, I have found in them the husks of rice, in a good state of preservation. A large slab of stone, five or six feet square, is sometimes placed above the urn, one or two feet below the ground, and the place of burial is indicated by a large circle of stones on the surface. The places of burial were usually selected in a hard and dry gravelly soil.

The second class of these ancient sepulchres is less common than the first. They are formed of slabs of stone, enclosing a small chamber, and covered by another slab, generally on a level with the surface of the ground. Quite a large collection of these is found about twenty-five miles from Madura, and a few rods to the east of the Trichinopoly road. Some of these are covered with heaps of stones, but most are surrounded with a circle of stones similar to those mentioned above. Some, I found on visiting them, had been opened, probably by some one in search of treasure. One or two, of better workmanship than the rest, were unclosed by a carefully built and well preserved platform of stone. The sides were formed of slabs from six to eight feet square, and three or four inches thick; and a similar slab divided the room into two equal compartments. Three or four feet from the top, a shelf of stone, twenty inches wide and three inches thick, ran across the whole length of the tomb. Near the bottom of each compartment, a hole, fifteen to eighteen inches in diameter, was cut through the stone, forming a passage into the tomb, which was closed by a flat stone placed against it on the outside. Through this passage, probably, the remains of the dead were conveyed to their final resting place.

One or two of the tombs were almost entirely above ground, and, having one of the sides partially broken out, were used as an occasional place of rest and shelter by the shepherds of the neighborhood.

From the form of these tombs, I should judge that the bodies were deposited in them without having been burned. No signs of funeral utensils were seen, and my limited time would not allow me to make any fresh excavations.

Tombs of this description are found in several places in the Madura district—in the mountains as well as in the plains, and also in the districts north of Madura. The present inhabitants have no knowledge of the people who constructed them. One tradition regards them as a race of men who never died, and who were placed in these tombs with a little rice and water in cups for their sustenance. Another tradition is, that in ancient times there lived here a race who were the enemies of the gods, and whose great wickedness led the latter to determine upon their destruction. They first attempted to accomplish this by a shower of fire, but the people constructed these stone dwellings, and thus protected themselves from the fiery storm. Afterwards the gods poured out a flood of mud and water, which filled their dwellings and destroyed the wicked race.

"This tradition possibly refers to the destruction of the Buddhists, who were always regarded as the enemies of the Brahmanical deities, and who, if other local traditions are true, were persecuted, and finally exterminated, by the Brahmins and their adherents, a few scattered remnants alone having continued in existence till the eleventh or twelfth century.

"Regretting that the remains I send are so scanty, and my information respecting them so meager, I remain, etc."

Annexed to Mr. Tracy's letter is a list of the coins sent, numbering about one hundred and fifty, among them a dozen silver coins and two gold ones. The coins and the remains from the tombs were laid upon the table, for the inspection of the members present.

Mr. Hyde Clarke, London, Sept. 13, 1868:

After giving a statement of the various ethnographical inquiries which he is engaged in pursuing, Mr. Clarke concludes:

"Next season I lay the foundations of a new subject by a course of lectures at the London institutions on Comparative History, or the phenomena common to the history of many nations."

After the reading of the correspondence, communications were called for.

1. On the Study of Alchemy in China, by Rev. William A. P. Martin, D.D., of Peking.

After tracing briefly the connection between alchemy and chemistry, the paper proceeded to its main object, viz: to demonstrate that the origin of European alchemy was to be sought in China.

In support of this view the following considerations were adduced, and illustrated by citations from Chinese and other works.

1. The study of alchemy had been in full vigor in China for at least six centuries, before it made its appearance in Europe. It did not appear in Europe until the fourth century, when intercourse with the far East had become somewhat frequent. It appeared first at Byzantium and Alexandria, where the commerce of the East chiefly centered, and was subsequently revived in Europe by the Saracens, whose most famous school of alchemy was at Bagdad, where intercourse with Eastern Asia was frequent.

2. The objects of pursuit in both schools were identical, and in either case twofold—immortality and gold. In Europe the former was the less prominent, because the people, being in possession of Christianity, had a vivid faith in a future life, to satisfy their longings on that head.

3. In either school there were two elixirs, the greater and the less, and the properties ascribed to them closely correspond.

4. The principles underlying both systems are identical—the composite nature of the metals, and their vegetation from a seminal germ. Indeed, the characters *ying* for the germ, and *fai* for the matrix, which constantly occur in the writings of Chinese alchemists, might be taken for the translation of terms in the vocabulary of the Western school, if their higher antiquity did not forbid the hypothesis.

5. The ends in view being the same, the means by which they were pursued were nearly identical—mercury and lead being as conspicuous in the laboratories of the East, as mercury and sulphur were in those of the West. It is of less significance to add that many other substances were common to both schools, than to note the remarkable coincidence that, in Chinese as in European alchemy, the names of the two principal reagents are used in a mystical sense.

6. Both schools, or at least individuals in both schools, held the doctrine of a cycle of changes, in the course of which the precious metals revert to their baser elements.

7. Both are closely interwoven with astrology.

8. Both led to the practice of magical arts, and unbounded charlatanism.

9. Both deal in language of equal extravagance; and the style of European alchemists, so unlike the sobriety of thought characteristic of the Western mind, would, if considered alone, give us no very uncertain indication of its origin in the ferrid fancy of the Orient.

2. Greek Inscriptions from the Vicinity of Amasia, in the Ancient Pontus, by Rev. Julius Y. Leonard, a Missionary of the American Board.

Mr. Leonard gave a brief description of Amasia in northern Asia Minor, where he has resided for several years as a missionary. It was the birth-place of the geographer Strabo, and at an earlier period had been the royal residence of the princes of Pontus. He spoke of the remains of ancient constructions found in and about it. Greek inscriptions were occasionally met with; several of them were given by Hamilton in his "Researches in Asia Minor." Mr. Leonard himself had copied seven or eight others, which he presented to this Society. Three were from a place called Vezir-Keopen; in the pashalic of Amasia: one was from Ak-Tepe, and two from Avdan-Keon, villages (each of them) about three miles distant from Vezir-Keopen. He entered into some details as to the places where the inscriptions were found, the size and shape of the stones, the size of the letters, etc.

Professor Hadley, after stating that he had had only a few minutes to look at the inscriptions, proceeded to make some remarks on their appearance. They seemed to be wholly of a sepulchral character. They were all more or less imperfect, having suffered losses, either by the breaking of the stone, or by defacement of its surface making many letters illegible. One or two inscriptions could hardly be made to yield any continuous sense. The most legible was that inscribed on the face of the rock at the entrance of a tomb in Amasia. It was also the most interesting in its contents, being in verse, and consisting of four elegiac distichs, which, however, were obviously rude and faulty in their metrical structure.

Some further account of these inscriptions will probably be given in the Journal of the Society.

3. On Onomatopœia in the Algonkin Languages, by Mr. J. Hammond Trumbull, of Hartford, Conn.

In Dr. Wilson's "Prehistoric Man" (2d edition, p. 56) is given a list of twenty-six names of animals which he regards as of onomatopœiotic origin, and as illustrating the fact that "primitives originating directly from the observation of natural sounds are not uncommon among the native root-words of the New World." This list has been used by Mr. Farrar (Chapters on Language, pp. 24-5) in support of his averment that, in savage vocabularies, "almost every name for an animal is a striking and obvious onomatopœia." Hence the inquiry raised in this paper as to the actual derivation of the names in question.

Mr. Trumbull premised by saying that, considering our imperfect comprehension of the Algonkin dialects, we could not be expected to refute every assumed and doubtful onomatopœia by a true etymology. Of a part of the words in the list, it can only be said that their origin is not *prima facie* mimetic. Respecting others, the fact can be proved. Thus *koo-kooch*, 'sow,' is demonstrably derived, by an adaptation of the name for 'porcupine,' from a root signifying 'sharp,' and it designates 'a bad bristly or prickly animal.' As to *pe-zheo*, 'wild cat,' forms of which are widely distributed, and used to denote various of the feline animals, there is a bare possibility that it may be imitative, but no more. These are the only names of quadrupeds in the list. Of the nineteen names of birds, four or five are presumably mimetic (including those of the owl and crow), six or seven possibly so, and the rest obviously derivative and significant. *Shi-sheeb*, 'duck,' like *duck* itself, comes from a root signifying 'dive.' *Pau-pau-say*, 'the common spotted woodpecker,' means 'a spotted bird.' *Maash-kah-oo*, 'bittern,' denotes a frequenter of marshes. *No-no-no-caus-e*, 'humming-bird,'—a strange enough onomatopœia!—means 'the exceedingly delicate creature.' Of the asserted mi-

met names for 'frog,' one signifies 'diver,' and the other, as it belongs also to the toad, is not likely to be truly imitative. And so on. If only one fourth of a list carefully gleaned from three dialects can be fairly set down as onomatopoeic, how much less is likely to be the proportion of such names to the whole vocabulary of any one tribe?

Mr. Trumbull affirmed that most Algonkin names of animals are descriptive derivatives, and that the few apparent exceptions belong to species which are more often heard than seen, while it is doubtful if any name of a quadruped is purely mimetic. To illustrate this, he gave a brief list of names, with their derivations. He further drew attention to certain curious features of Indian nomenclature, especially to the combination of a generic characteristic with specific names; as, for example, certain swimming animals have a common suffix of derivation coming from a root that means, 'put the head above water'; others, one that means 'bite'; others, 'scratch' or 'tear,' of plants, some are thus marked as to be eaten green, as nut-bearing, as having eatable roots, and so on. Such a suffix, in the Chippeway and allied tongues, is *gun*, the formative of the instrumentive participial; the occurrence of which at the end of the name for 'shooting-instrument' has misled Mr. Farrar into affirming (p. 34) that "in some cases the onomatopoeic instinct is so strong that it asserts itself side by side with the adoption of a name" from a foreign language.

At the evening gathering, at Pres. Woolsey's, the Society was called to order, after tea, at about 8 o'clock, and listened to a lecture by Dr. Martin, on the present and prospective relations of China to the Western world. Some of the topics which he treated of and illustrated, may be briefly stated as follows:

It was a mistake to suppose that the Chinese mind is utterly immobile and incapable of change.

China had passed through no fewer than twenty-two dynastic revolutions. Most of these had indeed originated in no better motive than the lust of power, and had left the wheels of the government to run on in their old ruts. But some of them had involved high political principles; as, for instance, that which led to the overthrow of the feudal system, and the establishment of a centralized government, B. C. 240.

The whole mass of the population had more than once been profoundly agitated by what may be called a religious movement; especially when the three prevailing systems rose from small beginnings, and successively made their way to the throne of the empire and a place in the heart of the nation.

Periods of intellectual awakening had also occurred, distinct from these great systems of morals and religion; such, for example, as that which followed the restoration of the ancient classics, after their destruction by the tyrant of Ts'in; such as that occasioned by the invention of paper in the dynasty of Han; the discovery of the art of printing in the dynasty of Tang, and the rise of speculative philosophy in that of Song.

The movement now in progress involved all three of these elements—politics, letters, and religion.

The political change was exhibited in the foreign relations of China, not in her domestic administration, and the Embassy that had recently arrived in the West was its proper exponent. The liberal policy they had adopted, the Chinese learned in the school of adversity. War, the great civilizer, had been their teacher. The unequal conflict they had waged with the nations of the West had taught them that knowledge is power, and set them on the career of improvement on which they have now entered.

At two places might be seen bodies of troops training in foreign tactics. At four places they had established arsenals, for the manufacture of foreign arms; and at two places they had commenced navy yards, for the building of war vessels, very inferior to those in vogue in the West.

They were not, however, limiting themselves to learning the art of war. In three of the provinces, schools had been opened, under the auspices of the pro-

vincial viceroys, for instruction in the languages and sciences of the West; and at the capital, a College had been established, under the patronage of the Emperor, which it was intended to expand into the proportions of a University.

The concluding session of the Society was held in the Sheffield Library at 9 o'clock on Thursday morning.

Prof. Salisbury first gave the meeting an account of a volume of Arabic manuscript written by a slave at the south, which had a few months ago been placed in his hands for examination.

Rev. Hyman A. Wilder, missionary to the Zulus in South Africa, presented, in an off-hand way, some interesting details respecting the language, character, and manners and customs of that people.

Dr. Martin exhibited a roll of the law from the Jewish congregations at Kai-fung-fu in China. It was written on kid skins, neatly sewed together, and measured over one hundred feet in length, by two feet in breadth. He proposed at a future time to say something with regard to its character. The circumstance was mentioned that a much older roll from the same locality had been recently presented to the library of the American Bible Society in New York, by Dr. S. Wells Williams.

The following additional communications were presented:

5. On the Ancient Chinese, and its Connection with the Aryan Languages, by Rev. Joseph Edkins, of Peking; presented by Dr. Martin.

Mr. Edkins complains that comparative philologists have paid less attention to the Chinese than its merits deserve, while those who have treated it have taken generally without question the modern forms of the Mandarin dialect, disregarding the secular changes which the language has undergone. These are to be traced out by the aid of the phonetic elements in the written characters, as interpreted especially by the dialects of the southeastern part of the country. The phonetic re-spelling used in Chinese native dictionaries of 1200 years ago shows the initials and finals in a very different condition from the present, and gives at least 700 separate words, instead of the 532 now in use. The odes of the Shi King, in part from before 1100 B. C., are written in rhyme, which renders possible the restoration in many cases of the pronunciation then usual. The beginnings of Chinese writing were explained by Mr. Edkins, in order to show how the phonetic elements were used to determine earlier pronunciation, and many examples were given in illustration. The application of evidence from the existing dialects was in like manner illustrated. A summary of general results teaches us that the early vocabulary of the language may have contained from twelve to sixteen hundred words, with few or none of the distinctions of tone now prevalent, which have gradually grown up to supplement the deficient resources of expression, the *p'ing* and *ju* appearing first, then, after B. C. 1000, the *shang*, and about the time of Christ the *ch'ü*; the modern Mandarin, with a fifth tone, since A. D. 700.

Through the whole paper, abundant comparisons are made between words of the Chinese language and words of similar sound in the Mongol and Manchu, and also in various western tongues, including the English.

Prof. Whitney remarked, in criticism of this paper, that, while its attempts at restoration of an earlier phase of the Chinese were highly important and interesting, and the successful prosecution of such researches would bring that language under the consideration of comparative philologists in quite a different way from hitherto, the same value could not be attributed to the author's comparisons of

words. Mr. Edkins estimated the difficulties of comparison between tongues of different family far too lightly, neglecting for the western languages the historical inquiries whose necessity he very properly insisted on for the Chinese, and calling attention to verbal resemblances which could in many cases be clearly proved valueless, and in the rest were presumably so. The way was not yet cleared for fruitful comparisons of the kind here essayed.

6. On Recent Explorations in Jerusalem, by Rev. Edward L. Clark, of New Haven.

Mr. Clark pointed out how the investigations of the Palestine Exploration Society have confirmed many of the statements of Josephus which were once held in doubt, and proved the truth of the conjectures of later writers, such as Dr. Gustav Schultz, T. Tobler, and Dr. Edward Robinson. The site of the sepulchre of David on Mt. Zion is shown to be that claimed by the Moslems, but a lower cave contains the actual burial place; and the former approach is found on the western side of Mt. Zion, through a large vestibule of native rock, with the remains of steps, piers, and doors.

The strength of the ancient fortress of the Jebusites is attested by stairs cut on the western face of the hill upon which it stood.

The valley of the Tyropoeon is found to be filled with rubbish nearly ninety feet deep, near the southwest angle of the temple walls; and, at that place, the massive pavement is laid bare. At the same time, piers decreasing in size as they are found successively on the west toward Mt. Zion, and opposite the wall whence spring the arches of Dr. Robinson's "bridge," suggest that this so-called bridge may have been a steep, broad stairway, an "ascent" to the holy house from the ancient Xystus. A corresponding break in the wall is noticed by Tobler on the southeastern side, over against the Kedron.

Beneath the temple area, the substructions of walls, piers, and massive arches, many of them as old as the days of Solomon, are found in perfect preservation. The subterranean passages, the stables of the Knights Templars, bearing the marks of the horses' hoofs, and the stairways from the south gate, now closed, were described.

The supply of water from Etham and the "upper pool" were alluded to, and the system of conduits and sewers in the ancient temple, with their cisterns, were illustrated as they are given by Ernests Pierotti, architect-engineer to Surrya, Pasha of Jerusalem.

The water supplies for the district of Ophel, the towers over the "Virgin's pool" and Siloam, and the proofs that Mt. Ophel, rather than Mt. Zion, was the site of Solomon's palace, other points were touched upon. Some facts were added which may have weight in deciding as to the course of the first and second walls of the city.

No further papers being offered, the Society adjourned, to meet again in Boston on the 19th of May, 1869.

Proceedings at Boston, May 19th, 1869.

The Society met at the usual time and place. In the absence of the President, the chair was taken by Prof. E. E. Salisbury, one of the Vice-Presidents.

After the reading of the minutes of the preceding meeting, reports of the retiring officers were called for. The Treasurer's Report showed the transactions of the past year to have been as follows:

RECEIPTS.	
Balance on hand, May 20th, 1868,	\$1,259.60.
Annual assessments paid in,	290.00
Sale of the Journal,	8.00
	<hr/>
Total receipts of the year,	298.00
	<hr/>
	\$1,557.60
EXPENDITURES.	
Printing of Journal (ix. 1), Proceedings, etc.,	\$ 1,153.72
Expenses of Library and Correspondence,	33.35
Paid for binding of books,	13.00
	<hr/>
Total expenditures of the year,	\$ 1,200.07
Balance on hand, May 19th, 1869,	357.53
	<hr/>
	\$ 1,557.60

The accounts were audited by a Committee appointed for the purpose, and accepted.

The Librarian made a verbal report, mentioning the principal donors to the library during the past year, and describing their contributions.

The Committee of Publication announced that the first half of vol. ix. of the Journal was out of the hands of the printer, and ready for delivery to the Members. It was hoped that the other half-volume would be published by the time of the next annual meeting.

The Directors gave notice that they had appointed the autumn meeting to be held in New Haven, on the 20th of October next, unless the Committee of Arrangements should see reason for changing the day:* that committee was composed of Prof. Chas. Short of New York, with the Recording and Corresponding Secretaries.

Further, they recommended to the Society the Election as Corporate Members of

* The day was in fact changed, and the meeting took place on Thursday, the 21st.

Prof. Theophilus Parsons, LL.D., of Cambridge, Mass.
 Prof. Edward J. Young, of Cambridge, Mass.
 Rev. Kinsley Twining, of Cambridge, Mass.
 Col. Thomas W. Higginson, of Newport, R. I.
 Prof. Frederic Gardiner, D.D., of Middletown, Conn.
 Mr. Francis P. Nash, of New York.
 Prof. George L. Cary, of Meadville, Pa.

and the transfer, from the list of Corresponding to that of Honorary Members, of the names of Hermann Brockhaus, Gustav Flügel, Adalbert Kuhn, Max Müller, John Muir, Adolphe Regnier, Ernest Renan, Rudolf Roth, Friedrich Spiegel, Constantin Tischendorf, and Albrecht Weber. These recommendations were, by ballot and vote, duly accepted and adopted by the Society.

The Corresponding Secretary called attention to the decease within the year of two of the Corporate Members, Rev. Swan L. Pomroy, D.D., of Portland, Me., and Prof. John J. Owen, D.D., of New York, for many years a Director of the Society. Dr. Proudfit, being called upon, paid an appropriate tribute to the character of Dr. Owen.

The correspondence of the past six months was laid upon the table, and extracts from it were read. Of most interest were a letter from Mr. Alexander J. Ellis, of London, in reference to Bell's system of "Visible Speech" (criticised in a communication presented to the Society at the preceding annual meeting: see the Proceedings of that meeting), expressing and explaining his high opinion of the system; and a letter from Prof. B. Jürg, of Innsbruck (in the Tyrol), from which the following is an extract:

"In 1866 I published (at Brockhaus's in Leipzig) the Tales of the Siddhi-Kür in the Kalmuck language, and, in 1868 (at Wagner's, Innsbruck) the supplementary tales to the Siddhi-Kür and the History of Arji-Borji-Chán in Mongolian. Although I received from the Vienna Academy a subsidy toward the expense of publication, I was obliged to add a very considerable sum out of my own pocket, which can only be covered by sale of the volumes. Of scholars interested in this special department there are but few, and the sale is almost exclusively to the larger libraries, so that I am very far from being reimbursed as yet. Hardly a copy has hitherto gone to America; and I beg that you will use your influence to have at least the original edition in Kalmuck and Mongolian procured by one and another College or University or other public library, where philological studies are pursued."

The Corresponding Secretary commended the works in question to the attention of the members present, as contributions of great and acknowledged importance to an interesting and little cultivated branch of linguistics.

The following gentlemen were next chosen by ballot, upon nomination of a special committee appointed for the purpose, as officers of the Society for the ensuing year:

President—Pres. T. D. WOOLSEY, D.D., LL.D., of New Haven.
Vice-Presidents—REV. RUFUS ANDERSON, D.D., "Boston."
 HON. PETER PARKER, M.D., "Washington."
 Prof. EDW. E. SALISBURY, LL.D., "New Haven."
Corresp. Secretary—Prof. W. D. WHITNEY, Ph.D., "New Haven."

<i>Sec. of Class. Section</i>	—Prof. JAMES HADLEY, LL.D.,	" New Haven.
<i>Recording Secretary</i>	—EZRA ARBOT, LL.D.,	" Cambridge.
<i>Treasurer</i>	—Prof. D. C. GILMAN,	" New Haven.
<i>Librarian</i>	—Prof. W. D. WHITNEY,	" New Haven.
<i>Directors</i>	{ Mr. A. I. COTHEAL,	" New York.
	{ Prof. W. W. GOODWIN, Ph.D.,	" Cambridge.
	{ Prof. W. H. GREEN, D.D.,	" Princeton.
	{ Prof. A. P. PEABODY, D.D.,	" Cambridge.
	{ Dr. CHARLES PICKERING,	" Boston.
	{ Prof. JOHN PROUDFIT, D.D.,	" New York.
	{ Prof. CHARLES SHORT, LL.D.,	" New York.

The following communications were then presented:

1. On Early Inventions of the Chinese; by Rev. Prof. W. A. P. Martin, of Peking.

Dr. Martin spoke of the various inventions, or discoveries, or applications of the resources of nature, in which China has preceded the rest of mankind, and the knowledge of which has, either demonstrably or probably, found its way to the western world from China. He first referred to tea, as an important contribution to human comfort, and the chief staple of a commerce which has led to important political results. Porcelain and silk were made only in China, until Europe learned to rival or surpass its teachers in these arts. Gunpowder is probably Chinese. The discovery of America is in a double sense owing to China, as the wealth of Cathay attracted Columbus westward, and the magnetic needle, which had been used in China for more than two thousand years, directed his course. Paper-making the Chinese invented in the first century of our era, and printing at least eight hundred years before its reinvention in Germany. Inoculation for the small-pox they had long practised before Europe learned it from the Turks, to whom it had probably found its way from the extreme East. And alchemy, the forerunner of chemistry, was pursued in China, before the Christian era, for the same objects which the early alchemists learned from the Arabs to seek after. The Chinese of the present day have ceased to invent; and while, a few centuries ago, they were in advance of all the rest of the world in the arts of civilized life, they are now, simply by having ceased to progress, as far behind the most civilized nations. Their stagnation is to be in the main attributed to their reverence for ancient times, their absorption in the study of language, literature, and antiquity, with consequent neglect of physical science, and the absence of Christianity.

2. On a Hebrew MS. of the Pentateuch, from the Jewish Congregation at Kai-fung-fu in China, by Mr. John W. Barrow of New York; presented by Dr. Martin.

This is a synagogue roll, written on 112 skins of white leather, in 237 columns, of 49 lines each; it measures 143 feet in length. The skins are in two or three places put together in the wrong order, and one passage, from Exodus xxxviii 18 to Leviticus i. 6, is wanting. They are generally in good condition, but a little water-stained. The character is clear and legible, though not elegant, and approaches the Spanish type. The text is the Masoretic, and the deviations from the received text are almost entirely mere errors in spelling. The original of which this is a representation must evidently have been of European and comparatively modern origin.

In the 26th chapter of Davidson's "Biblical Criticism" (ed. 1866, pp. 366-70), reference is made to the collation of another synagogue roll from the same source, with similar results. Dr. Lee, in the "Prolegomena in Biblia Polyglotta Londinensis Minor," gives extracts from Koenig's "Notitia S.S. Bibliorum Judeorum in Imperio Sinensi" (Halle, 1805), in which the Kai-fung-fu manuscripts are discussed.

Appended to Mr. Barrow's paper was a detailed conspectus of the various readings of the MS. in question, as compared with the received text.

After reading this paper, Dr. Martin gave, by request, an account of his journey to Kai-fung-fu, his intercourse with the remnants of the Jewish colony there (from whom he obtained the roll forming the subject of the paper), and the conditions in which they now exist.

3. On Ophir and Sheba, by Prof. Joseph W. Jenks, of Newtonville, Mass.

Prof. Jenks detailed the instances of occurrence in the Bible of the word *Ophir*, with their different orthography, and with their varying representation in the Septuagint. He briefly stated the views which had been put forward respecting the position of the country; and he proposed to harmonize their discordance by assuming that the Hebrew-Syrian fleet of Hiram and Solomon sailed through the Red Sea to rendezvous at some port of southern Arabia; that it there separated, a part going eastward to India, and a part southward to Zanguebar and Mozambique; and that, re-assembling in due time, and adding the valuable articles of traffic of Arabia itself, it returned to Eziongeber laden with the products of three countries. Sheba was claimed to be the region on both sides of the straits of Babelmandeb.

4. On Prehistoric Nations, by Rev. Ebenezer Burgess, of South Franklin, Mass.

This communication was mainly a defense of the current views of ancient history and chronology, founded on the Bible. It opposed especially the opinions of Mr. J. D. Baldwin, as set forth in his recent work entitled "Prehistoric Nations" (New York, 1869).

5. On the Hill-People of Kamaon, India, by Rev. J. T. Gracey, Missionary of the Methodist Board in Central India.

Mr. Gracey explained that what he had to say referred to the general population of the province of Kamaon, not to the Bhotiyas of the mountain passes, nor to such exceptional tribes as the Nathas. These people appeared to be destitute of legends or traditions accounting for their origin. They acknowledge but three castes, Brahmans, Rajputs, and a low degraded class called Doma. Among their peculiar customs is a game called *pathardna*, 'stoning,' in which two parties, of about two hundred each, pelt one another with stones, in a valley between hills, which are crowded with spectators; the players defending their heads by aid of a brass-studded skin shield. Polyandry is said to have prevailed formerly, but is now replaced by polygamy, and the marriage-tie is a very loose one. Among the divinities worshipped in the Hills are Goel and Sem, and the goddess Naint. Mr. Gracey gave some details respecting their worship, and related legends told of them. The people have an excessive dread of ghosts; those residing in the mountain passes are propitiated by the sacrifice of a bit of the clothing of each one who goes by.

A vocabulary of about two hundred words from the language of the hill-people of Kamaon, with their equivalents in Hindustani, was subjoined to the paper.

6. On the Competitive Examination-System in China, by Rev. Dr. Martin.

After briefly referring to the practical importance of his subject, and its bearing upon the question of an improved civil service in the United States, Dr. Martin began with speaking of the completeness and elaboration of the Chinese system, of the success with which it attained its object, the drawing in of the ablest minds of the empire to the service of the State, of the general capacity and culture of the mandarin class, and of the essential democracy of a constitution which neither recognized a hereditary aristocracy, nor left offices to be filled by the favorites of the Emperor or his representatives. The origin of the system is referred to the time of Shun (about B. C. 2200), who examined his officers every third year, for promotion or degradation. Under the Chau dynasty (about B.C. 1100), candidates for office, as well as officers, were examined in the six arts of music, archery, horsemanship, writing, arithmetic, and social and public etiquette. About the beginning

of our era, under the Han, candidates selected in the provinces for filial piety and integrity were examined at the capital in the arts above specified, and in civil and military affairs, agriculture, and geography. A thousand years later, under the Tang, the present classification of candidates and of officers was already established. Now, the subjects for examination are the same as of old, but, in accordance with the circumstances and spirit of modern times, the mode is prevaillingly literary rather than practical. The three grades of candidates are called *sü-t'ai*, *chü-jin*, and *tsün-shi*, or 'budding genius,' 'promoted scholar,' and 'ready for office.' The trial for the first degree is held in the chief city of each district or *hien*; about two thousand competitors are present, of every age, and each produces a poem and essays on assigned themes, during a night and a day of close confinement; and the authors of the few best, about one in a hundred, receive the degree of *sü-t'ai*. The holders of this title assemble once in three years at the capital of a province, and, after examination on a much wider range of subjects, in three sessions of near three days each, about one in a hundred is again advanced to the dignity of *chü-jin*. Each *chü-jin* is authorized to repair the next spring to Peking, to compete with his peers for the first degree, which is won by about three in a hundred. The successful *tsün-shi* has now open to him the highest offices in the empire, but begins usually as mayor, or sub-prefect, or sub-chancellor, to which place he is appointable by lot—if not first admitted, upon an examination presided over by the Emperor in person, into the highest literary body in the empire, the *Han-lin* ('Forest of Pencil'), or Imperial Institute. Once in three years the Emperor designates a *chuang-yuen*, or laureate scholar of the empire.

This system amounts to the most powerful incitement possible to study—more efficient, in fact, than common schools, colleges, and universities; and it wakes the most persistent and energetic labor, continued as long as the powers last. Of a certain list of ninety-nine successful competitors for the second degree, the average was above thirty years of age, while one was sixty-two, and one eighty-three. Nearly all who enter the first examination (many millions) devote their lives to education; and for readiness with the pen and retentiveness of memory are hard to parallel elsewhere. That their education is one-sided, devoted to words rather than things, exclusively literary and not scientific, the fault is not in the system, but in the national standard of knowledge. And the system affords the most powerful lever by which the standard might be raised and changed, under an enlightened central board.

In its political aspects, the system operates as a safety-valve, giving to those who are able and ambitious of distinction the means of receiving it legitimately; it affords a counterpoise to the authority of an absolute monarch; it makes administrators who understand the people whom they have to rule; and it furnishes an immense educated class who are interested in the permanence of existing institutions.

The strict standard of the examination has sometimes been lowered by allowing a greater number of successful competitors, and even, in times of special need, by selling the right to compete in a higher examination without having passed the lower; but, on the other hand, the purity of the system is carefully guarded, and a few years since the first president of the examining board at Peking was put to death for granting two or three fraudulent degrees.

In illustration of the style of the examinations, Dr. Martin gave translations of several examination-papers, or lists of questions given to the candidates to write upon.

After the reading of this paper, the Society adjourned, to meet again in October, at New Haven.

Proceedings at New Haven, October 21st and 22d, 1869.

The Society assembled for its autumn meeting on Thursday, October 21st, at 3 o'clock in the afternoon, the President in the chair.

After the reading of the minutes, the Committee of Arrangements gave notice that they had accepted on behalf of the Society an invitation from the Secretary of the Classical Section, Prof. Hadley, to take tea and hold the evening session at his house. On motion, their action in the matter was approved.

The Directors announced that they had appointed the next Annual Meeting to be held in Boston, on Wednesday, May 18th, 1870, and had designated Mr. J. S. Ropes, with the Recording and Corresponding Secretaries, as Committee of Arrangements for the meeting.

They also recommended for election as members of the Society:

to Corporate membership,

Rev. Mytton Maury, of Cold Spring, N. Y.

Mr. Nathaniel Paine, of Worcester, Mass.

Rev. William H. Ward, of New York.

Rev. Joseph K. Wight, of New Hamburg, N. Y.

to Corresponding membership,

Rev. Joseph Edkins, Missionary in China.

Rev. John T. Gracey, Missionary in Central India.

The gentlemen thus recommended were elected without dissent.

The Directors also informed the Society that, by a disastrous fire which occurred in the printing office of Messrs. Tuttle, Morehouse and Taylor, on the 21st September last, all the undistributed part of the edition of the half-volume of *Journal* just published (vol. ix. No. 1), along with the extra copies of the *Taittiriya-Pratigakhya*, had been destroyed. The Committee of Publication was now authorized by them to proceed to reprint the work and replace the loss, as soon as should be found convenient: the expense would be, it was expected, not far from two-thirds covered by an insurance of five hundred dollars which had been taken upon the Society's property in the building burnt.

Extracts from the correspondence of the past half-year were read by the Corresponding Secretary; among others, the following:

From Prof. G. Seyffarth, Dansville, N. Y., June 26th, 1869:

"I am about to publish a work entitled '*Clavis Aegyptiaca*: collection of all bilingual and some other hieroglyphic inscriptions, translated and explained. With the syllabic alphabet in hieroglyphic, hieratic, and demotic characters, and with glossaries and indexes.' This volume will contain thirty-four inscriptions, of which the famous one found in the ruins of Pompeii, on the altar in the temple of Isis, will interest the Italians."

From the Rev. J. Perkins, D.D., Chicopee, Mass, Oct. 9th, 1869:

"I am sorry to be obliged to report myself as confined to my room by protracted sickness, and not even able to use a pen. By another hand I send you two manuscripts, which I beg you to present to the Society's attention at your convenience. They are a brief grammar and vocabulary of the Kurdish language, prepared by the late lamented Rev. Samuel A. Rhea, one of your corresponding members. He had commenced copying the grammar for you before his death. Of Mr. Rhea you already know something. He was one of the most gifted men of all our missionaries. He resided eight years in Kurdistan, a much longer time than any other civilized man ever lived in the country; and, while he made the Nestorians and their language the objects of his special attention, he yet freely mingled with the Kurds also during the whole period. Yet it is to be presumed that Mr. Rhea would not claim for his grammar and vocabulary any merits beyond those of the briefest epitome of the language. I would present these manuscripts to the Oriental Society in the name of his widow. I hope in a few weeks to send you a copy of an admirable memoir of Mr. Rhea [by Rev. D. W. Marsh]."

Mr. Rhea's manuscripts here spoken of were laid before the Society later in the meeting.

From Mr. William Gamble, Superintendent of the Presbyterian Mission Press at Shanghai, dated May 18th, 1869:

"I shipped by the American Mail of March 20th two boxes of type for you, being the Chinese font ordered some time since for the American Oriental Society. Of the fund collected by Dr. Bradley there will still remain in your hands a considerable balance after paying for what are now sent. If you wish still to expend it in Chinese type, I would advise that, instead of having a larger font, you purchase the matrices for the more common sorts. In this way your font would be much more serviceable, if you wished to use it in printing. The great difficulty in printing Chinese with moveable type comes from our constantly running out of sorts. The total number of different characters in the font is 6000 full body, and 1500 primitives and radicals, which will by combination make a total of nearly 25,000 different characters. The type are in the cases, which are well packed in the boxes, and all you will have to do is to get a small cabinet made for the cases, and slip them into it according as they are numbered. . . . The Chinese and Japanese are commencing to use our method of printing to some extent."

The Secretary explained that the font procured was one of small pica size, recently cut at Shanghai under the direction of Mr. Gamble himself, and highly approved both by Chinese and foreigners for the beauty and delicacy of its style, and its convenience of practical use with English type.*

He was obliged to add that the packing had proved insufficient, and that the boxes had come to hand with most of the cases broken, and their contents in a state of *pi*, so that the font was not for the moment in condition to be used. The Directors have authorized such expenditure as should be required in order to restore its serviceableness.

From Dr. W. F. A. Behrman, dated Dresden, April 7th, 1869:

"I communicate herewith an account of the Arabic inscription found on the hippogriff of the Campo Santo at Pisa, with a rubbing made by my friend Dr. Detlefsen, during his studies, made in Italy at the end of 1859 and the beginning of 1860."

Dr. Behrman refers to the interpretation of this inscription given by M. Marcel

* The following is a specimen of it: 人之初性本善

in 1839, in the *Journal Asiatique*, and characterizes it as hardly satisfactory. Landi's plate, in his "Trattato delle simboliche rappresentanze Arabiche" (Paris, 1845, 4to, vol. ii, pp. 54, 154), is more accurate than Marcel's, but his explanation is also not to be approved: such is the opinion of Mr. Michel Amari, who gives a new reading of the inscription, copied by Dr. Behrman and translated as follows: "excellent benediction and high favor, perfect prosperity without envy, and perpetual wealth and unalterable health and happiness, and revenue not diminished for its possessor." Dr. Behrman quotes from De Morrona ("Pisa illustrata," Pisa, 1787, vol. i, p. 190-195) some account of the monument. It is 1½ metres (about five feet) high, and 1½ metres (a little over three feet) broad. It is said to have been found under ground while the foundations of the cathedral of Pisa were laid; and was placed as an ornament upon the point of the gable of the cathedral, where it remained until the beginning of the present century. It was somewhat damaged by musket-balls, fired at it while in that position.

The inscription of this monument has a great resemblance to the other legendary texts which are to be found on monuments of metal, on bowls and on vases, and the like.

The Corresponding Secretary also exhibited a copper fac-simile (electrotyped) of a supposed block-tin coin, stated to have been found, a foot and a half below the surface, at a place in Vermillion Co., Indiana, surrounded by forests but in the neighborhood of so-called "Aztec" mounds; and supposed to be a relic of the "mound-builders." It belongs at present to Mr. John Collett, of Eugene, Vermillion Co., Ind., who is desirous of having its true character determined. The characters on the coin were evidently Arabic, and several gentlemen present, practically familiar with Eastern coins, had no doubt of its being a quite modern Arabic coin, although no one was able to make out the legend. It was generally pronounced to belong to a class of spurious relics of which the West has been somewhat prolific of late.

Communications were now called for, and the following were presented:

1. On a Set of Ancient Chinese Scrolls, containing representations of early Emperors and other distinguished characters, by Dr. Peter Parker, of Washington, D. C.

These scrolls purport to be fac-similes of stones engraved during the Han dynasty (ended A. D. 260). They represent Hwang-ti (alleged date, B. C. 2596), Chuen-heuh Kaou-yang, son of Chang-i and grandson of Hwang-ti (B. C. 2400), Fuh-hi, the inventor of writing, and Tsang-tsing (B. C. 3254), Chah-tsung, Shun-ning the Divine husbandman (B. C. 3114), Te-yaou (B. C. 2330), the illustrious, "benevolent as heaven, wise as god, whom the people approached as the sun, and looked up to as the clouds," and various other worthies celebrated in the annals of China.

Dr. Parker gave a partial explanation of the contents of the scrolls. The fac-similes are highly valued by the Chinese, and their treatment serves to illustrate the zeal and cleverness of Chinese antiquarians. Scores of the latter have expended study upon them, with results which are recorded on the scrolls, each comment being dated, and having the signature and the seal of its author affixed. The original inscriptions are in part so effaced by time that only portions of the characters remain; but from these the reading has been restored and the sense determined.

A set of the scrolls was presented to the Society by Dr. Parker, who proposed to furnish later a complete translation of their contents, with notes.

2. On the Algonkin name *Manit* or *Manitou*, sometimes translated 'Great Spirit' and 'God,' by Mr. J. Hammond Trumbull, of Hartford, Conn.

This paper was introduced by remarks on the difficulty of distinguishing, in the present habits and opinions of the Indians of North America, that which they have inherited from remote ancestors and that which they have derived from foreign sources. In the absence of historical records and reliable traditions, traces of primitive beliefs must be sought in language; and such evidence as language supplies is the more valuable because it cannot be suspected of a European origin, or as of modern invention.

An analysis was given of the name *Manit* or *Manitou*, by which various Algonkin nations expressed their highest conception of an existence and a power superior to man's. *Manitou* (otherwise written *Mannittou*, *Minito*, *Munedo*, etc.) was shown to be formed from *Manit*, by affixing the representative of the verb-substantive. It means '*Manit* is,' or '*It is Manit*.' The next step in analysis separates the initial *M*, which is an indefinite and impersonal prefix, from *an-it*, a participle of the verb *an-eü*, meaning 'to be more than, to exceed, to surpass.' The adverbial form, *an-ne* (in the Massachusetts language), is the sign of the comparative degree, and means 'more, beyond.' *An-it* does not connote life, spiritual existence, or any moral attributes. One of its uses is in the sense of 'corrupt,' 'rotten,' or 'decayed,' that is, 'gone beyond' or 'more than' the natural and proper state. In this sense the Mass. *an-it* and *an-eük* (from the same verb) are used by Eliot; the Abnaki *an-ahoué* by Rale, and the corresponding *ai-et*, in the Delaware, by Zeisberger.

The primary meaning of *Manit* was thus found to be, 'Somebody who or something which goes beyond, exceeds, or is more than the common or the normal; something extra-ordinary or preter-natural—not necessarily, super-natural.' And this was shown to agree with the explanation of the word given by several early writers.

Other Algonkin words were mentioned, having similar meaning but no etymological affinity to *Manit*; such as the Abnaki *Nissek* and Micmac *Niskam*. The Dakota *wakan*, which has been translated 'God, a spirit, something consecrated; medicine,' etc., was derived from the preposition and adverb *aka*, 'above, superior.' Hence, *wakan* is as appropriately used to characterize a bad spirit as a good one, or any extra-ordinary natural phenomenon as either.

In a paper printed with the Proceedings of the Am. Philosophical Society for September, 1864, was pointed out the resemblance between the Algonkin *Manitou* and certain old-world names or titles of the Supreme Being, such as "the Chinese *mang taou*, Egyptian *ma ntr*, Latin *magnus deus*, Greek *μὴν θεός*, and Sanskrit *mahā deva*." Mr. Trumbull remarked that, with the reduction of *manitou* to its root *an*, this resemblance disappears, and with it the mathematical probability, which had been computed as not far from "a hundred millions to one," of the derivation of these names from the same original source. This analysis also deprives of all special significance what Dr. Schoolcraft regarded "as the remarkable fact, that the *-eü* or *-ü* of the Algonkin name of God is in sound both the Greek [Latin?] *deo* and the Aztec *teo transposed*." Mere verbal resemblance was proved (as Mr. Trumbull believed) in this instance, as it has been in many others, to be valueless as evidence of the genetic relationship of languages.

3. Brief Grammar and Vocabulary of the Kurdish Language, by the late Rev. Samuel A. Rhea, Missionary among the Nestorians of Kurdistan; presented by the Corresponding Secretary.

The letter of Dr. Perkins accompanying this paper has been given above.

In his grammatical sketch, Mr. Rhea goes through with the different parts of speech, explaining their inflections and modes of use; spending by far the most space upon the classification and conjugation of verbs. His vocabulary contains not far from fifteen hundred words, with very brief indication of their meaning, usually limited to a single synonym.

The Secretary read some extracts from the grammar, pointing out the very close accordance between the facts detailed and those of the Persian language. He remarked that the question of publication of the manuscript would of course remain to be determined by careful comparison with the already published data for the Kurdish, which alone could show how much that was new, and an addition to knowledge, was brought to light in it. There could hardly fail to be matter of de-

cided value here; and the collection and working up of it, in the leisure of a laborious life, was an evidence of scholarly taste and devotedness on the part of Mr. Rhea which was highly creditable to him, and could not but add to our sorrow for his early death.

4. Recent Archaeological Explorations and Discoveries in Asia Minor, by Rev. H. J. Van Lennep, Missionary of the A. B. C. F. M. in Asiatic Turkey.

Dr. Van Lennep gave a summary account of some of the results of his own explorations in Asia Minor, mentioning at the same time that most of them would be found more fully described and illustrated in a forthcoming work of his, entitled "Travels in Asia Minor," now in process of publication (by Murray, London).

He spoke first of the remains of a very ancient fort on the top of a mountain which is called Star mountain (*Yıldız Dağı*). Strabo describes a mountain by this same name, asserting that the most valuable treasures of King Mithridates were kept in the castle at its summit, and that it was taken by the Romans. Dr. Van Lennep pronounced Strabo's description to apply closely to this mountain, as regards both its situation and its character. Two streams gush forth high upon its side and flow not far apart; when they reach the base, they turn in opposite directions, pass completely around the mountain, and, uniting on the other side, form what is still called the Star river. The mountain lies between Tocat and Sivas, and the fort is more than eight thousand feet above the level of the Black Sea. It commands a view as far as that sea on the north, and Mt. Argens on the south.

Referring to the sculptures on Yazili Kayah (near the ancient Pterium, one day's journey north of Yuzghat), Dr. Van Lennep assented to Texier's explanation of them, as representing the introduction of the worship of Astarte into Phrygia; but claimed that the youth behind the goddess, whom Texier calls simply a prince, must be recognized as the Cupid of the Greeks. Mr. Layard had equally failed to recognize the child-god in the procession he copies from the carvings at Nineveh. Dr. Van Lennep supported his view by a gem recently obtained by him in Asia Minor, on which is cut an intaglio figure of the Assyrian Astarte, with the three-pointed crown on her head and the star and crescent moon on either side; while behind her, on a chair, sits a child, who is none other than Cupid. This gem was pronounced to be of Assyrian subject and Greek workmanship, pure Greek and Assyrian intaglios being exhibited to illustrate its character.

Next were described the remains of an unfinished Egyptian building at Euyuk, a day's journey north of Yazili Kayah. Its material is black granite, while Grecian monuments are usually of marble. Egyptian sphinxes stand on either side of the entrance, from which a line of sculptured stones extends to the right and left, as in other ancient monuments, both Assyrian and Egyptian. The sculptures seem to represent the erection of the building, and the festivities and ceremonies observed on the occasion. The bull Apis stands on a platform, and sacrifices of goats and oxen are offered to him by the king and queen. The features and hair of nearly all the figures are African.

Farther, the figure of Sesostris was spoken of, found carved on a ledge near the mouth of a pass through Mt. Tmolus, not far from the ancient road from Smyrna to Sardis. This is one of the two figures of the conqueror described by Herodotus.

Finally, Dr. Van Lennep described the interesting remains that lie around Smyrna; especially the old rubbish-heap of ancient Smyrna, where valuable remains are often brought to light by the rains. He spoke of the opening of several tombs of a very ancient date. He also exhibited to the Society various figures or fragments of figures in *terra cotta*, of the highest artistic merit, which had been found in those tombs or in the soil, and which appear to him to have been originally gilded, and to have represented the household divinities of the ancient Symnolotes.

5. On a Chinese Tablet illustrating the religious opinions of the literary class, by Dr. D. B. McCartee, Missionary of the Presbyterian Board at Ningpo, China.

Dr. McCartee said that the scroll which he exhibited was interesting both as a very favorable specimen of Chinese calligraphy, and as showing the views held by

a large proportion of the literary men of China with reference to the popular religion. He went on to set forth briefly the peculiar religious condition of China, explaining that the Chinese as a nation, instead of being divided between the Confucian faith, Buddhism, and the doctrines of Lao-tse, really accept them all, having recourse always to the particular divinity or rite which is reputed to be serviceable in such matters as they happen to have in hand. It has been stated that the *literati*, or so-called Confucianists, do not worship idols; but this is an error, for the stellar gods *Wu-chang* (Ursa major) and *Kwei-sing* (polar star) are worshipped by the literary class as such, and by them alone, as the speaker could testify from personal observation, having lived in a temple with these idols for more than a year.

The scroll exhibited was an impression or rubbing from a stone tablet erected in the *Ch'eng-Huang Miao*, or 'Temple of the Tutelar Deity' of the *Wei-hien* or 'district city of Wei,' in the province of Shan-tung, China; and the inscription was in the handwriting of *Chen Pan-k'iau*, the *Ch'ieh* or magistrate of the district—a literary gentleman celebrated as a poet, a calligrapher, and a wit, whose "Remains," consisting of poems, pencil drawings, and epistolary writings, have gone through many editions in China. The sentiments expressed in this document clearly mark Mr. Chen as a disciple of the school of Chu-hi, who may be said to have been the Comte of China. The inscription bears the date of the 17th year of Kien-lung, the 9th of the then current cycle (of 60 years), and the 5th moon (about June, A. D. 1752). Mr. Chen commences by referring to the *Ki-in*, the *fung* or phoenix, the serpent, and the dragon; to each of which are ascribed bodily members, and distinct personal characteristics. He then speaks of the heavens, as an azure vault, and the earth as a massive clod, and man as the being who, dwelling between heaven and earth, is characterized by certain bodily organs, the faculty of speech, a sense of propriety, etc. But, he asks, how can we suppose Heaven to possess bodily organs like man's, and ascribe to it a personal existence? He says that from the time of the Duke of Chou (B.C. 1130) the name "Supreme Ruler" (*Shang-ti*) has been applied to Heaven, and that the vulgar have styled it the "Gemmeous Emperor" (*Yah-Hwang*), and invested it with bodily organs, clothing, regalia, and a personal existence; have made images of it, and accompanied them with retinues of followers; and that subsequent ages have regarded it with awe and reverence. He then speaks of the *Ch'eng*, or wall which surrounds every city, and of the *Hwang*, or moat which encircles it, and asks why people have personified these as a god, and attributed to this god power over life and death, and jurisdiction over happiness and misery, surrounding (its images) with awe-inspiring objects, so that not only the common people are struck with awe, but even he himself confesses that, on entering the dark recesses of its temple, his hair stands on end, and his frame shudders, as though he stood in the presence of a demon. He quotes an ancient sage who says "these things are what make the people seek to conciliate them" (i. e., the gods), and adds that, unless the ignorant populace have a desire to conciliate the gods, the officers could not trust them (nor control them). After describing the repairs that had been thought necessary, and the expense incurred in making them, and in suitably furnishing the temple, he adds that some might be disposed to question the necessity, or propriety, of expending several thousand ounces of silver in erecting a pavilion and stage for theatrical exhibitions; and asks "Can it be that there are gods who delight in theatrical exhibitions?" He quotes from an ancient tablet an account of a female musician who "delighted the gods" with her performances, and cites from the Book of Odes the following passage: "With lyres and harps and strokes of the drum, welcome the Lord of the Fields;" and then asks, "Is there really a Lord of the Fields? and does he really delight in lyres and harps? If so, who ever heard of him?" He then explains it as being simply the natural way in which people give expression to their gratitude to the gods. He expresses his approbation of this system of instructing (and ruling) the people, devised by the ancients; and says that, since people have sacrificed to the *Ch'eng-Hwang* (literally 'City Wall and Moat') as though it had a personal existence, why not please it with songs and dances? And as to theatrical representations, he thinks the theatre, as a school of morals, has conferred great benefits upon mankind. All that he would stipulate is that indecent and otherwise unsuitable plays should be prohibited. In summing up, he says that Fu-hi, Shen-nung, Hwang-ti, Yau, Shun, Yu, Tang, Wen-wang, Wu-wang, the duke of Chou, and Confucius,

really did exist personally before they were deified, and there seems to be a propriety in sacrificing to them as though they (still) had a personal existence. But Heaven, earth, the sun, moon, wind, thunder, hills and streams, rivers and mountains, soil and grain, the wall and moat, the corners of the house, the well, and the fire-place, although they have been deified, have really no personal existence, and should not (properly or *per se*) be sacrificed to as though they had. Yet even the sages from the ancient times have all sacrificed to them, as though they really and personally existed; and he asks, do the deities of heaven enjoy the viands or make use of the utensils used in sacrificing to them? And he replies that, although the sounds, the colors, and the odors and tastes of things in heaven cannot be imitated, yet all these devices are but the modes of giving expression to the feelings of reverence and veneration which naturally arise in the human heart. Hence he concludes that the erection of a tablet to perpetuate the memory of the repairs made upon the Ch'eng-Hwang temple is not an affair of mere local or temporary interest, but is inseparably connected with the doctrines and ceremonial observances of remote antiquity; and since others (whose names he mentions) had liberally contributed funds to defray the expenses, he (the writer) could not be so parsimonious as to grudge a contribution of penmanship to the same object.

Dr. McCartee remarked in conclusion that he had often heard similar sentiments advanced by officers and *literati* in China, and it was interesting to observe that the wisest of that ancient nation gave such unequivocal assent to the doctrine that belief in a personal God, who will render to every man according to his work, is both a natural acting-out of the human heart, and absolutely requisite in order to secure good government.

Dr. McCartee further exhibited a set of very fine rubbings, taken from stone tablets set up in a Buddhist temple at Hangechow, and representing, nearly in life size, sixteen of the eighteen Lo-han (Sanskrit *arhant*), or personal attendants of Buddha. These rubbings he presented to the Society's collection.

6. On the Theory of the Greek Accent, by Prof. James Hadley, of New Haven.

The Greeks distinguished one syllable in each word by sounding its vowel on a higher key: this higher key was represented by the acute accent. The ordinary lower key was not represented in writing. But when it followed the higher key on the same long vowel, it was represented by the grave accent, which then united with the acute to form the circumflex. And when a high-tone ultima, followed by other words in close connection, dropped down to a lower key, it was written with a grave accent instead of the acute. The melodic character of the Greek accent Prof. Hadley illustrated from Dionysius Halic. (de Comp. Verb., 12), who calls the interval between the higher and lower keys a fifth (three tones and a semitone). That there was any difference in stress (or force of utterance) between accented and unaccented syllables, is not intimated by the ancient writers: that such difference, if it existed, cannot have been great, is made probable by the total disregard of accent in ancient verse. The question has been raised whether any distinction was made among the lower tones; whether there was any middle tone, intermediate between the highest and the lowest. Some ancient writers speak of a middle tone; but the statements are not so definite as could be wished. G. Hermann (de emend. rit. gramm. Græc.) recognized a middle tone in the grave accent where it takes the place of an acute on the ultima. G. Curtius (Jahn's Jahrb., vol. 72) recognized it also in the grave accent where it forms part of the circumflex. Recently, P. Misteli (Kuhn's Zeitsch., vol. 17), founding on the analogies of the Sanskrit accent, holds that the high tone (acute accent), where it was not final, was always followed by a middle tone. Prof. Hadley set forth a theory based on that of Misteli, but with additions and modifications of his own. In the undivided Indo-European, as in Sanskrit, there was no restriction on the place of the accent; it might fall on any syllable of the longest word. Hence the high tone with the following middle tone might be separated from the end of the word by a succession of low-tone syllables. If now there came to be a prevailing dislike for such a succession, an unwillingness to hear more than one low-tone syllable at the end of a word, the result would be to confine the accent to the last three syllables. This

result, as it is found both in Greek and in Latin, may be referred to the time of Græco-Italian unity. But for the Greek we have to assume also a subsequent restriction; the final low tone must not occupy the whole of a long syllable; if it came upon a long vowel, the first half of that vowel must be sounded with middle tone. Thus "high tone, middle tone, short low tone," became a prevailing cadence for Greek words, and was brought in wherever it could be attained without throwing back the accent. The leading rules of Greek accentuation—no accent allowed before the antepenult; only the acute used on that syllable, and not even this if the ultima is long; an accented penult must take the circumflex if it has a long vowel and the ultima a short one; an accented penult must take the acute in any other case;—all these are explained by this cadence, being all necessary to secure it. As for throwing back the accent to obtain this cadence (or as much of it as possible), one branch of the Greeks, the Æolians of Asia Minor, did so; whence Æolic forms like *χαλεπός*, *χαλεπώς*, *λελέκωτες*, for which the common Greek has *χαλεπός*, *χαλεπῶς*, *λελέκωτες*, with the primitive accent.

The Latin took a different, though analogous course. It allowed the final low tone to have either quantity, but would not allow the middle tone before it to occupy the whole of a long syllable, whether long by nature or position. Hence the cadence, "high tone, short middle tone, low tone," which the Latin procured, or as much of it as possible, in all words, even by throwing back the accent like the Æolic Greek. In this way all the varieties of Latin accent—*ligeres*, *ligeret*, *monères*, *monéret*, *legéndus*, *vixit*, *riés*—may be easily accounted for.

In conclusion, Prof. Hadley referred to the hypothetical character of this theory, pointing out the unproved assumptions contained in it; but remarked that these assumptions are so natural in themselves and furnish so simple an explanation for so many seemingly unconnected facts, that it is difficult to believe them wholly unfounded.

7. On the Order of Words in Attic Greek Prose, by Prof. Charles Short, of Columbia College, New York.

This communication was a verbal account of an Essay which Prof. Short was about to publish. The immediate occasion of the Essay is the republication in this country of Mr. Yonge's English-Greek Dictionary. That work being intended chiefly as an aid to students in Greek Composition, it seemed well to prefix to it something on the order of the words.

Prof. Short stated that, while there were several monographs on this subject by European scholars relating to single authors or to single points, as by Darpe, Braun, and Engelhardt, and while several commentators on Greek authors had here and there touched the matter, as Stallbaum, Weber, and Rehdantz, yet he was not aware that any systematic treatise upon the subject had anywhere appeared, and he had therefore undertaken to supply such a one as he could. The general subject being large, he had confined himself to the usages of prose, and to one form of that, the Attic.

Taking Xenophon as a basis, he had then carefully examined Thucydides, next the Attic Orators, and lastly Plato. His method had been to gather under each head a very large number of examples from these writers in the order just mentioned, and then to deduce the general law, noting the exceptions, and giving them in classes where this was practicable. When the reason for a particular order appeared, he had in many instances stated it, but his main purpose in the present Essay was rather to develop the laws of order than to discuss them, and by adding the exceptions to show the range within which diversity of order might take place.

Some of the general laws were specified: that the adjective follows the word it qualifies; that the genitive follows the noun it limits, with the curious exception that when the limited noun has the article, the genitive in general relations may stand between the article and the noun, but the partitive genitive, as a law, may not; that the predicate noun, pronoun, or adjective, stands directly before the verb finite, or an infinitive, or a participle either with or without the article; that the Greeks in respect to collocation made no distinction between the objective and the subjective infinitive, putting both alike after the leading word; that the modification of a word having the article intervenes between the article and the word, and

that it sometimes follows both wholly or in part, but only in the rarest instances (except a limiting genitive) precedes them, and that he had observed only one case in which an adverb modifying an infinitive with the article stood before the article, and that in a suspected piece of Xenophon, the *Apologia*.

In his treatment of the prepositions, he had first given their position with reference to their regimen and then added an elaborate section on a perplexing subject, the omission and repetition of the preposition under various circumstances; and after setting forth the prevailing usage in simple cases, he had considered the complex cases, and shown that the latter could be resolved into the former. He has perhaps discovered a law here not previously observed.

Where various readings existed affecting the matter of order, he had given the variation under its appropriate head and subjoined the name of the Editor who adopted it, and the examples in connection with which such reading was given might be regarded as so much testimony on its behalf.

8. On Prof. Max Müller's Translation of the Rig-Veda, by Prof. W. D. Whitney, of New Haven.

Prof. Whitney said that not more than two or three other Sanskritists had studied the Veda so long and so deeply as Prof. Max Müller, or were in position to furnish so authoritative a version of it. Hence, scholars had been looking forward with eager expectation to his translation, promised many years ago, and of which the first volume has left the press this season. The work as published would not be found in all respects to fulfil the expectations they had formed. Though advertised as one of a series of eight volumes, it actually contains only one seventy-fifth of the Vedic text (12 hymns out of 1017). The bulk of the volume is filled with a variety of material, which, though much of it valuable in itself, would gladly have been spared. The author has taken as his model Burnouf's work on the *Avesta*. But the circumstances of the two cases are so different that the model is an ill-chosen one. Burnouf was breaking a path in an entirely new subject. His work was left a fragment, and never could have been made any thing else. Müller has undertaken an impracticable task, that of accounting for and establishing his version of every passage. How incomplete, and open to criticism in regard to proportion, it is, appears from the circumstance that to the first verse translated there is a note of eleven pages on an adjective meaning 'ruddy,' while the making of an accusative plural (or gen. or abl. sing.) the subject of a verb, and the assumption that the sun could be regarded as Indra's horse, were let pass without any remark—and so in other cases, which were pointed out in a detailed criticism of a few verses. To the extension of the work by including a romanized text of the original hymns themselves, and the detailed versions of other translators, objection was taken on the score of want of necessity: since such things can be of service only to a professed Vedic scholar, who must be presumed to possess them in another form. If Müller would give simply his own understanding of the meaning of the hymns, with limited exposition of especially difficult points, he would consult the interests not only of the public at large, but also of his fellow-students in the same department.

The selection of this particular body of hymns (those to the Maruts, or storm-gods) for inclusion in the first volume is unfortunate, since they are among the most obscure and tedious of the collection, and may repel from a study of the Veda some who would have been attracted by a more pleasing first taste.

On the score of his over-abundant introductory and expository matter, Müller claims that his is the "first translation" of the Veda: a claim which few will be ready to admit. Burnouf called his work a "commentary," not a translation, though he had no real predecessor; while Müller has to quote several, one of whom (Benfey) has worked upon the same basis and with the same principles as himself, although doubtless with less thorough preparation. To Müller's method no exceptions can be taken: he utterly discards the native commentators as authority, and founds his interpretation upon grammar, etymology, and the comparison of parallel passages. He is also perfectly fair and modest in estimating the value of the results reached by him; putting forward his version as only a provisional solution of its very difficult problem, and as sure to be superseded by and by, when longer study shall have brought a better comprehension of the whole Vedic antiquity.

9. Notes on a Surveying Trip from the Phenician Coast to the Euphrates River, by Mr. Henry M. Canfield, of South Britain, Conn.

Mr. Canfield had expected to be present at the meeting, and to give an oral account of his trip; but, being unavoidably kept away, he sent instead a brief paper, which was read by the Corresponding Secretary.

Mr. Canfield joined Col. Romer's party, engaged to survey a route for a railroad from the Mediterranean to the Euphrates, in April, 1868. The line surveyed started at the mouth of El Kebir, and followed the road to Hamath nearly to the Nossariéh range. With some difficulty, a practicable route was found through the pass between the Nossariéh and the Lebanon, then across the beautiful fertile plain of the Beky'aa, through the Jebel Homs to Homs, and north-easterly over the desert to Selamieh, the farthest outpost of civilization; then, after extensive exploration reaching as far as Aleppo and Palmyra, through the great Wady in Jebel Assouet nearly to the Euphrates at Sheik Omar or Bais; when difficulties with the Arab tribes put an end, for the time, to the enterprise.

Mr. Canfield describes the Nusairi inhabitants of the mountains and desert as a large-framed race, usually with light hair and brown eyes, laborious, but treacherous and inhospitable; and speaks of their semi-subterranean dwellings, of their customs and religion. He was unable to discover or learn how they dispose of their dead. He calls attention to the square towers, called by the Arabs *bourgh*, scattered across the whole country to the Euphrates; also to the numerous castles of the middle ages, of which the finest he saw is Kalat el Husn, at the north-western edge of the Beky'aa. This is so immense a structure that it is now inhabited by 5000 people. The desert country beyond Selamieh is marked in places by groups of broken columns and heaps of ruins; at one point, west of the Orontes and east of Sherbt el-Humun, forming regular streets and squares over a space three miles long and two wide; deserted villages, in various styles of building, are also numerous.

A chief of the Ismaeliyéh was met with who had just returned from a trip to India; showing that the old *Assassins* have and maintain correspondence with some Indian sect.

Rev. Mr. Blodget, missionary at Peking, addressed the meeting briefly respecting the religion of the Chinese, and respecting the translation into Chinese of the word *God*.

After this (at one o'clock, Friday noon) the Society adjourned, to meet again in Boston, on Wednesday, May 18th, 1870.

LIST OF MEMBERS.

OCTOBER, 1869.

1. CORPORATE MEMBERS.

Names marked with † are those of Life Members.

EZRA ABBOT, New Haven
 Pres. CHARLES A. AIKEN, Chicago, Ill.
 Prof. WILLIAM F. ALLEN, Connecticut
 Rev. RUFUS ANDERSON, New York
 Prof. WILLIAM P. ATKINSON, Franklin, N. Y.
 Rev. GEORGE B. BACON, New Haven
 JOHN D. BALDWIN, Portland, Me.
 † JOHN W. BARROW, New York
 Prof. ELIJAH P. BARROWS, Madison, N. Y.
 JOHN R. BARTLETT, New Haven
 Rev. WILLIAM H. BENADE, Cambridge
 Prof. ALBERT S. BICKMORE, Cambridge
 CHARLES L. BRACE, Shanghai, China
 J. CARSON BREVOORT, Boston
 Prof. FISK P. BREWER, Durham, Conn.
 Rev. CHARLES H. BRIGHAM, Middlebury, Conn.
 C. ASTOR BRISTED, New Haven
 † J. CARTER BROWN, New Haven
 Rev. NATHAN BROWN, New Haven
 WILLIAM C. BRYANT, Cambridge
 Prof. HENRY C. CAMERON, Princeton
 Pres. WILLIAM H. CAMPBELL, West Hartford, Conn.
 Prof. GEORGE L. CARY, Princeton, N. J.
 PLINY E. CHASE, New Haven
 Prof. THOMAS CHASE, Columbia, Pa.
 Rev. EDSON L. CLARK, Philadelphia
 Rev. EDWARD L. CLARK, Albany, N. Y.
 JOSIAH CLARK, London, England
 Rev. NATHANIEL G. CLARK, New Haven
 Prof. EDWARD B. COE, Worcester, Mass.
 † JOSEPH G. COGSWELL, Boston
 JOSHUA COIT, Brookline, Mass.
 Rev. HENRY M. COLTON, New York
 ALEXANDER I. COTHEAL, Wallingford, Conn.
 BRUNTON COXE, Lancaster, N. J.
 Rev. OLIVER CRANE, Albany, N. Y.
 Prof. ALPHEUS CROSBY, New Haven
 Rev. HOWARD CROSBY, New York
 † EDWARD CUNNINGHAM, New York

Cambridge.
 Schenectady, N. Y.
 Prof. CHARLES ELLIOTT, New York
 RALPH W. EMMERSON, Boston
 † WILLIAM FENICOTT, Boston
 Rev. GEORGE H. FETTER, Orange, N. J.
 RICHARD S. FELLOWES, Worcester, Mass.
 Rev. WILLIAM H. FISK, New York
 ORANGE ISAAC FISKER, Middletown, Conn.
 Prof. JOHN H. FLETCHER, Providence, R. I.
 Prof. GEORGE F. FORTY, Pittsburg, Pa.
 JOHN FROST, Hamilton, N. Y.
 CHARLES FROMON, New York
 † FRANK B. FORBES, Brooklyn, N. Y.
 JOHN M. FORBES, Chapel Hill, N. C.
 Prof. WILLIAM C. FORTY, Ann Arbor, Mich.
 Prof. FREDERICK GARDNER, New York
 J. WILLARD GIBBS, Providence, R. I.
 Prof. DANIEL C. GILBERT, New York
 † Capt. JAMES GILLY, U. S. A., New York
 Prof. WILLIAM W. GOODWIN, Princeton, N. J.
 Prof. W. HERBERT, New Brunswick, N. J.
 Rev. LEWIS (Jr.), Meadville, Pa.
 Prof. ARSLOD GUSTAF, Philadelphia
 Prof. JAMES HALL, West Haverford, Pa.
 Prof. S. STURGEON, North Branford, Conn.
 Rev. CHARLES H. HARRIS, New Haven
 WILLIAM H. HARRIS, Northampton, Mass.
 † Prof. FREDERICK HARRIS, Boston
 Rev. EDWIN HAWOOD, New Haven
 SAMUEL F. HAYES, Cambridge
 JOHN HEARD, New Haven
 Prof. FREDERICK H. HENRI, New York
 THOMAS W. HICKSON, New York
 Rev. THOMAS HILL, Philadelphia
 Prof. G. WHELAN HODGE, Carbondale, Pa.
 HENRY A. HOBBS, Salem, Mass.
 Prof. JAMES M. HORTON, New York
 FREDERICK HOWE, Shanghai, China.

Pres. EDWIN A. DALRYMPLE,
 Prof. GEORGE E. DAY,
 Prof. HENRY N. DAY,
 JOHN W. DEFOREST,
 Rev. JAMES T. DICKINSON,
 Dr. GEORGE L. DITSON,
 EPES S. DIXWELL,
 †GEORGE B. DIXWELL,
 Prof. HENRY DRISLER,
 SAMUEL F. DUNLAP,
 Prof. TIMOTHY DWIGHT,
 Prof. CHARLES ELLIOTT,
 RALPH W. EMERSON,
 †WILLIAM ENDICOTT,
 Rev. GEORGE R. ENTLEB,
 RICHARD S. FELLOWES,
 Rev. WILLIAM H. FENN,
 CHAS. ISAAC FERRIS,
 Prof. JOHN B. FEULING,
 Prof. GEORGE P. FISHER,
 JOHN FISKE,
 CHARLES FOLSOM,
 †FRANK B. FORBES,
 †JOHN M. FORBES,
 Prof. WILLIAM C. FOWLER,
 Prof. FREDERIC GARDINER,
 J. WILLARD GIBBS,
 Prof. DANIEL C. GILMAN,
 †Capt. JAMES GLYNN, U. S. N.,
 Prof. WILLIAM W. GOODWIN,
 Prof. W. HENRY GREEN,
 Rev. LEWIS GROUT,
 Prof. ARNOLD GUYOT,
 Prof. JAMES HADLEY,
 Prof. S. STEPHAN HALDEMAN,
 Rev. CHARLES R. HALE, U. S. N.,
 WILLIAM H. HALE,
 †Prof. FITZ-EDWARD HALL,
 Rev. EDWIN HARWOOD,
 SAMUEL F. HAVEN,
 †JOHN HEARD,
 Prof. FREDERICK H. HEDGE,
 THOMAS W. HIGGINSON,
 Rev. THOMAS HILL,
 Prof. C. WINTAR HODGE,
 HENRY A. HOMES,
 Prof. JAMES M. HOPPIN,
 FISHER HOWE,

Baltimore.
 New Haven.
 New Haven.
 New Haven.
 Middlefield, Conn.
 Albany, N. Y.
 Cambridge.
 Shanghai, China.
 New York.
 New York.
 New Haven.
 Chicago, Ill.
 Concord, Mass.
 New York.
 Franklin, N. Y.
 New Haven.
 Portland, Me.
 New York.
 Madison, Wis.
 New Haven.
 Cambridge.
 Cambridge.
 Shanghai, China.
 Boston.
 Durham Centre, Conn.
 Middletown, Conn.
 New Haven.
 New Haven.
 New Haven.
 Cambridge.
 Princeton, N. J.
 West Brattleboro', Vt.
 Princeton, N. J.
 New Haven.
 Columbia, Pa.
 Philadelphia.
 Albany, N. Y.
 London, England.
 New Haven.
 Worcester, Mass.
 Boston.
 Brookline, Mass.
 Newport, R. I.
 Waltham, Mass.
 Princeton, N. J.
 Albany, N. Y.
 New Haven.
 New York.

JOSEPH HOWLAND, New York
 Rev. WILLIAM HUTCHINSON, London
 Rev. WILLIAM IRVIN, St. Louis, Mo.
 Prof. MELANCTHON W. JACOBS, St. Louis, Mo.
 †Prof. JOSEPH W. JENES, Springfield, Mass.
 Rev. SAMUEL JOHNSON, Boston
 HENRY C. KINGSLEY, New York
 WILLIAM L. KINGSLEY, Amherst, Mass.
 Rev. EDWARD N. KIRK, New Haven
 †HENRY LEIGHTON, New York
 †JAMES LENOX, New York
 J. PETER LESLEY, Boston
 Prof. TAYLER LEWIS, Hartford, Conn.
 Prof. JAMES R. LOWELL, Cambridge
 Rev. DWIGHT W. MARSH, Springfield, Mass.
 Rev. MYTTON MAURY, New Haven
 Prof. CHARLES M. MEAD, Hartford, Conn.
 Prof. JAMES C. MOFFAT, Springfield, Mass.
 CHARLES E. NORTON, New York
 †ROBERT M. OLYPHANT, New York
 Prof. LEWIS R. PACKARD, New Haven
 NATHANIEL PAINE, New Haven
 Dr. PETER PARKER, Glasgow, Scot.
 Prof. THEOPHILUS PARSONS, Brooklyn, N. Y.
 Rev. WILLIAM PATTON, Boston
 Prof. ANDREW P. PEABODY, New Haven
 †GREGORY A. PERDICARIS, New Haven
 Dr. CHARLES PICKERING, Cambridge
 Pres. HENRY M. PIERCE, New Haven
 Rev. THOMAS C. PITKIN, New Haven
 ELISHA R. POTTIER, New Haven
 Prof. JOHN PROUDFIT, Cambridge
 JOSEPH S. ROPES, New York
 D. WALDO SALISBURY, New York
 †Prof. EDWARD E. SALISBURY, New York
 STEPHEN SALISBURY, New Haven
 FRANK B. SANBORN, Cambridge
 Prof. M. SCHULE DE VERE, St. Louis, Mo.
 Dr. ERNST SCHMID, New York
 Rev. HENRY M. SCUDDER, New York
 Prof. GUSTAV SEYFFARTH, New York
 Prof. CHARLES SHORT, New York
 Dr. JOHN H. SLACK, New York
 Rev. E. BAILEY SMITH, New York
 †E. M. SMITH, New York
 †THOMAS C. SMITH, New York
 Gen. ADOLF VON STEINWEHR, New York
 Prof. AUSTIN STICKNEY, New York
 Rev. LYMAN STILSON, New York

Fishkill, N. Y.
 Norwich, Conn.
 Troy, N. Y.
 Allegheny City, Pa.
 Newtonville, Mass.
 Salem, Mass.
 New Haven.
 New Haven.
 Boston.
 Shanghai, China.
 New York.
 Philadelphia.
 Schenectady, N. Y.
 Cambridge.
 Whitney Point, N. Y.
 Cold Spring, N. Y.
 Andover, Mass.
 Princeton, N. J.
 Cambridge.
 New York.
 New Haven.
 Worcester, Mass.
 Washington.
 Cambridge.
 New Haven.
 Cambridge.
 Trenton, N. J.
 Boston.
 New York.
 Detroit, Mich.
 South Kingstown, R. I.
 New York.
 Boston.
 Boston.
 New Haven.
 Worcester, Mass.
 Springfield, Mass.
 University of Virginia.
 White Plains, N. Y.
 San Francisco, Cal.
 Dansville, N. Y.
 New York.
 Philadelphia.
 Middletown, Conn.
 Shanghai, China.
 Hongkong, China.
 New Haven.
 Hartford, Conn.
 Nunda, N. Y.

† WILLIAM W. STONE, Y. Y.
 † RUSSELL STURGIS, Norwich, Conn.
 LEONARD TAFEL, Troy, N. Y.
 Prof. RUDOLPH L. TAVEL, Allegheny City, Pa.
 † GEORGE W. TALBOT, Newburyport, Mass.
 JOHN TAPPAN, Salem, Mass.
 BAYARD TAYLOR, New Haven.
 SAMUEL H. TAYLOR, New Haven.
 Prof. THOMAS A. THACHER, Boston.
 Rev. JOSEPH P. THOMPSON, Shanghai, China.
 CHARLES TRACY, New York.
 Rev. SELAH B. TREAT, Philadelphia.
 J. HAMMOND TRUMBULL, Schenectady, N. Y.
 Rev. KINSLEY TWining, Cambridge.
 † J. T. TWOMBLY, White Plains, N. Y.
 ADDISON VAN NAME, Cold Spring, N. Y.
 Rev. THOMAS E. VERMILYNE, Andover, Mass.
 † THOMAS WALSH, Princeton, N. J.
 Rev. FERDINAND DE W. WARD, Cambridge, Mass.
 Rev. WILLIAM H. WARD, New York.
 ALBERT B. WATKINS, New Haven.
 FRANCIS WAYLAND, Worcester, Mass.
 Rev. EDWARD WEBB, Washington.
 CHARLES E. WEST, Cambridge.
 WILLIAM A. WHEELER, New Haven.
 Pres. ANDREW D. WHITE, Cambridge.
 Dr. MOSES C. WHITE, Trenton, N. J.
 Prof. JOSIAH D. WHITNEY, Boston.
 Prof. WILLIAM D. WHITNEY, New York.
 Rev. JAMES M. WHITON, Detroit, Mich.
 Rev. JOSEPH K. WIGHT, South Kingston, R. I.
 LYMAN R. WILLISTON, New York.
 Dr. JOSEPH WILSON, U. S. N., Boston.
 Prof. SAMUEL J. WILSON, Boston.
 Rev. GEORGE W. WOOD, New Haven.
 Pres. THEODORE D. WOOLSEY, Worcester.
 Prof. EDWARD J. YOUNG, Springfield, Mass.
 CHARLES W. ZABNER, University of Virginia.

New York.
 London, England.
 St. Louis, Mo.
 St. Louis, Mo.
 Shanghai, China.
 Boston.
 New York.
 Andover, Mass.
 New Haven.
 New York.
 New York.
 Boston.
 Hartford, Conn.
 Cambridge.
 Shanghai, China.
 New Haven.
 Hartford, Conn.
 Prof. CHARLES M. MANNING, New Haven.
 Shanghai, China.
 Rochester, N. Y.
 New York.
 Fairfield, N. Y.
 New Haven.
 Glasgow, Del.
 Brooklyn, N. Y.
 Boston.
 Ithaca, N. Y.
 New Haven.
 Cambridge.
 New Haven.
 Lynn, Mass.
 New Hamburg, N. Y.
 Cambridge.
 Allegheny City, Pa.
 New York.
 New Haven.
 Cambridge.
 St. Joseph, Mo.
 Dr. ERNST SCHMIDT, New York.
 Rev. HENRY M. SCHMIDT, New York.
 Prof. GEORGE STETTER, New York.
 Prof. CHARLES SPOFFORD, New York.
 Dr. JOHN H. STARR, New York.
 Rev. R. HARRIS SMITH, New York.
 Dr. M. SMITH, New York.
 † THOMAS C. SMITH, New York.
 Gen. ALGER VON STEINER, New York.
 Prof. ALGER STEINER, New York.
 Rev. JAMES STILSON, New York.

2. CORRESPONDING MEMBERS.

Rev. JOHN C. ADAMSON,	Belgrade.	Milan.	
Prof. GRAZIANO L. ASCOLI,	Missionary at Constantinople.	Missionary at Cape Palmas, W. Africa.	
Rev. JOHN G. AUBER,	Missionary in Southern India.	Berlin.	
ADOLF BASTIAN,	London.	Missionary at Rangoon, Burmah.	
Rev. CEPHAS BENNETT,	Missionary in China.	Missionary at Bhamdun, Syria.	
Rev. WILLIAM A. BENTON,	Missionary in Egypt.	Serajewo, Bosnia.	
OTTO BLAU,	Missionary at Beirut.	Capetown, S. Africa.	
WILLIAM H. I. BLEES,	Missionary at Beirut.	Beirut.	
Rev. DANIEL BLISS,	Missionary in Kurdistan.	Missionary at Peking.	
Rev. HENRY BLODGET,	Missionary.	Constantinople.	
JOHN P. BROWN,	Missionary at the Gambia.	Missionary in Japan.	
Rev. SAMUEL R. BROWN,	Missionary at Beirut.	Göttingen.	
Prof. HEINRICH BRUGSCH,	Heidelberg.	Missionary at the Gaboon, W. Africa.	
Rev. ALBERT BUSHNELL,	Yonkers.	Missionary at Abeih, Syria.	
Rev. SIMON H. CALHOUN,	Missionary at Beirut.	Milan.	
Rev. WILLIAM CLARK,	Melbourne.	London.	
HYDE CLARKE,	Hayes, England.	Cambridge, England.	
Prof. EDWARD B. COWELL,		Bombay.	
Dr. BHAO DASI,		Missionary at Calcutta.	
Rev. CHARLES H. A. DALL,		Berlin.	
Prof. AUGUST DILLMANN,		Beirut.	
Prof. D. STUART DODGE,		Missionary in South Africa.	
Rev. JACOB L. DOEHNE,		Missionary in China.	
Rev. JOSEPH EDKINS,		Exeter, England.	
Rev. ROMEO ELTON,		Paris.	
Prof. PHILIPPE ED. FOUCAUX,		Jerusalem.	
Dr. S. FRAENKEL,		Missionary in Central India.	
Rev. JOHN T. GRACEY,		Constantinople.	
Rev. CYRUS HAMLIN,		Christiania, Norway.	
Prof. CHRISTIAN A. HOLMBOM,		Missionary at Bangkok, Siam.	
Dr. SAMUEL R. HOUSE,		Missionary at Abeih, Syria.	
Rev. HENRY H. JESSUP,		Missionary at Swatow, China.	
Rev. J. W. JOHNSON,		St. Petersburg.	
Prof. MIRZA KASEM BEG,		Paris.	
NICHOLAS VON KHANIKOFF,		Paris.	
L. LEON DE ROSNY,			
Dr. DANIEL J. MCGOWAN,		Peking.	
Prof. WILLIAM A. P. MARTIN,		Missionary at Toungoo, Burmah.	
Rev. FRANCIS MASON,		London.	
Prof. COTTON MATHER,		Missionary at Ningpo, China.	
Dr. D. B. MCCARTHEE,			
THOMAS T. MEADOWS,		Constantinople.	
Dr. A. D. MORDTMANN,		Constantinople.	
Dr. A. G. PASPATI,		Missionary at Cape Palmas, W. Africa.	
Bishop JOHN PAYNE,		Missionary at Constantinople.	
Dr. ANDREW T. PRATT,			

RAJENDRALALA MITRA,
 JAMES W. REDHOUSE,
 Rev. ELIAS RIGGS,
 Dr. G. ROSEN,
 Rev. WILLIAM G. SCHAUFFLER,
 Rev. WILLIAM W. SCUDDER,
 HENRY STEVENS,
 Rev. EDWARD W. SYLVE,
 Rev. WILLIAM TRACY,
 Rev. WILLIAM M. THOMSON,
 Dr. CORNELIUS V. A. VAN DYCK,
 Rev. HENRY J. VAN LENNEP,
 Rev. DANIEL VROOMAN,
 Rev. WILLIAM WALKER,
 Rev. GEORGE T. WASHBURN,
 Prof. GUSTAV WEIL,
 Dr. S. WELLS WILLIAMS,
 Rev. W. FREDERICK WILLIAMS,
 WILLIAM WINTHROP,
 Rev. CHARLES H. H. WRIGHT.

Calcutta.
London.
Missionary at Constantinople.
Belgrade.
Missionary at Constantinople.
Missionary in Southern India.
London.
Missionary in China.
Missionary in S. India.
Missionary at Beirut.
Missionary at Beirut.
Missionary in Eastern Turkey.
Missionary.
Missionary at the Gaboon, W. Africa.
Missionary at Battalagundu, S. India.
Heidelberg.
Peking.
Missionary at Mardin, E. Turkey.
Malta.
Havre, France.

Bombay.
 Missionary at Calcutta.
 Berlin.
 Beirut.
 Missionary in South Africa.
 Missionary in China.
 Kanton, Hongkong.
 Paris.
 Jerusalem.
 Missionary in Central India.
 Constantinople.
 Christiania, Norway.
 Missionary at Bangkok, Siam.
 Missionary at Aboon, Syria.
 Missionary at Swatow, China.
 St. Petersburg.
 Paris.
 Paris.
 Peking.
 Missionary at Tientsin, Pootung.
 London.
 Missionary at Ningpo, China.
 Constantinople.
 Constantinople.
 Missionary at Cape Palmer, W. A.
 Missionary at Constantinople.

Dr. BRAD DALL,
Rev. CHARLES H. A. DALL,
Prof. AUGUST MILLMAN,
Prof. D. STUART DOUGLASS,
Rev. JAMES I. DOUGLASS,
Rev. JOSEPH RUSSELL,
Rev. ROMEO ELSON,
Prof. PHILLIPS RO. FORTNA,
Dr. S. F. JANKEN,
Rev. JOHN T. GLACIER,
Rev. OTTIE HAMMOND,
Prof. CHRISTIAN A. HOLMBOE,
Dr. SAMUEL H. HOGUE,
Rev. HERBERT H. JESSE,
Rev. J. W. JOHNSON,
Prof. MINNA KAREN BEE,
NICHOLAS VON KRAZINSKY,
L. LEON DE HOSBY,
Dr. DANIEL J. MCGOWAN,
Prof. WILLIAM A. P. MARTIN,
Rev. FRANK MARSH,
Prof. GUSTON MATHER,
Dr. D. B. MCGILLIVER,
THOMAS T. MENDOWS,
Dr. A. D. MONTGOMERY,
Dr. A. G. PARKYLL,
Bishop JOHN PAVLE,
Dr. ANDREW T. PRATT

3. HONORARY MEMBERS.

RAJA APURVA KRISHNA BAHADUR,	Calcutta.
JAMES BIRD,	London.
Prof. OTTO BOEHTLINGK,	Jena.
Sir JOHN BOWRING,	London.
Prof. HERMANN BROCKHAUS,	Leipzig.
RICHARD CLARKE,	London.
Prof. HEINRICH VON EWALD,	Göttingen.
M. CHAMPOLLION FIGEAC,	Paris.
Prof. GUSTAV FLÜGEL,	Dresden.
Prof. JULIUS FUERST,	Leipzig.
BRIAN HOUGHTON HODGSON,	Dursley, England.
Prof. STANISLAS JULIEN,	Paris.
Prof. ADALBERT KUHN,	Berlin.
Rev. JOHN DUNMORE LANG.	
Prof. CHRISTIAN LASSEN,	Bonn.
Prof. C. RICHARD LEPSIUS,	Berlin.
Prof. JULES MOHL,	Paris.
JOHN MUIR,	Edinburgh.
Prof. MAX MUELLER,	Oxford.
Prof. JULIUS HEINRICH PETERMANN,	Berlin.
Prof. AUGUST FRIEDRICH POTT,	Halle.
ADOLPHE REGNIER,	Paris.
ERNEST RENAN,	Paris.
Prof. EMIL RÖDIGER,	Berlin.
Prof. RUDOLF ROTH,	Tübingen.
SAFVET PASHA,	Constantinople.
Prof. FRIEDRICH SPIEGEL,	Erlangen.
Prof. GARCIN DE TASSY,	Paris.
Prof. CONSTANTIN TISCHENDORF,	Leipzig.
Prof. CARL J. TORNBORG,	Lund.
Prof. ALBRECHT WEBER,	Berlin.
Sir J. GARDNER WILKINSON,	London.
His Majesty PHRA-PARAMENDR MAHA MONGKUT, King of Siam.	

PROCEEDINGS AT BOSTON, MAY 18TH, 1870.

The Society assembled at 10 o'clock A. M., at the rooms of the American Academy. President Woolsey being absent, the chair was occupied alternately by Dr. Anderson and Dr. Parker, Vice-Presidents.

The record of the preceding meeting was read by the Recording Secretary. It was arranged that there should be a recess of only one hour at noon, that the business of the meeting might be finished before evening.

The Treasurer's Report was read, audited, and accepted. It was as follows:

RECEIPTS.	
Balance on hand, May 19th, 1869.	\$357.53
Annual assessments paid in.	15.00
Life-membership.	75.00
Sale of the Journal.	17.75
Total receipts of the year.	608.75
EXPENDITURES.	
Printing of Proceedings, etc.	43.24
Expenses of Library and Correspondence.	46.64
Paid for binding of books.	22.25
Total expenditures of the year.	112.13
Balance on hand, May 18th, 1870.	188.15

The Treasurer also made a statement respecting the condition of the fund for the purchase of Chinese type, provided by the kind offices of the late Hon. Charles W. Bradley. The arrival of the font ordered from Shanghai was reported at the last meeting. Its cost was as follows:

For type (180 lbs. small pica).	\$324.00
Type-cases.	13.00
Packing, freight, and insurance.	22.00
Premium on \$358 in Mexican dollars.	136.79
Expenses in New York, duty, cartage, etc.,	75.00
Total expense.	\$569.79

To meet this, the Treasurer had drawn on Messrs. Baring, Brothers, & Co., of London, with whom the fund was deposited by Mr. Bradley, for £100, which yielded in currency \$670.08. The balance, about \$100, is deposited in the Townsend Savings Bank at New Haven to the credit of the fund, and about £92 still remains in the hands of Messrs. Barings.

The Librarian excused himself, on the score of other pressing occupations, for having come unprepared with a full Report of the condition of the Library, and gave a brief oral statement respecting the additions made to it during the year. The most important donations had come from the Vienna Academy of Sciences, and from Prof. Fitz-Edward Hall of London.

The Committee of Publication reported that, as authorized by the Directors last fall, they had commenced the reprinting of Vol. ix., Part 1, of the Journal, as soon as the printing office had been restored to working order after the fire; and that the work had since gone on without interruption, but was not yet quite finished. It was intended to proceed with the printing of Part 2, as soon as the other should be out of the way.

The Directors notified the next meeting, as to be held in New Haven on the nineteenth of October, unless the Committee of Arrangements (Prof. Hadley of New Haven, with the Recording and Corresponding Secretaries) should alter the appointment—which they were authorized to do, if it appeared desirable.

The following persons, on recommendation of the Directors, were elected members of the Society: namely,

as Corporate Members,

Mr. Erastus B. Bigelow, of Boston.
 Prof. Ferdinand Böcher, of Boston.
 Prof. J. Lewis Diman, of Providence, R. I.
 Mr. James B. Greenough, of Cambridge, Mass.
 Mr. Thomas S. Perry, of Cambridge, Mass.
 Mr. Charles T. Russell, of Cambridge, Mass.
 Rev. J. Herbert Senter, of Cambridge, Mass.
 Prof. Peter H. Steenstra, of Cambridge, Mass.
 Prof. Francis Wharton, D.D., of Brookline, Mass.
 Rev. Henry A. Yardley, of Middletown, Conn.

as Corresponding Members,

Rev. Albert L. Long, D.D., Missionary at Constantinople.
 Rev. Hyman A. Wilder, Missionary in South Africa.

Mr. J. S. Ropes of Boston, Rev. W. H. Ward of New York, and Hon. J. D. Baldwin of Worcester, were appointed by the chair a Nominating Committee, to propose a ticket for officers for the ensuing year; and the following gentlemen, nominated by them, were elected without dissent:

<i>President</i> —Pres. T. D. WOOLSEY, D.D., LL.D.,	of New Haven.
<i>Vice-Presidents</i> {	Rev. RUFUS ANDERSON, D.D., “ Boston.
	Hon. PETER PARKER, M.D., “ Washington.
	Prof. EDW. E. SALISBURY, LL.D., “ New Haven.
<i>Corresp. Secretary</i> —Prof. W. D. WHITNEY, Ph.D.,	“ New Haven.
<i>Secr. of Class, Section</i> —Prof. JAMES HADLEY, LL.D.,	“ New Haven.
<i>Recording Secretary</i> —Mr. EZRA ABBOT, LL.D.,	“ Cambridge.
<i>Treasurer</i> —Prof. D. C. GILMAN,	“ New Haven.
<i>Librarian</i> —Prof. W. D. WHITNEY,	“ New Haven.

<i>Directors</i>	Mr. J. W. BARROW,	of New York.
	Mr. A. I. COTHEAL,	" New York.
	Prof. W. W. GOODWIN, Ph.D.,	" Cambridge.
	Prof. W. H. GREEN, D.D.,	" Princeton.
	Prof. A. P. PEABODY, D.D.,	" Cambridge.
	Dr. CHARLES PICKERING,	" Boston.
	Prof. CHARLES SHORT, LL.D.,	" New York.

While the committee were deliberating, an interesting series of photographs from India and Farther India were exhibited to the members, and briefly commented on, by Rev. J. T. Gracey.

The Corresponding Secretary then announced the losses which the Society had suffered by death during the year; namely, two Corporate Members, Rev. E. Burgess and Rev. Dr. Proudfit (the latter during some years past a Director); and three Corresponding Members; Prof. Romeo Elton, late of Exeter, England, Rev. Dr. Justin Perkins, during many years a missionary in Orûmiah, and Mr. William Winthrop, American consul at Malta. He said a few words with regard to each of these gentlemen, briefly setting forth the claims that they had upon the respectful and affectionate remembrance of the Society, as well as of scholars in America and through the world. He spoke especially of Mr. Burgess, who would be remembered in connection with the translation of the *Sûrya-Siddhanta* published some years since in the Society's Journal, and with whom he had himself for some time been thrown into intimate relations while that work was in preparation and passing through the press. Mr. Burgess returned to this country in 1854, after more than fourteen years of service as a missionary in western India. He died of pneumonia, near Boston, on the first day of this year.

Prof. Hadley gave a somewhat detailed account of the life and literary labors of Dr. Proudfit, and a view of his character as a scholar and as a man.

The eminent services of the venerable Dr. Perkins in the cause of Christian philanthropy and of learning were set forth by Rev. Mr. Treat, Dr. Parker, and others.

The correspondence of the past six months was presented, and read in part. The following are extracts:

From Mr. Freeman A. Smith, Treasurer of the American Baptist Missionary Union, dated Boston, Nov. 9th, 1869:

"Knowing you to be interested in such things, I send herewith a copy from an ancient metallic plate found by Mr. Bunker, one of our missionaries, among the Red Karens, together with a copy of our magazine, where you will see what he writes respecting it."

Mr. Bunker says:

"It has been long known that an ancient metal plate, having strange characters engraven on it, existed among the Red Karens. While at Kontie's village, we succeeded, after much difficulty, in obtaining a sight of the famous plate, and were also allowed to copy it. The plate is composed of copper, brass, and probably some gold. They regard it as very sacred, and guard it with most zealous care. It is supposed by them to possess life, and they say it requires to be 'fed with metal.' I fed it with a piece of silver of the value of about fifty cents, but did not

see it eat while I was near. The common people fear its power greatly, and dare not look at it, as they say it has power to blind their eyes. The traditions of most of the Karen tribes point to this tablet, I think, and it may be of very ancient origin. The character in which it is written is quite different from any of the characters in which the languages of the East are written, so far as I have been able to learn."

A copy of the inscription was exhibited to the members present, but no one could cast any light upon its strange characters. The Secretary said that he was hoping to obtain additional information upon the matter from Farther India, to be laid before the Society hereafter. The plate is one referred to in Mr. Cross's paper on the Karens and their language, read at the meeting in October, 1866, and reported in the Proceedings of that meeting (Journal, vol. ix., p. xii.).

From Rev. C. H. A. Dall, dated Calcutta, Nov. 27th, 1869:

"In Bombay, lately, I had the pleasure of meeting Dr. Bhau Daji at the monthly meeting of the Bombay Branch of the Royal Asiatic Society, and was surprised to hear him say that within a year or so, or as soon as his practice (as a physician) would permit, he expected to visit England and America. I am not very sorry that you are likely to see, yet sooner, Babu Keshub Chunder Sen; of whom you have heard as the eloquent leader of the partly christianized Hindus, the *Brahmos*. He does not feel settled as to the American part of his visit; but, when calls reach him, as they are sure to do, he will yield to the pressure, and accomplish a visit which I am very desirous that he should make. The presence of these two cultured Oriental gentlemen will, I am sure, make Orientalism dawn on America as never before."

From Mrs. S. J. Rhea, dated Jonesboro, Tennessee, Dec. 5th, 1869; respecting her late husband's Kurdish papers, presented at the previous meeting, giving some explanations as to their character, and expressing her desire to be helpful in any way toward their publication.

From Dr. A. T. Pratt, dated Constantinople, March 16th, 1870:

"... I procured a fine copy of a Cufic inscription some time since and sent it to you; but, together with a valuable lot of coins, it was lost on the way. I am now hoping to send you the stone itself in the course of the summer. . . . I have a grammar of the Turkish language of my own, which I hope to forward as soon as I can get an English translation to go with it. During nearly two years past I have been here, engaged on the revision of the version of the Bible made by Dr. Goodell.

Dr. Paspati is getting out a large work on the Gypsy language, of which I presume you will receive a copy."

Communications being now in order, the following were presented:

1. On the Glagolitic Alphabet, by Rev. A. L. Long, of Constantinople; presented by the Corresponding Secretary.

This was an inquiry into the origin of the Glagolitic character, in which a part of the oldest Slavic literature is preserved, and into its relation to the more usual character, the Cyrillic. Of the two, the Cyrillic is usually ascribed to the Slavic apostle Cyril, who used it for his translation of the Scriptures (about A.D. 862); respecting the other, opinions have been much divided, some attributing its invention to Methodius, Cyril's brother, others to Clement, archbishop of Velitsa in Bulgaria, and pupil of Cyril and Methodius; while yet others regard it as some centuries older than Cyril, and many accept the Dalmatian traditions which would make St. Jerome its inventor. Dr. Long, now, differing from all these, maintains that

the Glagolitic was the alphabet devised by Cyril, and was exclusively used in his time, while the so-called Cyrillic, which is no independent invention, but only an adaptation of the Greek alphabet to the Slavic language, was the work of Clement (who died A.D. 916). The various considerations which appear to support this view are detailed in the paper. At the end, the author acknowledges his obligations to P. J. Schaffarik's work "On the Origin and Home of Glagolitic" (Prague, 1858).

Remarks upon this paper, approving its conclusions, were made by Mr. J. S. Ropes.

2. On the Moabite Inscription of King Mesha, by Rev. Wm. Hayes Ward, of New York.

Mr. Ward first detailed the history of the securing of the inscription by M. Ganneau, from the first discovery of the monument by the German Klein. After showing that it was undoubtedly genuine, and dated back to nearly nine hundred years before Christ, Mr. Ward laid before the meeting a transliterated copy of it in Hebrew characters, and the following translation:

"I am Mesha son of Chemosh [nadab] King of Moab [the D-] ²Benite. | My father reigned over Moab thirty years and I reigned ³after my father. | And I made this high place to Chemosh in Karhah and [this House of Sal-] ⁴vation because he has saved me from all the attacks and because he has caused me to look on all my enemies. | O [m r] i ⁵was King of Israel, and he afflicted Moab many days, because Chemosh was angry with his [land]. | ⁶And his son succeeded him, and he also said, "I will afflict Moab." | In my days he spake thus, ⁷And I looked on him and on his house, | and Israel kept continually perishing. And Omri held possession of the land (?) of ⁸Medeba. And there dwelt in it [Omri and his son and his grand-] son forty years. [But] ⁹Chemosh [restored] it in my days. | And I built Baal-Meon and I made in it ———. And I [besieged] (?) ¹⁰Kirjathaim. | And the men of Gad had dwelt of old in the land [of Kirjathaim]. And the King of Israel built ¹¹for him [Kirjathaim]. | And I fought against the city and took it. | And I slew all the [men of] ¹²the city, a spectacle to Chemosh and to Moab. | And I brought back from thence the [altar of Jehovah, and] ¹³put it before Chemosh in Kerioth. | And I caused to dwell therein ¹⁴the men of Shiran; and the men of ——— ¹⁵Sharath. | And Chemosh said to me, "Go and take Nebo from Israel." | [And I ———] ¹⁶went in the night and I fought against it from the overspreading of the dawn till noon. | And I [took it and I] ¹⁷[utterly destroyed] it, and I slew all of it seven thousand ——— ¹⁸for to Ashtor Chemosh had [I] devoted [them]; and I took from thence ¹⁹the vessels of Jehovah, and I presented them before Chemosh. | And the King of Israel [built] ²⁰Jahaz and dwelt in it while he was fighting against me. | And Chemosh drove him from [before me]. ²¹And I took from Moab 200 men, all told; | and I attacked (?) Jahaz and took it, ²²adding it to Dibon. | I built Karhah, the wall of the forests and the wall of ²³the hill (Ophel). | And I built its gates and I built its towers. | and ²⁴I made a royal palace, and I made reservoirs for the collection of the waters in the midst of the city. | ²⁵And there was no cistern in the midst of the city in Karhah; and I said to all the people, "Make ²⁶for you each a cistern in his house." And I dug ditches (?) for Karhah in [the road to] ²⁷Israel. | I built [A]roer, and I made the high way to Arnon. I built ²⁸Beth-Bamoth, for it was ruined. | and I built Bozrah, for it was deserted. And I ²⁹set in Dibon garrisons (?); for all Dibon was submissive. | And I filled (?) ——— ³⁰in the cities which I added to the land. | And I built ——— and ³¹the temple of Diblathaim. | and the temple of Baal-Meon, and I raised up there ——— ³²the land. | And there dwelt in Honoraim ——— ³³Chemosh said to me, "Go, fight against Honoraim." | And I ³⁴——— Chemosh in my days * * * * *

Mr. Ward explained that in most points he agrees with either Ganneau, Schlottmann, Dérenbourg, Nöldeke, or Neubauer in their versions and corrections of the defective text. He drew, however, more especial attention to certain matters with regard to which he differed from previous commentators. The latter have made the perpendicular stroke near the end of the third line a mark of division between the sentences. This it cannot be, as the dot which divides the words also appears

here, and in no other case are both found together. The stroke can be either γ or ρ , and is no doubt the former. This puts a repetition of γ out of the question. The reading suggested, $\gamma \rho \alpha \nu \alpha \nu \alpha$, seems plausible. The doubtful character at the beginning of the eighth line must be either γ or ρ . The feminine form $\alpha \nu \alpha$ is often used for *plain*, which is just what we want. The masculine is put in the text. Still in Capt. Warren's impression the letter looks more like γ , which would allow $\alpha \nu \alpha$. The suggested emendations for the end of the fifteenth and the beginning of the sixteenth line, and for the seventeenth line, are new. The *fac-simile* of Ganneau seems to show in line twenty-three a flaw in the stone. The fact that the letters as they stand hardly make sense is an indication that the flaw did not exist when the inscription was made, in which case the scribe would have continued the unfinished word on the other side of the flaw, as is the case in the ninth line of the great Sidonian inscription of king Eshmunazer. But the letters which we have, $\alpha \nu \alpha \nu \alpha$, cannot be translated, the last word being neither plural of $\alpha \nu$, 'man,' nor anything else imaginable. Schlottmann and others have suggested $\alpha \nu \alpha \nu \alpha$, 'outpouring.' This word and its masculine form are only used in the Bible in connection with the geography of the region of Moab, and $\alpha \nu \alpha \nu \alpha$ of the old song of which we have a fragment in Num. xxi. 15 compares well with the $\alpha \nu \alpha \nu \alpha$ or $\alpha \nu \alpha \nu \alpha$, which even may be preferable, which I would suggest. Such expressions as "troughs of the waters," Gen. xxx. 38, "brook of the waters," 2 Sam. xvii. 20, "well of the waters," "well" or "fountain of waters," "storm of waters," Hab. iii. 10, are frequent in the Bible. The third word in the eighteenth line I read $\alpha \nu \alpha \nu \alpha$ from Capt. Warren's photographs, which he has misread. The first word in the twenty-second line is read from the photographs as $\alpha \nu \alpha$, giving us exactly the biblical phrase "wall of Ophel."

The language of the inscription is almost pure Hebrew, but with an approach toward the southern Semitic tongues. This appears in the comparative scarcity of quiescent letters, in the plural in *Nun*, and especially in the Hiphthael conjunction, $\alpha \nu \alpha$, which has its correspondences in Arabic, Ethiopic, and Assyrian. Another evident example of this is the use of verbs $\alpha \nu$ instead of $\alpha \nu$. Thus we have $\alpha \nu$ and $\alpha \nu$ for $\alpha \nu$ and $\alpha \nu$. In these cases Nöldeke assumes that the final α is a personal suffix, and that thus a double object is expressed, as is common in Syriac. But the language shows little assimilation to Aramaic peculiarities, and it is more probable that the root is preserved in these forms in a more archaic shape than in Hebrew.

The form of the characters proves the correctness of de Vogüé's assertion, that the oldest Canaanite alphabet was distinguished by its sharp angles. Among the more interesting forms are the γ , which is for the first time found as a simple triangle, like the Greek Δ ; ρ , which we first find here as a perpendicular crossed by three horizontal lines, which suggest the Greek Ξ ; α , which suggests the Greek Υ ; α , which is precisely the Greek κ ; and α , which is an oblique cross, or \times .


The separation of words is found in some other very ancient inscriptions, as in the second inscription of Citium, that of Tucca, and two others.

The lacuna in the eighth line is very unfortunate, as it leaves the chronology in some doubt. Schlottmann is certainly wrong in supposing it possible to make forty years out of the Bible chronology of the reigns of Omri, Ahab, and Ahaziah, which occupied only thirty-one years. If these scriptural figures are correct, and they appear to be, it must be supposed either that Omri began to afflict Moab before he became king while general of Baasha's army, or that the successes of Mesha occurred after the campaigns mentioned in Scripture, and during the latter years of Jehoram. The "round number," which Nöldeke, Schlottmann, and others have suggested, would have been *thirty* instead of *forty*, if this campaign be referred to the first rebellion of Mesha—even if a round number is assumable on such a monument.

3. Remarks on the Discovery of a second "Rosetta Stone," at Tanis in Lower Egypt, by Hon. J. D. Baldwin, of Worcester.

In this very brief paper, Mr. Baldwin called attention once more to the inscription of Tanis, brought to light by Lepsius in 1866, and published as a "bilingual decree" in the same year, the existence of its third, or Demotic, text being not then known. He read from a letter received by him from Lepsius, to the effect that "the original is now in the Museum of Bulaq. Its complete disinterment,

AL





Ms.

Central Archaeological Library,

NEW DELHI.

24509.

Call No. 891.05 / J.A.O.S.

Author—

Journal of the American

1911-12 9

"A book that is shut is but a block"

CENTRAL ARCHAEOLOGICAL LIBRARY
GOVT. OF INDIA
Department of Archaeology
NEW DELHI.

Please help us to keep the book
clean and moving.